HUME LIBRARY

INSTITUTE OF FOOD AND
AGRICULTURAL SCIENCES

UNIVERSITY OF FLORIDA
Gainesville

Copy 2

Dup.

FLORIDA STATE MARKETING BUREAU

ANNUAL FRUIT AND VEGETABLE REPORT

PRODUCTION, TRANSPORTATION AND MARKETING ANALYSIS

1946-47 SEASON

(Also Poultry, Egg, Livestock, Tobacco and Field Crop Statistics)

By Frank H. Scruggs, Market News Specialist

Neill Rhodes, Commissioner
Florida State Marketing Bureau
Division of
Florida State Department of Agriculture
Nathan Mayo, Commissioner

This Annual Report is available free of charge to parties interested

Released October 15, 1947

Florida State Marketing Bureau
505 W. Adams Street
P. O. Box 779
Jacksonville 1, Florida

F648p
c. 2
AGRI-
CULTURAL
LIBRARY
1947 S1

ACKNOWLEDGMENT

We wish to acknowledge the splendid cooperation we received from both offical and private sources during the preparation of this voluminous statistical report.

The rail freight and express carlot shipment figures were secured from the Fruit and Vegetable Branch of the Production and Marketing Administration, U. S. Department of Agriculture in Washington, D.C.

Exhaustive vegetable acreage, yield, production and value data and other assistance was supplied by Mr. J. C. Townsend and Mr. J. B. Owens, Agricultural Statisticians, and Mr. G. N. Rose, Truck Crop Statisitician, U. S. Bureau of Agricultural Economics, Federal Building, Orlando, Florida.

Mr. E. E. Raasch, Statistician of the Citrus Inspection Bureau, Florida Department of Agriculture, Winter Haven, Florida, supplied us with important record data and other information.

The daily reports from their Road Guard Stations, showing passings of fruits and vegetables, were very helpful throughout the season and for annual records shown in this report.

Mr. William B. Conner, of the Florida Citrus Exchange, Tampa, wholeheartedly complied with our requests for specified citrus information.

Mr. H. F. Willson, Federal-State Citrus Market News Service, and Mr. Hugh S. Flynt, of the Federal-State Inspection Service, also supplied useful data for use in this report.

Mr. La Monte Graw, Manager of the Florida Vegetable Committee, prepared an article and rendered other assistance.

Several official and private agencies and individuals not already mentioned supplied information directly or indirectly to us, for which we extend our thanks.

The preparation of this report is tedious and requires much thought and long, hard work, and appreciation by the writer is extended to our Bureau staff for their efforts.

- - - - - - - - - - - - - - - - - - -

Comments which would lead to the improvement of this Annual Report would be appreciated.

GENERAL TABLE OF CONTENTS

Citrus Fruits Only (Oranges, Grapefruit and Tangerines)

1946-47 Volume and Value Analysis of Citrus 6-7
Canners' Prices for Delivered Citrus and Volume Canned by Seasons 12
Tree to Auction Costs or Vice Versa 13
Volume and Value Analysis of Citrus by Years 1927-28 to 1946-47 16-23
Interstate Truck Shipments of Citrus by Months 1946-47 26
Inspections of Citrus, including Limes, by Counties 37
Auction Sales 18 Seasons 1929-30 to 1946-47 40-42
Florida f.o.b. Sales Averages 1901-10 to 1946-47 Seasons 43
Citrus Price Analysis 1931-32 to 1946-47 Seasons 44-45
Bearing Acreage of Citrus by Counties 3 Seasons 68-69
Orange Production by States 83
Interstate Truck Distribution by States 84
Rail Distribution by States 85
Citrus Trucked Through Road Guard Stations 86

Vegetables and Miscellaneous Fruits Only

Let's Not Fool Ourselves, article by La Monte Graw 10-11
Acreage, Yield, Production and Value for 1946-47 Season (U.S.Dept.of Agri.) 14-15
Truck Shipments by Weeks 1946-47 38-39
Acreage of Principal Truck Crops for 22 Seasons 46-47
Gross f.o.b. Packed Value 16 Seasons 48
Fall, Winter and Spring Acreage by Counties for 3 Seasons 70-77
Acreage, Yield and Value by Seasons 1929-30 to 1946-47 78-82

All Fruits and Vegetables

General Summary of the 1946-47 Season 1-4
Production and Value for 13 Seasons 5
Disposition of Units of Production and of carloads according to uses 8-9
Transportation - Freight, Express, Boat and Truck 1946-47 Season 24-27
Transportation - Freight, Express, Boat and Truck 10 Seasons 28-31
Transportation - Freight Carloads by Counties of Origin 32-35
Federal-State Inspections by Commodities 1946-47 Season 36
Weather Conditions and Production 1946-47 Season, by G. N. Rose 61
Acreage by Counties, All Fruits and Vegetables, 3 Seasons 62-69

General Agricultural Statistics

Egg and Poultry Prices in Jacksonville 1921-47 and in Tampa and Miami 1939-47 49-51
Livestock, General Facts of Industry by L. H. Lewis 52-53
Livestock Prices in Jacksonville and Southeast 54-55
General Crop Statistics 1920-1947 (Corn,Cotton,Peanuts,Tobacco, etc.) 56-57
Comsumption of Important fruits, vegetables, grains, meats,etc., in U.S. 58-59
Tobacco - Production, Value and Auction Data by Seasons 60
Comparison of grain prices, poultry and egg prices in Jacksonville 86

FLORIDA DEPARTMENT OF AGRICULTURE
STATE MARKETING BUREAU
1946-47
ANNUAL FRUIT AND VEGETABLE REPORT

By Frank H. Scruggs, Market News Specialist

VOLUME AND VALUE OF ALL FRUITS AND VEGETABLES

Another eventful crop season has passed but the beginning of the 1947-48 season is so upset as these words are written, October 17, 1947, that it hardly seems useful to go into the history of the 1946-47 season, which was only moderately and unevenly successful.

Looking back over the weather summary since 1925, no season shows such heavy rains and flooded conditions in September and to October 17 as prevailed this season in South Florida and to a lesser extent in Central Florida and Westward to the Suwannee River.

High winds and heavy rains lashed Florida's fruit and vegetable areas in South and Central Florida. Two hurricanes and two or more near hurricanes brought high winds and torrential rains over most of South Florida. Palm Beach, Broward and Dade Counties where the bulk of Florida's vegetable crops are grown, were already suffering from high water.

As of October 14, the citrus production for 1947-48 had sustained considerable damage, most of the vegetables in South Florida were drowned out, pastures were flooded. At this date, much of the vegetable land in the important Fall and Winter vegetable areas was still under water and may continue that way for many days. Unofficial reports are that the rainfall in South and East Florida as far North as Jacksonville up to October 15 is 20-30 inches above normal.

Up to the time of the September 17 hurricane and subsequent periods of heavy rains, Florida citrus groves located mostly in Central Florida or on higher ground in South Florida had been favored with ideal weather conditions for crop production and recovery from the February 5-11 freezes of the 1946-47 season. The September 17, 1947 hurricane caused extensive losses of grapefruit in the lower East coast, particularly in Indian River and St. Lucie Counties, which Counties normally produce less than 10% of the total Florida crop, and had some of the best of the State grapefruit crop. Lower I.R. Counties furnish 25 per cent or more of the fresh grapefruit shipments. The loss of 40 per cent or more of high quality fruit, generally accepted by the higher class trade, will likely affect the fresh grapefruit situation The higher quality grapefruit in the various citrus sections should benefit marketwise An appreciable loss of grapefruit was also sustained by growers in Highlands, South Polk, Hardee, DeSoto, Manatee, and Pinellas Counties, where some of the better grapefruit is grown. Most of the grapefruit crop in Lee County on the West coast was blown off the trees. Heavy rains in late September and to October 15 continued to plague the East coast. Many groves were flooded and additional loss of fruit may likely be sustained. Associated reports out of Ft. Lauderdale say that 5,000-6,000 A. of orange trees planted on the lower ground of the Davie section have been ruined beyond recovery. Time will tell.

Livestock in South Florida and lower Central Florida is also suffering from heavily flooded pastures and rangeland. Unofficial reports say that 10,000 or more head have died from either drowning or starvation or a combination of the two. If there are no additional flood rains in late October and November the livestock in the sections South of Orlando should pull thru fairly well. There may be enough grass to sustain the range cattle but they should be getting fatter instead of barely holding their own in the Fall season. More Florida livestock has been marketed this year, and at high prices, than ever in the history of Florida.

Unlike some States, we give the full facts even if bad, believing that truth is the best policy even if it hurts. This Bureau would not do anything else.

There are some bright sides to the 1946-47 season and even some good prospects for the 1947-48 season.

The 1947 corn crop of 7,946,000 bushels is 15 per cent above average. Cottc yields are better than a year ago, the farmers expecting 10,000 bales as compared to

6,000 bales in 1946. Tobacco yields were 25,190,000 pounds as compared to 22,251,000 pounds, and peanuts 57,000,000 pounds against 45,600,000 pounds; sweet potatoes 1,139,000 bushels compared to 1,088,000 bushels in 1946. Corn, sweet potatoes, peanuts are selling higher than last year, while tobacco and cotton are lower at 40.7¢ and 32¢ per pound, respectively. Poultry and egg prices have run higher in 1947 although feed prices are up too. Beef cattle on September 15 averaged $13.70 per 100 pounds compared to $10.70 a year ago. Hogs average $22.90 per 100 pounds compared to $15.00 a year ago as of September 15.

Most of the crop mentioned had been harvested before the September 17 hurricane. West Florida, which has not had too much rain, is the principal source of some of the field crops.

This brings us up to the fruit and vegetable summary for last year.

FRUITS AND VEGETABLES IN THE 1946-47 SEASON

Excessive rains delayed field operations in Palm Beach and Broward Counties last year. The hurricane of October 7-8 did some damage to vegetables and a lot to citrus. A tropical storm with heavy rains around November 1 did extensive damage to vegetables in part of the Everglades but less damage in the Ft. Pierce (St. Lucie County) tomato and vegetable area, and in the Broward County bean and vegetable area, and in the Dade potato and tomato area. Heavy rain was followed by hot sunshine with consequent heavy scald damage in most South Florida sections.

Strong winds December 2-5 whipped badly the crops along the lower East coast in the Lake Okeechobee section. Heavy rains December 13-14 did not do any good. Unseasonably warm weather prevailed throughout the State until early February. This was wonderful for tourists but bad on citrus which needs some cool to cold temperatures to ripen, sweeten and to make it firm for holding in the cars, warehouses, stores and homes until it is consumed.

Tender crops and tender citrus were hit hard by the freezes of February 5, 6, 10 and 11, 1947. Heavy rains March 1 and high winds March 2 further reduced tender crop acreage. Other damaging rains occurred in the Spring of last season.

We are not complaining about Florida weather conditions, as the weather conditions are most delightful generally to 2,500,000 Florida people and to about 1,000,000 out-of-State people who spend their winters or vacations here. Our freezes, although doing enormous damage to fruits and vegetables at times, are of short duration. We can have a freeze on Sunday and have real baseball weather by Wednesday. We expect the storms, as that is the penalty we must pay for sticking out into the Ocean and Gulf, and having over 1,200 miles of shoreline. We are semi-tropical and that means lots of storms and rains. Florida is a green State the year round in spite of some freezes and this green is attractive to all who live or come here. We have lots of lakes, bays and rivers which help to keep us wet but attractive. We can grow beans, eggplant, peppers, squash and strawberries in January and February and no other State can do this in any volume or regularly.

Even though we can and do grow these tender vegetables in the Winter it is strictly a gamble on the part of the individual grower who has to have nerve and comeback powers. The Nation owes a debt of gratitude to these hardy farmers who get fresh produce to them in the dead of winter even though the price might be high. Whenever the price is extra high it means that for every farmer who was not hurt there were probably ten who suffered heavy losses from a freeze and that the supply is very light.

GROSS VALUE OF 1946-47 CROP $248,700,000

In spite of all the weather handicaps, Florida produced 262,992 carloads of fruits and vegetables with a gross f.o.b. Florida packed value of $248,700,000. This was considerably lower than for the 1945-46 season when we produced 286,427 carloads for all purposes, with a gross value of $364,300,000. The 1945-46 season was the best season gross and net in the history of Florida. The gross value in 1946-47 season just passed was considerably above the pre-war average of about $110,000,000 gross. Our production of 262,992 carloads for the past season was higher than any prior year except the record 1945-46 season.

Gross prices during the last season or so cannot be fairly compared with pre-war seasons as all labor, crate materials, equipment and other costs have increased two, three or four-fold. Generally speaking, the citrus and vegetable growers did not do very well during the 1946-47 season. The extra costs of these storms or freezes, which require replanting of crops once or twice or more do not show up in the gross and net calculations. The citrus growers had to battle a freeze from February 5-11, using much fuel and much extra labor. California is used to this expense, while it is rather new to us. California is a good State in spite of her smoke and fog and cloudbursts. Florida at the moment sympathizes with California.

SOME RANDOM THOUGHTS

When Will We Get A 125,000,000-box Citrus Crop?

Most people in the citrus industry have been predicting that we would have tremendous increases in the citrus production from 1945 on, and that we would have 150,000,000 boxes by 1950. At the time these predictions were first made we had a crop of 86,000,000. They seemed right and probably are right. For the 1946-47 season it looked like 102,000,000 boxes or more. Along came a hurricane in October 1946 and a freeze in February 1947 and we ended up with 83,100,000 boxes used and another 4,600,000 boxes abandoned because of poor markets. In August 1947 it looked like a crop of 90 to 95 million boxes and we were hit by a hurricane in South Florida. The trees had not fully recovered from the freeze of February 1947 or we might have had prospects of considerably more than 100,000,000 boxes. We have the potentials for a 150,000,000-box crop by 1950, but is nature going to let the crop go that high? We do have good citrus weather sometimes for two years in a row and it is conceivable that our crop could jump to 125,000,000 or more in two years. So far nature in its destruction has been good to the citrus industry as a whole and saved them from some terrific marketing problems. Our 1946-47 crop is now just about average size and manageable. The price structure over this nation is still unsettled but marketing may not be any more of a problem than for the 1946-47 season just passed.

HIGH COST OF TRANSPORTATION

The writer, who has been with the Florida State Marketing Bureau since 1929 and four years longer in Florida and has seen the trucking of fruits and vegetables develop from scratch and has heard the railroad men groan and despair of ever effectively meeting this truck transportation and to a slightly lesser extent the transportation by boat from Florida, finds it interesting if not tragic to see them asking for higher and higher rates which they cannot or will not get down fast enough when the good times are over. The railroads have their costs problems and they can easily rationalize their present behavior. They are apparently tied to the present levels of high labor and material costs. After getting out of the bankrupt doldrums of the thirties, and before, they feel like they are entitled to a fair profit on their investment. Some growers would like to see the combined investment costs to present owners of all railroads out of bankruptcy and the combined net return for same. It must not be forgotten that the railroads own a tremendous volume of valuable unimproved real estate which they do not use in their operations. This could be sold and their taxes reduced. While the railroads may be tied to the high labor and material costs and claim a right to higher rates, the Florida grower is not so fortunate. He is tied to these same high costs but he has no Interstate Commerce Commission to help guarantee him a profit. We agree that the railroads are very necessary to this nation and that they did a good job during the war and are still doing so.

Perhaps we have our heads in the sands. We may never go back to pre-war prices; we may be permanently on an inflationary level 50-100% higher than pre-war Still we cannot get away from the fact that 4,600,000 boxes of citrus were abandoned last season at certain periods because the markets would not justify the cost of packing, marketing and transportation. We cannot forget that 1,465 carloads of cabbage and 1,500 cars of watermelons were abandoned for the same reason. We did not do so badly financially on the volume we were able to grow last year but this surplus volume and these periodic low prices seem a portent of worse things to come.

All of us, including the railroads, are spinning around on the wheel of fortune or disaster, and where she stops nobody knows.

DETAILS OF TRANSPORTATION OF FRUITS AND VEGETABLES FOR 1946-47 SEASON

Freight volume of citrus at 68,569 cars was the second lowest in the last five years, the high year being the 1943-44 season with 83,328 cars. The 1946-47 vegetable volume of 30,538 was the lowest in the last six years, the highest volume being in 1945-46 when 57,310 carloads were shipped by straight freight. (See page 28.)

The trucked out shipments of fruits and vegetables were the equivalent of 32,007 carloads, compared to 25,604 for 1945-46 and 17,161 carloads in 1944-45 season, showing a healthy increase over the last year of the war when 17,161 carloads were moved by truck. The record year was in 1940-41 just before the war when 41,712 carloads were moved by truck.

The railroads moved 111,756 carloads of fruits and vegetables out of a total freight express truck and boat movement of 148,606 carloads. In the 1940-41 season the railroad moved 79,775 out of 140,844 carloads moving out of State by all forms of transportation. Back in 1940-41 the coastwise boats were a factor with 19,357 carloads. The railroad percentage volume for 1946-47 is some higher than for 1940-41 season as the number of packages per car is generally 10-15 per cent higher than before the war. The trucking operations are increasing rapidly but the boat operations are increasing slowly.

1946-47 PRICES COMPARED WITH 1945-46 SEASON

The following tabulation shows the f.o.b. Florida gross packed value of some of the commercial fruits and vegetables in Florida. Commodities sold to canners or which were not packed, such as watermelons and some cabbage, are included at their gross f.o.b. average sales per unit.

Commodity	Unit	1946-47	1945-46	Volume Produced**	
				1946-47	1945-46
Beans, fresh mkt.	Bu.	$ 2.90	$ 2.70	5,749,000	7,355,000
Beans, for processing	Ton	116.00bu$1.67	111.44bu$1.67	800,700 bu	1,114,000 bu
Beans, all uses	Bu.	2.74	2.54	6,549,700	8,469,000
Limas	Bu.	3.51	3.28	338,000	555,000
Cabbage	Ton	37.80	49.00	99,400	116,200
Celery	Crts.	3.84	2.27	4,564,000	6,439,000
Cucumbers	Bu.	4.14	3.72	1,204,000	1,520,000
Eggplant	Bu.	2.42	1.63	725,000	1,344,000
Escarole	Bu.	1.30	-	910,000	***
Lettuce, Boston&Rom.	4-6 dz crts	2.95	3.00	70,000	142,000
Lettuce, Iceberg	4-6 dz crts	2.96	3.60	189,000	210,000
Peas, English	Bu.	2.95	3.00	64,000	118,000
Peppers	Bu.	4.14	2.45	2,193,000	3,050,000
Potatoes	Bu.	2.00	1.95	2,738,000	6,010,000
Tomatoes, fresh mkt.	Bu.	6.50	5.25	2,892,000	4,458,000
Tomatoes, fresh mkt.	Lug basis*	3.90	3.15	-	-
Tomatoes, processing	Ton	37.90bu$1.00	26.90 bu 70¢	305,700 bu	212,000 bu
Tomatoes, All	Bu, All	5.97	5.04	3,197,700	4,670,000
Carrots, Winter	Bu.	1.05	.85	80,000	230,000
Cauliflower, Winter	Crts.	1.75	2.25	120,000	150,000
Cantaloupes	Jumbo crts.	2.55	3.00	40,000	36,000
Strawberries	36-pt crts.	9.07	7.91	309,000	224,000
Watermelons	1000-M	447.00	525.00	12,123,000	10,575,000

* The tomato lug has a net weight approximately 60 per cent of the weight of a bushel

** These total volumes included any volumes abandoned because of markets too low to justify harvesting. Considerable volume was abandoned during the past two years. See pages 78-82 for more details.

***Uncertain as to the container unit used. The 1½ bushel hamper was formerly used.

FLORIDA PRODUCTION AND VALUE FOR 13 SEASONS
(Includes Canned and Locally Consumed)

ALL CITRUS

				Weighted Average All Production		
Season	Carloads Production	Boxes	Florida Gross Value	Gross	Marketing	Net
1934-35	82,865	32,835,854	$42,797,752	$1.33	$1.06	$ .27
1935-36	74,491	29,462,052	53,189,191	1.81	1.12	.69
1936-37	102,827	40,601,208	68,838,758	1.70	1.09	.61
1937-38	103,964	40,939,629	53,285,352	1.30	1.08	.22
1938-39	143,369	56,447,995	58,646,931	1.04	.97	.07
1939-40	109,119	42,973,112	50,365,127	1.17	1.05	.12
1940-41	140,903	55,890,754	64,192,695	1.15	.99	.16
1941-42	120,089	48,400,000	80,572,620	1.66	1.09	.57
1942-43	154,909	68,700,446	153,052,989	2.23	1.12	1.11
1943-44	181,592	80,800,000	199,688,696	2.47	1.31	1.16
1944-45	156,759	69,000,000	201,912,530	2.93	1.31	1.62
1945-46	197,050	86,000,000	236,230,700	2.75	1.29	1.46
1946-47	190,730	83,100,000	146,565,580	1.76	1.32	.44

	ALL VEGETABLES		ALL VEGETABLES & MISCL. FRUITS	
Season	Carloads Production	Florida Gross Value	Carloads Production	Florida Gross Value
1934-35	48,411	$30,134,054	57,306	$33,936,126
1935-36	45,718	30,666,719	52,670	34,144,707
1936-37	51,885	34,445,922	60,118	39,090,756
1937-38	70,000	37,306,680	82,130	41,410,710
1938-39	68,506	38,489,172	77,606	43,573,732
1939-40	65,151	37,962,385	75,404	42,738,720
1940-41	58,560	43,077,816	68,486	48,562,482
1941-42	70,191	57,417,670	80,219	62,706,220
1942-43	63,221	81,823,200	69,445	87,555,990
1943-44	70,219	87,328,394	79,605	94,944,402
1944-45	69,225	99,441,550	81,213	107,673,150
1945-46	76,943	116,239,000	89,377	128,099,000
1946-47	58,049	91,618,000	72,262	102,144,000

ALL FRUITS AND VEGETABLES

Season	Carloads Production	Florida Gross Value
1934-35	140,171	$ 77,156,615
1935-36	127,181	76,733,879
1936-37	162,945	107,929,514
1937-38	186,094	94,696,062
1938-39	220,975	102,220,663
1939-40	184,563	93,103,847
1940-41	209,389	112,768,552
1941-42	200,308	143,278,840
1942-43	224,554#	240,608,979
1943-44	261,197#	294,633,098
1944-45	237,912#	309,585,680
1945-46	286,427#	364,329,700
1946-47	262,992	248,709,580

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON-AUGUST 1,1946-JULY 31,1947

Carlot Shipments	Freight Straight & Mixed	Carloads Total Freight	Carloads Express	Boxes Freight Boat, Truck and Express	Gross FOB Returns Florida Points Box	Gross FOB Returns Florida Points For Crop	Production and Marketing Costs Box	Production and Marketing Costs For Crop	Net Return to Florida Growers Box	Net Return to Florida Growers For Crop
Oranges	43,390	48,917	2,596	30,143,271	$2.62	$ 78,975,370	$1.78	$53,655,022	$ .84	$25,320,348
Grapefruit	12,606	15,387	976	9,380,706	2.18	20,449,939	1.45	13,602,024	.73	6,847,915
Tangerines	2,974	4,265	58	2,496,546	3.75	9,362,408	2.40	5,992,071	1.35	3,370,337
Mxd.Citrus	9,599	Converted		-	-	-	-	-	-	-
Totals	68,569	68,569	3,630	42,020,523	$2.59	$108,787,717	$1.74	$73,249,117	$ .85	$35,538,600

GENERAL DISPOSITION ANALYSIS OF THE FLORIDA CITRUS CROP FOR SEASON 1946-47

BOXES	StraightCars Freight	Mxd.Cars Freight	Mxd.Cars Express	Tot.Bxs. Domestic Boat	Trucked Out	Rail, Boat Truck*	Canned Fresh Bxs.	Consumed Boxes	#Exports	Grand Total Boxes
Oranges	21,642,806	2,789,485	1,038,180	1,163,200	3,509,600	30,143,271	19,825,485	2,677,793	153,451	52,800,000
Grapefruit	6,453,849	1,403,469	390,588	574,800	558,000	9,380,706	15,864,346	1,098,797	56,151	26,400,000
Tangerines	1,294,741	651,373	23,232	88,800	433,400	2,496,546	930,751	472,703	-	3,900,000
Total	29,391,396	4,844,327	1,452,000	1,826,800	4,506,000	42,020,523	36,620,582	4,249,293	209,602	83,100,000

CARLOADS				Total Rail	Boat	Rail Boat	Truck	Rail Boat Truck*			Exports	
Oranges	43,390	5,527	2,596	51515	2908	54421	8774	63,195	49,563	6,695	384	119,837
Grapefruit	12,606	2,781	976	16363	1437	17800	1395	19,195	39,661	2,747	140	61,743
Tangerines	2,974	1,291	58	4323	222	4545	1096	5,641	2,327	1,182	-	9,150
Total	58,970	9,599	3,630	72199	4567	76766	11265	88,031	91,551	10,624	524	190,730

Estimated Cost of Producing and Marketing 88,031 Cars of ORANGES, GRAPEFRUIT, AND TANGERINES.

Cost of production such as fertilizer, spray materials, irrigation, pruning, labor, fuel, etc., but not including interest or taxes on strictly grove acreage, per Standard 1-3/5 bushel boxes.

ORANGES $ .53 GRAPEFRUIT $ .37 TANGERINES $ .68 WEIGHTED AVERAGE $ .50

Cost of picking, hauling, packing, selling, and other average ordinary marketing charges.

ORANGES $1.25 GRAPEFRUIT $1.08 TANGERINES $1.72 WEIGHTED AVERAGE $1.24

Total ordinary and average cost of production and marketing of citrus

ORANGES $1.78 GRAPEFRUIT $1.45 TANGERINES $2.40 WEIGHTED AVERAGE $1.74

1. Domestic boat movement reported: 4,567 cars; Exports 499 cars.
2. Estimated boxes per car: Straight Freight-Oranges 498.1, Grapefruit 511.97, Tangerines 435.35; Mixed Freight-504.67; Mixed Car Express-400 boxes; Boat Domestic & Export-400 boxes; Truck-400 boxes per car.
3. Mixed Car Freight Analysis: Oranges 57.58, Grapefruit 28.97, Tangerines 13.45 per cent.
4. Mixed Car Express Analysis: Oranges 71.5, Grapefruit 26.9, Tangerines 1.6 per cent.
5. Box cars used: Oranges, including any Tangerines, 4,597; Grapefruit 482; Mixed 1,611. Total 6,690.
6. Abandoned for market reasons: Oranges 1,200,000; Grapefruit 2,600,000; Tangerines 800,000. This total of 4,600,000 boxes not included in Disposition Analysis. These estimates made as of Sept. 20 and subject to revision.

* Interstate by-products: Oranges 60,069, Grapefruit 1,260 boxes, included in rail or truck shipments.

# Exports include U.S. Government exports of 53,027 boxes of oranges and 56,151 boxes of grapefruit. All exports included in Grand Total of boxes.

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON 1946-47 (Cont'd.)

TRUCK SHIPMENTS TO OUT-OF-STATE MARKETS (400 boxes to car)									
ORANGES	Carlot equiv.	8,774 or	$ 3,509,600 boxes.	Gross at	$2.62	$ 9,195,152	Net* at	$ .84	$ 2,948,064
GRAPEFRUIT	Carlot equiv.	1,395 or	558,000 boxes.	Gross at	2.18	1,216,440	Net* at	.73	407,340
TANGERINES	Carlot equiv.	1,096 or	438,000 boxes.	Gross at	3.75	1,643,000	Net* at	1.35	591,840
ALL CITRUS	Carlot equiv.	11,265 or	4,506,000 boxes.	Gross at	$2.67	$ 12,054,592	Net* at	$ .85	$ 3,947,244
FREIGHT, EXPRESS, BOAT AND TRUCK SHIPMENTS TO OUT-OF-STATE MARKETS									
ORANGES	Carlot equiv.	63,195 or	$30,143,271 boxes.	Gross at	$2.62	$ 78,975,370	Net* at	$ .84	$ 25,320,348
GRAPEFRUIT	Carlot equiv.	19,195 or	9,380,706 boxes.	Gross at	2.18	20,449,939	Net* at	.73	6,847,915
TANGERINES	Carlot equiv.	5,641 or	2,496,546 boxes.	Gross at	3.75	9,362,048	Net* at	1.35	3,370,337
ALL CITRUS	Carlot equiv.	88,031 or	$42,020,523 boxes.	Gross at	$2.59	$108,787,357	Net* at	$ .85	$ 35,538,600
EXPORT SHIPMENTS BY BOAT (400 boxes to car)									
ORANGES	Carlot equiv.	384 or	$ 153,451 boxes.	Gross at	$2.62	$ 402,042	Net* at	$ .84	$ 128,899
GRAPEFRUIT	Carlot equiv.	140 or	56,151 boxes.	Gross at	2.18	122,409	Net* at	.73	40,990
ALL CITRUS	Carlot equiv.	524 or	$ 209,602 boxes.	Gross at	$2.51	$ 524,451	Net* at	$ .81	$ 169,889
FRESH CITRUS CONSUMED IN FLORIDA (400 boxes to car)									
ORANGES	Carlot equiv.	6,695 or	$ 2,677,793 boxes.	Gross at	$2.35	$ 6,292,814	Net* at	$ .72	$ 1,928,016
GRAPEFRUIT	Carlot equiv.	2,747 or	1,098,797 boxes.	Gross at	1.90	2,087,714	Net* at	.60	629,280
TANGERINES	Carlot equiv.	1,182 or	472,703 boxes.	Gross at	3.30	1,559,920	Net* at	1.15	543,608
ALL CITRUS	Carlot equiv.	10,624 or	$ 4,249,293 boxes.	Gross at	$2.21	$ 9,940,448	Net* at	$ .73	$ 3,100,904
FRESH CITRUS USED FOR PROCESSING IN FLORIDA (400 boxes to car)									
ORANGES	Carlot equiv.	49,563 or	$19,825,485 boxes.	Gross at	$ .82	$ 16,256,898	Net* at	$-.05	$ - 991,274
GRAPEFRUIT	Carlot equiv.	39,661 or	15,864,346 boxes.	Gross at	.65	10,311,825	Net* at	-.04	- 634,573
TANGERINES	Carlot equiv.	2,327 or	930,751 boxes.	Gross at	.80	744,601	Net* at	-.42	- 391,915
ALL CITRUS	Carlot equiv.	91,551 or	$36,620,582 boxes.	Gross at	$ .75	$ 27,313,324	Net* at	-.5½	$ -2,017,762
TOTAL RAIL, BOAT, TRUCKED, PROCESSED, AND LOCALLY CONSUMED									
ORANGES	Carlot equiv.	119,837 or	$52,800,000 boxes.	Gross at	$1.93	$101,927,124	Net* at	$ .50	$ 26,385,989
GRAPEFRUIT	Carlot equiv.	61,743 or	26,400,000 boxes.	Gross at	1.25	32,971,887	Net* at	.26	6,883,612
TANGERINES	Carlot equiv.	9,150 or	3,900,000 boxes.	Gross at	2.99	11,666,569	Net* at	.90	3,522,030
ALL CITRUS	Carlot equiv.	190,730 or	$83,100,000 boxes.	Gross at	$1.76	$146,565,580	Net* at	$ .44	$ 36,791,631

NOTE: * Gross refers to returns f.o.b. cars Florida shipping points, and net refers to returns to growers or fruit owners before deducting for interest and taxes but after deducting for cost of production and marketing.

1. Trucked out shipment figures were based on passings through Road Guard Stations. Road Guard Stations for checking were open October 1-June 15. Prior and later passings estimated.
2. Cannery fruit represents average gross price delivered to canners, and the net price is the gross less the estimated picking, hauling, and marketing charges.
3. Figures for Consumed in Florida are rough estimates based on population, prices, etc. Our summer population in 1947 was nearly 2,400,000. Our winter tourist population is estimated at 750,000-1,000,000 people at height of season in February.
4. Abandoned for marketing reasons 4,600,000 boxes, which represented a loss of $2,420,000, which was not deducted.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS BY PRODUCTION UNITS

1946-47 SEASON

COMMODITY	Unit	All Freight Units	LCL Express	Trucked Out	Boat	Processed	Florida Consumption	Total Production Units Used	Abandoned
Beans	Bu.	2,536,600	60,000	1,931,400	-	800,700	660,000	5,988,700	561,000
Limas	Bu.	153,800	5,200	114,500	-	-	64,500	338,000	-
Cabbage	50 lbs.	1,344,520	2,000	1,501,480	-	-	400,000	3,248,000	728,000
Cabbage	Ton.	33,613	50	37,537	-	-	10,000	81,200	18,200
Celery	Crt.	3,812,700	12,000	377,400	40,000	-	321,900	4,564,000	-
Cucumbers	Bu.	648,600	16,000	403,200	1,200	-	135,000	1,204,000	-
Eggplant	Bu.	235,680	40,000	355,320	-	-	94,000	725,000	-
Escarole	Bu.	813,500	20,000	65,250	-	-	11,250	910,000	-
Lettuce,	4-6 dozen Crts	49,000	8,000	49,500	-	-	82,500	189,000	-
Peas, English	Bu.	15,020	2,000	15,080	-	-	31,900	64,000	-
Peppers	Bu.	1,082,400	117,600	793,000	-	-	200,000	2,193,000	-
Potatoes	Bu.	2,009,850	2,000	385,550	65,600	-	275,000	2,738,000	-
Tomatoes	Bu.	1,464,410	4,800	1,049,290	-	305,700	373,500	3,197,700	-
Miscl. Vegetables	Bu.	1,525,600	82,400	1,235,500	2,000	80,000	800,000	3,725,500	-
Mixed Cars		Converted	Converted	-	-	-	-	Converted	-
TOTAL UNITS(VEGS)#		15,725,293	372,050	8,314,007	108,800	1,186,400	3,459,550	29,166,100	1,307,200
Strawberries	36 pt Crt	47,550	11,200	276,750	-	**13,500	63,000	412,000	-
Watermelons	***Crts	(3,772,500)	-	(1,639,000)	-	-	(650,000)	(6,061,500)	(750,000)
Watermelons	Melons	7,545,000	-	3,278,000	-	-	1,300,000	12,123,000	1,500,000
Miscl. Fruits	Bu.	3,600	40,000	72,400	-	68,000	120,000	304,000	-
TOTAL UNITS(Misc.Fruits)#		3,823,650	51,200	1,988,150	-	81,500	833,000	6,777,500	750,000
Oranges	Crt.	24,432,291	1,038,180	3,509,600	1,316,651	19,825,485	2,677,793	52,800,000	1,200,000
Grapefruit	Crt.	7,857,318	390,588	558,000	630,951	15,864,346	1,098,797	26,400,000	2,600,000
Tangerines	Crt.	1,946,114	23,232	438,400	88,800	930,751	472,703	3,900,000	800,000
TOTAL UNITS(CITRUS)		34,235,723	1,452,000	4,506,000	2,036,402	36,620,582	4,249,293	83,100,000	4,600,000
GRAND TOTAL UNITS#		53,784,666	1,875,250	14,808,157	2,145,202	37,888,482	8,541,843	119,043,600	6,657,200

Notes cover Pages 8 and 9

NOTES: There is considerable difficultyin working out a detailed disposition sheet for vegetables and miscellaneous fruits as comprehensive data is not as available as for citrus. First it was considered advisable to use the U.S. Dept. of Agriculture estimate of total production and work back from there. We have the records on the truck shipments out of State which figures are used. We have the records on straight freight and boat for individual commodities. We have **only the totals for mixed freight and** LCL express. The Florida consumption figures are only estimates as there are no actual records. We had to apportion the mixed freight and mixed express totals as best we could to the various commodities with the handicap of having to make all of the separate totals check with the total official crop estimate. An additional problem was the disposition of the volume of squash, radishes, cauliflower, carrots, spinach, broccoli, endive, etc., included in the miscellaneous figures for vegetables. Miscellaneous Fruits included avocados, Persian and Key limes, mangoes, grapes, guavas, persimmons, blueberries, kumquats, etc.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS IN CARLOTS, OR EQUIVALENT, AND VALUE

1946-47 SEASON

Commodity	Straight Freight Cars	Mixed Freight Cars	LCL Express Cars	Boat Cars	Trucked Out Cars	Processed	Florida Consumption	Total Used Carlots	Abandoned ##	Total FOB Gross Value
Beans	3,403	561	100	-	3,219	1,334	1,100	9,717	935	$ 16,389,000
Limas	265	30	10	-	229	-	125	659	-	1,187,000
Cabbage	2,459	230	2	-	3,003	-	800	6,494	1,465	3,069,000
Celery	8,747	79	10	100	1,020	-	870	10,826	-	17,535,000
Cucumbers	1,138	92	40	3	896	-	300	2,469	-	4,964,000
Eggplant	81	304	100	-	756	-	200	1,441	-	1,664,000
Escarole	827	444	50	-	145	-	25	1,491	-	1,183,000
Lettuce	116	47	20	-	90	-	150	423	-	559,000
Peas, English	14	12	5	-	26	-	55	112	-	189,000
Peppers	744	847	280	-	1,586	-	400	3,857	-	9,086,000
Potatoes	4,001	19	5	164	701	-	500	5,390	-	5,475,000
Tomatoes	3,249	40	20	-	2,526	764	900	7,499	-	19,098,000
Miscl. Vegetables	790	1,999	206	5	2,471	200	2,000	7,671	-	11,200,000
Mixed Cars	-	Converted	Converted	-	-	-	-	-	-	-
TOTAL VEGETABLES	25,834	4,704	848	272	16,668	2,298	7,425	58,049	2,400	$ 91,618,000
Strawberries	99	-	(28)*	-	615	30	140	912	-	3,739,000
Watermelons	7,963	-	-	-	3,278	-	1,300	12,541	1,500	5,419,000
Miscl. Fruits	9	-	**100	-	181	170	300	760	-	1,368,000
TOTAL MISC.FRUITS	8,071	-	128	-	4,074	200	1,740	14,213	1,500	$ 10,526,000
TOTAL VEGS. AND MISCL. FRUITS	33,905	4,704	976	272	20,742	2,498	9,165	72,262	3,900	$ 102,144,000
Oranges	43,390	5,527	2,596	3,292	8,774	49,563	6,695	119,837	3,000	101,927,124
Grapefruit	12,606	2,781	976	1,577	1,395	39,661	2,747	61,743	6,500	32,971,887
Tangerines	2,974	1,291	58	222	1,096	2,327	1,182	9,150	2,000	11,666,569
Mixed Citrus	-	Converted		-	-	-	-	-	-	-
TOTAL CITRUS	58,970	9,599	3,630	5,091	11,265	91,551	10,624	190,730	11,500	$ 146,565,580
GRAND TOTAL	92,875	14,303	4,606	5,363	32,007	94,049	19,789	262,992	15,400	$ 248,709,580

Notes cover Pages 8 and 9

NOTES: # Ordinarily units of different kinds are not added but if the 50-lb sack is used for cabbage and the number of watermelons *** are divided by two to get crates, we find that all of the units are bushels or the equivalent of bushels with the exception of citrus which are in 1-3/5 bu. crates. * The 28 cars of strawberries assigned to L.C.L. express is without record data to support it. We know that some strawberries went out L.C.L. express and we included in this figure any shipments by air. ** We have no shipping record to support this 100 car estimate for L.C.L. express miscellaneous fruits, but since completing our shipment tabulation we learn that approximately 109 carloads of Persian limes were inspected for LCL express. Probably another 100 cars or more of avocados, mangoes, etc., went out by L.C.L. express. ## Abandoned because of market conditions and not included in the gross FOB Florida value. The gross includes the production, marketing costs, and packing costs if packed, and profit, if any. Most, or all, crops showed a profit.

LET'S NOT FOOL OURSELVES

By La Monte Graw, Manager, Florida Vegetable Committee

Florida 1946-47 vegetable crops yielded good prices for the grower, if he pulled his crop through, and there seems to be a feeling on the part of many growers that "everything in the future will come out all right." After all, they say, grower prices did not break down as predicted by agricultural economists and others, and those fortunate enough to pull their crops through got good prices. Therefore, they conclude, we can grow our products as we have in the past, package and sell them the same way, and **still** make money, IF we are lucky enough not to get drowned or frozen out.

Mother Nature has again been the ally of those who contend we can do business in the same old way. She has reduced the 1947 Fall crops, and they will probably bring good prices. (The Everglades Section early 1947 Fall plantings are practically drowned out as result of storms, rains and mid-September hurricane.)

Does that mean we can expect to continue to plant heavily, gambling that the market price will be high enough in future years to cover a cost increase of 150%-200% over pre-war, and still give us a profit? I don't think so.

Facts are facts. It is a fact that weather conditions last Spring and this Fall have reduced the crop, and prices held up. However, we can't forget that competing areas were also kicked around at the same time, a very unusual condition, and the Nation has had the highest employment and highest national income ever known.

It is a fact that we may have good prices all through 1947-48 if weather continues to cut the production in Florida and competing areas.

However, if we examine the experience of vegetable growers in areas where the supply has been ample during their season, we find that the vegetable price level has dropped considerably. Some of them took severe lickings.

What about the years when we - and our competitors - will have large crops; when the purchasing power of the Nation will drop from the present peak; when the full force of competition from frozen foods will be felt? Can we afford to sit back and say "everything will come out all right"?

Growers and shippers who have analyzed the situation don't believe so. They point out that:

(1) We can produce more.
(2) The cost of producing our crops has increased greatly.
(3) The transportation situation has not improved, and won't for some years.
(4) The terminal markets are antiquated and inefficient, resulting in costly delays and product deterioration.
(5) Retailers, with the exception of the big super-markets, are not equipped to store and display this increased volume, and seem to have little interest in increasing their sales through lower mark-ups.
(6) The housewife has fewer dollars for food, and
(7) The consumer price is too high - two to three times what the grower gets.

A nationally recognized authority warned the Vegetable Growers of America at their recent annual meeting that the trend is away from fresh produce. He even predicted that in future years the housewife may buy one-third of her fruits and vegetables frozen, one-third canned, and the remaining one-third fresh.

The retail trend is toward self-service. The retailer wants consumer-sized packages he can put into his display case without a lot of preparation and waste, both expensive to him.

The housewife is turning more than ever to convenient sized packages. She is more "finicky" and wants vegetables more mature, more palatable, better appearing, and in a package she can carry home in her arms and store in her limited refrigerator space. She wants something she can prepare with a minimum of effort and expense - and she wants it clean.

When the housewife had to buy fresh vegetables, particularly in the out-of-season months when the supply was relatively small, her wishes could be ignored. Today, when the frozen food people, the canners and others are fighting for her business; when the production of fresh fruits and vegetables is so great that it can no longer be absorbed by the "luxury" market, but must be sold in large quantities to consumers in the lower income groups; when the consumer price has been loaded down with costs that put fresh vegetables beyond the ability of many consumers to buy - today we must begin merchandising our products, or we won't be able to sell enough of them tomorrow to cover our costs and return a fair profit.

The grower who complacently figures that we will be "all right" if we do nothing to fit ourselves to changing conditions is in for a sad awakening, though he may go broke before he does wake up.

Certainly our competitors are not going to sit back and do nothing. Vegetable growers and shippers in Texas and California are aggressively going after the business. Mexico and Cuba are coming back into the picture bigger than ever. They can produce anything we can, and will do it as soon as transportation conditions permit. Many markets formerly served by Florida have been taken over by these competing areas. Certainly the transportation companies aren't going to give up their fight for higher rates. Proposed increases would add millions of dollars to the growers' cost of doing business, and will tend to restrict the market.

The distributors and retailers aren't going to make a lot of improvements in their way of doing business unless compelled to do so. Privately, some of them admit they must do a better job - and do it at lower cost - but terminal facilities and handling methods are not likely to be improved very much until the distributors find themselves losing money. Retailers continue to expect a big profit from small volume, rather than trying to sell a larger quantity and better variety at nominal prices. Most of them would have to install expensive display and storage equipment to do a better job.

On top of all this is the desire of the housewife for better foods for less money. Fresh vegetables must compete for her business on quality, appearance, availability, variety, convenience, cleanliness and price - with frozen foods and better-than-ever canned goods.

During the past year the frozen food people have learned to their sorrow that the housewife won't accept a product just because it is frozen. If the quality and value aren't there, she won't buy. Millions of dollars were lost by the frozen foods industry last year because some of the processors tried to make a quick profit from low quality merchandise. This year, having learned their lesson, they are going to be offering good merchandise at a price.

We congratulate ourselves on the fact that we can get good prices when production is reduced by Mother Nature, without realizing that this same condition has caused high consumer prices for poorer quality vegetables. The result is that many housewives stop buying Florida fresh produce and turn to other food items. It will be a hard job to win many of them back.

Let's not fool ourselves - we have a big fight ahead - and we can't win it unless we fight as a unit for what is rightfully ours.

The growers and shippers of Florida vegetables have generally done a good job of improving their production procedures - water control, soil analysis and treatment, labor saving cultural and protective equipment, washing and grading equipment,etc.

When they do an equally good job of adjusting plantings to avoid market gluts - diverting waste parts and surplus to profitable by-products, speeding up the process of transporting our goods to market in good condition, reducing marketing costs, and at the same time give the housewife a better product at a price she can pay - then we will be in a position to meet the competition from other areas and other products, and to hold our own in the fresh vegetable industry.

- - - - -

The Florida Vegetable Committee is a voluntary association of many, if not most, of the larger shippers and larger producers.

They contribute a lot of their time, thought and money, working for the benefits to the vegetable growers, large and small. Some smaller belong too.

They have a fully staffed office in Orlando and Mr. LaMonte Graw, the enterprising manager of same, may be found there when he is not in Washington, Texas, Mexico, California or Tallahassee, looking after the interests of the vegetable industry in Florida.

F. H. Scruggs

ESTIMATED PRICES PAID BY CANNERS
(Delivered to Canneries)
1943-44, 1944-45 , 1945-46 & 1946-47 Seasons

	ORANGES Per Box				GRAPEFRUIT Per Box			
	1943-44	1944-45	1945-46	1946-47	1943-44	1944-45	1945-46	1946-47
September	$ -	$ -	$2.49	$ -	$ -	$ -	$1.30	$1.18
October	2.03	1.98	2.49	1.33	1.37	1.83	1.30	1.19
November	2.03	1.98	2.41	1.00	1.37	1.83	1.53	1.18
December	2.03	1.93	2.52	.55	1.45	1.83	1.51	.77
January	1.86	2.18	2.37	.55	1.44	1.85	1.29	.60
February	1.63	2.49	2.31	.54	1.40	2.01	1.23	.52
March	1.87	2.74	2.62	.69	1.50	2.17	1.22	.53
April	2.27	3.11	3.00	1.17	1.74	2.19	1.29	.53
May	2.25	3.25	3.66	1.16	1.76	2.20	1.67	.44
June	2.20	3.06	3.68	1.08	1.66	1.92	1.76	.39
July	2.37	3.06	3.50	.79	1.67	-	1.77	.40
Average	2.02	2.60	2.83	.82	1.53	1.91	1.39	.65
Tangerines(For Season)			1.00	.80				

(1946-47 prices per month: Nov.$1.50; Dec.$1.00; Jan. $.60; Feb. $ .60; Mar. $.65; Apr. $.65.

TOTAL PRODUCTION, AND PORTION CANNED AND PROCESSED
DELIVERED PRICE PAID BY CANNERS
IN FLORIDA

	ORANGES Total Production Boxes	ORANGES Portion Canned Boxes	ORANGES Canner's Price Per Box	GRAPEFRUIT Total Production Boxes	GRAPEFRUIT Portion Canned Boxes	GRAPEFRUIT Canner's Price Per Box	Total Oranges Grapefruit Tangerines* Canned Boxes
1931-32	12,548,000	36,000	$0.65	10,431,000	930,000	$0.30	966,000
1932-33	14,964,000	50,000	.70	11,926,000	2,750,000	.32	2,800,000
1933-34	16,171,000	61,000	.80	11,113,000	2,605,000	.53	2,666,000
1934-35	15,590,000	178,000	.80	15,243,000	5,603,000	.37	5,781,000
1935-36	15,865,000	140,000	1.00	11,504,000	3,760,000	.73	3,900,000
1936-37	19,461,000	620,000	1.25	18,121,000	6,685,000	.55	7,305,000
1937-38	24,303,000	1,055,000	.36	14,379,000	5,793,000	.48	6,848,000
1938-39	30,015,000	1,867,000	.41	23,050,000	8,395,000	.22	10,262,000
1939-40	25,065,000	4,170,000	.19	15,650,000	8,800,000	.33	12,970,000
1940-41	28,752,000	3,941,000	.80	24,387,000	13,871,000	.37	17,812,000
1941-42	27,200,000	4,197,000	1.08	19,100,000	10,143,000	.71	14,340,000
1942-43	37,200,000	6,438,000	1.70	27,300,000	17,584,000	1.05	24,022,000
1943-44	46,200,000	10,912,501	2.02	31,000,000	20,429,310	1.53	31,341,811
1944-45	42,800,000	14,344,000	2.60	22,300,000	15,136,000	1.91	29,480,000
1945-46	49,800,000	19,183,860	2.83	32,000,000	22,124,976	1.39	41,824,436*
1946-47	54,700,000	19,825,485	.82	29,000,000	15,864,346	.65	36,620,582*

* Includes 515,600 boxes of tangerines.
**Includes 930,751,boxes of tangerines.

ESTIMATED CARLOADS CANNED BY MONTHS, 1945-46 AND 1946-47 SEASONS
(400 Boxes to Carload)

	ORANGES 1945-46	ORANGES 1946-47	GRAPEFRUIT 1945-46	GRAPEFRUIT 1946-47	TANGERINES 1945-46	TANGERINES 1946-47	TOTAL 1945-46	TOTAL 1946-47
Sept.	LCL	LCL	131	218		-	131	218
Oct.	1,230	1,311	1,236	1,983		-	2,466	3,294
Nov.	4,928	3,188	3,020	4,338		235	7,948	7,761
Dec.	4,996	3,457	5,000	4,149		845	9,996	8,451
Jan.	5,618	6,583	9,194	6,558	264	927	15,076	14,068
Feb.	5,182	8,076	7,438	4,602	406	287	13,026	12,965
Mar.	7,281	11,376	9,082	6,889	445	32	16,808	18,297
Apr.	7,660	5,623	9,395	6,304	166	1	17,221	11,928
May	7,819	6,046	7,539	3,238	8	-	15,366	9,284
June	3,117	3,418	2,899	1,206	-	-	6,016	4,624
July	129	452	377	150	-	-	506	602
Aug.	-	34	1	26	-	-	1	60
Carloads	47,960	49,564	55,312	39,661	1,289	2,327	104,561	91,552
Boxes	19,183,860	19,825,485	22,124,976	15,864,346	515,600	930,751	41824436	36620582

1946-47	Production(1)	Abandoned(2)
Oranges	54,000,000	1,200,000
Grapefruit	29,000,000	2,600,000
Tangerines	4,700,000	800,000
	87,700,000	4,600,000

(1) Excluding hurricane loss.
(2) For market reasons.

ESTIMATED COSTS FROM TREE TO AUCTIONS
1944-45, 1945-46 AND 1946-47 SEASONS.
(Private Sales not Included)

ORANGES	1944-45	1945-46	1946-47	Per Box 1944-45	Per Box 1945-46	Per Box 1946-47
Carloads Sold				9,022	8,265	14,770
Auction Sales at Terminal Markets				$ 4.48	$ 4.58	$ 3.50
Terminal Selling & Expenses				.09	.09	.07
Net at Terminal				4.39	4.49	3.43
Transportation Cost				.77	.77	.80
Florida F.O.B. Equivalent				$ 3.62	$ 3.72	$ 2.63
Florida Marketing Charges	.08	.08	.08	$ 1.21	$ 1.24	$ 1.30
Advertising & Inspection	.03	.03	.04			
Packing & Processing	.80	.81	.84			
Picking, Loading & Hauling	.30	.32	.34			
On Tree Equivalent				$ 2.41	$ 2.48	$ 1.33
Estimated Production Costs				.50	.48	.53
Net to Grower before Interest, Taxes & Depreciation				$ 1.91	$ 2.00	$ .80

GRAPEFRUIT	1944-45	1945-46	1946-47	Per Box 1944-45	Per Box 1945-46	Per Box 1946-47
Carloads Sold				3,132	4,384	7,094
Auction Sales at Terminal Markets				$ 4.24	$ 3.82	$ 3.29
Terminal Selling & Expenses				.08	.08	.07
Net at Terminal				4.16	3.74	3.22
Transportation Cost				.74	.74	.77
Florida F.O.B. Equivalent				$ 3.42	$ 3.00	$ 2.45
Florida Marketing Charges	.08	.08	.08	1.07	1.10	1.08
Advertising & Inspection	.05	.05	.05			
Packing & processing	.72	.73	.71			
Picking, Loading & Hauling	.22	.24	.24			
On Tree Equivalent				$ 2.35	$ 1.90	$ 1.37
Estimated Production Costs				.40	.34	.37
Net to Grower before Interest, Taxes & Depreciation				$ 1.95	$ 1.56	$ 1.00

TANGERINES	1944-45	1945-46	1946-47	Per Box 1944-45	Per Box 1945-46	Per Box 1946-47
Carloads Sold				1,465	2,201	2,403
Auction Sales at Terminal Markets				$ 4.82	$ 5.22	$ 4.34
Terminal Selling & Expenses				.10	.10	.09
Net at Terminal				4.72	5.12	4.25
Transportation Cost				.81	.81	.84
Florida F.O.B. Equivalent				$ 3.91	$ 4.31	$ 3.41
Florida Marketing Charges	.08	.08	.08	1.68	1.71	1.79
Advertising & Inspection	.07	.07	.07			
Packing & Processing	1.06	1.08	1.18			
Picking, Loading & Hauling	.47	.48	.46			
On Tree Equivalent				$ 2.23	$ 2.60	$ 1.62
Estimated Production Costs				.65	.64	.68
Net to Grower before Interest, Taxes & Depreciation				$ 1.58	$ 1.96	$ .94

Approximate Percentage all freight shipments sold at Auction -

	Oranges	Grapefruit	Tangerines
1940-41	32.6%	36.5%	47.3%
1941-42	32.7%	35.4%	45.5%
1942-43	27 %	36 %	48 %
1943-44	21.2%	24.8%	11.2%
1944-45	18.3%	26.2%	21.5%
1945-46	15.7%	26.8%	35.8%
1946-47	28.9%	43.4%	57.5%

Note: As has been stated above and in other pages of our report for many years, the citrus net prices do not allow any deductions for interest on investment, for taxes, or for depreciation of equipment. Pages 6-7 of this report which include private as well as auction sales of citrus should be used along with this page. Private sales of tangerines averaged considerably higher than auction sales in the 1945-46 and 1946-47 seasons. See pages 44-45 for Citrus Price Analysis.

See pages 40-42 for Auction Cars and Price Averages - yearly comparison.

The packing and marketing costs are itemized above for part of the crop, and total 1.30 for oranges, 1.08 for grapefruit, and 1.79 for tangerines. We preferred to use 1.25, 1.08, and 1.72, respectively, as you will see on page 6.

ACREAGE, YIELD, PRODUCTION AND VALUE
VEGETABLES AND MISCELLANEOUS FRUITS.
1946-47 SEASON

FLORIDA	Acreages Planted	Acreages For Harvest	Yield	Production Total	Abandoned	Production of Value	Season Avg FOB Price	Total Value Marketed
			Unit	Units	Units	Units	Unit	Dollars
SNAP BEANS			Bu.					
Fall(Fresh)	30,700	16,200	115	1,863,000	-	1,863,000	$ 2.80	$ 5,216,000
" (Process)	3,500	3,500	115	396,700	-	396,700	Ton	690,000
			1.7 T	5,950T.	-	5,950T	116.00	
" (Total)	34,200	19,700	115	2,259,700	-	2,259,700	2.61	5,906,000
Winter(Fresh)	43,200	27,200	80	2,176,000	376,000	1,800,000	3.05	5,490,000
" (Process)	1,300	1,300	80	104,000	-	104,000		
			1.2 T	1,560	-	1,560	112.00	175,000
" (Total)	44,500	28,500	80	2,280,000	376,000	1,904,000	2.98	5,665,000
Spring(Fresh)	33,000	28,500	60	1,710,000	185,000	1,525,000	2.85	4,346,000
" (Process)	5,000	5,000	60	300,000	-	300,000		
			.9 T	4,500T	-	4,500	105.00	472,000
" (Total)	38,000	33,500	60	2,010,000	185,000	1,825,000	2.64	4,818,000
TOTAL FRESH	106,900	71,900	80	5,749,000	561,000	5,188,000	2.90	15,052,000
TOTAL PROCESS	9,800	9,800	82	800,700	-	800,700	1.67	1,337,000
TOTAL ALL	116,700	81,700	80	6,549,700	561,000	5,988,700	2.74	16,389,000
LIMA BEANS			Bu					
Winter	2,100	1,600	65	104,000	-	104,000	$ 5.00	$ 520,000
Spring	4,700	3,600	65	234,000	-	234,000	2.85	667,000
Total	6,800	5,200	65	338,000	-	338,000	3.51	1,187,000
CABBAGE			Tons					
Winter	16,500	14,000	7.1	99,400	18,200	81,200	$ 37.80	$ 3,069,000
CARROTS			Bu.					
Winter	1,500	500	160	80,000	-	80,000	1.05	$ 84,000
CAULIFLOWER			Crts.					
Winter	700	600	200	120,000	-	120,000	1.75	$ 210,000
CELERY			Fla. Crts.					
Winter	7,600	7,300	375	2,738,000	-	2,738,000	3.55	$ 9,720,000
Spring	4,600	4,400	415	1,826,000	-	1,826,000	4.28	7,815,000
All	12,200	11,700	390	4,564,000	-	4,564,000	3.84	17,535,000
CUCUMBERS			Bu.					
Fall	6,100	5,000	75	375,000	-	375,000	4.10	$ 1,538,000
Winter	1,500	300	100	30,000	-	30,000	9.50	285,000
Spring(Fresh)	9,800	7,500	100	750,000	-	750,000	4.10	3,075,000
" Pickling	1,000	975	50	49,000	-	49,000	1.75	86,000
All	18,400	13,775	87	1,204,000	-	1,204,000	4.14	4,984,000
EGGPLANT			Bu.					
Fall	1,500	1,200	200	240,000	-	240,000	1.90	$ 456,000
Winter	1,150	1,000	210	210,000	-	210,000	2.15	452,000
Spring	1,150	1,100	250	275,000	-	275,000	2.75	756,000
All	3,800	3,300	220	725,000	-	725,000	2.42	1,664,000
ESCAROLE			Bu.					
Winter	3,600	2,800	325	910,000	-	910,000	1.30	$ 1,183,000
LETTUCE			Crts,4-6doz					
" BOSTON	1.000	700	100	70.000	-	70,000	2.95	$ 206,000
" ICEBERG								
Winter	1,700	1,000	100	100,000	-	100,000	3.10	$ 310,000
Spring	150	125	150	19,000	-	19,000	2.25	43,000
ALL LETTUCE	2,850	1,825	104	189,000	-	189,000	2.96	559,000
PEAS, ENGLISH			Bu.					
Winter	2,200	1,600	40	64,000	-	64,000	2.95	$ 189,000

(See pages 61-82 for acreage figures for other seasons, and particularly page 69 for citrus acreage by counties).

ACREAGE, YIELD, PRODUCTION AND VALUE(Cont'd)

VEGETABLES AND MISCELLANEOUS FRUITS.

1946-47 SEASON

FLORIDA	Acreages Planted	Acreages For Harvest	Yield	Production Total	Abandoned	Production of Value	Season Avg FOB Price	Total Value Marketed
			Unit	Units	Units	Units	Unit	Dollars
PEPPERS			Bu.					
Fall	2,000	7,750	235	411,000	-	411,000	$ 1.90	$ 781,000
Winter	4,000	3,600	300	1,080,000	-	1,080,000	4.05	4,374,000
Spring	8,500	5,200	135	702,000	-	702,000	5.60	3,931,000
All	14,500	10,550	208	2,193,000	-	2,193,000	4.14	9,086,000
POTATOES			Bu.					
Winter	12,000	9,900	110	1,089,000	-	1,089,000	2.15	$ 2,341,000
Spring	14,800	14,200	116	1,649,000	-	1,649,000	1.90	3,134,000
All	26,800	24,100	114	2,738,000	-	2,738,000	2.00	5,475,000
TOMATOES			Bu.					
Fall(Fresh)	8,200	8,200	113	927,000	-	927,000	5.30	$ 4,913,000
" (Process)	1,800	1,800	113	210,600	-	210,600		
			3.1 T	5,580 Tons	-	5,580	38.00	212,000
" (Total)	10,000	10,000	113	1,137,600	-	1,137,600	4.51	5,125,000
Winter(Fresh)	14,500	9,500	100	950,000	-	950,000	7.45	7,078,000
" (Process)			100	29,400	-	29,400		
	300	300	2.6 T	780 Tons	-	780	36.00	28,000
" (Total)	14,800	9,800	100	979,400	-	979,400	7.26	7,106,000
Spring(Fresh)	14,900	9,400	108	1,015,000	-	1,015,000	6.70	6,800,000
" (Process)			108	65,700	-	65,700		
	600	600	2.9 T	1,740 Tons	-	1,740	38.50	67,000
" (Total)	15,500	10,000	108	1,080,700	-	1,080,700	6.35	6,667,000
TOTAL FRESH	37,600	27,100	107	2,892,000	-	2,892,000	6.50	18,791,000
TOTAL PROCESS	2,700	2,700	113	305,700	-	305,700	1.00	307,000
TOTAL ALL	40,300	29,800	107	3,197,700	-	3,197,700	5.97	19,098,000
TOTAL VEGS.	266,850	201,450	(Packed Value per Acre harvested $400)					$80,712,000
CANTALOUPES			Jumbo crt.					
Spring	800	800	50	40,000	-	40,000	2.55	$ 102,000
			24-qt crt.					
STRAWBERRIES	4,750	4,750	65	309,000	-	309,000	12.10	$ 3,739,000
WATERMELONS			Melons					
Spring	51,000	47,000	290	13,623,000	1,500,000	12,123,000	447.00	$ 5,419,000
TOTAL MISCL.FRUITS	56,550	52,550	(Packed Value per Acre harvested $176)					$ 9,260,000
GRAND TOTAL	323,400	254,000	(Packed Value per Acre harvested $354)					$89,972,000

The above tabulation was prepared from data supplied by Mr. J. B. Owens and Mr. G. N. Rose, Agricultural Statisiticians, U.S. Bureau of Agricultural Economics, Federal Bldg., Orlando, Florida. They are the original and only source for acreage and production estimates in Florida.

These estimates were made as of September 20, 1947, and are subject to revision. Crop reporting is not an exact science. Later information will come showing that there was some isolated acreage not reported, some abandoned acreage not previously reported. These estimators do not have an all-seeing eye and look down from the heavens and locate exactly every acre that is planted, or at least know for sure what it is. They are just like the majority of the readers except that they have been in this business a long time in Florida, and have a lot of farmer and shipper contacts and a lot of "know how." They're pretty good.

Frank H. Scruggs.

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 20 YEARS

Records Estimates Season ALL	Total Carloads Rail&Boat Shipped	Portion Carloads Shipped By Rail	With No. Rail Haul, Shipped by Boat	Total Rail & Boat Shipments	Estimated Trucked out of Florida	Estimated Canned in Florida	Estimated Consumed (3) in Florida	Estimated Florida Production Utilized
ORANGES	Carloads	Cars	Carloads	Boxes	Boxes	Boxes	Boxes	Total Boxes
1927-28	16,437	16,310	127	5,917,320	520,000	12,000	650,000	7,099,320
1928-29	32,428	31,988	440	11,674,080	975,000	38,000	1,062,500	13,749,580
1929-30(4)	21,816	21,635	181	7,489,633	65,000	40,000	780,000	8,374,633
1930-31	40,353	39,354	999	14,000,130	1,584,000	61,351	1,308,582	16,954,063
1931-32	25,725	24,054	1,671	9,904,145	1,486,480	36,362	1,122,000	12,548,987
1932-33	32,580	26,414	6,166	11,728,800	1,854,000	50,000	1,332,000	14,964,800
1933-34	31,799	18,291	13,508	12,401,563	2,322,000	61,433	1,386,000	16,170,996
1934-35	28,213	14,843	13,370	11,094,459	2,891,643	177,937	1,425,000	15,589,039
1935-36	29,746	17,403	12,343	11,714,588	2,510,000	140,000	1,500,000	15,864,588
1936-37	37,208	23,382	13,826	14,580,603	2,560,000	620,185	1,700,000	19,460,788
1937-38	46,061	31,258	14,803	18,005,497	3,442,000	1,055,399	1,800,000	24,302,896
1938-39	55,697	37,380	18,317	21,528,758	5,175,741	1,186,689	2,000,000	30,015,287#
1939-40	38,285	29,286	8,999	14,718,568	4,376,000	4,170,134	1,800,000	25,064,702
1940-41	42,597	31,402	11,195	16,609,828	5,726,000	3,941,261	2,475,000	28,752,089
1941-42	41,598	40,443	1,155	16,853,616	4,099,200	4,197,299	2,049,885	27,200,000
1942-43	52,287	52,287	None	25,799,784	2,715,823	6,438,274	2,246,300	37,200,181
1943-44	61,160	61,160	None	30,511,378	2,155,200	11,010,841	2,522,581	46,200,000
1944-45	49,507	49,507	None	24,526,000	1,456,400	14,344,000	2,473,600	42,800,000
1945-46	52,665	52,589	76	26,007,841	2,054,000	19,219,412	2,518,747	49,800,000
1946-47	54,421	51,513	2,908	26,787,122 A	3,509,600	19,825,485	2,677,793	52,800,000 B

NOTES:

(A) Includes 153,451 boxes of oranges for export.

(B) Does not include 1,200,000 boxes abandoned for marketing reasons at a loss of $720,000.

(3) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(4) Fruit fly year when production harvest and shipments restricted.

(#) Includes 124,099 boxes diverted to other uses.

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 20 YEARS

Records and Estimates Season ALL ORANGES	Cost of Production(2) Before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail&Boat Shipments Per Box	Estimated Net Return(1) Rail & Boat Shipments Net Value	Estimated Net Return All Oranges Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Oranges Harvested and Used Gross Value
1927-28	$0.72	$1.30	$4.16	$2.14	$12,663,065	$13,905,825	$24,616,051	$26,804,051
1928-29	.72	1.28	2.12	.12	1,400,890	2,125,630	23,749,050	26,224,450
1929-30(4)	.80	1.30	3.30	1.20	8,987,560	9,648,310	24,715,789	26,157,789
1930-31	.48	1.10	2.15	.57	7,980,074	8,826,500	30,100,280	32,738,844
1931-32	.60	.95	2.30	.75	7,428,109	8,857,319	22,779,534	26,455,041
1932-33	.47	.90	1.48	.10	1,172,880	2,129,300	17,858,624	20,446,424
1933-34	.46	.87	1.71	.38	4,712,594	6,842,686	21,206,673	25,752,219
1934-35	.45	.90	1.85	.50	5,547,228	8,246,123	20,524,749	26,352,066
1935-36	.45	.95	2.30	.90	10,543,129	14,058,129	26,943,552	33,349,552
1936-37	.42	.93	2.50	1.15	16,767,693	20,689,419	36,451,507	44,979,738
1937-38	.38	.88	1.56	.30	5,401,649	6,053,959	28,088,575	34,339,559
1938-39	.34	.84	1.43	.25	5,382,190	6,035,321	30,786,124	39,687,098
1939-40	.42	.91	1.62	.29	4,268,365	4,214,941	23,843,970	33,663,815
1940-41	.40	.87	1.63	.36	5,979,538	9,126,658	27,074,020	42,442,109
1941-42	.44	.90	2.10	.76	12,808,748	18,918,916	35,392,593	51,904,503
1942-43	.40	1.01	2.97	1.56	40,247,695	53,904,492	76,625,358	101,089,208
1943-44	.50	1.25	3.10	1.35	41,190,360	60,686,332	94,585,272	129,867,001
1944-45	.50	1.21	3.50	1.79	43,901,540	74,132,856	85,841,000	135,653,600
1945-46	.48	1.24	3.55	1.83	47,414,930	91,767,533	91,979,783	161,818,586
1946-47	.53 (3)	1.25	2.62	1.78	22,372,056	26,385,989	72,728,282	101,927,124

NOTES:

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments.

(3) An allowance was made for unusual cost in grove protection in 1946-47 season. (February freeze)

(4) Fruit fly year when production, harvest and shipments restricted.

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 20 YEARS

Records Estimates Season GRAPE-FRUIT	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul, Shipped by Boat Carloads	Total Rail & Boat Shipments Boxes	Estimated Trucked out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(3) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	20,012	19,953	59	7,204,320	240,000	588,000	300,000	8,332,320
1928-29	28,294	28,091	203	10,185,840	450,000	1,489,320	675,000	12,800,160
1929-30(4)	16,415	16,354	61	6,341,913	30,000	1,670,000	360,000	8,401,913
1930-31	30,462	29,809	653	11,841,987	792,000	2,892,705	654,291	16,180,983
1931-32	20,315	17,865	2,450	7,821,313	897,940	930,171	782,000	10,431,424
1932-33	19,639	15,293	4,346	7,266,430	980,500	2,750,000	928,700	11,925,630
1933-34	17,514	11,340	6,174	6,981,916	684,000	2,605,964	841,320	11,113,200
1934-35	19,218	10,418	8,800	7,577,053	1,187,011	5,603,996	875,000	15,243,060
1935-36	15,196	8,838	6,358	5,936,067	1,028,000	3,760,000	780,000	11,504,067
1936-37	23,786	16,142	7,644	9,352,859	1,283,600	6,685,327	800,000	18,121,786
1937-38	16,952	11,511	5,441	6,602,063	1,233,600	5,793,097	750,000	14,378,760
1938-39	25,047	17,051	7,996	9,844,986	1,472,277	8,395,348	950,000	23,050,835#
1939-40	12,974	9,160	3,814	5,110,591	1,000,000	8,800,274	740,000	15,650,865
1940-41	19,962	14,478	5,484	7,956,475	1,559,600	13,870,966	1,000,000	24,387,041
1941-42	16,813	16,298	515	6,856,510	1,042,000	10,142,575	1,058,915	19,100,000
1942-43	16,529	16,529	None	8,009,134	612,807	17,584,025	1,094,150	27,300,116
1943-44	18,041	18,041	None	8,984,800	355,600	20,445,648	1,213,952	31,000,000
1944-45	11,742	11,742	None	5,860,000	205,200	15,136,000	1,098,800	22,300,000
1945-46	16,554	16,542	12	8,306,504	340,400	22,136,149	1,216,947	32,000,000
1946-47	17,800	16,363	1,437	8,878,857 A	558,000	15,864,346	1,098,797	26,400,000 (B)

NOTES:

(A) Includes 56,151 boxes of grapefruit for export.

(B) Does not include 2,600,000 boxes of grapefruit abandoned for marketing reasons at a loss of $1,092,000.

(3) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intra-state truck shipments, etc.

(4) Fruit fly year when production, harvest and shipments restricted.

(#) Includes 2,388,224 boxes diverted to other uses.

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 20 YEARS

Records and Estimates Season GRAPEFRUIT	Cost of Production(2) Before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail&Boat Shipments Per Box	Estimated Net Return(1) Rail&Boat Shipments Net Value	Estimated Net Return All Grapefruit Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Grapefrt. Harvested and Used Gross Value
1927-28	$0.52	$1.25	$3.28	$1.51	$10,878,523	$11,555,563	$23,630,170	$25,018,170
1928-29	.52	1.25	2.02	.25	2,546,460	3,078,488	20,575,397	22,557,557
1929-30(4)	.60	1.25	3.05	1.20	7,610,296	8,293,796	19,342,835	21,479,835
1930-31	.36	1.05	1.50	.09	1,065,779	1,199,727	17,762,980	20,366,366
1931-32	.40	.85	1.50	.25	1,955,328	2,012,557	11,731,970	13,522,967
1932-33	.38	.85	1.16	-.07	- 508,650	-1,285,321	8,429,059	10,170,789
1933-34	.39	.83	1.51	.29	2,024,756	2,591,790	10,542,693	13,296,632
1934-35	.37	.84	1.29	.08	606,164	199,847	9,774,397	13,409,984
1935-36	.39	.37	1.87	.61	3,621,001	5,269,881	11,100,445	15,936,845
1936-37	.30	.83	1.48	.35	3,273,500	4,448,605	13,842,231	19,731,121
1937-38	.36	.82	1.53	.35	2,310,722	2,613,485	10,101,156	15,063,803
1938-39	.30	.74	1.04	Zero	Zero	-2,099,526	10,238,785	14,688,400
1939-40	.40	.82	1.42	.20	1,022,120	- 146,121	7,257,052	12,289,942
1940-41	.35	.74	1.21	.12	954,777	- 514,241	9,627,335	17,335,152
1941-42	.40	.80	1.80	.60	4,113,906	6,439,418	12,341,718	22,849,773
1942-43	.35	.88	2.33	1.10	8,810,047	18,156,816	18,661,282	40,527,501
1943-44	.40	1.07	2.47	1.00	8,984,800	28,461,544	22,192,456	56,780,588
1944-45	.40	1.07	3.00	1.53	8,965,800	30,343,516	17,580,000	49,962,240
1945-46	.34	1.10	2.65	1.21	10,039,012	24,983,418	21,986,266	56,604,216
1946-47	.37 (B)	1.08	2.18	.73	6,440,575	6,883,612	19,640,839	32,971,887

NOTES:

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(3) An allowance was made for unusual cost in grove protection in 1946-47 season.

(4) Fruit fly year when production, harvest and shipments restricted.

(-) Minus sign indicates Net Loss.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 20 YEARS

Records Estimates Season TANGERINES	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul, Shipped by Boat Carloads	Total Rail and Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(3) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	1,427	1,417	10	513,720	40,000		50,000	603,720
1928-29	2,951	2,917	34	1,062,360	75,000		212,500	1,349,860
1929-30(4)	1,254	1,242	12	383,054	5,000		60,000	448,054
1930-31	3,830	3,786	44	1,387,828	264,000		218,097	1,869,925
1931-32	3,195	3,077	118	1,188,707	141,100		136,000	1,465,807
1932-33	3,282	2,749	533	1,181,520	175,680	No record made of the very few Tangerines processed prior to 1944-45 Season	162,000	1,519,200
1933-34	3,998	2,657	1,341	1,501,411	243,000		247,680	1,992,091
1934-35	3,676	2,199	1,477	1,461,049	267,706		275,000	2,003,755
1935-36	3,974	2,549	1,425	1,581,397	232,000		280,000	2,093,397
1936-37	5,885	4,046	1,839	2,288,234	430,000		300,000	3,018,634
1937-38	4,396	3,098	1,298	1,709,973	298,000		250,000	2,257,973
1938-39	6,323	4,502	1,821	2,553,332	478,541		350,000	3,381,873
1939-40	4,051	3,315	736	1,620,345	437,200		200,000	2,257,545
1940-41	4,513	3,449	1,064	1,791,824	434,800		525,000	2,751,624
1941-42	3,534	3,387	147	1,432,144	334,800		333,056	2,100,000
1943-43	7,382	7,382	None	3,407,401	400,048		392,700	4,200,149
1943-44	6,179	6,179	None	2,818,782	382,800		398,418	3,600,000
1944-45	6,847	6,487	None	3,149,000	327,600	3,000	420,400	3,900,000
1945-46	5,728	5,728	None	2,809,372	384,000	515,600	491,028	4,200.000
1946-47	4,543	4,323	222	2,058,146	438,400	930,751	472,703	3,900,000 A

NOTES:

(A) Does not include 800,000 boxes abandoned for marketing reasons at a loss of $608,000.

(3) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(4) Fruit fly year when production, harvest and shipments restricted.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 20 YEARS

Records and Estimates Season TANGERINES	Cost of Production(2) before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return(1) Rail & Boat Shipments Net Value	Estimated Net Return All Tangerines Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Tangerines Harvested and Used Gross Value
1927-28	$0.81	$1.70	$5.28	$2.77	$1,423,004	$1,519,104	$2,712,442	$2,892,442
1928-29	.81	1.70	2.90	.39	414,320	493,945	3,080,844	3,435,844
1929-30(4)	.90	1.70	3.50	..90	344,748	378,493	1,340,689	1,459,689
1930-31	.54	1.50	1.95	-.09	- 124,905	11,345	2,706,265	3,188,362
1931-32	.75	1.25	2.05	.05	59,435	73,290	2,436,849	2,713,949
1932-33	.56	1.16	1.42	-.30	- 354,456	- 281,513	1,677,758	1,999,238
1933-34	.56	1.05	1.80	.19	285,268	574,535	2,702,540	3,352,340
1934-35	.55	.95	1.66	.16	233,768	409,965	2,425,341	3,035,702
1935-36	.55	1.10	2.00	.35	553,489	883,889	3,162,794	3,902,794
1936-37	.50	1.15	1.45	-.20	- 457,646	- 558,726	3,317,939	4,127,899
1937-38	.52	1.16	1.86	.18	307,795	320,975	3,180,550	3,881,990
1938-39	.45	.95	1.34	-.06	- 153,200	- 242,481	3,421,465	4,291,433
1939-40	.50	1.06	2.00	.44	712,952	945,972	3,240,690	4,411,370
1940-41	.50	1.08	1.68	.10	179,182	219,216	3,010,264	4,415,434
1941-42	.58	1.16	2.85	1.11	1,589,680	2,280,955	4,081,610	5,818,344
1942-43	.40	1.35	2.79	1.03	3,509,623	4,223,464	9,472,575	11,436,280
1943-44	.65	1.58	3.70	1.37	3,861,731	4,884,190	10,429,493	13,041,107
1944-45	.65	1.68	4.25	1.92	6,046,080	7,437,192	13,383,250	16,296,690
1945-46	.64	1.71	4.80	2.45	6,882,962	8,800,902	13,484,986	17,807,898
1946-47	.68	1.72	3.75	1.35	2,778,497	3,522,030	8,310,248	11,666,569

NOTES:

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation pruning, fuel, labor, etc., but before deducting for taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(4) Fruit fly year when production, harvest and shipments restricted.

(-) Minus sign indicates Net Loss.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 20 YEARS

Records Estimates Season ALL CITRUS	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul, Shipped by Boat Carloads	Total Rail & Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(3) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	37,876	37,680	196	13,635,360	800,000	600,000	1,000,000	16,035,360
1928-29	63,673	62,996	677	22,922,280	1,500,000	1,527,320	1,950,000	27,899,600
1929-30(4)	39,485	39,231	254	14,214,600	100,000	1,710,000	1,200,000	17,224,600
1930-31	74,645	72,949	1,696	27,229,945	2,640,000	2,954,056	2,180,970	35,004,971
1931-32	49,235	44,996	4,239	18,914,165	2,525,520	966,533	2,040,000	24,446,218
1932-33	55,501	44,456	11,045	20,176,750	3,010,180	2,800,000	2,422,700	28,409,630
1933-34	53,311	32,288	21,023	20,884,890	3,249,000	2,667,397	2,475,000	29,276,287
1934-35	51,107	27,460	23,647	20,132,561	4,346,360	5,781,933	2,575,000	32,835,854
1935-36	48,916	28,790	20,126	19,232,052	3,770,000	3,900,000	2,560,000	29,462,052
1936-37	66,879	43,570	23,309	26,221,696	4,274,000	7,305,512	2,800,000	40,601,208
1937-38	67,409	45,867	21,542	26,317,533	4,973,600	6,848,496	2,800,000	40,939,629
1938-39	87,067	58,933	28,134	33,927,076	7,126,559	9,582,037	3,300,000	56,447,995#
1939-40	55,310	41,761	13,549	21,449,504	5,813,200	12,970,408	2,740,000	42,973,112
1940-41	67,072	49,329	17,743	26,358,127	7,720,400	17,812,227	4,000,000	55,890,754
1941-42	61,945	60,128	1,817	25,142,270	5,476,000	14,339,874	3,441,856	48,400,000
1942-43	76,198	76,198	None	37,216,319	3,728,678	24,022,299	3,733,150	68,700,446
1943-44	85,380	85,380	None	42,314,960	2,893,600	31,456,489	4,134,951	80,800,000
1944-45	68,096	68,096	None	33,535,000	1,989,200	29,483,000	3,992,800	69,000,000
1945-46	74,947	74,859	88	39,902,117	2,778,400	41,871,161	4,226,722	86,000,000
1946-47	76,766	72,199	4,567	37,724,125 A	4,506,000	36,620,582	4,249,293	83,100,000 B

NOTES:

(A) Includes Export Oranges and Grapefruit 209,602 boxes, and Domestic Boat Oranges and Grapefruit 1,826,800 boxes, Total 2,036,402 boxes.

(B) Does not include 4,600,000 boxes abandoned for marketing reasons.

(3) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(4) Fruit fly year when production, harvest and shipments restricted.

(#) Includes 2,512,323 boxes diverted to other uses.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 20 YEARS

Records and Estimates Season ALL CITRUS	Cost of Production(2) Before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return(1) Rail & Boat Shipments Net Value	Estimated Net Return All Citrus Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Citrus Harvested and Used Gross Value
1927-28	$0.63	$1.28	$3.74	$1.83	$24,964,592	$ 26,980,492	$50,958,663	$54,714,663
1928-29	.64	1.25	2.08	.19	4,361,670	5,698,063	47,405,291	52,217,851
1929-30(4)	.71	1.29	3.19	1.19	16,942,604	18,320,604	45,399,313	49,097,313
1930-31	.43	1.10	1.86	.33	8,920,948	10,037,572	50,569,525	56,293,572
1931-32	.53	.92	1.95	.50	9,442,872	10,943,166	36,948,353	42,691,957
1932-33	.45	.90	1.36	.01⅓	309,774	562,466	27,465,441	32,616,451
1933-34	.44	.87	1.65	.33½	7,022,618	10,009,011	34,451,906	42,401,191
1934-35	.43	.88	1.63	.32	6,387,160	8,855,935	32,724,487	42,797,752
1935-36	.44	.94	2.14	.76	14,717,619	20,211,899	41,206,791	53,189,191
1936-37	.37	.92	2.04	.75	19,583,547	24,579,298	53,611,677	68,838,758
1937-38	.38	.88	1.57	.30½	8,020,166	8,988,419	41,370,281	53,285,352
1938-39	.34	.82	1.31	.15	5,228,990	3,693,314	44,446,374	58,646,931
1939-40	.42	.90	1.60	.28	6,003,437	5,014,792	34,341,712	50,365,127
1940-41	.39	.85	1.51	.27	7,113,479	8,831,633	39,711,619	64,192,695
1941-42	.43	.89	2.06	.74	18,512,334	27,639,289	51,815,921	80,572,620
1942-43	.39	1.01	2.81	1.41	52,567,333	76,284,772	104,759,215	153,052,989
1943-44	.49	1.24	3.01	1.28	54,036,891	94,032,066	127,207,221	199,688,696
1944-45	.483	1.25	3.483	1.75	58,913,420	111,913,564	116,804,250	201,912,530
1945-46	.46	1.25	3.44	1.73	64,336,904	125,551,850	127,451,035	236,230,700
1946-47	.50	1.24	2.59	.85	31,591,356	36,791,631	100,679,009	146,565,580 A

NOTES:

(A) Does not include 4,600,000 boxes abandoned for marketing reasons at a loss of $2,420,000.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting for taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(4) Fruit fly year when production, harvest and shipments restricted.

FREIGHT CARLOT SHIPMENTS FROM FLORIDA BY COMMODITIES AND MONTHS, FOR 1946-47 SEASON

COMMODITY	Aug.	Sept	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	April	May	June	July	TOTAL
Oranges		1	3638	5102	4995	5758	4217	6100	5095	4505	3456	523	43,390
Grapefruit		1016	2189	1222	783	1435	931	1268	1404	1540	742	76	12,606
Tangerines			1	645	1007	1162	146	13					2,974
Mixed Citrus			609	1437	1855	1987	845	798	702	801	526	39	9,599
TOTAL CITRUS		1017	6437	8406	8640	10342	6139	8179	7201	6846	4724	638	68,569
Lemons		2	2										4
Strawberries					10	35	48	2	4				99
Watermelons										707	6763	493	7,963
Cantaloupes											5		5
TOTAL MISCL.FRUITS		2	2		10	35	48	2	4	707	6768	493	8,071
Beans(incl.Limas)			177	500	776	802	246	57	499	545	66		3,668
Cabbage			1	34	391	959	314	212	398	146	4		2,459
Celery				16	481	1549	1251	1585	1975	1708	182		8,747
Corn, Green			1							93	72		166
Cucumbers		2	148	170	46	1	1		93	642	35		1,138
Eggplant			1	8	5				1	15	38	12	81
Escarole				56	150	149	48	115	210	99			827
Lettuce & Romaine				14	26	30	10	20	16				116
Peas, English					1	10	2			1			14
Peppers			14	61	134	173	70	66	21	51	149	5	744
Potatoes					43	171	499	688	222	2323	47	8	4,001
Tomatoes			35	963	242	660	245	97	88	824	95		3,249
Other Vegetables				5	12	64	17	29	30	31	8	28	224
Mixed Car Veg's		1	53	403	850	1119	400	316	637	759	155	11	4,704
TOTAL VEGETABLES		3	430	2230	3157	5688	3103	3185	4190	7237	851	64	30,138
NON-CITRUS & VEGS		5	432	2230	3167	5723	5151	3187	4194	7944	7619	557	38,209
ALL FRUITS & VEGS		1022	6869	10636	11807	16065	9290	11366	11395	14790	12343	1195	106,778

PICK-UP-EXPRESS SHIPMENTS FROM FLORIDA STATIONS FOR 1946-47 SEASON

COMMODITY	Aug.	Sept	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	April	May	June	July	TOTAL
Mixed Citrus				103	1627	407	381	430	367	232	74	9	3,630
Mixed Vegetables	107	123	52	84	98	107	44	31	33	84	54	31	848
TOTAL FR. & VEGS.	107	123	52	187	1725	514	425	461	400	316	128	40	4,478

RAIL - FREIGHT & EXPRESS CARLOT SHIPMENTS, FOR 1946-47 SEASON

COMMODITY	Aug.	Sept	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	April	May	June	July	TOTAL
Oranges		1	3638	5102	4995	5758	4217	6100	5095	4505	3456	523	43,390
Grapefruit		1016	2189	1222	783	1435	931	1268	1404	1540	742	76	12,606
Tangerines			1	645	1007	1162	146	13					2,974
Mixed Citrus			609	1540	3482	2394	1226	1228	1069	1033	600	48	13,229
TOTAL CITRUS		1017	6437	8509	10267	10749	6520	8609	7568	7078	4798	647	72,199
Lemons		2	2										4
Strawberries					10	35	48	2	4				99
Watermelons										707	6763	493	7,963
Cantaloupes											5		5
TOTAL MISC.FRUITS		2	2		10	35	48	2	4	707	6768	493	8,071
Beans(Incl.Limas)			177	500	776	802	246	57	499	545	66		3,668
Cabbage			1	34	391	959	314	212	398	146	4		2,459
Celery				16	481	1549	1251	1585	1975	1708	182		8,747
Corn, Green			1							93	72		166
Cucumbers		2	148	170	46	1	1		93	642	35		1,138
Eggplant			1	8	5	1			1	15	38	12	81
Escarole				56	150	149	48	115	210	99			827
Lettuce & Romaine				14	26	30	10	20	16				116
Peas, English					1	10	2			1			14
Peppers			14	61	134	173	70	66	21	51	149	5	744
Potatoes					43	171	499	688	222	2323	47	8	4,001
Tomatoes			35	963	242	660	245	97	88	824	95		3,249
Other Vegetables				5	12	64	17	29	30	31	8	28	224
Mixed Car Veg's	107	124	105	487	948	1226	444	347	670	843	209	42	5,552
TOTAL VEGETABLES	107	126	482	2314	3255	5795	3147	3216	4223	7321	905	95	30,986
NON-CITRUS & VEGS	107	128	484	2314	3265	5830	3195	3218	4227	8028	7673	588	39,057
ALL FRUITS & VEGS	107	1145	6921	10823	13532	16579	9715	11827	11795	15106	12471	1235	111,256

NOTES: Other Vegetables include straight freight cars as enumerated: Carrots, Bunched 57, Cauliflower 35, Greens(ex.Spinach) 56, Spinach 17, Sweet Potatoes 59. Total 224.

BOAT SHIPMENTS (Carlot Equivalent FROM FLORIDA PORTS (Does not include initial rail haul exports)

COMMODITY	Jan.	Feb.	Mar.	April	May	TOTAL
Oranges	248	490	730	772	668	2,908
Grapefruit	59	98	429	476	375	1,437
Tangerines	102	96	21	3		222
TOTAL CITRUS	409	684	1180	1251	1043	4,567
Celery	11	18	30	22	19	100
Cucumbers					3	3

COMMODITY	Jan.	Feb.	Mar.	April	May	June	TOTAL
Corn, Green						3	3
Potatoes					164		164
Sweet Potatoes			1	1			2
TOTAL VEGETABLES	11	18	31	23	186	3	272
GRAND TOTAL	420	702	1211	1274	1229	3	4,839

FLORIDA INTERSTATE TRUCK SHIPMENT PASSINGS 1946-47 SEASON

Actual Check at Eight Road Guard Stations October 1-June 15
Estimated for August and September and June 15-July 31.

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	April	May	June	July	TOTAL
Oranges	lcl	8	833	733	1575	1164	1107	1397	922	640	340	55	8,774
Grapefruit	1	159	142	103	106	159	147	157	160	146	91	24	1,395
Tangerines			lcl	164	378	393	138	23	lcl	lcl			1,096
TOTAL CITRUS	1	167	975	1000	2059	1716	1392	1577	1082	786	431	79	11,265
Avocados	12	13	13	25	6	lcl	lcl				lcl	5	72
Limes	10	4	1	1	2	1	lcl	1	lcl	4	10	10	44
Strawberries				lcl	98	165	148	52	119	33	lcl		615
Watermelons										156	2722	400	3,278
Other **Fruits**										2	63		65
TOTAL MISC. FRUITS	22	17	14	24	106	166	148	53	119	195	2795	415	4,074
Beans, Snap			96	523	495	617	277	167	608	428	8		3,219
Limas				5	29	33	21	5	27	59	50		229
Butterbeans	1	1	1	lcl					lcl	38	48	5	94
Cabbage			1	16	177	622	697	781	564	144	1		3,003
Celery				1	107	175	190	206	226	108	7		1,020
Corn, Green	1		3	9	2	1	lcl		2	147	312	2	479
Cucumbers		3	85	119	78	33	11	3	179	373	12		896
Eggplant	1	1	27	57	65	130	76	80	81	142	91	5	756
Escarole				3	3	19	28	42	46	4			145
Field Peas	10	5	13	12	1				lcl	337	255	25	658
Lettuce & Romaine				2	9	33	21	13	11	1			90
Okra	3	2	8	6	2	1	1	lcl	1	29	52	6	111
Peas, English				2	5	6	3	4	6	lcl			26
Peppers	1		5	41	134	277	217	224	176	330	171	10	1,586
Potatoes				1	33	55	84	111	108	302	7		701
Squash	1	1	14	38	45	76	29	36	225	175	5		645
Tomatoes			10	388	330	457	219	123	87	644	263	5	2,526
Bunched Vegetables			lcl	4	9	10	3	9	7	8	lcl		50
Other Vegetables	2	2	lcl	10	30	102	67	150	64	2	3	2	434
TOTAL VEGETABLES	20	15	263	1237	1554	2647	1944	1954	2418	3271	1285	60	16,668
VEGS. & MISC. FRUITS	42	32	277	1261	1660	2813	2092	2007	2537	3466	4080	475	20,742
GRAND TOTAL	43	199	1252	2261	3719	4529	3484	3584	3619	4252	4511	554	32,007

See bottom of page 27 for conversion factors.

CARLOT SHIPMENTS (FREIGHT, EXPRESS, BOAT & TRUCK) FRUITS AND VEGETABLES BY MONTHS FOR SEASON 1946-47

August 1-July 31 (Truck October 1-June 15 except where estimated)

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	April	May	June	July	TOTAL
Oranges	lcl	9	4471	5835	6570	7170	5814	8227	6789	5813	3796	578	55,072
Grapefruit	1	1175	2331	1325	889	1653	1176	1854	2040	2061	833	100	15,438
Tangerines			1	809	1385	1657	380	57	3	lcl			4,292
Mixed Citrus			609	1540	3482	2394	1226	1228	1069	1033	600	48	13,229
TOTAL CITRUS	1	1184	7412	9509	12326	12874	8596	11366	9901	8907	5229	726	68,031
Avocados	12	13	13	23	6	lcl	lcl				lcl	5	72
Lemons		2	2										4
Strawberries				lcl	103	200	196	54	123	33	lcl		714
Watermelons										863	9485	893	11,241
Other Non-Citrus	10	4	1	1	2	1	lcl	1	lcl	6	78	10	114
TOTAL MISC. FRUITS	22	19	18	24	116	201	196	55	123	902	9563	908	12,145
Beans(incl. Limas)			273	1028	1300	1452	544	229	1134	1032	124		7,116
Cabbage			2	50	568	1581	1011	993	962	290	5		5,462
Celery				17	588	1735	1459	1821	2223	1835	189		9,867
Corn, Green	1		4	9	2	1	lcl		2	240	387	2	648
Cucumbers		5	233	289	124	34	12	3	272	1018	47		2,037
Eggplant	1	1	28	65	70	131	76	80	82	157	129	17	837
Escarole				59	153	168	76	157	256	103			972
Lettuce & Romaine				16	35	63	31	33	27	1			206
Peas, English				2	6	16	5	4	6	1			40
Peppers	1		19	102	268	450	287	290	197	331	320	15	2,330
Potatoes				1	76	226	583	799	330	2789	54	8	4,866
Tomatoes			45	1351	572	1117	464	220	175	1468	358	5	5,775
Other Vegetables	17	11	36	75	99	253	117	225	328	620	371	66	2,218
Mixed Car Vegetables	107	124	105	487	948	1226	444	347	670	843	209	42	5,552
TOTAL VEGETABLES	127	141	745	3551	4809	8453	5109	5201	6664	10778	2193	155	47,926
VEGS. & MISC. FRUITS	149	160	761	3575	4925	8654	5305	5256	6787	11680	11756	1063	60,071
ALL FRUITS & VEGS.	150	1344	8173	13084	17251	21528	13901	16622	16688	20587	16985	1789	148,102

NOTES FOR TRUCK SHIPMENTS (See previous page): The above vegetable and non-citrus passings were checked at Florida State Road Guard Stations October 1,1946 to June 15, 1947. August and September passings were estimated, based on general information available. June 16-30 passings, included in June totals, were likewise estimated as follows: Snap Beans 1, Lima Beans 15, Butterbeans 15, Green Corn 60, Eggplant 35, Field Peas 100, Okra 20, Peppers 40, Tomatoes 60, Limes 5, Cantaloupes 10, and Watermelons 1400 carloads. July passings estimates based on general information available.

Citrus Passings for August and September, June 16-30, and July, were estimated as 96% of the citrus inspected for interstate shipment. June 16-30 estimate: Oranges 134, Grapefruit 40.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS

(These figures have been revised and rearranged and may not agree or seem to agree with some previous tabulations. The totals are substantially the same.)

Commodity	Freight Shipments 1937-38	1938-39	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47
Oranges	26,131	31,065	24,812	27,084	34,374	43,390	51,405	41,049	41,848	43,390
Grapefruit	8,518	13,290	6,832	12,135	12,650	12,258	13,441	8,534	12,201	12,606
Tangerines	1,980	2,817	1,896	2,171	1,865	5,017	3,856	4,370	3,813	2,974
Mixed Citrus	7,887	11,073	7,249	6,770	10,062	13,162	13,626	11,102	13,573	9,599
Total Citrus	44,516	58,246	40,789	48,160	58,951	73,827	82,328	65,055	71,435	68,569
Strawberries	888	686	43	4	-	6	22	43	25	99
Watermelons	6,679	3,406	4,977	5,028	5,565	3,363	6,116	8,366	7,470	7,963
Miscl. Fruits	-	-	-	2	-	-	16	15	3	9
Total Non-Citrus	7,567	4,092	5,020	5,034	5,565	3,369	6,154	8,424	7,498	8,071
Beans & Limas	5,482	4,431	2,910	2,700	3,335	5,943	6,596	4,682	4,538	3,668
Cabbage	3,287	1,610	4,238	2,256	3,568	4,534	6,378	5,157	4,763	2,459
Celery	8,270	7,696	7,769	8,689	9,119	8,557	9,349	11,037	12,489	8,747
Corn, Green	53	32	22	2	7	17	18	42	104	166
Cucumbers	1,351	809	1,153	981	1,181	461	405	988	1,549	1,138
Eggplant	26	23	-	36	29	175	246	304	251	81
Escarole	818	816	882	573	818	1,003	1,120	1,347	1,317	827
Lettuce	355	233	371	235	147	197	207	152	166	116
Peas, English	663	186	270	80	130	115	153	83	62	14
Peppers	937	719	516	647	863	1,352	1,805	1,622	1,612	744
Potatoes	5,411	3,767	5,116	3,306	5,540	4,756	5,282	7,068	9,591	4,001
Tomatoes	11,460	8,660	5,222	3,679	5,035	4,367	4,592	5,305	5,269	3,249
Squash (estimated)	350	300	275	275	300	400	400	500	400	400*
Other Variety Vegs.	50	29	25	36	86	133	364	426	484	224
Mixed Car Vegs.	3,316	2,681	1,427	1,354	2,113	3,973	5,855	6,884	7,217	4,704
Total Vegetables	41,829	31,992	30,196	24,849	32,271	35,983	42,770	45,597	49,812	30,538
Total Vegs. & Non-Cit.	49,396	36,084	35,216	29,883	37,836	39,352	48,924	54,021	57,310	38,609
ALL FRUITS & VEGS.	93,912	94,329	76,005	78,043	96,787	113,179	131,252	119,076	128,745	107,178

NOTES: Mixed Citrus includes oranges, grapefruit, tangerines; usually around 57% oranges, 29% grapefruit, and 14% tangerines. Miscl. Fruits include lemons and cantaloupes. Mixed Cars of Vegetables include beans, cabbage, eggplant, peppers, squash, and practically all other Florida vegetables. Other Variety Vegetables include straight cars as follows: Turnips, carrots 57, cauliflower 55, greens 56, spinach 17, sweet potatoes 59. The mixed car analysis varies from year to year.

No provision is made by Federal Government for a report on straight cars of radishes and squash which are shipped each year.

* Squash carlots estimated at 400 carloads.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

Commodity	1937-38	1938-39	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47
					Express Shipments					
EXPRESS										
Mixed Citrus	1,351	688	972	1,169	1,177	2,371	3,100	3,041	5,376	3,630
Strawberries	36	235	180	47	58	55	1	-	-	-
Miscl. Fruits	100*	100*	75*	75*	125*	175*	175*	90*	90*	100*
Total Non-Citrus	136	335	255	122	183	230	176	90	90	100
Beans & Limas	243	44	76	45	-	-	-	-	-	-
Tomatoes	7	-	-	-	-	-	-	-	-	-
Mixed Car Vegs.	836	550	388	396	605	1,074	1,283	1,148	1,179	848
Total Vegetables	1,086	594	464	441	605	1,074	1,283	1,148	1,179	848
Total Vegs.& Non-Cit.	1,222	929	719	563	788	1,304	1,459	1,148	1,179	948
ALL FRUITS & VEGS.	2,573	1,617	1,691	1,732	1,965	3,675	4,559	4,279	4,645	4,578
BOAT					Boat Shipments					
Oranges	14,797	18,311	8,997	11,189	1,153				76	2,908
Grapefruit	5,438	7,992	3,812	5,481	514				12	1,437
Tangerines	1,297	1,819	735	1,063	147				-	222
Mixed Citrus	10	12	5	10	3				-	-
Total Citrus	21,542	28,134	13,549	17,743	1,817				88	4,567
Strawberries	-	-	-	-	-				-	-
Watermelons	25	17	16	-	-				-	-
Miscl. Fruits	10	10	10	5	-				-	-
Total Non-Citrus	35	27	26	5	-	No record of any			-	-
Beans & Limas	319	662	211	154	1				-	-
Cabbage	55	20	21	14	-	boat shipments			-	-
Celery	230	335	117	146	-				-	100
Corn, Green	1	-	-	-	-	during (War Period)			-	3
Cucumbers	92	86	32	40	-				-	3
Eggplant	250	279	11	35	-	1942-43 thru			-	-
Escarole	-	2	1	-	-				-	-
Lettuce	5	-	-	-	-	1944-45 seasons.			-	-
Peas, English	3	1	-	1	-				-	-
Peppers	1,545	1,107	241	163	6				-	-
Potatoes	2,009	1,674	1,176	898	-				-	164
Tomatoes	214	114	34	13	-				-	-
Squash	90	80	80	40	1				-	-
Other Variety Vegs.	215	175	171	103	3				-	2
Total Vegetables	5,028	4,535	2,095	1,609	11				-	272
Total Vegs. & Non-Cit.	5,063	4,562	2,121	1,614	11				-	272
ALL FRUITS & VEGS.	26,605	32,696	15,670	19,357	1,828				88	4,839

* Most of this volume is estimated amount of LCL express avocados, limes, mangoes, etc. Includes a few cars of limes and cantaloupes.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

	Trucked Out Shipments									
Commodity	1937-38	1938-39	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47
Oranges	8,605	12,939	11,148	14,315	10,248	6,790	5,388	3,641	5,135	8,774
Grapefruit	3,084	3,681	2,546	3,899	2,605	1,532	889	513	851	1,395
Tangerines	745	1,196	1,105	1,087	837	1,000	957	819	960	1,096
Total Citrus	12,434	17,816	14,799	19,301	13,690	9,322	7,234	4,973	6,946	11,265
Strawberries	600	1,190	1,228	1,073	860	300	164	263	446	615
Watermelons	1,000	990	838	976	695	190	630	654	2,538	3,278
Miscl. Fruits	250	328	496	321	250	110	192	452	182	181
Total Non-Citrus	1,850	2,508	2,562	2,370	1,805	600	986	1,369	3,166	4,074
Beans & Limas	3,000	6,075	5,020	5,485	6,526	2,400	2,504	2,257	3,129	3,448
Cabbage	2,000	2,487	4,959	2,298	3,539	1,900	2,116	1,449	2,083	3,003
Celery	350	684	1,260	1,681	1,582	360	401	405	566	1,020
Corn, Green	300	409	399	219	200	150	190	121	392	479
Cucumbers	600	800	1,269	1,196	866	265	250	444	741	896
Eggplant	250	620	301	586	734	300	525	380	682	756
Escarole	10	15	257	203	116	15	7	25	20	145
Lettuce	100	104	204	232	150	26	54	51	93	90
Peas, English	150	295	268	221	222	20	77	53	52	26
Peppers	600	1,155	936	1,445	1,656	900	865	809	1,524	1,586
Potatoes	600	642	1,289	1,068	1,116	500	426	872	759	701
Tomatoes	2,000	5,243	3,635	3,988	3,994	1,700	3,190	2,826	3,549	2,526
Squash	400	478	761	560	538	300	440	447	653	645
Other Variety Vegs.	800	306	793	859	805	450	661	680	1,249	1,347*
Total Vegetables	11,160	19,313	21,351	20,041	22,044	9,286	11,706	10,819	15,492	16,668
Total Vegs. & Non-Cit.	13,010	21,821	23,913	22,411	23,849	9,886	12,692	12,188	18,658	20,742
ALL FRUITS & VEGS.	25,444	39,637	38,712	41,712	37,539	19,208	19,926	17,161	25,604	32,007

* Other Vegetables include carloads as follows: Butterbeans 94, field peas 658, okra 111, bunched vegetables 50, and Miscellaneous vegetables 434.

NOTE: Shipments in packages, pounds, dozens, or units were converted in 1946-47 season as follows: Beans 600, limas 500, cabbage 25,000 lbs., celery 370, cucumbers 450, eggplant 470, escarole 450, lettuce 550, English peas 580, peppers 480, potatoes 550, strawberries 450, tomatoes 500, okra 500, squash 500, bunched vegetables 2,000 dozen, green corn 2,000 dozen, field peas 500, other vegetables 500, avocados 700, limes 800, watermelons 1,000, other fruits 500, all citrus 400. See Page 26 for Truck Shipments in more detail for 1946-47 season.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

Commodity	Total Freight, Express, Boat and Truck Shipments from Florida									
	1937-38	1938-39	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47
Oranges	49,533	62,315	44,957	52,588	45,775	50,180	56,793	44,690	47,059	55,072
Grapefruit	17,040	24,963	13,190	21,515	15,769	13,790	14,330	9,047	13,064	15,438
Tangerines	4,022	5,832	3,736	4,321	2,849	6,017	4,813	5,189	4,773	4,292
Mixed Citrus	9,248	11,773	8,226	7,949	11,242	15,533	16,726	14,143	16,949	13,229
Total Citrus	79,843	104,883	70,109	86,373	75,635	85,520	92,662	73,069	81,845	88,031
Strawberries	1,524	2,111	1,451	1,124	918	361	187	306	471	714
Watermelons	7,704	4,413	5,831	6,004	6,260	3,553	6,746	9,020	10,008	11,241
Miscl. Fruits	360	438	581	403	375	285	383	467	185	280
Total Non-Citrus	9,588	6,962	7,863	7,531	7,555	4,199	7,316	9,793	10,664	12,235
Beans & Limas	9,044	11,212	8,217	8,384	9,862	8,343	9,100	6,939	7,667	7,116
Cabbage	5,342	4,117	9,218	4,568	7,107	6,434	8,494	6,606	6,846	5,462
Celery	8,850	8,715	9,146	10,518	10,701	8,917	9,750	11,442	13,055	9,867
Corn, Green	354	441	421	221	207	167	208	163	496	648
Cucumbers	2,043	1,695	2,454	2,217	2,047	726	655	1,432	2,290	2,037
Eggplant	526	922	312	657	763	475	771	684	933	837
Escarole	828	833	1,140	776	934	1,018	1,127	1,372	1,337	972
Lettuce	460	337	575	467	297	223	261	203	259	206
Peas, English	816	482	538	302	352	135	230	136	114	40
Peppers	3,082	2,981	1,693	2,255	2,525	2,252	2,670	2,431	3,136	2,330
Potatoes	8,020	6,083	7,581	5,272	6,656	5,256	5,708	7,940	10,350	4,866
Tomatoes	13,681	14,017	8,891	7,680	9,029	6,067	7,782	8,131	8,818	5,775
Squash	840	858	1,116	875	839	700	840	947	1,053	1,045
Other Variety Vegs.	1,065	510	989	998	894	583	1,025	881	1,733	1,573
Mixed Car Vegs.	4,152	3,231	1,815	1,750	2,718	5,047	7,138	8,257	8,396	5,552
Total Vegetables	59,103	56,434	54,106	46,940	54,931	46,343	55,759	57,564	66,483	48,326
Total Vegs.& Non-Cit.	68,691	63,396	61,969	54,471	62,484	50,542	63,075	67,357	77,147	60,571
ALL FRUITS & VEGS.	148,534	168,279	132,078	140,844	138,119	136,062	155,737	140,426	158,992	148,602

NOTE: No boat shipments reported during 1942-43, 1943-44, and 1944-45 seasons due to War restrictions, but there might have been small amounts to the West Indies and some perhaps on Naval vessels or Army transports, if any in Florida waters. A few boat citrus shipments went out during the 1945-46 season. See Page 29 for further information regarding boat shipments.

RAIL FREIGHT SHIPMENTS BY COUNTIES
1946-47 SEASON
(August 1-July 31)

CARLOTS Florida Counties	Oranges	Grapefruit	Tangerines	Mixed Citrus	Total Citrus	Beans & Limas	Cabbage	Carrots	Cauliflower
Alachua	166	8	2	3	179	144	35		
Bradford									
Brevard	786	494	12	352	1644				
Broward	77				77	993	1		
Citrus	13		1	12	26				
Clay							12		
Collier									
Columbia									
Dade	2				2	147	47		
De Soto	814	16	58	245	1133		4		
Dixie									
Duval	482	39	62	69	652				
Escambia									
Flagler							2		
Gilchrist									
Glades							89		
Hamilton									
Hardee	28			3	31				
Hendry							69	3	
Hernando	238	26	134	94	492				
Highlands	1675	600	83	177	2535	2			
Hillsborough	1975	207	57	320	2559	2	41		29
Holmes									
Indian River	266	1300	11	446	2023				
Jackson									
Jefferson									
Lafayette									
Lake	4864	453	234	1180	6731		6		
Lee	172	23	4	43	242		1		
Levy									
Madison									
Manatee	95	170		76	341	3	72		1
Marion	1990	121	34	210	2355	33	14		
Martin		1			1	1			
Okeechobee	1				1				
Orange	9453	969	868	1379	12669	11	269	50	
Osceola	222	42	12	64	340				
Palm Beach		5		22	27	2298	763	4	
Pasco	379	103	39	65	584				
Pinellas	846	1247	51	324	2468				
Polk	15327	5197	905	3081	24510		50		
Putnam	167	4	40	89	300		45		
St.Johns	1				1		459		
St.Lucie	577	1318	40	558	2493	1			
Sarasota	157	16		4	177		7		4
Seminole	1962	213	128	544	2847	21	315		1
Sumter						6	8		
Suwannee									
Union						6			
Volusia	584	34	199	241	1058		150		
Washington									
Undistributed	71				71				
Straight Cars	43390	12606	2974	9599	68569	3668	2459	57	35
Boat	2908	1437	222		4567				
Pick-Up-Exp.				3630	3630				
GRAND TOTAL	46298	14043	3196	13229	76766	3668	2459	57	35

As of September 1, Subject to Revision.

RAIL FREIGHT SHIPMENTS BY COUNTIES
1946-47 SEASON
(August 1-July 31)

CARLOTS Florida Counties	Celery	Green Corn	Cukes	Eggplant	Escarole	Greens	Lettuce & Romaine	Peas English
Alachua	135		95	5				
Bradford		2						
Brevard								
Broward			77	2		9		
Citrus								
Clay								
Collier			109					
Columbia		24						
Dade		4				10		
De Soto			1					
Dixie								
Duval								
Escambia								
Flagler								
Gilchrist								
Glades								
Hamilton								
Hardee			155	1				
Hendry			13				21	
Hernando								
Highlands								
Hillsborough			102	28	1		4	1
Holmes								
Indian River								
Jackson			56					
Jefferson								
Lafayette								
Lake	480							
Lee			148	5				
Levy								
Madison								
Manatee		4	141	14	108		13	
Marion	94		7				9	
Martin								
Okeechobee								
Orange	328	41	66		66	4	1	
Osceola								
Palm Beach	2555	59		23	484	18	37	13
Pasco								
Pinellas								
Polk								
Putnam								
St. Johns								
St. Lucie			22	2		15		
Sarasota	1673		38		3			
Seminole	3482	32		1	165		31	
Sumter			81					
Suwannee			17					
Union			10					
Volusia								
Washington								
Undistributed								
Straight Cars	8747	166	1138	81	827	56	116	14
Boat	100	3	3					
Pick-Up-Exp.								
GRAND TOTAL	8847	169	1141	81	827	56	116	14

RAIL FREIGHT SHIPMENTS BY COUNTIES
1946-47 SEASON
(August 1-July 31)

CARLOTS Florida Counties	Peppers	Potatoes	Spinach	Sweet Potatoes	Tomatoes	Mixed Vegetables	Total Vegetables
Alachua	101	218	17	13		108	871
Bradford							2
Brevard							
Broward	331				236	1759	3408
Citrus							
Clay		10					22
Collier					29		138
Columbia							24
Dade		1302			886	13	2409
De Soto							5
Dixie							
Duval		4					4
Escambia		34		2			36
Flagler		213					215
Gilchrist							
Glades							89
Hamilton							
Hardee	11				19	38	224
Hendry					16	10	132
Hernando							
Highlands						23	25
Hillsborough	50				229	197	684
Holmes							
Indian River					93	5	98
Jackson							56
Jefferson							
Lafayette							
Lake						1	487
Lee	49	155		37	6	146	547
Levy							
Madison							
Manatee	19	1			246	98	720
Marion	4	12				211	384
Martin				7		1	9
Okeechobee					269		269
Orange	63	17				142	1058
Osceola							
Palm Beach	55	138			61	1459	7957
Pasco							
Pinellas							
Polk							50
Putnam		297					342
St. Johns		1599				6	2064
St. Lucie					1159	10	1209
Sarasota						16	1741
Seminole	36					425	4509
Sumter	25					35	155
Suwannee							17
Union		1				1	18
Volusia							150
Washington							
Undistributed							
Straight Cars	744	4001	17	59	3249	4704	30138
Boat		164		2			272
Pick-Up-Exp.						848	848
GRAND TOTAL	744	4165	17	61	3249	5552	31258

RAIL FREIGHT SHIPMENTS BY COUNTIES
1946-47 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Canta-loupes	Lemons	Straw-berries	Water-melons	Total Non-Citrus	Total Veg's & Non-Citrus	GRAND TOTAL
Alachua	1			821	822	1693	1872
Bradford						2	2
Brevard							1644
Broward						3408	3485
Citrus				6	6	6	32
Clay						22	22
Collier						138	138
Columbia				41	41	65	65
Dade						2409	2411
De Soto		1		12	13	18	1151
Dixie				1	1	1	1
Duval						4	656
Escambia						36	36
Flagler						215	215
Gilchrist				1038	1038	1038	1038
Glades						89	89
Hamilton				41	41	41	41
Hardee						224	255
Hendry						132	132
Hernando							492
Highlands						25	2560
Hillsborough			99	144	243	927	3486
Holmes				3	3	3	3
Indian River						98	2121
Jackson				118	118	174	174
Jefferson				220	220	220	220
Lafayette				50	50	50	50
Lake				2012	2012	2499	9230
Lee	1				1	548	790
Levy				391	391	391	391
Madison				299	299	299	299
Manatee						720	1061
Marion	3			925	928	1312	3667
Martin						9	10
Okeechobee						269	270
Orange				95	95	1153	13822
Osceola							340
Palm Beach						7367	7994
Pasco				224	224	224	808
Pinellas				11	11	11	2479
Polk		3		63	66	116	24626
Putnam				18	18	360	660
St. Johns						2064	2065
St. Lucie						1209	3702
Sarasota						1741	1918
Seminole						4509	7356
Sumter				711	711	866	866
Suwannee				674	674	691	691
Union						18	18
Volusia				2	2	152	1210
Washington				18	18	18	18
Undistributed				25	25	25	96
Straight Cars	5	4	99	7963	8071	38209	106778
Boat						272	4839
Pick-Up-Exp.						848	4478
GRAND TOTAL	5	4	99	7963	8071	39329	116095

As of September 1, Subject to Revision.

FEDERAL-STATE INSPECTION SERVICE

June 30, 1946 - June 28, 1947.

FLORIDA * Commodities	Type Container	Number of Cars Inspected	Number of Units (or containers)	Average Containers (or Units per car) 1946-47	1945-46	1944-45
CITRUS						
Grapefruit	Std. box equiv.	12,067	6,218,833	515	514	514
Oranges	Std. box equiv.	41,652	20,953,352	503	502	505
Tangerines	Std. box equiv.	3,010	1,331,059	442	449	452
Mixed Citrus	Std. box equiv.	10,145	5,119,890	505	497	494
Total Citrus		66,874	33,623,134			
VEGETABLES						
Beans	Bushel hampers	25	16,046	641	638	620
Cabbage	50 lb.Bags	589	296,394	503	501	508
Cabbage	Bulk for processing, lbs.	-	25,576 lbs.	-	-	-
Cabbage	1-1/2 bu. Hamper	56	23,760	424	-	-
Carrots	50 lb. Bags	14	8,663	619	595	-
Carrots	Bu. Hampers	-	-	-	-	719
Cauliflower	Crates	-	-	-	-	453
Celery	Howard Crates	7,589	3,225,966	425	445	443
Chicory	Bushel	1	640	640	640	-
Chinese Cabbage	Crates	1	416	416	-	-
Corn	Crates	3	1,325	442	-	-
Corn	50 lb.Sacks	-	-	-	696	620
Cucumbers	Bushel	79	36,269	459	437	570
Escarole	Bushel	23	14,081	612	642	610
Onions	50 lb. Sacks	-	-	-	550	712
Peppers	Bushel	15	10,083	672	652	782
Peppers	1½ Bu Crates	-	-	-	-	471
Potatoes (Com'l)	100 lb Bags	1,601	491,277	307	300	300
Potatoes "	50 lb Bags	1,415	920,470	651	619	638
Potatoes "	Bushels	10	5,134	513	-	642
Potatoes (PMA)	Bulk (pounds)	40	1,619,260 lbs	40,482	-	-
Potatoes "	100 lb. Bags	102	36,180	355	300	-
Squash	Bushel Hamper	-	-	-	-	500
Sweet Potatoes	Bushels	19	10,020	527	552	539
Tomatoes	Lugs	1,427	988,407	693	689	691
Mixed Vegetables	Various	73	43,961	602	-	578
Total Vegetables		13,082				
Limes	Std. Box equiv.	-		-	364	397
Watermelons	Melons	5,622	5,272,924	938	1,008	1,058
Peanuts *(Probably Fla)	Bulk, lbs.	356	17,121,204	48,093	-	50,225
GRAND TOTAL		85,934				

INSPECTIONS OF FLORIDA CITRUS FOR SHIPMENT
BY RAIL AND TRUCK BY COUNTIES
SEASON AUGUST, 1946 - JULY, 1947

County	BOXES (1-3/5 bushels) Grapefruit	Oranges	Tangerines	Total 1946-47	Total 1945-46
Alachua	4,831	86,550	3,244	94,625	63,279
Brevard	369,431	644,440	18,081	1,031,952	1,185,658
Broward	31,774	147,861	1,710	181,345	106,906
Citrus	3,803	27,774	1,342	32,919	33,190
Dade	31,987	62,293	344	94,624	101,343
De Soto	61,548	658,659	68,571	788,778	465,707
Duval	61,497	602,273	85,476	749,246	750,047
Hardee	533	15,091	929	16,553	38,536
Hernando	28,099	202,282	91,966	322,347	197,847
Highlands	348,263	918,567	47,679	1,314,509	1,130,970
Hillsborough	216,618	1,434,309	93,005	1,743,932	1,027,996
Indian River	962,390	342,873	20,556	1,325,819	1,359,746
Lake	429,002	3,269,738	256,687	3,955,427	4,018,197
Lee	19,629	113,216	6,595	139,440	61,748
Manatee	118,269	80,576	619	199,464	126,298
Marion	117,102	1,425,627	45,600	1,588,329	1,032,943
Orange	765,014	6,236,791	620,357	7,622,162	8,103,860
Osceola	46,520	259,638	22,154	328,312	202,066
Palm Beach	58,409	80,700	7,171	146,280	131,611
Pasco	73,133	269,139	26,948	369,220	319,332
Pinellas	745,640	540,896	40,801	1,327,337	1,192,068
Polk	3,468,754	9,334,885	633,449	13,437,088	13,139,162
Putnam	17,011	192,208	51,131	260,350	246,419
St. Johns	125	27,778	7	27,910	31,870
St. Lucie	1,109,746	777,096	56,525	1,943,367	1,727,290
Sarasota	9,666	83,861	-	93,527	66,026
Seminole	226,428	1,546,308	144,885	1,917,621	1,843,306
Volusia	60,914	632,758	171,451	865,123	922,142
TOTAL	9,336,136	30,014,187	2,517,283	41,917,606	39,625,563
Utilized in 1946-47	26,400,000	52,800,000	3,900,000	83,100,000	86,000,000

Note: Some commodities are produced in one county and inspected in another county. These inspections do not include fruit for processing and some other classes of fruit.

- - - - - - - - - - -

PERSIAN CERTIFIED LIME SHIPMENTS - By Counties, By Months-Season 1946-47
(In Terms of Equivalent Standard Boxes, 1-3/5 Bushels)

	Brevard	Dade	DeSoto	Highlands	Hillsborough	Pinellas	Polk	Totals
July 1946	38	18,611	-	8,675	5,393	-	7,141	39,858
Aug. "	49	15,341	-	3,713	1,772	-	5,217	26,092
Sept. "	2	7,909	-	1,085	-	-	2,711	11,707
Oct. "	3	6,787	37	2,352	-	156	1,276	10,611
Nov. "	-	4,066	-	2,222	-	63	1,073	7,424
Dec. "	-	4,051	-	-	-	-	-	4,051
Jan. 1947	-	3,522	-	547	-	-	17	4,086
Feb. "	-	1,600	-	67	-	-	235	1,902
Mar. "	1	1,553	-	824	-	86	-	2,464
Apr. "	-	3,701	-	22	-	-	44	3,767
May "	-	7,994	-	280	-	-	266	8,540
June "	-	16,975	-	2,182	1,600	559	2,354	23,670
Totals	93	92,110	37	21,969	8,765	864	20,334	144,172
Percentage	.1	63.9	-	15.2	6.1	.6	14.1	100.0

Note: The above data supplied by E. E. Raasch, Statistician, Florida Citrus Inspection Bureau, Winter Haven, Florida

TRUCK SHIPMENTS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS BY WEEKS FOR 1946-47 SEASON

(Rail Carload Equivalent)
Oct. 1, 1946-June 15, 1947*

Date by Weeks	Beans	Limas	Cabbage	Celery	Cukes	Eggplant	Escarole	Lettuce	Eng. Peas	Peppers	Potatoes	Tomatoes	Gr. Corn
Aug. & Sept.*					3	2				1			1
Oct. 1-5					4	1							
6-12	LCL				15	2				1			
13-19	6				17	5				LCL			
20-26	40		1		28	13				2		1	1
Oct. 27-Nov.2	115		1		50	14				7		27	3
3-9	61		1		24	11	LCL			5		49	3
10-16	97	LCL	2		19	10	LCL	1	1	8		108	1
17-23	177	3	4		24	17	1	LCL	1	10	LCL	118	1
24-30	122	2	8	1	24	11	2	1	LCL	13	LCL	95	2
Dec. 1-7	119	6	15	8	27	13	LCL	1	2	25	5	108	1
8-14	114	10	21	41	22	13		2	1	27	7	87	LCL
15-21	119	7	45	33	19	23	1	3	1	48	7	72	LCL
22-28	87	4	57	9	5	10	2	2	1	17	2	32	LCL
Dec. 29-Jan.4	141	7	115	42	7	19	1	3	2	40	20	102	LCL
5-11	133	6	136	36	11	27	3	8	2	59	14	126	LCL
12-18	148	10	134	31	8	32	3	10	2	68	8	100	LCL
19-25	117	5	155	43	7	33	7	6	1	72	14	94	LCL
Jan. 26-Feb.1	164	9	146	48	5	31	8	10	1	72	15	80	1
2-8	118	10	151	37	6	24	9	7	2	63	30	69	LCL
9-15	49	3	153	45	3	18	5	5	LCL	59	16	65	LCL
16-22	45	3	220	58	1	16	9	3	LCL	47	24	43	
Feb. 23-Mar.1	43	3	161	54	LCL	16	6	4	LCL	45	17	33	
2-8	40	2	220	50	LCL	20	6	2	1	51	25	40	LCL
9-15	45	LCL	166	44	LCL	15	16	4	1	50	26	37	
16-22	37	1	178	50	1	23	7	3	1	52	26	22	
23-29	36	1	171	46	2	15	10	4	2	53	24	15	LCL
Mar. 30-Apr.5	69	3	182	40	4	13	19	4	2	47	18	14	LCL
6-12	121	2	116	48	12	8	12	4	2	33	26	9	LCL
13-19	148	7	114	61	31	15	13	2	1	35	14	15	1
20-26	157	11	111	62	66	29	2	1	LCL	42	31	32	LCL
Apr. 27-May 3	190	7	101	35	101	36	2	LCL	LCL	40	45	78	2
4-10	156	9	59	34	135	30	1	LCL	LCL	48	89	119	2
11-17	116	15	40	29	115	34	1	LCL	LCL	84	99	154	12
18-24	63	16	15	18	67	30	1	1		91	69	136	43
25-31	19	17	5	13	23	32		LCL		92	24	179	89
June 1-7	5	20	1	6	10	29				80	6	127	149
8-14	2	14	LCL	1	1	25				48	1	72	96
15	LCL	1	LCL	LCL	LCL	2				3	LCL	4	8
16-30*	1	15				35				40		60	60
July*						5				10		5	2
Total	3220	229	3005	1023	894	755	147	91	27	1587	702	2527	477

*Estimated from special information; (1) LCL means less than rail carload; (2) The above shipments represent passings through Florida Road Guard Stations Oct. 1 to June 15, 1947; (3) Above truck passings converted into pre-War rail carload equivalent on basis of: Beans 600 bu; Limas 500 bu; Cabbage 25,000 lbs; Celery 370 crates; Cukes 450 bu; Eggplant 470 pkgs; Escarole 450 pkgs; Lettuce 550 pkgs; English Peas 580 bu; Peppers 480 pkgs; Potatoes 550 pkgs; Tomatoes 500 pkgs; Green Corn 2000 doz.

The Weekly Totals differ from, and are slightly higher than the Monthly Totals due to fractional totals by weeks.

TRUCK SHIPMENTS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS BY WEEKS FOR 1946-47 SEASON

(Rail Carload Equivalent)

Oct. 1, 1946-June 15, 1947*[5]

Date by Weeks	Okra	Squash	Bun. Vegs.	Oth. Vegs.	# F. Peas B. Beans	Tot. Vegs.	Avocados	Strawberries	Limes	W-Mel.	Oth. Fru.	Tot. Fru.	Grand Total
Aug. & Sept.*	5	2		4	17	35	25		14			39	74
Oct. 1-5	1	LCL	LCL		LCL	6	1		LCL			1	7
6-12	1	2	LCL		1	22	2		LCL			2	24
13-19	2	3	LCL		2	35	5		1			6	41
20-26	3	4	LCL	LCL	7	100	4		1			5	105
Oct. 27-Nov.2	4	11	1	1	6	240	8		1			9	249
3-9	2	3	LCL	LCL	3	162	3		LCL			3	165
10-16	1	5	LCL	LCL	4	257	9		LCL			9	266
17-23	1	10	1	5	1	374	4	LCL	LCL			4	378
24-30	1	14	2	5	1	304	1	LCL	LCL			1	305
Dec. 1-7	LCL	11	4	5	1	351	3	4	1			8	359
8-14	LCL	9	3	7	LCL	364	2	16	LCL			18	382
15-21	LCL	11	1	8		398	1	31	LCL			32	430
22-28	LCL	8	1	5		242	LCL	26	LCL			26	268
Dec. 29-Jan.4	1	17	2	14		533	LCL	41	LCL			41	574
5-11	1	20	3	22		607	LCL	39	LCL			39	646
12-18	LCL	19	3	26		602	LCL	32	LCL			32	634
19-25	LCL	15	2	28		599	LCL	24	LCL			24	623
Jan. 26-Feb.1	LCL	14	1	23		628	LCL	64	LCL			64	692
2-8	1	17	1	18		563	LCL	50	LCL			50	613
9-15	LCL	5	LCL	14		440		32				32	472
16-22	LCL	3	1	13		486		31				31	517
Feb.23-Mar.1	LCL	3	1	21		407		26	LCL			26	433
2-8		7	1	32		497		10				10	507
9-15	LCL	7	1	31		443		13				13	456
16-22	LCL	9	3	42		455		7				7	462
23-29	LCL	10	3	33	LCL	425		13	LCL			13	438
Mar. 30-Apr.5	LCL	26	3	35		479		25	LCL			25	504
6-12	LCL	38	1	17		449		25	LCL			25	474
13-19	1	54	2	11	LCL	525	LCL	21	LCL			21	546
20-26	LCL	67	1	6	LCL	618		28	LCL			28	646
Apr. 27-May 3	1	68	1	3	1	711	LCL	38	LCL			38	749
4-10	2	58	1	1	9	753		15	LCL			15	768
11-17	4	48	1	3	45	800		1	1			2	802
18-24	8	27	LCL	1	148	734		LCL	1	10		11	745
25-31	16	15	LCL	3	173	700		2	2	146	2	152	852
June 1-7	18	5	LCL	1	146	603	LCL	LCL	3	410	18	431	1034
8-14	12	1	LCL	1	40	314		LCL	2	765	35	802	1116
15	2	LCL	LCL	LCL	2	22			LCL	147		147	169
16-30*	20				115	346			5	1400	10	1415	1761
July*	6			2	30	60		5	10	400		415	475
Total	114	646	45	441	752	16689	68	619	42	3278	65	4072	20761

(4) Converted into pre-War rail carload equivalent on basis of: Okra 500 pkgs; Squash 500 pkgs; Bunched Vegetables 2000 doz; Other Vegetables 500 pkgs; Field Peas-Butter Beans 500 pkgs; Avocados 700 pkgs; Strawberries 450 pkgs; Limes 800 pkgs; Watermelons 1000 melons; Other Fruits 500 pkgs. (5) Pre-War carload conversion factors retained for more accurate passings with other years. #Field Peas 658; Butterbeans 94 carloads.

The Shipments are the passings by Road Guard Stations (open October 1st to June 15th) and destined for out-of-State points, excepting several carloads to West Florida. Several carloads of West Florida vegetables going out of State were not included. An estimate was made for Watermelons originating West of the Suwannee River and going out of State.

FLORIDA AUCTION SALES, 1929-30 - 1946-47

Furnished through courtesy of the Statistical Department
Florida Citrus Exchange, Tampa, Fla.

ORANGES

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1929-30	Cars	4848	1409	982	739	395	621	211	483	- -	- -	9688
	Average	$4.94	3.98	4.43	3.79	4.70	5.08	4.15	4.38	-	-	4.62
1930-31	Cars	8444	3164	1679	952	707	1112	358	729	308	-	17453
	Average	$3.53	3.30	3.37	3.14	3.27	3.34	3.05	3.14	3.21	-	3.40
1931-32	Cars	6517	2228	1182	511	497	776	174	447	179	-	12511
	Average	$3.40	3.21	3.24	3.06	3.20	3.25	2.90	3.14	3.26	-	3.30
1932-33	Cars	9238	2868	1419	579	553	921	273	614	256	-	16721
	Average	$2.43	2.45	2.53	2.35	2.40	2.55	2.30	2.30	2.46	-	2.44
1933-34	Cars	7613	2632	1436	515	526	894	266	495	267	142	14786
	Average	$2.75	2.62	2.69	2.54	2.63	2.67	2.46	2.47	2.69	2.88	2.70
1934-35	Cars	8243	2720	1419	511	578	1070	258	553	280	258	15890
	Average	$2.61	2.47	2.58	2.44	2.53	2.59	2.34	2.35	2.47	2.44	2.56
1935-36	Cars	7503	2624	1561	340	559	878	249	555	271	240	14780
	Average	$3.02	2.93	3.02	2.95	3.04	3.15	2.72	2.87	3.08	2.82	3.00
1936-37	Cars	9112	3164	1657	429	824	1080	264	708	412	282	17932
	Average	$3.23	3.15	3.28	3.12	3.21	3.33	3.01	3.12	3.27	2.98	3.21
1937-38	Cars	10228	3376	1849	495	298	1394	413	1181	550	302	20686
	Average	$2.26	2.20	2.24	2.18	2.28	2.39	2.05	2.16	2.26	1.98	2.24
1938-39	Cars	12440	4049	2132	694	1091	1639	511	1555	717	396	25224
	Average	$2.10	1.99	2.16	2.11	2.20	2.26	2.01	2.01	2.16	1.94	2.09
1939-40	Cars	8758	2908	1290	364	589	1012	318	1031	393	173	16836
	Average	$2.43	2.25	2.47	2.16	2.31	2.41	2.09	2.05	2.25	2.23	2.35
1940-41	Cars	10089	3320	1385	426	647	1020	312	1077	434	261	18971
	Average	$2.37	2.26	2.45	2.31	2.44	2.45	2.25	2.18	2.42	2.22	2.35
1941-42	Cars	9053	3064	1377	337	568	863	204	1002	353	312	17133
	Average	$2.86	2.76	2.90	2.73	2.91	2.88	2.70	2.64	2.88	2.77	2.83
1942-43	Cars	6771	2330	851	439	483	939	359	742	412	277	13603
	Average	$3.85	3.70	3.82	3.72	3.85	3.77	3.70	3.55	3.87	3.56	3.79
1943-44	Cars	6239	2257	678	522	488	815	476	516	658	200	12849
	Average	$3.98	3.82	4.02	3.86	3.86	3.89	3.67	3.65	3.85	3.71	3.90
1944-45	Cars	4765	1651	425	293	264	532	271	299	365	157	9022
	Average	$4.62	4.38	4.47	4.27	4.34	4.29	4.17	4.02	4.37	4.39	4.48
1945-46	Cars	4510	1478	363	237	197	345	196	372	262	308	8268
	Average	$4.72	4.44	4.70	4.48	4.43	4.39	4.24	4.17	4.43	4.45	4.58
1946-47	Cars	7824	1930	870	420	639	921	430	801	562	373	14770
	Average	$3.60	3.35	3.62	3.29	3.47	3.38	3.27	3.25	3.47	3.35	3.50

FLORIDA AUCTION SALES, 1929-30 - 1946-47 (Cont'd.)

GRAPEFRUIT

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1929-30	Cars	3253	1153	756	640	458	1029	235	303	-	-	7827
	Average	$4.45	4.00	4.00	3.70	4.15	4.81	4.03	3.93	-	-	4.28
1930-31	Cars	5269	1610	1037	762	718	1388	462	425	516	-	12187
	Average	$2.66	2.42	2.44	2.41	2.44	2.55	2.38	2.33	2.51	-	2.54
1931-32	Cars	4680	1254	935	505	510	805	207	354	328	-	9578
	Average	$2.49	2.34	2.50	2.38	2.49	2.59	2.41	2.31	2.54	-	2.47
1932-33	Cars	5138	1266	892	429	433	738	228	409	330	-	9863
	Average	$2.05	1.95	2.06	2.02	2.21	2.29	1.96	2.01	2.31	-	2.06
1933-34	Cars	3948	1129	696	310	388	684	221	370	298	41	8085
	Average	$2.41	2.25	2.40	2.38	2.39	2.55	2.37	2.29	2.51	2.42	2.39
1934-35	Cars	4893	1326	898	389	403	721	200	444	350	135	9759
	Average	$2.04	1.81	1.93	1.94	2.09	2.19	2.05	1.92	2.10	1.86	2.00
1935-36	Cars	3928	1072	872	262	396	395	132	340	251	117	7765
	Average	$2.67	2.38	2.49	2.40	2.54	2.68	2.40	2.32	2.62	2.28	2.57
1936-37	Cars	5376	1650	956	274	415	494	151	423	307	151	10197
	Average	$2.24	2.06	2.22	2.14	2.29	2.58	2.53	2.24	2.41	2.12	2.23
1937-38	Cars	4881	1244	814	190	313	353	72	342	219	127	8555
	Average	$2.20	2.06	2.13	2.05	2.11	2.28	2.16	2.09	2.21	1.88	2.16
1938-39	Cars	6389	1429	1020	329	384	361	118	432	277	187	10926
	Average	$1.75	1.57	1.73	1.68	1.77	1.95	1.85	1.66	1.80	1.46	1.72
1939-40	Cars	4765	1153	633	181	141	182	62	241	140	85	7483
	Average	$2.21	1.92	2.10	1.92	2.11	2.29	2.10	1.98	2.06	1.73	2.13
1940-41	Cars	5035	1334	805	249	256	313	109	416	215	91	8823
	Average	$1.96	1.75	1.95	1.76	1.92	2.00	1.77	1.74	1.91	1.61	1.91
1941-42	Cars	4519	1166	712	125	136	208	51	222	98	88	7325
	Average	$2.55	2.36	2.55	2.33	2.61	2.83	2.73	2.33	2.64	2.60	2.52
1942-43	Cars	3411	967	487	142	96	114	19	201	85	82	5604
	Average	$3.18	2.97	3.21	2.90	2.90	3.17	2.96	2.67	3.00	2.70	3.10
1943-44	Cars	2628	778	338	128	49	69	44	90	97	43	4264
	Average	$3.63	3.48	3.64	3.36	3.32	3.20	3.51	3.05	3.31	3.14	3.56
1944-45	Cars	2320	498	183	31	23	21	13	16	13	14	3132
	Average	$4.35	4.03	4.11	3.74	3.01	3.31	3.38	3.13	3.15	3.54	4.24
1945-46	Cars	3293	737	213	33	12	19	2	18	14	45	4386
	Average	$3.88	3.67	3.88	3.06	2.60	3.62	3.33	2.91	2.81	3.19	3.82
1946-47	Cars	4894	890	546	63	80	154	31	183	111	142	7094
	Average	$3.39	3.11	3.17	2.89	3.10	3.16	3.55	2.87	3.18	2.54	3.29

FLORIDA AUCTION SALES, 1929-30 - 1946-47 (Cont'd.)

TANGERINES

($\frac{1}{2}$ box basis)

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1929-30	Cars	612	238	95	119	56	62	12	30	-	-	1224
	Average	$2.44	2.19	1.94	2.02	2.74	2.83	2.78	2.58	-	-	2.35
1930-31	Cars	1311	426	207	229	154	237	62	97	126	-	2849
	Average	$1.62	1.49	1.46	1.48	1.45	1.44	1.36	1.45	1.48	-	1.53
1931-32	Cars	1190	396	203	175	116	161	65	88	60	-	2454
	Average	$1.54	1.44	1.49	1.39	1.41	1.52	1.32	1.41	1.53	-	1.49
1932-33	Cars	1308	375	157	95	108	180	58	102	73	-	2456
	Average	$1.28	1.20	1.28	1.23	1.21	1.22	1.14	1.09	1.22	-	1.24
1933-34	Cars	1134	433	144	142	114	179	67	96	71	1	2381
	Average	$1.21	1.15	1.17	1.25	1.24	1.21	1.21	1.15	1.22	1.48	1.20
1934-35	Cars	1071	356	132	136	71	155	66	108	71	31	2197
	Average	$1.18	1.10	1.12	1.25	1.27	1.25	1.26	1.20	1.28	1.22	1.18
1935-36	Cars	1124	365	157	139	116	217	54	113	87	26	2398
	Average	$1.35	1.32	1.30	1.40	1.42	1.36	1.32	1.34	1.41	1.23	1.35
1936-37	Cars	1557	572	196	210	193	306	103	138	116	33	3424
	Average	$1.12	1.03	1.05	1.19	1.09	1.14	1.10	1.08	1.16	.96	1.10
1937-38	Cars	1311	382	149	95	117	149	74	125	88	23	2513
	Average	$1.26	1.21	1.20	1.28	1.30	1.25	1.10	1.18	1.23	1.08	1.24
1938-39	Cars	1851	551	172	152	189	257	107	203	148	33	3663
	Average	$1.07	.92	.93	.95	.98	.97	.86	.91	.96	.79	1.00
1939-40	Cars	1192	345	66	65	104	142	48	115	57	9	2143
	Average	$1.37	1.34	1.41	1.37	1.47	1.45	1.31	1.27	1.34	1.33	1.37
1940-41	Cars	1425	454	109	77	154	195	59	149	82	13	2717
	Average	$1.23	1.16	1.19	1.07	1.20	1.22	1.09	1.12	1.14	1.06	1.19
1941-42	Cars	1152	359	78	39	106	135	38	105	48	25	2085
	Average	$1.86	1.75	1.75	1.65	1.82	1.66	1.52	1.58	1.76	1.50	1.79
1942-43	Cars	1485	670	143	108	188	303	101	193	151	57	3399
	Average	$1.82	1.84	1.62	1.81	1.86	1.81	1.66	1.80	1.74	1.53	1.80
1943-44	Cars	326	134	22	22	22	40	26	21	31	-	644
	Average	$2.16	2.28	2.27	2.32	2.37	2.27	2.36	2.26	2.40	-	2.23
1944-45	Cars	669	300	32	72	66	150	41	53	73	9	1465
	Average	$2.42	2.38	2.35	2.49	2.45	2.42	2.15	2.40	2.47	2.77	2.41
1945-46	Cars	1188	414	57	70	86	167	46	88	59	26	2201
	Average	$2.67	2.52	2.43	2.58	2.68	2.54	2.32	2.59	2.50	2.61	2.61
1946-47	Cars	1233	335	69	91	139	202	63	128	108	35	2403
	Average	$2.28	2.18	2.11	2.12	1.99	1.90	1.92	1.99	2.04	2.08	2.17

RAIL AND BOAT SHIPMENTS
F.O.B. PRICES
AVERAGES AT TAMPA OFFICE ON PACKED FRUIT

Florida Citrus Exchange Report
Seasons 1909-10 to 1929-30

SEASONS	ORANGES	GRAPEFRUIT	TANGERINES*	ALL CITRUS (Average)
1909-10	$1.15	$2.38	$1.81	$1.34
1910-11	1.51	1.95	2.60	1.65
1911-12	1.93	3.58	1.93	2.21
1912-13	1.97	2.01	1.92	1.96
1313-14	1.69	2.09	2.51	1.83
1914-15	1.47	1.32	1.66	1.42
1915-16	1.99	1.89	2.07	1.96
1916-17	1.94	2.07	2.82	2.01
1917-18	3.92	2.72	4.39	3.46
1918-19	3.69	3.18	4.79	3.52
1919-20	4.20	2.84	5.49	3.37
1920-21	2.57	2.46	4.96	2.65
1921-22	3.77	2.41	5.57	3.17
1922-23	2.96	2.10	4.39	2.62
1923-24	1.86	1.51	4.31	1.82
1924-25	3.51	1.94	4.43	2.74
1925-26	3.58	2.92	4.83	3.36
1926-27	2.78	2.25	3.50	2.58
1927-28	4.39	3.22	5.28	3.90
1928-29	1.99	2.07	2.91	2.09
1929-30	3.22	2.98	3.38	3.13

FLORIDA STATE MARKETING BUREAU AVERAGES

Seasons 1930-31 to 1946-47
(Comparable to above prices)
Gross f.o.b. Florida per box

1930-31	$2.15	$1.50	$1.95	$1.86
1931-32	2.30	1.50	2.05	1.95
1932-33	1.48	1.16	1.42	1.36
1933-34	1.71	1.51	1.80	1.65
1934-35	1.85	1.29	1.66	1.63
1935-36	2.30	1.87	2.00	2.14
1936-37	2.50	1.48	1.45	2.04
1937-38	1.56	1.53	1.86	1.57
1938-39	1.43	1.04	1.34	1.31
1939-40	1.62	1.42	2.00	1.60
1940-41	1.63	1.21	1.68	1.51
1941-42	2.10	1.80	2.85	2.06
1942-43	2.97	2.33	2.78	2.81
1943-44	3.10	2.47	3.70	3.01
1944-45	3.50	3.00	4.25	3.48
1945-46	3.55	2.65	4.80	3.44
1946-47	2.62	2.18	3.75	2.59

See pages 44-45 for the Citrus Price Analysis covering period 1931-32 to 1946-47, inclusive. This analysis shows weighted average prices for truck shipments, Florida local consumption, and for fruit used in canning or other processing.

CITRUS PRICE ANALYSIS 1931-32 TO 1946-47

		FLORIDA GROSS FOR MARKET OR EQUIVALENT PER BOX					NET*TO GROWER		RAIL AND BOAT	
	BOX YIELD	RAIL & BOAT	TRUCKED OUT	FLORIDA CONSUMED	FLORIDA CANNED	GROSS ALL	NET ALL	NET RAIL & BOAT	COST PRODUCTION	COST PICKING HAULING MARKETING RAIL&BOAT
ORANGES										
1931-32	12,548,987	$2.30	$1.40	$1.40	$ .65	$2.10	$ .71	$ .75	$ .60	$ .95
1932-33	14,964,800	1.48	1.00	.90	.70	1.36	.14	.10	.48	.90
1933-34	16,170,996	1.71	1.25	1.15	.80	1.59	.42	.38	.46	.87
1934-35	15,589,039	1.85	1.35	1.25	.80	1.69	.53	.50	.45	.90
1935-36	15,864,588	2.30	1.60	1.50	1.00	2.10	.88	.90	.45	.95
1936-37	19,460,788	2.50	1.90	1.70	1.25	2.31	1.06	1.15	.42	.93
1937-38	24,302,896	1.56	1.12	1.12	.38	1.41	.25	.30	.38	.88
1938-39	30,015,287	1.43	1.15	1.15	.41	1.32	.20	.25	.34	.84
1939-40	25,064,702	1.62	1.52	1.32	.19	1.37	.17	.29	.42	.91
1940-41	28,752,089	1.63	1.58	1.28	.80	1.48	.32	.36	.40	.87
1941-42	27,200,000	2.10	2.05	1.70	1.08	1.91	.69	.76	.44	.90
1942-43	37,200,181	2.97	2.91	2.50	1.70	2.72	1.45	1.56	.40	1.01
1943-44	46,200,000	3.10	3.10	2.60	2.02	2.81	1.31	1.35	.50	1.25
1944-45	42,800,000	3.50	3.50	3.00	2.60	3.17	1.73	1.79	.50	1.21
1945-46	49,800,000	3.55	3.55	3.10	2.83	3.25	1.84	1.83	.48	1.24
1946-47	52,800,000	2.62	2.62	2.35	.82	1.93	.50	.84	.53	1.25
GRAPEFRUIT										
1931-32	10,431,424	$1.50	$ .90	$ .90	$ .30	$1.33	$ .22	$ .25	$ .40	$ .85
1932-33	11,925,630	1.16	.50	.40	.32	.86	-.11	-.07	.38	.85
1933-34	11,113,200	1.51	.90	.90	.53	1.19	.23	.29	.39	.83
1934-35	15,243,060	1.29	.80	.70	.37	.88	.01	.08	.37	.84
1935-36	11,504,067	1.87	1.20	1.10	.73	1.39	.46	.61	.39	.87
1936-37	18,121,786	1.48	1.10	1.00	.55	1.09	.25	.35	.30	.83
1937-38	14,378,760	1.53	1.10	1.10	.48	1.05	.18	.35	.36	.82
1938-39	23,050,835	1.04	.80	.80	.22	.64	-.09	-	.30	.74
1939-40	15,650,865	1.42	1.30	1.12	.33	.79	-.01	.20	.40	.82
1940-41	24,387,041	1.21	1.10	.86	.37	.71	-.02	.12	.35	.74
1941-42	19,100,000	1.80	1.70	1.45	.71	1.20	.34	.60	.40	.80
1942-43	27,300,116	2.33	2.25	1.85	1.05	1.48	.67	1.10	.35	.88
1943-44	31,000,000	2.47	2.47	2.00	1.53	1.83	.92	1.00	.40	1.07
1944-45	22,300,000	3.00	3.00	2.60	1.91	2.24	1.36	1.53	.40	1.07
1945-46	32,000,000	2.65	2.65	2.40	1.39	1.77	.78	1.21	.34	1.10
1946-47	26,400,000	2.18	2.18	1.90	.65	1.25	.26	.73	.37	1.08

*Net to grower (or fruit owner) indicates the amount per box after deducting production and all other costs except interest, taxes and depreciation. The "On Tree" average price may be obtained by adding production costs to "Net to Grower" return.

CITRUS PRICE ANALYSIS 1931-32 TO 1946-47

	FLORIDA GROSS FOB MARKET OR EQUIVALENT PER BOX						NET* TO GROWER			RAIL & BOAT
	BOX YIELD	RAIL & BOAT	TRUCKED OUT	FLORIDA CONSUMED	FLORIDA CANNED	GROSS ALL	NET ALL	NET RAIL & BOAT	COST PRODUCTION	COST PICKING HAULING MARKETING RAIL&BOAT
TANGERINES										
1931-32	1,465,807	$2.05	$1.00	$1.00	$ -	$1.85	$ .05	$ .05	$ .75	$1.25
1932-33	1,519,200	1.42	1.00	.90	-	1.32	-.18	-.30	.56	1.16
1933-34	1,992,091	1.80	1.40	1.25	-	1.68	.29	.19	.56	1.05
1934-35	2,003,755	1.66	1.15	1.10	-	1.51	.21	.16	.55	.95
1935-36	2,093,397	2.00	1.50	1.40	-	1.86	.42	.35	.55	1.10
1936-37	3,018,634	1.45	1.15	1.05	-	1.37	-.18	-.20	.50	1.15
1937-38	2,257,973	1.86	1.28	1.28	-	1.72	.14	.18	.52	1.16
1938-39	3,381,873	1.34	1.05	1.05	-	1.27	-.07	-.06	.45	.95
1939-40	2,257,545	2.00	1.90	1.70	-	1.95	.42	.44	.50	1.06
1940-41	2,751,624	1.68	1.65	1.31	-	1.60	.08	.10	.50	1.08
1941-42	2,100,000	2.85	2.80	2.40	-	2.77	1.09	1.11	.58	1.16
1942-43	4,200,149	2.78	2.70	2.25	-	2.72	.98	1.03	.40	1.35
1943-44	3,600,000	3.70	3.70	3.00	-	3.62	1.36	1.37	.66	1.68
1944-45	3,900,000	4.25	4.25	3.60	-	4.18	1.91	1.92	.65	1.68
1945-46	4,200,000	4.80	4.80	4.00	1.00	4.24	2.10	2.45	.64	1.71
1946-47	3,900,000	3.75	3.75	3.30	.80	2.99	.90	1.35	.68	1.72
TOTAL CITRUS										
1931-32	24,446,218	1.95	1.20	1.18	.31	1.75	.45	.50	.55	.92
1932-33	28,409,630	1.36	.80	.70	.33	1.15	.02	.015	.45	.90
1933-34	29,276,287	1.65	1.19	1.08	.54	1.45	.34	.336	.44	.87
1934-35	32,835,854	1.63	1.19	1.05	.38	1.33	.27	.32	.43	.88
1935-36	29,462,052	2.14	1.48	1.37	.74	1.81	.69	.76	.44	.94
1936-37	40,601,208	2.04	1.58	1.43	.61	1.70	.61	.75	.37	.92
1937-38	40,939,629	1.57	1.12	1.13	.46	1.30	.22	.305	.38	.88
1938-39	56,447,995	1.31	1.07	1.04	.24	1.04	.07	.15	.34	.82
1939-40	42,973,112	1.60	1.51	1.29	.28	1.17	.12	.28	.42	.90
1940-41	55,890,754	1.51	1.49	1.18	.47	1.15	.16	.27	.39	.85
1941-42	48,400,000	2.06	2.05	1.69	.83	1.66	.57	.74	.43	.89
1942-43	68,700,000	2.81	2.78	2.28	1.22	2.23	1.11	1.41	.39	1.01
1943-44	80,800,000	3.01	3.10	2.37	1.70	2.47	1.16	1.28	.49	1.24
1944-45	69,000,000	3.48	3.57	2.95	2.25	2.93	1.62	1.75	.48	1.25
1945-46	86,000,000	3.44	3.61	3.00	2.05	2.75	1.46	1.73	.46	1.25
1946-47	83,100,000	2.59	2.59	2.21	.75	1.76	.44	.85	.50	1.24

*Net to grower (or fruit owner) indicates amount per box after deducting production and all other costs except interest, taxes and depreciation. The "On Tree" average price may be obtained by adding the production costs to the "Net to Grower" return.

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 22 SEASONS

(For Harvest)

Season	Beans Acreage	Limas Acreage	Cabbage Acreage	Celery Acreage	Cucumbers Acreage	Season
1925-26	16,000	(1)	3,660	3,520	7,590	1925-26
1926-27	19,490	(1)	3,010	4,240	7,440	1926-27
1927-28	29,730	(1)	2,900	3,380	9,450	1927-28
1928-29	27,000	(1)	6,500	6,620	11,340	1928-29
1929-30	35,800	(1)	3,700	6,650	12,100	1929-30
1930-31	40,000	(1)	6,500	6,150	9,650	1930-31
1931-32	41,500	(1)	5,500	6,850	7,300	1931-32
1932-33	50,800	(1)	6,200	6,650	5,600	1932-33
1933-34	61,300	1,500	10,700	6,000	5,000	1933-34
1934-35	65,500	1,500	5,600	6,000	5,100	1934-35
1935-36	59,200	1,800	9,000	6,500	5,700	1935-36
1936-37	58,800	2,400	8,500	7,500	5,600	1936-37
1937-38	60,700	4,500	9,400	8,000	7,000	1937-38
1938-39	64,000	4,800	10,000	7,300	7,600	1938-39
1939-40	52,000	4,000	16,000	7,500	8,200	1939-40
1940-41	62,500	7,000	10,000	8,700	8,800	1940-41
1941-42	68,000	5,000	18,000	9,350	9,700	1941-42
1942-43	80,000	5,400	10,000	8,750	6,500	1942-43
1943-44	96,500	4,500	23,500	9,900	6,300	1943-44
1944-45	80,500	4,800	17,500	11,050	7,700	1944-45
1945-46	80,200	6,300	13,200	13,450	11,950	1945-46
1946-47	81,700	5,200	14,000	11,700	13,775	1946-47

Note: (1) Limas were included with snap beans prior to the 1933-34 season. The lima figures are for the Fordhook or large variety and do not include acreage of baby limas or butterbeans.

Season	Eggplant Acreage	Escarole (2) Acreage	Boston Lettuce (3) Acreage	Iceberg Lettuce (4) Acreage	English Peas Acreage	Season
1925-26	1,020	(2)	1,500	-	760	1925-26
1926-27	630	(2)	1,500	-	700	1926-27
1927-28	1,550	340	1,500	-	1,230	1927-28
1928-29	1,320	500	1,500	-	1,350	1928-29
1929-30	1,680	460	1,100	-	700	1929-30
1930-31	1,800	850	1,600	-	2,000	1930-31
1931-32	1,950	700	1,000	-	3,800	1931-32
1932-33	2,450	700	950	-	3,600	1932-33
1933-34	2,050	700	1,100	-	4,800	1933-34
1934-35	1,500	650	900	(4)	5,000	1934-35
1935-36	1,100	700	550	(4)	8,200	1935-36
1936-37	1,480	900	800	(4)	6,200	1936-37
1937-38	1,800	1,000	900	(4)	6,200	1937-38
1938-39	2,100	1,000	750	250	5,000	1938-39
1939-40	1,400	1,350	900	1,100	5,000	1939-40
1940-41	1,900	1,000	500	2,000	3,000	1940-41
1941-42	2,350	1,200	500	3,000	3,500	1941-42
1942-43	1,950	1,450	800	1,700	1,500	1942-43
1943-44	3,500	2,350	1,100	1,350	2,500	1943-44
1944-45	2,850	2,800	400	1,000	2,600	1944-45
1945-46	3,900	2,500	550	1,300	1,600	1945-46
1946-47	3,300	2,800	700	1,125	1,600	1946-47

Notes: (2) Escarole acreage included with lettuce prior to 1927-28 season.
(3) Big Boston figures include Romaine acreage.
(4) Iceberg Lettuce included in Big Boston acreage figures until the 1938-39 season.

All 1946-47 acreage figures are preliminary as of September 20, 1947 and are subject to revision.

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 21 SEASONS (Cont'd).

(For Harvest)

Season	Peppers Acreage	Potatoes Acreage	Tomatoes Acreage	Total Vegetables Acreage	Season
1925-26	3,370	23,070	20,700	81,190	1925-26
1926-27	2,700	28,000	29,800	97,510	1926-27
1927-28	6,410	30,000	29,280	115,770	1927-28
1928-29	5,650	22,000	38,700	122,480	1928-29
1929-30	6,550	31,000	31,260	131,000	1929-30
1930-31	8,200	27,000	26,800	130,550	1930-31
1931-32	8,050	21,500	23,700	121,850	1931-32
1932-33	8,300	17,000	24,900	127,150	1932-33
1933-34	6,000	23,500	30,500	153,150	1933-34
1934-35	7,700	24,800	32,500	156,750	1934-35
1935-36	6,500	24,500	32,600	156,350	1935-36
1936-37	7,200	31,300	35,700	166,380	1936-37
1937-38	7,400	31,400	45,300	183,600	1937-38
1938-39	7,300	26,700	40,700	177,500	1938-39
1939-40	6,200	25,600	34,000	163,250	1939-40
1940-41	7,200	26,800	26,500	165,900	1940-41
1941-42	6,500	25,000	43,000	195,100	1941-42
1942-43	7,100	26,200	25,500	176,850	1942-43
1943-44	8,950	28,600	34,900	223,950	1943-44
1944-45	9,350	31,100	32,500	204,150	1944-45
1945-46	11,080	35,300	30,400	220,950	1945-46
1946-47	10,550	24,100	29,800	200,350*	1946-47

*Does not include 600 acres of cauliflower and 500 acres of commercial carrots. Does not include acreage for squash, radishes, broccoli, or any other vegetables not named. The Miscellaneous Vegetables probably total 20,000 acres.

Season	Cantaloupes (3) Acreage	Strawberries Acreage	Watermelons Acreage	Grand Total Acreage	Season
1925-26	600	2,980	24,150	108,920	1925-26
1926-27	600	3,680	29,420	131,210	1926-27
1927-28	600	4,500	37,840	158,710	1927-28
1928-29	600	6,300	35,900	165,280	1928-29
1929-30	600	8,800	34,700	175,100	1929-30
1930-31	250	9,100	31,000	170,900	1930-31
1931-32	200	7,800	28,500	158,350	1931-32
1932-33	400	10,600	22,500	160,650	1932-33
1933-34	300	8,400	23,400	185,250	1933-34
1934-35	200	8,000	20,000	184,950	1934-35
1935-36	200	8,900	16,000	181,450	1935-36
1936-37	300	8,800	19,500	194,980	1936-37
1937-38	700	7,500	22,500	214,300	1937-38
1938-39	500	9,000	22,600	209,600	1938-39
1939-40	500	7,200	23,500	194,450	1939-40
1940-41	500	5,500	25,500	198,100	1940-41
1941-42	500	5,000	21,500	221,200	1941-42
1942-43	400	2,600	12,500	192,350	1942-43
1943-44	550	1,400	25,500	251,400	1943-44
1944-45	500	2,050	39,000	245,700	1944-45
1945-46	800	2,800	51,000	275,550 (4)	1945-46
1946-47	800	4,750	47,000	252,900 (5)	1946-47

Notes: (3) Acreage of cantaloupes for 1926, 1927 and 1928 seasons not immediately available, but is estimated the same as for 1929 and 1930 seasons.

(4) These acreage figures do not include acres abandoned in various stages of growth for reasons other than economic marketing.

All acreage figures are preliminary as of September 20, 1947 and are subject to revision. Years prior to 1946-47 may have been revised slightly.

(5) Does not include 65,400 acres of vegetables and 4,000 acres of watermelons planted but not reaching harvest stage. Some acreage was abandoned for

FLORIDA FOB PACKED VALUE OF SELECTED VEGETABLES AND NON-CITRUS FRUITS FOR 16 SEASONS

Season	Beans	Limas	Cabbage	Celery	Cucumbers
1931-32	$ 5,958,000	$ Included	$ 704,000	$ 3,783,000	$ 655,000
1932-33	4,356,000	with Beans	590,000	1,949,000	633,000
1933-34	5,773,000	236,000	685,000	2,996,000	845,000
1934-35	5,967,000	270,000	1,630,000	4,368,000	765,000
1935-36	6,250,000	202,000	612,000	4,488,000	928,000
1936-37	7,031,000	390,000	496,000	4,532,000	1,101,000
1937-38	6,272,000	507,000	978,000	3,289,000	1,053,000
1938-39	7,041,000	720,000	990,000	5,375,000	1,391,000
1939-40	7,480,000	420,000	2,061,000	5,868,000	1,938,000
1940-41	8,615,000	616,000	2,334,000	8,066,000	1,858,000
1941-42	11,412,000	704,000	1,602,000	7,154,000	2,124,000
1942-43	17,989,000	1,041,000	6.460,000	17,158,000	2,592,000
1943-44	19,116,000	1,436,000	4,284,000	16,236,000	2,079,000
1944-45	18,405,000	1,779,000	3,959,000	18,553,000	3,637,000
1945-46	18,359,000	1,533,000	5,571,000	14,260,000	5,377,000
1946-47	16,389,000	1,187,000	3,069,000	17,535,000	4,984,000

Season	Eggplant	Escarole	Lettuce	English Peas	Peppers
1931-32	$ 277,000	$ 204,000	$ 256,000	$ 266,000	$1,780,000
1932-33	369,000	212,000	269,000	403,000	1,284,000
1933-34	289,000	267,000	286,000	507,000	1,676,000
1934-35	212,000	235,000	255,000	520,000	1,277,000
1935-36	268,000	207,000	185,000	508,000	1,273,000
1936-37	323,000	306,000	170,000	418,000	1,905,000
1937-38	356,000	204,000	149,000	642,000	1,668,000
1938-39	514,000	264,000	270,000	648,000	2,771,000
1939-40	417,000	304,000	612,000	520,000	2,121,000
1940-41	378,000	364,000	423,750	409,500	2,537,000
1941-42	628,000	324,000	481,000	434,000	2,838,000
1942-43	1,294,000	1,142,000	1,340,000	254,000	5,917,000
1943-44	1,501,000	645,000	562,000	450,000	5,460,000
1944-45	1,814,000	1,352,000	634,000	284,000	6,623,000
1945-46	1,805,000	875,000	1,285,220	339,000	6,545,000
1946-47	1,758,000	1,133,000	559,000	189,000	9,086,000

Season	Potatoes	Tomatoes	Total Value Vegetables
1931-32	$1,933,000	$ 5,748,000	$21,564,000
1932-33	1,908,000	4,377,000	16,350,000
1933-34	3,708,000	8,476,000	25,744,000
1934-35	2,503,000	6,835,000	24,837,000
1935-36	3,187,000	8,224,000	26,332,000
1936-37	5,078,000	7,683,000	29,438,000
1937-38	2,939,000	8,711,000	26,768,000
1938-39	3,644,000	12,323,000	35,951,000
1939-40	3,725,000	8,216,000	33,684,000
1940-41	2,799,000	8,618,000	36,844,000
1941-42	6,018,000	13,468,000	47,187,000
1942-43	5,914,000	11,795,000	72,896,000
1943-44	7,431,000	20,734,000	80,025,000
1944-45	12,033,000	20,376,000	89,449,000
1945-46	11,744,000	22,405,000	90,098,220
1946-47	5,475,000	19,093,000	80,512,000

Season	Cantaloupes	Strawberries	Watermelons	Total Value Misc. Fruits* & Vegetables
1931-32	$15,000	$2,846,000	$ 912,000	$25,337,000
1932-33	24,000	2,322,000	990,000	19,686,000
1933-34	23,000	2,646,000	779,000	29,192,000
1934-35	18,000	2,236,000	726,000	27,817,000
1935-36	15,000	1,972,000	896,000	29,215,000
1936-37	28,000	2,746,000	1,310,000	33,522,000
1937-38	65,000	2,100,000	945,000	29,878,000
1938-39	44,000	3,175,000	976,000	40,146,000
1939-40	38,000	2,344,000	1,193,000	37,259,000
1940-41	37,500	2,194,000	1,445,850	40,521,000
1941-42	52,000	2,275,000	1,572,000	51,086,000
1942-43	84,500	1,498,000	2,641,000	77,119,500
1943-44	91,000	1,107,000	4,593,000	85,725,000
1944-45	120,000	1,541,000	4,918,000	96,028,000
1945-46	54,000	2,363,000	5,552,000	98,067,220
1946-47	102,000	3,737,000	5,419,000	89,770,000

Note: *Does not include citrus fruits. Tabulations based on information supplied by U.S. Agricultural Statisticians, Orlando, Florida. Valuation figures represent gross packed value, when packed at Florida shipping points. Several vegetables of commercial importance not included above.

POULTRY AND EGG WHOLESALE PRICES-TAMPA AND MIAMI

TAMPA (January 1, 1939-September 30, 1947)

WHITE EGGS (Standard 24 oz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Aver.
1939	31.2	24.5	22.1	23.4	23.4	25.0	30.5	29.0	31.6	34.3	35.8	32.5	28.6
1940	31.5	29.2	21.5	22.1	22.3	24.2	29.5	32.5	35.9	37.5	37.1	38.6	30.2
1941	34.6	26.2	24.2	26.0	28.4	32.0	27.5	40.0	51.1	43.5	45.1	45.5	35.2
1942	41.9	33.2	31.2	33.0	32.4	35.5	41.0	46.1	47.3	49.0C	49.0	49.0	40.7
1943	48.7	40.1	39.0	43.0	43.0	43.1	47.1	51.3	55.0	58.3	57.3	53.3	48.3
1944	46.5	40.5	37.1	37.0	38.6	40.6	44.3	50.5	52.2	58.6	60.0	59.1	47.1
1945	49.3	44.0	38.2	41.8	42.0	44.8	49.3	55.0	57.9	58.7	60.1	59.0	50.0
1946	49.9	41.8	39.0	39.3	42.0	45.1C	51.1	56.0	61.2	67.0	62.8	63.8	51.5
1947	58.7	55.0	52.2	52.3	57.0	58.2	63,3	66.4	70.8				

HENS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Aver.
1939	19.1#	17.8	17.9	17.9	17.5	17.3	16.9	16.0	16.6	17.2	16.4	16.6	17.2
1940	17.1	17.1	17.3	18.0	17.0	16.5	14.8	14.7	16.8	16.6	17.5	17.5	16.7
1941	17.5	18.9	18.9	19.5	19.0	20.2	21.0	20.5	21.1	23.0	23.7	24.0	20.6
1942	24.5	24.0	23.1	24.4	24.3	22.5	22.3	22.0	23.9	26.0C	26.0	26.0	24.1
1943	28.5	29.5	29.4	29.4	29.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	28.2
1944	27.4	27.4	27.4	27.4	29.6	28.4	27.4	27.4	27.4	27.4	27.4	27.4	27.7
1945	27.5	27.8	28.8	29.2	29.6	28.5	27.6	27.4	27.3	27.3	27.3	27.3	27.9
1946	27.3	28.3	28.5	28.7	29.5	28.7C	24.8	25.1	31.2	35.6	32.1	32.0	29.3
1947	31.4	31.4	36.1	35.5	30.8	30.0	30.8	31.4	31.5				

FRYERS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Aver.
1939	19.1#	17.3	19.8	20.8	18.6	19.8	19.3	18.2	18.6	19.4	19.1	19.0	18.9
1940	21.5	19.5	19.3	21.5	21.3	22.4	18.6	17.9	19.4	19.5	19.7	19.4	20.0
1941	19.2	20.2	21.4	22.0	19.7	20.7	22.2	22.5	22.7	23.0	23.7	24.0	21.8
1942	25.8	24.0	23.5	25.3	26.7	27.0	27.6	29.0	29.9	31.0C	31.0	31.0	27.7
1943	33.0	31.5	31.6	31.9	31.1	30.9	30.9	30.9	30.9	30.9	30.9	30.9	31.3
1944	30.9	30.9	30.9	31.2	33.1	31.9	30.9	30.9	30.9	30.9	30.9	30.9	31.2
1945	31.0	31.5	32.3	32.7	33.1	32.0	31.7	31.7	31.6	31.6	31.6	31.6	31.8
1946	31.6	32.6	32.8	33.0	33.8	33.5C	35.2	38.1	40.4	47.3	43.0	44.6	37.1
1947	39.9	32.9	34.4	35.5	36.7	37.0	39.3	41.4	41.7				

MIAMI (January 1, 1939-September 30, 1947)

WHITE EGGS (Standard 24 oz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Aver.
1939	35.1	27.3	24.3	25.0	24.9	Unavailable			33.8	37.2	39.5	36.5	31.5
1940	36.5	35.3	26.0	25.8	25.5	25.8	31.8	35.0	38.4	43.1	40.0	42.9	N
1941	38.3	31.7	28.1	29.0	31.6	34.1	38.6	41.5	43.1	45.0	47.8	48.0	N
1942	43.0	41.0	33.0	35.0	35.0	42.0	47.0	49.0	51.0	52.0C	52.0	52.0	44.4
1943	52.0	44.0	42.0	44.5	44.5	46.5	49.6	53.9	57.5	60.9	59.8	55.2	50.9
1944	51.5	47.5	44.5	44.5	44.5	45.5	50.0	54.5	57.6	58.0	60.5	59.3	51.5
1945	50.8	45.6	43.2	43.2	43.2	45.6	49.9	54.7	58.3	59.2	60.5	59.8	51.2
1946	50.7	45.5	43.2	43.2	43.2	45.8C	50.3	52.0	57.0	63.6	61.0	59.2	50.5
1947	53.1	52.0	52.2	57.6	54.5	53.7I	62.6	66.9	72.4				

HENS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Aver.
1939	24.5	23.6	24.0	23.3	21.5	Unavailable			21.7	24.0	23.5	22.8	23.2
1940	22.5	22.0	22.0	22.0	22.0	22.0	22.0	22.3	22.0	23.5	23.0	23.0	22.4
1941	23.0	23.0	23.0	23.0	23.5	24.5	26.5	25.0	25.0	25.0	25.5	26.0	24.4
1942	27.0	27.0	30.0	30.0	30.0	30.0	30.0	30.0	32.0	32.0C	28.0	28.0	29.5
1943	28.0	28.0	28.0	28.0	28.0	28.0	(- - No quotations on account of consider-						
1944	able price ceiling confusion - -)						29.7	29.7	29.7	29.7	29.7	29.7	29.7
1945	29.7	28.5	29.9	31.6	29.1	28.7	27.8	27.5	27.5	27.5	27.5	27.5	28.5
1946	27.5	27.5	27.5	27.5	31.4	32.4C	32.1	32.8	38.7	31.9	38.8	40.0	32.3
1947	41.4	40.6	41.9	41.3	40.9	38.3I	35.6	35.0	37.4				

FRYERS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Aver.
1939	24.3	24.7	26.0	25.0	23.4	Unavailable			23.9	25.0	24.5	23.8	24.5
1940	23.5	22.9	23.0	23.0	23.0	23.0	23.0	24.6	25.0	24.1	24.0	24.0	23.6
1941	25.0	25.0	27.0	26.5	25.0	25.0	26.0	25.0	25.0	25.0	26.0	27.0	25.6
1942	30.0	30.0	30.0	30.0	32.0	35.0	35.0	35.0	37.0	37.0C	32.0	32.0	33.0
1943	32.0	32.0	32.0	32.0	32.0	32.0	(- - No quotations on account of consider-						
1944	able price ceiling confusion - -)						33.2	33.2	33.2	33.2	33.2	33.2	33.2
1945	33.2	32.0	33.4	35.2	32.2	32.5	32.0	32.0	32.0	32.0	32.0	32.0	32.5
1946	32.0	32.0	32.0	32.0	35.9	37.1C	38.7	38.5	44.0	46.3	43.4	45.0	38.1
1947	39.2	35.0	39.6	40.0	41.3	43.0I	43.0	43.0	45.7				

C Ceiling prices in effect from October 3, 1942 through June 30, 1946.
* Quotations temporarily discontinued in August 1931.
# August 8, 1938 through January 1939, quotations based on buying instead of selling prices of poultry. N - Not calculated.

JACKSONVILLE JOBBING MARKET
SALES TO RETAILER OR EQUIVALENT SALES
MONTHLY SIMPLE AVERAGES

EGGS - Florida White Grade A-24 oz. per Dozen

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1921	74.3	48.6	36.0	31.3	30.5	31.9	42.7	47.9	50.0	59.4	64.8	60.0	48.1
1922	48.0	40.7	26.5	29.4	28.3	34.7	37.5	37.5	52.8	55.0	62.8	53.9	40.6
1923	49.6	36.0	30.0	29.5	29.0	33.8	39.5	42.6	49.8	56.3	59.3	58.0	42.8
1924	47.4	44.6	26.6	25.8	28.5	32.5	39.0	43.6	52.1	62.0	66.2	64.9	44.4
1925	56.8	45.3	30.2	33.5	30.3	38.6	44.4	48.4	55.2	64.0	65.6	67.0	48.3
1926	57.2	42.1	31.3	34.1	32.5	36.1	41.6	44.4	51.8	62.2	61.0	57.1	45.9
1927	47.6	35.9	28.0	29.2	27.9	29.7	33.9	41.4	49.0	52.1	55.0	50.4	40.0
1928	48.0	32.4	30.0	29.7	28.2	33.4	36.5	41.7	48.3	54.8	55.0	48.5	40.4
1929	42.2	34.5	35.1	29.2	30.2	33.7	39.3	43.2	45.2	54.1	55.3	54.0	41.5
1930	47.1	35.4	28.5	27.0	27.0	27.0	30.6	34.9	38.2	45.4	43.9	40.9	35.5
1931	32.0	22.0	23.0	22.0	20.0	21.0	25.0	28.5	32.0	37.5	38.0	33.0	27.9
1932	26.5	16.5	18.0	15.5	14.7	18.3	21.0	25.0	28.2	31.5	32.6	35.2	23.5
1933	23.5	17.0	15.5	15.5	17.3	16.3	22.9	25.5	31.4	33.0	32.0	34.4	23.7
1934	28.7	25.6	19.2	19.8	20.1	23.5	28.0	31.6	36.8	38.0	40.0	40.0	29.3
1935	35.8	31.8	23.0	24.9	26.3	26.8	31.5	35.6	39.0	39.3	37.0	40.6	32.6
1936	33.5	31.2	23.5	22.9	24.1	25.7	31.9	34.0	37.5	38.4	41.9	43.4	32.3
1937	29.8	27.5	25.1	25.5	24.2	25.8	30.1	33.0	37.2	38.1	39.6	38.0	31.2
1938	32.5	26.6	22.2	22.3	25.0	25.7	31.5	32.8	36.3	36.3	36.8	40.1	30.7
1939	30.8	24.3	21.6	21.9	22.6	23.0	29.1	29.6	28.8	32.4	33.9	30.9	27.4
1940	31.4	26.8	20.7	20.8	21.2	23.5	28.8	31.7	34.5	36.4	36.3	38.2	29.2
1941	33.3	25.4	24.1	25.2	28.4	31.2	36.8	39.2	41.4	42.0	44.5	42.2	34.5
1942	40.0	31.5	30.5	31.4	31.4	34.7	39.5	45.0	46.1	48.0*	48.0*	48.0*	39.7
1943	47.6	38.7	38.0	38.4*	43.0*	43.6*	46.9*	51.0*	54.8*	58.0*	57.0*	53.6*	47.6
1944	49.3*	39.7*	37.1*	37.0*	38.2*	41.4*	45.2*	50.3*	55.1*	58.6*	59.9*	59.0*	47.6
1945	50.0*	44.0*	37.8*	42.4*	42.6*	44.9*	49.3*	54.4*	57.8*	58.6*	59.9*	58.8*	50.0
1946	49.7*	40.7*	39.0*	39.1*	42.4*	45.0**	50.7	55.6	60.4	66.2	61.3	62.8	51.1
1947	59.4	52.4	51.1	52.4	56.0	57.4	62.3	64.9					

FRYERS - Heavy Breed

1921	39.1	39.7	46.9	49.5	46.6	35.0	31.2	30.3	34.0	35.5	29.1	29.0	37.2
1922	29.0	29.5	38.4	40.0	40.0	35.5	31.5	29.0	31.0	29.0	29.0	29.0	32.6
1923	29.5	31.0	36.5	37.0	39.8	36.7	30.0	30.0	33.0	32.4	31.0	31.0	33.1
1924	32.7	36.6	37.8	42.0	42.5	37.4	32.7	30.7	34.0	33.0	31.5	34.3	35.4
1925	41.4	44.0	45.6	45.9	43.7	39.4	36.0	35.0	38.0	39.0	37.0	38.6	40.3
1926	43.5	48.0	49.7	50.0	48.3	38.3	37.8	35.3	35.0	35.0	35.3	37.1	41.1
1927	42.0	45.0	45.0	46.3	43.0	36.1	31.8	30.0	30.0	31.1	33.1	35.8	37.4
1928	37.0	36.2	38.9	39.0	39.0	38.1	34.5	31.2	33.0	35.3	36.3	35.7	36.3
1929	26.0	36.2	39.1	42.8	37.7	37.3	31.0	31.1	35.0	34.2	36.1	36.8	36.1
1930	33.1	32.9	33.6	36.7	32.7	32.8	24.5	27.4	29.0	29.0	29.0	29.0	30.9
1931	30.0	31.0	37.0	40.0	37.0	35.0	29.0	27.0	27.5	26.0	24.5	24.5	30.6
1932	24.4	23.2	27.1	26.8	23.9	23.5	18.0	17.3	18.0	18.7	17.3	14.9	21.0
1933	14.6	20.4	22.2	24.3	22.1	18.0	15.4	16.1	17.0	17.0	15.7	16.1	18.2
1934	17.6	20.2	23.9	25.2	24.9	22.5	20.1	18.7	19.7	20.0	20.5	20.5	21.2

(Cont'd.)

* Ceiling prices in effect.

** Ceiling prices ended June 30, 1946

JACKSONVILLE JOBBING MARKET
SALES TO RETAILER OR EQUIVALENT SALES
MONTHLY SIMPLE AVERAGES

FRYERS - Heavy Breed (Cont'd.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1935	21.5	24.3	26.1	25.9	22.8	23.1	21.2	20.3	21.0	22.4	23.2	24.5	23.0
1936	25.5	25.6	27.0	27.2	25.7	25.5	23.1	22.6	22.3	21.2	20.5	20.0	23.7
1937	22.3	24.0	24.1	27.0	24.1	25.3	25.5	24.5	25.8	27.1	26.7	27.7	25.4
1938	25.8	24.6	27.2	27.8	24.0	21.8	20.5	21.6	22.9	22.9	23.0	23.6	23.8
1939	23.4	21.6	21.9	24.8	22.0	21.8	22.5	21.9	21.0	22.0	22.3	22.1	22.3
1940	22.0	21.8	22.8	22.6	24.3	23.2	21.4	20.5	21.5	21.9	20.8	21.5	22.0
1941	21.8	22.4	23.8	24.3	23.0	22.8	22.8	22.2	22.6	23.0	23.9	24.0	23.1
1942	24.1	23.7	24.2	25.6	26.8	27.5	27.4	27.5	29.0	30.5	30.5	31.4	27.4
1943	31.8	31.8	31.8	31.9*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	31.0
1944	30.6*	30.6*	30.6*	31.0*	32.6*	31.8*	31.1*	30.6*	30.6*	30.6*	30.6*	30.6*	30.9
1945	30.6*	31.6*	32.0*	32.4*	32.8*	31.6*	31.4*	31.3*	31.3*	31.3*	31.3*	31.3*	31.6
1946	31.6*	32.1*	32.5*	32.9*	33.3*	33.0**	39.1	38.5	43.3	47.1	41.5	41.2	37.2
1947	36.2	32.5	34.5	35.0	37.4	38.0	38.5	39.0					

HENS - Heavy Breed

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1921	33.6	32.6	31.7	29.3	26.9	26.3	25.1	26.2	30.3	31.8	26.0	26.0	28.8
1922	26.0	26.0	26.7	25.5	25.4	24.0	24.0	24.0	27.5	26.0	26.0	26.0	25.6
1923	26.0	26.0	26.0	25.0	23.0	23.0	20.9	21.1	24.7	26.0	24.3	24.7	24.2
1924	27.8	26.0	26.4	26.0	27.0	25.1	24.0	26.6	29.4	30.0	28.6	27.8	27.1
1925	31.6	29.2	29.7	28.0	28.0	26.6	25.9	29.0	30.0	31.0	28.1	29.3	28.7
1926	30.7	30.2	32.5	31.8	31.9	30.0	30.0	29.7	31.0	31.0	30.2	31.1	30.7
1927	30.0	30.0	29.8	29.1	29.0	24.7	23.7	25.6	26.0	26.0	25.0	25.0	26.9
1928	25.0	25.0	25.0	25.0	24.5	23.0	21.9	21.1	23.9	27.2	25.5	24.5	24.3
1929	24.8	26.4	28.8	28.8	27.4	29.3	28.0	29.0	31.2	29.5	29.5	29.8	28.5
1930	29.8	30.0	28.5	27.5	26.6	24.5	22.5	22.6	23.0	22.8	23.0	23.0	25.3
1931	23.0	20.0	22.0	24.0	23.0	22.0	21.0	20.0	21.5	23.0	22.5	22.0	22.0
1932	20.5	18.6	18.7	19.0	17.5	16.1	14.5	14.5	15.5	16.7	17.0	14.4	16.9
1933	13.2	13.5	13.0	14.7	14.1	13.1	13.0	14.6	15.8	16.7	15.4	14.0	14.3
1934	14.3	15.5	16.0	15.5	18.8	16.0	15.7	14.8	16.6	17.2	17.8	17.5	16.1
1935	17.5	17.8	18.3	18.0	18.0	18.7	18.2	18.4	19.3	21.0	21.7	20.6	19.0
1936	20.0	19.9	19.5	20.3	20.8	20.5	20.9	20.7	20.2	19.6	19.6	18.7	20.1
1937	18.7	19.3	18.6	18.5	19.0	19.5	16.8	16.0	17.5	18.7	20.2	20.7	18.6
1938	20.1	19.0	19.9	19.7	19.0	19.3	19.4	18.7	20.2	20.2	21.0	21.2	19.8
1939	21.4	20.7	20.4	21.1	19.3	18.8	17.8	18.2	16.9	16.9	17.9	15.3	18.7
1940	16.2	16.7	17.5	17.5	17.1	16.2	15.5	16.1	16.5	18.5	17.8	17.2	16.9
1941	17.6	18.1	19.0	19.9	19.8	20.8	20.7	20.5	21.1	21.5	23.0	23.1	20.4
1942	23.9	22.8	23.0	23.6	23.2	21.5	21.0	21.8	24.9	26.5	26.5	27.8	23.9
1943	29.3	29.3	29.3	29.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.8
1944	27.1*	27.1*	27.1*	27.5*	29.2*	28.4*	27.6*	27.1*	27.1*	27.1*	27.1*	27.1*	27.5
1945	27.1*	28.1*	28.5*	28.9*	29.3*	28.1*	27.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.7
1946	27.6*	28.1*	28.5*	28.9*	29.3*	28.1**	29.1	29.2	35.0	40.6	35.2	35.0	31.2
1947	33.1	34.5	38.1	36.4	34.3	32.6	32.8	33.9					

* Ceiling prices in effect.
** Ceiling prices ended June 30, 1946

GENERAL FACTS ABOUT FLORIDA'S LIVESTOCK INDUSTRY

By L. H. Lewis, Livestock Specialist, Florida State Marketing Bureau

CATTLE AND CALVES

Q. 1: How many cattle and calves in Florida: Answer: U.S.D.A., BAE figures state that on January 1, 1947, there were 1,265,000 head of cattle and calves in Florida. There were 148,000 milking dairy cows.

Q. 2: What position has Florida as a cattle State? Answer: In beef or range cattle 14th, in dairying 35th, in total cattle 25th.

Q. 3: What are the leading range or beef cattle counties in Florida? Answer: Fifteen leading beef cattle counties have 48% of the total beef cattle of the State. Their order of importance are Polk, Osceola, Highlands, Marion, Glades, Hillsborough, Hardee, Okeechobee, Jackson, Sumter, Clay, Pasco, Putnam, Alachua, and Manatee.

Q. 4: How many cattle and calves are slaughtered in Florida? Answer: During the year 1946 there were approximately 400,000 head of cattle and calves slaughtered; during the year 1945 there were about 370,000 head slaughtered, which represents about 27 to 30% of the totals as of January 1st.

Q. 5: Where are most of the range or beef cattle in Florida found? Answer: Most of the farm beef cattle are found in west Florida; most of the range beef cattle are found in the peninsular of Florida or south Florida, and about 75% of the total cattle of the State are fenced.

Q. 6: What types and kinds of marketing facilities for livestock are in Florida? Answer: There are 14 meat packing plants and 14 abattoirs, and about 500 butchers; there are 21 livestock auction markets, 6 cash daily not including packers and abattoirs, as well as numerous local buyers. These facilities are scattered well over the State.

Q. 7: What is the live weight of different species and classes of livestock in Florida? Answer: The following table shows the live weight dressing percent and average dressed weight of livestock in Florida for the year 1944. These figures have a practical application for the years 1946 and 1947.

Class	Live Weight	Dressing Percent	Average Dressed Weight
Cattle	656 lbs.	49%	321 lbs.
Calves	233	52	122
Hogs	168	67	113
Sheep and Lambs	68	53	36

Q. 8: During what months does Florida, Alabama and Georgia market most of their livestock? Answer: During the months of February thru June each year, a smaller percentage of cattle and calves are marketed, while during the months of June, July, August and September a smaller percentage of the hogs are marketed. Those persons producing and selling hogs as well as cattle therefore market throughout the year while those producing hogs or cattle have a fluctuating supply for market.

Q. 9: How many purebred registered beef cattle herds in Florida? Answer: There are approximately 200 to 210 herds. The order of their importance as to numbers as follows:- Brahman, Hereford, Angus, Shorthorn, Red Polled, Devon.

Q. 10: Do the different purebred breeders have State associations? Answer: Yes for Angus, Brahman, Hereford and Shorthorn. The dairymen have an association for Guernseys and Jerseys: the Duroc-Jersey breeders have an association, and the Quarter Horse as well as the Palomino horse breeders each are organized. There may be others.

Q. 11: When does Florida market her livestock? Answer: The following table shows the average monthly marketings of slaughtered livestock for Florida for 3-year period, 1944-46 inclusive. Data furnished by U.S.D.A., P. & M.A., 402 Upchurch Bldg., Thomasville, Ga., and consolidated by the Florida State Marketing Bureau, Jacksonville, Florida.

Livestock Monthly Marketings, 3-year period, years indicated, Florida vs U.S.A.

Month	Florida - years 1944- 1946						U.S.A. 1940-42 *		
	CATTLE		CALVES		HOGS				
	Ave. Number	Ave. %	Ave. Number	Ave. %	Ave. Number	Ave. %	Cattle Average	Calves Average	Hogs Average
January	10,853	7.900	3,661	5.666	128,469	15.333	8.4 %	7.63%	10.56%
February	7,774	5.733	2,746	4.300	81,045	9.433	7.03	6.96	8.06
March	5,434	3.933	1,957	3.100	87,989	10.466	7.3	8.26	8.13
April	4,374	3.200	1,181	1.866	54,859	6.266	7.6	9.00	7.83
May	6,242	4.433	2,077	3.100	52,237	6.033	7.9	8.90	8.30
June	7,656	5.433	2,126	3.066	38,564	4.333	7.97	8.16	7.96
July	12,162	9.033	5,041	7.966	43,883	5.133	8.63	8.20	6.83
August	16,068	11.533	6,356	10.166	50,001	5.866	8.76	7.90	6.13
September	16,313	11.766	9,436	14.500	49,637	5.766	8.96	8.26	6.70
October	19,926	14.500	12,959	19.966	68,521	8.200	10.16	9.76	8.20
November	18,104	13.166	10,778	16.233	92,194	11.166	8.63	8.67	9.76
December	12,691	9.366	6,740	10.066	99,822	12.000	8.66	8.30	11.63
Total	137,597	100%	65,358	100%	847,227	100%	100 %	100 %	100 %

* Data USA years 1944-46 not at hand but comparisons are in line with other comparisons. Note more uniform marketings by months USA than in Florida.

According to USDA, BAE information, there were slaughtered of Florida's cattle production for the year 1946; 289,000 cattle and 105,300 calves, 3,700 sheep, 822,000 hogs. Cattle and calves were worth approximately $20,000,000. Sheep and lambs about $120,000, hogs about $15,000,000. These items include those slaughtered on the farm as well as non-farm slaughtered.

Q. 12: Are there any frozen food lockers in Florida? Answer: June survey, 1946, indicated 42 frozen food lockers in the State, at present-Sept. 1, 1947, there are approximately 50.

Q. 13: Is Florida self-supporting on meats? Answer: Florida is producing about 60% of its beef and veal and about 70% of its pork and lard on the basis of average per capita consumption for USA. There is no reason why Florida should not be self-supporting in meats.

The question is often asked, how do Florida cattle and calves grade as compared with USA. The following table shows percentage by grades for Florida in a recent survey and for that of USA, as USDA data.

Grade	Cattle average USA	Cattle average Southern States	Cattle average Florida	Calves average Florida	Grade of Meat
Choice	19.4 %	2.5 %	2.05 %	1.75 %	- AA or Choice
Good	31.1	12.2	6.60	13,40	A or Good
Medium	23.1	33.5	20.60	33,70	B or Commercial
Common	14.7	22.6	35,30	39,86	C or Utility
Cutter & Canner	11.7	29.2	35.45	11.27-Culls	D (or Canner & cutter (for cattle: Cull (for calves boned out
	100%	100%	100%	100%	

The grades in the USA were for the year 1944 while those for Florida were in a survey of 1947. From the above figures it is evident of the need of good purebred bulls, improved pasture and feed conditions, fencing and herd management practices, etc., as a means to bring about increase in grade.

For additional information write the Florida State Marketing Bureau for Bulletin No. 21, new series, year 1947, "Hog Production and Marketing in Florida" and for Bulletin No. 28, new series, September 1947, "Beef Cattle in Florida."

L. H. Lewis
Livestock Marketing Specialist
Florida State Marketing Bureau
P.O. Box 779
Jacksonville 1, Florida

JACKSONVILLE LIVESTOCK MARKET

(Substantially Southeastern Prices)

	COWS		CALVES		STEERS		HOGS	
	Medium	Common	Good	Medium	Good	Medium	No. 1	No. 2
	100 lbs		100 lbs.		100 lbs.		100 lbs.	
1930:							1930	
3-4	5.00-6.00	4.00-5.50	7.00-8.25	5.50-7.00	7.00-8.50	6.00-7.00	8.50	7.50
9-5	3.75-4.50	3.25-3.75	5.00-6.50	4.00-5.00	5.00-6.00	4.00-5.00	9.25-9.50	8.25-8.50
1931							1931	
3-3	3.50-4.25	2.50-3.50	5.50-6.50	4.75-5.50	5.50-6.75	4.50-5.50	6.00	5.50
9-4	2.50-3.25	2.00-2.75	4.00-5.00	3.00-4.00	4.00-4.75	3.00-4.25	5.25	4.75
1932							1932	
3-4	2.50-3.00	1.75-2.50	3.50-4.75	3.00-4.00	3.50-4.25	3.00-3.75	3.50	3.20
9-6	2.25-2.75	1.25-2.00	3.75-4.25	3.00-3.50	4.00-5.25	3.50-4.25	3.75	3.50
1933							1933	
3-7	2.00-2.50	1.50-2.00	3.25-3.75	3.00-3.25	3.50-4.25	3.00-3.50	2.65	2.40
9-5	2.00-2.75	1.00-2.00	3.25-3.75	2.50-3.25	3.75-4.25	3.00-3.75	3.75-4.00	3.50-3.75
1934							1934	
3-6	2.25-2.75	1.50-2.25	4.00-4.75	3.00-4.00	4.00-4.50	3.50-4.00	3.75-4.00	3.50-3.75
9-4	2.00-2.50	1.00-2.00	3.50-4.25	2.50-3.75	4.00-4.25	3.25-4.00	5.40-5.60	4.90-5.90
1935							1935	
3-5	3.50-4.00	1.75-3.25	5.50-6.50	3.75-5.25	6.25-7.25	5.00-6.25	7.00-7.25	6.25-6.50
6-7	3.25-4.50	2.00-3.50	5.25-6.25	4.50-5.50	6.00-7.50	4.75-6.00	7.25-7.50	6.50-6.75
9-6	2.75-4.25	2.00-2.75	5.50-6.50	4.50-5.50	5.50-6.25	4.00-5.25	9.25-9.75	8.75-9.25
12-6	3.25-4.50	2.50-3.25	5.00-5.75	4.00-5.25	5.75-6.75	4.75-6.00	7.75-8.00	7.25-7.50
1936							1936	
3-6	4.00-5.00	3.25-4.00	5.75-6.50	4.50-5.75	6.00-7.00	5.00-6.00	7.50-7.75	7.00-7.25
6-5	4.25-5.00	3.50-4.25	5.25-6.00	4.50-5.25	6.25-7.00	5.75-6.50	8.00-8.50	7.50-8.00
9-4	3.75-4.50	3.00-3.75	5.00-6.00	4.25-5.00	5.50-6.00	4.50-5.50	9.00-9.50	8.50-9.00
12-4	3.50-4.00	2.75-3.50	5.00-6.00	4.25-5.25	5.25-6.00	4.50-5.25	8.60-8.90	8.10-8.40
1937							1937	
3-12	4.00-4.50	3.25-4.00	5.25-5.75	4.00-5.25	6.00-7.25	5.00-6.50	8.00-8.40	7.60-7.90
6-4	4.50-5.00	3.50-4.25	5.75-6.50	4.75-5.50	7.00-8.00	5.50-6.75	9.50-10	9.00-9.50
9-7	4.00-5.25	3.00-4.00	5.50-6.00	4.50-5.25	6.00-7.25	5.00-6.25	8.75-9.00	8.25-8.50
12-7	4.00-4.50	3.00-4.00	5.00-5.50	4.00-5.25	6.00-7.00	5.00-6.00	6.25-6.65	6.00-6.40
1938							1938	
3-4	4.25-5.00	3.25-4.25	5.25-6.50	4.50-5.50	6.25-7.00	5.50-6.50	6.75-7.75	6.25-7.25
6-7	4.50-5.25	3.50-4.25	5.50-7.00	4.50-5.50	6.50-7.50	5.50-6.50	7.70	7.20
9-6	4.00-5.00	3.00-4.00	5.00-6.00	4.50-5.25	6.25-7.00	5.50-6.50	7.00	6.50
12-3	4.00-4.50	3.00-4.00	5.50-6.75	4.50-5.50	6.50-7.50	5.50-6.50	6.00	5.50
1939							1939	
3-4	4.75-5.50	3.75-4.75	6.50-7.50	5.00-6.50	7.00-8.00	6.00-7.00	6.85	6.30
6-3	5.00-5.75	4.00-5.00	6.00-7.50	5.00-6.00	6.50-8.00	5.50-6.50	6.00	5.50
9-2	4.50-5.25	4.00-4.75	5.75-7.25	4.75-5.75	6.50-7.50	5.50-6.50	5.90	5.40
12-2	4.50-5.25	3.75-4.50	6.00-7.25	5.00-6.00	7.00-7.75	6.00-7.00	4.90	4.65
1940							1940	
3-2	5.00-5.75	4.00-5.00	6.25-7.25	5.25-6.25	7.00-8.00	6.00-7.00	5.00	4.75
6-1	4.75-5.25	3.75-4.75	6.50-7.50	5.50-6.50	7.00-8.25	6.00-7.00	5.25	5.00
9-7	4.25-5.00	3.75-4.50	6.00-7.00	5.00-6.00	6.75-7.75	5.50-6.75	6.75	6.50
12-7	4.25-5.00	4.00-4.50	6.00-7.00	5.00-6.00	7.00-8.25	6.00-7.00	5.65	5.40
1941							1941	
3-1	5.25-6.00	4.50-5.25	6.25-7.50	5.25-6.50	7.50-8.75	6.50-7.50	6.50	6.00
6-7	5.25-6.25	4.25-5.25	6.75-7.75	5.50-6.50	7.75-8.50	6.75-7.75	8.90	8.40
9-6	5.50-6.75	4.50-5.50	7.50-8.75	6.50-7.50	8.00-9.00	7.00-8.00	10.25	9.75
12-5	5.50-6.50	4.25-5.50	7.00-8.00	6.00-7.00	7.50-8.50	6.50-7.50	8.25	7.75
1942							1942	
3-6	7.50-8.25	5.75-7.25	8.20-10	6.75-8.00	9-10.50	8.00-9.00	11.25	10.75
6-6	7.00-8.50	6.00-7.00	9.00-11	7.00-9.00	10-11.50	8.75-10	12-13.00	11.5-12.5
9-4	7.50-8.50	6.25-7.50	10-11.00	8.00-10	9.75-11¼	8.00-10	12.75-13¼	12¼-12.75
12-4	7.50-8.50	6.00-7.25	10.00-11¼	8.00-10	9.25-11	8.00-9.25	11.50-12	11-11.50
1943							1943	
3-5	9.00-11	7.50-8.75	11.00-13	9.00-11	11-13.50	9.00-11	13.75-14¼	13½-13.75
6-4	9-10.50	7.00-8.75	11.00-13¼	9.50-11	11-13.50	9½-11.25	13¼-13.75	12.75-13¼
Sept	9.00-10.5	8.00-9.00	12-13.50	12.00-13	13.00	12.00-13	13.50-14¼	12.75-13.5
Dec.	8.50-10	7.25-8.50	12-12.50	11-11.50	12-15.30	9.50-12	11¼-12.50	10.5-11.75

JACKSONVILLE LIVESTOCK MARKET (Cont'd.)
(Substantially Southeastern Prices)

	COWS		CALVES		STEERS		HOGS	
	Medium	Common	Good	Medium	Good	Medium	No. 1	No. 2
	100 lbs.		100 lbs.		100 lbs.		100 lbs.	
1944								
Jan.	9.00-10	7.50-8.50	12-12.50	11-12.00	12.50-14	10-12.00	11-12.10	10½-11.35
Feb.	9.00-10.5	7.75-9.50	12-14.00	11-12.00	13-14.50	10.50-13	11-13.00	10¾-12.25
Mch	9.75-11	9-10.00	12-14.00	11-12.00	13.25-15	11.5-13.5	12-13.25	11½-12.50
Apr.	9.50-10.5	8.00-9.50	14-15.00	11-13.00	14-15.00	11.5-13.5	12.25-13	11.5-12¾
June	9.25-10.5	8.00-9.00	13-14.00	11-12.00	13.5-15	10-13.50	12-13.00	11.25-12¾
July	9.25-10.5	7.25-9.25	13-14.50	10-12.00	13.5-14.5	10-13.00	12½-13.50	11.5-12.75
Aug.	8.75-10	7.50-8.50	12-14.50	10-12.00	13-14.50	10-12.50	13-14.35	11.75-14
Sept	8.25-10	6.75-8.30	12-14.00	9.50-11½	12½-14½	9.50-12¼	13-14.25	12-14.00
Oct	8.25-9.60	6.50-8.10	12-14.00	9-11.75	12.50-14	9.25-12¾	13½-14¼	12-13.25
Nov	8.10-9.50	6.25-8.00	12-13.50	9-11.75	12.25-14	9.00-12¾	13-13.75	12-13.75
Dec	8.60-10	7.25-8.50	12.50-14	9.75-12	12.50-14½	9.75-13	12-13.25	11½-13¼
1945								
Jan.	9.25-10½	8.00-9.50	12.75-14½	10.50-13	13.50-15	11.00-13	12-14.35	11¼-13.75
Feb	9.50-10½	9.00-9.50	14-15.50	11.50-14	14-15.25	11.50-14	13.85-14.35	13-14.35
Mch	9.75-11	9.25-9.75	14.00-15	12.00-14	14-15.50	12.00-14	14¼-14.35	13.75-14.35
Apr.	10-11.50	9.25-10	14-15.50	12.00-14	14.25-15½	12.00-14	14¼-14.35	14¼-14.35
May	9.75-11½	9.00-10	13.50-14	11.50-13½	14.50-16	12.50-14½	14¼-14.35	14¼-14.35
June	9.50-11	9.00-9.50	13.50-15	11.00-13	14-15.50	12-14.50	14¼-14.35	14¼-14.35
July	10-11.50	9.25-10	13.50-15	11.00-13	14-15.50	11.50-14	14¼-14.35	14¼-14.35
Aug.	9.50-11½	8.50-9.50	13-14.50	9.50-13	14-15.50	11.25-13	14¼-14.35	14¼-14.35
Sept	9.50-11	8.00-9.00	12.00-15	9.50-12¼	13½-15½	11.00-13	14¼-14.35	14¼-14.35
Oct	9.50-11	8.00-9.25	12.50-14	11.00-13	13½-14½	11.50-13	14-14.35	14-14.35
Nov.	9.50-11½	8.50-9.50	12.50-14	11½-13½	13.50-15	11-13.50	14-14.35	14-14.35
Dec.	9.50-11½	8.50-9.50	13.00-14	11.00-13	13.00-15	11.00-13	13.75-14.35	13.75-14.35
1946								
Jan.	10.00-13	8.50-10	13½-14½	11.00-14	14½-16½	12.00-14	14-14.35	13.75-14.35
Feb.	11-13.50	9.50-10½	14-15.50	11.50-14½	14.50-17	12.50-15	14¼-14.35	13.75-14.35
Mch	11.00-14	10.00-11	14.00-16	12.50-15	14.50-17	12.50-16	14.35only	14.35only
Apr.	11.50-14	10-11.50	14.50-16½	13.50-16	14.50-17	12.50-16	14.35only	14.35only
May	11.50-13½	10.50-11½	14.50-16½	12-15.50	15.00-17	13.00-16	14.35only	14.35only
June	12.00-14	10-12.50	14.50-17	12.00-16	16.00-18	12.50-16	14.35only	14.35only
July	11.50-16	11.50-14½	14.00-18	12-16.50	17.00-19	13.00-17	15.50-19	15.50-19
Aug.	11.50-16	9.10-12¾	13.25-15½	11.00-16	14.50-18½	12-17.10	14.35-22	14.35-22
Sept	10.20-14	8.50-11½	13-16.50	11-14.50	14-18.25	11-16.50	15.60only	15.10-15.6
Oct*	11.1-15.6	8.40-14.4	13-16.90	11½-16½	14.50-18	12-18.00	15.60-26	15.60-26
Nov	10.50-14	8.90-12.	13.50-18	12.00-17	15.00-19	11½-16½	22-24.50	21-24¼
Dec	11.35-14½	9-13.25	14.50-17	13.00-16	15½-22.10	11½-16½	18½-22½	18-22¼
1947								
Jan	13-15.10	10.00-13	15.50-20	14.00-13	16-24.85	13.00-19	18-22.25	17-21.75
Feb	12½-15.10	10.00-13	16.50-21	13-18.50	15.75-22½	13.50-18	21½-25¼	20½-24¼
Mch	13½-15.40	11.45-13½	16.50-22½	14-18.90	18.00-23	14.60-20½	22½-26¼	22.00-26
Apr	14-16.50	12.40-14	17-23.75	15-19.50	18.00-23	15-21.50	17.50-23	17.00-23
May	14-16.50	11.50-14	18-22.50	15.00-19	18.50-22	15.50-20	19½-23.10	18½-22½
June	14.10-17	11.00-14	18.70-22½	14.00-19	19.00-23	16.00-20	22½-24½	21½-23½
July	14.00-16	10.00-14	19-22.50	14.00-19	19-23.50	15.00-20	23-25.50	21.50-25

Note: Where figure shows, for example, 10.5 it means that the animal sold for 10.5¢ per pound or $10.50 per hundred lbs. * Ceilings went off about Oct. 15, 1946.
Information furnished through cooperation of Production & Marketing Administration, 402 Upchurch Bldg., Thomasville, Ga.

SUPPORT PRICES FOR HOGS, Basic Data Compiled by P.M.A., Market News, Thomasville, Ga. "Support prices effective from Oct. 1, 1947 to March 31, 1948 will be based on parity prices figured as of September 15th.

"On April 16, 1947, support prices of hogs from April 15 thru September 1947 are based on 90% of parity as figured in March, while the support prices for October 1, 1947, to March 31, 1948, will be based on parity prices figured as of September 15, 1947. Parity prices are usually announced around the 29th of month. The new price level represents an annual support level of $15.60 per hundred, basis Chicago for hard hogs."

The Southeastern area soft hogs have been running about $2.15 a hundred under Chicago hard hogs and about $1.50 a hundred under Southeastern hard hogs. The actual differentials in price in the Southeast obtained by producers vary with seasonal marketing, due to supply and demand, basis Chicago, while support prices are based on parity prices.

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS
(For Selected Years)

Commodity	1920 Unit	1920 Production	1920 Farm Value	1922 Unit	1922 Production	1922 Farm Value
Corn	Bu.	8,668,000	$ 9,795,000	Bu.	6,888,000	$ 7,110,000
Cotton	Bale	20,000	1,782,000	Bale	28,000	2,902,000
Tobacco	Lbs.	4,200,000	2,041,000	Lbs.	3,330,000	1,551,000
Peanuts (Picked & Threshed)	Lbs.	40,000,000	2,520,000	Lbs.	26,875,000	1,344,000
Sweet Potatoes	Bu.	2,300,000	3,174,000	Bu.	1,680,000	2,184,000
Cow Peas	Bu.	Included in Other Field Crops				
Oats	Bu.	255,000	230,000	Bu.	180,000	137,000
Velvet Beans	Tons	Included in Other Field Crops				
Hay	Tons	83,000	1,768,000	Tons	64,000	1,254,000
Sugar Cane Syrup	Gals	3,675,000	3,454,000	Gals	2,320,000	1,067,000
Sugar-Raw	Tons	No Record		Tons	No Record	
Black Strap Molasses	Gals	No Record		Gals	No Record	
Pecans	Lbs.	440,000	141,000	Lbs	880,000	309,000
Total Incomplete			$24,905,000			$17,858,000
Other Field Crops	Misc.		*2,000,000	Misc.		*1,400,000

Commodity	1924 Unit	1924 Production	1924 Farm Value	1925 Unit	1925 Production	1925 Farm Value
Corn	Bu.	7,200,000	$ 7,848,000	Bu.	8,262,000	$ 7,684,000
Cotton	Bale	21,000	2,451,000	Bale	43,000	4,561,000
Tobacco	Lbs.	4,901,000	1,916,000	Lbs.	5,810,000	1,743,000
Peanuts (Picked & Threshed)	Lbs.	28,350,000	1,474,000	Lbs.	23,400,000	1,147,000
Sweet Potatoes	Bu.	1,764,000	2,699,000	Bu.	1,840,000	3,386,000
Cow Peas	Bu.	54,000	170,000	Bu.	36,000	129,000
Oats	Bu.	148,000	138,000	Bu.	125,000	85,000
Velvet Beans	Tons	59,000	844,000	Tons	53,000	753,000
Hay	Tons	58,000	1,119,000	Tons	51,000	1,061,000
Sugar Cane Syrup	Gals	1,350,000	1,350,000	Gals	1,650,000	1,732,000
Sugar-Raw	Tons	No Record		Tons	No Record	Very Light
Black Strap Molasses	Gals	No Record		Gals	No Record	Very Light
Pecans	Lbs.	1,300,000	449,000	Lbs.	1,916,000	609,000
Total Incomplete			$20,458,000			$22,890,000
Other Field Crops	Misc.		*1,500,000	Misc.		*1,500,000

Commodity	1928 Unit	1928 Production	1928 Farm Value	1930 Unit	1930 Production	1930 Farm Value
Corn	Bu.	7,073,000	$ 7,427,000	Bu.	5,886,000	$ 5,180,000
Cotton	Bale	22,000	1,091,000	Bale	56,000	2,720,000
Tobacco	Lbs.	8,635,000	2,539,000	Lbs.	9,748,000	2,672,000
Peanuts (Picked & Threshed)	Lbs.	28,175,000	1,352,000	Lbs.	26,520,000	902,000
Sweet Potatoes	Bu.	1,700,000	2,465,000	Bu.	1,360,000	1,646,000
Cow Peas	Bu.	48,000	162,000	Bu.	86,000	233,000
Oats	Bu.	135,000	92,000	Bu.	112,000	87,000
Velvet Beans	Tons	68,000	877,000	Tons	44,000	572,000
Hay	Tons	54,000	1,048,000	Tons	48,000	830,000
Sugar Cane Syrup	Gals	1,485,000	1,262,000	Gals	1,530,000	994,000
Sugar-Raw	Tons	1,000	No Record	Tons	27,000	No Record
Black Strap Molasses	Gals	134,000	No Record	Gals	2,202,000	No Record
Pecans	Lbs.	2,000,000	545,000	Lbs.	1,150,000	302,000
Total Incomplete			$19,670,000			$16,138,000
Other Field Crops	Misc.		*2,500,000	Misc.		*2,000,000

Commodity	1932 Unit	1932 Production	1932 Farm Value	1935 Unit	1935 Production	1935 Farm Value
Corn	Bu.	6,350,000	$ 2,921,000	Bu.	7,496,000	$ 5,322,000
Cotton	Bale	18,000	556,000	Bale	31,000	1,576,000
Tobacco	Lbs.	3,310,000	836,000	Lbs.	8,680,000	2,398,000
Peanuts (Picked & Threshed)	Lbs.	24,070,000	1,361,000	Lbs.	38,430,000	1,114,000
Sweet Potatoes	Bu.	1,560,000	1,232,000	Bu.	1,610,000	1,368,000
Cow Peas	Bu.	94,000	99,000	Bu.	88,000	154,000
Oats	Bu.	75,000	28,000	Bu.	112,000	77,000
Velvet Beans	Tons	60,000	255,000	Tons	70,000	700,000
Hay	Tons	41,000	369,000	Tons	52,000	582,000
Sugar Cane Syrup	Gals	1,760,000	634,000	Gals	2,660,000	984,000
Sugar-Raw	Tons	37,000	**1,295,000	Tons	42,000	**1,470,000
Black Strap Molasses	Gals	3,489,000	248,900	Gals	3,292,000	395,040
Pecans	Lbs.	625,000	80,000	Lbs.	1,400,000	153,000
Total Incomplete			$9,914,900			$16,293,040
Other Field Crops	Misc.		*1,500,000	Misc.		*2,000,000

* Estimated by Marketing Bureau
**Estimate from unofficial sources.

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS (Cont'd.)
(For Selected Years)

Commodity	1938			1940		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,760,000	$ 4,656,000	Bu.	8,418,000	$ 5,893,000
Cotton	Bale	26,000	1,158,000	Bale	21,000	1,102,000
Tobacco	Lbs.	19,720,000	5,325,000	Lbs.	16,328,000	4,552,000
Peanuts(Picked & Threshed)	Lbs.	56,250,000	1,688,000	Lbs.	68,400,000	1,915,000
Sweet Potatoes	Bu.	1,400,000	1,274,000	Bu.	900,000	810,000
Cow Peas	Bu.	48,000	75,000	Bu.	40,000	67,000
Oats	Bu.	140,000	69,000	Bu.	154,000	102,000
Velvet Beans	Tons	57,000	661,000	Tons	59,000	649,000
Hay	Tons	70,000	763,000	Tons	70,000	665,000
Sugar Cane Syrup	Gals.	1,815,000	817,000	Gals.	1,120,000	560,000
Sugar-Raw	Tons	**(920,000)	**(3,680,000)	Tons	**(970,000)	**(4,268,000)
Black Strap Molasses	Gals.	5,497,000	** (657,000)	Gals.	5,170,000	**(1,125,000)
Pecans	Lbs.	3,575,000	309,000	Lbs.	3,564,000	341,000
Total Incomplete			$21,132,000			$22,049,000
Other Field Crops	Misc.		* 2,500,000	Misc.		* 3,000,000

Commodity	1941			1942		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,200,000	$ 5,904,000	Bu.	7,766,000	$ 8,154,000
Cotton	Bale	13,000	1,461,000	Bale	17,000	1,534,000
Tobacco	Lbs.	11,711,000	4,052,000	Lbs.	14,778,000	6,808,000
Peanuts(Picked & Threshed)	Lbs.	57,800,000	2,312,000	Lbs.	65,550,000	3,343,000
Sweet Potatoes	Bu.	1,260,000	1,399,000	Bu.	1,122,000	1,560,000
Cow Peas	Bu.	45,000	102,000	Bu.	45,000	122,000
Oats	Bu.	160,000	107,000	Bu.	210,000	176,000
Velvet Beans	Tons	65,000	845,000	Tons	53,000	742,000
Hay	Tons	64,000	813,000	Tons	72,000	979,000
Sugar Cane Syrup	Gals.	1,750,000	962,000	Gals.	1,980,000	1,287,000
Sugar-Raw	Tons	949,000	3,768,000	Tons	949,000	3,072,000
Black Strap Molasses	Gals.	5,157,000	** (928,000)	Gals.	4,100,000	** (750,000)
Pecans	Lbs.	4,672,000	474,000	Lbs.	4,600,000	752,000
Total Incomplete			$23,127,000			$29,279,000
Other Field Crops	Misc.		* 3,000,000			* 3,500,000

Commodity	1943			1944		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	8,522,000	$13,124,000	Bu.	7,550,000	$12,231,000
Cotton	Bale	16,000	1,678,000	Bale	13,000	1,343,000
Tobacco	Lbs.	14,240,000	9,203,000	Lbs.	20,095,000	10,421,000
Peanuts(Picked & Threshed)	Lbs.	74,800,000	5,236,000	Lbs.	62,500,000	4,688,000
Sweet Potatoes	Bu.	1,365,000	3,044,000	Bu.	1,156,000	2,821,000
Cow Peas	Bu.	36,000	141,000	Bu.	32,000	153,000
Oats	Bu.	300,000	342,000	Bu.	704,000	887,000
Velvet Beans	Tons	62,000	1,240,000	Tons	48,000	1,152,000
Hay	Tons	66,000	1,063,000	Tons	65,000	1,079,000
Sugar Cane Syrup	Gals.	2,040,000	2,040,000	Gals.	2,400,000	2,280,000
Sugar -Raw	Tons	694,000	3,040,000	Tons	780,000	3,487,000
Black Strap Molasses	Gals.	4,100,000	** (750,000)	Gals.	5,400,000	**(1,000,000)
Pecans	Lbs.	4,524,000	1,060,000	Lbs.	5,100,000	1,143,000
Total Incomplete			$41,961,000			$42,685,000
Other Field Crops	Misc.		* 4,500,000			* 5,000,000

Commodity	1945			1946		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,755,000	$13,339,000	Bu.	6,910,000	$12,991,000
Cotton	Bale	8,000	896,000	Bale	6,000	982,000
Tobacco	Lbs.	20,082,000	10,923,000	Lbs.	22,251,000	15,739,000
Peanuts(Picked & Threshed)	Lbs.	66,000,000	5,280,000	Lbs.	45,600,000	3,785,000
Sweet Potatoes	Bu.	1,024,000	2,652,000	Bu.	1,088,000	2,992,000
Cow Peas	Bu.	36,000	174,000	Bu.	40,000	224,000
Oats	Bu.	900,000	963,000	Bu.	720,000	986,000
Velvet Beans	Tons	56,000	1,568,000	Tons	44,000	1,408,000
Hay	Tons	63,000	1,147,000	Tons	53,000	943,000
Sugar Cane Syrup	Gals.	2,090,000	2,090,000	Gals.	1,980,000	3,168,000
Sugar-Raw	Tons	1,042,000	6,387,000	Tons	1,025,000	7,534,000
Black Strap Molasses	Gals.	5,700,000	**(1,200,000)	Gals.	6,000,000	**(1,200,000)
Pecans	Lbs.	6,300,000	1,010,000	Lbs.	4,526,000	1,507,000
Total Incomplete			$47,629,000			$53,459,000
Other Field Crops	Misc.		* 5,200,000			* 5,500,000

* Estimated by the State Marketing Bureau

** Figures in parenthesis( ) are estimates from unofficial sources. Except as otherwise noted, the production and farm value figures are supplied by the U.S. Agricultural Statisticians, Federal Building, Orlando, Florida.

CONSUMPTION OF IMPORTANT FOODS IN THE UNITED STATES

(Per Capita Civilian Consumption)

The consumption of food statistics may appear very dull reading except for those who really desire to study and have need for them. These data are assembled from various sources but mostly from the U.S. Department of Agriculture Statistical Year Books.

It may be noted that the per capita consumption of red meat has changed very little since 1910.

The increase in chicken meat has been about 25%, while turkey meat consumed shows a marked increase, and may increase even more. Consumption of eggs has increase about 30%.

Margarine has not shown any marked increase and probably would have decrease except that butter supplies were short in 1945.

Lard shows little change, but other edible fats showed about 1/3 increase in 1940 prior to the war in 1941.

Years	Beef and Veal	Pork except Lard	Lamb and Mutton	Total Meats	Chickens Dressed	Turkeys Dressed	Eggs	Margarine	Butter	Lard for Food
	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	No.	Lbs.	Lbs.	Lbs.
1910	77.6	62.3	6.5	146.4	20.6	*	306	*	*	*
1920	67.1	63.6	5.4	136.1	18.3	*	299	2.9	14.8	12.0
1925	68.0	66.8	5.2	140.0	19.8	1.7	318	1.7	18.0	12.2
1930	55.1	66.6	6.6	128.3	21.5	1.8	329	2.2	17.2	12.6
1935	61.0	69.6	6.8	115.9	18.1	2.1	278	2.4	17.1	9.5
1940	62.0	72.4	6.6	141.0	18.0	3.6	316	1.9	16.9	14.7
1945	70.3	60.2	7.2	137.7	25.3	4.3	392	3.3	10.9	12.0

Condensed and evaporated milk, cheese and ice cream show about a 50% increase. The per capita consumption of grains and cereals shows a marked decrease. Sugar consumption showed a considerable increase from 1910 to 1940.

Years	All Edible Fats & Oils	Fluid Milk and Cream	Canned & Evaporated Milk & Cream	Cheese	Ice Cream	Total Milk for Human Consumption	Wheat and Products	Corn and Products	Other(1) Cereals	Cane and Beet Sugar Refined
	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.
1910	38.5	320	*	3.85	*	*	214.9	71.8	16.5	75.4
1920	39.1	***	12.3	3.50	*	*	186.5	48.6	19.0	85.6
1925	46.4	353.5	11.7	4.6	9.4	801.6	176.9	45.0	17.1	104.2
1930	47.7	350.9	13.5	4.6	9.1	814.8	172.4	46.7	19.6	109.1
1935	46.4	335.4	16.1	5.2	7.3	799.0	153.8	36.7	13.8	96.4
1940	50.0	343.1	19.2	6.0	11.3	820.0	150.2	38.2	12.6	95.2
1945	42.2	438.0	18.3	5.9	13.8	799.0	164.2	39.2	10.9	73.2

Per capita consumption shows a decided decrease for potatoes and a down-tren for sweet potatoes, while dried beans show a moderate increase.

Apples are losing in popularity, but the figures for 1910 and 1935 are not comparable, as commercial production only was considered after 1933.

Citrus fruits per capita show a remarkable increase, being more than 3½ times what it was in 1910.

Years	Potatoes	Sweet Pots.	Dried Beans	(2) Apples	Citrus Fresh	Total Fresh Fruits	All Melons	Tomatoes Fresh	Leafy Vegs.	Total(5) Fresh Vegs.
	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.	Lbs.
1910	197.0	29.0	6.6	59.4	17.8	137.9	*	*	*	194.0
1920	146.0	34.4	5.7	63.0	26.0	145.3	34.5	27.4	82.9	220.0
1925	153.0	18.4	7.3	46.3	28.9	136.2	32.6	25.9	71.0	202.0
1930	136.0	20.7	9.5	41.9	31.0	134.2	35.2	23.9	76.9	213.0
1935	144.0	28.6	8.4	32.4	44.3	135.9	33.8	27.8	86.6	230.0
1940	131.0	19.3	8.3	29.3	56.3	142.6	37.5	28.3	89.1	239.0
1945	129.0	20.0	8.0	23.0	65.7	144.7	37.8	32.3	105.0	268.0

Fresh fruits as a whole show only a slight increase, but canned fruits and canned fruit juices show about 5 times the volume consumed per capita in 1910 and considerable increase over 1930.

Fresh vegetables show a moderate increase. Tomatoes fresh and tomatoes canned, popular for decades show no material change. Other canned vegetables show a remarkable increase since 1910, and about a 50% increase since 1930.

The consumption of corn meal, which is included with the corn and corn products consumption figures, shows a marked decrease. Rice is just about as popular as in 1920. The same holds for dried fruits.

Years	Corn Canned Lbs.	Peas Canned Lbs.	Green Beans Canned Lbs.	Tomatoes Canned Lbs.	All Canned Vegs Lbs.	All Fruits Canned Lbs.	Fruit Juices(3) Canned Lbs.	Fruits (4) Frozen Lbs.	Dried Fruits Lbs.	Rice Milled Lbs.	Corn(6) Meal Lbs.
1910	3.2	1.4	**	4.8	14.6	3.5	**	**	3.3	*	62.8
1920	4.2	3.4	**	5.1	19.2	9.4	**	**	6.5	5.2	35.0
1925	4.8	4.1	**	7.9	28.8	11.0	**	.2	6.2	5.2	29.4
1930	4.1	4.7	1.9	6.4	29.0	12.0	.3	.5	5.3	5.7	28.0
1935	4.8	4.8	1.6	6.4	30.2	13.1	2.0	.5	4.7	5.2	24.5
1940	4.1	5.7	2.2	6.3	35.0	17.5	7.1	1.2	6.3	6.0	23.7
1945	6.3	7.4	3.4	3.2	44.5	16.6	10.0	2.4	5.9	4.7	19.0

Any person over 50 years of age who was raised in the country or in a small city can recollect the changes in eating habits since 1910. We had plenty of red meat and chicken in 1910. Butter and lard were plentiful. Lots of home made bread, biscuits, and corn meal were available at low cost. Oatmeal was the principal cereal in 1910. Sugar was a little high priced for some. The cheap American cheese made up most of the cheese consumption. A slice of cheese and some crackers made a meal for the more thrifty farmers and workers in town for the day. Potatoes were required in large quantities in the North; sweet potatoes, rice and grits in the South. A lot of hard work with long hours was done in those days and the worker needed plenty of solid, nourishing foods.

In late years few off-the-farm work over 40 hours a week, but people still eat a lot of meat but less potatoes and bread. The doctors have recommended cereals, citrus, fruit juices, etc. Many women are working in offices and eating out of cans at night, having fruit or vegetable salads for lunch. Many manual workers now eat a lighter breakfast and lighter lunch.

The per capita consumption of red meats, wheat, corn, potatoes, sweet potatoes, dried beans and lard was approximately 696.7 pounds in 1910 as compared to 509.0 pounds in 1945, while for a group of foods including milk, butter, eggs, fresh and canned fruits and juices, and vegetables, the per capita consumption was approximately 716.0 pounds in 1910 and 970.8 pounds in 1945. The total of these two groups was 1412.7 pounds in 1910 and 1480.7 pounds in 1945. This shows that we eat more volume, get less calories, but get more minerals, etc.

The physical condition of the inhabitants is considered much better in 1945 than in 1910, but this is not entirely due to a better balanced diet. Much of this improvement is due to better health and medical care, and perhaps to the lighter physical work of many.

* Not available to writer at present, probably not available at all.
** Not immediately available, probably little or no production or consumption.
*** Not immediately available.
(1) Includes rye, oats, barley, and milled rice products.
(2) Excludes non-commercial apples after 1933.
(3) Single strength or converted to single strength. Includes all citrus, apples, grapes, prunes, pineapples, and fruit nectar juices.
(4) Principally cherries, strawberries, and other berries.
(5) Except potatoes, sweet potatoes, and dried beans.
(6) Included in corn and corn products.

Frank H. Scruggs, Market News Specialist
STATE MARKETING BUREAU

FLORIDA TOBACCO

Flue Cured (Bright Leaf) Type No. 14

Year	Acreage	Production	Estimated Farm Value
1930	7,300	5,767,000 Lbs.	$ 600,000 or 10.4¢ per lb.
1931	6,000	4,350,000	287,000 " 6.6¢ " "
1932	2,000	1,200,000	132,000 " 11¢ " "
1933	5,000	3,700,000	444,000 " 12¢ " "
1934	4,700	3,408,000	682,000 " 20¢ " "
1935	7,000	6,020,000	1,066,000 " 17.8¢ " "
1936	8,000	7,200,000	1,584,000 " 22¢ " "
1937	16,800	14,112,000	2,978,000 " 21.1¢ " "
1938	16,300	15,892,000	3,226,000 " 20.3¢ " "
1939	29,500	20,650,000	2,540,000 " 12.3¢ " "
1940	12,700	11,748,000	2,056,000 " 17.5¢ " "
1941	11,300	8,192,000	1,745,000 " 21.3¢ " "
1942	13,000	11,180,000	3,611,000 " 32.3¢ " "
1943	13,600	11,832,000	4,827,000 " 40.8¢ " "
1944	19,000	17,100,000	6,190,000 " 36.2¢ " "
1945	19,400	17,169,000	6,662,000 " 38.8¢ " "
1946	20,400	19,176,000	9,147,000 " 47.7¢ " "
1947	22,000	21,560,000	8,387,000 " 38.9¢ " "

Sun Cured (Filler 1931-1939 Binder, 1936-47)Dark Leaf
(Types 45 and 56)

Year Summer	Acreage	Type	Production	Estimated Farm Value	Per Pound
1931	700	F	623,000	$ 93,000	14.9¢
1932	200	F	140,000	14,000	10¢
1933	100	F	82,000	9,000	11¢
1934	300	F	360,000	43,000	11.9¢
1935	700	F	770,000	104,000	13.5¢
1936	400	F & B	380,000	51,000	13.4¢
1937	700	F & B	784,000	106,000	13.5¢
1938	900	F & B	1,116,000	151,000	13.5¢
1939	1,000	F & B	960,000	127,000	13.2¢
1940	1,000	B	1,300,000	174,000	13.4¢
1941	600	B	450,000	65,000	14.4¢
1942	600	B	630,000	110,000	17.5¢
1943	200	B	166,000	37,000	22¢
1944	100	B	70,000	19,000	27.0¢
1945	100	B	93,000	31,000	33.0¢
1946	100	B	105,000	58,000	55.0
1947	100	B	110,000	-	-

NOTE: F: Filler (Type 45) discontinued after 1939. B: Binder (Type 56) started in 1936 and continued to date.

Shade Grown-Air Cured (Dark Leaf) Wrapper Type 62

Year	Acreage	Production	Estimated Farm Value
1931	2,400	2,616,000 Lbs.	$ 785,000 or 30¢ per lb.
1932	2,000	1,970,000	690,000 " 35¢ " "
1933	1,100	990,000	317,000 " 32¢ " "
1934	1,600	1,424,000	854,000 " 59.9¢ per lb.
1935	2,100	1,890,000	1,228,000 " 65¢ per lb.
1936	2,000	2,050,000	1,414,000 " 69¢ " "
1937	2,100	1,890,000	1,304,000 " 70¢ " "
1938	2,400	2,712,000	1,953,000 " 72¢ " "
1939	2,500	2,150,000	1,570,000 " 73¢ " "
1940	3,200	3,280,000	2,296,000 " 70¢ " "
1941	3,300	3,069,000	2,240,000 " 73¢ " "
1942	2,800	2,968,000	2,879,000 " $1.04" "
1943	2,600	2,912,000	3,087,000 " 1.49" "
1944	2,600	2,925,000	4,212,000 " 1.44" "
1945	2,400	2,820,000	4,230,000 " 1.50" "
1946	3,000	2,970,000	6,534,000 " 2.20" "
1947	3,200	3,520,000	- -

Florida Auction Sales Flue Cured Type No. 14

Original Sales	Volume	Total Value
1939	14,799,094 lbs.	$1,804,969 or 12.20¢ per lb.
1940	8,391,086	1,487,537 " 17.73¢ " "
1941	6,015.352	1,305,148 " 21.41¢ " "
1942	8,228,284	2,669,449 " 32.45¢ " "
1943	9,246,183	3,777,990 " 40.86¢ " "
1944	12,393,680	4,487,980 " 36.21¢ " "
1945	12,148,104	4,742,528 " 39.03¢ " "
1946	14,768,370	7,051,896 " 47.75¢ " "
1947	18,648,643	7,259,917 38.93¢ " "

Type 14 not sold in Florida Auctions presumably went to out-of-State Auctions.

THE PRODUCTION OF FLORIDA FRUITS AND VEGETABLES AS AFFECTED BY WEATHER CONDITIONS - 1946-47 SEASON

By G. N. Rose, Associate Agricultural Economist

Old man weather gathered together his most unfavorable items, bound them in a neat package and threw the book at Florida during the 1946-47 season. Beginning in the Fall with heavy rains, followed by abnormally high temperatures in the late Fall and early Winter with a reversal into a February freeze, the elements took a heavy toll of fruits and vegetables. A cool, wet Spring and Summer revived the freeze battered citrus acreage, but the 1946-47 season ended and the 1947-48 started with a hurricane September 17, accompanied by heavy rains, laying waste Fall vegetable plantings and causing some loss to citrus, mainly grapefruit. At this time (October 6, 1947) much land is still under water, dimming the prospects for Fall vegetable production.

FRUIT - Florida started the 1946-47 season with prospects for a record citrus production of over a hundred million box crop. Warm weather during October, November, and December resulted in a deterioration of quality to the extent that prices were demoralized and considerable quantities of fruit hit the ground. The February freeze took an additional toll of eleven or twelve million boxes and when the season had ended, about 83.1 million boxes had been utilized and over 4 million boxes lost through low prices.

VEGETABLES - Florida farmers planted approximately 350,000 acres of vegetables during the 1946-47 season and were able to bring through about 280,000 acres for harvest, or about 80% of the planted acreage. However, acreage re-planted to the same crop within either the Fall, Winter or Spring season is not counted in the above planted acreage. Production from the harvested acreages amounted to approximately 60,000 cars and car equivalents.

The first chapter from the book huffed and puffed its way across the State October 7 and 8, 1946, and vegetables unhurt by the blow had a wet blanket draped very ungracefully over them by the rains which followed. The next chapter was a hot one! In fact it stayed too hot for favorable production, especially for leaf crops, until the assassin killed its innocent victims February 6 and 7. Tender crops in all Florida areas were hard hit by the heavy frost and cold. Snap beans occupied the largest acreage, followed by tomatoes, potatoes, peppers, peas, lima beans, cucumbers, eggplant and squash. The various leaf crops were damaged but to a lesser degree. Continued cold and rain came intermittently throughout February and March, 1947. Crops were either abandoned or planted again and again. The enevitable result was a seriously reduced production and delayed harvest.

There was one comforting factor: Farmers able to bring even a part of a crop through were amply rewarded, in most cases, with fancy prices. END.

- - - - - - -

NOTE: For Truck Crop News released monthly or oftener, write to Mr. G. N. Rose, U.S. Bureau of Agricultural Economics, Federal Building, Orlando, Florida.

- - - - - - -

The above brief review of the effects of weather on Florida production seems gloomy and is gloomy, but it is not the first year that Florida has been hit hard by the weather. In fact we hardly would go through a season without some bad weather and crop losses.

As this report goes to press October 14, 1947, we are having as bad fall weather perhaps as we have ever had in South Florida which is principal vegetable production area in Florida. All plantings are being delayed and our November and December crops in South Florida will be light. Central and North Florida areas are better off.

In spite of bad weather in various seasons, from 1926-27 to 1945-46 seasons inclusive, Florida has shipped 1,087,237 cars of vegetables and miscellaneous fruits and the total production of fruits and vegetables was equivalent to 3,366,921 carloads with a gross fob packed value of $2,669,450,000 for the 20-year period.

- - - - - - - - - -

F. H. Scruggs

See succeeding pages for acreage, production and value.

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1944-45, 1945-46 AND 1946-47

Florida Counties	Snap Beans			Lima Beans			Cabbage		
	1944-45	1945-46	1946-47	1944-45	1945-46	1946-47	1944-45	1945-46	1946-47
Alachua	800	1,550	1,700	1,100	1,400	1,500	400	200	150
Bradford	125	150	150	100	200	125	150	100	50
Brevard	-	-	-	-	-	-	50	50	50
Broward	19,800	20,200	18,300	150	150	100	250	40	50
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	600	200	200
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	200	50	25
Dade	3,000	3,100	2,000	150	100	100	350	300	350
DeSoto	-	-	-	-	-	-	50	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	100	100
Escambia	-	230	250	-	-	-	-	100	50
Flagler	-	-	-	-	-	-	700	800	1,000
Gadsden	200	450	450	-	-	-	100	50	50
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	250	110	-	-	-	-	350	550	450
Hamilton	-	-	-	-	-	-	100	50	50
Hardee	50	40	50	-	-	-	50	50	50
Hendry	150	150	-	-	-	-	50	50	50
Hernando	150	140	100	-	-	-	-	-	-
Highlands	550	230	550	-	-	-	100	25	25
Hillsborough	250	1,200	1,850	100	250	500	450	500	750
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	50	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	50	50	-	-	-	-	-	-
Lake	350	140	100	-	-	-	300	150	150
Lafayette	-	-	-	-	-	-	-	-	-
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	100	50	-	-	-	-	100	50	50
Madison	-	-	-	-	-	-	-	-	-
Manatee	250	450	550	-	-	-	1,000	300	200
Marion	500	800	1,300	400	700	600	500	500	400
Martin	600	340	600	150	300	125	50	100	100
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	100	150	350	-	-	-	800	650	800
Osceola	-	-	-	-	-	-	100	50	-
Palm Beach	52,100	48,800	51,400	2,250	3,525	1,850	4,100	3,000	3,500
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	50	200	200	-	-	-	400	200	150
Putnam	-	240	250	-	-	-	1,500	900	1,000
Santa Rosa	-	-	-	-	-	-	-	-	-
Sarasota	-	-	-	-	-	-	250	100	100
Seminole	150	350	550	-	-	-	1,150	1,000	1,000
St. Johns	-	-	-	-	-	-	2,400	2,500	2,700
St. Lucie	100	100	-	300	200	100	50	50	-
Sumter	475	230	250	-	-	-	200	50	50
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	100	240	250	50	50	150	150	50	50
Volusia	-	-	-	-	-	-	300	200	200
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	300	510	450	50	125	50	150	135	100
Total	80,500	80,200	81,700	4,800	7,000	5,200	17,500	13,200	14,000

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1944-45, 1945-46 AND 1946-47

Florida Counties	Celery 1944-45	Celery 1945-46	Celery 1946-47	Cucumbers 1944-45	Cucumbers 1945-46	Cucumbers 1946-47	Eggplant 1944-45	Eggplant 1945-46	Eggplant 1946-47
Alachua	150	135	130	2,000	2,250	1,900	150	200	250
Bradford	-	-	-	150	200	150	-	-	-
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	400	450	650	475	425	500
Calhoun	-	-	-	500	200	175	-	-	-
Charlotte	-	-	-	-	-	50	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	150	300	325	25	25	-
Columbia	-	-	-	25	-	-	-	-	-
Dade	-	-	-	-	-	-	-	-	-
DeSoto	-	-	-	50	100	125	-	-	25
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	100	50	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	100	50	25
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	400	500	575	-	-	-
Hardee	-	-	-	825	1,200	1,400	100	250	150
Hendry	-	-	-	25	100	200	-	-	-
Hernando	-	-	-	-	-	-	100	50	-
Highlands	-	-	-	50	-	50	25	25	25
Hillsborough	-	-	-	475	800	975	350	475	350
Holmes	-	-	-	-	-	200	-	-	-
Indian River	-	-	-	-	-	75	-	-	25
Jackson	-	-	-	100	500	375	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lake	350	810	875	200	400	275	100	50	-
Lafayette	-	-	-	-	-	-	-	-	-
Lee	-	-	-	300	500	700	375	350	300
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	100	200	50	-	-	-
Madison	-	-	-	25	-	-	-	-	-
Manatee	100	100	75	100	950	725	150	500	375
Marion	200	220	190	225	300	275	125	225	200
Martin	-	-	-	25	50	100	75	225	200
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	950	1,165	695	150	400	400	25	50	-
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	4,125	5;175	4,280	350	700	1,600	700	775	575
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	50	50	200	-	-	-
Putnam	-	-	-	-	-	-	-	-	-
Santa Rosa	-	-	-	-	-	-	-	-	-
Sarasota	1,300	1,360	1,285	150	150	250	-	-	-
Seminole	3,850	4,475	4,150	-	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	100	150	400	125	50	125
Sumter	-	-	-	500	1,050	1,000	150	150	75
Suwannee	-	-	-	50	-	200	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	150	150	200	-	-	-
Volusia	-	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	25	10	20	75	200	125	100	175	100
Total	11,050	13,450	11,700	7,700	11,950	13,775	3,250	4,050	3,300

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1944-45, 1945-46 AND 1946-47

Florida Counties	Escarole 1944-45	Escarole 1945-46	Escarole 1946-47	English Peas 1944-45	English Peas 1945-46	English Peas 1946-47	Lettuce Boston & Romaine 1944-45	Lettuce Boston & Romaine 1945-46	Lettuce Boston & Romaine 1946-47
Alachua	-	-	-	200	200	150	-	-	-
Bradford	-	-	-	-	-	-	-	-	-
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	-	-	-	-	-	-
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-	-
Dade	-	-	-	-	-	-	-	-	-
DeSoto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	100	50	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	-	-	-	-	-	-	-	-	-
Hendry	-	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	100	50	-	-	-
Hillsborough	-	-	40	200	400	200	-	-	-
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lake	-	20	40	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-	-
Manatee	475	400	240	150	50	50	150	50	125
Marion	50	10	50	100	100	25	150	200	200
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	225	150	190	50	50	-	-	-	25
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	1,600	1,400	1,700	1,300	900	1,000	25	100	125
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	-	-	25	-	-	-
Putnam	-	-	-	-	-	-	-	-	-
Santa Rosa	-	-	-	-	-	-	-	-	-
Sarasota	100	20	500	-	-	-	-	-	-
Seminole	350	600	-	100	100	50	75	150	200
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	-	-	-	-	-	-
Sumter	-	-	-	-	-	-	-	-	-
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	-	-	-
Volusia	-	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	-	-	40	-	-	-	-	-	25
Total	2,800	2,600	2,800	2,600	2,000	1,600	400	500	700

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1944-45, 1945-46 AND 1946-47

Florida Counties	Lettuce Iceberg 1944-45	1945-46	1946-47	Peppers 1944-45	1945-46	1946-47	Potatoes 1944-45	1945-46	1946-47
Alachua	-	30	25	600	500	450	2,000	2,200	1,550
Bradford	-	-	-	40	50	50	100	150	100
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	3,000	3,200	2,075	-	-	-
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	100	100	50
Collier	-	-	-	-	-	-	50	-	-
Columbia	-	-	-	-	-	-	-	-	-
Dade	-	-	-	-	-	25	6,500	6,770	6,000
DeSoto	-	-	-	25	-	25	100	100	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	800	850	700
Flagler	-	-	-	-	-	-	2,000	2,250	2,100
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	300	400	225	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	-	-	-	225	450	235	100	50	-
Hendry	-	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	200	80	-
Hillsborough	175	250	325	1,850	2,675	2,600	400	650	100
Holmes	-	-	-	-	-	-	50	50	100
Indian River	-	-	-	-	-	25	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lake	-	-	25	100	150	250	50	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lee	-	-	-	375	500	400	1,200	1,360	900
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-	-
Manatee	25	150	100	150	350	350	100	50	-
Marion	50	50	25	125	125	150	-	100	50
Martin	-	-	-	135	150	225	50	240	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	25	180	25	75	350	250	300	240	150
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	325	250	275	1,500	1,900	1,625	6,300	9,200	3,250
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	200	300	525	50	50	-
Putnam	50	25	25	-	-	-	2,850	2,600	2,200
Santa Rosa	-	-	-	-	-	-	-	-	-
Sarasota	-	50	-	-	100	25	300	280	50
Seminole	25	50	50	225	275	125	150	200	-
St. Johns	-	-	-	-	-	-	6,900	7,300	6,200
St. Lucie	-	-	-	175	100	100	-	-	-
Sumter	-	-	-	500	725	800	-	-	-
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	100	150	50
Volusia	-	-	-	-	-	-	150	150	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	50	50	-
Miscellaneous	25	15	25	50	100	190	150	100	550
Total	1,000	1,450	1,125	9,350	12,000	10,550	31,100	35,300	24,100

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1944-45, 1945-46 AND 1946-47

Florida	Tomatoes			Total Vegetables			Cantaloupes		
Counties	1944-45	1945-46	1946-47	1944-45	1945-46	1946-47	1944-45	1945-46	1946-47
Alachua	75	50	25	7,475	8,715	7,830	100	150	250
Bradford	100	50	25	765	900	650	25	50	-
Brevard	200	200	50	250	250	100	-	-	-
Broward	5,000	3,250	3,450	29,075	27,715	25,125	-	-	-
Calhoun	-	-	-	500	200	175	-	-	-
Charlotte	-	-	275	-	-	325	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	700	300	250	-	-	-
Collier	1,175	1,400	1,200	1,400	1,725	1,525	-	-	-
Columbia	-	-	-	225	50	25	-	-	-
Dade	13,000	13,200	8,200	23,000	23,470	16,700	-	-	-
DeSoto	125	225	175	550	425	350	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	100	100	-	-	-
Escambia	-	-	-	800	1,130	1,000	-	-	-
Flagler	-	-	-	2,700	3,250	3,200	-	-	-
Gadsden	-	-	-	300	500	500	-	-	-
Gilchrist	-	-	-	100	50	25	-	-	-
Glades	-	-	175	900	1,060	850	-	-	-
Hamilton	-	-	-	500	550	625	75	75	50
Hardee	1,025	2,025	1,225	2,375	4,065	3,160	-	-	-
Hendry	-	-	275	225	300	525	-	-	-
Hernando	-	-	-	250	190	100	-	-	-
Highlands	-	-	25	925	460	750	-	-	-
Hillsborough	1,250	1,825	1,775	5,500	9,005	9,765	-	-	-
Holmes	-	-	-	50	50	300	-	-	-
Indian River	575	300	550	625	300	675	-	-	-
Jackson	-	-	-	-	500	375	-	75	100
Jefferson	-	-	-	-	50	50	-	-	-
Lake	325	375	125	1,775	2,095	1,860	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lee	450	700	550	2,700	3,410	2,850	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	300	300	100	100	100	50
Madison	-	-	-	25	-	-	-	-	50
Manatee	2,225	2,600	1,450	4,875	5,950	4,440	-	-	-
Marion	450	1,050	500	2,675	4,380	3,965	150	250	150
Martin	250	500	400	1,335	1,905	1,750	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	75	-	-	2,775	3,335	3,215	-	-	-
Osceola	-	-	-	100	50	-	-	-	-
Palm Beach	2,100	1,950	750	77,275	77,675	71,980	-	-	-
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	100	200	175	850	1,000	1,275	-	-	-
Putnam	-	-	-	4,400	3,765	3,475	-	-	-
Santa Rosa	-	-	-	-	-	-	-	-	-
Sarasota	100	75	-	2,200	2,135	1,740	-	-	-
Seminole	-	-	-	6,075	7,200	6,725	-	-	-
St. Johns	-	-	-	9,300	9,800	8,900	-	-	-
St. Lucie	2,500	5,750	7,450	3,350	8,400	8,175	-	-	-
Sumter	1,250	1,300	650	3,075	3,505	2,825	-	-	-
Suwannee	-	-	-	50	-	200	25	50	50
Taylor	-	-	-	-	-	-	-	-	50
Union	-	-	-	550	640	700	-	-	-
Volusia	-	-	-	450	350	200	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	50	50	-	-	-	-
Miscellaneous	150	275	325	1,075	1,645	2,020	25	50	50
Total	32,500	37,300	29,800	204,550	221,000	201,450	500	800	800

Note: * Total Vegetable Acreage includes- Carrots as follows: Dade 25, Highlands 25, Lake 20, Orange 330, Palm Beach 50, Seminole 50. Grand Total 500.
Total Vegetable Acreage includes- Cauliflower as follows: Hillsborough 300, Manatee 200, Sarasota 30, Seminole 50, Miscellaneous 20. Grand Total 600.

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1944-45, 1945-46 AND 1946-47

Florida Counties	Strawberries			Watermelons			Total Miscellaneous Fruits		
	1944-45	1945-46	1946-47	1944-45	1945-46	1946-47	1944-45	1945-46	1946-47
Alachua	-	-	-	3,000	6,800	5,000	3,100	6,950	5,250
Bradford	200	225	400	100	100	100	325	375	500
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	100	200	100	100	200	100
Calhoun	-	-	-	1,000	300	150	1,000	300	150
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	100	200	200	100	200	200
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	-	100	50	-	100	50
Columbia	-	-	-	300	350	250	300	350	250
Dade	100	150	150	-	-	-	100	150	150
DeSoto	-	-	-	-	300	100	-	300	100
Dixie	-	-	-	100	100	100	100	100	100
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-	-
Gadsden	-	-	-	50	50	-	50	50	-
Gilchirst	-	-	-	-	5,400	5,800	-	5,400	5,800
Glades	-	-	-	3,500	-	-	3,500	-	-
Hamilton	-	-	-	300	200	250	375	275	300
Hardee	200	200	400	100	100	50	300	300	450
Hendry	-	-	-	100	100	-	100	100	-
Hernando	-	-	-	50	-	-	50	-	-
Highlands	-	-	-	-	-	-	-	-	-
Hillsborough	1,100	1,700	3,000	300	400	500	1,400	2,100	3,500
Holmes	-	-	-	-	200	400	-	200	400
Indian River	-	-	-	100	100	-	100	100	-
Jackson	-	-	-	5,000	5,000	2,500	5,000	5,075	2,600
Jefferson	-	-	-	1,200	3,800	3,200	1,200	3,800	3,200
Lake	-	-	-	6,500	6,000	8,500	6,500	6,000	8,500
Lafayette	-	-	-	-	1,000	700	-	1,000	700
Lee	-	-	-	150	150	50	150	150	50
Leon	-	-	-	100	200	50	100	200	50
Levy	-	-	-	1,200	2,500	2,400	1,300	2,600	2,450
Madison	-	-	-	3,000	2,000	1,800	3,000	2,000	1,850
Manatee	25	-	-	100	150	150	125	150	150
Marion	-	-	-	3,000	3,500	4,550	3,150	3,750	4,700
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	25	-	-	100	1,200	1,100	125	1,200	1,100
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	-	-	-	100	200	200	100	200	200
Pasco	-	-	-	500	200	750	500	200	750
Pinellas	-	-	-	-	-	100	-	-	100
Polk	200	300	500	150	200	350	350	500	850
Putnam	-	-	-	100	100	300	100	100	300
Santa Rosa	-	-	-	-	-	-	-	-	-
Sarasota	-	-	-	-	-	50	-	-	50
Seminole	-	-	-	-	-	-	-	-	-
St. Johns	-	-	-	50	-	-	50	-	-
St. Lucie	-	-	-	100	100	50	100	100	50
Sumter	75	100	150	2,100	2,700	3,200	2,200	2,850	3,400
Suwannee	-	-	-	5,000	5,500	3,000	5,000	5,500	3,050
Taylor	-	-	-	50	50	100	50	50	100
Union	-	-	-	100	100	50	100	100	50
Volusia	-	-	-	50	100	50	50	100	50
Walton	-	-	-	-	250	150	-	250	150
Washington	-	-	-	1,000	800	500	1,000	800	500
Miscellaneous	125	125	150	150	200	100	300	375	300
Total	2,050	2,800	4,750	39,000	51,000	47,000	41,550	54,600	52,550

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1944-45, 1945-46 AND 1946-47

Florida Counties	Total Vegetables & Miscellaneous Fruits			Oranges			Grapefruit		
	1944-45	1945-46	1946-47	1944-45	1945-46	1946-47	1944-45	1945-46	1946-47
Alachua	10,575	15,665	13,080	-	-	-	-	-	-
Bradford	1,090	1,275	1,150	-	-	-	-	-	-
Brevard	250	250	100	11,540	11,720	11,760	3,600	3,620	3,630
Broward	29,175	27,915	25,225	2,560	2,930	3,070	270	300	300
Calhoun	1,500	500	325	-	-	-	-	-	-
Charlotte	-	-	325	-	-	-	-	-	-
Citrus	100	200	200	-	-	-	-	-	-
Clay	700	300	250	-	-	-	-	-	-
Collier	1,400	1,825	1,575	-	-	-	-	-	-
Columbia	525	400	275	-	-	-	-	-	-
Dade	23,100	23,620	16,850	2,820	2,960	3,030	3,690	3,710	3,720
DeSoto	350	725	450	6,660	6,715	6,765	1,350	1,350	1,350
Dixie	100	100	100	-	-	-	-	-	-
Duval	-	100	100	-	-	-	-	-	-
Escambia	800	1,180	1,000	-	-	-	-	-	-
Flagler	2,700	3,250	3,200	-	-	-	-	-	-
Gadsden	350	550	500	-	-	-	-	-	-
Gilchrist	360	5,450	5,825	-	-	-	-	-	-
Glades	900	1,060	850	-	-	-	-	-	-
Hamilton	875	825	925	-	-	-	-	-	-
Hardee	2,675	4,365	3,610	8,720	8,950	9,090	900	910	910
Hendry	325	400	525	-	-	-	-	-	-
Hernando	300	190	100	1,540	1,555	1,585	360	360	360
Highlands	925	460	750	8,970	9,120	9,260	4,320	4,330	4,340
Hillsborough	6,900	11,105	13,265	16,410	16,900	17,170	3,690	3,700	3,720
Holmes	50	250	700	-	-	-	-	-	-
Indian River	725	400	675	4,870	4,940	5,050	6,390	6,520	6,600
Jackson	5,100	5,575	2,975	-	-	-	-	-	-
Jefferson	1,200	3,850	3,250	-	-	-	-	-	-
Lake	8,275	8,095	10,360	24,100	25,680	26,450	6,750	6,760	6,810
Lafayette	-	1,000	700	-	-	-	-	-	-
Lee	2,850	3,560	2,900	3,330	3,365	3,405	2,880	2,880	2,890
Leon	100	200	50	-	-	-	-	-	-
Levy	1,600	2,900	2,550	-	-	-	-	-	-
Madison	3,025	2,000	1,850	-	-	-	-	-	-
Manatee	5,000	6,100	4,590	4,610	4,625	4,655	4,860	4,860	4,870
Marion	6,025	8,130	8,665	8,970	9,015	9,065	720	720	720
Martin	1,335	1,905	1,750	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	2,900	4,585	4,315	33,320	35,090	36,240	3,810	3,810	3,860
Osceola	100	50	-	4,360	4,445	4,485	900	900	900
Palm Beach	77,375	77,875	72,180	-	-	-	-	-	-
Pasco	500	200	750	6,410	6,780	7,120	1,440	1,450	1,480
Pinellas	-	-	100	7,180	7,290	7,390	7,830	7,860	7,890
Polk	1,200	1,500	2,125	55,630	57,530	58,890	26,100	26,140	26,250
Putnam	4,500	3,865	3,775	4,360	4,410	4,420	450	450	450
Santa Rosa	-	-	-	-	-	-	-	-	-
Sarasota	2,200	2,135	1,790	2,560	2,590	2,610	1,080	1,080	1,080
Seminole	6,075	7,200	6,725	6,660	6,790	6,840	720	720	720
St. Johns	9,350	9,800	8,900	-	-	-	-	-	-
St. Lucie	3,450	6,500	8,225	8,200	8,480	8,620	4,230	4,420	4,460
Sumter	5,275	6,355	6,225	-	-	-	-	-	-
Suwannee	5,050	5,500	3,250	-	-	-	-	-	-
Taylor	50	50	100	-	-	-	-	-	-
Union	650	740	750	-	-	-	-	-	-
Volusia	500	450	250	12,560	12,705	12,745	1,350	1,350	1,350
Walton	-	250	150	-	-	-	-	-	-
Washington	1,050	850	500	-	-	-	-	-	-
Miscellaneous	1,375	2,020	2,320	9,960	10,315	10,285	2,310	2,300	2,340
Total	246,100	275,600	254,000	256,300	264,900	270,000	90,000	90,500	91,000

NOTE: 1946-47 figures as of September 20 subject to revision.

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1944-45, 1945-46 AND 1946-47

Florida Counties	Tangerines 1944-45	Tangerines 1945-46	Tangerines 1946-47	Total Citrus 1944-45	Total Citrus 1945-46	Total Citrus 1946-47	Grand Total 1944-45	Grand Total 1945-46	Grand Total 1946-47
Alachua	-	-	-	-	-	-	10,575	15,665	13,080
Bradford	-	-	-	-	-	-	1,090	1,275	1,150
Brevard	468	469	470	15,608	15,809	15,860	15,858	16,059	15,960
Broward	94	96	100	2,924	3,326	3,470	32,099	31,241	28,695
Calhoun	-	-	-	-	-	-	1,500	500	325
Charlotte	-	-	-	-	-	-	-	-	325
Citrus	-	-	-	-	-	-	100	200	200
Clay	-	-	-	-	-	-	700	300	250
Collier	-	-	-	-	-	-	1,400	1,825	1,575
Columbia	-	-	-	-	-	-	525	400	275
Dade	398	403	425	6,908	7,073	7,175	30,008	30,693	24,025
DeSoto	515	515	520	8,525	8,580	8,635	8,875	9,305	9,085
Dixie	-	-	-	-	-	-	100	100	100
Duval	-	-	-	-	-	-	-	100	100
Escambia	-	-	-	-	-	-	800	1,180	1,000
Flagler	-	-	-	-	-	-	2,700	3,250	3,200
Gadsden	-	-	-	-	-	-	350	550	500
Gilchrist	-	-	-	-	-	-	3,600	5,450	5,825
Glades	-	-	-	-	-	-	900	1,060	850
Hamilton	-	-	-	-	-	-	875	825	925
Hardee	656	656	660	10,276	10,516	10,660	12,951	14,881	14,270
Hendry	-	-	-	-	-	-	325	400	525
Hernando	820	820	830	2,720	2,735	2,775	3,020	2,925	2,875
Highlands	820	820	830	14,110	14,270	14,430	15,035	14,730	15,180
Hillsborough	1,218	1,233	1,240	21,318	21,833	22,130	28,218	32,938	35,395
Holmes	-	-	-	-	-	-	50	250	700
Indian River	515	519	525	11,775	11,979	12,175	12,500	12.379	12,850
Jackson	-	-	-	-	-	-	5,100	5,575	2,975
Jefferson	-	-	-	-	-	-	1,200	3,850	3,250
Lake	1,944	1,952	1,930	32,794	34,392	35,240	41,069	42,487	45,600
Lafayette	-	-	-	-	-	-	-	1,000	700
Lee	117	119	120	6,327	6,364	6,415	9,177	9,924	9,315
Leon	-	-	-	-	-	-	100	200	50
Levy	-	-	-	-	-	-	1,600	2,900	2,550
Madison	-	-	-	-	-	-	3,025	2,000	1,850
Manatee	117	117	120	9,587	9,602	9,645	14,587	15,702	14,235
Marion	398	398	400	10,088	10,153	10,185	16,113	18,263	18,850
Martin	-	-	-	-	-	-	1,335	1,905	1,750
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	3,044	3,094	3,105	40,174	41,994	43,205	43,074	46,579	47,520
Osceola	585	585	590	5,845	5,930	5,975	5,945	5,980	5,975
Palm Beach	-	-	-	-	-	-	77,375	77,875	72,180
Pasco	585	587	590	8,435	8,817	9,190	8,935	9,017	9,940
Pinellas	656	659	660	15,666	15,309	15,940	15,666	15,809	16,040
Polk	5,457	5,471	5,500	87,187	39,141	90,640	88,387	90,641	92,765
Putnam	632	632	640	5,442	5,492	5,510	9,942	9,357	9,285
Santa Rosa	-	-	-	-	-	-	-	-	-
Sarasota	-	-	-	3,640	3,670	3,690	5,840	5,805	5,460
Seminole	820	820	825	8,200	8,330	8,385	14,275	15,530	15,110
St. Johns	-	-	-	-	-	-	9,350	9,800	8,900
St. Lucie	890	890	900	13,320	13,790	13,980	16,770	20,290	22,205
Sumter	-	-	-	-	-	-	5,275	6,355	6,225
Suwannee	-	-	-	-	-	-	5,050	5,500	3,250
Taylor	-	-	-	-	-	-	50	50	100
Union	-	-	-	-	-	-	650	740	750
Volusia	1,920	1,923	1,930	15,830	15,976	16,025	16,330	16,428	16,275
Walton	-	-	-	-	-	-	-	250	150
Washington	-	-	-	-	-	-	1,050	850	500
Miscellaneous	750	771	745	13,020	13,386	13,370	14,395	15,406	15,690
Total	23,419	23,549	23,705	367,719	378,949	384,705	615,819	654,549	638,705

NOTE: 1946-47 figures as of September 20 subject to revision.

SOURCE: U.S. Bureau of Agricultural Economics, Orlando, Florida.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS 1944-45, 1945-46, & 1946-47.

Source: U. S. Agricultural Statisticians, Orlando, Florida.

	1944-45				1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
ALACHUA												
Beans	50	-	750	800	100	-	1450	1550	200	-	1500	1700
Limas	-	-	1100	1100	-	-	1400	1400	-	-	1500	1500
Cabbage	-	-	-	400	-	200	-	200	-	150	-	150
Celery	-	-	150	150	-	-	135	135	-	-	130	130
Cucumbers	-	-	2000	2000	50	-	2200	2250	150	-	1750	1900
Eggplant	50	-	100	150	100	-	100	200	150	-	100	250
Lettuce, Ice.	-	-	-	-	-	-	30	30	-	-	25	25
Peas, English	-	200	-	200	-	200	-	200	-	150	-	150
Peppers	-	-	600	600	-	-	500	500	-	-	450	450
Potatoes	-	-	2000	2000	-	-	2200	2200	-	-	1550	1550
Tomatoes	-	-	75	75	-	-	50	50	-	-	25	25
Total Vegs.	100	200	6775	7475	250	400	8065	8715	500	300	7030	7830
Cantaloupes	-	-	-	100	-	-	150	150	-	-	250	250
Watermelons	-	-	-	3000	-	-	-	6800	-	-	5000	5000
Grand Total	100	200	6775	10575	250	400	8215	15665	500	300	12280	13080
BRADFORD												
Beans	25	-	100	125	50	-	100	150	50	-	100	150
Limas	-	-	100	100	-	-	200	200	-	-	125	125
Cabbage	-	-	-	150	-	100	-	100	-	50	-	50
Cucumbers	-	-	150	150	-	-	200	200	-	-	150	150
Peppers	-	-	40	40	-	-	50	50	-	-	50	50
Potatoes	-	-	100	100	-	-	150	150	-	-	100	100
Tomatoes	-	-	100	100	-	-	50	50	-	-	25	25
Total Vegs.	25	-	590	765	50	100	750	900	50	50	550	650
Cantaloupes	-	-	-	25	-	-	50	50	-	-	-	-
Strawberries	-	-	-	200	-	225	-	225	-	400	-	400
Watermelons	-	-	-	100	-	-	-	100	-	-	100	100
Grand Total	25	-	590	1090	50	325	800	1275	50	450	650	1150
BREVARD												
Cabbage	-	-	-	50	-	50	-	50	-	50	-	50
Tomatoes	100	-	100	200	50	-	150	200	50	-	-	50
Total Vegs.	100	-	100	250	50	50	150	250	50	50	-	100
BROWARD												
Beans	2200	17600	-	19800	3300	16900	-	20200	4500	12000	1800	18300
Limas	-	150	-	150	-	150	-	150	-	100	-	100
Cabbage	-	-	-	250	-	40	-	40	-	50	-	50
Cucumbers	200	200	-	400	350	100	-	450	300	50	300	650
Eggplant	50	225	200	475	75	200	150	425	50	250	200	500
Peppers	100	2200	700	3000	150	2100	950	3200	175	1900	-	2075
Tomatoes	200	4300	500	5000	200	2550	500	3250	500	2150	800	3450
Total Vegs.	2750	24675	1400	29075	4075	22040	1600	27715	5525	16500	3100	25125
Watermelons	-	-	-	100	-	-	-	200	-	-	100	100
Grand Total	2750	24675	1400	29175	4075	22040	1600	27915	5525	16500	3200	25225
CALHOUN												
Cucumbers	-	-	500	500	-	-	200	200	-	-	175	175
Watermelons	-	-	-	1000	-	-	-	300	-	-	150	150
Grand Total	-	-	500	1500	-	-	200	500	-	-	325	325
CHARLOTTE												
Cucumbers	-	-	-	-	-	-	-	-	50	-	-	50
Tomatoes	-	-	-	-	-	-	-	-	150	-	125	275
Total Vegs.	-	-	-	-	-	-	-	-	200	-	125	325
CITRUS												
Watermelons	-	-	-	100	-	-	-	200	-	-	200	200
CLAY												
Cabbage	-	-	-	600	-	200	-	200	-	200	-	200
Potatoes	-	-	100	100	-	-	100	100	-	-	50	50
Total Vegs.	-	-	100	700	-	200	100	300	-	200	50	250

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1944-45				1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
COLLIER												
Cucumbers	50	-	100	150	100	150	50	300	200	-	125	325
Eggplant	25	-	-	25	25	-	-	25	-	-	-	-
Potatoes	-	50	-	50	-	-	-	-	-	-	-	-
Tomatoes	275	300	600	1175	200	600	600	1400	250	700	250	1200
Total Vegs.	350	350	700	1400	325	750	650	1725	450	700	375	1525
Watermelons	-	-	-	-	-	-	-	100	-	-	50	50
Grand Total	350	350	700	1400	325	750	650	1825	450	700	425	1575
COLUMBIA												
Cabbage	-	-	-	200	-	50	-	50	-	25	-	25
Cucumbers	-	-	25	25	-	-	-	-	-	-	-	-
Total Vegs.	-	-	25	225	-	50	-	50	-	25	-	25
Watermelons	-	-	-	300	-	-	-	350	-	-	250	250
Grand Total	-	-	25	525	-	50	-	400	-	25	250	275
DADE												
Beans	-	3000	-	3000	-	3100	-	3100	-	1700	300	2000
Limas	-	50	100	150	-	50	50	100	-	50	50	100
Cabbage	-	-	-	350	-	300	-	300	-	350	-	350
Carrots	-	-	-	-	-	-	-	-	-	25	-	25
Peppers	-	-	-	-	-	-	-	-	-	25	-	25
Potatoes	-	6300	200	6500	-	6500	270	6770	-	6000	-	6000
Tomatoes	500	12500	-	13000	200	10000	3000	13200	1500	6200	500	8200
Total Vegs.	500	21850	300	23000	200	19950	3320	23470	1500	14350	850	16700
Strawberries	-	-	-	100	-	150	-	150	-	150	-	150
Grand Total	500	21850	300	23100	200	20100	3320	23620	1500	14500	850	16850
DE SOTO												
Cabbage	-	-	-	50	-	-	-	-	-	-	-	-
Cucumbers	-	-	50	50	50	-	50	100	75	-	50	125
Eggplant	-	-	-	-	-	-	-	-	25	-	-	25
Peppers	25	-	-	25	-	-	-	-	25	-	-	25
Potatoes	-	-	100	100	-	-	100	100	-	-	-	-
Tomatoes	25	-	100	125	25	-	200	225	25	-	150	175
Total Vegs.	50	-	250	350	75	-	350	425	150	-	200	350
Watermelons	-	-	-	-	-	-	-	300	-	-	100	100
Grand Total	50	-	250	350	75	-	350	725	150	-	300	450
DIXIE												
Watermelons	-	-	-	-	-	-	-	100	-	-	100	100
DUVAL												
Cabbage	-	-	-	-	-	100	-	100	-	100	-	100
ESCAMBIA												
Beans	-	-	-	-	-	-	230	230	-	-	250	250
Cabbage	-	-	-	-	-	100	-	100	-	50	-	50
Potatoes	-	-	800	800	-	-	850	850	-	-	700	700
Total Vegs.	-	-	800	800	-	100	1080	1180	-	50	950	1000
FLAGLER												
Cabbage	-	-	-	700	-	800	-	800	-	1000	-	1000
Cucumbers	-	-	-	-	-	-	100	100	-	-	50	50
Peas, English	-	-	-	-	-	100	-	100	-	50	-	50
Potatoes	-	-	2000	2000	-	-	2250	2250	-	-	2100	2100
Total Vegs.	-	-	2000	2700	-	900	2350	3250	-	1050	2150	3200
GADSDEN												
Beans	-	-	200	200	150	-	300	450	150	-	300	450
Cabbage	-	-	-	100	-	50	-	50	-	50	-	50
Total Vegs.	-	-	200	300	150	50	300	500	150	50	300	500
Watermelons	-	-	-	50	-	-	-	50	-	-	-	-
Grand Total	-	-	200	350	150	50	300	550	150	50	300	500
GILCHRIST												
Eggplant	100	-	-	100	50	-	-	50	25	-	-	25
Watermelons	-	-	-	3500	-	-	-	5400	-	-	5800	5800
Grand Total	100	-	-	3600	50	-	-	5450	25	-	5800	5825

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1944-45				1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
GLADES												
Beans	50	-	200	250	50	-	60	110	-	-	-	-
Cabbage	-	-	-	350	-	550	-	550	-	450	-	450
Lettuce,Ice.	-	300	-	300	-	400	-	400	-	225	-	225
Tomatoes	-	-	-	-	-	-	-	-	175	-	-	175
Total Vegs.	50	300	200	900	50	950	60	1060	175	675	-	850
HAMILTON												
Cabbage	-	-	-	100	-	50	-	50	-	50	-	50
Cucumbers	-	-	-	400	-	-	500	500	-	-	575	575
Total Vegs.	-	-	-	500	-	50	500	550	-	50	575	625
Cantaloupes	-	-	-	75	-	-	75	75	-	-	50	50
Watermelons	-	-	-	300	-	-	-	200	-	-	250	250
Grand Total	-	-	-	875	-	50	575	825	-	50	875	925
HARDEE												
Beans	-	-	50	50	-	-	40	40	-	-	50	50
Cabbage	-	-	-	50	-	50	-	50	-	50	-	50
Cucumbers	325	-	500	825	500	-	700	1200	800	-	600	1400
Eggplant	100	-	-	100	250	-	-	250	150	-	-	150
Peppers	175	-	50	225	400	-	50	450	260	-	25	285
Potatoes	-	-	100	100	-	-	50	50	-	-	-	-
Tomatoes	25	-	1000	1025	25	-	2000	2025	25	-	1200	1225
Total Vegs.	625	-	1700	2375	1175	50	2840	4065	1235	50	1875	3160
Strawberries	-	-	-	200	-	200	-	200	-	400	-	400
Watermelons	-	-	-	100	-	-	-	100	-	-	50	50
Grand Total	625	-	1700	2675	1175	250	2840	4365	1235	450	1925	3610
HENDRY												
Beans	50	-	100	150	50	100	-	150	-	-	-	-
Cabbage	-	-	-	50	-	50	-	50	-	50	-	50
Cucumbers	25	-	-	25	-	-	100	100	150	-	50	200
Tomatoes	-	-	-	-	-	-	-	-	250	-	25	275
Total Vegs.	75	-	100	225	50	150	100	300	400	50	75	525
Watermelons	-	-	-	100	-	-	-	100	-	-	-	-
HERNANDO												
Beans	-	-	150	150	-	-	140	140	-	-	100	100
Eggplant	50	-	50	100	50	-	-	50	-	-	-	-
Total Vegs.	50	-	200	250	50	-	140	190	-	-	100	100
Watermelons	-	-	-	50	-	-	-	-	-	-	-	-
HIGHLANDS												
Beans	200	200	150	550	-	-	230	230	200	-	350	550
Cabbage	-	-	-	100	-	25	-	25	-	25	-	25
Carrots	-	-	-	-	-	-	-	-	-	25	-	25
Cucumbers	-	-	50	50	-	-	-	-	50	-	-	50
Eggplant	-	-	25	25	-	-	25	25	25	-	-	25
Peas,English	-	-	-	-	-	100	-	100	-	50	-	50
Potatoes	-	-	200	200	-	-	80	80	-	-	-	-
Tomatoes	-	-	-	-	-	-	-	-	25	-	-	25
Total Vegs.	200	200	425	925	-	125	335	460	300	100	350	750
HILLSBOROUGH												
Beans	50	-	200	250	100	-	1100	1200	150	-	1700	1850
Limas	-	-	100	100	-	-	250	250	-	-	500	500
Cabbage	-	-	-	450	-	500	-	500	-	750	-	750
Cauliflower	-	-	-	-	-	-	-	-	-	300	-	300
Cucumbers	125	-	350	475	300	-	500	800	275	-	700	975
Eggplant	50	-	300	350	150	-	325	475	75	25	250	350
Escarole	-	-	-	-	-	-	-	-	-	40	-	40
Lettuce,Ice.	-	175	-	175	-	200	50	250	-	325	-	325
Peas,English	-	200	-	200	-	400	-	400	-	200	-	200
Peppers	50	-	1800	1850	75	-	2600	2675	-	-	2600	2600
Potatoes	-	200	200	400	-	300	330	630	-	-	100	100
Tomatoes	100	-	1150	1250	325	-	1500	1825	425	-	1350	1775
Total Vegs.	375	575	4100	5500	950	1400	6655	9005	925	1640	7200	9765
Strawberries	-	-	-	1100	-	1700	-	1700	-	3000	-	3000
Watermelons	-	-	-	300	-	-	-	400	-	-	500	500
Grand Total	375	575	4100	6900	950	3100	6655	11105	925	4640	7700	13265

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1944-45				1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
HOLMES												
Cucumbers	-	-	-	-	-	-	-	-	-	-	200	200
Potatoes	-	-	50	50	-	-	50	50	-	-	100	100
Total Vegs.	-	-	50	50	-	-	50	50	-	-	300	300
Watermelons	-	-	-	-	-	-	-	200	-	-	400	400
INDIAN RIVER												
Cabbage	-	-	-	50	-	-	-	-	-	-	-	-
Cucmbers	-	-	-	-	-	-	-	-	-	-	75	75
Eggplant	-	-	-	-	-	-	-	-	-	25	-	25
Peppers	-	-	-	-	-	-	-	-	-	-	25	25
Tomatoes	175	50	350	575	150	-	150	300	350	-	200	550
Total Vegs.	175	50	350	625	150	-	150	300	350	25	300	675
Watermelons	-	-	-	100	-	-	-	100	-	-	-	-
JACKSON												
Cucumbers	-	-	100	100	-	-	500	500	-	-	375	375
Cantaloupes	-	-	-	-	-	-	75	75	-	-	100	100
Watermelons	-	-	-	5000	-	-	-	5000	-	-	2500	2500
Grand Total	-	-	100	5100	-	-	575	5575	-	-	2975	2975
JEFFERSON												
Beans	-	-	-	-	-	-	50	50	-	-	50	50
Watermelons	-	-	-	1200	-	-	-	3800	-	-	3200	3200
LAFAYETTE												
Watermelons	-	-	-	-	-	-	-	1000	-	-	700	700
LAKE												
Beans	-	-	350	350	-	-	140	140	-	-	100	100
Cabbage	-	-	-	300	-	150	-	150	-	150	-	150
Carrots	-	-	-	-	-	-	-	-	-	20	-	20
Celery	-	50	300	350	-	135	675	810	-	225	650	875
Cucumbers	-	-	200	200	-	-	400	400	75	-	200	275
Eggplant	-	-	100	100	-	-	50	50	-	-	-	-
Escarole	-	-	-	-	-	20	-	20	-	40	-	40
Lettuce, Ice.	-	-	-	-	-	-	-	-	-	25	-	25
Peppers	-	-	100	100	-	-	150	150	100	-	150	250
Potatoes	-	-	50	50	-	-	-	-	-	-	-	-
Tomatoes	25	-	300	325	25	-	350	375	25	-	100	125
Total Vegs.	25	50	1400	1775	25	305	1765	2095	200	460	1200	1360
Watermelons	-	-	-	6500	-	-	-	6000	-	-	8500	8500
Grand Total	25	50	1400	8275	25	305	1765	8095	200	460	9700	10360
LEE												
Cucumbers	150	-	150	300	300	100	100	500	500	-	200	700
Eggplant	75	250	50	375	100	150	100	350	100	150	50	300
Peppers	100	275	-	375	350	150	-	500	250	150	-	400
Potatoes	-	1200	-	1200	-	1360	-	1360	-	900	-	900
Tomatoes	150	300	-	450	400	300	-	700	450	100	-	550
Total Vegs.	475	2025	200	2700	1150	2060	200	3410	1300	1300	250	2850
Watermelons	-	-	-	150	-	-	-	150	-	-	50	50
Grand Total	475	2025	200	2850	1150	2060	200	3560	1300	1300	300	2900
LEON												
Watermelons	-	-	-	100	-	-	-	200	-	-	50	50
LEVY												
Beans	-	-	100	100	-	-	50	50	-	-	-	-
Cabbage	-	-	-	100	-	50	-	50	-	50	-	50
Cucumbers	-	-	100	100	-	-	200	200	-	-	50	50
Total Vegs.	-	-	200	300	-	50	250	300	-	50	50	100
Cantaloupes	-	-	-	100	-	-	100	100	-	-	50	50
Watermelons	-	-	-	1200	-	-	-	2500	-	-	2400	2400
Grand Total	-	-	200	1600	-	50	350	2900	-	50	2500	2550
MADISON												
Cucumbers	-	-	25	25	-	-	-	-	-	-	-	-
Cantaloupes	-	-	-	-	-	-	-	-	-	-	50	50
Watermelons	-	-	-	3000	-	-	-	2000	-	-	1800	1800
Grand Total	-	-	25	3025	-	-	-	2000	-	-	1850	1850

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1944-45				1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
MANATEE												
Beans	-	-	250	250	50	-	400	450	50	-	500	550
Cabbage	-	-	-	1000	-	300	-	300	-	200	-	200
Cauliflower	-	-	-	-	-	-	-	-	-	200	-	200
Celery	-	100	-	100	-	100	-	100	-	75	-	75
Cucumbers	50	-	50	100	450	-	500	950	500	-	225	725
Eggplant	50	-	100	150	150	100	250	500	150	100	125	375
Escarole	-	-	-	475	-	400	-	400	-	240	-	240
Lettuce, Boston	-	-	-	150	-	50	-	50	-	125	-	125
" Iceberg	-	25	-	25	-	100	50	150	-	100	-	100
Peas, English	-	150	-	150	-	50	-	50	-	50	-	50
Peppers	50	50	50	150	150	-	200	350	250	-	100	350
Potatoes	-	50	50	100	-	50	-	50	-	-	-	-
Tomatoes	175	100	1950	2225	600	-	2000	2600	700	-	750	1450
Total Vegs.	325	475	2450	4875	1400	1150	3400	5950	1650	1090	1700	4440
Strawberries	-	-	-	25	-	-	-	-	-	-	-	-
Watermelons	-	-	-	100	-	-	-	150	-	-	150	150
Grand Total	325	475	2450	5000	1400	1150	3400	6100	1650	1090	1350	4590
MARION												
Beans	200	-	300	500	100	-	700	800	300	-	1000	1300
Limas	-	-	400	400	-	-	700	700	-	-	600	600
Cabbage	-	-	-	500	-	500	-	500	-	-	400	400
Celery	-	-	200	200	-	-	220	220	-	60	130	190
Cucumbers	-	-	225	225	-	-	300	300	25	-	250	275
Eggplant	100	-	25	125	150	-	75	225	200	-	-	200
Escarole	-	-	-	50	-	10	-	10	-	50	-	50
Lettuce, Boston	-	-	-	150	-	200	-	200	-	200	-	200
" Iceberg	-	50	-	50	-	-	50	50	-	-	25	25
Peas, English	-	100	-	100	-	100	-	100	-	-	-	25
Peppers	25	-	100	125	25	-	100	125	-	-	150	150
Potatoes	-	-	-	-	-	-	100	100	-	-	50	50
Tomatoes	-	-	450	450	-	-	1050	1050	-	-	500	500
Total Vegs.	325	150	1700	2875	275	810	3295	4380	550	310	3105	3965
Cantaloupes	-	-	-	150	-	-	250	250	-	-	150	150
Watermelons	-	-	-	3000	-	-	-	3500	-	-	4550	4550
Grand Total	325	150	1700	6025	275	810	3545	8130	550	310	7805	8665
MARTIN												
Beans	200	200	200	600	-	100	240	340	200	200	200	600
Limas	-	150	-	150	-	100	200	300	-	125	-	125
Cabbage	-	-	-	50	-	100	-	100	-	100	-	100
Cucumbers	25	-	-	25	50	-	-	50	100	-	-	100
Eggplant	-	50	25	75	50	125	50	225	50	125	25	200
Peppers	-	100	35	135	-	100	50	150	75	100	50	225
Potatoes	-	50	-	50	-	240	-	240	-	-	-	-
Tomatoes	100	50	100	250	100	300	100	500	300	100	-	400
Total Vegs.	325	600	360	1335	200	1065	640	1905	725	750	275	1750
ORANGE												
Beans	-	-	100	100	100	-	50	150	150	-	200	350
Cabbage	-	-	-	800	-	650	-	650	-	-	800	800
Carrots	-	-	-	-	-	-	-	-	-	330	-	330
Celery	-	150	800	950	-	490	675	1165	-	315	380	695
Cucumbers	-	-	150	150	-	-	400	400	50	-	350	400
Eggplant	25	-	-	25	50	-	-	50	-	-	-	-
Escarole	-	-	-	225	-	150	-	150	-	190	-	190
Lettuce, Boston	-	-	-	-	-	-	-	-	-	25	-	25
Lettuce, Iceberg	-	-	25	25	-	50	130	180	-	25	-	25
Peas, English	-	50	-	50	-	50	-	50	-	-	-	-
Peppers	75	-	-	75	350	-	-	350	250	-	-	250
Potatoes	-	-	300	300	-	40	200	240	-	-	150	150
Tomatoes	-	-	75	75	-	-	-	-	-	-	-	-
Total Vegs.	100	200	1450	2775	500	1430	1455	3385	450	885	1880	3215
Strawberries	-	-	-	25	-	-	-	-	-	-	-	-
Watermelons	-	-	-	100	-	-	-	1200	-	-	1100	1100
Grand Total	100	200	1450	2900	500	1430	1455	4585	450	885	2980	4315
OSCEOLA												
Cabbage	-	-	-	100	-	50	-	50	-	-	-	-

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1944-45				1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
PALM BEACH												
Beans	16800	16300	19000	52100	17800	17800	13200	48800	13300	14500	23600	51400
Limas	-	1500	750	2250	-	2175	1350	3525	-	1200	650	1850
Cabbage	-	-	-	4100	-	3000	-	3000	-	3500	-	3500
Carrots	-	-	-	-	-	-	-	-	-	50	-	50
Celery	-	3300	825	4125	-	3750	1425	5175	-	3000	1280	4280
Cucumbers	150	200	-	350	300	350	50	700	1000	200	400	1600
Eggplant	50	200	450	700	125	200	450	775	125	250	200	575
Escarole	-	-	-	1600	-	1400	-	1400	-	1700	-	1700
Lettuce, Boston	-	-	-	25	-	100	-	100	-	125	-	125
Lettuce, Iceberg	-	325	-	325	-	150	100	250	-	225	50	275
Peas, English	-	1800	-	1800	-	900	-	900	-	1000	-	1000
Peppers	100	1050	350	1500	100	1250	550	1900	125	1400	100	1625
Potatoes	-	3800	2500	6300	-	5000	4200	9200	-	2800	450	3250
Tomatoes	100	900	1100	2100	200	1000	750	1950	200	500	50	750
Total Vegs.	17200	29375	24975	77275	18525	37075	22075	77675	14750	30450	26780	71980
Watermelons	-	-	-	100	-	-	-	200	-	-	200	200
Grand Tot.	17200	29375	24975	77375	18525	37075	22075	77875	14750	30450	26980	72180
PASCO												
Watermelons	-	-	-	500	-	-	-	200	-	-	750	750
PINELLAS												
Watermelons	-	-	-	-	-	-	-	-	-	-	100	100
POLK												
Beans	-	-	50	50	-	-	200	200	-	-	200	200
Cabbage	-	-	-	400	-	200	-	200	-	150	-	150
Cucumbers	-	-	50	50	-	-	50	50	100	-	100	200
Peas, English	-	-	-	-	-	-	-	-	-	25	-	25
Peppers	-	-	200	200	-	-	300	300	25	-	500	525
Potatoes	-	-	50	50	-	-	50	50	-	-	-	-
Tomatoes	-	-	100	100	-	-	200	200	-	-	175	175
Total Vegs.	-	-	450	850	-	200	800	1000	125	175	975	1275
Strawberries	-	-	-	200	-	300	-	300	-	500	-	500
Watermelons	-	-	-	150	-	-	-	200	-	-	350	350
Grand Total	-	-	450	1200	-	500	800	1500	125	675	1325	2125
PUTNAM												
Beans	-	-	-	-	-	-	240	240	-	-	250	250
Cabbage	-	-	-	1500	-	900	-	900	-	1000	-	1000
Lettuce, Iceberg	-	-	50	50	-	-	25	25	-	-	25	25
Potatoes	-	-	2850	2850	-	-	2600	2600	-	-	2200	2200
Total Vegs.	-	-	2900	4400	-	900	2865	3765	-	1000	2475	3475
Watermelons	-	-	-	100	-	-	-	100	-	-	300	300
Grand Total	-	-	2900	4500	-	900	2865	3865	-	1000	2775	3775
ST. JOHNS												
Cabbage	-	-	-	2400	-	2500	-	2500	-	2700	-	2700
Potatoes	-	-	6900	6900	-	-	7300	7300	-	-	6200	6200
Total Vegs.	-	-	6900	9300	-	2500	7300	9800	-	2700	6200	8900
Watermelons	-	-	-	50	-	-	-	-	-	-	-	-
ST. LUCIE												
Beans	50	-	50	100	100	-	-	100	-	-	-	-
Limas	-	100	200	300	-	125	75	200	-	100	-	100
Cabbage	-	-	-	50	-	50	-	50	-	-	-	-
Cucumbers	50	-	50	100	100	-	50	150	200	-	200	400
Eggplant	25	50	50	125	50	-	-	50	50	50	25	125
Peppers	25	100	50	175	50	50	-	100	75	-	25	100
Tomatoes	800	100	1600	2500	2700	200	2850	5750	4450	-	3000	7450
Total Vegs.	950	350	2000	3350	3000	425	2975	6400	4775	150	3250	8175
Watermelons	-	-	-	100	-	-	-	100	-	-	50	50
Grand Total	950	350	2000	3450	3000	425	2975	6500	4775	150	3300	8225

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1944-45				1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
SARASOTA												
Cabbage	-	-	-	250	-	100	-	100	-	100	-	100
Cauliflower	-	-	-	-	-	-	-	-	-	30	-	30
Celery	-	800	500	1300	-	1000	360	1360	-	925	360	1285
Cucumbers	25	-	125	150	50	-	100	150	100	-	150	250
Escarole	-	-	-	100	-	20	-	20	-	-	-	-
Lettuce, Iceberg	-	-	-	-	-	50	-	50	-	-	-	-
Peppers	-	-	-	-	-	100	-	100	25	-	-	25
Potatoes	-	100	200	300	-	100	180	280	-	-	50	50
Tomatoes	-	-	100	100	-	-	75	75	-	-	-	-
Total Vegs.	25	900	925	2200	50	1370	715	2135	125	1055	560	1740
Watermelons	-	-	-	-	-	-	-	-	-	-	50	50
SEMINOLE												
Beans	50	-	100	150	100	-	250	350	350	-	200	550
Cabbage	-	-	-	1150	-	1000	-	1000	-	1000	-	1000
Carrots	-	-	-	-	-	-	-	-	-	50	-	50
Cauliflower	-	-	-	-	-	-	-	-	-	50	-	50
Celery	-	2400	1450	3850	-	3075	1400	4475	-	2700	1450	4150
Escarole	-	-	-	350	-	600	-	600	-	500	-	500
Lettuce, Boston	-	-	-	75	-	150	-	150	-	200	-	200
" Iceberg	-	25	-	25	-	50	-	50	-	50	-	50
Peas, English	-	100	-	100	-	100	-	100	-	50	-	50
Peppers	25	-	200	225	25	-	250	275	25	-	100	125
Potatoes	-	-	150	150	-	-	200	200	-	-	-	-
Total Vegs.	75	2525	1900	6075	125	4975	2100	7200	375	4600	1750	6725
SUMTER												
Beans	25	-	450	475	-	-	230	230	-	-	250	250
Cabbage	-	-	-	200	-	50	-	50	-	50	-	50
Cucumbers	-	-	500	500	50	-	1000	1050	200	-	800	1000
Eggplant	-	-	150	150	-	-	150	150	-	-	75	75
Peppers	-	-	500	500	25	-	700	725	-	-	800	800
Tomatoes	50	-	1200	1250	50	-	1250	1300	50	-	600	650
Total Vegs.	75	-	2800	3075	125	50	3330	3505	250	50	2525	2825
Cantaloupes	-	-	-	25	-	-	50	50	-	-	50	50
Strawberries	-	-	-	75	-	100	-	100	-	150	-	150
Watermelons	-	-	-	2100	-	-	-	2700	-	-	3200	3200
Grand Total	75	-	2800	5275	125	150	3380	6355	250	200	5775	6225
SUWANNEE												
Cucumbers	-	-	50	50	-	-	-	-	-	-	200	200
Cantaloupes	-	-	-	-	-	-	-	-	-	-	50	50
Watermelons	-	-	-	5000	-	-	-	5500	-	-	3000	3000
Grand Total	-	-	50	5050	-	-	-	5500	-	-	3250	3250
TAYLOR												
Watermelons	-	-	-	-	-	-	-	50	-	-	100	100
UNION												
Beans	-	-	100	100	-	-	240	240	-	-	250	250
Limas	-	-	50	50	-	-	50	50	-	-	150	150
Cabbage	-	-	-	150	-	50	-	50	-	50	-	50
Cucumbers	-	-	150	150	-	-	150	150	50	-	150	200
Potatoes	-	-	100	100	-	-	150	150	-	-	50	50
Total Vegs.	-	-	400	550	-	50	590	640	50	50	600	700
Watermelons	-	-	-	100	-	-	-	100	-	-	50	50
VOLUSIA												
Cabbage	-	-	-	300	-	200	-	200	-	200	-	200
Potatoes	-	-	150	150	-	-	150	150	-	-	-	-
Total Vegs.	-	-	150	450	-	200	150	350	-	200	-	200
Watermelons	-	-	-	50	-	-	-	100	-	-	50	50
WALTON												
Watermelons	-	-	-	-	-	-	-	250	-	-	150	150
WASHINGTON												
Potatoes	-	-	50	50	-	-	50	50	-	-	-	-
Watermelons	-	-	-	1000	-	-	-	800	-	-	500	500
Grand Total	-	-	50	1050	-	-	50	850	-	-	500	500

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1944-45				1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
MISCELLANEOUS												
Beans	50	200	50	300	50	-	460	510	100	100	250	450
Limas	-	50	-	50	-	75	50	125	-	25	25	50
Cabbage	-	-	-	150	-	135	-	135	-	100	-	100
Cauliflower	-	-	-	-	-	-	-	-	-	20	-	20
Celery	-	-	25	25	-	-	10	10	-	-	20	20
Cucumbers	25	-	50	75	50	50	100	200	50	50	25	125
Eggplant	50	25	25	100	25	50	100	175	25	25	50	100
Escarole	-	-	-	-	-	-	-	-	-	40	-	40
Lettuce, Boston	-	-	-	-	-	-	-	-	-	25	-	25
" Iceberg	-	-	25	25	-	-	15	15	-	25	-	25
Peppers	-	25	25	50	-	50	50	100	90	25	75	190
Potatoes	-	50	100	150	-	10	90	100	-	200	350	550
Tomatoes	-	-	150	150	50	50	175	275	100	50	175	325
Total Vegs.	125	350	450	1075	175	420	1050	1645	365	685	970	2020
Cantaloupes	-	-	-	25	-	-	50	50	-	-	50	50
Strawberries	-	-	-	125	-	125	-	125	-	150	-	150
Watermelons	-	-	-	300	-	-	-	200	-	-	100	100
Grand Total	125	350	450	1525	175	545	1100	2020	365	835	1120	2320

TOTAL ALL COUNTIES

	1943-44				1944-45			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	29000	39500	23000	91500	20000	37500	23000	80500
Limas	-	1500	3000	4500	-	2000	2800	4800
Cabbage	-	-	-	19000	-	-	-	17500
Celery	-	5900	3250	9150	-	6800	4250	11050
Cucumbers	1800	-	4500	6300	1200	400	6100	7700
Eggplant	1300	1000	1200	3500	800	800	1650	3250
Escarole	-	-	-	1650	-	-	-	2800
Lettuce, Boston	-	-	-	850	-	-	-	400
" Iceberg	-	1050	100	1150	-	850	150	1030
Peas, English	-	-	-	2500	-	2600	-	2600
Peppers	1950	3600	3400	8950	750	3800	4800	9350
Potatoes	-	13000	15600	28600	-	11800	19300	31100
Tomatoes	4400	18500	12000	34900	2800	18600	11100	32500
Total Vegetables	38450	84050	66050	212550	25550	85150	73150	204550
Cantaloupes	-	-	-	550	-	-	-	500
Strawberries	-	-	-	1400	-	-	-	2050
Watermelons	-	-	-	25500	-	-	-	39000
Grand Total	38450	84050	66050	240000	25550	85150	73150	246100

	1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	22100	38000	20100	80200	19700	28500	33500	81700
Limas	-	2675	4325	7000	-	1600	3600	5200
Cabbage	-	13200	-	13200	-	14000	-	14000
Carrots	-	-	-	-	-	500	-	500
Cauliflower	-	-	-	-	-	600	-	600
Celery	-	8550	4900	13450	-	7300	4400	11700
Cucumbers	2700	750	8500	11950	5000	300	8475	13775
Eggplant	1400	825	1825	4050	1200	1000	1100	3300
Escarole	-	2600	-	2600	-	2800	-	2800
Lettuce, Boston	-	500	-	500	-	700	-	700
Iceberg	-	1000	450	1450	-	1000	125	1125
Peas, English	-	2000	-	2000	-	1600	-	1600
Peppers	1700	3800	6500	12000	1750	3600	5200	10550
Potatoes	-	13600	21700	35300	-	9900	14200	24100
Tomatoes	5300	15000	17000	37300	10000	9800	10000	29800
Total Vegetables	33200	102500	85300	221000	37650	83200	80600	201450
Cantaloupes	-	-	800	800	-	-	800	800
Strawberries	-	2800	-	2800	-	4750	-	4750
Watermelons	-	-	-	51000	-	-	47000	47000
Grand Total	33200	105300	86100	275600	37650	87950	128400	254000

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS

BEANS, SNAP

Season	Harvested Acreage	Yield Bushels	Volume Production		Price per Bushel	Canning	FOB Packed Total Value
1929-30	35,800	89	3,172,000		$2.15		$6,805,000
1930-31	40,000	84	3,376,000		1.95		6,592,000
1931-32	41,500	109	4,508,000	A/(284,000)	1.41		5,958,000
1932-33	50,800	98	5,002,000	A/(144,000)	.90		4,356,000
1933-34	61,300	101	6,216,000	A/(430,000)	1.00		5,773,000
1934-35	65,500	76	4,948,000		1.21		5,967,000
1935-36	59,200	71	4,183,000		1.49		6,250,000
1936-37	58,800	80	4,688,000		1.50		7,037,000
1937-38	60,700	89	5,381,000		1.17		6,272,000
1938-39	64,000	111	7,135,000	A/(288,000)	1.03		7,041,000
1939-40	52,000	98	5,090,000		1.47		7,480,000
1940-41	62,500	92	5,780,000		1.55		8,933,000
1941-42	68,000	105	5,783,000		1.84	.91	11,913,000
1942-43	80,000	131	7,795,000		2.62	$1.27	17,989,000
1943-44	96,500	86	8,273,000	A/(269,000)	2.56	1.29	18,713,000
1944-45	80,500	92	7,440,000	A/(496,000)	2.92	1.67	18,405,000
1945-46	80,200	106	8,469,000	A/(1,240,000)	2.73	1.67	18,359,000
1946-47	81,700	80	6,549,700	A/(561,000)	2.90	1.67	16,389,000

A - Not harvested, due to economic abandonment. Values cover harvested portion of crop. Canning production: 1941-42 bu. 1,367,000; 1942-43 bu. 2,677,000; 1943-44 1,268,000; 1944-45 bu. 1,486,000; 1945-46 bu. 1,106,000; 1946-47 bu. 561,000.

LIMAS

Season	Harvested Acreage	Yield Bushels	Volume Production		Price per Bushel	FOB Packed Total Value
1934-35	1,500	90	135,000		$2.00	$ 270,000
1935-36	1,800	70	126,000		1.60	202,000
1936-37	2,400	65	156,000		2.50	390,000
1937-38	4,500	75	338,000		1.50	507,000
1938-39	4,800	100	480,000		1.50	720,000
1939-40	4,000	70	280,000		1.50	420,000
1940-41	7,000	40	280,000		2.20	616,000
1941-42	5,000	65	325,000		2.10	682,000
1942-43	5,400	59	321,000		3.31	1,041,000
1943-44	4,500	77	345,000		4.16	1,436,000
1944-45	4,800	88	420,000	A/(14,000)	4.38	1,779,000
1945-46	6,300	88	555,000	A/(87,000)	3.28	1,533,000
1946-47	5,200	65	338,000		3.51	1,187,000

CABBAGE

Season	Harvested Acreage	Yield Tons	Volume Production		Price per Ton	FOB Packed Total Value
1930-31	6,500	7.4	48,100	A/(7,100)	$22.40	$ 918,000
1931-32	5,500	4.0	22,100		32.00	704,000
1932-33	6,200	7.0	43,400	A/(6,500)	16.00	590,000
1933-34	10,700	6.0	64,200	A/(21,400)	16.00	685,000
1934-35	5,600	5.2	29,120		56.00	1,630,000
1935-36	9,000	4.0	36,000		17.00	612,000
1936-37	8,500	6.0	51,000	A/(20,000)	16.00	496,000
1937-38	9,400	6.5	61,000		16.00	978,000
1938-39	10,000	5.5	55,000		18.00	990,000
1939-40	16,000	7.0	112,000		18.40	2,061,000
1940-41	10,000	6.0	60,000		38.90	2,334,000
1941-42	18,000	6.0	108,000		17.80	1,602,000
1942-43	10,000	8.5	85,000		76.00	6,460,000
1943-44	23,500	7.1	166,800	A/(47,100)	36.00	4,309,000
1944-45	17,500	7.5	131,000	A/(24,000)	37.00	3,959,000
1945-46	13,200	8.8	116,200	A/(2,500)	49.00	5,571,000
1946-47	14,000	7.1	99,400	A/(18,200)	37.80	3,069,000

A - Not harvested, due to economic abandonment. Values cover harvested portion of crop. Abandoned volume is included in production volume.

NOTE: All 1946-47 acreage figures are preliminary as of September 20, 1947 and are subject to revision. Revisions are usually of minor consequence.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd).

CELERY

Season	Harvested Acreage	Yield N.Y.	Crates Fla.	Volume Production		Price per NY 2/3 Crates	FOB Packed Total Value	Price per Fla. Crates
1930-31	6,150	308	(513)	1,894,000		$ 2.75	$ 5,212,000	$1.65
1931-32	6,850	255	(425)	1,746,000		2.17	3,783,000	1.30
1932-33	6,650	262	(437)	1,743,000	A/(207,000)	1.27	1,949,000	.76
1933-34	6,000	312	(520)	1,872,000		1.60	2,996,000	.96
1934-35	6,000	280	(467)	1,680,000		2.60	4,368,000	1.56
1935-36	6,500	265	(442)	1,723,000		2.60	4,488,000	1.56
1936-37	7,500	280	(467)	2,097,000		2.16	4,532,000	1.30
1937-38	8,000	286	(477)	2,290,000	A/(255,000)	1.62	3,289,000	.97
1938-39	7,300	299	(498)	2,184,000		2.46	5,375,000	1.48
1939-40	7,500	304	(507)	2,279,000		2.57	5,868,000	1.54
1940-41	9,100	278	(463)	2,531,000		3.19	8,066,000	1.91
1941-42	9,350	269	(465)	2,608,000	F/(4,347,000)	2.74	7,154,000	1.64
1942-43	8,750	-	447	4,175,500	(Fla.Crts)	-	17,158,000	4.11
1943-44	9,900	-	502	4,969,000	A/(400,000)	-	14,520,000	3.18
1944-45	11,050	-	493	5,448,000	A/(102,000)	-	18,353,000	3.47
1945-46	13,450	-	479	6,439,000	A/(151,000)	-	14,260,000	2.27
1946-47	11,700	-	390	4,564,000		-	17,535,000	3.84

A - Not harvested due to economic abandonment. Values cover harvested portion crops. Florida crates are approximately 60 per cent as large as NY 2/3 crates.

CUCUMBERS

Season	Harvested Acreage	Yield Bushels	Volume Production	Price per Bushel	FOB Packed Total Value
1929-30	12,100	54	649,000	$2.42	$1,568,000
1930-31	9,650	100	961,000	1.35	1,293,000
1931-32	7,300	53	390,000	1.63	655,000
1932-33	5,600	64	361,000	1.75	632,000
1933-34	5,000	95	474,000	1.78	845,000
1934-35	5,100	93	473,000	1.62	765,000
1935-36	5,700	82	468,000	1.98	928,000
1936-37	5,600	65	364,000	3.02	1,101,000
1937-38	7,000	121	850,000	1.24	1,053,000
1938-39	7,600	115	876,000	1.58	1,391,000
1939-40	8,200	145	1,186,000	1.63	1,938,000
1940-41	8,800	121	1,064,000	1.75	1,853,000
1941-42	9,700	94	912,000	2.24	2,042,000
1942-43	6,500	80	520,000	4.98	2,592,000
1943-44	6,300	73	459,000	4.55	2,079,000
1944-45	7,700	110	814,000	4.31	3,627,000
1945-46	11,150	136	1,520,000A(76,000)	3.72	5,377,000
1946-47	13,775	87	1,204,000	4.14	4,984,000

EGGPLANT

Season	Harvested Acreage	Yield Bushels	Volume Production	Price per Bushel	FOB Packed Total Value
1929-30	1,680	224	377,000	$1.20	$ 454,000
1930-31	1,800	240	432,000	.82	356,000
1931-32	1,950	189	367,000	.75	277,000
1932-33	2,450	253	620,000	.58	359,000
1933-34	2,050	187	384,000	.75	289,000
1934-35	1,500	180	270,000	.79	212,000
1935-36	1,100	286	315,000	.85	268,000
1936-37	1,460	283	413,000	.79	323,000
1937-38	1,800	261	470,000	.76	366,000
1938-39	2,100	326	686,000	.75	514,000
1939-40	1,400	207	290,000	1.44	417,000
1940-41	1,800	180	324,000	1.17	378,000
1941-42	2,350	237	556,500	1.16	643,000
1942-43	1,950	278	541,500	2.39	1,294,000
1943-44	3,500	259	908,000A(40,000)	1.65	1,501,000
1944-45	3,250	271	880,000	2.06	1,814,000
1945-46	3,900	345	1,344,000A(240,000)	1.63	1,805,000
1946-47	3,300	220	725,000	2.42	1,758,000

A - Not harvested due to economic abandonment. Value covers harvested portion of crop. Abandoned volume is included in production volume.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

ESCAROLE

Season	Harvested Acreage	Yield L.A.Crates		Volume Production		Price Crates*		FOB Packed Total Value
1931-32	700	243		170,000		$1.20		$ 204,000
1932-33	700	420		294,000		.72		212,000
1933-34	700	477		334,000		.80		267,000
1934-35	650	330		214,000		1.10		235,000
1935-36	700	370		259,000		.80		207,000
1936-37	900	453	1½ bu.hpr	408,000		.75	1½bu.hpr.	306,000
1937-38	1,000	453	" " "	453,000		.45	" " "	204,000
1938-39	1,000	440	" " "	440,000		.60	" " "	264,000
1939-40	1,350	400		540,000		.56	" " "	304,000
1940-41	1,000	373		373,000		.98	" " "	366,000
1941-42	1,200	400	" " "	480,000		.68	" " "	326,000
1942-43	1,450	350	" " "	507,500		2.25	" " "	1,142,000
1943-44	2,350	425	" " "	999,000	A	1.15	" " "	645,000
1944-45	2,800	310	" " "	868,000	A	2.10	" " "	1,352,000
1945-46	2,500	374	" " "	935,000		1.20	" " "	875,000
1946-47	2,800	325	Bu. hpr.	910,000		1.30	Bu. hpr.	1,183,000

* 4-6 doz. lettuce crates. A - 438,000 (1943-44) & 224,000 (1944-45)(1½ bu.) not harvested due to economic abandonment. Very low yield for 1946-47 Season

LETTUCE (Boston and Romaine)

Season	Harvested Acreage	Yield 4-6 doz.Crts.	Volume Production		Price Crates	FOB Packed Total Value
1931-32*	1,000*	200	200,000		$1.28	$ 256,000
1932-33*	950*	295	280,000		.96	269,000
1933-34*	1,100*	236	260,000		1.10	286,000
1934-35*	900*	210	189,000		1.35	255,000
1935-36*	550*	270	148,000		1.25	185,000
1936-37*	800*	185	148,000		1.15	170,000
1937-38*	900*	185	166,000		.90	149,000
1938-39	750	180	135,000		1.50	203,000
1939-40	900	180	162,000		1.10	178,000
1940-41	500	150	75,000		2.00	150,000
1941-42	500	100	50,000		2.60	130,000
1942-43	800	175	140,000		3.05	427,000
1943-44	1,100	150	165,000	A(59,000)	2.15	228,000
1944-45	400	200	80,000		2.70	216,000
1945-46	550	258	142,000	A(17,000)	3.00	375,000
1946-47	700	100	70,000		2.95	206,000

*Seasons 1930-31/1937-38 include Boston, Romaine, Iceberg. A-Crates not harvested.

LETTUCE (Iceberg) 4-6 doz.crates

1938-39	250	180	45,000		$1.49	$ 67,000
1939-40	1,100	180	198,000		2.30	455,000
1940-41	2,000	75	150,000		1.83	274,000
1941-42	3,000	55	165,000		2.16	356,000
1942-43	1,700	135	230,000		3.97	913,000
1943-44	1,350	143	193,000	A	2.90	334,000
1944-45	1,000	143	143,000	A	3.51	418,000
1945-46	1,300	165	214,000	A	3.72	910,250
1946-47	1,125	107	119,000		2.97	353,000

Note: Prior to 1938-39 the acreage of Iceberg type was not commercially important. A-78,000 crates in 1943-44; 24,000 in '44-45; 20,000 in '45-46 were abandoned.

PEAS, ENGLISH

Season	Harvested Acreage	Yield Bushels		Volume Production		Price per Bushel	FOB Packed Total Value
1931-32	3,800	35		133,000		$2.00	$ 266,000
1932-33	3,600	70		252,000		1.60	403,000
1933-34	4,800	96		461,000		1.10	507,000
1934-35	5,000	80		400,000		1.30	520,000
1935-36	8,200	62		508,000		1.00	508,000
1936-37	6,200	50		310,000		1.35	418,000
1937-38	6,200	90		558,000		1.15	642,000
1938-39	5,000	70		350,000		1.85	648,000
1939-40	5,000	90	A/(75,000)	450,000		1.30	488,000
1940-41	3,000	70		210,000		1.95	410,000
1941-42	3,500	70		245,000		1.55	380,000
1942-43	1,500	65		93,000		2.60	254,000
1943-44	2,500	60		150,000		3.00	450,000
1944-45	2,600	75		195,000	A	2.70	284,000
1945-46	1,600	74		118,000	A	3.00	339,000
1946-47	1,600	40		64,000		2.95	189,000

A - 90,000 bu. in 1944-45 season, and 5,000 bu. in 1945-46 season not harvested, due to economic abandonment. Values cover harvested portion of crop.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

PEPPERS, GREEN

Season	Acreage	Yield Bushels	Production	Price per Bushel	FOB Packed Total Value
1930-31	8,200	228	1,869,000	$1.23	$2,294,000
1931-32	8,050	221	1,782,000	1.00	1,780,000
1932-33	8,300	266	2,210,000	.58	1,284,000
1933-34	6,000	241	1,446,000	1.16	1,676,000
1934-35	7,700	149	1,150,000	1.11	1,277,000
1935-36	6,500	226	1,467,000	.87	1,273,000
1936-37	7,200	221	1,590,000	1.20	1,905,000
1937-38	7,400	295	2,180,000	.77	1,668,000
1938-39	7,300	303	2,212,000	1.25	2,771,000
1939-40	6,200	224	1,390,000	1.53	2,121,000
1940-41	7,200	225	1,621,500	1.56	2,537,000
1941-42	6,500	276	1,792,000	1.75	3,133,000
1942-43	7,100	284	2,018,000	2.93	5,917,000
1943-44	8,950	265	2,371,000A 680,000	2.16	4,964,000
1944-45	9,350	287	2,687,000	2.46	6,623,000
1945-46	11,080	275	3,050,000A 380,000	2.45	6,545,000
1946-47	10,550	208	2,193,000	4.14	9,086,000

A - 86,000 bushels not harvested due to economic abandonment.

POTATOES

Season	Acreage	Yield Bushels	Production	Price per Bushel	FOB Packed Total Value
1929-30	31,000	80	2,480,000	$1.86	$4,806,000
1930-31	27,000	132	3,564,000	1.07	3,818,000
1931-32	21,500	70	1,505,000	1.28	1,933,000
1932-33	17,000	132	2,244,000	.85	1,908,000
1933-34	23,500	140	3,290,000	1.13	3,708,000
1934-35	24,800	97	2,406,000	1.04	2,503,000
1935-36	24,500	91	2,235,000	1.43	3,187,000
1936-37	31,300	123	3,842,000	1.32	5,087,000
1937-38	31,400	133	4,177,000	.70	2,939,000
1938-39	26,700	121	3,235,000	1.13	3,644,000
1939-40	25,600	157	4,020,000	.93	3,725,000
1940-41	26,800	117	3,126,000	.90	2,799,000
1941-42	25,000	154	3,848,000	1.54	5,924,000
1942-43	26,200	134	3,523,000	1.96	5,914,000
1943-44	28,600	112	3,212,000	2.00	6,431,000
1944-45	31,100	162	5,035,000	2.39	12,033,000
1945-46	35,300	170	6,010,000	1.95	11,744,000
1946-47	24,100	114	2,738,000	2.00	5,475,000

TOMATOES

Season	Acreage	Yield Bushels	Production		Price per Bu.		FOB Packed Total Value
			Fresh	Canning	Fresh	Canning	
1929-30	31,260	76	2,371,000	-	$3,79	$-	$ 8,976,000
1930-31	26,800	75	2,020,000	-	1.87	-	3,778,000
1931-32	23,700	95	2,255,000	-	2.55	-	5,748,000
1932-33	24,900	94	2,343,000	-	1.87	-	4,377,000
1933-34	30,500	113	2,886,000	557,000	2.86	.39	8,476,000
1934-35	32,500	102	2,714,000	589,000	2.46	.28	6,835,000
1935-36	32,600	100	2,954,000	321,000	2.75	.31	8,224,000
1936-37	35,700	86	2,746,000	314,000	2.76	.32	7,688,000
1937-38	45,300	120	4,953,000	500,000	1.73	.28	8,711,000
1938-39	40,700	129	4,948,000	312,000	2.47	.28	12,325,000
1939-40	34,000	88	3,225,000	232,000	2.53	.28	8,216,000
1940-41	26,500	110	2,765,000	165,000	3.10	.28	8,618,000
1941-42	43,000	101	3,412,000	951,000	3.92	.46	13,821,000
1942-43	25,500	102	2,226,000		5.30		11,795,000
1943-44	34,900	109	3,405,000	395,000	5.72	.59	19,712,000
1944-45	32,500	137	4,456,000	289,000	5.27	.72	20,376,000
1945-46	30,400	154	4,670,000	265,000	5.25	.74	22,405,000
1946-47	29,800	107	3,198,000	306,000	6.50	1.00	19,098,000

A - 342,000 bushels in 1944-45 and 221,000 bushels in 1945-46 not harvested due to economic abandonment.

All 1946-47 acreage figures are preliminary as of September 20, 1947 and are subject to revision.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

CANTALOUPES

Season	Acreage	Yield Crates	Production		Price per Crate	FOB Packed Total Value
1929-30	600	50	30,000		$1.75	$ 52,000
1930-31	250	50	12,000		1.50	18,000
1931-32	200	75	15,000		1.00	15,000
1932-33	400	60	24,000		1.00	24,000
1933-34	300	60	18,000		1.30	23,000
1934-35	200	60	12,000		1.50	18,000
1935-36	200	60	12,000		1.25	15,000
1936-37	300	55	16,000		1.75	28,000
1937-38	700	75	52,000		1.25	65,000
1938-39	500	80	40,000		1.10	44,000
1939-40	500	70	35,000		1.10	38,000
1940-41	500	60	30,000		1.25	38,000
1941-42	500	70	35,000		1.50	52,000
1942-43	400	65	26,000		3.25	85,000
1943-44	550	60	33,000		3.75	124,000
1944-45	500	50	25,000	A 5,000	6.00	120,000
1945-46	800	45	36,000	A 18,000	3.00	54,000
1946-47	800	50*	40,000		2.55	102,000

A - Crates not harvested due to economic abandonment. * Jumbo Crates.

STRAWBERRIES

Season	Acreage	24 Crts.	Production	24 Quarts*	FOB Packed Total Value	36 Pint Crate
1929-30	8,800	67	590,000	$6.70	3,953,000	$5.02
1930-31	9,100	72	655,000	5.75	3,766,000	4.31
1931-32	7,800	76	593,000	4.80	2,846,000	3.60
1932-33	10,600	73	774,000	3.00	2,322,000	2.25
1933-34	8,400	75	630,000	4.20	2,646,000	3.15
1934-35	8,000	65	520,000	4.30	2,236,000	3.23
1935-36	8,900	54	481,000	4.10	1,972,000	3.08
1936-37	8,800	65	572,000	4.80	2,746,000	3.60
1937-38	7,500	70	525,000	4.00	2,100,000	3.00
1938-39	9,000	85	765,000	4.15	3,175,000	3.11
1939-40	7,200	70	504,000	4.65	2,344,000	3.49
1940-41	5,500	70	384,000	5.70	2,194,000	4.28
1941-42	5,000	70	350,000	6.50	2,275,000	4.88
1942-43	2,600	60	156,000	9.60	1,498,000	7.20
1943-44	1,400	70	98,000	11.30	1,107,000	8.47
1944-45	2,050	70	144,000	10.70	1,541,000	8.03
1945-46	2,800	80	224,000	10.55	2,363,000	7.92
1946-47	4,750	65	309,000	12.10	3,739,000	9.08

*Now shipped almost exclusively in 36-pt.crates. The 24-qt. crate was formerly used, and it is continued here for statistical purposes.

WATERMELONS

Season	Acreage	Yield Melons	Production 1000 melons		Price per 1000 melons	FOB Packed Total Value
1929-30	34,700	300	10,410	A/(937)	$250	$2,368,000
1930-31	31,000	330	10,230		200	2,046,000
1931-32	28,500	200	5,700		160	912,000
1932-33	22,500	220	4,950		200	990,000
1933-34	23,400	180	4,212		185	779,000
1934-35	20,000	330	6,600		110	726,000
1935-36	16,000	280	4,480		200	896,000
1936-37	19,500	300	5,850	A/(390)	240	1,310,000
1937-38	22,500	310	6,975	A/(675)	150	945,000
1938-39	22,600	240	5,424		180	976,000
1939-40	23,500	290	6,815		175	1,193,000
1940-41	25,500	270	6,885		210	1,445,850
1941-42	22,000	325	7,150		225	1,609,000
1942-43	12,500	325	4,063		650	2,641,000
1943-44	25,500	305	7,778		655	5,095,000
1944-45	39,000	260	10,140		485	4,918,000
1945-46	47,000	225	10,575		525	5,552,000
1946-47	47,000	290	13,623		447	5,419,000

A - Not harvested due to economic abandonment. Not included in total value figures. The average carload is usually figured at 1000 melons but new varieties of round type melons have lowered this average to 935-940 melons, many in 3 tiers.

All 1946-47 acreage figures are preliminary as of September 20, 1947 and are subject to revision.

UNITED STATES: Total Orange Production-By States-
Census Years 1889, 1899, 1909 & Yearly 1919-1946
Bureau of Agricultural Economics

Crop Year		CALIF.#	FLA.#	TEX.#	ARIZ.#	ALA.#	LA.#	MISS.#	TOTAL
		Thousand Boxes							
1889		1,245	3,147	--	--	--	--	--	4,392
1899		5,882	273	--	11	1/ --	11	--	6,167
1909		14,440	4,888	11	33	1	152	5	19,530
1919		16,632	8,000	9	80	20	37	31	24,809
1920		23,771	9,400	5	60	82	42	25	33,385
1921		14,021	8,400	5	80	82	50	30	22,668
1922		21,283	10.900	10	81	190	60	45	32,569
1923		24,153	13,700	6	86	225	75	55	38,300
	Average	19,972	10,080	7	77	120	53	37	30,346
1924		18,506	11,300	17	60	2	75	--	29,960
1925		24,200	10,200	12	86	130	100	27	34,755
1926		28,252	11,000	41	75	75	150	42	39,535
1927		22,737	9,500	85	54	110	200	50	32,736
1928		39,159	16,500	125	99	65	220	30	56,218
	Average	26,571	11,700	56	75	80	149	30	38,661
1929		21,195	9,800	261	137	212	187	37	31,829
1930		35,179	19,200	250	139	3	287	2	55,060
1931		34,658	14,200	520	145	80	245	54	49,902
1932		34,265	16,400	325	147	120	278	80	51,615
1933		28,439	17,900	430	155	3	245	2	47,174
	Average	30,747	15,500	357	145	84	248	35	47,116
1934		45,047	17,600	650	170	140	293	88	63,988
1935		32,809	18,000	777	240	2	244	1	52,073
1936		29,827	22,100	2,000	220	56	309	26	54,538
1937		45,914	26,200	1,440	350	76	238	67	74,285
1938		41,420	33,300	2,815	430	96	385	85	78,531
	Average	39,003	23,440	1,536	282	74	294	53	64,683
1939		44,404	28,000	2,360	520	75	226	59	75,646
1940		50,695	31,300	2,650	528	1	253	-	85,427
1941		52,155	29,300	2,850	660	5	192	1	85,163
1942		44,329	41,400	2,550	730	*	340	*	89,349
1943		51,961	49,800	3,550	1,100	-	240	-	106,651
1944		60,500	46,800	4,400	1,150	-	360	-	113,210
1945		44,010	54,000	4,800	1,210	-	330	-	104,350
1946		53,700	2/ 58,400	5,000	1,200	-	410	-	118,710

- - - - - - - - -

FLORIDA PRODUCTION-SEGREGATED-EARLY & MID-SEASON, VALENCIAS & TANGERINES

Crop Year	Early & Mid-season	Valencias	Tangerines	Total Production
	1,000 boxes	1,000 boxes	1,000 boxes	1,000 boxes
1933-34	9,500	6,400	2,000	17,900
1934-35	10,700	4,900	2,000	17,600
1935-36	9,600	6,300	2,100	18,000
1936-37	11,700	7,400	3,000	22,100
1937-38	13,400	10,500	2,300	26,200
1938-39	17,150	12,750	3,400	33,300
1939-40	15,600	10,000	2,400	28,000
1940-41	16,200	12,400	2,700	31,300
1941-42	15,200	12,000	2,100	29,300
1942-43	19,100	18,100	4,200	41,400
1943-44	25,800	20,400	3,600	49,800
1944-45	21,700	21,100	3/ 4,000	46,800
1945-46	25,400	24,400	4,200	54,000
1946-47	30,500	23,200	4,700	2/ 58,400

1/ 500 boxes or less.
2/ Includes economic abandonment: Early & Midseason, 900,000 boxes: Tangerines, 800,000 boxes.
3/ Includes economic abandonment: Tangerines, 150,000 boxes.
* Negligible.
# Includes tangerines.

INTERSTATE TRUCK DISTRIBUTION, FLORIDA CITRUS, 1946-47 SEASON

(Made available thru the courtesy of the State Dept.of Agriculture, Winter Haven,Fla.)
Oct. 1, 1946 to June 15, 1947, Inclusive.

Destinations	Oranges	Grapefruit	Tangerines	Total
Alabama	312,177	22,983	27,367	362,527
Arizona	230	40	-	270
Arkansas	21,774	1,295	103	23,172
Connecticut	1,214	404	232	1,850
Delaware	12,080	626	926	13,632
Dist. of Columbia	44,425	6,330	8,701	59,456
Georgia	891,471	128,052	92,472	1,111,995
Illinois	84,565	9,778	11,159	105,502
Indiana	159,612	16,041	14,697	190,350
Iowa	3,257	8	-	3,265
Kansas	3,769	256	1,193	5,218
Kentucky	45,672	2,149	6,237	54,058
Louisiana	19,653	427	2,083	22,163
Maine	390	-	-	390
Maryland	152,868	27,628	34,267	214,763
Massachusetts	3,158	319	208	3,685
Michigan	50,019	4,925	8,805	63,749
Minnesota	152	-	-	152
Mississippi	56,154	1,990	5,012	63,156
Missouri	12,952	2,970	2,779	18,701
Nebraska	-	-	540	540
New Jersey	14,551	2,162	1,235	17,948
New York	92,099	16,634	17,584	126,317
North Carolina	407,520	52,141	60,753	520,414
Ohio	47,322	6,978	10,732	65,032
Oklahoma	625	-	398	1,023
Pennsylvania	100,904	16,352	15,031	132,287
Rhode Island	965	466	950	2,381
South Carolina	336,406	43,133	45,922	425,461
Tennessee	148,999	16,765	13,537	179,301
Texas	47,069	6,071	2,564	55,704
Virginia	165,546	46,705	30,583	242,834
West Virginia	42,432	4,116	7,458	54,006
Wisconsin	3,117	159	203	3,479
Out of State	7,864	1,622	796	10,282
Canada	19,340	4,877	5,293	29,510
Grand Total	3,310,351	444,402	429,820	4,184,573
Florida-North West *	121,759	23,555	7,989	153,303

* North West Florida is shown as it is beyond the Road Guard Stations located along the Suwannee River. Some of this fruit destined to North West Florida finally goes out of the State.

RECAPITULATION OF RAIL DISTRIBUTION, FLORIDA CITRUS FRUITS
BY STATES - 1946-47 AND 1945-46 SEASONS

STATE	ORANGES		GRAPEFRUIT		TANGERINES		MIXED CITRUS		GRAND TOTAL	
	46-47	45-46	46-47	45-46	46-47	45-46	46-47	45-46	46-47	45-46
	Rail & Boat	Rail Only	Rail & Boat	Rail Only	Rail-Boat	Rail Only	Rail & Boat	Rail Only	Rail & Boat	Rail Only
	Cars	Cars	Cars	Cars	Cars	Cars	Cars	Cars	Cars	Cars
Alabama	922	876	104	77	6	23	293	504	1,325	1,480
Arkansas	129	87	6	1	-	2	13	14	148	104
California	-	3	-	-	-	1	-	-	-	4
Colorado	7	27	13	3	8	12	2	1	30	43
Connecticut	1,081	706	205	94	96	86	52	147	1,434	1,033
Delaware	18	45	-	-	-	-	1	5	19	50
Dist. of Columbia	937	742	350	286	22	42	49	149	1,358	1,219
Florida	34#	178#	31#	129#	-#	-#	14#	26#	79#	333#
Georgia	996*	1,030*	218*	184*	29*	22*	303*	507*	1,546*	1,743*
Idaho	-	1	2	3	-	-	-	1	2	5
Illinois	2,416	1,986	326	253	200	200	252	331	3,194	2,770
Indiana	675	530	51	40	22	30	70	140	818	740
Iowa	108	97	35	19	1	10	9	6	153	132
Kansas	36	44	6	4	3	9	1	1	46	58
Kentucky	688	706	70	70	17	23	116	230	891	1,029
Louisiana	457	411	30	31	1	28	32	57	520	527
Maine	137	126	15	13	1	1	22	25	175	165
Maryland	1,851	1,499	607	449	117	129	213	414	2,788	2,491
Massachusetts	3,069	2,411	928	671	243	183	405	634	4,645	3,899
Michigan	1,727	1,280	368	248	211	154	239	232	2,545	1,914
Minnesota	183	116	56	30	24	21	14	44	277	211
Mississippi	397	442	1	4	1	2	62	78	461	526
Missouri	665	500	69	52	46	73	53	73	833	698
Montana	2	3	6	10	-	-	-	2	8	15
Nebraska	46	48	25	6	6	8	5	7	82	69
New Hampshire	10	8	-	2	-	-	3	11	13	21
New Jersey	1,287	1,555	318	385	25	85	57	182	1,687	2,207
New York	12,995	8,772	6,053	4,342	1,190	870	1,703	2,903	21,941	16,887
North Carolina	1,217	1,344	201	199	18	50	443	649	1,879	2,242
North Dakota	5	4	2	3	-	-	-	1	7	8
Ohio	3,470	2,609	466	288	301	365	471	506	4,708	3,768
Oklahoma	42	59	18	7	4	8	2	6	66	80
Oregon	7	39	18	40	4	11	2	5	31	95
Pennsylvania	5,723	4,688	1,603	1,293	628	605	768	1,225	8,722	7,811
Rhode Island	468	369	80	68	36	36	35	85	619	558
South Carolina	767	632	62	47	13	18	344	563	1,186	1,260
South Dakota	3	1	4	-	-	-	1	1	8	2
Tennessee	1,683	1,365	116	87	50	71	443	628	2,292	2,151
Texas	89	127	20	2	4	15	2	4	115	148
Utah	8	14	14	20	-	-	1	1	23	35
Vermont	49	24	4	3	-	-	16	19	69	46
Virginia	932"	676*̲	246"	171*̲	12"	13*̲	313"	412*̲	1,503"	1,272*̲
Washington	12	57	35	39	5	10	1	6	53	112
West Virginia	397	368	29	31	8	17	162	249	596	665
Wisconsin	293	266	53	63	5	12	57	82	408	423
Wyoming	1	.5	3	-	-	1	-	-	4	6
CANADA	671	598	479	456	127	187	66	144	1,343	1,385
TOTAL	46,710	37,474	13,346	10,223	3,484	3,433	7,110	11,310	70,650	62,440

# - Includes Jacksonville.

" - Petersburg not included.

* - Does not include Savannah.

*̲ - Petersburg and Richmond not included.

CITRUS TRUCKED THROUGH FLORIDA ROAD GUARD STATIONS

1946-47 Season - Oct.1-June 15
(Tabulated from records of Florida Citrus Inspection Bureau)

	Wilcox US 19	Branford Fla.5A	Ellaville US 90	Suwannee Spgs Fla.50	White Spgs. US 41	Hilliard US 1	Yulee US 17	Lake City Fla.82	Total Passings
Oranges	1,647	27	207	27	2,401	1,142	3,094	31	8,576
Grapefruit	153	4	39	4	299	180	489	3	1,171
Tangerines	137	2	17	3	287	83	565	2	1,096
Total	1,937	33	263	34	2,987	1,404	4,148	36	10,743

INSPECTIONS FOR INTERSTATE TRUCK SHIPMENTS					PASSINGS THRU ROAD GUARD STATIONS			
1946-47 Season	Oranges	Grapefruit	Tangerines	Total	Oranges	Grapefruit	Tangerines	Total
August	LCL	1	-	1	-	-	-	-
September	8	166	-	174	-	-	-	-
October	863	167	LCL	1,030	833	142	LCL	975
November	801	129	175	1,105	733	103	164	1,000
December	1,558	120	381	2,059	1,575	106	378	2,058
January	1,221	185	416	1,822	1,164	159	393	1,716
February	1,112	169	131	1,412	1,107	147	138	1,391
March	1,412	183	19	1,614	1,397	157	LCL	1,576
April	933	187	LCL	1,120	922	160	-	1,082
May	655	158	LCL	813	640	146	-	786
June	346	95	-	441	June to 15th 206	51	-	257
July	58	25	-	83	-	-	-	-
Total	8,967	1,585	1,122	11,674	8,576	1,170	1,095	10,841

PRICES OF GRAINS AND EGGS AND POULTRY 1929-46

By: F. W. Risher, Poultry & Dairy Specialist
Florida State Marketing Bureau

U.S. average farm prices for the grains and materials used in making feed for poultry compared with the Jacksonville average wholesale prices on Florida eggs and liveweight poultry.

	Wheat Price per Bu.	Corn Price per Bu.	Oats Price per Bu.	Tankage price per Ton	Jacksonville Wholesale Mkt. Eggs-White Fla.-24 oz. Avg.per Doz.	Jacksonville Wholesale Mkt. Fryers Heavy Avg.per Lb.
1929	$1.03	$0.80	$0.42	$ -	41.5¢	36.1¢
1930	.67	.60	.32	-	35.5	30.9
1931	.39	.32	.21	-	27.9	30.6
1932	.38	.31½	.16	-	23.5	21.0
1933	.74	.52	.33	-	23.7	18.2
1934	.85	.81	.48	-	29.3	21.2
1935	.83	.66	.26	48.15	32.6	23.0
1936	1.02	1.04	.45	55.69	32.3	23.7
1937	.96	.52	.30	46.01	31.2	24.4
1938	.56	.49	.24	52.57	30.7	23.8
1939	.69	.57	.31	49.66	27.4	22.3
1940	.68	.62	.30	53.14	29.2	22.0
1941	.94	.75	.41	73.28	34.5	23.1
1942	1.10	.92	.49	74.55	39.7	27.4
1943	1.36	1.12	.72	74.55	47.6	31.0
1944	1.41	1.09	.71	74.55	47.6	30.9
1945	1.49	1.14	.67	74.55	50.0	31.6
1946	1.53	1.16	.72	74.65	51.1	37.2
1947 (Un-official)	2.85	2.45	1.10	-	74	37

The 1947 average for 24 oz. eggs will likely be around 73¢ per dozen, and for heavy breed fryers around 37¢ a pound.

Florida producers do not, of course, get grain from Kansas or Iowa at farm prices. They are buying mixed feed at $5.70-6.30 per 100 pounds with prospects of higher prices. Florida producers generally get a lower price than the Jacksonville quotations.

Dup

FLORIDA STATE MARKETING BUREAU

ANNUAL FRUIT AND VEGETABLE REPORT

PRODUCTION, TRANSPORTATION AND MARKETING ANALYSIS

1947-48 SEASON

(Also Poultry, Egg, Livestock, Tobacco and Field Crop Statistics)

By Frank H. Scruggs, Market News Specialist

Neill Rhodes, Commissioner
Florida State Marketing Bureau
Division of
Florida State Department of Agriculture
Nathan Mayo, Commissioner

This Annual Report is available free of charge to parties interested

Released October 11, 1948

Florida State Marketing Bureau
505 West Adams Street
P. O. Box 779
Jacksonville 1, Florida

ACKNOWLEDGMENT

We wish to acknowledge the splendid cooperation we received from both official and private sources during the preparation of this rather comprehensive statistical report.

The rail freight and express carlot shipment figures were secured from the Fruit and Vegetable Branch of the Production and Marketing Administration, U.S. Department of Agriculture in Washington, D.C.

Exhaustive vegetable acreage, yield, production and value data and other assistance was supplied by Mr. J. C. Townsend, Jr. and Mr. J. B. Owens, Agricultural Statisticians, and Mr. G. N. Rose, Truck Crop Statistician, U.S. Bureau of Agricultural Economics, Federal Building, Orlando, Florida.

Mr. A. L. Scarborough, Statistician of the Citrus and Vegetable Division, Florida Department of Agriculture, Winter Haven, Florida, supplied us with important record data and other information. Mr. Hugh Flynt, Assistant Director of this division, supplied a detailed summary of inspections for the season. The daily reports from their Road Guard Stations, operated by the Citrus and Vegetable Divisio showing passings of fruits and vegetables, were very helpful to shippers and growers throughout the season and for record purposes in this report.

Mr. H. F. Willson, Federal-State Citrus Market News Service, also supplied useful data for use in this report.

Mr. H. G. Clayton, Director of Agricultural Extension Service, Gainesville Florida, prepared an interesting article on government price supports.

Mr. LaMonte Graw, Manager of the Florida Fruit and Vegetable Association, prepared an article on the farm labor situation.

Mr. William B. Conner, of the Florida Citrus Exchange, Tampa, wholeheartedly complied with our requests for specified citrus information.

Several official and private agencies and individuals not already mentione supplied information directly or indirectly to us, for which we extend our thanks.

The preparation of this report is tedious and requires long and hard work, and appreciation by the writer is extended to our Bureau staff for their efforts an accomplishments. Mr. L. H. Lewis, Specialist, Live Stock and Field Crops, and Mr. Gifford N. Rhodes, Specialist, Live Stock Market News, of this Bureau, supplied certain livestock information.

- - - - - - -

Comments which would lead to the improvement of this Annual Report would be appreciated. We have never gotten any suggestions for improving this report and therefore we suspect that no one reads this page.

GENERAL TABLE OF CONTENTS

Citrus Fruits Only (Oranges, Grapefruit and Tangerines)

Page Number

Citrus Acreage, Yield per Acre, Yield per Tree and Prices Received 4
Volume and Value Analysis of Citrus for 1947-48 Season 6-7
Canners' Prices for Delivered Citrus and Volume Canned by Seasons 10
Tree to Auction Costs or Vice Versa, for Last 3 Seasons 11
Interstate Truck Distribution by States 1947-48 Season 14
Rail Distribution of Citrus by States for 2 Seasons 15
Volume and Value Analysis of Citrus by Years 1927-28 to 1947-48 (21 Years) 16-23
Inspections of Citrus, Including Limes, by Counties 37
Auction Sales 18 Seasons 1930-31 to 1947-48 40-42
Florida F.O.B. Sales Averages 1909-10 to 1947-48 Seasons 43
Citrus Price Analysis 1932-33 to 1947-48 Seasons 44-45
Bearing Acreage of Citrus by Counties 3 Seasons 76-77
Production of Citrus by Florida, California, Texas, and other States 86
Citrus Trees Moving from Nurseries 1946-47 Season 87
Citrus Trucked Through Road Guard Stations and Truck Shipments by Months 88

Vegetables and Miscellaneous Fruits Only

Acreage, Yield, Production and Value of 1947-48 Season (U.S. Dept. of Agri.) 12-13
Truck Shipments by Weeks for 1947-48 Season 38-39
Gross F.O.B. Packed Value 16 Seasons 61
Acreage of Principal Truck Crops for 23 Seasons (2-page summary) 62-63
Acreage, Yield and Value Selected Commodities by Seasons 1929-30 to 1947-48 64-68
Fall, Winter and Spring Acreage by Counties for 3 Seasons 78-85

All Fruits and Vegetables

General Summary of the 1947-48 Season by F. H. Scruggs 1-2
Florida's Farm Labor Situation (Article by LaMonte Graw) 3-4
Production and Value for 14 Seasons 5
Disposition of Units of Production and of Carloads According to Uses 8-9
Transportation-Freight, Express, Boat and Truck by Months-1947-48 Season 24-27
Transportation-Freight, Express, Boat and Truck 10 Seasons 28-31
Transportation-Rail Freight Carloads by Counties of Origin 32-35
Federal-State Inspections by Commodities 1947-48 Season 36
County Fruit and Vegetable Value Formula (By F. H. Scruggs) 48
Weather Conditions and Production 1947-48 Season (By J. C. Townsend, Jr.) 60
Acreage by Counties, All Fruits and Vegetables, 3 Seasons 70-77

General Agricultural Statistics

Government Price Supports (Article by H. G. Clayton) 46-47
General Crop Statistics 1920-1948 (Crop, Cotton, Peanuts, etc.) 49-51
Tobacco - Production, Value and Auction Data by Seasons 52
Egg and Poultry Prices, Jacksonville 1921-48, Tampa and Miami 1939-48 53-55
Livestock, General Facts of Industry (By L.H.Lewis and Gifford N. Rhodes) 56-57
Livestock Prices in Jacksonville and Southeast, 1930 to 1948 58-59
Average Prices Received September 15 with Comparison 69

FLORIDA DEPARTMENT OF AGRICULTURE
STATE MARKETING BUREAU
1947-48
ANNUAL FRUIT AND VEGETABLE REPORT

By Frank H. Scruggs, Market News Specialist

VOLUME AND VALUE OF ALL FRUITS AND VEGETABLES

The first paragraph of our last year's (1946-47) Annual Report was as follow to wit: "Another eventful crop season has passed but the beginning of the 1947-48 season is so upset as these words are written, October 17, 1947, that it barely seems useful to go into the history of the 1946-47 season, which was only moderately and unevenly successful." We can say almost the same thing for 1947-48 season this October 12, 1948, and for the 1948-49 season getting underway.

We had two hurricanes in the fall of 1947 and two lesser ones in late September and early October of this year. We had more water spread over Florida in October 1947 than in October 1948, but we have far more than we need right now. The vegetabl plantings in South Florida are being greatly delayed. This is true to a lesser extent in some other vegetable sections of Florida.

There is little good to say about the season just passed except to say it could have been a little worse for citrus and much worse for vegetables.

We had a net of 10¢ per box on citrus last season which was the lowest since the 1938-39 season when we had 7¢ and in the 1932-33 season when we had 2¢ net. Taxes and interest on investment should be deducted from this net which makes the 1947-48 citrus crop a total loss as far as the average grower is concerned. All he did was to work for nothing for a lot of people. Too much citrus is going to the canner at a low price to be sold later in cans at a price far too low for the good of fresh citrus. On the other hand the retailer is charging the consumer too much for fresh citrus. Some of them work on a 100 per cent markup. If 33 per cent was enough before the war certainly 40 per cent seems enough now.

RECORD VOLUME IN 1947-48 SEASON

Florida produced and utilized 297,984 carloads of fruits and vegetables last season as compared to 262,992 carload equivalent in the 1946-47 season. The gross fob value was however only $214,742,000 compared to $246,700,000 for the 1946-47 season.

Citrus alone accounted for 214,045 carloads produced at a gross fob value of only $114,925,000. The average price on carload basis was 30 per cent off from average for 1946-47 season.

Vegetables, strawberries and watermelons accounted for 83,939 carloads with a gross value of $99,817,000 compared to 72,262 carloads and $102,144,000 for the 1946-47 season. They were off 15% from average price in 1946-47 season.

Similar information to that above may be found on page 5 of this report covering all the seasons from 1934-35 to date.

Instead of using up several pages to express his own ideas, the writer has called in some of the experts of the State to say a few words.

LaMonte Graw, manager of the Florida Fruit and Vegetable Assn., a non-profit organization, formerly the Florida Vegetable Committee, gives us a summary of the Florida Farm Labor Situation. He says that long experience has shown that higher wag rates (to certain kinds of farm workers) usually reduce rather than encourage efficiency and reliability. This is an interesting observation and there are more interesting thoughts in his article. Turn to page 3 later on.

H. G. Clayton, Director of the Agricultural Extension Service, one of the foremost leaders of agriculture in Florida, agreed to discuss in question and answer form, Price Support, Parity, "Steagall" commodities, etc. If you cannot name the six basic commodities and the Steagall commodities and do not know the definition of parity you should turn to page 46 of this report. This Annual Report is used by a large number of students, amateur & professional economists, and also research specialists, and I am sure many of them will be pleased to have these answers where they can find them easily. This stuff is hard to remember, much less recollect.

Some questions and answers on Florida livestock prepared by L. H. Lewis and Gifford N. Rhodes, Livestock Specialists of the State Marketing Bureau, can be found on page 56. You know, of course, that Florida ranks 14th in beef or range cattle, 35th in dairy cattle and 25th in total cattle. There is a lot of misinformation on the ranking of Florida in cattle production. We are making rapid progress, but we are not pushing Texas out of the picture yet. There is perhaps more probability of great expansion in livestock than in any other Florida agricultural activity.

J. C. Townsend, Jr., U.S. Agricultural Statistician, in charge of Florida's Crop Reporting Service, discusses the Production of Florida Fruits and Vegetables as affected by Weather Conditions during the 1947-48 Season. When he gives you some agricultural facts its better than a tip right from the feed bag. See page 60.

- - - - - - - - - -

1947-48 PRICES COMPARED WITH THE 1946-47 AND 1945-46 SEASONS

The following tabulation shows the f.o.b. Florida gross packed value of some of the commercial fruits and vegetables in Florida.

Florida Commodities	Unit	FOB Unit Value 1947-48	FOB Unit Value 1946-47	FOB Unit Value 1945-46	Volume Produced ** 1947-48	Volume Produced ** 1946-47	Volume Produced ** 1945-46
					(Thousands omitted)		
Beans, fresh mkt.	Bu.	$ 2.57	$ 2.90	$ 2.70	5,315	5,749	7,355
Beans, for processing	Ton	96.70	116.00	111.44	-	-	-
" " "	Bu.	1.54	1.67	1.67	583	801	1,114
Beans, all uses	Bu.	2.55	2.74	2.54	5,898	6,550	8,469
Limas	Bu.	3.00	3.51	3.28	387	338	555
Cabbage	Ton	52.50	37.80	49.00	145	99	116
Celery	Crts.	2.05	3.84	2.26	5,651	4,564	6,439
Cucumbers	Bu.	3.25	4.14	3.72	1,957	1,204	1,520
Eggplant	Bu.	1.65	2.42	1.63	894	725	1,344
Escarole	Hprs.	1.05	1.30	1.20	1,376	910	935
Lettuce, Boston & Rom.	4-6 doz crts.	2.05	2.95	3.00	69	70	142
Lettuce, Iceberg	4-6 doz crts.	2.88	2.96	3.60	130	189	210
Peas, English	Bu.	2.55	2.95	3.00	36	64	118
Peppers	Bu.	2.17	4.14	2.45	2,860	2,193	3,050
Potatoes	Bu.	2.79	2.00	1.95	3,614	2,738	6,010
Tomatoes, fresh mkt.	Bu.	6.32	6.50	5.25	3,588	2,892	4,458
Tomatoes, fresh mkt.	Lug basis*	3.80	3.90	3.15	-	-	-
Tomatoes, processing	Ton	28.50	37.90	26.90	-	-	-
" "	Bu.	.75	1.00	.70	346	306	212
Tomatoes, all	Bu.	5.83	5.97	5.04	3,934	3,198	4,670
Carrots, Winter	Bu.	3.00	1.05	.85	90	80	230
Cauliflower, Winter	Crts.	2.20	1.75	2.25	80	120	150
Cantaloupes	Jumbo Crts.	4.35	2.55	3.00	78	40	36
Strawberries	36-pt Crts.	7.95	9.07	7.91	189	300	224
Watermelons	1000-Melon	500.00	447.00	525.00	13,725	12,123	10,575
Oranges	Boxes	$ 1.41	$ 1.93	$ 3.25	58,400	53,700	49,800
Grapefruit	Boxes	.82	1.25	1.77	33,000	29,000	32,000
Tangerines	Boxes	2.41	2.99	4.24	4,000	4,700	4,200
All Citrus		1.26	1.76	2.75	95,400	86,400	86,000

* The tomato lug has a net weight approximately 60 per cent of the weight of a bushel.

** These total volumes included any volumes abandoned because of markets too low to justify harvesting. Considerable volume was abandoned during the past two years. See pages 64-68 for more details.

- - - - - - - - - -

The Florida citrus forecast as follows as of October 10 for 1948-49 Season is as follows: Oranges 64,000,000, Grapefruit 31,000,000, and Tangerines 4,000,000, a total of 99,000,000, 1-3/5 bu boxes.

FLORIDA'S FARM LABOR SITUATION

By: LaMonte Graw, Secy.-Mgr.
Florida Fruit and Vegetable Association
(Formerly the Florida Vegetable Committee)

Prior to World War II, farm wage rates in Florida were low -- $1.60 to $2.00 per day. The workers available were for the most part younger, stronger and more willing to work than those who are now paid $5.00 per day and upward -- and fa more for piece rates when harvesting. In spite of these low wage rates, many pre-war farms did not survive, because of the small profit margin between cost and selling price.

During the war many of the best workers went to industry, thus reducing th supply at a time when Florida's farm labor needs were increasing 50% or more. Thos who remained were less able to perform field tasks, or to learn new ones, and coul make enough in two or three days to carry them through the week. They worked short hours, and produced less per man, because they lacked the vital necessity of working full time to obtain the week's cash requirements.

From the standpoint of the nation's economy, it is difficult to justify wages as low as $2.00 per day, even in pre-war dollars. Yet the fact remains that few Florida vegetable producers grossed sufficient income from their products befor 1942 to have permitted them to pay higher wages for the services performed.. If a grower had offered higher wage rates, without a corresponding increase in efficienc or worker output, he would soon have gone broke.

Despite these wage increases that provide the opportunity for a good farm hand to earn from $40 to $100 per week on vegetable farms, the average Florida farm worker has shown little initiative or desire for economic advancement, or to accumulate funds. Higher wages have meant merely that he worked fewer hours for th dollars to pay for that week's needs.

Some industries have been able to reduce their unit costs by cutting the number of hours worked and increasing wage rates. This has been true where labor saving equipment was used, and conditions permitted the employer to adopt better production practices. During the past ten years many Florida growers have adopted improved practices that materially reduced the number of man-hours of labor require but this reduction is in large measure offset by the higher wage rates and worker inefficiency, resulting in unit costs often being higher than before labor saving devices were purchased.

This was not important during the war years, when good prices prevailed f all products, including some that should have gone to the cull bin. A seller's market permitted the grower to ignore sound business practices and still make a profit. Such will not be the case in the future.

Production of fresh vegetables over widely separated areas in the United States, Cuba and Mexico, has increased to a point where the nation's markets can be kept constantly over-supplied except after major disasters. Unless the Florida producer can reduce his cost per unit of marketable products, he cannot long expect to compete with Texas, Cuba and Mexico, which have far lower labor costs, or with California, whose higher wage rates are offset by higher yields.

So long as national employment and living costs are high (and prices for Florida products will drop before wages) there is little likelihood that the wages paid Florida farm workers will be materially lowered, in spite of their inefficienc They may even rise during the present shortage.

The Florida producer can lower his unit production cost through the more efficient use of more efficient and reliable workers. To attract this type of worker, or to induce those we have now to do better, we must offer incentives other than the pay, for long experience has shown that higher wage rates usually reduce rather than encourage efficiency and reliability.

The Florida State and U.S. Employment Services are seeking to recruit sufficient workers to produce and harvest our crops, but they cannot compel or indu the worker to accept employment when offered. The Florida Fruit and Vegetable Association, through its labor division, is providing more than 1½ million man hour of supplementary Bahaman labor. The latter is not a permanent solution to the problem, for there are economic and political reasons why the use of foreign worker cannot be continued beyond the present emergency. When they leave, farmers may find themselves unable to get sufficient labor.

Improvement of the Florida farm labor situation, so that the farmer can afford to pay today's wage rates and stay in business, and continuance of the almost total absence of labor strife that has been the history of the Florida vegetable industry, are largely dependent on the development of a procedure which gives both the worker and the employer greater assurance that their mutual needs will be met. It must be a program that "recognizes" the worker as an individual and not as "just another migrant;" it must reward him for effort and accomplishment -- in addition to his pay; competent workers must be given greater consideration than those of lesser skills and willingness, including assurance of the best available housing, maximum opportunity for employment, and other incentives that will encourage him to be more diligent, more interested in his work, more reliable and thrifty, and more desirous of improving his skills. And it must provide the grower with a dependable working force than can enable him to grow and harvest his crops with a minimum of delay and a maximum of efficiency.

Individual farmers, who employ migrants for only short periods during each season, can greatly improve their methods of handling farm workers, but they cannot provide them with adequate incentives and rewards to keep up the interest of the worker. Continuity of contact with the individual worker, to assure that he is sufficiently "recognized" and rewarded for merit, is possible only through a central organization which can maintain records from season to season, and make certain that the worker gets his just dues, no matter where he may be employed.

With these factors before it, Florida Fruit and Vegetable Association's Labor Committee is studying various methods of attaining the desired results, and it is hoped they can be developed and put into operation soon enough to aid the grower in meeting the labor shortage anticipated for 1948-49. END.

CITRUS ACREAGE, YIELD PER ACRE AND TREE, AND PRICE RETURN

					All Fruit			
Season	Acres	Total Production in 1-3/5Bu Box	Box Yield Per Acre	Boxes Yield Per Tree	Gross Return Box	Net Return Box	Unsold Abandoned Boxes	Net Dollars Per Acre
ORANGES								
1942-43	246,340	37,200,000	151	2.3	$2.72	$1.45	-	$ 219
1943-44	251,340	46,200,000	184	2.8	2.81	1.31	-	241
1944-45	256,340	42,800,000	167	2.5	3.17	1.73	-	289
1945-46	264,900	49,800,000	188	2.8	3.25	1.84	-	346
1946-47	270,000	53,700,000	199	3.0	1.93	.50	900,000	995
1947-48	280,500	58,400,000	208	3.2	1.41	.15	-	31
GRAPEFRUIT								
1942-43	94,390	27,300,000	289	4.4	1.48	.67	-	194
1943-44	95,190	31,000,000	326	4.9	1.83	.92	-	300
1944-45	90,000	22,300,000	248	3.8	2.24	1.36	-	337
1945-46	90,500	32,000,000	354	5.4	1.77	.78	-	276
1946-47	91,000	29,000,000	319	4.8	1.25	.26	2,600,000	83
1947-48	93,000	33,000,000	355	5.4	.82	-.01	3,700,000	- 3½
TANGERINES								
1942-43	23,419	4,200,000	179	2.7	2.72	.98	-	175
1943-44	23,419	3,600,000	154	2.3	3.62	1.36	-	209
1944-45	23,419	4,000,000	171	2.6	4.13	1.91	150,000	327
1945-46	23,549	4,200,000	178	2.7	4.24	2.10	-	374
1946-47	23,705	4,700,000	198	3.0	2.92	.90	800,000	178
1947-48	23,800	4,000,000	168	2.5	2.41	.20	600,000	34
TOTAL CITRUS								
1942-43	364,149	68,700,000	189	2.9	2.23	1.11	-	210
1943-44	369,949	80,800,000	218	3.3	2.47	1.16	-	253
1944-45	369,759	69,100,000	187	2.8	2.93	1.62	150,000	303
1945-46	378,949	86,000,000	227	3.4	2.75	1.46	-	331
1946-47	384,705	87,400,000	227	3.4	1.76	.44	3,400,000	100
1947-48	397,300	95,400,000	240	3.6	1.26	.10	4,300,000	24

There are several reasons why the production per tree has increased. One reason is that the bearing surfaces of the trees have been increasing each year. Some of the non-bearing acreage set out during the war may reduce the average per tree during the next few years as it comes into bearing. Another reason for increased production per tree is better grove care. Some say the groves have been pushed.

The Net Return is the net after production costs and all other costs except taxes, interest on investment, and depreciation on equipment.

FLORIDA PRODUCTION AND VALUE FOR 14 SEASONS
(Includes Canned and Locally Consumed)

ALL CITRUS

Season	Carloads Production	Boxes	Florida Gross Value	Gross	Weighted Average All Production & Marketing	Net*
1934-35	82,865	32,835,854	$42,797,752	$1.33	$1.06	.27
1935-36	74,491	29,462,052	53,189,191	1.81	1.12	.69
1936-37	102,827	40,601,208	68,838,758	1.70	1.09	.61
1937-38	103,964	40,939,629	53,285,352	1.30	1.08	.22
1938-39	143,369	56,447,995	58,646,931	1.04	.97	.07
1939-40	107,119	42,973,112	50,365,127	1.17	1.05	.12
1940-41	140,903	55,890,754	64,192,695	1.15	.99	.16
1941-42	120,089	48,400,000	80,572,620	1.66	1.09	.57
1942-43	154,909	68,700,446	153,032,989	2.23	1.12	1.11
1943-44	181,592	80,800,000	199,688,696	2.47	1.31	1.16
1944-45	156,759	69,000,000	201,912,530	2.93	1.31	1.62
1945-46	197,050	86,000,000	236,230,700	2.75	1.29	1.46
1946-47	190,730	83,100,000	146,565,580	1.76	1.32	.44
1947-48	214,045	91,100,000	114,925,000	1.26	1.16	.10

ALL VEGETABLES

Season	Carloads Production	Florida Gross Value
1934-35	48,411	$30,134,054
1935-36	45,718	30,666,719
1936-37	51.885	34,445,922
1937-38	70,000	37,306,680
1938-39	63,506	38,489,172
1939-40	65,151	37,962,385
1940-41	58,560	43,077,816
1941-42	70,191	57,417,670
1942-43	63,221	81,823,200
1943-44	70,219	87,328,394
1944-45	69,225	99,441,550
1945-46	76,943	116,239,000
1946-47	58,049	91,618,000
1947-48	68,670	89,237,000

ALL VEGETABLES & MISCL. FRUITS

Carloads Production	Florida Gross Value
57,306	$33,936,126
52,670	34,144,707
60,118	39,090,756
82,130	41,410,710
77,606	43,573,732
75,404	42,738,720
66,486	48,562,482
80,219	62,706,220
69,445	87,555,990
79,605	94,944,402
81,213	107,673,150
89,377	128,099,000
72,262	102,144,000
83,939	99,817,000

ALL FRUITS AND VEGETABLES

Season	Carloads Production	Florida Gross Value
1934-35	140,171	$ 77,156,615
1935-36	127,181	76,733,879
1936-37	162,945	107,929,514
1937-38	186,094	94,696,062
1938-39	220,975	102,220,663
1939-40	184,563	93,103,847
1940-41	209,389	112,768,552
1941-42	200,308	143,278,840
1942-43	224,554	240,608,979
1943-44	261,197	294,633,098
1944-45	237,912	309,585,680
1945-46	286,427	364,329,700
1946-47	262,992	248,709,580
1947-48	297,984	214,742,000

* Net before deducting for taxes, interest on investment and depreciation if any.

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON-AUGUST 1, 1947-JULY 31, 1948

Carlot Shipments	Freight Straight & Mixed	Carloads Total Freight	Carloads Express	Boxes Freight Boat, Truck and Express	Gross FOB Returns Florida Points Box	Gross FOB Returns Florida Points For Crop	Production and Marketing Costs Box	Production and Marketing Costs For Crop	Net Return to Florida Growers Box	Net Return to Florida Growers For Crop
Oranges	35,532	37,349	2,267	25,339,286	$2.10	$53,212,501	$1.82	$46,117,501	$ .28	$ 7,095,000
Grapefruit	11,802	13,999	777	8,631,094	1.80	15,535,969	1.44	12,428,775	.36	3,107,194
Tangerines	2,884	3,548	62	2,367,660	2.90	6,866,214	2.50	5,919,150	.40	947,064
Mxd.Citrus	6,678	Converted		-	-	-	-	-	-	-
Total	54,896	54,896	3,106	36,338,040	2.08	75,614,684	1.77	64,465,426	.31	11,149,258

GENERAL DISPOSITION ANALYSIS OF THE FLORIDA CITRUS CROP FOR SEASON 1947-48

BOXES	StraightCars Freight	Mxd.Cars Freight	Mxd.Cars Express	Tot.Boxes Rail	Trucked Out	Rail Truck*	Canned Fresh Bxs.	Consumed Boxes	#Exports	Grand Total Boxes
Oranges	16,793,544	1,836,946	906,952	19,587,442	5,707,300	25,339,286	30,376,340	2,656,990	27,384	58,400,000
Grapefruit	6,089,194	1,085,720	310,600	7,485,514	1,143,367	8,631,094	19,448,586	1,210,947	9,373	29,300,000
Tangerines	1,346,631	328,336	24,848	1,699,815	667,845	2,367,660	598,505	433,835	--	3,400,000
Total	24,229,369	3,301,002	1,242,400	28,772,771	7,518,512	33,338,040	50,423,431	4,301,772	36,757	91,100,000

CARLOADS				Total Rail	Boat	Rail Boat	Truck	Rail Boat Truck*			Exports	
Oranges	33,532	3,817	2,267	39616	-	39616	14263	53995	75,941	6,851	68	136,855
Grapefruit	11,802	2,197	777	14776	-	14776	2858	17640	48,621	3,045	23	69,329
Tangerines	2,884	664	62	3610	-	3610	1670	5280	1,496	1,085	-	7,861
Total	48,218	6,678	3,106	58002	-	58002	18796	76915	126,058	10,981	91	214,045

ESTIMATED COST OF PRODUCING AND MARKETING 76,915 CARS OF ORANGES, GRAPEFRUIT, AND TANGERINES BY RAIL AND TRUCK

Cost of production such as fertilizer, spray materials, irrigation, pruning, labor, fuel, etc., but not including interest or taxes on strictly grove acreage, per Standard 1-3/5 bushel boxes.

ORANGES $ .50 GRAPEFRUIT $ .35 TANGERINES $ .68 WEIGHTED AVERAGE $ .48

Cost of picking, hauling, packing, selling, and other average ordinary marketing charges.

ORANGES $1.32 GRAPEFRUIT $1.09 TANGERINES $1.82 WEIGHTED AVERAGE $1.29

Total ordinary and average cost of production and marketing of citrus

ORANGES $1.82 GRAPEFRUIT $1.44 TANGERINES $2.50 WEIGHTED AVERAGE $1.77

---

1. Estimated boxes per car: Straight Freight-Oranges 501.6, Grapefruit 519.1, Tangerines 467.9. Mixed Freight-494.3. Mixed Car Express 400 boxes. Export 400 boxes. Truck 400 boxes per car.
2. Mixed Car Freight Analysis: Oranges 57.7, Grapefruit 32.4, Tangerines 9.9 per cent.
3. Mixed Car Express Analysis: Oranges 73.0, Grapefruit 25.0, Tangerines 2.0 per cent.
4. Ventilated Box Cars Used: Oranges 2934, Tangerines 13, Grapefruit 442, Mixed 1052. Total 4441 cars.
5. Abandoned for Market Reasons: Oranges none, Grapefruit 3,700,000, Tangerines 600,000. This total of 4,300,000 boxes not included in Disposition Analysis. These estimates made as of September 17 and subject to revision.

* Interstate By-product Oranges 44,544 (111 cars), Grapefruit 2,213 (6 cars), added to rail & truck, & included in totals.

# Exports include U.S. Government exports of 27,384 boxes of oranges and 9,373 boxes of grapefruit. All exports included in Grand Total of boxes. No Domestic (coastwise) boat movement reported.

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON 1947-48 (Cont'd.)

TRUCK SHIPMENTS TO OUT-OF-STATE MARKETS (400 boxes to car)

ORANGES	Carlot equiv.	14,268 or	5,707,300 boxes.	Gross at	$2.10	$ 11,985,330	Net* at	$ .28	$ 1,598,044
GRAPEFRUIT	Carlot equiv.	2,858 or	1,143,367 boxes.	Gross at	1.80	2,058,061	Net* at	.36	411,612
TANGERINES	Carlot equiv.	1,670 or	667,845 boxes.	Gross at	2.90	1,936,751	Net* at	.40	267,138
ALL CITRUS	Carlot equiv.	18,796 or	7,518,512 boxes.	Gross at	$2.13	$ 15,980,142	Net* at	$ .30	$ 2,276,794

FREIGHT, EXPRESS, BOAT AND TRUCK SHIPMENTS TO OUT-OF-STATE MARKETS

ORANGES	Carlot equiv.	53,995 or	25,339,286 boxes.	Gross at	$2.10	$ 53,212,501	Net* at	$ .28	$ 7,095,000
GRAPEFRUIT	Carlot equiv.	17,640 or	8,631,094 boxes.	Gross at	1.80	15,535,969	Net* at	.36	3,107,194
TANGERINES	Carlot equiv.	5,280 or	2,367,660 boxes.	Gross at	2.90	6,866,214	Net* at	.40	947,064
ALL CITRUS	Carlot equiv.	76,915 or	36,338,040 boxes.	Gross at	$2.08	$ 75,614,684	Net* at	$ .31	$11,149,258

EXPORT SHIPMENTS BY BOAT (400 boxes to car)

ORANGES	Carlot equiv.	68 or	27,384 boxes.	Gross at	$2.10	$ 57,506	Net* at	$ .28	$ 7,668
GRAPEFRUIT	Carlot equiv.	23 or	9,373 boxes.	Gross at	1.80	16,871	Net* at	.36	3,374
TANGERINES	Carlot equiv.	-	-		-	-		-	-
ALL CITRUS	Carlot equiv.	91 or	36,757 boxes.	Gross at	$2.02	$ 74,377	Net* at	$ .30	$ 11,042

FRESH CITRUS CONSUMED IN FLORIDA (400 boxes to car)

ORANGES	Carlot equiv.	6,642 or	2,656,990 boxes.	Gross at	$1.90	$ 5,048,281	Net* at	$ .18	$ 478,258
GRAPEFRUIT	Carlot equiv.	3,027 or	1,210,947 boxes.	Gross at	1.60	1,937,515	Net* at	.20	242,189
TANGERINES	Carlot equiv.	1,085 or	433,835 boxes.	Gross at	2.60	1,127,971	Net* at	.25	108,459
ALL CITRUS	Carlot equiv.	10,754 or	4,301,772 boxes.	Gross at	$1.89	$ 8,113,767	Net* at	$ .19	$ 828,906

FRESH CITRUS USED FOR PROCESSING IN FLORIDA (400 boxes to car)

ORANGES	Carlot equiv.	75,941 or	30,376,340 boxes.	Gross at	$ .80	$ 24,301,072	Net* at	$ .03	$ 911,290
GRAPEFRUIT	Carlot equiv.	48,621 or	19,448,586 boxes.	Gross at	.34	6,612,519	Net* at	-.19	-3,695,231
TANGERINES	Carlot equiv.	1,496 or	598,505 boxes.	Gross at	.35	209,477	Net* at	-.60	- 359,103
ALL CITRUS	Carlot equiv.	126,058 or	50,423,431 boxes.	Gross at	$ .62	$ 31,123,068	Net* at	$-.06	$-3,143,044

TOTAL RAIL, BOAT, TRUCKED, PROCESSED, AND LOCALLY CONSUMED

ORANGES	Carlot equiv.	136,646 or	58,400,000 boxes.	Gross at	$1.41	$ 82,619,360	Net* at	$ .15	$ 8,492,216
GRAPEFRUIT	Carlot equiv.	69,311 or	29,300,000 boxes.	Gross at	.82	24,102,874	Net* at	-.01	- 342,474
TANGERINES	Carlot equiv.	7,861 or	3,400,000 boxes.	Gross at	2.41	8,203,662	Net* at	.20	696,420
ALL CITRUS	Carlot equiv.	213,818 or	91,100,000 boxes.	Gross at	$1.26	$114,925,896	Net* at	$ .10	$ 8,846,162

NOTE: *Gross refers to returns FOB cars Florida shipping points, and net refers to returns to growers or fruit owners before deducting for interest, depreciation, and taxes, but after deducting for cost of production and marketing.

1. Trucked-out shipment figures were based on inspection certified for interstate movement. Road Guard Stations for checking were open October 16 - May 31. Aug. 1 - Oct. 15 and June 1 - July 31 estimated.
2. Cannery fruit represents average gross price and the net price is the gross less the estimated picking, hauling, and marketing charges.
3. Figures for Consumed in Florida are rough estimates based on population, prices, etc. Any person who does not approve this home consumption estimate can make his own estimate, but this volume, which is probably under estimated cannot be ignored.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS BY PRODUCTION UNITS

1947-48 SEASON

COMMODITY	Units	Straight Freight	Mixed Freight	LCL Express	Trucked Out	Boat	Processed	Florida Consumed	Total Production Units Used	Abandoned (not included)
Beans	Bu.	1,827,000	310,000	24,000	2,503,000	-	458,000	553,000	5,675,000	225,000
Limas	Bu.	104,000	26,000	4,000	171,000	-	-	50,000	355,000	32,000
Cabbage	50Lbs	(2,440,000)	(120,000)	-	(2,000,000)	-	-	(400,000)	(4,960,000)	(840,000)
Cabbage	Ton	61,000	3,000	-	50,000	-	-	10,000	124,000	21,000
Celery	Crt.	3,810,000	38,000	4,000	510,000	-	-	296,000	4,658,000	867,000
Cucumbers	Bu.	720,000	86,000	8,000	900,000	-	120,000	116,000	1,950,000	50,000
Eggplant	Bu.	109,000	132,000	28,000	354,000	-	-	88,000	711,000	197,000
Escarole	Bu.	664,000	336,000	8,000	90,000	-	-	11,000	1,109,000	266,000
Lettuce, 4-6 doz.	W.Crt	27,000	9,000	6,000	56,000	-	-	69,000	167,000	33,000
Peas, English	Bu.	9,000	6,000	1,200	10,000	-	-	10,000	36,000	-
Peppers	Bu.	1,079,000	468,000	72,000	954,000	-	-	184,000	2,757,000	143,000
Potatoes	Bu.	2,451,000	51,000	2,000	703,000	-	-	407,000	3,614,000	-
Tomatoes	Bu.	1,512,000	71,000	8,000	1,607,000	-	346,000	390,000	3,934,000	-
Miscl. Vegetables	Bu.	260,000	991,000	40,000	1,336,000	2,500	80,000	1,000,000	3,709,500	-
Mixed Cars		Converted	Converted	Converted	-	-	-	-	-	-
TOTAL UNITS(VEGS)		15,012,000	2,644,000	205,200	11,194,000	2,500	1,004,000	3,574,000	33,635,500	2,653,000
Strawberries	36-pt.Crt	27,000	-	*4,000	144,000	-	28,000	49,000	252,000	-
Watermelons	***Crts	(4,554,000)	-	-	(1,751,500)	-	-	(557,000)	(6,862,500)	-
Watermelons	Melons	9,108,000	-	-	3,503,000	-	-	1,114,000	13,725,000	-
Miscl. Fruits	Bu.	-	-	**80,000	60,000	-	80,000	120,000	340,000	-
TOTAL UNITS(MISC.FRTS)#		4,581,000	-	84,000	1,955,500	-	108,000	726,000	74,545,000	-
Oranges	Boxes	16,793,544	1,886,946	906,952	5,707,300	-	30,376,340	2,656,990	58,400,000	-
Grapefruit	Boxes	6,089,194	1,085,720	310,600	1,143,367	-	19,448,586	1,210,947	29,300,000	3,700,000
Tangerines	Boxes	1,346,631	328,336	24,848	667,845	-	598,505	433,835	3,400,000	600,000
TOTAL UNITS CIT.		24,229,369	3,301,002	1,242,400	7,518,512	-	50,423,431	4,301,772	91,100,000	4,300,000
GRAND TOTAL UNITS#		43,822,369	5,945,002	1,531,600	20,668,012	2,500	51,535,431	8,601,772	132,190,000	6,953,000

Notes cover Pages 8 and 9

NOTES: There is considerable difficulty in working out a detailed disposition sheet for vegetables and miscellaneous fruits as comprehensive data is not as available as for citrus. First it was considered advisable to try to use the U.S. Dept. of Agriculture estimate of total production and work back from there. We have the records on the truck shipments out of State which figures are used. We have the records on straight freight and boat for individual commodities. We have only the totals for mixed freight and LCL express. The Florida consumption figures are only estimates as there are no actual records. We had to apportion the mixed freight and mixed express totals as best we could to the various commodities with the handicap of trying to make all of the separate totals check with the total official crop estimate. An additional problem was the disposition of the volume of squash, radishes, cauliflower, carrots, spinach, broccoli, endive, etc., included in the miscellaneous figures for vegetables. Miscellaneous Fruits included avocados, Persian and Key limes, mangoes, grapes, guavas, persimmons, blueberries, kumquats, etc.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS IN CARLOTS, OR EQUIVALENT, AND VALUE

1947-48 SEASON

Commodity	Straight Freight Cars	Mixed Freight Cars	LCL Express Cars	Boat Cars	Trucked Out Cars	Processed	Florida Consumption	Total Used Carlots	Abandoned (not included)##	Total FOB Gross Value
Beans	2,948	500	60	-	4,172	763	921	9,364	375	$ 14,500,000
Limas	200	50	10	-	343	-	100	703	64	1,065,000
Cabbage	4,934	240	-	-	3,983	-	800	9,957	168	6,500,000
Celery	8,966	90	10	-	1,381	-	800	11,247	2,343	9,800,000
Cucumbers	1,500	180	-	-	1,999	266	258	4,203	111	6,235,000
Eggplant	182	220	70	-	754	-	187	1,413	420	1,175,000
Escarole	1,039	525	-	-	200	-	25	1,789	591	1,165,000
Lettuce	90	30	10	-	103	-	222	455	106	440,000
Peas, English	16	11	3	-	18	-	18	66	-	92,000
Peppers	1,499	650	180	-	1,987	-	383	4,699	298	5,982,000
Potatoes	4,807	100	5	-	1,278	-	740	6,930	-	10,073,000
Tomatoes	3,782	150	20	-	3,826	865	975	9,618	-	22,936,000
Miscl. Vegetables	519	1,696	165	5	3,341	-	2,500	8,226	-	9,274,000
Mixed Cars	-	Converted	Converted	-	-	-	-	-	-	-
TOTAL VEGETABLES	30,482	4,442	533	5	23,385	1,894	7,929	68,670	4,476	$ 89,237,000
Strawberries	56	-	*(10)	-	321	58	110	555	-	2,000,000
Watermelons	9,247	-	-	-	3,503	-	1,114	13,864	-	6,860,000
Miscl. Fruits	-	-	**(200)	-	150	200	300	850	-	1,720,000
TOTAL MISC. FRUITS	9,303	-	210	-	3,974	258	1,524	15,269	-	$ 10,580,000
TOTAL VEGS. AND MISCL. FRUITS	39,785	4,442	743	5	27,359	2,152	9,453	83,939	4,476	$ 99,817,000
Oranges	33,532	3,817	2,267	-	14,268	75,941	6,851	136,855	-	82,620,000
Grapefruit	11,802	2,197	777	-	2,858	48,621	3,045	69,329	9,250	24,100,000
Tangerines	2,884	664	62	-	1,670	1,496	1,085	7,861	1,500	8,205,000
Mixed Citrus	-	Converted		-	-	-	-	-	-	-
TOTAL CITRUS	48,218	6,678	3,106	-	18,796	126,058	10,981	214,045	10,750	$ 114,925,000
GRAND TOTAL	88,003	11,120	3,849	5	46,155	128,210	20,434	297,984	15,226	$ 214,742,000

Notes cover Pages 8 and 9

NOTES: # Ordinarily units of different kinds are not added but if the 50-lb sack is used for cabbage instead of tons and the number of watermelons *** are divided by two to get crates, we find that all of the units are bushels or the near equivalent of bushels with the exception of citrus which are in 1-3/5 bu. boxes. * The 10 cars of strawberries assigned to L.C.L. express is without record data to support it. We know that some strawberries went out L.C.L. express and we included in this figure any shipments by air. ** We have no shipping record to support this 200 car estimate for L.C.L. express miscellaneous fruits, except we have 84 cars of Persian limes for express shipments. Probably another 116 cars or more of avocados, mangoes, etc., went out by L.C.L. express.

Abandoned because of market conditions and not included in the gross FOB Florida value. The gross includes the production, marketing costs, and packing costs if packed, and profit, if any.

ESTIMATED PRICES PAID BY CANNERS
(Delivered to Canneries)
1944-45, 1945-46, 1946-47 and 1947-48 Seasons

	ORANGES Per Box 1944-45	1945-46	1946-47	1947-48	GRAPEFRUIT Per Box 1944-45	1945-46	1946-47	1947-48
September	$ -	$2.49	$ -	$ -	$ -	$1.30	$1.18	$ -
October	1.98	2.49	1.33	.87	1.83	1.30	1.19	.51
November	1.98	2.41	1.00	.87	1.83	1.53	1.18	.51
December	1.93	2.52	.55	.80	1.83	1.51	.77	.44
January	2.18	2.37	.55	.88	1.85	1.29	.60	.40
February	2.49	2.31	.54	1.09	2.01	1.23	.52	.36
March	2.74	2.62	.69	.91	2.17	1.22	.53	.31
April	3.11	3.00	1.17	.70	2.19	1.29	.53	.28
May	3.25	3.66	1.16	.65	2.20	1.67	.44	.28
June	3.06	3.68	1.08	.51	1.92	1.76	.39	.25
July	3.06	3.50	.79	.42	-	1.77	.40	.24
Average	$2.60	$2.83	$ .82	.80	$1.91	$1.39	$ .65	.34

Tangerines(For Season). 1.00 .80 .35(1947-48 prices per month: Nov. 50¢; Dec 40¢; Jan. 30¢; Feb. 35¢; March 35¢; April - ¢).

TOTAL PRODUCTION, AND PORTION CANNED AND PROCESSED DELIVERED PRICE PAID BY CANNERS IN FLORIDA

	ORANGES Total Production Boxes	Portion Canned Boxes	Canner's Price Per Box	GRAPEFRUIT Total Production Boxes	Portion Canned Boxes	Canner's Price Per Box	Total Oranges Grapefruit Tangerines* Canned Boxes
1931-32	12,548,000	36,000	$0.65	10,431,000	930,000	$0.30	966,000
1932-33	14,964,000	50,000	.70	11,926,000	2,750,000	.32	2,800,000
1933-34	16,171,000	61,000	.80	11,113,000	2,605,000	.53	2,666,000
1934-35	15,590,000	178,000	.80	15,243,000	5,603,000	.37	5,781,000
1935-36	15,865,000	140,000	1.00	11,504,000	3,760,000	.73	3,900,000
1936-37	19,461,000	620,000	1.25	18,121,000	6,685,000	.55	7,305,000
1937-38	24,303,000	1,055,000	.36	14,379,000	5,793,000	.48	6,848,000
1938-39	30,015,000	1,867,000	.41	23,050,000	8,395,000	.22	10,262,000
1939-40	25,065,000	4,170,000	.19	15,650,000	8,800,000	.33	12,970,000
1940-41	28,752,000	3,941,000	.80	24,387,000	13,871,000	.37	17,812,000
1941-42	27,200,000	4,197,000	1.08	19,100,000	10,143,000	.71	14,340,000
1942-43	37,200,000	6,438,000	1.70	27,300,000	17,584,000	1.05	24,022,000
1943-44	46,200,000	10,912,501	2.02	31,000,000	20,429,310	1.53	31,341,811
1944-45	42,800,000	14,344,000	2.60	22,300,000	15,136,000	1.91	29,480,000
1945-46	49,800,000	19,183,860	2.83	32,000,000	22,124,976	1.32	41,824,436
1946-47	53,700,000	19,825,485	.82	29,000,000	15,864,346	.65	36,620,582
1947-48	58,400,000	30,376,340	.80	33,000,000	19,448,586	.34	50,423,431*

* Includes 515,600 boxes of tangerines for 1945-46, 930,751 for 1946-47, and 598,505 boxes for 1947-48.

ESTIMATED CARLOADS CANNED BY MONTHS, 1946-47 AND 1947-48 SEASONS
(400 Boxes to Carload)

	ORANGES 1946-47	1947-48	GRAPEFRUIT 1946-47	1947-48	TANGERINES 1946-47	1947-48	TOTAL 1946-47	1947-48
September	LCL	-	218	-	-	-	218	-
October	1,311	756	1,983	745	-	-	3,294	1,501
November	3,188	4,537	4,338	2,674	235	72	7,761	7,283
December	3,457	9,746	4,149	5,936	845	549	8,451	16,231
January	6,583	13,865	6,558	7,074	927	615	14,068	21,554
February	8,076	14,100	4,602	7,211	287	260	12,965	21,571
March	11,376	8,278	6,889	7,634	32	1	18,297	15,913
April	5,623	7,621	6,304	8,253	1	-	11,928	15,874
May	6,046	8,749	3,238	5,178	-	-	9,284	13,927
June	3,418	6,388	1,206	2,529	-	-	4,624	8,917
July	452	1,801	150	1,161	-	-	602	2,962
August	34	100#	26	225#	-	-	60	325
Carloads	49,564	75,941	39,661	48,620	2,327	1497	91,552	126,058
Boxes	19,825,485	30,376,340	15864,346	19448,586	930,751	598505	36620582	50,423,431

# Week ending August 28th.

Season 1947-48	Utilized	Abandoned	Total
Oranges	58,400,000	-	58,400,000
Grapefruit	29,300,000	3,700,000	33,000,000
Tangerines	3,400,000	600,000	4,000,000
Total	91,100,000	4,300,000	95,400,000

ESTIMATED COSTS FROM TREE TO AUCTIONS
1945-46, 1946-47 AND 1947-48 SEASONS
(Private Sales not Included)

ORANGES	1945-46	1946-47	1947-48	Per Box 1945-46	Per Box 1946-47	Per Box 1947-48
Carloads Sold				8,265	14,770	13,406
Auction Sales at Terminal Markets				$4.58	$3.50	$3.27
Terminal Selling & Expenses				.09	.07	.07
Net at Terminal				4.49	3.43	3.20
Transportation Cost				.77	.80	.95
Florida F.O.B. Equivalent				$3.72	$2.63	$2.25
Florida Marketing Charges	.08	.08	.08	$1.24	$1.30	$1.32
Advertising & Inspection	.03	.04	.04			
Packing & Processing	.81	.84	.86			
Picking, Loading & Hauling	.32	.34	.34			
On Tree Equivalent				$2.48	$1.33	$ .93
Estimated Production Costs				.48	.53	.55
Net to Grower before Interest, Taxes & Depreciation				$2.00	$ .80	$ .38

GRAPEFRUIT	1945-46	1946-47	1947-48	Per Box 1945-46	Per Box 1946-47	Per Box 1947-48
Carloads Sold				4,384	7,094	6,660
Auction Sales at Terminal Markets				$3.82	$3.29	$3.07
Terminal Selling & Expenses				.08	.07	.06
Net at Terminal				3.74	3.22	3.01
Transportation Cost				.74	.77	.90
Florida F.O.B. Equivalent				$3.00	$2.45	$2.11
Florida Marketing Charges	.08	.08	.08	1.10	1.08	1.09
Advertising & Inspection	.05	.05	.05			
Packing & Processing	.73	.71	.72			
Picking, Loading & Hauling	.24	.24	.24			
On Tree Equivalent				$1.90	$1.37	$1.02
Estimated Production Costs				.34	.37	.38
Net to Grower before Interest, Taxes & Depreciation				$1.56	$1.00	$ .64

TANGERINES	1945-46	1946-47	1947-48	Per Box 1945-46	Per Box 1946-47	Per Box 1947-48
Carloads Sold				2,201	2,403	2,202
Auction Sales at Terminal Markets				$5.22	$4.34	$3.96
Terminal Selling & Expenses				.10	.09	.08
Net at Terminal				5.12	4.25	3.88
Transportation Cost				.81	.84	.95
Florida F.O.B. Equivalent				$4.31	$3.41	$2.93
Florida Marketing Charges	.08	.08	.08	1.71	1.79	1.82
Advertising & Inspection	.07	.07	.07			
Packing & Processing	1.08	1.18	1.20			
Picking, Loading & Hauling	.48	.46	.47			
On Tree Equivalent				$2.60	$1.62	$1.11
Estimated Production Costs				.64	.68	.68
Net to Grower before Interest, Taxes & Depreciation				$1.96	$ .94	.43

Approximate Percentage all freight shipments sold at Auction -

	Oranges	Grapefruit	Tangerines
1940-41	32.6%	36.5%	47.3%
1941-42	32.7%	35.4%	45.5%
1942-43	27 %	36 %	48 %
1943-44	21.2%	24.8%	11.2%
1944-45	18.3%	26.2%	21.5%
1945-46	15.7%	26.8%	35.8%
1946-47	28.0%	43.4%	57.5%
1947-48	26.0%	37.8%	40.5%

NOTE: As has been stated above and in other pages of our report for many years, the citrus net prices do not allow any deductions for interest on investment, for taxes, or for depreciation of equipment. Pages 6-7 of this report, which include private as well as auction sales of citrus, should be used along with this page. Private sales of tangerines averaged considerably higher than auction sales in the last few seasons. See pages 44-45 for Citrus Price Analysis.

See pages 40-42 for Auction Cars and Price Averages - yearly comparison.

THIS DOES NOT INCLUDE ANY PRIVATE SALES.

ACREAGE, YIELD, PRODUCTION AND VALUE
VEGETABLES AND MISCELLANEOUS FRUITS
1947-48 SEASON

FLORIDA	Acreages Planted	Acreages For Harvest	Yield Units	Production Total Units	Abandoned Units	Production of Value Units	Season Avg FOB Price Units	Total Value Marketed Dollars
SNAP BEANS			Bu.					
Fall (Fresh)	19,400	14,200	106	1,505,000	125,000	1,380,000	$ 2.55	$ 3,519,000
(Process)	3,000	3,000	100	300,000	-	300,000	1.45	435,000
			1.5T	4,500		4,500T	96.70	(435,000)
" (Total)	22,400	17,200	105	1,805,000	125,000	1,680,000	2.35	3,954,000
Winter (Fresh)	36,000	35,000	70	2,450,000	100,000	2,350,000	2.75	6,462,000
" (Process)	1,500	1,500	73	110,000		110,000	1.55	170,000
			1.1T	1,650		1,650T	103.35	(170,000)
" (Total)	37,500	36,500	70	2,560,000	100,000	2,460,000	2.70	6,632,000
Spring (Fresh)	17,500	16,000	85	1,360,000		1,360,000	2.65	3,604,000
" (Process)	2,000	2,000	86	173,000		173,000	1.70	294,000
			1.3T	2,600		2,600T	113.40	(294,000)
" (Total)	19,500	18,000	85	1,533,000	100,000	1,533,000	2.54	3,898,000
TOTAL FRESH	72,900	65,200	82	5,315,000	225,000	5,090,000	2.57	13,585,000
TOTAL PROCESS	6,500	6,500	90	583,000		583,000	1.54	899,000
TOTAL ALL	79,400	71,700	82	5,898,000	225,000	5,673,000	2.55	14,484,000
LIMA BEANS								
Winter	1,900	1,500	65	98,000		98,000	3.65	358,000
Spring	3,100	2,750	105	289,000	32,000	257,000	2.75	707,000
TOTAL	5,000	4,250	91	387,000	32,000	355,000	3.00	1,065,000
CABBAGE			Tons					
Winter	16,500	16,100	9T	144,900	21,100	123,800T	52.50	6,500,000
CARROTS			Bu.					
Winter	450	450	200	90,000		90,000	3.00	270,000
			Crt.			Crt.		
CAULIFLOWER-Wint.	400	400	200	80,000		80,000	2.20	176,000
CELERY *			Crt.			Crt.		
Winter	6,300	6,300	490	3,087,000	289,000	2,798,000	2.25	6,295,000
Spring	5,500	5,300	[illegible]	2,438,000	578,000	1,860,000	1.75	3,255,000
TOTAL	11,800	11,600	476	5,525,000	867,000	4,658,000	2.05	9,550,000
CUCUMBERS			Bu.					
Fall	5,400	5,000	100	500,000	50,000	450,000	3.95	1,778,000
Winter	1,000	1,000	85	85,000		85,000	5.20	442,000
Spring	10,000	9,000	140	1,260,000		1,260,000	3.05	3,843,000
" Pickling	900	900	125	112,000		112,000	1.25	140,000
TOTAL	17,300	15,900	123	1,957,000	50,000	1,907,000	3.25	6,203,000
EGGPLANT			Bu.					
Fall	950	400	75	30,000		30,000	3.95	118,000
Winter	375	325	310	101,000		101,000	3.50	354,000
Spring	2,750	2,500	305	763,000	197,000	566,000	1.20	679,000
TOTAL	4,075	3,225	277	894,000	197,000	697,000	1.65	1,151,000
ESCAROLE			Bu.					
Winter	3,500	3,200	430	1,376,000	266,000	1,110,000	1.05	1,165,000
LETTUCE			Crt.					
BOSTON (Winter)	750	550	125	69,000	23,000	46,000	2.05	94,000
ICEBERG "	1,300	1,000	120	120,000	10,000	110,000	2.95	324,000
" (Spring)	100	100	100	10,000		10,000	2.25	22,000
TOTAL	2,150	1,650	121	199,000	33,000	166,000	2.65	440,000
PEAS, ENGLISH			Bu.					
Winter	700	600	60	36,000		36,000	2.55	92,000
PEPPERS			Bu.					
Fall	700	500	185	92,000		92,000	4.35	400,000
Winter	2,600	2,600	390	1,014,000		1,014,000	2.55	2,586,000
Spring	9,100	8,350	210	1,754,000	143,000	1,611,000	1.80	2,900,000
TOTAL	12,400	11,450	250	2,860,000	143,000	2,717,000	2.17	5,886,000

* NOTE: Celery was corrected at the last minute, making total abandoned 25,000 crates less and total value $228,000 less, but this small revenue is not reflected in some of the Grand Totals and on Page 65, which should be corrected with above figures.

ACREAGE, YIELD, PRODUCTION AND VALUE
VEGETABLES AND MISCELLANEOUS FRUITS
1947-48 SEASON

FLORIDA	Acreage Planted	Acreage For Harvest	Yield Units	Production Total Units	Abandoned Units	Production of Value Units	Season Avg FOB Price Units	Total Value Marketed Dollars
POTATOES			Bu.					
Winter	8,100	7,400	200	1,480,000		1,480,000	$ 2.85	$ 4,218,000
Spring	13,700	13,400	159	2,134,000		2,134,000	2.74	5,855,000
TOTAL	21,800	20,800	174	3,614,000		3,614,000	2.79	10,073,000
TOMATOES			Bu.					
Fall(Fresh)	7,250	2,500	155	388,000		388,000	6.60	2,560,000
" (Process)	300	300	155	46,000		46,000	.75	34,000
			4.1T	1,230		1,230T	28.50	(34,000)
" (Total)	7,550	2,800	155	434,000		434,000	5.98	2,594,000
Winter(Fresh)	12,700	10,000	95	950,000		950,000	8.15	7,742,000
(Process)	1,100	1,100	94	104,000		104,000	.75	78,000
			2.5T	2,750		2,750T	28.50	(78,000)
" (Total)	13,800	11,100	95	1,054,000		1,054,000	7.42	7,820,000
Spring(Fresh)	15,000	15,000	150	2,250,000		2,250,000	5.50	12,375,000
" (Process)	1,300	1,300	150	196,000		196,000	.75	146,000
			4T	5,200		5,200T	28.50	(146,000)
" (Total)	16,300	16,300	150	2,446,000		2,446,000	5.12	12,521,000
TOTAL FRESH	34,950	27,500	130	3,588,000		3,588,000	6.32	22,677,000
TOTAL PROCESS	2,700	2,700	128	346,000		346,000	.75	258,000
TOTAL ALL	37,650	30,200	130	3,934,000		3,934,000	5.83	22,936,000
TOTAL VEGS.	213,125	191,525	(Packed Value per Acre Harvested $420)					$80,219,000
CANTALOUPES			Crts.					
Spring	1,200	1,200	65	78,000		78,000	4.35	$ 339,000
STRAWBERRIES			24-qt.crt.					
Winter	4,200	4,200	45	189,000		189,000	10.60	$ 2,003,000
WATERMELONS			per 1000					
Spring	51,000	45,000	305	13,725,000		13,725,000	500.00	$ 6,862,000
TOTAL MISCL.FRUITS	56,400	50,400	(Packed Value per Acre Harvested $183)					$ 9,204,000
GRAND TOTAL	269,525	241,925	(Packed Value per Acre Harvested $370)					$89,423,000

TOTAL ACRES, VALUE PER ACRE AND TOTAL PACKED VALUE IN 1946-47 SEASON

	Acres Used	Per Acre	Total Value
Vegetables	201,450	$400	$80,712,000
Miscellaneous Fruits	52,550	176	9,260,000
Grand Total	254,000	$354	$89,972,000

The above officially reported acreage does not include a large acreage of miscellaneous vegetables such as squash, radishes, broccoli, collards, turnips, carrots, okra baby limas, etc., and it does not include avocados, limes, mangoes, guavas, etc. in miscellaneous fruits. Citrus acreage and value is covered elsewhere in this report.

Some beans and tomatoes processed show volume in tons as well as in bushels. The value for the ton volume is in parenthesis and should not be included in the totals as it would be a duplication.

The above tabulation was prepared from data supplied by Mr. J. B. Owens and Mr. G. N. Rose, Agricultural Statisticians, U.S. Bureau of Agricultural Economics, Federal Building, Orlando, Florida. They are the original and only source for acreage and production estimates of vegetables and miscellaneous fruits in Florida.

If you have any questions on acreage, production and values not shown in this report you may write directly to the above named statisticians. They have all the acreage data.

Frank H. Scruggs

(See pages 62-68 for acreage figures for other seasons.)

INTERSTATE TRUCK DISTRIBUTION, FLORIDA CITRUS, 1947-48 SEASON

(Made available thru the courtesy of the State Dept. of Agriculture, Winter Haven, Fla., and H. F. Willson, Federal-State Market News Service, Lakeland, Florida).

Oct. 16, 1947 to May 31, 1948, Inclusive.

Destinations	Oranges Boxes	Grapefruit Boxes	Tangerines Boxes	Total Boxes
Alabama	395,270	34,677	30,382	460,329
Arkansas	70,409	3,109	1,204	74,722
Colorado	370	750	-	1,120
Connecticut	3,237	109	1,313	4,659
Delaware	8,329	324	1,645	10,298
Dist. of Columbia	179,318	48,652	20,564	248,534
Georgia	849,947	171,115	93,456	1,114,518
Illinois	421,021	44,640	63,766	529,427
Indiana	261,053	40,643	36,557	338,253
Iowa	6,071	1	5	6,077
Kansas	1,996	650	850	3,496
Kentucky	107,573	11,728	12,876	132,177
Louisiana	79,029	9,077	716	88,822
Maine	5,061	94	265	5,420
Maryland	174,607	40,438	33,220	248,265
Massachusetts	10,980	1,974	3,624	16,578
Michigan	114,319	22,098	17,989	154,406
Minnesota	33,937	583	2,570	37,090
Mississippi	151,385	3,096	5,559	160,040
Missouri	24,551	1,978	6,495	33,024
Nebraska	1,662	245	1,863	3,770
New Jersey	38,374	7,608	5,107	51,089
New York	270,186	40,234	37,486	347,906
North Carolina	401,654	74,381	71,975	548,010
Ohio	117,673	23,854	23,086	164,613
Oklahoma	1,242	7	1,832	3,081
Pennsylvania	245,348	45,965	42,964	334,277
Rhode Island	6,432	699	6,868	13,999
South Carolina	435,532	93,842	54,229	583,603
Tennessee	197,347	19,358	17,014	233,719
Texas	8,246	542	4,691	13,479
Vermont	6,909	1,557	683	9,149
Virginia	310,070	107,661	41,457	459,188
West Virginia	84,036	12,376	8,720	105,132
Wisconsin	18,928	222	713	19,863
Out of State	7,643	2,165	1,839	11,647
Canada	28,700	6,167	3,321	38,188
Grand Total - Boxes	5,078,445	872,619	656,904	6,607,968
Oct. 16-May 31, Cars	12,696	2,182	1,642	16,520
North West Florida-Bxs	117,969	23,970	9,707	151,636
" " " Cars	290	60	24	374
Grand Total - Boxes	5,196,414	896,589	666,611	6,759,604
Oct. 16-May 31, Cars	12,986	2,242	1,666	16,894
Sept. 1-Aug 31, Cars*	14,268	2,858	1,670	18,796

Note: * The figures for Sept. 1-Aug 31 taken from a different source than those for Oct. 16-May 31.

RECAPITULATION OF RAIL DISTRIBUTION, FLORIDA CITRUS FRUITS
BY STATES - 1947-48 AND 1946-47 SEASONS

STATE	ORANGES		GRAPEFRUIT		TANGERINES		MIXED CITRUS		GRAND TOTAL	
	47-48 Rail Only	46-47 Rail & Boat	47-48 Rail Only	46-47 Rail & Boat	47-48 Rail Only	46-47 Rail & Boat	47-48 Rail Only	46-47 Rail & Boat	47-48 Rail Only	46-47 Rail & Boat
	Cars	Cars	Cars	Cars	Cars	Cars	Cars	Cars	Cars	Cars
Alabama	569	922	97	104	3	6	57	293	726	1,325
Arkansas	9	129	3	6	2	-	2	13	16	148
Colorado	9	7	5	13	6	8	1	2	21	30
Connecticut	757	1,081	169	205	39	96	15	52	980	1,434
Delaware	39	18	-	-	-	-	-	1	39	19
Dist. of Columbia	552	937	245	350	10	22	36	49	843	1,358
Florida	4#	34#	-#	31#	-#	-#	-#	14#	4#	79
Georgia	607*	996*	167*	218*	5*	29*	188*	303*	967*	1,546*
Idaho	-	-	-	2	-	-	-	-	-	2
Illinois	1,437	2,416	283	326	181	200	84	252	1,985	3,194
Indiana	306	675	67	51	13	22	20	70	406	818
Iowa	67	108	5	35	5	1	3	9	80	153
Kansas	11	36	4	6	1	3	1	1	17	46
Kentucky	453	688	64	70	16	17	38	116	571	891
Louisiana	334	457	3	30	1	1	11	32	349	520
Maine	163	137	25	15	4	1	7	22	199	175
Maryland	1,174	1,851	588	607	91	117	220	213	2,073	2,788
Massachusetts	2,603	3,069	957	928	233	243	386	405	4,179	4,645
Michigan	1,160	1,727	340	368	200	211	93	239	1,793	2,545
Minnesota	53	183	44	56	21	24	6	14	124	277
Mississippi	110	397	1	1	-	1	19	62	130	461
Missouri	561	665	82	69	81	46	13	53	737	833
Montana	1	2	6	6	-	-	1	-	8	8
Nebraska	44	46	23	25	2	6	1	5	70	82
New Hampshire	15	10	-	-	-	-	8	3	23	13
New Jersey	944	1,287	268	318	15	25	36	57	1,263	1,687
New York	10,034	12,995	4,822	6,053	905	1,190	1,708	1,703	17,469	21,941
North Carolina	869	1,217	263	201	20	13	241	443	1,393	1,879
North Dakota	5	5	-	2	-	-	1	-	6	7
Ohio	2,392	3,470	377	466	286	301	196	471	3,251	4,708
Oklahoma	17	42	5	18	2	4	-	2	24	66
Oregon	1	7	23	18	5	4	-	2	29	31
Pennsylvania	4,747	5,723	1,764	1,603	653	628	862	768	8,026	8,722
Rhode Island	434	468	121	80	24	36	7	35	586	619
South Carolina	428	767	29	62	9	13	150	344	616	1,186
South Dakota	1	3	1	4	-	-	-	1	2	8
Tannessee	1,209	1,683	109	116	40	50	130	443	1,488	2,292
Texas	30	89	6	20	1	4	-	2	37	115
Utah	10	8	18	14	-	-	-	1	28	23
Vermont	7	49	-	4	-	-	7	16	14	69
Virginia	689	932"	319	246"	9	12"	84	313"	1,101	1,503"
Washington	7	12	50	35	10	5	-	1	67	53
West Virginia	252	397	15	29	9	8	61	162	337	596
Wisconsin	293	293	55	53	16	5	32	57	396	408
Wyoming	1	1	-	3	1	-	-	-	2	4
CANADA	375	671	360	479	51	127	31	66	817	1,343
TOTAL	33,783	46,710	11,783	13,346	2,970	3,484	4,756	7,110	53,292	70,650

- Includes Jacksonville.

* - Does not include Savannah.

" - Petersburg not included

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 21 YEARS

Records Estimates Season ALL ORANGES	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped By Rail Cars	With No. Rail Haul, Shipped by Boat(2) Carloads	Total Rail & Boat Shipments Boxes	Estimated Trucked out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed (3) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	16,437	16,310	127	5,917,320	520,000	12,000	650,000	7,099,320
1928-29	32,428	31,988	440	11,674,080	975,000	38,000	1,062,500	13,749,580
1929-30(4)	21,816	21,635	181	7,489,633	65,000	40,000	780,000	8,374,633
1930-31	40,353	39,354	999	14,000,130	1,584,000	61,351	1,308,582	16,954,063
1931-32	25,725	24,054	1,671	9,904,145	1,486,480	36,362	1,122,000	12,548,987
1932-33	32,580	26,414	6,166	11,728,800	1,854,000	50,000	1,332,000	14,964,800
1933-34	31,799	18,291	13,508	12,401,563	2,322,000	61,433	1,386,000	16,170,996
1934-35	28,213	14,843	13,370	11,094,459	2,891,643	177,937	1,425,000	15,589,039
1935-36	29,746	17,403	12,343	11,714,588	2,510,000	140,000	1,500,000	15,864,588
1936-37	37,208	23,382	13,826	14,580,603	2,560,000	620,135	1,700,000	19,460,788
1937-38	46,061	31,258	14,803	18,005,497	3,442,000	1,055,399	1,800,000	24,302,896
1938-39	55,697	37,380	18,317	21,528,758	5,175,741	1,186,689	2,000,000	29,900,000
1939-40	38,285	29,286	8,999	14,718,568	4,376,000	4,170,134	1,800,000	25,064,702
1940-41	42,597	31,402	11,195	16,609,828	5,726,000	3,941,261	2,475,000	28,752,089
1941-42	41,598	40,443	1,155	16,853,616	4,099,200	4,197,299	2,049,885	27,200,000
1942-43	52,287	52,287	None	25,799,784	2,715,823	6,438,274	2,246,300	37,200,181
1943-44	61,160	61,160	None	30,511,378	2,155,200	11,010,841	2,522,581	46,200,000
1944-45	49,507	49,507	None	24,526,000	1,456,400	14,344,000	2,473,600	42,800,000
1945-46	52,665	52,589	76	26,007,841	2,054,000	19,219,412	2,518,747	49,800,000
1946-47	54,421	51,513	2,908	26,787,122	3,509,600	19,825,485	2,677,793	52,800,000 B
1947-48	39,616	39,616	-	19,659,370 A	5,707,300	30,376,340	2,656,990	58,400,000

NOTES:

(A) Includes 27,384 boxes of oranges for export and 44,544 boxes for interstate by-products.

(B) Does not include 900,000 boxes abandoned in 1946-47 season for marketing reasons. No oranges abandoned in 1947-48 season. Abandonment, if any, prior to 1945-46 season not shown.

(2) Domestic boat in coastwise trade.

(3) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(4) Fruit fly year when production harvest and shipments restricted. Many trees cut down and many so-called host plants destroyed by the federal agencies.

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 21 YEARS

Records and Estimates Season ALL ORANGES	Cost of Production(2) Before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail&Boat Shipments Per Box	Estimated Net Return(1) Rail & Boat Shipments Net Value	Estimated Net Return All Oranges Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Oranges Harvested and Used Gross Value
1927-28	$0.72	$1.30	$4.16	$2.14	$12,663,065	$13,905,825	$24,616,051	$26,804,051
1928-29	.72	1.28	2.12	.12	1,400,890	2,125,630	23,749,050	26,224,450
1929-30(4)	.80	1.30	3.30	1.20	8,987,560	9,648,310	24,715,789	26,157,789
1930-31	.48	1.10	2.15	.57	7,980,074	8,826,500	30,100,280	32,738,844
1931-32	.60	.95	2.30	.75	7,428,109	8,857,319	22,779,534	26,455,041
1932-33	.47	.90	1.48	.10	1,172,880	2,129,300	17,858,624	20,446,424
1933-34	.46	.87	1.71	.38	4,712,594	6,842,686	21,206,673	25,752,219
1934-35	.45	.90	1.85	.50	5,547,228	8,246,123	20,524,749	26,352,066
1935-36	.45	.95	2.30	.90	10,543,129	14,058,129	26,943,552	33,349,552
1936-37	.42	.93	2.50	1.15	16,767,693	20,689,419	36,451,507	44,979,738
1937-38	.38	.88	1.56	.30	5,401,649	6,053,959	26,088,575	34,339,559
1938-39	.34	.84	1.43	.25	5,382,190	6,035,321	30,786,124	39,687,098
1939-40	.42	.91	1.62	.29	4,268,365	4,214,941	23,843,970	33,663,815
1940-41	.40	.87	1.63	.36	5,979,538	9,126,658	27,074,020	42,442,109
1941-42	.44	.90	2.10	.76	12,808,748	18,918,916	35,392,593	51,904,503
1942-43	.40	1.01	2.97	1.56	40,247,695	53,904,492	76,625,358	101,089,208
1943-44	.50	1.25	3.10	1.35	41,190,360	60,688,332	94,585,272	129,867,001
1944-45	.50	1.21	3.50	1.79	43,901,540	74,132,856	85,841,000	135,653,600
1945-46	.48	1.24	3.55	1.83	47,414,930	91,767,533	91,979,783	161,818,586
1946-47*	.53 (3)	1.25	2.62	.84	25,320,348	26,385,989	78,975,370	101,927,124
1947-48*	.50	1.32	2.10	.28	7,095,000	8,492,216	53,212,501	82,619,360

NOTES:

* Truck Shipments included with Rail & Boat, their FOB prices being same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments.

(3) An allowance was made for unusual cost in grove protection in 1946-47 season. (February freeze.)

(4) Fruit fly year when production, harvest and shipments restricted.

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 21 YEARS

Records Estimates Season GRAPE-FRUIT	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul, Shipped by Boat(2) Carloads	Total Rail & Boat Shipments Boxes	Estimated Trucked out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(3) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	20,012	19,953	59	7,204,320	240,000	586,000	300,000	8,332,320
1928-29	28,294	28,091	203	10,185,840	450,000	1,489,320	675,000	12,800,160
1929-30(4)	16,415	16,354	61	6,341,913	30,000	1,670,000	360,000	8,401,913
1930-31	30,462	29,809	653	11,641,987	792,000	2,892,705	654,291	16,180,983
1931-32	20,315	17,865	2,450	7,821,313	897,940	930,171	782,000	10,431,424
1932-33	19,639	15,293	4,346	7,266,430	980,500	2,750,000	928,700	11,925,630
1933-34	17,514	11,340	6,174	6,981,916	684,000	2,605,964	841,320	11,113,200
1934-35	19,218	10,418	8,800	7,577,053	1,187,011	5,603,996	875,000	15,243,060
1935-36	15,196	8,838	6,358	5,936,067	1,028,000	3,760,000	780,000	11,504,067
1936-37	23,786	16,142	7,644	9,352,859	1,283,600	6,685,327	800,000	18,121,786
1937-38	16,952	11,511	5,441	6,602,063	1,233,600	5,793,097	750,000	14,378,760
1938-39	25,047	17,051	7,996	9,844,986	1,472,277	8,395,348	950,000	20,662,611#
1939-40	12,974	9,160	3,814	5,110,591	1,000,000	8,800,274	740,000	15,650,865
1940-41	19,962	14,478	5,484	7,956,475	1,559,600	13,870,966	1,000,000	24,387,041
1941-42	16,813	16,298	515	6,856,510	1,042,000	10,142,575	1,058,915	19,100,000
1942-43	16,529	16,529	None	8,009,134	612,807	17,584,025	1,094,150	27,300,116
1943-44	18,041	18,041	None	8,984,800	355,600	20,445,643	1,213,952	31,000,000
1944-45	11,742	11,742	None	5,860,000	205,200	15,136,000	1,098,800	22,300,000
1945-46	16,554	16,542	12	8,306,504	340,400	22,136,149	1,216,947	32,000,000
1946-47	17,800	16,363	1,437	8,878,857	558,000	15,864,346	1,098,797	26,400,000
1947-48	14,776	14,776	-	7,497,100 A	1,143,367	19,448,586	1,210,947	29,300,000 B

NOTES:

(A) Includes 9,373 boxes of grapefruit for export and 2,213 boxes for inter-state by-products.

(B) Does not include 3,700,000 boxes of grapefruit abandoned for marketing reasons. Abandonment, if any, for years prior to 1947-48 season not shown.

(2) Domestic Boat Shipments in coast-wise trade.

(3) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intra-state truck shipments, etc.

(4) Fruit fly year when production, harvest and shipments restricted.

(#) **Does not include** 2,388,224 **boxes diverted to** other uses.

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 21 YEARS

Records and Estimates Season GRAPEFRUIT	Cost of Production(2) before Picked Per Box	Cost of Picking Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail&Boat Shipments Per Box	Estimated Net Return(1) Rail&Boat Shipments Net Value	Estimated Net Return All Grapefruit Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Grapefruit Harvested and Used Gross Value
1927-28	$0.52	$1.25	$3.28	$1.51	$10,878,523	$11,555,563	$23,630,170	$25,018,170
1928-29	.52	1.25	2.02	.25	2,546,460	3,078,488	20,575,397	22,557,557
1929-30(4)	.60	1.25	3.05	1.20	7,610,296	8,293,796	19,342,835	21,479,835
1930-31	.36	1.05	1.50	.09	1,065,779	1,199,727	17,762,980	20,366,366
1931-32	.40	.85	1.50	.25	1,955,328	2,012,557	11,731,970	13,522,967
1932-33	.38	.85	1.16	-.07	- 508,650	- 1,285,321	8,429,059	10,170,789
1933-34	.39	.83	1.51	.29	2,024,756	2,591,790	10,542,693	13,296,632
1934-35	.37	.84	1.29	.08	606,164	199,847	9,774,397	13,409,984
1935-36	.39	.87	1.87	.61	3,621,001	5,269,881	11,100,445	15,936,845
1936-37	.30	.83	1.48	.35	3,273,500	4,448,605	13,842,231	19,731,121
1937-38	.36	.82	1.53	.35	2,310,722	2,613,485	10,101,156	15,063,803
1938-39	.30	.74	1.04	Zero	Zero	- 2,099,526	10,238,785	14,688,400
1939-40	.40	.82	1.42	.20	1,022,120	- 146,121	7,257,052	12,289,942
1940-41	.35	.74	1.21	.12	954,777	- 514,241	9,627,335	17,335,152
1941-42	.40	.80	1.80	.60	4,113,906	6,439,418	12,341,718	22,849,773
1942-43	.35	.88	2.33	1.10	8,810,047	18,156,816	18,661,282	40,527,501
1943-44	.40	1.07	2.47	1.00	8,984,800	28,461,544	22,192,456	56,780,588
1944-45	.40	1.07	3.00	1.53	8,965,800	30,343,516	17,580,000	49,962,240
1945-46	.34	1.10	2.65	1.21	10,039,012	24,983,418	21,986,266	56,604,216
1946-47*	.37 (3)	1.08	2.18	.73	6,440,575	6,883,612	19,640,839	32,971,867
1947-48*	.35	1.09	1.80	.36	3,107,194	- 342,474	15,535,969	24,102,874

NOTES:

* Truck shipments included with Rail & Boat, their FOB prices being same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(3) An allowance was made for unusual cost in grove protection in 1946-47 season.

(4) Fruit fly year when production, harvest and shipments restricted.

(-) Minus sign indicates Net Loss.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 21 YEARS

Records Estimates Season TANGERINES	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul, Shipped by Boat(2) Carloads	Total Rail and Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(3) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	1,427	1,417	10	513,720	40,000		50,000	603,720
1928-29	2,951	2,917	34	1,062,360	75,000		212,500	1,349,860
1929-30(4)	1,254	1,242	12	383,054	5,000		60,000	448,054
1930-31	3,830	3,786	44	1,387,828	264,000		218,097	1,869,925
1931-32	3,195	3,077	118	1,188,707	141,100		136,000	1,465,807
1932-33	3,282	2,749	533	1,181,520	175,680	No record made of the very few Tangerines processed prior to 1944-45 Season	162,000	1,519,200
1933-34	3,998	2,657	1,341	1,501,411	243,000		247,680	1,992,091
1934-35	3,676	2,199	1,477	1,461,049	267,706		275,000	2,003,755
1935-36	3,974	2,549	1,425	1,581,397	232,000		280,000	2,093.397
1936-37	5,885	4,046	1,839	2,288,234	430,000		300,000	3,018,634
1937-38	4,396	3,098	1,298	1,709,973	298,000		250,000	2,257,973
1938-39	6,323	4,502	1,821	2,553,332	478,541		350,000	3,381,873
1939-40	4,051	3,315	736	1,620,345	437,200		200,000	2,257,545
1940-41	4,513	3,449	1,064	1,791,824	434,800		525,000	2,751,624
1941-42	3,534	3,387	147	1,432,144	334,800		333,056	2,100,000
1942-43	7,382	7,382	None	3,407,401	400,048		392,700	4,200,149
1943-44	6,179	6,179	None	2,818,782	382,800		398,418	3,600,000
1944-45	6,847	6,847	None	3,149,000	327,600	3,000	420,400	3,900,000
1945-46	5,728	5,728	None	2,809,372	384,000	515,600	491,028	4,200,000
1946-47	4,543	4,323	222	2,058,146	438,400	930,751	472,703	3,900,000
1947-48	3,610	3,610	-	1,699,815	667,845	598,505	433,835	3,400,000 A

NOTES:

(A) Does not include 600,000 boxes abandoned for marketing reasons. Abandonment, if any, for prior years not shown here.

(2) Domestic Boat Shipments in coast-wise trade.

(3) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intra-state truck shipments, etc.

(4) Fruit fly year when production, harvest and shipments restricted.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 21 YEARS

Redords and Es- timates Season TAN- GERINES	Cost of Produc- tion(2) before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return(1) Rail & Boat Shipments Net Value	Estimated Net Return All Tangerines Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Tangerines Harvested and Used Gross Value
1927-28	$0.81	$1.70	$5.28	$2.77	$1,423,004	$1,519,104	$ 2,712,442	$ 2,892,442
1928-29	.81	1.70	2.90	.39	414,320	493,945	3,080,844	3,435,844
1929-30(4)	.90	1.70	3.50	.90	344,748	378,498	1,340,689	1,459,689
1930-31	.54	1.50	1.95	-.09	- 124,905	11,345	2,706,265	3,188,362
1931-32	.75	1.25	2.05	.05	59,435	73,290	2,436,849	2,713,949
1932-33	.56	1.16	1.42	-.30	- 354,456	- 281,513	1,677,758	1,999,238
1933-34	.56	1.05	1.80	.19	285,268	574,535	2,702,540	3,352,340
1934-35	.55	.95	1.66	.16	233,768	409,965	2,425,341	3,035,702
1935-36	.55	1.10	2.00	.35	553,489	883,889	3,162,794	3,902,794
1936-37	.50	1.15	1.45	-.20	- 457,646	- 558,726	3,317,939	4,127,899
1937-38	.52	1.16	1.86	.18	307,795	320,975	3,180,550	3,881,990
1938-39	.45	.95	1.34	-.06	- 153,200	- 242,481	3,421,465	4,291,433
1939-40	.50	1.06	2.00	.44	712,952	945,972	3,240,690	4,411,370
1940-41	.50	1.08	1.68	.10	179,182	219,216	3,010,264	4,415,434
1941-42	.58	1.16	2.85	1.11	1,589,680	2,280,955	4,081,610	5,818,344
1942-43	.40	1.35	2.79	1.03	3,509,623	4,223,464	9,472,575	11,436,280
1943-44	.65	1.68	3.70	1.37	3,861,731	4,884,190	10,429,493	13,041,107
1944-45	.65	1.68	4.25	1.92	6,046,080	7,437,192	13,383,250	16,296,690
1945-46	.64	1.71	4.80	2.45	6,882,962	8,800,902	13,484,986	17,807,898
1946-47*	.68	1.72	3.75	1.35	2,778,497	3,522,030	8,310,248	11,666,569
1947-48*	.68	1.82	2.90	.40	947,064	696,420	6,866,214	8,203,662

NOTES:

* Truck shipments included with Rail & Boat, their FOB prices being same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation pruning, fuel, labor, etc., but before deducting for taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(4) Fruit fly year when production, harvest and shipments restricted.

(-) Minus sign indicates Net Loss.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 21 YEARS

Records Estimates Season ALL CITRUS	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul, Shipped by Boat Carloads	Total Rail & Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(3) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	37,876	37,680	196	13,635,360	800,000	600,000	1,000,000	16,035,360
1928-29	63,673	62,996	677	22,922,280	1,500,000	1,527,320	1,950,000	27,899,600
1929-30(4)	39,485	39,231	254	14,214,600	100,000	1,710,000	1,200,000	17,224,600
1930-31	74,645	72,949	1,696	27,229,945	2,640,000	2,954,056	2,180,970	35,004,971
1931-32	49,235	44,996	4,239	18,914,165	2,525,520	966,533	2,040,000	24,446,218
1932-33	55,501	44,456	11,045	20,176,750	3,010,180	2,800,000	2,422,700	28,409,630
1933-34	53,311	32,288	21,023	20,884,890	3,249,000	2,667,397	2,475,000	29,276,287
1934-35	51,107	27,460	23,647	20,132,561	4,346,360	5,781,933	2,575,000	32,835,854
1935-36	48,916	28,790	20,126	19,232,052	3,770,000	3,900,000	2,560,000	29,462,052
1936-37	66,879	43,570	23,309	26,221,696	4,274,000	7,305,512	2,800,000	40,601,208
1937-38	67,409	45,867	21,542	26,317,533	4,973,600	6,848,496	2,800,000	40,939,629
1938-39	87,067	58,933	28,134	33,927,076	7,126,559	9,582,037	3,300,000	56,447,995#
1939-40	55,310	41,761	13,549	21,449,504	5,813,200	12,970,408	2,740,000	42,973,112
1940-41	67,072	49,329	17,743	26,358,127	7,720,400	17,812,227	4,000,000	55,890,754
1941-42	61,945	60,128	1,817	25,142,270	5,476,000	14,339,874	3,441,856	48,400,000
1942-43	76,198	76,198	None	37,216,319	3,728,678	24,022,299	3,733,150	68,700,446
1943-44	85,380	85,380	None	42,314,960	2,893,600	31,456,489	4,134,951	80,800,000
1944-45	68,096	68,096	None	33,535,000	1,989,200	29,483,000	3,992,800	69,000,000
1945-46	74,947	74,859	88	39,902,117	2,778,400	41,871,161	4,226,722	86,000,000
1946-47*	76,766	72,199	4,567	37,724,125	4,506,000	36,620,582	4,249,293	83,100,000
1947-48*	58,002	58,002	-	28,772,771	7,518,512	50,423,431	4,301,772	91,100,000 B

NOTES:

* Truck Shipments included with Rail & Boat, their FOB prices being the same.

(A) Includes Export Oranges and Grapefruit 36,757 boxes, and 44,544 boxes Oranges, and 2,213 boxes of Grapefruit, classified as Inter-State By-Products.

(B) Does not include 4,300,000 boxes abandoned for marketing reasons.

(2) Domestic Boat in Coastwise Trade.

(3) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intra-state truck shipments, etc.

(4) Fruit fly year when production, harvest and shipments restricted.

(#) Includes 2,512,323 boxes diverted to other uses.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 21 YEARS

Records and Estimates Season ALL CITRUS	Cost of Production(2) before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return(1) Rail & Boat Shipments Net Value	Estimated Net Return All Citrus Harvested and Used Net Value	Estimated Gross FOB Returns Rail& Boat Shipments Gross Value	Estimated Gross Return All Citrus Harvested and Used Gross Value
1927-28	$0.63	$1.28	$3.74	$1.83	$24,964,592	$ 26,980,492	$50,958,663	$54,714,663
1928-29	.64	1.25	2.08	.19	4,361,670	5,698,063	47,405,291	52,217,851
1929-30(4)	.71	1.29	3.19	1.19	16,942,604	18,320,604	45,399,313	49,097,313
1930-31	.43	1.10	1.86	.33	8,920,948	10,037,572	50,569,525	56,293,572
1931-32	.53	.92	1.95	.50	9,442,872	10,943,166	36,948,353	42,691,957
1932-33	.45	.90	1.36	.01½	309,774	562,466	27,465,441	32,616,451
1933-34	.44	.87	1.65	.33½	7,022,618	10,009,011	34,451,906	42,401,191
1934-35	.43	.88	1.63	.32	6,387,160	8,855,935	32,724,487	42,797,752
1935-36	.44	.94	2.14	.76	14,717,619	20,211,899	41,206,791	53,189,191
1936-37	.37	.92	2.04	.75	19,583,547	24,579,298	53,611,677	68,838,758
1937-38	.38	.88	1.57	.30½	8,020,166	8,988,419	41,370,281	53,285,352
1938-39	.34	.82	1.31	.15	5,228,990	3,693,314	44,446,374	58,646,931
1939-40	.42	.90	1.60	.28	6,003,437	5,014,792	34,341,712	50,365,127
1940-41	.39	.85	1.51	.27	7,113,479	8,831,633	39,711,619	64,192,695
1941-42	.43	.89	2.06	.74	18,512,334	27,639,289	51,815,921	80,572,620
1942-43	.39	1.01	2.81	1.41	52,567,333	76,284,772	104,759,215	153,052,989
1943-44	.49	1.24	3.01	1.28	54,036,891	94,032,066	127,207,221	199,688,696
1944-45	.483	1.25	3.483	1.75	58,913,420	111,913,564	116,804,250	201,912,530
1945-46	.46	1.25	3.44	1.73	64,336,904	125,551,850	127,451,035	236,230,700
1946-47*	.50	1.24	2.59	.85	31,591,356	36,791,631	100,679,009	146,565,580
1947-48*	.48	1.29	2.08	.31	11,149,258	8,846,162	75,614,684	114,925,896 A

NOTES:

* Truck Shipments included with Rail & Boat, their FOB prices being the same.

(A) Does not include the production **value** of 4,300,000 **boxes** abandoned for marketing reasons.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting for taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(4) Fruit fly year when production, harvest and shipments restricted.

FREIGHT CARLOT SHIPMENTS FROM FLORIDA BY COMMODITIES AND MONTHS, FOR 1947-48 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	50		703	3082	4062	4418	4254	4816	4396	4055	3114	574	33,524
Grapefruit	6	98	2202	1505	886	1027	1313	1177	1396	1339	698	154	11,801
Tangerines				376	1311	1020	177						2,884
Mixed Citrus	8		125	699	1342	1199	890	547	648	678	413	118	6,667
TOTAL CITRUS	64	98	3030	5662	7601	7664	6634	6540	6440	6072	4225	846	54,876
Strawberries					3	3	18	32					56
Watermelons									30	5109	3781	327	9,247
TOTAL MISCL. FRUITS					3	3	18	32	30	5109	3781	327	9,303
Beans(incl.Limas)			19	237	782	407	200	698	559	228	18		3,148
Cabbage					113	519	792	1455	1917	137	1		4,934
Celery				24	348	1122	1636	1758	1781	1653	644		8,966
Corn, Green								3	55	128	152		338
Cucumbers			15	223	176	13		115	787	171			1,500
Eggplant		1						3	23	66	77	12	182
Escarole				42	186	279	161	147	127	97			1,039
Lettuce & Romaine				18	39	10	14	9					90
Peas, English						6	7			3			16
Peppers				9	19	16	47	392	313	539	164		1,499
Potatoes					1	89	630	1021	1620	1439	7		4,807
Tomatoes				37	530	378	92	293	802	1642	8		3,782
Other Vegetables	2				18	38	56	17	13	13	5	19	181
Mixed Car Vegetables			34	99	464	449	584	962	1065	633	151	1	4,442
TOTAL VEGETABLES	2	1	68	689	2676	3326	4219	6873	9062	6749	1227	32	34,924
NON-CITRUS & VEGS.	2	1	68	689	2679	3329	4237	6905	9092	11858	5008	359	44,227
ALL FRUITS & VEGS.	66	99	3098	6351	10280	10993	10871	13445	15532	17930	9233	1205	99,103

PICK-UP-EXPRESS SHIPMENTS FROM FLORIDA STATIONS FOR 1947-48 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Mixed Citrus				36	1415	374	516	346	243	113	51	21	3,115
Mixed Vegetables	31	29	47	62	64	58	29	32	30	64	66	21	533
TOTAL FRUITS & VEGS.	31	29	47	98	1479	432	545	378	273	177	117	42	3,648

RAIL - FREIGHT & EXPRESS CARLOT SHIPMENTS, FOR 1947-48 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	50		703	3082	4062	4418	4254	4816	4396	4055	3114	574	33,524
Grapefruit	6	98	2202	1505	886	1027	1313	1177	1396	1339	698	154	11,801
Tangerines				376	1311	1020	177						2,884
Mixed Citrus	8		125	735	2757	1573	1406	893	891	791	464	139	9,782
TOTAL CITRUS	64	98	3030	5698	9016	8038	7150	6886	6683	6185	4276	867	57,991
Strawberries						3	3	18	32				56
Watermelons										30	5109	3781	327	9,247
TOTAL MISCL. FRUITS					3	3	18	32	30	5109	3781	327	9,303
Beans(incl. Limas)			19	237	782	407	200	698	559	228	18		3,148
Cabbage					113	519	792	1455	1917	137	1		4,934
Celery				24	348	1122	1636	1758	1781	1653	644		8,966
Corn, Green								3	55	128	152		338
Cucumbers			15	223	176	13		115	787	171			1,500
Eggplant		1						3	23	66	77	12	182
Escarole				42	186	279	161	147	127	97			1,039
Lettuce & Romaine				18	39	10	14	9					90
Peas, English						6	7			3			16
Peppers				9	19	16	47	392	313	539	164		1,499
Potatoes					1	89	630	1021	1620	1439	7		4,807
Tomatoes				37	530	378	92	293	802	1642	8		3,782
Other Vegetables	2				18	38	56	17	13	13	5	19	181
Mixed Car Vegetables	31	29	81	161	528	507	613	994	1095	697	217	22	4,975
TOTAL VEGETABLES	33	30	115	751	2740	3384	4248	6905	9092	6813	1293	53	35,457
NON-CITRUS & VEGS.	33	30	115	751	2743	3387	4266	6937	9122	11022	5074	380	44,760
ALL FRUITS & VEGS.	97	128	3145	6449	11759	11425	11416	13823	15805	18107	9350	1247	102,751

NOTES: Other Vegetables include straight freight cars as enumerated: Broccoli 3, Carrots 48, Cauliflower 28, Greens(ex.Spinach) 61, Spinach 8, Sweet Potatoes 31, Turnips 2. Total 181.

BOAT SHIPMENTS (Carlot Equivalent FROM FLORIDA PORTS (Does not include initial rail haul exports).

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Sweet Potatoes			1			1	1	1	1				5

NOTE: No Domestic Boat Shipments of Citrus reported.

FLORIDA INTERSTATE TRUCK SHIPMENT PASSINGS 1947-48 SEASON

Actual Check at Nine Road Guard Stations October 16 -May 31
Estimated for August 1-October 15 and June 1-July 31 Periods

COMMODITY	Aug.	Sept	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	7	4	675	1547	2376	1568	1810	1990	1550	1583	944	214	14,268
Grapefruit	18	61	376	309	206	267	306	329	324	360	204	98	2,858
Tangerines			1cl	261	697	559	149	4	1cl				1,670
TOTAL CITRUS	25	65	1051	2117	3279	2394	2265	2323	1874	1943	1148	312	18,796
Avocados	10	10	16	28	7	1				1cl		10	82
Limes	6	4	1	2	1	1cl	1cl	1	1	4		10	30
Strawberries				1cl	41	50	89	128	10	3			321
Watermelons									1cl	1754	1549	200	3,503
Other Non-Citrus Frts	2	2								29	3	2	38
TOTAL MISC. FRUITS	18	16	17	30	49	51	89	129	11	1790	1552	222	3,974
Beans, Snap			21	352	742	471	457	1009	833	285	2		4,172
Limas					1cl	63	30	47	103	92	8		343
Baby Limas									10	111	22	2	145
Cabbage			1cl	2	147	644	972	1143	947	128			3,983
Celery				7	66	230	298	313	225	162	80		1,381
Corn, Green					1cl	1	1cl	1	138	398	109	15	662
Cucumbers			41	205	158	105	49	245	862	321	10	3	1,999
Eggplant	1	1	3	14	19	20	21	89	238	190	128	30	754
Escarole				5	48	25	40	24	31	27			200
Field Peas	5	5	4	5	1	1cl		1cl	135	505	129	15	804
Lettuce & Romaine				3	20	46	19	8	7				103
Okra	4	2	7	8	1	1	1	4	11	77	50	20	186
Peas, English				1cl	4	4	3	4	3				18
Peppers			2	12	39	72	256	447	511	542	91	15	1,987
Potatoes					8	61	125	290	424	370			1,278
Squash			4	45	85	85	65	175	273	81	2		815
Tomatoes				34	237	381	274	357	776	1521	241	5	3,826
Bunched Vegetables				1	11	25	28	27	17	1			110
Other Vegetables	1		1cl	5	31	103	201	168	54	34	7	15	619
TOTAL VEGETABLES	11	8	82	698	1617	2337	2839	4351	5598	4845	879	120	23,385
VEGS. & MISC. FRUITS	29	24	99	728	1666	2388	2928	4480	5609	6635	2431	342	27,359
GRAND TOTAL	54	89	1150	2845	4945	4782	5193	6803	7483	8578	3579	654	46,155

See bottom of page 30 for conversion factors.

CARLOT SHIPMENTS (FREIGHT, EXPRESS, BOAT & TRUCK) FRUITS AND VEGETABLES BY MONTHS FOR SEASON 1947-48

August 1-July 31 (Truck October 16-May 31 except where estimated)

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	57	4	1378	4629	6438	5986	6064	6806	5946	5638	4058	788	47,792
Grapefruit	24	159	2578	1814	1092	1294	1619	1506	1720	1699	902	252	14,659
Tangerines			1cl	637	2008	1579	326	4	1cl				4,554
Mixed Citrus	8	-	125	735	2757	1573	1406	893	891	791	464	139	9,782
TOTAL CITRUS	89	163	4081	7815	12295	10432	9415	9209	8557	8128	5424	1179	76,787
Avocados	10	10	16	28	7	1	-	-		1cl	-	10	82
Limes	6	4	1	2	1	1cl	1cl	1	1	4	-	10	30
Strawberries				1cl	44	53	107	160	10	3			377
Watermelons									30	6863	5330	527	12,750
Other Non-Citrus	2	2	-	-	-	-	-	-	-	29	3	2	38
TOTAL MISC. FRUITS	18	16	17	30	52	54	107	161	41	6899	5333	549	13,277
Beans (incl. Limas)			40	589	1524	941	687	1754	1495	605	28		7,663
Cabbage			1cl	2	260	1163	1764	2598	2864	265	1		8,917
Celery				31	414	1352	1934	2071	2006	1815	724		10,347
Corn, Green					1cl	1	1cl	4	193	526	261	15	1,000
Cucumbers			56	428	334	118	49	360	1649	492	10	3	3,499
Eggplant	1	2	3	14	19	20	21	92	261	256	205	42	936
Escarole				47	234	304	201	171	158	124			1,239
Lettuce & Romaine				21	59	56	33	17	7				193
Peas, English					4	10	10	4	3	3			34
Peppers			2	21	58	88	303	839	824	1031	255	15	3,486
Potatoes					9	150	755	1311	2044	1809	7		6,085
Tomatoes				71	767	759	366	650	1578	3163	249	5	7,608
Other Vegetables	11	7	16	59	116	150	151	224	460	786	208	56	2,246
Mixed Car Vegetables	32	29	81	166	559	610	814	1162	1149	731	224	37	5,594
TOTAL VEGETABLES	44	38	198	1449	4357	5722	7088	11257	14691	11658	2172	173	58,847
VEGS. & MISC. FRUITS	62	54	215	1479	4409	5776	7195	11418	14732	18557	7505	722	72,124
ALL FRUITS & VEGS.	151	217	4296	9294	16704	16208	16610	20627	23289	26685	12929	1901	148,911

NOTES FOR TRUCK SHIPMENTS (See previous page): The above vegetable and non-citrus passings were checked at Florida State Road Guard Stations October 16, 1947 to August 31, 1948. August 1 to October 16 passings were estimated, based on general information available. June and July were likewise estimated.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS

(These figures have been revised and rearranged and may not agree or seem to agree with some previous tabulations. The totals are substantially the same.)

Commodity	Freight Shipments 1938-39	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48
Oranges	31,065	24,812	27,084	34,374	43,390	51,405	41,049	41,848	43,390	33,524
Grapefruit	13,290	6,832	12,135	12,650	12,258	13,441	8,534	12,201	12,606	11,801
Tangerines	2,817	1,896	2,171	1,865	5,017	3,856	4,370	3,813	2,974	2,884
Mixed Citrus	11,073	7,249	6,770	10,062	13,162	13,626	11,102	13,573	9,599	6,667
Total Citrus	58,245	40,789	48,160	58,951	73,827	82,328	65,055	71,435	68,569	54,876
Strawberries	686	43	4	-	6	22	43	25	99	56
Watermelons	3,406	4,977	5,028	5,565	3,363	6,116	8,366	7,470	7,963	9,247
Miscl.Fruits	-	-	2	-	-	16	15	3	9	-
Total Non-Citrus	4,092	5,020	5,034	5,565	3,369	6,154	8,424	7,498	8,071	9,303
Beans & Limas	4,431	2,910	2,700	3,335	5,943	6,596	4,682	4,538	3,668	3,148
Cabbage	1,610	4,238	2,256	3,568	4,534	6,378	5,157	4,763	2,459	4,934
Celery	7,696	7,769	8,689	9,119	8,557	9,349	11,037	12,489	8,747	8,966
Corn, Green	32	22	2	7	17	18	42	104	166	338
Cucumbers	809	1,153	981	1,181	461	405	988	1,549	1,138	1,500
Eggplant	23	-	36	29	175	246	304	251	81	182
Escarole	816	882	573	818	1,003	1,120	1,347	1,317	827	1,039
Lettuce	233	371	235	147	197	207	152	166	116	90
Peas, English	186	270	80	130	115	153	83	62	14	16
Peppers	719	516	647	863	1,352	1,805	1,622	1,612	744	1,499
Potatoes	3,767	5,116	3,306	5,540	4,756	5,282	7,068	9,591	4,001	4,807
Tomatoes	8,660	5,222	3,679	5,035	4,367	4,592	5,305	5,269	3,249	3,782
Squash (estimated)	300	275	275	300	400	400	500	400	400*	500*
Other Variety Vegs.	29	25	36	86	133	364	426	484	224	181
Mixed Car Vegetables	2,681	1,427	1,354	2,113	3,973	5,855	6,884	7,217	4,704	4,442
Total Vegetables	31,992	30,196	24,849	32,271	35,983	42,770	45,597	49,812	30,538	35,424
Total Vegs.& Non-Cit.	36,084	35,216	29,883	37,836	39,352	48,924	54,021	57,310	38,609	44,727
ALL FRUITS & VEGS.	94,329	76,005	78,043	96,787	113,179	131,252	119,076	128,745	107,178	99,603

NOTES: Mixed Citrus includes oranges, grapefruit, tangerines; usually around 57% oranges, 29% grapefruit, and 14% tangerines. Miscl. Fruits include any lemons and cantaloupes. Mixed Car of Vegetables may include beans, cabbage, eggplant, peppers, squash, and practically any other Florida vegetables. Other Variety Vegetables may include straight cars of broccoli, turnips, carrots, cauliflower, greens, spinach, sweet potatoes, etc. The mixed car analysis varies from year to year.

No provision is made by Federal Government for a report on straight cars of radishes and squash which are shipped each year. * Squash carlots estimated at 500 carloads.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRASNPORTATION FOR TEN SEASONS (Cont'd.)

Commodity	1938-39	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48
	Express Shipments									
EXPRESS										
Mixed Citrus	688	972	1,169	1,177	2,371	3,100	3,041	3,376	3,630	3,115
Strawberries	235	180	47	58	55	1	-	-	-	-
Miscl. Fruits	100*	75*	75*	125*	175*	175*	90*	90*	100*	100*
Total Non-Citrus	335	255	122	183	230	176	90	90	100	100
Beans & Limas	44	76	45	-	-	-	-	-	-	-
Tomatoes	-	-	-	-	-	-	-	-	-	-
Mixed Car Vegs.	550	388	396	605	1,074	1,283	1,148	1,179	848	533
Total Vegetables	594	464	441	605	1,074	1,283	1,148	1,179	848	533
Total Vegs.& Non-Cit.	929	719	563	788	1,304	1,459	1,148	1,179	948	633
ALL FRUITS & VEGS.	1,617	1,691	1,732	1,965	3,675	4,559	4,279	4,645	4,578	3,748
BOAT					Boat Shipments					
Oranges	18,311	8,997	11,189	1,153				76	2,908	-
Grapefruit	7,992	3,812	5,481	514				12	1,437	-
Tangerines	1,819	735	1,063	147				-	222	-
Mixed Citrus	12	5	10	3				-	-	-
Total Citrus	28,134	13,549	17,743	1,817	No record of any			88	4,567	-
Strawberries	-	-	-	-				-	-	-
Watermelons	17	16	-	-	boat shipments			-	-	-
Miscl. Fruits	10	10	5	-				-	-	-
Total Non-Citrus	27	26	5	-	during (War Period)			-	-	-
Beans & Limas	662	211	154	1				-	-	-
Cabbage	20	21	14	-	1942-43 thru			-	-	-
Celery	335	117	148	-				-	100	-
Corn, Green	-	-	-	-	1944-45 seasons.			-	3	-
Cucumbers	86	32	40	-				-	3	-
Eggplant	279	11	35	-				-	-	-
Escarole	2	1	-	-				-	-	-
Lettuce	-	-	-	-				-	-	-
Peas, English	1	-	1	-				-	-	-
Peppers	1,107	241	163	6				-	-	-
Potatoes	1,674	1,176	898	-				-	164	-
Tomatoes	114	34	13	-				-	-	-
Squash	80	80	40	1				-	-	-
Other Variety Vegs.	175	171	103	3				-	2	5
Total Vegetables	4,535	2,095	1,609	11				-	272	5
Total Vegs. Non-Cit.	4,562	2,121	1,614	11				-	272	5
ALL FRUITS & VEGS.	32,696	15,670	19,357	1,828				88	4,839	5

* Most of this volume is estimated amount of LCL express avocados, limes, mangoes, etc. Includes a few cars of limes and cantaloupes.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

Commodity	Trucked Out Shipments									
	1938-39	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48
Oranges	12,939	11,148	14,315	10,248	6,790	5,388	3,641	5,135	8,774	14,268
Grapefruit	3,681	2,546	3,699	2,605	1,532	869	513	851	1,395	2,858
Tangerines	1,196	1,105	1,087	837	1,000	957	819	960	1,096	1,670
Total Citrus	17,816	14,799	19,301	13,690	9,322	7,234	4,973	6,946	11,265	18,796
Strawberries	1,190	1,228	1,073	860	300	164	263	446	615	321
Watermelons	990	838	976	695	190	630	654	2,538	3,278	3,503
Miscl. Fruits	328	496	321	250	110	192	452	182	181	150
Total Non-Citrus	2,508	2,562	2,370	1,805	600	986	1,369	3,166	4,074	3,974
Beans & Limas	6,075	5,020	5,485	6,526	2,400	2,504	2,257	3,129	3,448	4,515
Cabbage	2,487	4,959	2,298	3,539	1,900	2,116	1,449	2,083	3,003	3,983
Celery	684	1,260	1,681	1,582	360	401	405	566	1,020	1,381
Corn, Green	409	399	219	200	150	190	121	392	479	662
Cucumbers	800	1,269	1,196	866	265	250	444	741	896	1,999
Eggplant	620	301	566	734	300	525	380	682	756	754
Escarole	15	257	203	116	15	7	25	20	145	200
Lettuce	104	204	232	150	26	54	51	93	90	103
Peas, English	295	268	221	222	20	77	53	52	26	18
Peppers	1,155	936	1,445	1,656	900	865	809	1,524	1,586	1,987
Potatoes	642	1,289	1,068	1,116	500	426	872	759	701	1,278
Tomatoes	5,243	3,635	3,988	3,994	1,700	3,190	2,826	3,549	2,526	3,826
Squash	478	761	560	538	300	440	447	653	645	815
Other Variety Vegs.	306	793	859	805	450	661	680	1,249	1,347	1,864*
Total Vegetables	19,313	21,351	20,041	22,044	9,286	11,706	10,819	15,492	16,668	23,385
Total Vegs.& Non-Cit.	21,821	23,913	22,411	23,849	9,886	12,692	12,188	18,658	20,742	27,359
ALL FRUITS & VEGS.	39,637	38,712	41,712	37,539	19,208	19,926	17,161	25,604	32,007	46,155

* Other Vegetables include carloads as follows: Butterbeans 145, Field Peas 804, Okra 186, Bunched Vegetables 110, and Miscellaneous Vegetables 619.

NOTE: Shipments in packages, pounds, dozens, or units were converted in 1947-48 season as follows: Beans 600, limas 500, cabbage 25,000 lbs., celery 370, cucumbers 450, eggplant 470, escarole 450, lettuce 550, English peas 580, peppers 480, potatoes 550, strawberries 450, tomatoes 500, okra 500, squash 500, bunched vegetables 2,000 dozen, green corn 2,000 dozen, field peas 500, other vegetables 500, avocados 700, limes 800, watermelons 1,000, other fruits 500, all citrus 400. See page 26 for Truck Shipments in more detail for 1947-48 season.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

	Total Freight, Express, Boat and Truck Shipments from Florida									
Commodity	1938-39	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48
Oranges	62,315	44,957	52,588	45,775	50,180	56,793	44,690	47,059	55,072	47,792
Grapefruit	24,963	13,190	21,515	15,769	13,790	14,330	9,047	13,064	15,438	14,659
Tangerines	5,832	3,736	4,321	2,849	6,017	4,813	5,189	4,773	4,292	4,554
Mixed Citrus	11,773	8,226	7,949	11,242	15,533	16,726	14,143	16,949	13,229	9,782
Total Citrus	104,883	70,109	86,373	75,635	85,520	92,662	73,069	81,845	88,031	76,787
Strawberries	2,111	1,451	1,124	918	361	187	306	471	714	377
Watermelons	4,413	5,831	6,004	6,260	3,553	6,746	9,020	10,008	11,241	12,750
Miscl. Fruits	438	581	403	375	235	383	467	185	280	150
Total Non-Citrus	6,962	7,863	7,531	7,553	4,199	7,316	9,793	10,664	12,235	13,277
Beans & Limas	11,212	8,217	8,384	9,862	8,343	9,100	6,939	7,667	7,116	7,663
Cabbage	4,117	9,218	4,568	7,107	6,434	8,494	6,606	6,846	5,462	8,917
Celery	8,715	9,146	10,518	10,701	8,917	9,750	11,442	13,055	9,867	10,347
Corn, Green	441	421	221	207	167	208	163	496	648	1,000
Cucumbers	1,695	2,454	2,217	2,047	726	655	1,432	2,290	2,037	3,499
Eggplant	922	312	657	763	475	771	684	933	837	936
Escarole	833	1,140	776	934	1,018	1,127	1,372	1,337	972	1,239
Lettuce	337	575	467	297	223	261	203	259	206	193
Peas, English	482	538	302	352	135	230	136	114	40	34
Peppers	2,981	1,693	2,255	2,525	2,252	2,670	2,431	3,136	2,330	3,486
Potatoes	6,083	7,581	5,272	6,656	5,256	5,708	7,940	10,350	4,866	6,085
Tomatoes	14,017	8,891	7,660	9,029	6,067	7,782	8,131	8,818	5,775	7,608
Squash	858	1,116	875	839	700	840	947	1,053	1,045	815
Other Variety Vegs.	510	989	998	894	583	1,025	881	1,733	1,573	1,431
Mixed Car Vegs.	3,231	1,815	1,750	2,718	5,047	7,138	8,257	8,396	5,552	5,594
Total Vegetables	56,434	54,106	46,940	54,931	46,343	55,759	57,564	66,483	48,326	58,847
Total Vegs.& Non-Cit.	63,396	61,969	54,471	62,484	50,542	63,075	67,357	77,147	60,571	72,124
ALL FRUITS VEGS.	168,279	132,078	140,844	138,119	136,062	155,737	140,426	158,992	148,602	148,911

NOTE: No boat shipments reported during 1942-43, 1943-44, and 1944-45 seasons due to War restrictions, but there might have been small amounts to the West Indies and some perhaps on Naval vessels or Army transports, if any in Florida waters. See Page 29 for further information regarding boat shipments.

RAIL FREIGHT SHIPMENTS BY COUNTIES
1947-48 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Oranges	Grapefruit	Tangerines	Mixed Citrus	Total Citrus	Beans & Limas	Broccoli	Cabbage
Alachua	108	3	4	7	122	74		36
Bradford						4		
Brevard	1411	477	7	584	2479			
Broward	54				54	917		
Citrus	29	3		4	36			
Clay								24
Collier								1
Columbia								3
Dade	1			116	117	45		69
De Soto	718	8	47	113	886			
Duval	834	52	120	113	1119			
Escambia								
Flagler								35
Gilchrist								
Glades								184
Hamilton								4
Hardee	61	5	4	3	73			4
Hendry								272
Hernando	120	1	123	71	315			
Highlands	1353	497	58	120	2028			
Hillsborough	1375	195	47	175	1792	3		76
Holmes								
Indian River	467	1227	4	521	2219			10
Jackson								
Jefferson								
Lafayette								
Lake	3211	318	222	858	4609	8		17
Lee	101	25	2	14	142			
Leon								
Levy								
Madison								
Manatee	98	176		76	350			155
Marion	1857	77	29	120	2083	27		28
Martin								2
Okeechobee				1	1			1
Orange	8188	533	775	791	10287	33		260
Osceola	128	31	12	27	198			
Palm Beach	7	5		1	13	1986	3	1529
Pasco	286	134	73	103	596			
Pinellas	524	1307	77	414	2322			
Polk	9098	5407	781	2091	17377	1		32
Putnam	94	1	71	35	201			177
St. Johns	2				2			1142
St. Lucie	1361	1226	22	508	3117			63
Sarasota	12	12		1	25			32
Seminole	1569	63	159	232	2023	41		573
Sumter				1	1	8		11
Suwannee								
Taylor								
Union						1		19
Volusia	457	18	247	311	1033			175
Washington								
				(-744)*	(-744)*			
Straight Cars	33524	11801	2884	7411*	55620*	3148	3	4934
Boat								
Pick-Up-Exp.				2371*	2371*			
GRAND TOTAL	33524	11801	2884	9782	57991	3148	3	4934

As of September 2, 1948. Subject to Revision.

* 744 straight cars express which was distributed by counties should be deducted from freight and added to express, thus making 3115 for mixed citrus and total citrus by express.

RAIL FREIGHT SHIPMENTS BY COUNTIES
1947-48 SEASON
(August 1-July 31)

CARLOTS Florida Counties	Carrots	Cauliflower	Celery	Green Corn	Cucumbers	Eggplant	Escarole	Greens
Alachua			43		53	9		
Bradford					1			
Brevard								
Broward					32	20		8
Citrus								
Clay								
Collier					112			
Columbia				7				
Dade				3	8			9
De Soto					5			
Duval								
Escambia								
Flagler								
Gilchrist								
Glades				4	20			
Hamilton								
Hardee					202			
Hendry					9			
Hernando								
Highlands	2							
Hillsborough		21	5	19	164	45	5	
Holmes								
Indian River								
Jackson								
Jefferson								
Lafayette								
Lake			810		5			
Lee				3	144	15		
Leon								
Levy				7				
Madison								
Manatee		6	5		207	36	171	
Marion			194		9	1		2
Martin								
Okeechobee								
Orange	44		400	180	115		195	
Osceola								
Palm Beach			2155	72	13	55	438	22
Pasco								
Pinellas								
Polk								
Putnam					6			
St. Johns								
St. Lucie		1			20			20
Sarasota			1411		42			
Seminole	2		3943	42			230	
Sumter					326	1		
Suwannee					5			
Taylor								
Union				1	2			
Volusia								
Washington								
Straight Cars	48	28	8966	338	1500	182	1039	61
Boat								
Pick-Up-Exp.								
GRAND TOTAL	48	28	8966	338	1500	182	1039	61

RAIL FREIGHT SHIPMENTS BY COUNTIES
1947-48 SEASON
(August 1-July 31)

CARLOTS Florida Counties	Lettuce & Romaine	Peas English	Peppers	Potatoes	Spinach	Sweet Potatoes	Tomatoes	Turnips
Alachua	1		95	110	1	14		
Bradford			1					
Brevard								
Broward			526				236	
Citrus								
Clay				1				
Collier							73	
Columbia								
Dade			1	1569			445	
De Soto								
Duval								
Escambia				6		1		
Flagler				543				
Gilchrist								
Glades								
Hamilton								
Hardee			9				84	
Hendry	6							
Hernando								
Highlands		2						
Hillsborough	5		414	2		4	573	
Holmes								
Indian River							135	
Jackson								2
Jefferson								
Lafayette								
Lake			4		7	4	2	
Lee			21	318			2	
Leon						1		
Levy								
Madison								
Manatee	8		1				806	
Marion	7			5			30	
Martin			1			7		
Okeechobee							222	
Orange	7		35	1				
Osceola								
Palm Beach	11	13	108	205			3	
Pasco								
Pinellas								
Polk			8					
Putnam				169				
St. Johns				1877				
St. Lucie		1		1			1146	
Sarasota			2					
Seminole	45		142				18	
Sumter			131				7	
Suwannee								
Taylor								
Union								
Volusia								
Washington								
Straight Cars	90	16	1499	4807	8	31	3782	2
Boat						5		
Pick-Up-Exp.								
GRAND TOTAL	90	16	1499	4807	8	36	3782	2

RAIL FREIGHT SHIPMENTS BY COUNTIES
1947-48 SEASON
(August 1-July 31)

CARLOTS Florida Counties	Mixed Veg's	Total Vegetables	Straw-berries	Water-melons	Total Non-Citrus	Total Veg's & Non-Citrus	GRAND TOTAL
Alachua	84	520		834	834	1354	1476
Bradford		6				6	6
Brevard				2	2	2	2481
Broward	1342	3081				3081	3135
Citrus				29	29	29	65
Clay		25				25	25
Collier	3	189		7	7	196	196
Columbia		10		18	18	28	28
Dade	12	2161				2161	2278
De Soto		5		71	71	76	962
Duval							1119
Escambia		7				7	7
Flagler	1	579				579	579
Gilchrist				1298	1298	1298	1298
Glades	1	209				209	209
Hamilton		4		22	22	26	26
Hardee	43	342				342	415
Hendry		287				287	287
Hernando							315
Highlands	46	50		7	7	57	2035
Hillsborough	344	1680	56	313	369	2049	3841
Holmes				1	1	1	1
Indian River		145		3	3	148	2367
Jackson	7	9		80	80	89	89
Jefferson				390	390	390	390
Lafayette				28	28	28	28
Lake	2	859		1958	1958	2817	7426
Lee	93	596				596	738
Leon		1				1	1
Levy		7		538	538	545	545
Madison				120	120	120	120
Manatee	72	1467				1467	1817
Marion	191	494		1323	1323	1817	3900
Martin	82	92				92	92
Okeechobee		223				223	224
Orange	276	1546		17	17	1563	11850
Osceola							198
Palm Beach	1280	7893				7893	7906
Pasco				313	313	313	909
Pinellas				13	13	13	2335
Polk		41		121	121	162	17539
Putnam		352		23	23	375	576
St. Johns	36	3055				3055	3057
St. Lucie	9	1261		28	28	1289	4406
Sarasota	7	1494				1494	1519
Seminole	420	5456				5456	7479
Sumter	91	575		1039	1039	1614	1615
Suwannee		5		580	580	585	585
Taylor				2	2	2	2
Union		23		19	19	42	42
Volusia		175		43	43	218	1251
Washington				7	7	7	7
							(-744)*
Straight Cars	4442	34924	56	9247	9303	44227	99847*
Boat		5				5	5
Pick-Up-Exp.	533	533				533	2904*
GRAND TOTAL	4975	35462	56	9247	9303	44765	102756

As of September 2, 1948. Subject to Revision.

* 744 straight cars of mixed citrus express distributed by counties should be deducted from freight and added to express, thus making total express 3648 carloads.

FEDERAL-STATE INSPECTION SERVICE
July 1, 1947 - June 30, 1948

FLORIDA Commodities	Type Container	No.of Cars Inspected	No. Units or Containers	Average Containers (or Units per Car) 1947-48	1946-47	1945-46	1944-45
CITRUS							
Oranges	Std.Box Equiv.	32,238	16,091,481	499	503	502	505
Grapefruit	"	11,073	5,701,651	515	515	514	514
Tangerines	"	2,835	1,237,453	437	442	449	452
Mixed Citrus	"	7,069	3,494,287	494	505	497	494
Total Citrus		53,215	26,524,872	498			
VEGETABLES							
Beans	Bu.	11	6,993	636	641	638	620
Cabbage	50# Bags	1,990	997,370	501	503	501	508
"	Crts.	1,270	610,491	481	--	-	-
"	1½ bu. Hprs.	-	-	-	424	-	-
Cauliflower	Crts.	20	11,129	556	-	-	453
Celery	Crts.	7,800	3,318,887	426	425	445	443
Corn	Crts.	21	10,717	510	442	--	-
"	50# Sks.	-	-	-	-	696	620
Cucumbers	Bu.	207	77,136	373?	459	437	570
Escarole	Bu.	5	3,200	640	612	642	610
Peppers	Bu.	91	47,856	526	672	652	782
"	1½ Bu.Crts.	-	-	-	-	-	471
Potatoes	Coml.50# Bags	1,995	1,279,104	641	651	619	638
"	" 100# "	1,898	563,818	297	307	300	300
"	P.M.A.100# "	7	2,520	360	355	300	-
"	Bu.	-	-	-	563	--	642
Tomatoes	Lugs	1,597	1,087,531	681	693	689	691
Sweet Potatoes		8	4,313	539	527	552	539
Mixed & Miscl.		25	10,168	407	602	-	578
Total Vegetables		16,945					
Limes	Std. Box	12	4,786	399	-	364	397
Watermelons	Melons	7,916	7,794,500	985	938	1008	1058
Total Fruits & Vegetables		78,088					
Peanuts	Bulk-100 lbs.	74	37,630	508	481	-	502
Grand Total Carlots-1947-48		78,162					
1946-47		85,934					

NOTE: Except for citrus, celery, cabbage, potatoes, tomatoes and watermelons, the inspection sample was too limited to indicate the actual rail carlot loadings. Loadings are different in different sections of Florida. In some sections the Federal-State inspections are used little except when mandatory. For some vegetables the official inspections are little used.

The above is tabulated from a report made by Mr. Hugh S. Flynt, Assistant Director, Vegetable Branch, Citrus and Vegetable Inspection Division, Florida Department of Agriculture, Room 305, Post Office Building, Orlando, Florida.

INSPECTIONS OF FLORIDA CITRUS FOR SHIPMENT
BY RAIL AND TRUCK BY COUNTIES
SEASON AUGUST 1, 1947 - JULY 31, 1948
BOXES (1-3/5 bushels)

County	Grapefruit	Oranges	Tangerines	Total 1947-48	Total 1946-47
Alachua	3,788	59,936	2,755	66,479	94,695
Brevard	368,318	919,709	19,913	1,307,940	1,031,952
Broward	6,780	73,692	973	81,445	181,345
Citrus	3,542	25,565	1,181	30,288	32,919
Dade	33,746	85,588	325	119,659	94,624
DeSoto	51,834	673,884	54,644	780,362	788,770
Duval	45,515	474,109	94,216	613,840	749,246
Hardee	854	35,331	2,906	39,091	16,553
Hernando	11,785	104,124	63,900	179,809	322,347
Highlands	291,581	762,569	38,654	1,092,804	1,314,509
Hillsborough	204,727	1,064,907	76,279	1,345,913	1,743,232
Indian River	822,634	435,605	12,287	1,270,526	1,325,819
Lake	319,660	2,541,374	255,621	3,116,655	3,955,427
Lee	13,519	64,727	2,921	81,167	139,440
Manatee	118,922	79,255	504	198,681	199,464
Marion	79,383	1,338,041	29,233	1,446,657	1,588,329
Orange	522,044	5,971,463	577,655	7,071,162	7,622,162
Osceola	45,413	221,428	32,789	299,630	328,312
Palm Beach	31,718	75,515	4,067	111,300	146,280
Pasco	99,249	235,602	48,791	383,642	369,220
Pinellas	841,200	449,642	51,450	1,342,292	1,327,337
Polk	3,791,170	6,493,027	577,816	10,862,013	13,437,088
Putnam	9,788	133,797	54,923	198,508	260,350
St. Johns	73	29,218	-	29,291	27,910
St. Lucie	809,003	950,260	36,929	1,796,192	1,943,367
Sarasota	6,486	6,536	-	13,022	93,527
Seminole	111,403	1,369,147	161,016	1,641,566	1,917,621
Volusia	40,961	469,566	178,898	689,425	865,123
Others	60	1,102	-	1,162	-
TOTAL	8,685,156	25,144,719	2,380,646	36,210,521	41,917,606
Used '47-48	29,300,000	58,400,000	3,400,000	91,100,000	83,100,000

NOTE: Some commodities are produced in one County and inspected in another County. These inspections do not include fruit for processing and some other classes of fruit.

- - - - - -

PERSIAN CERTIFIED LIME SHIPMENTS - By Counties, By Months - Season 1947-48
(In Terms of Equivalent Standard Boxes, 1-3/5 Bushels)

	Dade	Highlands	Hillsborough	Pinellas	Polk	Totals
July, 1947	29,595	3,945	2,836	716	3,595	40,687
Aug. "	25,920	3,882	1,701	221	5,146	36,870
Sept. "	10,372	1,314	506		708	12,900
Oct. "	6,050	328			38	6,416
Nov. "	4,543	144			65	4,752
Dec. "	4,246	16			708	4,970
Jan., 1948	2,611	3				2,614
Feb. "	1,834	145				1,979
Mar. "	2,972	231				3,203
Apr. "	5,043	221				5,264
May "	9,839	529				10,368
June "	26,059	3,375	690	639	901	31,664
TOTAL	129,084	14,133	5,733	1,576	11,161	161,687
Percentage	79.8	8.8	3.5	1.0	6.9	100.0

NOTE: No shipment certifications reported for Broward and DeSoto Counties.

NOTE: The above data supplied by A. L. Scarborough, Statistician, Citrus and Vegetable Inspection Division, Winter Haven, Florida.

TRUCK SHIPMENTS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS BY WEEKS FOR 1947-48 SEASON

(Rail Carload Equivalent)

Oct. 15, 1947-May 31, 1948

Date by Weeks	Beans	Limas	Cabbage	Celery	Cukes	Eggplant	Escarole	Lettuce	Eng. Peas	F.Peas B.Beans	Peppers	Potatoes	Tomatoes
Aug. 1-Oct.14	*					2				10			
Oct. 15-18	LCL			LCL	LCL	LCL		LCL			LCL		LCL
19-25	7		LCL		10	2		LCL		2	LCL	LCL	LCL
Oct. 26-Nov.1	16	LCL	LCL		40	1		LCL		2	3		LCL
Nov. 2-8	36				57	4				2	1		
9-15	76				45	3				1	2		1
16-22	120		LCL	3	54	4	1		LCL	2	2		8
23-29	109		2	3	36	3	4	3	LCL	1	7	LCL	21
Nov. 30-Dec.6	186		5	18	28	2	9	1	LCL	LCL	9	LCL	35
Dec. 7=13	185	LCL	22	7	33	4	14	1	2	LCL	5	1	54
14-20	180	LCL	34	23	58	6	17	8	1	LCL	15	4	78
21-27	108	LCL	29	12	30	4	5	5	1	LCL	8	2	47
Dec. 28-Jan.3	146	1	91	34	21	6	5	10	1	LCL	9	4	90
Jan. 4-10	166	22	129	52	44	7	5	15	2	LCL	16	12	112
11-17	123	18	136	36	25	6	3	14	1	LCL	16	16	82
18-24	68	12	174	67	16	4	8	7	1	LCL	13	16	49
25-31	61	10	171	56	11	2	8	5	LCL		20	14	76
Feb. 1-7	91	10	218	60	12	4	6	5	LCL		56	15	63
8-14	133	7	236	73	15	6	16	4	LCL		58	17	77
15-21	96	4	237	76	10	6	11	5	1		66	36	63
22-28	109	8	239	79	10	5	6	5	1		67	47	57
Feb. 29-Mar.6	229	7	206	80	5	6	6	3	1		87	45	61
Mar. 7-13	264	10	297	87	9	6	1	3	1		114	74	76
14-20	210	9	265	73	32	21	4	1	1		101	82	85
21-27	221	14	250	64	96	34	7	1	1		104	72	111
Mar. 28-Apr.3	196	21	276	38	182	66	11	1	1	LCL	81	64	103
Apr. 4-10	215	46	326	81	244	51	8	6	1	6	99	111	100
11-17	200	21	232	44	288	55	4	LCL	1	19	126	106	131
18-24	173	15	172	45	134	54	14	1	1	46	132	88	219
Apr. 25-May 1	183	13	120	45	138	45	2	LCL		84	150	92	314
May 2-8	114	16	68	39	136	40	6			163	155	123	405
9-15	114	19	35	35	106	49	6			160	160	148	496
16-22	30	43	7	40	50	42	11			153	123	74	322
23-29	6	9	3	35	10	43	4			109	69	13	216
30-31	2	1	LCL	6	2	7	-			21	9	2	34
June 1-30 *	1	8		69	3	128				151	91		241
July 1-31 *						30				17	15		5
Total	4174	344	3980	1380	1990	758	202	104	19	949	1989	1278	3832

*Estimated from special information. (1) LCL means less than rail carload; (2) The above shipments represent passings through Florida Road Guard Stations Oct. 15; 1947 to May 31, 1948; (3) Above truck passings converted into pre-War rail carload equivalent on basis of: Beans 600 bu; Limas 500 bu; Cabbage 25,000 lbs; Celery 370 crates; Cukes 450 bu; Eggplant 470 pkgs; Escarole 450 pkgs; Lettuce 550 pkgs; English Peas 580 bu; Peppers 480 pkgs; Potatoes 550 pkgs; Tomatoes 500 pkgs; Green Corn 2000 doz.

The Weekly Totals differ from, and are usually slightly higher than the Monthly Totals, due to fractional totals by weeks.

TRUCK SHIPMENTS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS
BY WEEKS FOR 1947-48 SEASON

(Rail Carload Equivalent)
Oct. 15, 1947-May 31, 1948

Date by Weeks	Gr. Corn	Okra	Squash	Bun. Vegs.	Oth. Vegs.	Tot. Vegs.	Avocados	Strawberries	Limes	W-mel.	Oth. Fru.	Tot. Fru.	Grand Total
Aug. 1-Oct.14*		6			1	18	20		10		4	34	52
Oct. 15-18		1	LCL		LCL	2	2		LCL		LCL	2	4
19-25		3	2	LCL	1	27	4		LCL			4	31
Oct. 26-Nov.1		3	2	LCL	LCL	67	11		LCL			11	78
2-8		4	3	LCL		107	7		1			8	115
9-15		2	7	LCL	LCL	137	9		1			10	147
16-22		1	17		3	215	7		1			8	223
23-29		1	14	1	2	207	2	LCL	1			3	210
Nov. 30-Dec.6		LCL	15	2	6	316	3	LCL	LCL			3	319
7-13		1	27	1	4	361	2	7	1			10	371
14-20	LCL	LCL	30	4	11	469	1	14	LCL			15	484
21-27	LCL	LCL	10	1	2	264	2	14	LCL			16	280
Dec. 28-Jan.3	LCL	LCL	14	6	16	454	1	14	LCL			15	469
Jan. 4-10	LCL	1	29	6	22	640	LCL	21	LCL			21	661
11-17	LCL	LCL	25	6	13	520	LCL	14	LCL			14	534
18-24	LCL	LCL	14	6	27	482	LCL	6	LCL			6	488
25-31	LCL	LCL	10	5	33	482	LCL	2				2	484
Feb. 1-7	LCL	LCL	10	5	48	603	LCL	5	LCL			5	608
8-14	LCL	LCL	16	6	55	719	LCL	9	LCL			9	728
15-21	LCL	LCL	14	8	47	680		17				17	697
22-28	LCL	1	19	8	42	703		48	LCL			48	751
Feb. 29-Mar.6	LCL	1	26	8	43	814		66	LCL			66	880
Mar. 7-13	LCL	1	27	7	47	1024		28	LCL			28	1052
14-20	LCL	LCL	36	5	36	961		21	LCL			21	982
21-27	LCL	1	50	6	34	1066		16	LCL			16	1082
Mar. 28-Apr.3	1	2	68	4	27	1142		10	1			11	1153
Apr. 4-10	8	1	69	9	17	1398		5				5	1403
11-17	20	2	69	3	9	1330		1	1			2	1332
18-24	45	3	54	2	13	1211		LCL	LCL				1211
Apr. 25-May 1	71	6	58	2	7	1330		1	LCL			1	1331
May 2-8	108	13	35	1	10	1432		1	LCL	44	LCL	45	1477
9-15	114	19	22	LCL	10	1493		1	LCL	262	2	265	1758
16-22	81	22	14	LCL	5	1017	LCL	1	1	587	7	596	1613
23-29	73	18	4	-	4	616	LCL		1	708	17	726	1342
30-31	16	5	1	-	2	108			1	151	3	155	263
June 1-30*	109	50	2		7	860				1549	3	1552	2412
July 1-31*	15	20			15	117	10		10	200	2	122	339
Total	661	188	813	112	612	23392	81	322	30	3501	38	3872	27364

(4) Converted into pre-War rail carload equivalent on basis of: Okra 500 pkgs; Squash 500 pkgs; Bunched Vegetables 2000 doz; Other Vegetables 500 pkgs; Field Peas-Butter Beans 500 pkgs; Avocados 700 pkgs; Strawberries 450 pkgs; Limes 800 pkgs; Watermelons 1000 melons; Other Fruits 500 pkgs. (5) Pre-War carload conversion factors retained for more accurate passings with other years. #Field Peas 804; Butterbeans 145 carloads.

The Shipments are the passings by Road Guard Stations (open October 15th to May 31, 1948) and destined for out-of-State points, excepting some carloads to West Florida. Several carloads of West Florida vegetables going out of State were not included. Watermelons originating West of the Suwannee River and going out of State were included in the estimates for period after May 31st.

FLORIDA AUCTION SALES, 1930-31 - 1947-48

Furnished through courtesy of the Statistical Department
Florida Citrus Exchange, Tampa, Fla.

ORANGES

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1930-31	Cars	8444	3164	1679	952	707	1112	358	729	308	-	17453
	Average	$3.53	3.30	3.37	3.14	3.27	3.34	3.05	3.14	3.21	-	3.40
1931-32	Cars	6517	2228	1182	511	497	776	174	447	179	--	12511
	Average	$3.40	3.21	3.24	3.06	3.20	3.25	2.90	3.14	3.26	--	3.30
1932-33	Cars	9238	2868	1419	579	553	921	273	614	256	-	16721
	Average	$2.43	2.45	2.53	2.35	2.40	2.55	2.30	2.30	2.46	--	2.44
1933-34	Cars	7613	2632	1436	515	526	894	266	495	267	142	14786
	Average	$2.75	2.62	2.69	2.54	2.63	2.67	2.46	2.47	2.69	2.88	2.70
1934-35	Cars	8243	2720	1419	511	578	1070	258	553	280	258	15890
	Average	$2.61	2.47	2.58	2.44	2.53	2.59	2.34	2.35	2.47	2.44	2.56
1935-36	Cars	7503	2624	1561	340	559	878	249	555	271	240	14780
	Average	$3.02	2.93	3.02	2.95	3.04	3.15	2.72	2.87	3.08	2.82	3.00
1936-37	Cars	9112	3164	1657	429	824	1080	264	708	412	282	17932
	Average	$3.23	3.15	3.28	3.12	3.21	3.33	3.01	3.12	3.27	2.98	3.21
1937-38	Cars	10228	3376	1849	495	298	1394	413	1181	550	302	20686
	Average	$2.26	2.20	2.24	2.18	2.28	2.39	2.05	2.16	2.26	1.98	2.24
1938-39	Cars	12440	4049	2132	694	1091	1639	511	1555	717	396	25224
	Average	$2.10	1.99	2.16	2.11	2.20	2.26	2.01	2.01	2.16	1.94	2.09
1939-40	Cars	8758	2908	1290	364	589	1012	318	1031	393	173	16836
	Average	$2.43	2.25	2.47	2.16	2.31	2.41	2.09	2.05	2.25	2.23	2.35
1940-41	Cars	10089	3320	1385	426	647	1020	312	1077	434	261	18971
	Average	$2.37	2.26	2.45	2.31	2.44	2.45	2.25	2.18	2.42	2.22	2.35
1941-42	Cars	9053	3064	1377	337	568	863	204	1002	353	312	17133
	Average	$2.86	2.76	2.90	2.73	2.91	2.88	2.70	2.64	2.83	2.77	2.83
1942-43	Cars	6771	2330	851	439	483	939	359	742	412	277	13603
	Average	$3.85	3.70	3.82	3.72	3.85	3.77	3.70	3.55	3.87	3.56	3.79
1943-44	Cars	6239	2257	678	522	488	815	476	516	658	200	12849
	Average	$3.98	3.82	4.02	3.86	3.86	3.89	3.67	3.65	3.85	3.71	3.90
1944-45	Cars	4765	1651	425	293	264	532	271	299	365	157	9022
	Average	$4.62	4.38	4.47	4.27	4.34	4.29	4.17	4.02	4.37	4.39	4.48
1945-46	Cars	4510	1478	363	237	197	345	196	372	262	308	8268
	Average	$4.72	4.44	4.70	4.48	4.43	4.39	4.24	4.17	4.43	4.45	4.58
1946-47	Cars	7824	1930	870	420	639	921	430	801	562	373	14770
	Average	$3.60	3.35	3.62	3.29	3.47	3.38	3.27	3.25	3.47	3.35	3.50
1947-48	Cars	6856	2550	867	342	534	608	249	689	479	234	13406
	Average	$3.40	3.16	3.34	3.12	3.19	3.08	2.91	3.01	3.12	2.96	3.27

FLORIDA AUCTION SALES, 1930-31 - 1947-48 (Cont'd.)

GRAPEFRUIT

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1930-31	Cars	5269	1610	1037	762	718	1388	462	425	516	-	12187
	Average	$2.66	2.42	2.44	2.41	2.44	2.55	2.38	2.33	2.51	-	2.54
1931-32	Cars	4680	1254	935	505	510	805	207	354	328	-	9578
	Average	$2.49	2.34	2.50	2.38	2.49	2.59	2.41	2.31	2.54	-	2.47
1932-33	Cars	5138	1266	892	429	433	738	228	409	330	-	9863
	Average	$2.05	1.95	2.06	2.02	2.21	2.29	1.96	2.01	2.31	-	2.06
1933-34	Cars	3948	1129	696	310	388	684	221	370	298	41	8085
	Average	$2.41	2.25	2.40	2.38	2.39	2.55	2.37	2.29	2.51	2.42	2.39
1934-35	Cars	4893	1326	898	389	403	721	200	444	350	135	9759
	Average	$2.04	1.81	1.93	1.94	2.09	2.19	2.05	1.92	2.10	1.86	2.00
1935-36	Cars	3928	1072	872	262	396	395	132	340	251	117	7765
	Average	$2.67	2.38	2.49	2.40	2.54	2.68	2.40	2.32	2.62	2.28	2.57
1936-37	Cars	5376	1650	956	274	415	494	151	423	307	151	10197
	Average	$2.24	2.06	2.22	2.14	2.29	2.58	2.53	2.24	2.41	2.12	2.23
1937-38	Cars	4881	1244	814	190	313	353	72	342	219	127	8555
	Average	$2.20	2.06	2.13	2.05	2.11	2.28	2.16	2.09	2.21	1.88	2.16
1938-39	Cars	6389	1429	1020	329	384	361	118	432	277	187	10926
	Average	$1.75	1.57	1.73	1.68	1.77	1.95	1.85	1.66	1.80	1.46	1.72
1939-40	Cars	4765	1153	633	181	141	182	62	241	140	85	7483
	Average	$2.21	1.92	2.10	1.92	2.11	2.29	2.10	1.98	2.06	1.73	2.13
1940-41	Cars	5035	1334	805	249	256	313	109	416	215	91	8823
	Average	$1.96	1.75	1.95	1.76	1.92	2.00	1.77	1.74	1.91	1.61	1.91
1941-42	Cars	4519	1166	712	125	136	208	51	222	98	88	7325
	Average	$2.55	2.36	2.55	2.33	2.61	2.83	2.73	2.33	2.64	2.60	2.52
1942-43	Cars	3411	967	487	142	96	114	19	201	85	82	5604
	Average	$3.18	2.97	3.21	2.90	2.90	3.17	2.96	2.67	3.00	2.70	3.10
1943-44	Cars	2628	778	338	128	49	69	44	90	97	43	4264
	Average	$3.63	3.48	3.64	3.36	3.32	3.20	3.51	3.05	3.31	3.14	3.56
1944-45	Cars	2320	498	183	31	23	21	13	16	13	14	3132
	Average	$4.35	4.03	4.11	3.74	3.01	3.31	3.38	3.13	3.15	3.54	4.24
1945-46	Cars	3293	737	213	33	12	19	2	18	14	45	4386
	Average	$3.88	3.67	3.88	3.06	2.60	3.62	3.33	2.91	2.81	3.19	3.82
1946-47	Cars	4894	890	546	63	80	154	31	183	111	142	7094
	Average	$3.39	3.11	3.17	2.89	3.10	3.16	3.55	2.87	3.18	2.54	3.29
1947-48	Cars	4258	1260	456	73	85	106	34	158	92	138	6660
	Average	$3.22	2.82	2.89	2.55	2.99	2.92	2.97	2.54	3.03	2.31	3.07

FLORIDA AUCTION SALES, 1930-31 - 1947-48 (Cont'd.)

TANGERINES

(½ box-basis)

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1930-31	Cars	1311	426	207	229	154	237	62	97	126	-	2849
	Average	$1.62	1.49	1.46	1.48	1.45	1.44	1.36	1.45	1.48	-	1.53
1931-32	Cars	1190	396	203	175	116	161	65	88	60	-	2454
	Average	$1.54	1.44	1.49	1.39	1.41	1.52	1.32	1.41	1.53	-	1.49
1932-33	Cars	1308	375	157	95	108	180	58	102	73	-	2456
	Average	$1.28	1.20	1.28	1.23	1.21	1.22	1.14	1.09	1.22	-	1.24
1933-34	Cars	1134	433	144	142	114	179	67	96	71	1	2381
	Average	$1.21	1.15	1.17	1.25	1.24	1.21	1.21	1.15	1.22	1.48	1.20
1934-35	Cars	1071	356	132	136	71	155	66	108	71	31	2197
	Average	$1.18	1.10	1.12	1.25	1.27	1.25	1.26	1.20	1.28	1.22	1.18
1935-36	Cars	1124	365	157	139	116	217	54	113	87	26	2398
	Average	$1.35	1.32	1.30	1.40	1.42	1.36	1.32	1.34	1.41	1.23	1.35
1936-37	Cars	1557	572	196	210	193	306	103	138	116	33	3424
	Average	$1.12	1.03	1.05	1.19	1.09	1.14	1.10	1.08	1.16	.96	1.10
1937-38	Cars	1311	382	149	95	117	149	74	125	88	23	2513
	Average	$1.26	1.21	1.20	1.28	1.30	1.25	1.10	1.18	1.23	1.08	1.24
1938-39	Cars	1851	551	172	152	189	257	107	203	148	33	3663
	Average	$1.07	.92	.93	.95	.98	.97	.86	.91	.96	.79	1.00
1939-40	Cars	1192	345	66	65	104	142	48	115	57	9	2143
	Average	$1.37	1.34	1.41	1.37	1.47	1.45	1.31	1.27	1.34	1.33	1.37
1940-41	Cars	1425	454	109	77	154	195	59	149	82	13	2717
	Average	$1.23	1.16	1.19	1.07	1.20	1.22	1.09	1.12	1.14	1.06	1.19
1941-42	Cars	1152	359	78	39	106	135	38	105	48	25	2085
	Average	$1.86	1.75	1.75	1.65	1.82	1.66	1.52	1.58	1.76	1.50	1.79
1942-43	Cars	1485	670	143	108	188	303	101	193	151	57	3399
	Average	$1.82	1.84	1.62	1.81	1.86	1.81	1.66	1.80	1.74	1.53	1.80
1943-44	Cars	326	134	22	22	22	40	26	21	31	-	644
	Average	$2.16	2.28	2.27	2.32	2.37	2.27	2.36	2.26	2.40	-	2.23
1944-45	Cars	669	300	32	72	66	150	41	53	73	9	1465
	Average	$2.42	2.38	2.35	2.49	2.45	2.42	2.15	2.40	2.47	2.77	2.41
1945-46	Cars	1188	414	57	70	86	167	46	88	59	26	2201
	Average	$2.67	2.52	2.43	2.58	2.68	2.54	2.32	2.59	2.50	2.61	2.61
1946-47	Cars	1233	335	69	91	139	202	63	128	108	35	2403
	Average	$2.28	2.18	2.11	2.12	1.99	1.90	1.92	1.99	2.04	2.08	2.17
1947-48	Cars	943	433	69	77	147	193	63	120	140	24	2209
	Average	$2.09	2.01	1.87	1.81	1.88	1.91	1.70	1.81	1.73	1.92	1.98

RAIL AND BOAT SHIPMENTS
F.O.B. PRICES
AVERAGES ON PACKED FRUIT

Florida Citrus Exchange Report
Seasons 1909-10 to 1929-30

SEASONS	ORANGES	GRAPEFRUIT	TANGERINES*	ALL CITRUS (Average)
1909-10	$1.15	$2.38	$1.81	$1.34
1910-11	1.51	1.95	2.60	1.65
1911-12	1.93	3.58	1.93	2.21
1912-13	1.97	2.01	1.92	1.96
1913-14	1.69	2.09	2.51	1.83
1914-15	1.47	1.32	1.66	1.42
1915-16	1.99	1.89	2.07	1.96
1916-17	1.94	2.07	2.82	2.01
1917-18	3.92	2.72	4.39	3.46
1918-19	3.69	3.18	4.79	3.52
1919-20	4.20	2.84	5.49	3.37
1920-21	2.57	2.46	4.96	2.65
1921-22	3.77	2.41	5.57	3.17
1922-23	2.96	2.10	4.39	2.62
1923-24	1.86	1.51	4.31	1.82
1924-25	3.51	1.94	4.43	2.74
1925-26	3.58	2.92	4.83	3.36
1926-27	2.78	2.25	3.50	2.58
1927-28	4.39	3.22	5.28	3.90
1928-29	1.99	2.07	2.91	2.09
1929-30	3.22	2.98	3.38	3.13

FLORIDA STATE MARKETING BUREAU AVERAGES

Seasons 1930-31 to 1947-48
(Comparable to above prices).
Gross f.o.b. Florida per box

1930-31	$2.15	$1.50	$1.95	$1.86
1931-32	2.30	1.50	2.05	1.95
1932-33	1.48	1.16	1.42	1.36
1933-34	1.71	1.51	1.80	1.65
1934-35	1.85	1.29	1.66	1.63
1935-36	2.30	1.87	2.00	2.14
1936-37	2.50	1.48	1.45	2.04
1937-38	1.56	1.53	1.86	1.57
1938-39	1.43	1.04	1.34	1.31
1939-40	1.62	1.42	2.00	1.60
1940-41	1.63	1.21	1.68	1.51
1941-42	2.10	1.80	2.85	2.06
1942-43	2.97	2.33	2.78	2.81
1943-44	3.10	2.47	3.70	3.01
1944-45	3.50	3.00	4.25	3.48
1945-46	3.55	2.65	4.30	3.44
1946-47	2.62	2.18	3.75	2.59
1947-48	2.10	1.80	2.90	2.08

See pages 44-45 for the Citrus Price Analysis covering period 1932-33 to 1947-48, inclusive. This analysis shows weighted average prices for truck shipments, Florida local consumption, and for fruit used in canning or other processing.

CITRUS PRICE ANALYSIS 1932-33 TO 1947-48

	FLORIDA GROSS FOB MARKET OR EQUIVALENT PER BOX							NET* TO GROWER			COST PICKING
	BOX YIELD	RAIL & BOAT	TRUCKED OUT	FLORIDA CONSUMED	FLORIDA CANNED	GROSS ALL	ON TREE ALL	NET ALL	NET RAIL AND BOAT	COST PRODUCTION	PACKING MARKETING RAIL&BOAT
ORANGES											
1932-33	14,964,800	$1.48	$1.00	$ .90	$ .70	$1.36	$ .62	$ .14	$ .10	$ .48	$ .90
1933-34	16,170,996	1.71	1.25	1.15	.80	1.59	.88	.42	.38	.46	.87
1934-35	15,589,039	1.85	1.35	1.25	.80	1.69	.98	.53	.50	.45	.90
1935-36	15,864,588	2.30	1.60	1.50	1.00	2.10	1.33	.88	.90	.45	.95
1936-37	19,460,788	2.50	1.90	1.70	1.25	2.31	1.48	1.06	1.15	.42	.93
1937-38	24,302,896	1.56	1.12	1.12	.36	1.41	.63	.25	.30	.38	.88
1938-39	30,015,287	1.43	1.15	1.15	.41	1.32	.54	.20	.25	.34	.84
1939-40	25,064,702	1.62	1.52	1.32	.19	1.37	.59	.17	.29	.42	.91
1940-41	28,752,089	1.63	1.58	1.28	.80	1.48	.72	.32	.36	.40	.87
1941-42	27,200,000	2.10	2.05	1.70	1.08	1.91	1.13	.69	.76	.44	.90
1942-43	37,200,181	2.97	2.91	2.50	1.70	2.72	1.85	1.45	1.56	.40	1.01
1943-44	46,200,000	3.10	3.10	2.60	2.02	2.81	1.81	1.31	1.35	.50	1.25
1944-45	42,800,000	3.50	3.50	3.00	2.60	3.17	2.23	1.73	1.79	.50	1.21
1945-46	49,800,000	3.55	3.55	3.10	2.83	3.25	2.32	1.84	1.83	.48	1.24
1946-47	52,300,000	2.62	2.62	2.35	.82	1.93	1.03	.50	.84	.53	1.25
1947-48	58,400,000	2.10	2.10	1.90	.80	1.41	.65	.15	.28	.50	1.32
GRAPEFRUIT											
1932-33	11,925,630	$1.16	$ .50	$ .40	$ .32	$ .86	$ .27	$ -.11	$ -.07	$ .38	$ .85
1933-34	11,113,200	1.51	.90	.90	.53	1.19	.62	.23	.29	.39	.83
1934-35	15,243,060	1.29	.80	.70	.37	.88	.38	.01	.08	.37	.84
1935-36	11,504,067	1.87	1.20	1.10	.73	1.39	.85	.46	.61	.39	.87
1936-37	18,121,786	1.48	1.10	1.00	.55	1.09	.55	.25	.35	.30	.83
1937-38	14,378,760	1.53	1.10	1.10	.48	1.05	.54	.18	.35	.36	.82
1938-39	23,050,835	1.04	.80	.80	.22	.64	.21	-.09	-	.30	.74
1939-40	15,650,865	1.42	1.30	1.12	.33	.79	.39	-.01	.20	.40	.82
1940-41	24,387,041	1.21	1.10	.86	.37	.71	.33	-.02	.12	.35	.74
1941-42	19,100,000	1.80	1.70	1.45	.71	1.20	.74	.34	.60	.40	.80
1942-43	27,300,116	2.33	2.25	1.85	1.05	1.48	1.02	.67	1.10	.35	.88
1943-44	31,000,000	2.47	2.47	2.00	1.53	1.83	1.32	.92	1.00	.40	1.07
1944-45	22,300,000	3.00	3.00	2.60	1.91	2.24	1.76	1.36	1.53	.40	1.07
1945-46	32,000,000	2.65	2.65	2.40	1.39	1.77	1.12	.78	1.21	.34	1.10
1946-47	26,400,000	2.18	2.18	1.90	.65	1.25	.63	.26	.73	.37	1.08
1947-48	29,300,000	1.80	1.80	1.60	.34	.82	.34	-.01	.36	.35	1.09

*Net to grower (or fruit owner) indicates the amount per box after deducting production and all other costs except interest, taxes and depreciation. The State Marketing Bureau "On Tree" average price may be obtained by adding Production Costs to "Net to Grower" return for All Fruit.

CITRUS PRICE ANALYSIS 1932-33 TO 1947-48

	FLORIDA GROSS FOB MARKET OR EQUIVALENT PER BOX							NET* TO GROWER			COST
	BOX YIELD	RAIL & BOAT	TRUCKED OUT	FLORIDA CONSUMED	FLORIDA CANNED	GROSS ALL	ON TREE ALL	NET ALL	NET RAIL AND BOAT	COST PRODUCTION	PICKING PACKING MARKETING RAIL&BOAT
TANGERINES											
1932-33	1,519,200	$1.42	$1.00	$ .90	$-	$1.32	$ .38	$-.18	$-.30	$ .56	$1.16
1933-34	1,992,091	1.80	1.40	1.25	-	1.68	.85	.29	.19	.56	1.05
1934-35	2,003,755	1.66	1.15	1.10	-	1.51	.76	.21	.16	.55	.95
1935-36	2,093,397	2.00	1.50	1.40	-	1.86	.97	.42	.35	.55	1.10
1936-37	3,018,634	1.45	1.15	1.05	-	1.37	.32	-.18	-.20	.50	1.15
1937-38	2,257,973	1.86	1.28	1.28	-	1.72	.66	.14	.18	.52	1.16
1938-39	3,381,873	1.34	1.05	1.05	-	1.27	.38	-.07	-.06	.45	.95
1939-40	2,257,545	2.00	1.90	1.70	-	1.95	.92	.42	.44	.50	1.06
1940-41	2,751,624	1.68	1.65	1.31	-	1.60	.58	.08	.10	.50	1.08
1941-42	2,100,000	2.85	2.80	2.40	-	2.77	1.67	1.09	1.11	.58	1.16
1942-43	4,200,149	2.78	2.70	2.25	-	2.72	1.38	.98	1.03	.40	1.35
1943-44	3,600,000	3.70	3.70	3.00	-	3.62	2.01	1.36	1.37	.65	1.68
1944-45	3,900,000	4.25	4.25	3.60	-	4.18	2.56	1.91	1.92	.65	1.68
1945-46	4,200,000	4.80	4.80	4.00	1.00	4.24	2.74	2.10	2.45	.64	1.71
1946-47	3,900,000	3.75	3.75	3.30	.80	2.99	1.58	.90	1.35	.68	1.72
1947-48	3,400,000	2.90	2.90	2.60	.35	2.41	.88	.20	.40	.68	1.82
TOTAL CITRUS (And Average of All Citrus)											
1932-33	28,409,630	1.36	.80	.70	.33	1.15	.47	.02	.015	.45	.90
1933-34	29,276,287	1.65	1.19	1.08	.54	1.45	.78	.34	.336	.44	.87
1934-35	32,835,854	1.63	1.19	1.05	.38	1.33	.70	.27	.32	.43	.88
1935-36	29,462,052	2.14	1.48	1.37	.74	1.81	1.13	.69	.76	.44	.94
1936-37	40,601,208	2.04	1.58	1.43	.61	1.70	.98	.61	.75	.37	.92
1937-38	40,939,629	1.57	1.12	1.13	.46	1.30	.60	.22	.305	.38	.88
1938-39	56,447,995	1.31	1.07	1.04	.24	1.04	.41	.07	.15	.34	.82
1939-40	42,973,112	1.60	1.51	1.29	.28	1.17	.54	.12	.28	.42	.90
1940-41	55,890,754	1.51	1.49	1.18	.47	1.15	.55	.16	.27	.39	.85
1941-42	48,400,000	2.06	2.05	1.69	.83	1.66	1.00	.57	.74	.43	.89
1942-43	68,700,000	2.81	2.78	2.28	1.22	2.23	1.50	1.11	1.41	.39	1.01
1943-44	80,800,000	3.01	3.10	2.37	1.70	2.47	1.65	1.16	1.28	.49	1.24
1944-45	69,000,000	3.48	3.57	2.95	2.25	2.93	2.10	1.62	1.75	.48	1.25
1945-46	86,000,000	3.44	3.61	3.00	2.05	2.75	1.92	1.46	1.73	.46	1.25
1946-47	83,100,000	2.59#	2.67	2.21	.75	1.76	.94	.44	.85	.50	1.24
1947-48	91,100,000	2.08#	2.13	1.89	.62	1.26	.58	.10	.31	.48	1.29

*Net to grower (or fruit owner) indicates the amount per box after deducting production and all other costs except interest, taxes and depreciation. The State Marketing Bureau "On Tree" average price may be obtained by adding Production Costs to "Net to Grower" return for All Fruit. # Rail, Boat and Truck.

SOME QUESTIONS AND ANSWERS

By: H. G. Clayton

(In a recent meeting of the Agricultural Division of the Florida State Chamber of Commerce I heard Mr. H. G. Clayton, who is the Director of the Agricultural Extension Service, County Agent and Home Demonstration Work, discuss the subject of government supports for agricultural commodities. Mr. Clayton, who has been in the Federal-State agricultural work for more than 25 years in top ranking positions, is well qualified to discuss such a subject. I asked then and there that he give in question and answer form simple explanations of price supports, ratios, increased yields, population trends, etc. I am very pleased to have these price support explanations in black and white where I can refer to them when I need to. Unless everyone else is smarter than I am they may be able to use some of this too.)

Frank H. Scruggs.

What is the background of Price Support Programs?

A few farm crops have had price support since 1933 as part of the overall program of economic recovery. The ever normal granary idea of storing the surplus in years of high production was a part of this program. From 1938-41 support prices were instrumental in building up large stocks of cotton, corn and wheat that were helpful to the war effort -- by making it possible to expand livestock to supply meat to our military forces and those of the allies, and to reduce cotton acreage and plant this land to oil seed crops needed in the war effort.

During the war Congress passed the Steagall Amendment which provided that when farmers were asked to increase production of any crops or livestock, price support would be available for a period extending two years after the end of the war. During this same period industry operated on a cost plus basis with guarantees against loss.

Agriculture has been operating under a goal program for many products since 1941 and the goals have been for maximum production and the result has been approximately a 40 percent increase in output. This high production has kept prices from rising higher than they have in the face of the greater food consumption at home (12 percent per capita more than pre war) and the competition from buyers in foreign countries where food is still short.

How do price support programs operate?

Programs must vary with the various commodities. For staple commodities that can be stored loans are the usual method of support. Such loans enable farmers to market their commodities in an orderly manner. For perishable commodities direct purchases to support the market when prices fall below the support level are used in some instances. In other instances the commodity is diverted, as in the case of direct purchases of dried eggs the vendor is required to pay the producer at least a fixed minimum price for eggs. There are many variations.

Name the six basic commodities.

Corn, wheat, cotton, tobacco, rice and peanuts.

What is the Support Level for basic commodities?

90% of parity except cotton and this is 92½ percent of parity.

Name the Steagall Commodities.

Milk, butterfat, hogs, chickens, eggs, turkeys, dry beans, dry peas, Irish potatoes, sweet potatoes, American Egyptian cotton, flax seed, soy beans and peanuts for oil. Wool is also supported and there is provision to support other commodities under certain conditions.

What is the present Support Level for Steagall Commodities?

Not less than 90% of parity through December 31, 1948.

What will the support levels be after 1948?

90% of parity for corn, wheat, cotton, tobacco, rice and peanuts marketed before June 30, 1950. Irish potatoes harvested before January 1, 1949. Milk and its products, hogs, chickens and eggs marketed before January 1, 1950.

The 1946 price support level (about 42 cents a pound) for wool.

Not less than 60 percent of parity nor more than the 1948 price support level for: dry beans, dry peas, sweet potatoes, flax seed, soy beans, turkeys, American Egyptian cotton and Irish potatoes harvested after January 1, 1949. Provision for continued price support, for other agricultural commodities under certain conditions.

(Cont'd.)

What is Parity?

As applied to any agricultural commodity, parity is the price for the commodity which will give a purchasing power with respect to articles that farmers buy, equivalent to the purchasing power for such commodity in the base period.

Base periods are selected years during which price relationships were found to be equitable. For most commodities the base period is August 1910 to July 1914. However for most kinds of tobacco August 1919 to July 1929 is the base period. For flue-cured and Burley tobacco the base period is August 1934 to July 1939.

When does parity go down?

It automatically goes down if prices paid by farmers go down.

Do price supports apply to beef cattle and lambs?

No, they are not included in the support program. Pressure on food prices comes from livestock products all of which are well above parity at the present time. (Hogs are included with the Steagall commodities.)

Name some commodities that are now close to support level.

Potatoes, eggs, wheat, corn, and cotton.

What is the egg-feed ratio?

The number of pounds poultry feed equal in value to one dozen eggs.

What is the corn-hog ratio?

The number of bushels of corn equal in value to 100 pounds of live hogs.

Have crop yields increased or decreased in recent years?

Average crop yields increased about 13 percent from 1942 to 1947. This increase was due to the use of more fertilizer, and to technological developments such as higher yielding varieties, improved cultivating and harvesting methods and to better soil management.

What is the world relationship between crop land and population?

There are about 1-3/4 acres of crop land per person. There are 2-1/4 billion people and the world has about 4 billion acres of crop land.

What is the United States relationship between crop land and population?

About 2-3/4 acres per person. There are 145 million people and the United States harvests about 350 million acres of crops annually from about 400 million acres used as crop land.

At what rate is population increasing?

For the United States the increase is about 3/4 million per year and world population is increasing about 20 million per year.

Is there any relation between soil fertility and the nutritive value of foods?

Yes, there is a direct relation and if the soil is deficient in certain plant food elements the crops grown on the land will be deficient in nutritive value. The livestock produced from pastures and crops grown on soils deficient in certain plant food elements cannot develop properly unless these deficiencies are supplied.

How do cover crops benefit the land?

By protecting the land from wind and water erosion, direct rays of the sun, by producing organic matter to turn back into the land and if a legume by adding nitrogen obtained from the air. (END)

- - - - - -

Mr. H. G. Clayton is Director of Cooperative Extension Work in Agriculture and Home Economics under the College of Agriculture of the University of Florida and the United States Department of Agriculture cooperating. His office and address is in Gainesville, Florida. Prior to assuming this important position Mr. Clayton was top man of the U.S. Department of Agriculture in Florida, and rendered outstanding service during the recent war.

F. H. Scruggs.

WE WISH WE HAD IT

BY; F. H. Scruggs
Florida State Marketing Bureau

A few of our readers are never satisfied with the great volume of information we have prepared in compact form for them in our Annual Report. They don't write us that we have the best statistical report released by any State agency of the principal fruit and vegetable States and that they cannot get anything like this from California or Texas, but they do ask us for more data.

They ask us some very good questions but most of them are questions we have been getting for twenty years.

The question which comes up most often from various people is about the volume of production of some particular County. The question however comes to us as follows: "How many rail cars were shipped from _____ County?" forgetting about truck shipments for fresh use, truck to port for boat shipments, express shipments, and volume trucked to canners and processors. We can give them the rail freight shipments loaded in and credited to a particular County but we have to explain that a commodity may be produced in one County and loaded in and credited to an adjoining County or even to a County far away.

All of the production moves from grove or field to packing house or rail siding on trucks and once these trucks are loaded they can go five miles or twenty-five miles with little difference in expense in relation to value of product.

We do not know the volume of each County which goes out by truck or by express, or which may be canned within the County. We could guess. We have learned from experience not to guess for if we guess for one season then someone wishes the same information for every season since 1925. The writer has been working up this Annual Report for nineteen years and knows the sources of information fairly well and he has the desire to give every bit of important volume and value data he can. So if you do not find the data in this report it probably is not obtainable.

We also get requests for the value as well as the volume of production in individual Counties or in particular groups of Counties. We have said above that we don't know the volume of production of fruits and vegetables in any particular County, therefore, we cannot know the value of said volume.

The writer can give his readers a formula for estimating the volume and value of fruits and vegetables in any particular County. It is not perfect. For example, we will use a mythical County with theoretical acreage.

BASCOM COUNTY

Commodity	Acres		State Unit Yield		Total Production		State Average Unit Val.		Total Gross Value
Beans	600	x	80 bu.	=	48,000	x	$2.50 bu.	=	$ 120,000
Limas	100	x	70 bu.	=	7,000	x	3.50 bu.	=	24,500
Eggplant	100	x	250 bu.	=	25,000	x	2.50 bu.	=	62,500
Cucumbers	200	x	100 bu.	=	20,000	x	4.00 bu.	=	80,000
Peppers	200	x	220 bu.	=	44,000	x	4.00 bu.	=	176,000
Potatoes	200	x	150 bu.	=	30,000	x	2.00 bu.	=	60,000
Tomatoes	400	x	110 bu.	=	44,000	x	5.00 bu.	=	220,000
Total Vegetables	1,800								$ 743,000
Miscellaneous Vegetables	180		(10% of Vegetable Total)						74,300
Miscellaneous Fruits	90		(5% of Vegetable Total)						37,150
Oranges	1,700	x	192 boxes	=	326,400	x	$1.93 bu.	=	$ 629,952
Grapefruit	1,000	x	290 boxes	=	290,000	x	1.25 bu.	=	362,500
Tangerines	200	x	122 boxes	=	24,400	x	3.00 bu.	=	73,200
Total Citrus	2,900								1,065,652
County Total	4,970								$1,920,102

All of this acreage, yield, production, and unit value may be found in this Annual Report. We do not know the volume and the values in each County. Some Counties may average a little more in yield and price than others but not much more. The Counties which have some of the best yields and prices during part of the season may have some of the poorest yields due to frosts and water, and some of the poorest prices due to poor market conditions in another part of the same season.

We allow 10% of officially reported acreage to cover miscellaneous vegetables such as broccoli, carrots, squash, etc. We allow 5% to cover miscellaneous fruits such as avocadoes, limes, mangoes, pears, persimmons, guavas, grapes, etc. In some Counties the percentage may be a little higher or a little lower.

To find the volume and value in the manner shown above will be a little tedious but not difficult.

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS
(For Selected Years)

	1920			1922		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	8,668,000	$ 9,795,000	Bu.	8,888,000	$ 7,110,000
Cotton	Bale	20,000	1,782,000	Bale	28,000	2,902,000
Tobacco	Lbs.	4,200,000	2,041,000	Lbs.	3,330,000	1,551,000
Peanuts(Picked & Threshed)	Lbs.	40,000,000	2,520,000	Lbs.	26,875,000	1,344,000
Sweet Potatoes	Bu.	2,300,000	3,174,000	Bu.	1,680,000	2,184,000
Cow Peas	Bu.	Included in Other Field Crops				
Oats	Bu.	255,000	230,000	Bu.	180,000	137,000
Velvet Beans	Tons	Included in Other Field Crops				
Hay	Tons	83,000	1,768,000	Tons	64,000	1,254,000
Sugar Cane Syrup	Gals.	3,675,000	3,454,000	Gals.	2,320,000	1,067,000
Sugar-Raw	Tons	No Record		Tons	No Record	
Black Strap Molasses	Gals.	No Record		Gals.	No Record	
Pecans	Lbs.	140,000	141,000	Lbs.	880,000	309,000
Total Incomplete			$24,905,000			$17,858,000
Other Field Crops	Misc.		* 2,000,000	Misc.		* 1,400,000

	1924			1925		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,200,000	$ 7,848,000	Bu.	8,262,000	$ 7,684,000
Cotton	Bale	21,000	2,451,000	Bale	43,000	4,561,000
Tobacco	Lbs.	4,901,000	1,916,000	Lbs.	5,810,000	1,743,000
Peanuts(Picked & Threshed)	Lbs.	28,350,000	1,474,000	Lbs.	23,400,000	1,147,000
Sweet Potatoes	Bu.	1,764,000	2,699,000	Bu.	1,840,000	3,386,000
Cow Peas	Bu.	54,000	170,000	Bu.	36,000	129,000
Oats	Bu.	148,000	138,000	Bu.	125,000	85,000
Velvet Beans	Tons	59,000	844,000	Tons	53,000	753,000
Hay	Tons	58,000	1,119,000	Tons	51,000	1,061,000
Sugar Cane Syrup	Gals.	1,350,000	1,350,000	Gals.	1,650,000	1,732,000
Sugar-Raw	Tons	No Record		Tons	No Record	Very Light
Black Strap Molasses	Gals.	No Record		Gals.	No Record	Very Light
Pecans	Lbs.	1,300,000	449,000	Lbs.	1,916,000	609,000
Total Incomplete			$20,458,000			$22,890,000
Other Field Crops	Misc.		* 1,500,000	Misc.		* 1,500,000

	1928			1930		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,073,000	$ 7,427,000	Bu.	5,886,000	$ 5,180,000
Cotton	Bale	22,000	1,091,000	Bale	56,000	2,720,000
Tobacco	Lbs.	8,635,000	2,539,000	Lbs.	9,748,000	2,672,000
Peanuts(Picked & Threshed)	Lbs.	28,175,000	1,352,000	Lbs.	26,520,000	902,000
Sweet Potatoes	Bu.	1,700,000	2,465,000	Bu.	1,360,000	1,646,000
Cow Peas	Bu.	48,000	162,000	Bu.	86,000	233,000
Oats	Bu.	135,000	92,000	Bu.	112,000	87,000
Velvet Beans	Tons	68,000	877,000	Tons	44,000	572,000
Hay	Tons	54,000	1,048,000	Tons	48,000	830,000
Sugar Cane Syrup	Gals.	1,485,000	1,262,000	Gals.	1,530,000	994,000
Sugar-Raw	Tons	1,000	No Record	Tons	27,000	No Record
Black Strap Molasses	Gals.	134,000	No Record	Gals.	2,202,000	No Record
Pecans	Lbs.	2,000,000	545,000	Lbs.	1,150,000	302,000
Total Incomplete			$19,670,000			$16,138,000
Other Field Crops	Misc.		* 2,500,000	Misc.		* 2,000,000

* Estimated by Marketing Bureau

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS (Cont'd.)

(For Selected Years)

Commodity	1932			1935		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	6,350,000	$ 2,921,000	Bu.	7,496,000	$ 5,322,000
Cotton	Bale	18,000	556,000	Bale	31,000	1,576,000
Tobacco	Lbs.	3,310,000	836,000	Lbs.	8,680,000	2,398,000
Peanuts(Picked & Threshed)	Lbs.	24,070,000	1,361,000	Lbs.	38,430,000	1,114,000
Sweet Potatoes	Bu.	1,560,000	1,232,000	Bu.	1,610,000	1,368,000
Cow Peas	Bu.	94,000	99,000	Bu.	88,000	154,000
Oats	Bu.	75,000	28,000	Bu.	112,000	77,000
Velvet Beans	Tons	60,000	255,000	Tons	70,000	700,000
Hay	Tons	41,000	369,000	Tons	52,000	582,000
Sugar Cane Syrup	Gals.	1,760,000	634,000	Gals.	2,660,000	984,000
Sugar-Raw	Tons	37,000	**(1,295,000)	Tons	42,000	**(1,470,000)
Black Strap Molasses	Gals.	3,489,000	248,900	Gals.	3,292,000	395,040
Pecans	Lbs.	625,000	80,000	Lbs.	1,400,000	153,000
Total Incomplete			$ 9,914,900			$16,293,040
Other Field Crops	Misc.		* 1,500,000	Misc.		* 2,000,000

Commodity	1938			1940		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,760,000	$ 4,656,000	Bu.	8,418,000	$ 5,893,000
Cotton	Bale	26,000	1,158,000	Bale	21,000	1,102,000
Tobacco	Lbs.	19,720,000	5,325,000	Lbs.	16,328,000	4,552,000
Peanuts(Picked & Threshed)	Lbs.	56,250,000	1,688,000	Lbs.	68,400,000	1,915,000
Sweet Potatoes	Bu.	1,400,000	1,274,000	Bu.	900,000	810,000
Cow Peas	Bu.	48,000	75,000	Bu.	40,000	67,000
Oats	Bu.	140,000	69,000	Bu.	154,000	102,000
Velvet Beans	Tons	57,000	661,000	Tons	59,000	649,000
Hay	Tons	70,000	763,000	Tons	70,000	665,000
Sugar Cane Syrup	Gals.	1,815,000	817,000	Gals.	1,120,000	560,000
Sugar-Raw	Tons	**(920,000)	**(3,680,000)	Tons	**(970,000)	**(4,268,000)
Black Strap Molasses	Gals.	5,497,000	** (657,000)	Gals.	5,170,000	**(1,125,000)
Pecans	Lbs.	3,575,000	309,000	Lbs.	3,564,000	341,000
Total Incomplete			$21,132,000			$22,049,000
Other Field Crops	Misc.		* 2,500,000	Misc.		* 3,000,000

Commodity	1941			1942		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,200,000	$ 5,904,000	Bu.	7,766,000	$ 8,154,000
Cotton	Bale	18,000	1,461,000	Bale	17,000	1,534,000
Tobacco	Lbs.	11,711,000	4,052,000	Lbs.	14,778,000	6,808,000
Peanuts(Picked & Threshed)	Lbs.	57,800,000	2,312,000	Lbs.	65,550,000	3,343,000
Sweet Potates	Bu.	1,260,000	1,399,000	Bu.	1,122,000	1,560,000
Cow Peas	Bu.	45,000	102,000	Bu.	45,000	122,000
Oats	Bu.	160,000	107,000	Bu.	210,000	176,000
Velvet Beans	Tons	65,000	845,000	Tons	53,000	742,000
Hay	Tons	64,000	813,000	Tons	72,000	979,000
Sugar Cane Syrup	Gals.	1,750,000	962,000	Gals.	1,980,000	1,287,000
Sugar-Raw	Tons	949,000	3,768,000	Tons	949,000	3,072,000
Black Strap Molasses	Gals.	5,157,000	** (928,000)	Gals.	4,100,000	** (750,000)
Pecans	Lbs.	4,672,000	474,000	Lbs.	4,600,000	752,000
Total Incomplete			$23,127,000			$29,279,000
Other Field Crops	Misc.		* 3,000,000			* 3,500,000

* Estimated by the State Marketing Bureau

** Figures in parenthesis ( ) are estimates from unofficial sources.

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS (Cont'd.)
(For Selected Years)

Commodity	1943 Unit	1943 Production	1943 Farm Value	1944 Unit	1944 Production	1944 Farm Value
Corn	Bu.	8,522,000	$13,124,000	Bu.	7,550,000	$12,231,000
Cotton	Bale	16,000	1,678,000	Bale	13,000	1,343,000
Tobacco	Lbs.	14,240,000	9,203,000	Lbs.	20,095,000	10,421,000
Peanuts(Picked & Threshed)	Lbs.	74,800,000	5,236,000	Lbs.	62,500,000	4,688,000
Sweet Potatoes	Bu.	1,365,000	3,044,000	Bu.	1,156,000	2,821,000
Cow Peas	Bu.	36,000	141,000	Bu.	32,000	153,000
Oats	Bu.	300,000	342,000	Bu.	704,000	887,000
Velvet Beans	Tons	62,000	1,240,000	Tons	43,000	1,152,000
Hay	Tons	66,000	1,063,000	Tons	65,000	1,079,000
Sugar Cane Syrup	Gals.	2,040,000	2,040,000	Gals.	2,400,000	2,280,000
Sugar-Raw	Tons	694,000	3,040,000	Tons	780,000	3,487,000
Black Strap Molasses	Gals.	4,100,000	** (750,000)	Gals.	5,400,000	**(1,000,000)
Pecans	Lbs.	4,524,000	1,060,000	Lbs.	5,100,000	1,143,000
Total Incomplete			$41,961,000			$42,685,000
Other Field Crops	Misc.		* 4,500,000			* 5,000,000

Commodity	1945 Unit	1945 Production	1945 Farm Value	1946 Unit	1946 Production	1946 Farm Value
Corn	Bu.	7,755,000	$13,339,000	Bu	6,910,000	$13,060,000
Cotton	Bale	8,000	896,000	Bale	6,000	983,000
Tobacco	Lbs.	20,082,000	10,923,000	Lbs.	22,251,000	15,739,000
Peanuts(Picked & Threshed)	Lbs.	66,000,000	5,280,000	Lbs.	46,500,000	3,860,000
Sweet Potatoes	Bu.	1,024,000	2,652,000	Bu.	1,088,000	2,959,000
Cow Peas	Bu.	36,000	174,000	Bu.	40,000	220,000
Oats	Bu.	900,000	963,000	Bu.	720,000	994,000
Velvet Beans	Tons	56,000	1,568,000	Tons	44,000	1,408,000
Hay	Tons	63,000	1,147,000	Tons	57,000	1,037,000
Sugar Cane Syrup	Gals.	2,090,000	2,090,000	Gals.	1,980,000	3,168,000
Sugar-Raw	Tons	1,042,000	6,387,000	Tons	1,037,000	7,207,000
Black Strap Molasses	Gals.	5,700,000	**(1,200,000)	Gals.	6,711,000	**(1,200,000)
Pecans	Lbs.	4,234,000	1,010,000	Lbs.	4,526,000	1,507,000
Total Incomplete			$47,629,000			$53,342,000
Other Field Crops	Misc.		* 5,200,000			* 5,500,000

Commodity	1947 Unit	1947 Production	1947 Farm Value	Preliminary 1948 Unit	Preliminary 1948 Production	Preliminary 1948 Farm Value
Corn	Bu.	8,638,000	$18,572,000	Bu.	8,027,000	
Cotton	Bale	11,000	1,749,000	Bale	14,000	
Tobacco	Lbs.	27,036,000	18,054,000	Lbs.	21,097,000	Final Value Estimate Not Yet Available as of Sept. 15.
Peanuts(Picked & Threshed)	Lbs	69,300,000	6,514,000	Lbs.	66,960,000	
Sweet Potatoes	Bu.	1,275,000	3,251,000	Bu.	1,005,000	
Cow Peas	Bu.	36,000	245,000	Bu.	#	
Oats	Bu.	600,000	960,000	Bu.	399,000	
Velvet Beans	Tons	44,000	1,408,000	Tons	#	
Hay	Tons	63,000	1,292,000	Tons	64,000	
Sugar Cane Syrup	Gals.	2,400,000	3,000,000	Gals.	#	
Sugar-Raw	Tons	923,000	7,061,000	Tons	1,213,000	
Black Strap Molasses	Gals	5,400,000	**(1,080,000)	Gals.	#	
Pecans	Lbs.	2,774,000	628,000	Lbs.	5,037,000	
Total Incomplete			$63,814,000	# Estimate not yet available.		
Other Field Crops	Misc.		* 6,000,000			

---

* Estimated by the State Marketing Bureau. ** Figures in parenthesis ( ) are estimated from unofficial sources. All other production and farm value figures supplied by the U.S. Agricultural Statisticians, B.A.E., Federal Building, Orlando, Florida.

FLORIDA TOBACCO

Flue Cured (Bright Leaf) Type No. 14

Year	Acreage	Production	Estimated Farm Value				
1932	2,000	1,200,000 Lbs.	$ 132,000	or	11¢	per	lb.
1933	5,000	3,700,000	444,000	"	12¢	"	"
1934	4,700	3,408,000	682,000	"	20¢	"	"
1935	7,000	6,020,000	1,066,000	"	17.8¢	"	"
1936	8,000	7,200,000	1,584,000	"	22¢	"	"
1937	16,800	14,112,000	2,978,000	"	21.1¢	"	"
1938	16,300	15,892,000	3,226,000	"	20.3¢	"	"
1939	29,500	20,650,000	2,540,000	"	12.3¢	"	"
1940	12,700	11,748,000	2,056,000	"	17.5¢	"	"
1941	11,300	8,192,000	1,745,000	"	21.3¢	"	"
1942	13,000	11,180,000	3,611,000	"	32.3¢	"	"
1943	13,600	11,832,000	4,827,000	"	40.8¢	"	"
1944	19,000	17,100,000	6,190,000	"	36.2¢	"	"
1945	19,400	17,169,000	6,662,000	"	38.8¢	"	"
1946	20,400	19,176,000	9,147,000	"	47.7¢	"	"
1947	22,800	23,256,000	9,070,000	"	39.0¢	"	"
1948	17,100	15,561,000	7,391,475	"	47.5¢	"	"

Sun Cured (Filler 1932-1939 Binder, 1936-48) Dark Leaf
(Types 45 and 56)

Year Summer	Acreage	Type	Production	Estimated Farm Value	Per Pound
1932	200	F	140,000	$ 14,000	10¢
1933	100	F	82,000	9,000	11¢
1934	300	F	360,000	43,000	11.9¢
1935	700	F	770,000	104,000	13.5¢
1936	400	F & B	380,000	51,000	13.4¢
1937	700	F & B	784,000	106,000	13.5¢
1938	900	F & B	1,116,000	151,000	13.5¢
1939	1,000	F & B	960,000	127,000	13.2¢
1940	1,000	B	1,300,000	174,000	13.4¢
1941	600	B	450,000	65,000	14.4¢
1942	600	B	630,000	110,000	17.5¢
1943	200	B	166,000	37,000	22¢
1944	100	B	70,000	19,000	27.0¢
1945	100	B	93,000	31,000	33.0¢
1946	100	B	105,000	58.000	55.0¢
1947	200	B	140,000	66,000	47.0¢
1948	100	B	98,000	-	-

NOTE: F: Filler (Type 45) discontinued after 1939. B: Binder (Type 56) started in 1936 and continued to date.

Shade Grown-Air Cured (Dark Leaf) Wrapper Type 62

Year	Acreage	Production	Estimated Farm Value				
1932	2,000	1,970,000 Lbs.	$ 690,000	or	35¢	per	lb.
1933	1,100	990,000	317,000	"	32¢	"	"
1934	1,600	1,424,000	854,000	"	52.9¢	per	lb.
1935	2,100	1,890,000	1,228,000	"	65¢	per	lb.
1936	2,000	2,050,000	1,414,000	"	69¢	"	"
1937	2,100	1,890,000	1,304,000	"	70¢	"	"
1938	2,400	2,712,000	1,953,000	"	72¢	"	"
1939	2,500	2,150,000	1,570,000	"	73¢	"	"
1940	3,200	3,280,000	2,296,000	"	70¢	"	"
1941	3,300	3,062,000	2,240,000	"	73¢	"	"
1942	2,800	2,968,000	2,879,000	"	$1.04	"	"
1943	2,600	2,912,000	3,087,000	"	1.49	"	"
1944	2,600	2,925,000	4,212,000	"	1.44	"	"
1945	2,400	2,820,000	4,230,000	"	1.50	"	"
1946	3,000	2,970,000	6,534,000	"	2.20	"	"
1947	3,500	3,640,000	8,918,000	"	2.45	"	"
1948	3,800	4,180,000	-		-		

Florida Auction Sales Flue Cures Type No. 14

Original Sales	Volume	Total	Value			
1940	8,391,086 lbs.	$ 1,487,537	or	17.73¢	per	lb.
1941	6,015,352	1,305,148	"	21.41¢	"	"
1942	8,228,234	2,669,449	"	32.45¢	"	"
1943	9,246,183	3,777,990	"	40.86¢	"	"
1944	12,393,680	4,487,280	"	36.21¢	"	"
1945	12,148,104	4,742,528	"	39.03¢	"	"
1946	14,768,370	7,051,896	"	47.75¢	"	"
1947	18,648,643	7,259,917	"	38.93¢	"	"
1948	14,054,916	6,676,085	"	47.50¢	"	"

POULTRY AND EGG WHOLESALE PRICES-TAMPA AND MIAMI

TAMPA (January 1, 1939--September 30, 1948)

WHITE EGGS (Standard 24 oz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1939	31.2	24.5	22.1	23.4	23.4	25.0	30.5	29.0	31.6	34.3	35.8	32.5	28.6
1940	31.5	29.2	21.5	22.1	22.3	24.2	29.5	32.5	35.9	37.5	37.1	38.6	30.2
1941	34.6	26.2	24.2	26.0	28.4	32.0	27.5	40.0	51.1	43.3	45.1	43.5	35.2
1942	41.9	33.2	31.2	33.0	32.4	35.5	41.0	46.1	47.3	49.0C	49.0	49.0	40.7
1943	48.7	40.1	39.0	43.0	43.0	43.1	47.1	51.3	55.0	58.3	57.3	53.0	48.3
1944	46.5	40.5	37.1	37.0	38.6	40.6	44.3	50.5	52.2	58.6	60.0	59.1	47.1
1945	49.3	44.0	38.2	41.8	42.0	44.8	49.3	55.0	57.9	58.7	60.1	59.0	50.0
1946	49.9	41.8	39.0	39.3	42.0	45.1C	51.1	56.0	61.2	67.0	62.8	63.8	51.5
1947	58.7	55.0	52.2	52.3	57.0	58.2	63.3	66.4	70.8	74.0	75.0	76.0	63.2
1948	69.6	58.2	55.2	56.3	58.0	60.5	64.8	69.0					
HENS (Heavy Breed)													
1939	19.1	17.8	17.9	17.9	17.5	17.3	16.9	16.0	16.6	17.2	16.4	16.6	17.2
1940	17.1	17.1	17.3	18.0	17.0	16.5	14.8	14.7	16.8	16.6	17.5	17.5	16.7
1941	17.5	18.9	18.9	19.5	19.0	20.2	21.0	20.5	21.1	23.0	23.7	24.0	20.6
1942	24.5	24.0	23.1	24.4	24.3	22.5	22.3	22.0	23.9	26.0C	26.0	26.0	24.1
1943	28.5	29.5	29.4	29.4	29.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	28.2
1944	27.4	27.4	27.4	27.4	29.6	28.4	27.4	27.4	27.4	27.4	27.4	27.4	27.7
1945	27.5	27.8	28.8	29.2	29.6	28.5	27.6	27.4	27.3	27.3	27.3	27.3	27.9
1946	27.3	28.3	28.5	28.7	29.5	28.7C	24.8	25.1	31.2	35.6	32.1	32.0	29.3
1947	31.4	31.4	36.1	35.5	30.8	30.0	30.8	31.4	31.5	33.0	34.7	37.0	32.8
1948	38.6	36.0	36.0	36.0	36.0	36.0	34.4	33.0					
FRYERS (Heavy Breed)													
1939	19.1	17.3	19.8	20.8	18.6	19.8	19.3	18.2	18.6	19.4	19.1	19.0	18.9
1940	21.5	19.5	19.3	21.5	21.3	22.4	18.6	17.9	19.4	19.5	19.7	19.4	20.0
1941	19.2	20.2	21.4	22.0	19.7	20.7	22.2	22.5	22.7	23.0	23.7	24.0	21.8
1942	25.8	24.0	23.5	25.3	26.7	27.0	27.6	29.0	29.9	31.0C	31.0	31.0	27.7
1943	33.0	31.5	31.6	31.9	31.1	30.9	30.9	30.9	30.9	30.9	30.9	30.9	31.3
1944	30.9	30.9	30.9	31.2	33.1	31.9	30.9	30.9	30.9	30.9	30.9	30.9	31.2
1945	31.0	31.3	32.3	32.7	33.1	32.0	31.7	31.7	31.6	31.6	31.6	31.6	31.8
1946	31.6	32.6	32.8	33.0	33.8	33.5C	35.2	38.1	40.4	47.3	43.0	44.6	37.1
1947	39.9	32.9	34.4	35.5	36.7	37.0	39.3	41.4	41.7	40.0	34.0	38.3	37.6
1948	40.5	40.5	41.6	44.5	42.3	44.0	41.2	39.0					

MIAMI (January 1, 1939-September 30, 1948)

WHITE EGGS (Standard 24 oz)

1939	35.1	27.3	24.3	25.0	24.9	Unavailable			33.8	37.2	39.5	36.5	31.5
1940	36.5	35.3	26.0	25.8	25.5	25.8	31.8	35.0	38.4	43.1	40.0	42.9	N
1941	38.3	31.7	28.1	29.0	31.6	34.1	38.6	41.5	43.1	45.0	47.8	48.0	N
1942	43.0	41.0	33.0	35.0	35.0	42.0	47.0	49.0	51.0	52.0C	52.0	52.0	44.4
1943	52.0	44.0	42.0	44.5	44.5	46.5	49.6	53.9	57.5	60.9	59.8	55.2	50.9
1944	51.5	47.5	44.5	44.5	44.5	45.5	50.0	54.5	57.6	58.0	60.5	59.3	51.5
1945	50.8	45.6	43.2	43.2	43.2	45.6	49.9	54.7	58.3	59.2	60.5	59.8	51.2
1946	50.7	45.5	43.2	43.2	43.2	45.8C	50.3	52.0	57.0	63.6	61.0	59.2	50.5
1947	53.1	52.0	52.2	57.6	54.5	53.7I	62.6	66.9	72.4	75.6	76.0	77.9	62.9
1948	66.1	52.0	53.9	56.7	54.4	60.0	62.4	66.8					
HENS (Heavy Breed)													
1939	24.5	23.6	24.0	23.3	21.5	Unavailable			21.7	24.0	23.5	22.8	23.2
1940	22.5	22.0	22.0	22.0	22.0	22.0	22.0	22.3	22.0	23.5	23.0	23.0	22.4
1941	23.0	23.0	23.0	23.0	23.5	24.5	26.5	25.0	25.0	25.0	25.5	26.0	24.4
1942	27.0	27.0	30.0	30.0	30.0	30.0	30.0	30.0	32.0	32.0C	28.0	28.0	29.5
1943	28.0	28.0	28.0	28.0	28.0	28.0	(- - No quotations on account of consider						
1944	able price ceiling confusion - -).						29.7	29.7	29.7	29.7	29.7	29.7	29.7
1945	29.7	28.5	29.9	31.6	29.1	28.7	27.8	27.5	27.5	27.5	27.5	27.5	28.5
1946	27.5	27.5	27.5	27.5	31.4	32.4C	32.1	32.8	38.7	31.9	38.8	40.0	32.3
1947	41.4	40.6	41.9	41.3	40.9	38.3I	35.6	35.0	37.4	38.6	38.7	39.0	39.1
1948	41.0	43.8	45.2	45.0	42.6	39.4	38.6	38.9					
FRYERS (Heavy Breed)													
1939	24.3	24.7	26.0	25.0	23.4	Unavailable			23.9	25.0	24.5	23.8	24.5
1940	23.5	22.9	23.0	23.0	23.0	23.0	23.0	24.6	25.0	24.1	24.0	24.0	23.6
1941	25.0	25.0	27.0	26.5	25.0	25.0	26.0	25.0	25.0	25.0	26.0	27.0	25.6
1942	30.0	30.0	30.0	30.0	32.0	35.0	35.0	35.0	37.0	37.0C	32.0	32.0	33.0
1943	32.0	32.0	32.0	32.0	32.0	32.0	(- - No quotations on account of consider						
1944	able price ceiling confusion - -)						33.2	33.2	33.2	33.2	33.2	33.2	33.2
1945	33.2	32.0	33.4	35.2	32.2	32.5	32.0	32.0	32.0	32.0	32.0	32.0	32.5
1946	32.0	32.0	32.0	32.0	35.9	37.1C	38.7	38.5	44.0	46.3	43.4	45.0	38.1
1947	39.2	35.0	39.6	40.0	41.3	43.0I	43.0	43.0	45.7	42.6	39.6	40.5	41.0
1948	44.8	45.7	47.0	49.6	45.3	44.2	42.3	41.9					

C Ceiling prices. See notes for Jacksonville market quotations. N-Not calculated.
I Incomplete, part month only. See pages for Jacksonville prices.

JACKSONVILLE JOBBING MARKET
SALES TO RETAILER OR EQUIVALENT SALES
MONTHLY SIMPLE AVERAGES

EGGS - Florida White Grade A-24 oz. per Dozen

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1921	74.3	48.6	36.0	31.3	30.5	31.9	42.7	47.9	50.0	59.4	64.8	60.0	48.1
1922	48.0	40.7	26.5	29.4	28.3	34.7	37.5	37.5	52.8	55.0	62.8	53.9	40.6
1923	49.6	36.0	30.0	29.5	29.0	33.8	39.5	42.6	49.8	56.3	59.3	58.0	42.8
1924	47.4	44.6	26.6	25.8	28.5	32.5	39.0	43.6	52.1	62.0	66.2	64.9	44.4
1925	56.8	45.3	30.2	33.5	30.3	38.6	44.4	48.4	55.2	64.0	65.6	67.0	48.3
1926	57.2	42.1	31.3	34.1	32.5	36.1	41.6	44.4	51.8	62.2	61.0	57.1	45.9
1927	47.6	35.9	28.0	29.2	27.9	29.7	33.9	41.4	49.0	52.1	55.0	50.4	40.0
1928	48.0	32.4	30.0	29.7	28.2	33.4	36.5	41.7	48.3	54.8	55.0	48.5	40.4
1929	42.2	34.5	35.1	29.2	30.2	33.7	39.3	43.2	45.2	54.1	55.3	54.0	41.5
1930	47.1	35.4	28.5	27.0	27.0	27.0	30.6	34.9	38.2	45.4	43.9	40.9	35.5
1931	32.0	22.0	23.0	22.0	20.0	21.0	25.0	28.5	32.0	37.5	38.0	33.0	27.9
1932	26.5	16.5	18.0	15.5	14.7	18.3	21.0	25.0	28.2	31.5	32.6	35.2	23.5
1933	23.5	17.0	15.5	15.5	17.3	16.3	22.9	25.5	31.4	33.0	32.0	34.4	23.7
1934	28.7	25.6	19.2	19.8	20.1	23.5	28.0	31.6	36.8	38.0	40.0	40.0	29.3
1935	35.8	31.8	23.0	24.9	26.3	26.8	31.5	35.6	39.0	39.3	37.0	40.6	32.6
1936	33.5	31.2	23.5	22.9	24.1	25.7	31.9	34.0	37.5	38.4	41.9	43.4	32.3
1937	29.8	27.5	25.1	25.5	24.2	25.8	30.1	33.0	37.2	38.1	39.6	38.0	31.2
1938	32.5	26.6	22.2	22.3	25.0	25.7	31.5	32.8	36.3	36.3	36.8	40.1	30.7
1939	30.8	24.3	21.6	21.9	22.6	23.0	29.1	29.6	28.8	32.4	33.9	30.9	27.4
1940	31.4	26.8	20.7	20.8	21.2	23.5	28.8	31.7	34.5	36.4	36.3	38.2	29.2
1941	33.3	25.4	24.1	25.2	28.4	31.2	36.8	39.2	41.4	42.0	44.5	42.2	34.5
1942	40.0	31.5	30.5	31.4	31.4	34.7	39.5	45.0	46.1	48.0*	48.0*	48.0*	39.7
1943	47.6	38.7	38.0	38.4*	43.0*	43.6*	46.9*	51.0*	54.8*	58.0*	57.0*	53.6*	47.6
1944	49.3*	39.7*	37.1*	37.0*	38.2*	41.4*	45.2*	50.3*	55.1*	58.6*	59.9*	59.0*	47.6
1945	50.0*	44.0*	37.8*	42.4*	42.6*	44.9*	49.3*	54.4*	57.8*	58.6*	59.9*	58.8*	50.0
1946	49.7*	40.7*	39.0*	39.1*	42.4*	45.0**	50.7	55.6	60.4	66.2	61.3	62.8	51.1
1947	59.4	52.4	51.1	52.4	56.0	57.4	62.3	64.9	70.1	73.0	74.0	75.5	62.5
1948	68.6	57.2	54.1	55.4	57.7	60.2	63.3	68.2					

FRYERS - Heavy Breed

1921	39.1	39.7	46.9	49.5	46.6	35.0	31.2	30.3	34.0	35.5	29.1	29.0	37.2
1922	29.0	29.5	38.4	40.0	40.0	35.5	31.5	29.0	31.0	29.0	29.0	29.0	32.6
1923	29.5	31.0	36.5	37.0	39.8	36.7	30.0	30.0	33.0	32.4	31.0	31.0	33.1
1924	32.7	36.6	37.8	42.0	42.5	37.4	32.7	30.7	34.0	33.0	31.5	34.3	35.4
1925	41.4	44.0	45.6	45.9	43.7	39.4	36.0	35.0	38.0	39.0	37.0	38.6	40.3
1926	43.5	48.0	49.7	50.0	48.3	38.3	37.8	35.3	35.0	35.0	35.3	37.1	41.1
1927	42.0	45.0	45.0	46.3	43.0	36.1	31.8	30.0	30.0	31.1	33.1	35.8	37.4
1928	37.0	36.2	38.9	39.0	39.0	38.1	34.5	31.2	33.0	35.3	36.3	35.7	36.3
1929	26.0	36.2	39.1	42.8	37.7	37.3	31.0	31.1	35.0	34.2	36.1	36.8	36.1
1930	33.1	32.9	33.6	36.7	32.7	32.8	24.5	27.4	29.0	29.0	29.0	29.0	30.9
1931	30.0	31.0	37.0	40.0	37.0	35.0	29.0	27.0	27.5	26.0	24.5	24.5	30.6
1932	24.4	23.2	27.1	26.8	23.9	23.5	18.0	17.3	18.0	18.7	17.3	14.9	21.0
1933	14.6	20.4	22.2	24.3	22.1	18.0	15.4	16.1	17.0	17.0	15.7	16.1	18.2
1934	17.6	20.2	23.9	25.2	24.9	22.5	20.1	18.7	19.7	20.0	20.5	20.5	21.2

(Cont'd)

---

* Temporary ceiling prices in allpoultry and eggs went into effect October 3, 1942.
** All ceiling poultry and egg prices ended June 30, 1946.

JACKSONVILLE JOBBING MARKET
SALES TO RETAILER OR EQUIVALENT SALES
MONTHLY SIMPLE AVERAGES

FRYERS - Heavy Breed (Cont'd.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1935	21.5	24.3	26.1	25.9	22.8	23.1	21.2	20.3	21.0	22.4	23.2	24.5	23.0
1936	25.5	25.6	27.0	27.2	25.7	25.5	23.1	22.6	22.3	21.2	20.5	20.0	23.7
1937	22.3	24.0	24.1	27.0	24.1	25.3	25.5	24.5	25.8	27.1	26.7	27.7	25.4
1938	25.8	24.6	27.2	27.8	24.0	21.8	20.5	21.6	22.9	22.9	23.0	23.6	23.8
1939	23.4	21.6	21.9	24.8	22.0	21.8	22.5	21.9	21.0	22.0	22.3	22.1	22.3
1940	22.0	21.8	22.8	22.6	24.3	23.2	21.4	20.5	21.5	21.9	20.8	21.5	22.0
1941	21.8	22.4	23.8	24.3	23.0	22.8	22.8	22.2	22.6	23.0	23.9	24.0	23.1
1942	24.1	23.7	24.2	25.6	26.8	27.5	27.4	27.5	29.0	30.5	30.5	31.4	27.4
1943	31.8	31.8	31.8	31.9*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	31.0
1944	30.6*	30.6*	30.6*	31.0*	32.6*	31.8*	31.1*	30.6*	30.6*	30.6*	30.6*	30.6*	30.9
1945	30.6*	31.6*	32.0*	32.4*	32.8*	31.6*	31.4*	31.3*	31.3*	31.3*	31.3*	31.3*	31.6
1946	31.6*	32.1*	32.5*	32.9*	33.3*	33.0**	39.1	38.5	43.3	47.1	41.5	41.2	37.2
1947	36.2	32.5	34.5	35.0	37.4	38.0	38.5	39.0	41.2	37.9	34.7	36.8	36.8
1948	40.2	39.4	41.9	42.4	40.3	41.7	39.7	39.0					

HENS - Heavy Breed

1921	33.6	32.6	31.7	29.3	26.9	26.5	25.1	26.2	30.3	31.8	26.0	26.0	28.8
1922	26.0	26.0	26.7	25.5	25.4	24.0	24.0	24.0	27.5	26.0	26.0	26.0	25.6
1923	26.0	26.0	26.0	25.0	23.0	23.0	20.9	21.1	24.7	26.0	24.3	24.7	24.2
1924	27.8	26.0	26.4	26.0	27.0	25.1	24.0	26.6	29.4	30.0	28.6	27.8	27.1
1925	31.6	29.2	29.7	28.0	23.0	26.6	25.9	29.0	30.0	31.0	28.1	29.3	28.7
1926	30.7	30.2	32.5	31.8	31.9	30.0	30.0	29.7	31.0	31.0	30.2	31.1	30.7
1927	30.0	30.0	29.8	29.1	29.0	24.7	23.7	25.6	26.0	26.0	25.0	25.0	26.9
1928	25.0	25.0	25.0	25.0	24.5	23.0	21.9	21.1	23.9	27.2	25.5	24.5	24.3
1929	24.8	26.4	28.8	28.8	27.4	29.3	28.0	29.0	31.2	29.5	29.5	29.8	28.5
1930	29.8	30.0	28.5	27.5	26.6	24.5	22.5	22.6	23.0	22.8	23.0	23.0	25.3
1931	23.0	20.0	22.0	24.0	23.0	22.0	21.0	20.0	21.5	23.0	22.5	22.0	22.0
1932	20.5	18.6	18.7	19.0	17.5	16.1	14.5	14.5	15.2	16.7	17.0	14.4	16.9
1933	13.2	13.5	13.0	14.7	14.1	13.1	13.0	14.6	15.9	16.7	15.4	14.0	14.3
1934	14.3	15.5	16.0	15.5	13.8	16.0	15.7	14.8	16.6	17.2	17.3	17.5	16.1
1935	17.5	17.8	18.3	18.0	18.0	18.7	18.2	18.4	19.3	21.0	21.7	20.6	19.0
1936	20.0	19.9	19.5	20.3	20.8	20.5	20.9	20.7	20.2	19.6	19.6	18.7	20.1
1937	18.7	19.3	18.6	18.5	19.0	19.5	16.8	16.0	17.5	18.7	20.2	20.7	18.6
1938	20.1	19.0	19.9	19.7	19.0	19.3	19.4	18.7	20.2	20.2	21.0	21.2	19.8
1939	21.4	20.7	20.4	21.1	19.3	18.8	17.8	18.2	16.9	16.9	17.9	15.3	18.7
1940	16.2	16.7	17.5	17.5	17.1	16.2	15.5	16.1	16.5	18.5	17.8	17.2	16.9
1941	17.6	18.1	19.0	19.9	19.8	20.8	20.7	20.5	21.1	21.5	23.0	23.1	20.4
1942	23.9	22.8	23.0	23.6	23.2	21.5	21.0	21.8	24.9	26.5	26.5	27.8	23.9
1943	29.3	29.3	29.3	29.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.8
1944	27.1*	27.1*	27.1*	27.5*	29.2*	28.4*	27.6*	27.1*	27.1*	27.1*	27.1*	27.1*	27.5
1945	27.1*	28.1*	28.5*	28.9*	29.3*	28.1*	27.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.7
1946	27.6*	28.1*	28.5*	28.9*	29.3*	28.1**	29.1	29.2	35.0	40.6	35.2	35.0	31.2
1947	33.1	34.5	38.1	36.4	34.3	32.6	32.8	33.9	36.4	36.5	37.4	37.9	35.3
1948	40.5	40.2	41.7	42.8	43.0	43.0	40.3	38.0					

* Permanent ceiling prices went into effect on March 6, 1943 on eggs and April 6, 1943 on poultry.

** All ceiling poultry and egg prices ended June 30, 1946.

GENERAL FACTS ABOUT FLORIDA'S LIVESTOCK INDUSTRY

By: L. H. Lewis, Livestock Specialist, Florida State Marketing Bureau,
Gifford N. Rhodes, Livestock Market News, Florida State Marketing Bureau

CATTLE AND CALVES

Q. 1: What is the number and value of cattle and calves in Florida?
The following Table shows number of head, value per head and total value for selected years from 1925, etc.

CATTLE

Year	No. Head	Avg. Val. per Head	Total Value
1925	656,000	$18.20	$11,948,000.00
1930	432,000	29.10	12,571,000.00
1935	788,000	14.60	11,504,800.00
1940	821,000	20.90	17,158,900.00
1945	1,159,000	42.50	49,289,000.00
1946	1,205,000	46.80	56,442,000.00
1947	1,265,000	54.00	68,310,000.00
1948	1,265,000	58.20	74,256,000.00

Q. 2: What is Florida's 1947 position as a cattle State?
In beef or range cattle 14th; in dairying 35th; in total cattle 25th.

Q. 3: Where are most of the range or beef cattle in Florida found?
Most farm beef cattle in West Florida; most range beef cattle in the peninsular of Florida, or South Florida. The 15 leading beef cattle Counties have 48% of the total beef cattle in the State. Their order of importance in numbers: Polk Osceola, Highlands, Marion, Glades, Hillsborough, Hardee, Okeechobee, Jackson, Sumter, Clay, Pasco, Putnam, Alachua and Manatee. About 75% of the total cattle in the State are fenced.

Q. 4: How many purebred registered beef cattle herds are there in Florida?
Approximately 225 herds. The order of their importance as to numbers is: Brahman, Hereford, Angus, Shorthorn, Red Polled and Devon.

Q. 5: Are there any purebred cattle State breeders' associations?
Yes, for Angus, Brahman, Hereford and Shorthorn. Dairymen have an association for Guernseys and Jerseys.

Q. 6. What kind of marketing facilities for livestock are found in Florida?
There are 14 meat packing plants, 14 abattoirs, about 500 butchers, 24 livestock auction markets, 6 cash daily markets not including packers and abattoirs, as well as numerous local buyers. These facilities are scattered well over the State.

Q. 7: How does the average price per hundred pounds (cattle and calves) in Florida compare with the average U.S.A. price?

	1946		1947	
	Cattle	Calves	Cattle	Calves
U.S.A.	$14.50	$15.30	$18.50	$20.40
Florida	11.20	13.00	12.20	14.00

These differences between U.S.A. and Florida average prices are due mainly to breeding and feeding.

Q. 8: How does the calf crop in Florida compare with the U.S.A. average?
In 1946, U.S.A. 80%, Florida 64%. In 1947, U.S.A. 81%, Florida 64%.

Q. 9: What was the approximate average weight and average price received for Florida range cattle during the past year?
The following yearly average figures were obtained based on sales of over 25,000 range cattle marketed at one sales point in peninsular Florida for a period of one year ending June 30, 1948:

	Steers	Heifers	Yearlings	Calves	Cows	Bulls	Stags	Total
Pct. by Classes	15.6%	6.9%	5.3%	35.15%	34.6%	2.3%	.15%	100.0%
Avg. Weight - Lbs.*	499.4	358.0	295.4	204.1	539.0	707.5	659.3	393.8
Avg. Price/Cwt *	$16.06	$14.79	$15.59	$15.28	13.39	$15.16	$17.70	$14.52
Avg. Price per Hd.*	$80.22	$52.94	$46.06	$31.18	$72.18	$107.24	$116.70	$57.20

* Average cattle weight 496.7, calves 204.1 lbs.
Average cattle price Cwt. $14.36, calves $15.28. Per Head, cattle $71.30, calves $31.18.

Q.10: How many cattle and calves were marketed in Florida in 1947?
Approximately 382,500 head of cattle and calves slaughtered. Total numbers marketed, including those sold as stockers and feeders, probably exceeded 450,000 head.

Q.11: When are most of the cattle and calves marketed in Florida?
A greater percentage are marketed from July through January, calves mostly June through December, as shown by the following table:

(Cont'd.)

PERCENTAGE MONTHLY SLAUGHTER CATTLE & CALVES - FLORIDA, 1947

	CATTLE		CALVES		TOTAL	
	No. Head	Percent	No. Head	Percent	No. Head	Percent
January	21,200	8.61	8,000	5.87	29,200	7.63
February	16,000	6.50	6,800	4.99	22,800	5.96
March	14,000	5.69	7,200	5.28	21,200	5.54
April	15,000	6.09	7,400	5.43	22,400	5.85
May	19,000	7.72	9,000	6.60	28,000	7.32
June	19,000	7.72	11,200	8.22	30,200	7.90
July	23,000	9.34	14,000	10.27	37,000	9.68
August	22,000	8.93	14,300	10.49	36,300	9.50
September	23,000	9.34	14,000	10.27	37,000	9.67
October	27,000	10.97	17,000	12.47	44,000	11.50
November	23,000	9.34	16,000	11.74	39,000	10.20
December	24,000	9.75	11,400	8.37	35,400	9.25
Total	246,200	100%	136,300	100%	382,500	100%

HOGS

Q. 12: What is the number and value of hogs in Florida?
The following Table shows numbers and value of hogs on Florida Farms for years indicated?

	No. Head	Avg. Value	Total Value
1925	498,000	$ 6.50	$ 3,237,000.00
1930	490,000	7.50	3,675,000.00
1935	447,000	3.55	1,586,850.00
1940	555,000	4.30	2,386,700.00
1945	609,000	10.80	6,574,000.00
1946	630,000	12.70	8,001,000.00
1947	630,000	16.20	10,206,000.00
1948	640,000	23.40	14,976,000.00

Source of Tables above: U.S.D.A. Yearbook and Agricultural Statistical Yearbook, U.S.D.A.

Q. 13: What is Florida's position as a hog State?
Comparative figures indicate that Florida has remained about 28th in total number of hogs.

Q. 14: Where are most of the hogs in Florida found?
About 75% of Florida's hogs are found north and west from Ocala in Marion County. The leading hog producing Counties in Florida in order are: Jackson, Marion, Gadsden, Madison, Suwannee, Holmes, Lafayette, Liberty, Alachua, Gilchrist and Washington, all of which are in north-central and west Florida.

Q. 15: How does the average weight of Florida hogs compare with average for the U.S.A?
The U.S.A. average is about 230 lbs., Florida's about 170 lbs.

Q. 16: How does the number of pigs per litter in Florida compare with the U.S.A?
10-year average 1937-1946 gives U.S.A. 6.23 pigs, Florida 5.1 per litter.

Q. 17: How does the average value per head of Florida hogs compare with U.S.A?

	U.S.A.	Florida
Average 1936-45	$13.90	$ 7.20
Average 1947	39.00	16.20

This difference is due mainly to management, breeding, and feed.

Q. 18: How many hogs are marketed in Florida annually?
Approximately 500,000 and about 250,000 additional are for farm use.

Q. 19: When are most of the hogs marketed in Florida?
About 47½% are marketed from December 1st to March 1st.

GENERAL LIVESTOCK

Q. 20: Is Florida self-supporting on meats?
Florida is producing about 60% of its beef and veal and about 70% of its pork and lard. There is no reason why Florida should not be self-supporting in meats.

Q. 21: What is the gross income from meat animals in Florida?
The following Table shows the gross income in Florida from meat animals for years indicated:

Year	Cattle & Calves	Hogs & Pigs	Sheep & Lambs*	Total
1930	$ 2,130,000	$ 5,924,000	$48,000	$ 8,102,000
1935	3,232,000	4,197,000	36,000	7,465,000
1940	3,544,000	5,112,000	22,000	8,678,000
1945	18,189,000	14,621,000	13,000	32,823,000
1946	19,558,000	19,312,000	20,000	38,890,000
1947	22,770,000	24,017,000	21,000	46,808,000
Total				

*Does not include wool.

Many people overlook the fact that Florida's income from hogs and pigs for the past 5 years has nearly equalled that from cattle and calves.

Q. 22: How many frozen food lockers are there in Florida?
There are about 70.

NOTE: See Livestock Market Quotations on pages 58 and 59.

JACKSONVILLE LIVESTOCK MARKET
(Substantially Southeastern Prices)

	COWS		CALVES		STEERS		HOGS	
	Medium	Common	Good	Medium	Good	Medium	No. 1	No. 2
	100 lbs		100 lbs.		100 lbs		100 lbs	
1930:								1930
3-4	5.00-6.00	4.00-5.50	7.00-8.25	5.50-7.00	7.00-8.50	6.00-7.00	8.50	7.50
9-5	3.75-4.50	3.25-3.75	5.00-6.50	4.00-5.00	5.00-6.00	4.00-5.00	9.25-9.50	8.25-8.50
1931								1931
3-3	3.50-4.25	2.50-3.50	5.50-6.50	4.75-5.50	5.50-6.75	4.50-5.50	6.00	5.50
9-4	2.50-3.25	2.00-2.75	4.00-5.00	3.00-4.00	4.00-4.75	3.00-4.25	5.25	4.75
1932								1932
3-4	2.50-3.00	1.75-2.50	3.50-4.75	3.00-4.00	3.50-4.25	3.00-3.75	3.50	3.20
9-6	2.25-2.75	1.25-2.00	3.75-4.25	3.00-3.50	4.00-5.25	3.50-4.25	3.75	3.50
1933								1933
3-7	2.00-2.50	1.50-2.00	3.25-3.75	3.00-3.25	3.50-4.25	3.00-3.50	2.65	2.40
9-5	2.00-2.75	1.00-2.00	3.25-3.75	2.50-3.25	3.75-4.25	3.00-3.75	3.75-4.00	3.50-3.75
1934								1934
3-6	2.25-2.75	1.50-2.25	4.00-4.75	3.00-4.00	4.00-4.50	3.50-4.00	3.75-4.00	3.50-3.75
9-4	2.00-2.50	1.00-2.00	3.50-4.25	2.50-3.75	4.00-4.25	3.25-4.00	5.40-5.60	4.90-5.90
1935								1935
3-5	3.50-4.00	1.75-3.25	5.50-6.50	3.75-5.25	6.25-7.25	5.00-6.25	7.00-7.25	6.25-6.50
6-7	3.25-4.50	2.00-3.50	5.25-6.25	4.50-5.50	6.00-7.50	4.75-6.00	7.25-7.50	6.50-6.75
9-6	2.75-4.25	2.00-2.75	5.50-6.50	4.50-5.50	5.50-6.25	4.00-5.25	9.25-9.75	8.75-9.25
12-6	3.25-4.50	2.50-3.25	5.00-5.75	4.00-5.25	5.75-6.75	4.75-6.00	7.75-8.00	7.25-7.50
1936								1936
3-6	4.00-5.00	3.25-4.00	5.75-6.50	4.50-5.75	6.00-7.00	5.00-6.00	7.50-7.75	7.00-7.25
6-5	4.25-5.00	3.50-4.25	5.25-6.00	4.50-5.25	6.25-7.00	5.75-6.50	8.00-8.50	7.50-8.00
9-4	3.75-4.50	3.00-3.75	5.00-6.00	4.25-5.00	5.50-6.00	4.50-5.50	9.00-9.50	8.50-9.00
12-4	3.50-4.00	2.75-3.50	5.00-6.00	4.25-5.25	5.25-6.00	4.50-5.25	8.60-8.90	8.10-8.40
1937								1937
3-12	4.00-4.50	3.25-4.00	5.25-5.75	4.00-5.25	6.00-7.25	5.00-6.50	8.00-8.40	7.60-7.90
6-4	4.50-5.00	3.50-4.25	5.75-6.50	4.75-5.50	7.00-8.00	5.50-6.75	9.50-10	9.00-9.50
9-7	4.00-5.25	3.00-4.00	5.50-6.00	4.50-5.25	6.00-7.25	5.00-6.25	8.75-9.00	8.25-8.50
12-7	4.00-4.50	3.00-4.00	5.00-5.50	4.00-5.25	6.00-7.00	5.00-6.00	6.25-6.65	6.00-6.40
1938								1938
3-4	4.25-5.00	3.25-4.25	5.25-6.50	4.50-5.50	6.25-7.00	5.50-6.50	6.75-7.75	6.25-7.25
6-7	4.50-5.25	3.50-4.25	5.50-7.00	4.50-5.50	6.50-7.50	5.50-6.50	7.70	7.20
9-6	4.00-5.00	3.00-4.00	5.00-6.00	4.50-5.25	6.25-7.00	5.50-6.50	7.00	6.50
12-3	4.00-4.50	3.00-4.00	5.50-6.75	4.50-5.50	6.50-7.50	5.50-6.50	6.00	5.50
1939								1939
3-4	4.75-5.50	3.75-4.75	6.50-7.50	5.00-6.50	7.00-8.00	6.00-7.00	6.85	6.30
6-3	5.00-5.75	4.00-5.00	6.00-7.50	5.00-6.00	6.50-8.00	5.50-6.50	6.00	5.50
9-2	4.50-5.25	4.00-4.75	5.75-7.25	4.75-5.75	6.50-7.50	5.50-6.50	5.90	5.40
12-2	4.50-5.25	3.75-4.50	6.00-7.25	5.00-6.00	7.00-7.75	6.00-7.00	4.90	4.65
1940								1940
3-2	5.00-5.75	4.00-5.00	6.25-7.25	5.25-6.25	7.00-8.00	6.00-7.00	5.00	4.75
6-1	4.75-5.25	3.75-4.75	6.50-7.50	5.50-6.50	7.00-8.25	6.00-7.00	5.25	5.00
9-7	4.25-5.00	3.75-4.50	6.00-7.00	5.00-6.00	6.75-7.75	5.50-6.75	6.75	6.50
12-7	4.25-5.00	4.00-4.50	6.00-7.00	5.00-6.00	7.00-8.25	6.00-7.00	5.65	5.40
1941								1941
3-1	5.25-6.00	4.50-5.25	6.25-7.50	5.25-6.50	7.50-8.75	6.50-7.50	6.50	6.00
6-7	5.25-6.25	4.25-5.25	6.75-7.75	5.50-6.50	7.75-8.50	6.75-7.75	8.90	8.40
9-6	5.50-6.75	4.50-5.50	7.50-8.75	6.50-7.50	8.00-9.00	7.00-8.00	10.25	9.75
12-5	5.50-6.50	4.25-5.50	7.00-8.00	6.00-7.00	7.50-8.50	6.50-7.50	8.25	7.75
1942								1942
3-6	7.50-8.25	5.75-7.25	8.20-10	6.75-8.00	9-10.50	8.00-9.00	11.25	10.75
6-6	7.00-8.50	6.00-7.00	9.00-11	7.00-9.00	10-11.50	8.75-10	12-13.00	11.5-12.5
9-4	7.50-8.50	6.25-7.50	10-11.00	8.00-10	9.75-11¼	8.00-10	12.75-13¼	12¼-12.75
12-4	7.50-8.50	6.00-7.25	10.00-11¼	8.00-10	9.25-11	8.00-9.25	11.50-12	11-11.50
1943								1943
3-5	9.00-11	7.50-8.75	11.00-13	9.00-11	11-13.50	9.00-11	13.75-14¼	13¼-13.75
6-4	9-10.50	7.00-8.75	11.00-13¼	9.50-11	11-13.50	9½-11.25	13¼-13.75	12.75-13¼
Sept	9.00-10.5	8.00-9.00	12-13.50	12.00-13	13.00	12.00-13	13.50-14¼	12.75-13.5
Dec.	8.50-10	7.25-8.50	12-12.50	11-11.50	12-15.30	9.50-12	11¼-12.50	10.5-11.75

JACKSONVILLE LIVESTOCK MARKET (Cont'd.)
(Substantially Southeastern Prices)

	COWS		CALVES		STEERS		HOGS	
	Medium	Common	Good	Medium	Good	Medium	No. 1	No. 2
	100 lbs.		100 lbs.		100 lbs.		100 lbs.	
1944:							1944	
Jan.	9.00-10	7.50-8.50	12-12.50	11-12.00	12.50-14	10-12.00	11-12.10	10½-11.35
Feb.	9.00-10.5	7.75-9.50	12-14.00	11-12.00	13-14.50	10.50-13	11-13.00	10¾-12.25
Mch	9.75-11	9-10.00	12-14.00	11-12.00	13.25-15	11.5-13.5	12-13.25	11¼-12.50
Apr.	9.50-10.5	8.00-9.50	14-15.00	11-13.00	14-15.00	11.5-13.5	12.25-13	11.5-12.
May	9.50-10¼	8.00-9.50	13-14.50	11-13.00	14-15.00	11.5-13.5	12-13.25	11.25-12.5
June	9.25-10.5	8.00-9.00	13-14.00	11-12.00	13.5-15	10-13.50	12-13.00	11.25-12¼
July	9.25-10.5	7.25-9.25	13-14.50	10-12.00	13.5-14.5	10-13.00	12¼-13.50	11.5-12.75
Aug.	8.75-10	7.50-8.50	12-14.50	10-12.00	13-14.50	10-12.50	13-14.35	11.75-14
Sept	8.25-10	6.75-8.30	12-14.00	9.50-11½	12½-14½	9.50-12¼	13-14.25	12-14.00
Oct.	8.25-9.60	6.50-8.10	12-14.00	9-11.75	12.50-14	9.25-12¼	13¼-14¼	12-13.25
Nov.	8.10-9.50	6.25-8.00	12-13.50	9-11.75	12.25-14	9.00-12¼	13-13.75	12-13.75
Dec.	8.60-10	7.25-8.50	12.50-14	9.75-12	12.50-14½	9.75-13	12-13.25	11¼-13¼
1945							1945	
Jan.	9.25-10½	8.00-9.50	12.75-14½	10.50-13	13.50-15	11.00-13	12-14.35	11¼-13.75
Feb.	9.50-10½	9.00-9.50	14-15.50	11.50-14	14-15.25	11.50-14	13.85-14.35	13-14.35
Mch	9.75-11	9.25-9.75	14.00-15	12.00-14	14-15.50	12.00-14	14¼-14.35	13.75-14.35
Apr.	10-11.50	9.25-10	14-15.50	12.00-14	14.25-15½	12.00-14	14¼-14.35	14¼-14.35
May	9.75-11½	9.00-10	13.50-14	11.50-13½	14.50-16	12.50-14½	14¼-14.35	14¼-14.35
June	9.50-11	9.00-9.50	13.50-15	11.00-13	14-15.50	12-14.50	14¼-14.35	14¼-14.35
July	10-11.50	9.25-10	13.50-15	11.00-13	14-15.50	11.50-14	14¼-14.35	14¼-14.35
Aug.	9.50-11½	8.50-9.50	13-14.50	9.50-13	14-15.50	11.25-13	14¼-14.35	14¼-14.35
Sept	9.50-11	8.00-9.00	12.00-15	9.50-12½	13½-15½	11.00-13	14¼-14.35	14¼-14.35
Oct.	9.50-11	8.00-9.25	12.50-14	11.00-13	13½-14½	11.50-13	14-14.35	14-14.35
Nov.	9.50-11½	8.50-9.50	12.50-14	11½-13½	13.50-15	11-13.50	14-14.35	14-14.35
Dec.	9.50-11½	8.50-9.50	13.00-14	11.00-13	13.00-15	11.00-13	13.75-14.35	13.75-14.3
1946							1946	
Jan.	10.00-13	8.50-10½	13½-14½	11.00-14½	14½-16½	12.00-14	14-14.35	13.75-14.35
Feb.	11-13.50	9.50-10½	14-15.50	11.50-14½	14.50-17	12.50-15	14¼-14.35	13.75-14.35
Mch	11.00-14	10.00-11	14.00-16½	12.50-15	14.50-17	12.50-16	14.35 only	14.35 only
Apr.	11.50-14½	10-11.50	14.50-16¾	13.50-16	14.50-17	12.50-16	14.35 only	14.35 only
May	11.50-13½	10.50-11½	14.50-16½	12-15.50	15.00-17	13.00-16	14.35 only	14.35 only
June	12.00-14	10-12.50	14.50-17	12.00-16	16.00-18	12.50-16	14.35 only	14.35 only
July	11.50-16	11.50-14½	14.00-18	12-16.50	17.00-19	13.00-17	15.50-19	15.50-19
Aug.	11.50-16	9.10-12¼	13.25-15½	11.00-16	14.50-18½	12-17.10	14-35-22	14.35-22
Sept	10.20-14	8.50-11½	13-16.50	11-14.50	14-18.25	11-16.50	15.60 only	15.10-15.6
Oct*	11.1-15.6	8.40-14.4	13-16.90	11½-16½	14.50-18	12-18.00	15.60-26	15.60-26
Nov.	10.50-14	8.90-12	13.50-18	12.00-17	15.00-19	11¼-16¾	22-24.50	21-24¼
Dec.	11.35-14½	9-13.25	14.50-17	13.00-16	15½-22.10	11½-16½	18½-22½	18-22¼
1947							1947	
Jan.	13½-15.10	10.00-13	15.50-20	14.00-18	16-24.85	13.00-19	18-22.25	17-21.75
Feb.	12½-15.10	10.00-13	16.50-21	13-18.50	15.75-22½	13.50-18	21½-25¼	20½-24½
Mch	13½-15.40	11.45-13½	16.50-22½	14-18.90	18.00-23	14.60-20½	22½-26¼	22.00-26
Apr.	14-16.50	12.40-14	17-23.75	15-19.50	18.00-23	15-21.50	17.50-23	17.00-23
May	14-16.50	11.50-14	18-22.50	15-19.00	18.50-22	15.50-20	19½-23.10	18½-22½
June	14.10-17	11.00-14	18.70-22½	14.00-19	19.00-23	16.00-20	22½-24¼	21½-23½
July	14.00-16	10.00-14	19-22.50	14.00-19	19-23.50	15.00-20	23-25.50	21.50-25
Aug.	14.00-16	11.00-14	19-23.00	14.00-19	19.00-23	15-19.50	24-25.50	23.50-25
Sept	14.00-18	11.50-15	19-25.00	15.00-20	19.50-23½	15.50-20	24-26.50	23-25.75
Oct.	14.50-17	11-14.50	17-19.00	14-18.50	18.00-22	14.50-18½	22-26.75	21-26.50
Nov.	14-16.50	11.50-14½	18-21.00	14-18.50	18.00-23	14-18.50	22.50-24½	21.75-23½
Dec.	15-20.00	12.50-16	19-22.00	16-20.00	20.00-26	16.00-22	24-25.25	23-24.50
1948							1948	
Jan.	18-21.00	15-18.50	24-28.00	18.50-25	24-28.50	18-24.50	23-25.50	22.50-24¼
Feb.	19-24.00	16-19.00	24-28.00	20-25.00	24-26.00	19-24.00	17-22.50	15.75-21.75
Mch	19.50-23	17-20.00	23.50-29	19.50-25	23.50-28	19.50-25	17-20.00	16-19.00
Apr.	19.50-24	17.50-20½	24.50-30	20.50-25½	24.50-28½	20-25.50	17-19.25	16-18.50
May	20.50-24½	18.50-21½	26-31.00	21.50-26½	25.50-30	21.50-27	18-22.50	17-21.75
June	20.50-25	18-21.00	27-34.00	23.50-28	27-32.00	23-28.50	22.50-26½	20.75-25.50
July	20.50-24½	19-21.50	26-33.00	22-27.50	27.50-33	23-29.00	26-27.25	24.50-26.50
Aug.	19.50-23½	18-20.50	25-29.00	21.50-26½	26.50-31	22.50-27½	25½-27.25	24.25-26.50

NOTE: Where figure shows, for example, 10.5 it means that the animal sold for 10.5¢ per pound or $10.50 per hundred lbs. * Ceilings went off about Oct. 15, 1946.
Much of this information furnished through cooperation of Production & Marketing Administration, 402 Upchurch Bldg., Thomasville, Georgia.

THE PRODUCTION OF FLORIDA FRUITS AND VEGETABLES AS AFFECTED BY WEATHER CONDITIONS - 1947-48 SEASON

By J. C. Townsend, Jr., Agricultural Statistician
Florida Crop Reporting Service

The regularity of occurrence of storms and freezes the past few years keeps us from using the old stock phrase of calling these phenomena "unusual." We have started off too many seasons with hurricanes and have had enough cold weather in January and February to deem them abnormal. The crop year 1947-48 was no exception. The season began with a hurricane in September which was accompanied by heavy rains. Three months period of recuperative weather followed and in mid-January the winter freeze occurred. Spring and early summer were generally favorable and the final resulting production of fruits and vegetables approached normal or above normal volume. Another record crop of citrus was chalked up in the book and some vegetables exceeded or neared former peaks of production.

FRUIT - Despite storm losses of two or three million boxes of citrus in the Indian River area in September, Florida's 390,000 acres of citrus produced another record volume. When an economic loss of 3,700,000 boxes of grapefruit and 600,000 boxes of tangerines are included, the total citrus crop reached nearly 96 million boxes -- a jump of nearly 9 million over 1946-47. Set of fruit last year was only moderately heavy but plenty of moisture and generally warm weather during the growing season boosted sizes in building up a record production. Low prices, especially for grapefruit, resulted in about 4 million boxes being left unharvested. The January freeze also caused a loss of several hundred thousand boxes of tangerines.

VEGETABLES - Heavy fall rains reduced the acreage and production of early vegetables, delaying seeding of tender crops in some areas so that a greater than usual toll was taken by the mid-January freeze. Overall loss of acreage from adverse weather conditions amounted to some 30,000 acres out of 270,000 acres planted. This loss was not as heavy as the year before when 25 percent of the planted acreage (or nearly 70,000 acres) was destroyed. Since the freeze came in January instead of February, growers were able to replant without too much loss to acreage in the spring. Despite storms, rains, freezes and frosts, a few new vegetable records were set in 1947-48. The 15,900 acres of cucumbers, 3,200 acres of escarole, 11,400 acres of peppers are all new peaks in acreage harvested. Green pea plantings at 700 acres were the lowest in 20 years, while 20,800 acres of Irish potatoes represented the smallest acreage since 1933. Watermelons set a new production record when 13.7 million melons were harvested. Nearly 2 million bushels of cucumbers also set a new peak for that crop. Second only to 1944-45, cabbage production in 1948 amounted to nearly 145,000 tons, and escarole at 1,376,000 bushels produced and 1,100,000 harvested was another top performance.

(In general, fall vegetable production was sharply cut from a year ago as a result of water losses. Fall acreage harvested was only 57 percent of the year before and production 64 percent of 1946.)

Growers planted 12 percent fewer acres of winter vegetables but harvested a higher percentage and with generally higher yields produced a greater volume during the winter of 1948 than in 1947. Returns to growers were disastrously low on celery and peppers during the winter but most of the others brought higher returns than in 1946-47. Some production was left in the fields.

Spring plantings followed the same general pattern with most of the reduction in snap beans. Plantings of cucumbers, celery, and peppers were increased. Yields were considerably higher this past spring, resulting in higher production. Low prices continued through the spring for celery, eggplant and peppers, resulting in some abandonment. Returns from other crops were higher. The overall returns for vegetables for the 1947-48 season amounted to nearly 90 million dollars at the F.O.B. Level -- about the same as 1946-47. (END)

- - - -

Mr. Townsend's address is U.S. Bureau of Agricultural Economics, 302 Federal Bldg., Orlando, Florida. Write to him with regard to acreage, production and value figures.

FLORIDA FOB PACKED VALUE OF SELECTED VEGETABLES AND NON-CITRUS FRUITS FOR 16 SEASONS

Season	Beans	Limas	Cabbage	Celery	Cucumbers
1932-33	$ 4,356.000	Incl.with Beans	$ 590,000	$ 1,949,000	$ 633.000
1933-34	5,773,000	236,000	685,000	2,996,000	845,000
1934-35	5,967,000	270,000	1,630,000	4,360,000	765,000
1935-36	6,250,000	202,000	612,000	4,488,000	928,000
1936-37	7,031,000	390,000	496,000	4,532,000	1,101,000
1937-38	6,272,000	507,000	973,000	3,289,000	1,053.000
1938-39	7,041,000	720,000	990,000	5,375,000	1,391,000
1939-40	7,480,000	420,000	2,061,000	5,868,000	1,238,000
1940-41	8,615,000	316,000	2,334,000	8,066,000	1,858,000
1941-42	11,412,000	704,000	1,602,000	7,154,000	2,124,000
1942-43	17;989,000	1,041,000	6,460,000	17,153,000	2,592 000
1943-44	19,116,000	1,436,000	4,284,000	16,236,000	2,072,000
1944-45	18,405,000	1,779,000	3,959,000	18,553,000	3,637,000
1945-46	18,359,000	1,533,000	5,571,000	14,260,000	5,377,000
1946-47	16,389,000	1,187,000	3,069,000	17,525,000	4,984,000
1947-48	14,484,000	1,065,000	6,500,000	9,778,000	6,203,000

Season	Eggplant	Escarole	All Lettuce	English Peas	Peppers
1932-33	$ 369,000	$ 212,000	$ 269,000	$ 403,000	$1,284,000
1933-34	289,000	267,000	286,000	507,000	1,676,000
1934-35	212,000	235,000	255,000	520,000	1,277,000
1935-36	268,000	207,000	165,000	508,000	1,273,000
1936-37	323,000	306,000	170,000	418,000	1,205,000
1937-38	356,000	204,000	149,000	642,000	1,668,000
1938-39	514,000	264,000	270,000	648,000	2,771,000
1939-40	417,000	304,000	612,000	520,000	2,121,000
1940-41	378,000	364,000	423,750	409,500	2,537,000
1941-42	628,000	324,000	481,000	434,000	2,838,000
1942-43	1,294,000	1,142,000	1,340,000	254,000	5,917,000
1943-44	1,501,000	645,000	562,000	450,000	5,460,000
1944-45	1,814,000	1,352,000	634,000	284,000	6,623,000
1945-46	1,805,000	875,000	1,285,220	339,000	6,545,000
1946-47	1,758,000	1,183,000	559,000	189,000	9,086,000
1947-48	1,151,000	1,165,000	440,000	92,000	5,866,000

Season	Potatoes	Tomatoes	Total Value Vegetables
1932-33	$1,908,000	$ 4,377,000	$16,350,000
1933-34	3,708,000	8,476,000	25,744,000
1934-35	2,503,000	6,835,000	24,837,000
1935-36	3,187,000	8,224,000	26,332,000
1936-37	5,078,000	7,688,000	29,438,000
1937-38	2,939,000	8,711,000	26,768,000
1938-39	3,644,000	12,323,000	35,951,000
1939-40	3,725,000	8,216,000	33,684,000
1940-41	2,799,000	8,618,000	36,844,000
1941-42	6,018,000	13,468,000	47,187,000
1942-43	5,914,000	11,795,000	72,896,000
1943-44	7,431,000	20,734,000	80,025,000
1944-45	12,033,000	20,376,000	89,449,000
1945-46	11,744,000	22,405,000	90,028,220
1946-47	5,475,000	19.098,000	80,512,000
1947-48	10,073,000	22,936,000	72,773,000

Note: * Miscl. Fruits does not include Citrus.

Season	Cantaloupes	Strawberries	Watermelons	Total Value Misc.Fruits* & Vegetables
1932-33	$ 24,000	$2,322,000	$ 990,000	$19,686,000
1933-34	23,000	2,646,000	779,000	29,192,000
1934-35	18,000	2,236,000	726,000	27,817,000
1935-36	15,000	1,972,000	896,000	29,215,000
1936-37	28,000	2,746,000	1,310,000	33,522,000
1937-38	65,000	2,100,000	945,000	29,878,000
1938-39	44,000	3,175,000	976,000	40,146,000
1939-40	38,000	2,344,000	1,193,000	37,259,000
1940-41	37,500	2,194,000	1,445,850	40,521,000
1941-42	52,000	2,275,000	1,572,000	51,086,000
1942-43	84,500	1,498,000	2,641,000	77,119,500
1943-44	91,000	1,107,000	4,593,000	85,725,000
1944-45	120,000	1,541,000	4,918,000	96,028,000
1945-46	54,000	2,363,000	5,552,000	98,067,220
1946-47	102,000	3,737,000	5,419,000	89,770,000
1947-48	339,000	2,003,000	6,862,000	88,977,000

Note: Tabulations based on information supplied by U.S. Agricultural Statisticians, Orlando, Florida. Valuation figures represent gross packed value, when packed at Florida shipping points. Several vegetables of commercial importance not included above. Does not include Carrots $270,000 and Cauliflower $176,000.

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 23 SEASONS
(For Harvest)

Season	Beans Acreage	Limas Acreage	Cabbage Acreage	Celery Acreage	Cucumbers Acreage	Season
1925-26	16,000	(1)	3,660	3,520	7,590	1925-26
1926-27	19,490	(1)	3,010	4,240	7,440	1926-27
1927-28	29,730	(1)	2,900	3,380	9,450	1927-28
1928-29	27,000	(1)	6,500	6,620	11,340	1928-29
1929-30	35,800	(1)	3,700	6,650	12,100	1929-30
1930-31	40,000	(1)	6,500	6,150	9,650	1930-31
1931-32	41,500	(1)	5,500	6,850	7,300	1931-32
1932-33	50,800	(1)	6,200	6,650	5,600	1932-33
1933-34	61,300	1,500	10,700	6,000	5,000	1933-34
1934-35	65,500	1,500	5,600	6,000	5,100	1934-35
1935-36	59,200	1,800	9,000	6,500	5,700	1935-36
1936-37	58,800	2,400	8,500	7,500	5,600	1936-37
1937-38	60,700	4,500	9,400	8,000	7,000	1937-38
1938-39	64,000	4,600	10,000	7,300	7,600	1938-39
1939-40	52,000	4,000	16,000	7,500	8,200	1939-40
1940-41	62,500	7,000	10,000	8,700	8,800	1940-41
1941-42	68,000	5,000	18,000	9,350	9,700	1941-42
1942-43	80,000	5,400	10,000	8,750	6,500	1942-43
1943-44	96,500	4,500	23,500	9,900	6,300	1943-44
1944-45	80,500	4,800	17,500	11,050	7,700	1944-45
1945-46	80,200	6,300	13,200	13,450	11,950	1945-46
1946-47	81,700	5,200	14,000	11,700	13,775	1946-47
1947-48	71,700	4,250	16,100	11,600	15,900	1947-48

Note: (1) Limas were included with snap beans prior to the 1933-34 season. The lima figures are for the Fordhook or large variety and do not include acreage of baby limas or butterbeans.

Season	Eggplant Acreage	Escarole (2) Acreage	Boston Lettuce (3) Acreage	Iceberg Lettuce (4) Acreage	English Peas Acreage	Season
1925-26	1,020	(2)	1,500	-	760	1925-26
1926-27	630	(2)	1,500	-	700	1926-27
1927-28	1,550	340	1,500	-	1,230	1927-28
1928-29	1,320	500	1,500	-	1,350	1928-29
1929-30	1,680	460	1,100	-	700	1929-30
1930-31	1,800	850	1,600	-	2,000	1930-31
1931-32	1,950	700	1,000	-	3,800	1931-32
1932-33	2,450	700	950	-	3,600	1932-33
1933-34	2,050	700	1,100	-	4,800	1933-34
1934-35	1,500	650	900	(4)	5,000	1934-35
1935-36	1,100	700	550	(4)	8,200	1935-36
1936-37	1,480	900	800	(4)	6,200	1936-37
1937-38	1,800	1,000	900	(4)	6,200	1937-38
1938-39	2,100	1,000	750	250	5,000	1938-39
1939-40	1,400	1,350	900	1,100	5,000	1939-40
1940-41	1,900	1,000	500	2,000	3,000	1940-41
1941-42	2,350	1,200	500	3,000	3,500	1941-42
1942-43	1,950	1,450	800	1,700	1,500	1942-43
1943-44	3,500	2,350	1,100	1,350	2,500	1943-44
1944-45	2,850	2,800	400	1,000	2,600	1944-45
1945-46	3,900	2,500	550	1,300	1,600	1945-46
1946-47	3,300	2,800	700	1,125	1,600	1946-47
1947-48	3,225	3,200	550	1,100	600	1947-48

Notes:
(2) Escarole acreage included with lettuce prior to 1927-28 season.
(3) Big Boston figures include Romaine acreage.
(4) Iceberg Lettuce included in Big Boston acreage figures until the 1938-39 season.

All 1947-48 acreage figures are preliminary as of September 20, 1948 and are subject to revision.

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 23 SEASONS (Cont'd.)
(For Harvest)

Season	Peppers Acreage	Potatoes Acreage	Tomatoes Acreage	Total Vegetables Acreage	Season
1925-26	3,370	23,070	20,700	81,190	1925-26
1926-27	2,700	28,000	29,800	97,510	1926-27
1927-28	6,410	30,000	29,280	115,770	1927-28
1928-29	5,650	22,000	38,700	122,480	1928-29
1929-30	6,550	31,000	31,260	131,000	1929-30
1930-31	8,200	27,000	26,800	130,550	1930-31
1931-32	8,050	21,500	23,700	121,850	1931-32
1932-33	9,300	17,000	24,900	127,150	1932-33
1933-34	6,000	23,500	30,500	153,150	1933-34
1934-35	7,700	24,800	32,500	156,750	1934-35
1935-36	6,500	24,500	32,600	156,350	1935-36
1936-37	7,200	31,300	35,700	166,880	1936-37
1937-38	7,400	31,400	45,300	183,600	1937-38
1938-39	7,300	26,700	40,700	177,500	1938-39
1939-40	6,200	25,600	34,000	163,250	1939-40
1940-41	7,200	26,800	26,500	165,900	1940-41
1941-42	6,500	25,000	43,000	195,100	1941-42
1942-43	7,100	26,200	25,500	176,850	1942-43
1943-44	8,950	28,600	34,900	223,950	1943-44
1944-45	9,350	31,100	32,500	204,150	1944-45
1945-46	11,080	35,300	30,400	220,950	1945-46
1946-47	10,550	24,100	29,800	200,350	1946-47
1947-48	11,450	20,800	30,200	190,675*	1947-48

* Does not include 400 acres of cauliflower and 450 acres of commercial carrots. Does not include acreage for squash, radishes, broccoli, or any other vegetables not named. The Miscellaneous Vegetables probably total 20,000 acres.

Season	Cantaloupes (3) Acreage	Strawberries Acreage	Watermelons Acreage	Grand Total Officially Reported (5) Acreage	Season
1925-26	600	2,980	24,150	108,920	1925-26
1926-27	600	3,680	29,420	131,210	1926-27
1927-28	600	4,500	37,840	158,710	1927-28
1928-29	600	6,300	35,900	165,280	1928-29
1929-30	600	8,800	34,700	175,100	1929-30
1930-31	250	9,100	31,000	170,900	1930-31
1931-32	200	7,800	28,500	158,350	1931-32
1932-33	400	10,600	22,500	160,650	1932-33
1933-34	300	8,400	23,400	185,250	1933-34
1934-35	200	8,000	20,000	184,950	1934-35
1935-36	200	8,900	16,000	181,450	1935-36
1936-37	300	8,300	19,500	194,980	1936-37
1937-38	700	7,500	22,500	214,300	1937-38
1938-39	500	9,000	22,600	209,600	1938-39
1939-40	500	7,200	23,500	194,450	1939-40
1940-41	500	5,500	25,500	198,100	1940-41
1941-42	500	5,000	21,500	221,200	1941-42
1942-43	400	2,600	12,500	192,350	1942-43
1943-44	550	1,400	25,500	251,400	1943-44
1944-45	500	2,050	39,000	245,700	1944-45
1945-46	800	2,800	51,000	275,550	1945-46
1946-47	800	4,750	47,000	252,900	1946-47
1947-48	1,200	4,200	45,000	241,075(4)	1947-48

Notes: (3) Acreage of cantaloupes for 1926, 1927 and 1928 seasons not immediately available, but is estimated the same as for 1929 and 1930 seasons.

(4) These acreage figures do not include acres abandoned in various stages of growth for reasons other than economic marketing (poor markets).
Does not include 21,600 acres of vegetables and 6,000 acres of watermelon planted but not reaching harvest stage. Some additional acreage was abandoned for marketing reasons.

(5) Does not include 450 acres of carrots and 400 acres of cauliflower officially reported. See pages 12-13, also 64-68.

All acreage figures are preliminary as of September 20, 1948 and are subject to revision. Years prior to 1947-48 may have been revised slightly.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS

BEANS, SNAP

Season	Harvested Acreage	Yield Bushels	Volume Production	Abandoned Volume	Price per Bushel	used	FOB Packed Total Value
1929-30	35,800	89	3,172,000	Included in	$2.15		$6,805,000
1930-31	40,000	84	3,376,000	Total Production	1.95		6,592,000
1931-32	41,500	109	4,508,000	A/(284,000)	1.41		5,958,000
1932-33	50,800	98	5,002,000	A/(144,000)	.90		4,356,000
1933-34	61,300	101	6,216,000	A/(430,000)	1.00		5,773,000
1934-35	65,500	76	4,948,000	-	1.21		5,967,000
1935-36	59,200	71	4,183,000	-	1.49		6,250,000
1936-37	58,600	80	4,688,000	-	1.50		7,037,000
1937-38	60,700	89	5,381,000	-	1.17		6,272,000
1938-39	64,000	111	7,135,000	A/(288,000)	1.03		7,341,000
1939-40	52,000	98	5,090,000	-	1.47		7,480,000
1940-41	62,500	92	5,750,000	-	1.55	Canning	8,933,000
1941-42	68,000	105	5,783,000	-	1.84	.91	11,913,000
1942-43	80,000	131	7,795,000	-	2.62	$1.27	17,989,000
1943-44	96,500	86	8,273,000	A/(269,000)	2.56	1.29	18,713,000
1944-45	80,500	92	7,440,000	A/(496,000)	2.92	1.67	18,405,000
1945-46	80,200	106	8,469,000	A/(1,240,000)	2.73	1.67	18,359,000
1946-47	81,700	80	6,549,700	A/(561,000)	2.90	1.67	16,389,000
1947-48	71,700	82	5,898,000	A/(225,000)	2.57	1.54	14,484,000

A - Not harvested, account poor markets. Canning production; 1941-42 bu 1,367,000; 1942-43 bu. 2,677,000; 1943-44 bu 1,260,000; 1944-45bu 1,486,000; 1945-46 bu 1,106,000; 1946-47 bu 800,700; 1947-48 bu 583,000.

LIMAS

Season	Harvested Acreage	Yield Bushels	Volume Production	Abandoned Volume	Price per Bushel	FOB Packed Total Value
1934-35	1,500	90	135,000		$2.00	$ 270,000
1935-36	1,800	70	126,000		1.60	202,000
1936-37	2,400	65	156,000	Account	2.50	390,000
1937-38	4,500	75	338,000	poor	1.50	507,000
1938-39	4,800	100	480,000	markets	1.50	720,000
1939-40	4,000	70	280,000		1.50	420,000
1940-41	7,000	40	280,000		2.20	616,000
1941-42	5,000	65	325,000		2.10	682,000
1942-43	5,400	59	321,000		3.31	1,041,000
1943-44	4,500	77	345,000		4.16	1,436,000
1944-45	4,800	88	420,000	A/(14,000)	4.38	1,779,000
1945-46	6,300	88	555,000	A/(87,000)	3.28	1,533,000
1946-47	5,200	65	338,000		3.51	1,187,000
1947-48	4,250	91	387,000	A/(32,000)	3.00	1,065,000

CABBAGE

Season	Harvested Acreage	Yield Tons	Volume Production	Abandoned Volume	Price per Ton Used	FOB Packed Total Value
1930-31	6,500	7.4	48,100	A/(7,100)	$22.40	$ 918,000
1931-32	5,500	4.0	22,100	-	32.00	704,000
1932-33	6,200	7.0	43,400	A/(6,500)	16.00	590,000
1933-34	10,700	6.0	64,200	A/(21,400)	16.00	685,000
1934-35	5,600	5.2	29,120		56.00	1,630,000
1935-36	9,000	4.0	36,000		17.00	612,000
1936-37	8,500	6.0	51,000	A/(20,000)	16.00	496,000
1937-38	9,400	6.5	61,000		16.00	978,000
1938-39	10,000	5.5	55,000		18.00	990,000
1939-40	16,000	7.0	112,000		18.40	2,061,000
1940-41	10,000	6.0	60,000		38.90	2,334,000
1941-42	18,000	6.0	108,000		17.80	1,602,000
1942-43	10,000	8.5	85,000		76.00	6,460,000
1943-44	23,500	7.1	166,800	A/(47,100)	36.00	4,309,000
1944-45	17,500	7.5	131,000	A/(24,000)	37.00	3,959,000
1945-46	13,200	8.8	116,200	A/(2,500)	49.00	5,571,000
1946-47	14,000	7.1	99,400	A/(18,200)	37.80	3,069,000
1947-48	16,100	9.0	144,900	A/(21,100)	52.50	6,500,000

A - Not harvested, due to economic abandonment. Values cover harvested portion of crop. Abandoned volume is included in production volume.

NOTE: All 1947-48 acreage figures are preliminary as of September 20, 1948 and are subject to revision. Revisions are usually of minor consequence.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

CELERY

Season	Harvested Acreage	Yield N.Y.	Crates Fla.	Volume Production	Abandoned Volume	Prices per NY 2/3 Crates	FOB Packed Total Value	Price per Fla. Crates
1930-31	6,150	308	(513)	1,894,000	-	$ 2.75	$ 5,212,000	$1.65
1931-32	6,850	255	(425)	1,746,000	--	2.17	3,783,000	1.30
1932-33	6,650	262	(437)	1,743,000	A/(207,000)	1.27	1,949,000	.76
1933-34	6,000	312	(520)	1,872,000	--	1.60	2,996,000	.96
1934-35	6,000	280	(467)	1,680,000	-	2.60	4,368,000	1.56
1935-36	6,500	265	(442)	1,723,000	-	2.60	4,488,000	1.56
1936-37	7,500	280	(467)	2,097,000	-	2.16	4,532,000	1.30
1937-38	8,000	286	(477)	2,290,000	A/(255,000)	1.62	3,289,000	.97
1938-39	7,300	299	(498)	2,184,000	-	2.46	5,375,000	1.48
1939-40	7,500	304	(507)	2,279,000	-	2.57	5,868,000	1.54
1940-41	9,100	278	(463)	2,531,000	-	3.19	8,066,000	1.91
1941-42	9,350	269	(465)	2,608,000	F/(4,347,000)	2.74	7,154,000	1.64
1942-43	8,750	-	447	4,175,500	(Fla.Crts)	-	17,158,000	4.11
1943-44	9,900	-	502	4,969,000	A/(400,000)	-	14,530,000	3.18
1944-45	11,050	-	493	5,448,000	A/(102,000)	-	18,553,000	3.47
1945-46	13,450	-	479	6,439,000	A/(151,000)	-	14,250,000	2.27
1946-47	11,700	-	390	4,564,000		--	17,535,000	3.84
1947-48	11,600	-	487	5,651,000	A/(892,000)	-	9,778,000	2.05

A - Not harvested, due to economic abandonment. Values cover harvested portion crops. Florida crates are approximately 60 per cent as large as NY 2/3 crates.

CUCUMBERS

Season	Harvested Acreage	Yield Bushels	Volume Production	Abandoned Volume	Price per Bushel	FOB Packed Total Value
1929-30	12,100	54	649,000	-	$2.42	$1,568,000
1930-31	9,650	100	961,000	-	1.35	1,293,000
1931-32	7,300	53	390,000	-	1.68	655,000
1932-33	5,600	64	361,000	-	1.75	633,000
1933-34	5,000	95	474,000	-	1.78	845,000
1934-35	5,100	93	473,000	-	1.62	765,000
1935-36	5,700	82	468,000	-	1.98	928,000
1936-37	5,600	65	364,000	-	3.02	1,101,000
1937-38	7,000	121	850,000	-	1.24	1,053,000
1938-39	7,600	115	876,000	-	1.58	1,391,000
1939-40	8,200	145	1,186,000	-	1.63	1,938,000
1940-41	8,800	121	1,064,000	-	1.75	1,858,000
1941-42	9,700	94	912,000	-	2.24	2,042,000
1942-43	6,500	80	520,000	-	4.98	2,592,000
1943-44	6,300	73	459,000	-	4.55	2,079,000
1944-45	7,700	110	844,000	-	4.31	3,637,000
1945-46	11,150	136	1,520,000	A/(76,000)	3.72	5,377,000
1946-47	13,775	87	1,204,000	-	4.14	4,984,000
1947-48	15,900	123	1,957,000	A/(50,000)	3.25	6,203,000

EGGPLANT

Season	Harvested Acreage	Yield Bushels	Volume Production	Abandoned Volume	Price per Bushel	FOB Packed Total Value
1929-30	1,680	224	377,000	--	$1.20	$ 454,000
1930-31	1,800	240	432,000	--	.82	356,000
1931-32	1,950	189	367,000	-	.75	277,000
1932-33	2,450	253	620,000	-	.58	359,000
1933-34	2,050	187	384,000	-	.75	289,000
1934-35	1,500	180	270,000	-	.79	213,000
1935-36	1,100	286	315,000	-	.85	268,000
1936-37	1,460	283	410,000	-	.79	323,000
1937-38	1,800	261	470,000	-	.76	366,000
1938-39	2,100	326	686,000	-	.75	514,000
1939-40	1,400	207	290,000	-	1.44	417,000
1940-41	1,800	180	324,000	-	1.17	378,000
1941-42	2,350	237	556,500	-	1.16	643,000
1942-43	1,950	278	541,500	-	2.39	1,294,000
1943-44	3,500	259	908,000	A/(40,000)	1.65	1,501,000
1944-45	3,250	271	880,000	-	2.06	1,814,000
1945-46	3,900	345	1,344,000	A/(240,000)	1.63	1,805,000
1946-47	3,300	220	725,000	-	2.42	1,758,000
1947-48	3,225	277	894,000	A/(197,000)	1.65	1,151,000

A - Not harvested, due to economic abandonment. Value covers harvested portion of crop. Abandoned volume is included in production volume.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

ESCAROLE

Season	Harvested Acreage	Yield L.A.Crates		Volume Production		Price Crates*		FOB Packed Total Value
1932-33	700	420		294,000		$ .72		$ 212,000
1933-34	700	477		334,000		.80		267,000
1934-35	650	330		214,000		1.10		235,000
1935-36	700	370		259,000		.80		207,000
1936-37	900	453	1½ bu.hpr	408,000		.75	1½ bu.hpr	306,000
1937-38	1,000	453	" " "	453,000		.45	" " "	204,000
1938-39	1,000	440	" " "	440,000		.60	" " "	264,000
1939-40	1,350	400		540,000		.56	" " "	304,000
1940-41	1,000	373		373,000		.98	" " "	366,000
1941-42	1,200	400	" " "	480,000		.68	" " "	326,000
1942-43	1,450	350	" " "	507,500		2.25	" " "	1,142,000
1943-44	2,350	425	" " "	999,000	A	1.15	" " "	645,000
1944-45	2,800	310	" " "	868,000	A	2.10	" " "	1,352,000
1945-46	2,500	374	" " "	935,000		1.20	" " "	875,000
1946-47	2,800	325	Bu. hpr.	910,000		1.30	Bu. hpr.	1,183,000
1947-48	3,200	430	" "	1,376,000	A266,000	1.05	" "	1,165,000

* 4-6 doz. lettuce crates. A - Abandoned 1943-44 438,000, 1944-45 224,000 and 1947-48 266,000 hprs.

LETTUCE (Boston and Romaine)

Season	Harvested Acreage	Yield 4-6 doz.Crts.	Volume Production	Abandoned Volume	Price Crates	FOB Packed Total Value
1932-33*	950*	295	280,000	-	$ .96	$ 269,000
1933-34*	1,100*	236	260,000	-	1.10	286,000
1934-35*	900*	210	189,000	-	1.35	255,000
1935-36*	550*	270	148,000	-	1.25	185,000
1936-37*	800*	185	148,000	-	1.15	170,000
1937-38*	900*	185	166,000	-	.90	149,000
1938-39	750	180	135,000	-	1.50	203,000
1939-40	900	180	162,000	-	1.10	178,000
1940-41	500	150	75,000	-	2.00	150,000
1941-42	500	100	50,000	-	2.60	130,000
1942-43	800	175	140,000	-	3.05	427,000
1943-44	1,100	150	165,000	A(59,000)	2.15	228,000
1944-45	400	200	80,000	-	2.70	216,000
1945-46	550	258	142,000	A(17,000)	3.00	375,000
1946-47	700	100	70,000	-	2.95	206,000
1947-48	550	125	69,000	A(23,000)	2.05	94,000

*Seasons 1932-33/1937-38 include Boston, Romaine, Iceberg. A-Crates not harvested.

LETTUCE (Iceberg) 4-6 doz.crates.

1938-39	250	180	45,000	-	$1.49	$ 67,000
1939-40	1,100	180	198,000	-	2.30	455,000
1940-41	2,000	75	150,000	-	1.83	274,000
1941-42	3,000	55	165,000	-	2.16	356,000
1942-43	1,700	135	230,000	-	3.97	913,000
1943-44	1,350	143	193,000	A(78,000)	2.90	334,000
1944-45	1,000	143	143,000	A(24,000)	3.51	418,000
1945-46	1,300	165	214,000	A(20,000)	3.72	910,250
1946-47	1,125	107	119,000	-	2.97	353,000
1947-48	1,100	118	130,000	A(10,000)	2.88	346,000

A - Abandoned (not harvested, due to poor markets).

PEAS, ENGLISH

Season	Harvested Acreage	Yield Bushels	Abandoned Volume	Volume Production		Price per Bushel	FOB Packed Total Value
1932-33	3,600	70	-	252,000		$1.60	$ 403,000
1933-34	4,800	96	-	461,000		1.10	507,000
1934-35	5,000	80	-	400,000		1.30	520,000
1935-36	8,200	62	-	508,000		1.00	508,000
1936-37	6,200	50	-	310,000		1.35	418,000
1937-38	6,200	90	-	558,000		1.15	642,000
1938-39	5,000	70	-	350,000		1.85	648,000
1939-40	5,000	90	A/(75,000)	450,000		1.30	488,000
1940-41	3,000	70	-	210,000		1.95	410,000
1941-42	3,500	70	-	245,000		1.55	380,000
1942-43	1,500	65	-	98,000		2.60	254,000
1943-44	2,500	60	-	150,000		3.00	450,000
1944-45	2,600	75	A/(90,000)	195,000	A	2.70	284,000
1945-46	1,600	74	A/(5,000)	118,000	A	3.00	339,000
1946-47	1,600	40	-	64,000		2.95	189,000
1947-48	600	60	-	36,000		2.55	92,000

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

PEPPERS, GREEN

Season	Acreage	Yield Bushels	Production		Price per Bushel	FOB Packed Total Value
1930-31	8,200	228	1,869,000		$1.23	$ 2,294,000
1931-32	8,050	221	1,782,000		1.00	1,780,000
1932-33	8,300	266	2,210,000		.56	1,234,000
1933-34	6,000	241	1,446,000		1.16	1,676,000
1934-35	7,700	149	1,150,000		1.11	1,277,000
1935-36	6,500	226	1,467,000		.87	1,273,000
1936-37	7,200	221	1,590,000		1.20	1,902,000
1937-38	7,400	295	2,180,000		.77	1,663,000
1938-39	7,300	303	2,212,000		1.25	2,771,000
1939-40	6,200	224	1,390,000		1.53	2,121,000
1940-41	7,200	225	1,621,500		1.56	2,537,000
1941-42	6,500	276	1,792,000		1.75	3,133,000
1942-43	7,100	284	2,018,000		2.93	5,917,000
1943-44	8,950	265	2,371,000A	(86,000)	2.16	4,964,000
1944-45	9,350	287	2,687,000		2.46	6,623,000
1945-46	11,080	275	3,050,000A	(380,000)	2.45	6,545,000
1946-47	10,550	208	2,193,000		4.14	9,066,000
1947-48	11,450	250	2,860,000A	(143,000)	2.17	5,886,000

A - Not harvested, due to economic abandonment (poor markets).

POTATOES

Season	Acreage	Yield Bushels	Production	Price per Bushel	FOB Packed Total Value
1930-31	27,000	132	3,564,000	$1.07	$ 3,818,000
1931-32	21,500	70	1,505,000	1.28	1,933,000
1932-33	17,000	132	2,244,000	.85	1,908,000
1933-34	23,500	140	3,290,000	1.13	3,708,000
1934-35	24,800	97	2,406,000	1.04	2,503,000
1935-36	24,500	91	2,235,000	1.43	3,187,000
1936-37	31,300	123	3,842,000	1.32	5,087,000
1937-38	31,400	133	4,177,000	.70	2,939,000
1938-39	26,700	121	3,235,000	1.13	3,644,000
1939-40	25,600	157	4,020,000	.93	3,725,000
1940-41	26,800	117	3,126,000	.90	2,799,000
1941-42	25,000	154	3,848,000	1.54	5,924,000
1942-43	26,200	134	3,523,000	1.96	5,914,000
1943-44	28,600	112	3,212,000	2.00	6,431,000
1944-45	31,100	162	5,035,000	2.39	12,033,000
1945-46	35,300	170	6,010,000	1.95	11,744,000
1946-47	24,100	114	2,733,000	2.00	5,475,000
1947-48	20,800	174	3,614,000	2.79	10,073,000

TOMATOES

Season	Acreage	Yield Bushels	Production		Price per Bu.		FOB Packed Total Value
			Fresh	Canning	Fresh	Canning	
1930-31	26,800	75	2,020,000	-	$1.87	-	$ 3,778,000
1931-32	23,700	95	2,255,000	-	2.55	-	5,748,000
1932-33	24,900	94	2,343,000	-	1.87	-	4,377,000
1933-34	30,500	113	2,886,000	557,000	2.86	.39	8,476,000
1934-35	32,500	102	2,714,000	589,000	2.46	.28	6,335,000
1935-36	32,600	100	2,954,000	321,000	2.75	.31	8,224,000
1936-37	35,700	86	2,748,000	314,000	2.76	.32	7,688,000
1937-38	45,300	120	4,953,000	500,000	1.73	.28	8,711,000
1938-39	40,700	129	4,948,000	312,000	2.47	.28	12,323,000
1939-40	34,000	88	3,225,000	232,000	2.53	.28	8,216,000
1940-41	26,500	110	2,765,000	165,000	3.10	.28	8,618,000
1941-42	43,000	101	3,412,000	951,000	3.92	.46	13,821,000
1942-43	25,500	102	2,226,000	*	5.30	*	11,795,000
1943-44	34,900	109	3,405,000	325,000	5.72	.59	19,712,000
1944-45	32,500	137	4,456,000A	289,000	5.27	.72	20,376,000
1945-46	30,400	154	4,670,000A	265,000	5.25	.74	22,405,000
1946-47	29,800	107	3,198,000	306,000	6.50	1.00	19,098,000
1947-48	30,200	130	3,588,000	346,000	5.83	.75	22,936,000

A - 342,000 bushels in 1944-45 and 221,000 bushels in 1945-46 not harvested due to economic abandonment.

All 1947-48 acreage figures are preliminary as of September 20, 1948 and are subject to revision.

* Separate volume and price not available for 1942-43 season.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

CANTALOUPES

Season	Acreage	Yield Crates	Production		Price per Crate	FOB Packed Total Value
1930-31	250	50	12,000		$1.50	$ 18,000
1931-32	200	75	15,000		1.00	15,000
1932-33	400	60	24,000		1.00	24,000
1933-34	300	60	18,000		1.30	23,000
1934-35	200	60	12,000		1.50	18,000
1935-36	200	60	12,000		1.25	15,000
1936-37	300	55	16,000		1.75	28,000
1937-38	700	75	52,000		1.25	65,000
1938-39	500	80	40,000		1.10	44,000
1939-40	500	70	35,000		1.10	38,000
1940-41	500	60	30,000		1.25	38,000
1941-42	500	70	35,000		1.50	52,000
1942-43	400	65	26,000		3.25	85,000
1943-44	550	60	33,000		3.75	124,000
1944-45	500	50	25,000	A(5,000)	6.00	120,000
1945-46	800	45	36,000	A(18,000)	3.00	54,000
1946-47	800	50*	40,000		2.55	102,000
1947-48	1,200	65	78,000		4.35	339,000

A - Crates not harvested due to economic abandonment. * Jumbo Crates.

STRAWBERRIES

Season	Acreage	24-Qt.Crts.	Production	(48 Pints) 24 Quarts*	FOB Packed Total Value	36 Pint Crate
1930-31	9,100	72	655,000	$5.75	$ 3,766,000	$4.31
1931-32	7,800	76	593,000	4.80	2,846,000	3.60
1932-33	10,600	73	774,000	3.00	2,322,000	2.25
1933-34	8,400	75	630,000	4.20	2,646,000	3.15
1934-35	8,000	65	520,000	4.30	2,236,000	3.23
1935-36	8,900	54	481,000	4.10	1,972,000	3.08
1936-37	8,800	65	572,000	4.80	2,746,000	3.60
1937-38	7,500	70	525,000	4.00	2,100,000	3.00
1938-39	9,000	85	765,000	4.15	3,175,000	3.11
1939-40	7,200	70	504,000	4.65	2,344,000	3.49
1940-41	5,500	70	384,000	5.70	2,194,000	4.28
1941-42	5,000	70	350,000	6.50	2,275,000	4.88
1942-43	2,600	60	156,000	9.60	1,498,000	7.20
1943-44	1,400	70	98,000	11.30	1,107,000	8.47
1944-45	2,050	70	144,000	10.70	1,541,000	8.03
1945-46	2,800	80	224,000	10.55	2,363,000	7.92
1946-47	4,750	65	309,000	12.10	3,739,000	9.08
1947-48	4,200	45	189,000	10.60	2,003,000	7.95

*Now shipped almost exclusively in 36-pt.crates. The 24-qt. crate was formerly used, and it is continued here for statistical purposes. Florida crate ~~is~~ 75% as large.

WATERMELONS

Season	Acreage	Yield Melons	Production 1000 melons	Abandoned Volume	Price per 1000 melons	FOB Packed Total Value
1930-31	31,000	330	10,230	-	$200	$2,046,000
1931-32	28,500	200	5,700	-	160	912,000
1932-33	22,500	220	4,950	-	200	990,000
1933-34	23,400	180	4,212	-	185	779,000
1934-35	20,000	330	6,600	-	110	726,000
1935-36	16,000	280	4,480	-	200	896,000
1936-37	19,500	300	5,850	A/(390)	240	1,310,000
1937-38	22,500	310	6,975	A/(675)	150	945,000
1938-39	22,600	240	5,424	-	180	976,000
1939-40	23,500	290	6,815	-	175	1,193,000
1940-41	25,500	270	6,885	-	210	1,445,850
1941-42	22,000	325	7,150	-	225	1,609,000
1942-43	12,500	325	4,063	-	650	2,641,000
1943-44	25,500	305	7,778	-	655	5,095,000
1944-45	39,000	260	10,140	-	485	4,918,000
1945-46	47,000	225	10,575	-	525	5,552,000
1946-47	47,000	290	13,623	-	447	5,419,000
1947-48	45,000	305	13,725	-	500	6,862,000

A - Not harvested due to economic abandonment. Not included in total value figures. The average carload is usually figured at 1000 melons but new varieties of round type melons have lowered this average to 935-940 melons, many in 3 tiers.

AVERAGE PRICES RECEIVED FOR FARM PRODUCTS BY FARMERS-ALSO INDEX NUMBERS

			FLORIDA				UNITED STATES		
Commodity	Unit		Sept. 15 1947	Aug. 15 1948	Sept. 15 1948	Average August 1909 to July'14	Sept. 15 1947	Aug. 15 1948	Sept. 15 1948
Corn	Bu.	$	2.21	2.25	2.05	.642	2.40	1.91	1.76
Oats	Bu.	$	1.85	1.65	1.65	.399	1.08	.686	.657
Potatoes	Bu.	$	2.20	2.15	2.15	.697	a/1.48	1.58	1.53
Sweet Potatoes	Bu.	$	2.90	2.50	2.50	.878	2.40	2.65	2.32
Cotton	Lb.	¢	32.0	30.8	30.2	12.4	31.21	30.41	30.94
Cottonseed	Ton	$	70.00	70.00	62.00	22.55	75.60	76.60	66.10
Tobacco	Lb.	¢	-	37.5	-	10.0	40.7	47.4	46.7
Peanuts	Lb.	¢	9.7	9.6	9.8	4.8	10.0	10.4	10.4
Cowpeas	Bu.	$	6.00	6.50	5.00	-	4.39	4.71	[illegible]
Hogs	Cwt.	$	22.90	24.00	23.00	7.27	a/26.70	27.10	27.30
Beef Cattle	Cwt.	$	a/12.50	17.00	16.50	5.42	a/19.00	24.40	24.20
Veal Calves	Cwt.	$	a/15.50	20.20	19.60	6.75	a/21.40	26.60	26.20
Sheep	Cwt.	$	7.50	9.00	9.00	4.53	a/ 8.64	10.20	9.70
Lambs	Cwt.	$	15.00	15.00	15.00	5.88	a/21.50	24.80	23.40
Milk Cows	Head	$	107.00	125.00	125.00	48.00	156.00	197.00	198.00
Chickens	Lb.	¢	42.0	36.0	36.0	11.4	27.9	32.5	31.9
Turkeys	Lb.	¢	48.0	48.0	44.0	14.4	33.8	43.2	43.3
Eggs	Lb.	¢	65.0	62.0	64.0	21.5	53.0	49.2	51.4
Butter	Lb.	¢	69.0	72.0	70.0	25.5	68.5	66.7	66.2
Butterfat	Lb.	¢	65.0	70.0	68.0	26.3	84.0	81.1	75.6
Milk, Wholesale	Cwt.	$	6.50	a/7.10	7.20	1.60	a/4.45	a/5.00	5.08
Milk, retail b/	Qt.	¢	21.0	22.0	22.5	6.8	17.6	19.0	19.4
Wool	Lb.	¢	a/40.0	46.0	46.0	18.3	a/41.9	47.1	46.3
Hay, loose	Ton	$	26.00	23.00	19.50	11.87	16.10	17.80	18.00
Oranges, on tree	Box	$	-	-	-	-	1.31	1.43	1.96
Tangerines, on tree	Box	$	-	-	-	-	(Included in Oranges)		
Grapefruit, on tree	Box	$	-	-	.44	-	2.53	1.01	.36
Limes, on tree	Box	$	2.33	1.02	.99	-	-	-	-

a/ Revised. b/ Sold by farmers directly to consumers.

INDEX NUMBERS - August 1909 - July 1914 = 100

	FLORIDA				UNITED STATES		
Commodity	Sept. 15 1947	Aug. 15 1948	Sept. 15 1948	Average August 1909 to July'14	Sept. 15 1947	Aug. 15 1948	Sept. 15 1948
ALL FARM PRODUCTS	191	169	169	100	286	293	290
Grain	253	257	235	-	-	-	-
Food Grain	-	-	-	100	278	227	223
Feed Grain and Hay	-	-	-	100	297	235	223
Cotton and Cottonseed	211	204	198	-	-	-	-
Cotton	-	-	-	100	252	245	250
Dairy Products	199	212	216	100	282	305	302
Poultry and Eggs	266	247	253	100	246	247	253
Meat Animals	308	359	347	100	367	411	408
Citrus	81	42	42	-	-	-	-
Fruits	-	-	-	100	181	183	185
Truck Crops	245	215	215	100	179	172	150
Miscellaneous	324	310	310	-	-	-	-

J. C. Townsend, Jr. & John F. Steffens, Jr., Agri. Statis.
U.S. Department of Agriculture
Federal Building, Orlando, Florida

The foregoing set of prices and index numbers may be read in connection with the article by Mr. H. G. Clayton on pages 46-47 explaining some of the government support prices.

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASON 1945-46, 1946-47 AND 1947-48

Florida Counties	Snap Beans			Lima Beans			Cabbage		
	1945-46	1946-47	1947-48	1945-46	1946-47	1947-48	1945-46	1946-47	1947-48
Alachua	1,550	1,700	1,275	1,400	1,500	1,200	200	150	200
Bradford	150	150	125	200	125	50	100	50	50
Brevard	-	-	-	-	-	-	50	50	-
Broward	20,200	18,300	13,700	150	100	400	40	50	-
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	200	200	400
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	50	25	50
Dade	3.100	2.000	3,000	100	100	-	300	350	200
DeSoto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	100	100	100
Escambia	230	250	100	-	-	-	100	50	50
Flagler	-	-	-	-	-	-	800	1,000	1,500
Gadsden	450	450	350	-	-	-	50	50	50
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	110	-	-	-	-	-	550	450	1,500
Hamilton	-	-	-	-	-	-	50	50	50
Hardee	40	50	50	-	-	-	50	50	150
Hendry	150	-	-	-	-	-	50	50	-
Hernando	140	100	-	-	-	-	-	-	-
Highlands	230	550	500	-	-	-	25	25	25
Hillsborough	1,200	1,850	1,050	250	500	100	500	750	350
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	50	50	-	-	-	-	-	-	-
Lake	140	100	300	-	-	-	150	150	150
Lafayette	-	-	-	-	-	-	-	-	-
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	50	-	-	-	-	-	50	50	25
Madison	-	-	-	-	-	-	-	-	-
Manatee	450	550	450	-	-	-	300	200	300
Marion	800	1,300	800	700	600	300	500	400	500
Martin	340	600	700	300	125	-	100	100	75
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	150	350	600	-	-	-	650	800	600
Osceola	-	-	-	-	-	-	50	-	-
Palm Beach	48,800	51,400	46,800	3,525	1,850	2,100	3,000	3,500	3,600
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	200	200	100	-	-	-	200	150	100
Putnam	240	250	-	-	-	-	900	1,000	1,400
Sarasota	-	-	-	-	-	-	100	100	75
Seminole	350	550	600	-	-	-	1,000	1,000	1,200
St. Johns	-	-	-	-	-	-	2,500	2,700	2,800
St. Lucie	100	-	100	200	100	-	50	-	100
Sumter	230	250	600	-	-	-	50	50	50
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	240	250	350	50	150	-	50	50	150
Volusia	-	-	-	-	-	-	200	200	200
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	510	450	150	125	50	100	135	100	100
Total	80,200	81,700	71,700	7,000	5,200	4,250	13,200	14,000	16,100

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASON 1945-46, 1946-47 AND 1947-48

Florida Counties	Celery 1945-46	Celery 1946-47	Celery 1947-48	Cucumbers 1945-46	Cucumbers 1946-47	Cucumbers 1947-48	Eggplant 1945-46	Eggplant 1946-47	Eggplant 1947-48
Alachua	135	130	200	2,250	1,900	1,525	200	250	150
Bradford	-	-	-	200	150	200	-	-	-
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	450	650	800	425	500	450
Calhoun	-	-	-	200	175	250	-	-	-
Charlotte	-	-	-	-	50	100	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	300	325	400	25	-	-
Columbia	-	-	-	-	-	100	-	-	-
Dade	-	-	-	-	-	-	-	-	-
DeSoto	-	-	-	100	125	150	-	25	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	100	50	50	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	50	25	-
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	500	575	100	-	-	-
Hardee	-	-	-	1,200	1,400	2,200	250	150	100
Hendry	-	-	-	100	200	350	-	-	-
Hernando	-	-	-	-	-	-	50	-	-
Highlands	-	-	-	-	50	50	25	25	-
Hillsborough	-	-	-	800	975	1,200	475	350	825
Holmes	-	-	-	-	200	150	-	-	-
Indian River	-	-	-	-	75	50	-	25	-
Jackson	-	-	-	500	375	500	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lake	810	875	150	400	275	450	50	-	25
Lafayette	-	-	-	-	-	-	-	-	-
Lee	-	-	-	500	700	400	350	300	225
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	200	50	50	-	-	-
Madison	-	-	-	-	-	-	-	-	-
Manatee	100	75	35	950	725	450	500	375	125
Marion	220	190	420	300	275	325	225	200	125
Martin	-	-	-	50	100	50	225	200	50
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	1,165	625	1,365	400	400	400	50	-	-
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	5,175	4,280	4,000	700	1,600	2,400	775	575	975
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	50	200	250	-	-	100
Putnam	-	-	-	-	-	200	-	-	-
Sarasota	1,360	1,285	1,300	150	250	225	-	-	-
Seminole	4,475	4,150	4,065	-	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	150	400	300	50	125	-
Sumter	-	-	-	1,050	1,000	1,300	150	75	50
Suwannee	-	-	-	-	200	300	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	150	200	350	-	-	-
Volusia	-	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	50	-	-	-
Miscellaneous	10	20	65	200	125	225	175	100	25
Total	13,450	11,700	11,600	11,950	13,775	15,900	4,050	3,300	3,225

NOTE: 1947-48 figures as of September 20 subject to revision.

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1945-46, 1946-47 AND 1947-48

Florida Counties	Escarole			English Peas			Lettuce Boston & Romaine		
	1945-46	1946-47	1947-48	1945-46	1946-47	1947-48	1945-46	1946-47	1947-48
Alachua	-	-	-	200	150	100	-	-	-
Bradford	-	-	-	-	-	-	-	-	-
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	-	-	-	-	-	-
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-	-
Dade	-	-	-	-	-	-	-	-	-
DeSoto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	100	50	25	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	-	-	-	-	-	-	-	-	-
Hendry	-	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	100	50	-	-	-	-
Hillsborough	-	40	50	400	200	150	-	-	-
Hilmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lake	20	40	50	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-	-
Manatee	400	240	250	50	50	25	50	125	50
Marion	10	50	-	100	25	25	200	200	50
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	150	190	350	50	-	-	-	-	-
Osceola	-	-	-	-	-	-	-	25	-
Palm Beach	1,400	1,700	2,000	900	1,000	200	100	125	275
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	-	-	-	-	-	-
Putnam	-	-	-	-	25	25	-	-	-
Sarasota	20	500	-	-	-	-	-	-	-
Seminole	600	-	450	100	50	50	150	200	125
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	-	-	-	-	-	-
Sumter	-	-	-	-	-	-	-	-	-
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	-	-	-
Volusia	-	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	-	40	50	-	-	-	-	25	50
Total	2,600	2,800	3,200	2,000	1,600	600	500	700	550

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1945-46, 1946-47 AND 1947-48

Florida Counties	Lettuce Iceberg 1945-46	Lettuce Iceberg 1946-47	Lettuce Iceberg 1947-48	Peppers 1945-46	Peppers 1946-47	Peppers 1947-48	Potatoes 1945-46	Potatoes 1946-47	Potatoes 1947-48
Alachua	30	25	-	500	450	550	2,200	1,550	1,600
Bradford	-	-	-	50	50	-	150	100	100
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	3,200	2,075	1,800	-	-	-
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	75	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	100	50	50
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-	-
Dade	-	-	-	-	25	-	6,770	6,000	5,850
DeSoto	-	-	-	-	25	-	100	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	850	700	550
Flagler	-	-	-	-	-	-	2,250	2,100	1,950
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	400	225	300	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	-	-	-	450	285	175	50	-	-
Hendry	-	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	80	-	-
Hillsborough	250	325	175	2,675	2,600	3,850	630	100	200
Holmes	-	-	-	-	-	-	50	100	-
Indian River	-	-	-	-	25	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lake	-	25	25	150	250	240	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lee	-	-	-	500	400	325	1,360	900	950
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-	-
Manatee	150	100	150	350	350	50	50	-	-
Marion	50	25	-	125	150	200	100	50	50
Martin	-	-	-	150	225	100	240	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	180	25	50	350	250	175	240	150	50
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	250	275	200	1,900	1,625	2,000	9,200	3,250	1,100
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	300	525	700	50	-	-
Putnam	25	25	-	-	-	-	2,600	2,200	2,400
Sarasota	50	-	-	100	25	25	280	50	-
Seminole	50	50	50	275	125	125	200	-	-
St. Johns	-	-	-	-	-	-	7,300	6,200	5,750
St. Lucie	-	-	-	100	100	25	-	-	-
Sumter	-	-	75	725	800	775	-	-	-
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	100	150	50	100
Volusia	-	-	-	-	-	-	150	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	50	-	-
Miscellaneous	15	25	75	100	190	160	100	550	100
Total	1,450	1,125	1,100	12,000	10,550	11,450	35,300	24,100	20,800

NOTE: 1947-48 figures as of September 20 subject to revision.

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1945-46, 1946-47 AND 1947-48

Florida Counties	Tomatoes 1945-46	Tomatoes 1946-47	Tomatoes 1947-48	Total Vegetables 1945-46	Total Vegetables 1946-47	Total Vegetables 1947-48	Cantaloupes 1945-46	Cantaloupes 1946-47	Cantaloupes 1947-48
Alachua	50	25	100	8,715	7.830	6,900	150	250	500
Bradford	50	25	-	900	650	525	50	-	-
Brevard	200	50	50	250	100	50	-	-	-
Broward	3,250	3,450	1,250	27,715	25,125	18,400	-	-	-
Calhoun	-	-	-	200	175	250	-	-	-
Charlotte	-	275	100	-	325	275	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	300	250	450	-	-	-
Collier	1,400	1,200	800	1,725	1,525	1,200	-	-	-
Columbia	-	-	-	50	25	150	-	-	50
Dade	13,200	8,200	10,500	23,470	16,700	17,600	-	-	-
DeSoto	225	175	200	425	350	350	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	100	100	100	-	-	-
Escambia	-	-	-	1,180	1,000	700	-	-	-
Flagler	-	-	-	3,250	3,200	3,525	-	-	-
Gadsden	-	-	-	500	500	400	-	-	-
Gilchrist	-	-	-	50	25	-	-	-	-
Glades	-	175	835	1,060	850	2,635	-	-	-
Hamilton	-	-	-	550	625	150	75	50	50
Hardee	2,025	1,225	2,000	4,065	3,160	4,675	-	-	-
Hendry	-	275	375	300	525	725	-	-	-
Hernando	-	-	-	190	100	-	-	-	-
Highlands	-	25	240	460	750	865	-	-	-
Hillsborough	1,825	1,775	2,100	9,005	9,765	10,300	-	-	-
Holmes	-	-	-	50	300	150	-	-	-
Indian River	300	550	350	300	675	400	-	-	-
Jackson	-	-	-	500	375	500	75	100	-
Jefferson	-	-	-	50	50	-	-	-	-
Lake	375	125	200	2,025	1,860	1,590	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lee	700	550	250	3,410	2,850	2,150	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	50	300	100	125	100	50	75
Madison	-	-	-	-	-	-	-	50	50
Manatee	2,600	1,450	1,850	5,950	4,440	3,835	-	-	-
Marion	1,050	500	900	4,380	3,965	3,625	250	150	300
Martin	500	400	75	1,905	1,750	1,050	-	-	-
Okeechobee	-	-	700	-	-	700	-	-	-
Orange	-	-	-	3,385	3,215	3,870	-	-	-
Osceola	-	-	-	50	-	-	-	-	-
Palm Beach	1,950	750	900	77,675	71,980	66,550	-	-	-
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	200	175	100	1,000	1,275	1,375	-	-	-
Putnam	-	-	-	3,765	3,475	4,000	-	-	-
Sarasota	75	-	-	2,135	1,740	1,625	-	-	-
Seminole	-	-	-	7,200	6,725	6,710	-	-	-
St. Johns	-	-	-	9,800	8,900	8,550	-	-	-
St. Lucie	5,750	7,450	5,000	6,400	8,175	5,525	-	-	-
Sumter	1,300	650	1,000	3,505	2,625	3,850	50	50	75
Suwannee	-	-	-	-	200	300	-	50	25
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	640	700	1,050	-	-	-
Volusia	-	-	-	350	200	200	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	50	-	50	-	-	-
Miscellaneous	275	325	275	1,645	2,020	1,450	50	50	75
Total	37,300	29,800	30,200	221,000	201,450	191,525*	800	800	1,200

Note: * Total Vegetables Acreage includes- Carrots as follows: Dade 50, Highlands 50, Orange 280, Seminole 20, Miscellaneous 50. Grand Total 450.
Total Vegetable Acr age includes- Cauliflower as follows: Hillsborough 250, Manatee 100, Seminole 25, Miscellaneous 25. Grand Total 400.

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1945-46, 1946-47 AND 1947-48

Florida Counties	Strawberries 1945-46	Strawberries 1946-47	Strawberries 1947-48	Watermelons 1945-46	Watermelons 1946-47	Watermelons 1947-48	Total Miscellaneous Fruits 1945-46	Total Miscellaneous Fruits 1946-47	Total Miscellaneous Fruits 1947-48
Alachua	-	-	-	6,800	5,000	4,700	6,950	5,250	5,200
Bradford	225	400	200	100	100	50	375	500	250
Brevard	-	-	-	-	-	50	-	-	50
Broward	-	-	-	200	100	150	200	100	150
Calhoun	-	-	-	300	150	150	300	150	150
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	200	200	150	200	200	150
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	100	50	50	100	50	50
Columbia	-	-	-	350	250	300	350	250	350
Dade	150	150	-	-	-	-	150	150	-
DeSoto	-	-	-	300	100	400	300	100	400
Dixie	-	-	-	100	100	100	100	100	100
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-	-
Gadsden	-	-	-	50	-	100	50	-	100
Gilchrist	-	-	-	5,400	5,800	6,200	5,400	5,800	6,200
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	200	250	350	275	300	400
Hardee	200	400	400	100	50	75	300	450	475
Hendry	-	-	-	100	-	50	100	-	50
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	50	-	-	50
Hillsborough	1,700	3,000	2,900	400	500	600	2,100	3,500	3,500
Holmes	-	-	-	200	400	400	200	400	400
Indian River	-	-	-	100	-	150	100	-	150
Jackson	-	-	-	5,000	2,500	1,000	5,075	2,600	1,000
Jefferson	-	-	-	3,800	3,200	2,400	3,800	3,200	2,400
Lake	-	-	-	6,000	8,500	6,200	6,000	8,500	6,200
Lafayette	-	-	-	1,000	700	1,000	1,000	700	1,000
Lee	-	-	-	150	50	50	150	50	50
Leon	-	-	-	200	50	50	200	50	50
Levy	-	-	-	2,500	2,400	2,200	2,600	2,450	2,275
Madison	-	-	-	2,000	1,800	1,500	2,000	1,850	1,550
Manatee	-	-	-	150	150	100	150	150	100
Marion	-	-	-	3,500	4,550	6,500	3,750	4,700	6,800
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	-	-	-	1,200	1,100	100	1,200	1,100	100
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	-	-	-	200	200	150	200	200	150
Pasco	-	-	-	200	750	1,200	200	750	1,200
Pinellas	-	-	-	-	100	100	-	100	100
Polk	300	500	500	200	350	700	500	850	1,200
Putnam	-	-	-	100	300	150	100	300	150
Sarasota	-	-	-	-	50	-	-	50	-
Seminole	-	-	-	-	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	100	50	300	100	50	300
Sumter	100	150	150	2,700	3,200	3,500	2,850	3,400	3,725
Suwannee	-	-	-	5,500	3,000	2,400	5,500	3,050	2,425
Taylor	-	-	-	50	100	50	50	100	50
Union	-	-	-	100	50	200	100	50	200
Volusia	-	-	-	100	50	250	100	50	250
Walton	-	-	-	250	150	-	250	150	-
Washington	-	-	-	800	500	500	800	500	500
Miscellaneous	125	150	50	200	100	325	375	300	450
Total	2,800	4,750	4,200	51,000	47,000	45,000	54,600	52,550	50,400

NOTE: 1947-48 figures as of September 20 subject to revision.

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1945-46, 1946-47 AND 1947-48

Florida Counties	Total Vegetables & Miscellaneous Fruits 1945-46	1946-47	1947-48	Oranges 1945-46	1946-47	1947-48	Grapefruit 1945-46	1946-47	1947-48
Alachua	15,665	13,080	12,100	-	-	-	-	-	-
Bradford	1,275	1,150	775	-	-	-	-	-	-
Brevard	250	100	100	11,720	11,760	11,950	3,620	3,630	3,780
Broward	27,915	25,225	18,550	2,930	3,070	3,770	300	300	400
Calhoun	500	325	400	-	-	-	-	-	-
Charlotte	-	325	275	-	-	-	-	-	-
Citrus	200	200	150	-	-	-	-	-	-
Clay	300	250	450	-	-	-	-	-	-
Collier	1,825	1,575	1,250	-	-	-	-	-	-
Columbia	400	275	500	-	-	-	-	-	-
Dade	23,620	16,850	19,600	2,960	3,030	3,230	3,710	3,720	3,760
DeSoto	725	450	750	6,715	6,765	6,835	1,350	1,350	1,360
Dixie	100	100	100	-	-	-	-	-	-
Duval	100	100	100	-	-	-	-	-	-
Escambia	1,180	1,000	700	-	-	-	-	-	-
Flagler	3,250	3,200	3,525	-	-	-	-	-	-
Gadsden	550	500	500	-	-	-	-	-	-
Gilchrist	5,450	5,825	6,200	-	-	-	-	-	-
Glades	1,060	850	2,635	-	-	-	-	-	-
Hamilton	825	925	550	-	-	-	-	-	-
Hardee	4,365	3,610	5,150	8,950	9,090	9,290	910	910	910
Hendry	400	525	775	-	-	-	-	-	-
Hernando	190	100	-	1,555	1,585	1,665	360	360	360
Highlands	460	750	915	9,120	9,260	9,460	4,330	4,340	4,340
Hillsborough	11,105	13,265	13,800	16,900	17,170	17,790	3,700	3,720	3,800
Holmes	250	700	550	-	-	-	-	-	-
Indian River	400	675	550	4,940	5,050	5,310	6,520	6,600	6,840
Jackson	5,575	2,975	1,500	-	-	-	-	-	-
Jefferson	3,850	3,250	2,400	-	-	-	-	-	-
Lake	8,095	10,360	7,790	25,680	26,450	27,980	6,760	6,810	6,980
Lafayette	1,000	700	1,000	-	-	-	-	-	-
Lee	3,560	2,900	2,200	3,365	3,405	3,445	2,880	2,890	2,900
Leon	200	50	50	-	-	-	-	-	-
Levy	2,900	2,550	2,400	-	-	-	-	-	-
Madison	2,000	1,850	1,550	-	-	-	-	-	-
Manatee	6,100	4,590	3,935	4,625	4,655	4,785	4,860	4,870	4,890
Marion	8,130	8,665	10,495	9,015	9,065	9,335	720	720	730
Martin	1,905	1,750	1,050	-	-	-	-	-	-
Okeechobee	-	-	700	-	-	-	-	-	-
Orange	4,585	4,315	3,970	35,090	36,240	38,040	3,810	3,860	4,010
Osceola	50	-	-	4,445	4,485	4,605	900	900	900
Palm Beach	77,875	72,180	66,700	-	-	-	-	-	-
Pasco	200	750	1,200	6,780	7,120	7,420	1,450	1,480	1,510
Pinellas	-	100	100	7,290	7,320	7,800	7,860	7,690	8,040
Polk	1,500	2,125	2,575	57,530	58,890	61,250	26,140	26,250	26,740
Putnam	3,865	3,775	4,150	4,410	4,420	4,450	450	450	450
Sarasota	2,135	1,790	1,625	2,590	2,610	2,630	1,080	1,080	1,100
Seminole	7,200	6,725	6,710	6,790	6,840	7,110	720	720	720
St. Johns	9,800	8,900	8,550	-	-	-	-	-	-
St. Lucie	6,500	8,225	5,825	8,480	8,620	9,180	4,420	4,460	4,780
Sumter	6,355	6,225	7,575	-	-	-	-	-	-
Suwannee	5,500	3,250	2,725	-	-	-	-	-	-
Taylor	50	100	50	-	-	-	-	-	-
Union	740	750	1,250	-	-	-	-	-	-
Volusia	450	250	450	12,705	12,745	12,885	1,350	1,350	1,360
Walton	250	150	-	-	-	-	-	-	-
Washington	850	500	550	-	-	-	-	-	-
Miscellaneous	2,020	2,320	1,900	10,315	10,285	10,285	2,300	2,340	2,340
Total	275,600	254,000	241,925	264,900	270,000	280,500	90,500	91,000	93,000

FRUITS AND VEGETABLES-
COUNTY ACREAGE SEASONS 1945-46, 1946-47 AND 1947-48

Florida Counties	Tangerines			Total Citrus			Grand Total		
	1945-46	1946-47	1947-48	1945-46	1946-47	1947-48	1945-46	1946-47	1947-48
Alachua	-	-	-	-	-	-	15,665	13,080	12,100
Bradford	-	-	-	-	-	-	1,275	1,150	775
Brevard	469	470	470	15,809	15,860	16,200	16,059	15,960	16,300
Broward	96	100	100	3,326	3,470	4,270	31,241	28,695	22,820
Calhoun	-	-	-	-	-	-	500	325	400
Charlotte	-	-	-	-	-	-	-	325	[illegible]
Citrus	-	-	-	-	-	-	200	200	150
Clay	-	-	-	-	-	-	300	250	550
Collier	-	-	-	-	-	-	1,825	1,575	1,250
Columbia	-	-	-	-	-	-	400	275	500
Dade	403	425	435	7,073	7,175	7,425	30,693	24,025	27,025
DeSoto	515	520	520	8,580	8,635	8,715	9,305	9,065	9,465
Dixie	-	-	-	-	-	-	100	100	100
Duval	-	-	-	-	-	-	100	100	100
Escambia	-	-	-	-	-	-	1,180	1,000	700
Flagler	-	-	-	-	-	-	3,250	3,200	3,525
Cadsden	-	-	-	-	-	-	550	500	500
Gilchrist	-	-	-	-	-	-	5,450	5,325	6,200
Glades	-	-	-	-	-	-	1,060	350	2,635
Hamilton	-	-	-	-	-	-	825	925	550
Hardee	656	660	665	10,516	10,660	10,865	14,881	14,270	16,015
Hendry	-	-	-	-	-	-	400	525	775
Hernando	820	830	830	2,735	2,775	2,855	2,925	2,875	2,855
Highlands	820	830	830	14,270	14,430	14,630	14,730	15,180	15,545
Hillsborough	1,233	1,240	1,255	21,833	22,130	22,345	32,938	35,395	36,645
Holmes	-	-	-	-	-	-	250	700	550
Indian River	519	525	525	11,979	12,175	12,675	12,379	12,850	13,225
Jackson	-	-	-	-	-	-	5,575	2,975	1,500
Jefferson	-	-	-	-	-	-	3,850	3,250	2,400
Lake	1,952	1,980	1,990	34,392	35,240	36,950	42,487	45,600	44,740
Lafayette	-	-	-	-	-	-	1,000	700	1,000
Lee	119	120	120	6,364	6,415	6,465	9,924	9,315	8,665
Leon	-	-	-	-	-	-	200	50	50
Levy	-	-	-	-	-	-	2,900	2,550	2,400
Madison	-	-	-	-	-	-	2,000	1,850	1,550
Manatee	117	120	125	9,602	9,645	9,800	15,702	14,235	13,735
Marion	398	400	400	10,133	10,185	10,465	18,263	18,850	20,960
Martin	-	-	-	-	-	-	1,905	1,750	1,050
Okeechobee	-	-	-	-	-	-	-	-	700
Orange	3,094	3,105	3,115	41,994	43,205	45,165	46,579	47,520	49,135
Osceola	585	590	590	5,930	5,975	6,095	5,980	5,975	6,095
Palm Beach	-	-	-	-	-	-	77,875	72,180	66,700
Pasco	587	590	590	8,817	9,190	9,520	9,017	9,940	10,720
Pinellas	659	660	670	15,809	15,940	16,510	15,809	16,040	16,610
Polk	5,471	5,500	5,515	89,141	90,640	93,505	90,641	92,765	96,030
Putnam	632	640	640	5,492	5,510	5,540	9,357	9,285	9,690
Sarasota	-	-	-	3,670	3,690	3,730	5,805	5,480	5,355
Seminole	820	825	825	8,330	8,385	8,655	15,530	15,110	15,365
St. Johns	-	-	-	-	-	-	9,800	8,900	8,550
St. Lucie	890	900	900	13,790	13,980	14,860	20,290	22,205	20,685
Sumter	-	-	-	-	-	-	6,355	6,225	7,575
Suwannee	-	-	-	-	-	-	5,500	3,250	2,725
Taylor	-	-	-	-	-	-	50	100	50
Union	-	-	-	-	-	-	740	750	1,250
Volusia	1,923	1,930	1,940	15,978	16,025	16,185	16,428	16,275	16,635
Walton	-	-	-	-	-	-	250	150	-
Washington	-	-	-	-	-	-	850	500	550
Miscellaneous	771	745	750	13,386	13,370	13,375	15,406	15,690	15,275
Grand Total	23,549	23,705	23,800	378,949	384,705	397,300	654,549	638,705	639,225

NOTE: 1947-48 figures as of September 20 subject to revision.

SOURCE: U.S. Bureau of Agricultural Economics, Orlando, Florida.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS 1945-46, 1946-47, & 1947-48.

Source: U. S. Agricultural Statisticians, Orlando, Florida.

	1945-46				1946-47				1947-48			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
ALACHUA												
Beans	100	-	1450	1550	200	-	1500	1700	75	-	1200	1275
Limas	-	-	1400	1400	-	-	1500	1500	-	-	1200	1200
Cabbage	-	200	-	200	-	150	-	150	-	200	-	200
Celery	-	-	135	135	-	-	130	130	-	-	200	200
Cucumbers	50	-	2200	2250	150	-	1750	1900	25	-	1500	1525
Eggplant	100	-	100	200	150	-	100	250	50	-	100	150
Lettuce, Ice.	-	-	30	30	-	-	25	25	-	-	-	-
Peas, English	-	200	-	200	-	150	-	150	-	100	-	100
Peppers	-	-	500	500	-	-	450	450	-	-	550	550
Potatoes	-	-	2200	2200	-	-	1550	1550	-	-	1600	1600
Tomatoes	-	-	50	50	-	-	25	25	-	-	100	100
Total Vegs.	250	400	8065	8715	500	300	7030	7830	150	300	6450	6900
Cantaloupes	-	-	150	150	-	-	250	250	-	-	500	500
Watermelons	-	-	-	6800	-	-	5000	5000	-	-	4700	4700
Grand Total	250	400	8215	15665	500	300	12280	13080	150	300	11650	12100
BRADFORD												
Beans	50	-	100	150	50	-	100	150	25	-	100	125
Limas	-	-	200	200	-	-	125	125	-	-	50	50
Cabbage	-	100	-	100	-	50	-	50	-	50	-	50
Cucumbers	-	-	200	200	-	-	150	150	-	-	200	200
Peppers	-	-	50	50	-	-	50	50	-	-	-	-
Potatoes	-	-	150	150	-	-	100	100	-	-	100	100
Tomatoes	-	-	50	50	-	-	25	25	-	-	-	-
Total Vegs.	50	100	750	900	50	50	550	650	25	50	450	525
Cantaloupes	-	-	50	50	-	-	-	-	-	-	-	-
Strawberries	-	225	-	225	-	400	-	400	-	-	200	200
Watermelons	-	-	-	100	-	-	100	100	-	-	50	50
Grand Total	50	325	800	1275	50	450	650	1150	25	250	500	775
BREVARD												
Cabbage	-	50	-	50	-	50	-	50	-	-	-	-
Tomatoes	50	-	150	200	50	-	-	50	-	-	50	50
Total Vegs.	50	50	150	250	50	50	-	100	-	-	50	50
Watermelons	-	-	-	-	-	-	-	-	-	-	50	50
BROWARD												
Beans	3300	16900	-	20200	4500	12000	1800	18300	1500	12000	200	13700
Limas	-	150	-	150	-	100	-	100	-	300	100	400
Cabbage	-	40	-	40	-	50	-	50	-	-	-	-
Cucumbers	350	100	-	450	300	50	300	650	500	200	100	800
Eggplant	75	200	150	425	50	250	200	500	-	100	350	450
Peppers	150	2100	250	3200	175	1900	-	2075	-	1100	700	1800
Tomatoes	200	2550	500	3250	500	2150	800	3450	-	850	400	1250
Total Vegs.	4075	22040	1600	27715	5525	16500	3100	25125	2000	14550	1850	18400
Watermelons	-	-	-	200	-	-	100	100	-	-	150	150
Grand Total	4075	22040	1600	27915	5525	16500	3200	25225	2000	14550	2000	18550
CALHOUN												
Cucumbers	-	-	200	200	-	-	175	175	-	-	250	250
Watermelons	-	-	-	300	-	-	150	150	-	-	150	150
Grand Total	-	-	200	500	-	-	325	325	-	-	400	400
CHARLOTTE												
Cucumbers	-	-	-	-	50	-	-	50	50	-	50	100
Peppers	-	-	-	-	-	-	-	-	-	-	75	75
Tomatoes	-	-	-	-	150	-	125	275	-	50	50	100
Total Vegs.	-	-	-	-	200	-	125	325	50	50	175	275
CITRUS												
Watermelons	-	-	-	200	-	-	200	200	-	-	150	150
CLAY												
Cabbage	-	200	-	200	-	200	-	200	-	400	-	400
Potatoes	-	-	100	100	-	-	50	50	-	-	50	50
Total Vegs.	-	200	100	300	-	200	50	250	-	400	50	450

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1945-46				1946-47				1947-48			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
COLLIER												
Cucumbers	100	150	50	300	200	-	125	325	200	100	100	400
Eggplant	25	-	-	25	-	-	-	-	-	-	-	-
Tomatoes	200	600	600	1400	250	700	250	1200	-	300	500	800
Total Vegs.	325	750	650	1725	450	700	375	1525	200	400	600	1200
Watermelons	-	-	-	100	-	-	50	50	-	-	50	50
Grand Total	325	750	650	1825	450	700	425	1575	200	400	650	1250
COLUMBIA												
Cabbage	-	50	-	50	-	25	-	25	-	50	-	50
Cucumbers	-	-	-	-	-	-	-	-	-	-	100	100
Total Vegs.	-	50	-	50	-	25	-	25	-	50	100	150
Cantaloupes	-	-	-	-	-	-	-	-	-	-	50	50
Watermelons	-	-	-	350	-	-	250	250	-	-	300	300
Grand Total	-	50	-	400	-	25	250	275	-	50	450	500
DADE												
Beans	-	3100	-	3100	-	1700	300	2000	200	2500	300	3000
Limas	-	50	50	100	-	50	50	100	-	-	-	-
Cabbage	-	300	-	300	-	350	-	350	-	200	-	200
Carrots	-	-	-	-	-	25	-	25	-	50	-	50
Peppers	-	-	-	-	-	25	-	25	-	-	-	-
Potatoes	-	6500	270	6770	-	6000	-	6000	-	5850	-	5850
Tomatoes	200	10000	3000	13200	1500	6200	500	8200	200	8000	2300	10500
Total Vegs.	200	19950	3320	23470	1500	14350	850	16700	400	16600	2600	19600
Strawberries	-	150	-	150	-	150	-	150	-	-	-	-
Grand Total	200	20100	3320	23620	1500	14500	850	16850	400	16600	2600	19600
DE SOTO												
Cucumbers	50	-	50	100	75	-	50	125	-	-	150	150
Eggplant	-	-	-	25	-	-	-	25	-	-	-	-
Peppers	-	-	-	-	25	-	-	25	-	-	-	-
Potatoes	-	-	100	100	-	-	-	-	-	-	-	-
Tomatoes	25	-	200	225	25	-	150	175	-	-	200	200
Total Vegs.	75	-	350	425	150	-	200	350	-	-	350	350
Watermelons	-	-	-	300	-	-	100	100	-	-	400	400
Grand Total	75	-	350	725	150	-	300	450	-	-	750	750
DIXIE												
Watermelons	-	-	-	100	-	-	100	100	-	-	100	100
DUVAL												
Cabbage	-	100	-	100	-	100	-	100	-	100	-	100
ESCAMBIA												
Beans	-	-	230	230	-	-	250	250	-	-	100	100
Cabbage	-	100	-	100	-	50	-	50	-	50	-	50
Potatoes	-	-	850	850	-	-	700	700	-	-	550	550
Total Vegs.	-	100	1080	1180	-	50	950	1000	-	50	650	700
FLAGLER												
Cabbage	-	800	-	800	-	1000	-	1000	-	1500	-	1500
Cucumbers	-	-	100	100	-	-	50	50	-	-	50	50
Peas, English	-	100	-	100	-	50	-	50	-	25	-	25
Potatoes	-	-	2250	2250	-	-	2100	2100	-	-	1950	1950
Total Vegs.	-	900	2350	3250	-	1050	2150	3200	-	1525	2000	3525
GADSDEN												
Beans	150	-	300	450	150	-	300	450	150	-	200	350
Cabbage	-	50	-	50	-	50	-	50	-	50	-	50
Total Vegs.	150	50	300	500	150	50	300	500	150	50	200	400
Watermelons	-	-	-	50	-	-	-	-	-	-	100	100
Grand Total	150	50	300	550	150	50	300	500	150	50	300	500
GILCHRIST												
Eggplant	50	-	-	50	25	-	-	25	-	-	-	-
Watermelons	-	-	-	5400	-	-	5800	5800	-	-	6200	6200
Grand Total	50	-	-	5450	25	-	5800	5825	-	-	6200	6200

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1945-46				1946-47				1947-48			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
GLADES												
Beans	50	-	60	110	-	-	-	-	-	-	-	-
Cabbage	-	550	-	550	-	450	-	450	-	1500	-	1500
Lettuce, Ice.	-	400	-	400	-	225	-	225	-	300	-	300
Tomatoes	-	-	-	-	175	-	-	175	125	150	550	825
Total Vegs.	50	950	60	1060	175	675	-	850	125	1950	550	2625
HAMILTON												
Cabbage	-	50	-	50	-	50	-	50	-	50	-	50
Cucumbers	-	-	500	500	-	-	575	575	-	-	100	100
Total Vegs.	-	50	500	550	-	50	575	625	-	50	100	150
Cantaloupes	-	-	75	75	-	-	50	50	-	-	50	50
Watermelons	-	-	-	200	-	-	250	250	-	-	350	350
Grand Total	-	50	575	825	-	50	875	725	-	50	500	550
HARDEE												
Beans	-	-	40	40	-	-	50	50	50	-	-	50
Cabbage	-	50	-	50	-	50	-	50	-	150	-	150
Cucumbers	500	-	700	1200	800	-	600	1400	1200	-	1000	2200
Eggplant	250	-	-	250	150	-	-	150	100	-	-	100
Peppers	400	-	50	450	260	-	25	285	125	-	50	175
Potatoes	-	-	50	50	-	-	-	-	-	-	-	-
Tomatoes	25	-	2000	2025	25	-	1200	1225	-	-	2000	2000
Total Vegs.	1175	50	2840	4065	1235	50	1875	3160	1475	150	3050	4675
Strawberries	-	200	-	200	-	400	-	400	-	400	-	400
Watermelons	-	-	-	100	-	-	50	50	-	-	75	75
Grand Total	1175	250	2840	4365	1235	450	1925	3610	1475	550	3125	5150
HENDRY												
Beans	50	100	-	150	-	-	-	-	-	-	-	-
Cabbage	-	50	-	50	-	50	-	50	-	-	-	-
Cucumbers	-	-	100	100	150	-	50	200	200	100	50	350
Tomatoes	-	-	-	-	250	-	25	275	-	175	200	375
Total Vegs.	50	150	100	300	400	50	75	525	200	275	250	725
Watermelons	-	-	-	200	-	-	-	-	-	-	50	50
HERNANDO												
Beans	-	-	140	140	-	-	100	100	-	-	-	-
Eggplant	50	-	-	50	-	-	-	-	-	-	-	-
Total Vegs.	50	-	140	190	-	-	100	100	-	-	-	-
HIGHLANDS												
Beans	-	-	230	230	200	-	350	550	-	-	500	500
Cabbage	-	25	-	25	-	25	-	25	-	25	-	25
Carrots	-	-	-	-	-	25	-	25	-	50	-	50
Cucumbers	-	-	-	-	50	-	-	50	-	-	50	50
Eggplant	-	-	25	25	25	-	-	25	-	-	-	-
Peas, English	-	100	-	100	-	50	-	50	-	-	-	-
Potatoes	-	-	80	80	-	-	-	-	-	-	-	-
Tomatoes	-	-	-	-	25	-	-	25	-	40	200	240
Total Vegs.	-	125	335	460	300	100	350	750	-	115	750	865
Watermelons	-	-	-	-	-	-	-	-	-	-	50	50
HILLSBOROUGH												
Beans	100	-	1100	1200	150	-	1700	1850	200	-	850	1050
Limas	-	-	250	250	-	-	500	500	-	-	100	100
Cabbage	-	500	-	500	-	750	-	750	-	-	350	350
Cauliflower	-	-	-	-	-	300	-	300	-	250	-	250
Cucumbers	300	-	500	800	275	-	700	975	200	-	1000	1200
Eggplant	150	-	325	475	75	25	250	350	75	-	750	825
Escarole	-	-	-	-	-	40	-	40	-	50	-	50
Lettuce, Ice.	-	200	50	250	-	325	-	325	-	175	-	175
Peas, Eng.	-	400	-	400	-	200	-	200	-	150	-	150
Peppers	75	-	2600	2675	-	-	2600	2600	25	-	3825	3850
Potatoes	-	300	330	630	-	-	100	100	-	50	150	200
Tomatoes	325	-	1500	1825	425	-	1350	1775	450	150	1500	2100
Total Vegs.	950	1400	6655	9005	925	1640	7200	9765	950	1175	8175	10300
Strawberries	-	1700	-	1700	-	3000	-	3000	-	2900	-	2900
Watermelons		-	-	400	-	-	500	500	-	-	600	600
Grand Total	950	3100	6655	11105	925	4640	7700	13265	950	4075	8775	13800

FLORIDA VEGETABLE, STRAWBERRY AND WATER ELON ACREAGE BY COUNTIES AND SEASONS

	1945-46				1946-47				1947-48			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
HOLMES												
Cucumbers	-	-	-	-	-	-	200	200	-	-	150	150
Potatoes	-	-	50	50	-	-	100	100	-	-	-	-
Total Vegs.	-	-	50	50	-	-	300	300	-	-	150	150
Watermelons	-	-	-	200	-	-	400	400	-	-	400	400
INDIAN RIVER												
Cucumbers	-	-	-	-	-	-	75	75	-	-	50	50
Eggplant	-	-	-	-	-	25	-	25	-	-	-	-
Peppers	-	-	-	-	-	-	25	25	-	-	-	-
Tomatoes	150	-	150	300	350	-	200	550	50	-	300	350
Total Vegs.	150	-	150	300	350	25	300	675	50	-	350	400
Watermelons	-	-	-	100	-	-	-	-	-	-	150	150
JACKSON												
Cucumbers	-	-	500	500	-	-	375	375	-	-	500	500
Cantaloupes	-	-	75	75	-	-	100	100	-	-	-	-
Watermelons	-	-	-	5000	-	-	2500	2500	-	-	1000	1000
Grand Total	-	-	575	5575	-	-	2975	2975	-	-	1500	1500
JEFFERSON												
Beans	-	-	50	50	-	-	50	50	-	-	-	-
Watermelons	-	-	-	3800	-	-	3200	3200	-	-	2400	2400
LAFAYETTE												
Watermelons	-	-	-	1000	-	-	700	700	-	-	1000	1000
LAKE												
Beans	-	-	140	140	-	-	100	100	100	-	200	300
Cabbage	-	150	-	150	-	150	-	150	-	150	-	150
Carrots	-	-	-	-	-	20	-	20	-	-	-	-
Celery	-	135	675	810	-	225	650	875	-	150	-	150
Cucumbers	-	-	400	400	75	-	200	275	50	-	400	450
Eggplant	-	-	50	50	-	-	-	-	-	-	25	25
Escarole	-	20	-	20	-	40	-	40	-	50	-	50
Lettuce, Ice.	-	-	-	-	-	25	-	25	-	25	-	25
Peppers	-	-	150	150	100	-	150	250	40	-	200	240
Tomatoes	25	-	350	375	25	-	100	125	-	-	200	200
Total Vegs.	25	305	1765	2095	200	460	1200	1860	190	375	1025	1590
Watermelons	-	-	-	6000	-	-	8500	8500	-	-	6200	6200
Grand Total	25	305	1765	8095	200	460	9700	10360	190	375	7225	7790
LEE												
Cucumbers	300	100	100	500	500	-	200	700	250	100	50	400
Eggplant	100	150	100	350	100	150	50	300	25	100	100	225
Peas, Eng.	350	150	-	500	250	150	-	400	-	-	-	-
Peppers	-	-	-	-	-	-	-	-	50	200	75	325
Potatoes	-	1360	-	1360	-	900	-	900	-	950	-	950
Tomatoes	400	300	-	700	450	100	-	550	50	200	-	250
Total Vegs.	1150	2060	200	3410	1300	1300	250	2850	375	1550	225	2150
Watermelons	-	-	-	150	-	-	50	50	-	-	50	50
LEON												
Watermelons	-	-	-	200	-	-	50	50	-	-	50	50
LEVY												
Beans	-	-	50	50	-	-	-	-	-	-	-	-
Cabbage	-	50	-	50	-	50	-	50	-	25	-	25
Cucumbers	-	-	200	200	-	-	50	50	-	-	50	50
Tomatoes	-	-	-	-	-	-	-	-	-	-	50	50
Total Vegs.	-	50	250	300	-	50	50	100	-	25	100	125
Cantaloupes	-	-	100	100	-	-	50	50	-	-	75	75
Watermelons	-	-	-	2500	-	-	2400	2400	-	-	2200	2200
Grand Total	-	50	350	2900	-	50	2500	2550	-	25	2375	2400
MADISON												
Cantaloupes	-	-	-	-	-	-	50	50	-	-	50	50
Watermelons	-	-	-	2000	-	-	1800	1800	-	-	1500	1500
Grand Total	-	-	-	2000	-	-	1850	1850	-	-	1550	1550

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1945-46				1946-47				1947-48			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
MANATEE												
Beans	50	-	400	450	50	-	500	550	200	-	250	450
Cabbage	-	300	-	300	-	200	-	200	-	300	-	300
Cauliflower	-	-	-	-	-	200	-	200	-	100	-	100
Celery	-	100	-	100	-	75	-	75	-	35	-	35
Cucumbers	450	-	500	950	500	-	225	725	150	-	300	450
Eggplant	150	100	250	500	150	100	125	375	75	-	50	125
Escarole	-	400	-	400	-	240	-	240	-	250	-	250
Lettuce, Boston	-	50	-	50	-	125	-	125	-	50	-	50
" Iceberg	-	100	50	150	-	100	-	100	-	150	-	150
Peas, English	-	50	-	50	-	50	-	50	-	25	-	25
Peppers	150	-	200	350	250	-	100	350	-	-	50	50
Potatoes	-	50	-	50	-	-	-	-	-	-	-	-
Tomatoes	600	-	2000	2600	700	-	750	1450	450	100	1300	1850
Total Vegs.	1400	1150	3400	5950	1650	1090	1700	4400	875	1010	1950	3835
Watermelons	-	-	-	150	-	-	150	150	-	-	100	100
MARION												
Beans	100	-	700	800	300	-	1000	1300	200	-	600	800
Limas	-	-	700	700	-	-	600	600	-	-	300	300
Cabbage	-	500	-	500	-	-	400	400	-	500	-	500
Celery	-	-	220	220	-	60	130	190	-	-	420	420
Cucumbers	-	-	300	300	25	-	250	275	25	-	300	325
Eggplant	150	-	75	225	200	-	-	200	75	-	50	125
Escarole	-	10	-	10	-	50	-	50	-	-	-	-
Lettuce, Boston	-	200	-	200	-	200	-	200	-	50	-	50
" Iceberg.	-	-	50	50	-	-	25	25	-	-	-	-
Peas, English	-	100	-	100	-	-	-	25	-	25	-	25
Peppers	25	-	100	125	-	-	150	150	-	-	200	200
Potatoes	-	-	100	100	-	-	50	50	-	-	50	50
Tomatoes	-	-	1050	1050	-	-	500	500	-	-	900	900
Total Vegs.	275	810	3295	4380	550	310	3105	3965	300	575	2820	3695
Cantaloupes	-	-	250	250	-	-	150	150	-	-	300	300
Watermelons	-	-	-	3500	-	-	4550	4550	-	-	6500	6500
Grand Total	275	810	3545	8130	550	310	7805	8665	300	575	9620	10495
MARTIN												
Beans	-	100	240	340	200	200	200	600	100	200	400	700
Limas	-	100	200	300	-	125	-	125	-	-	-	-
Cabbage	-	100	-	100	-	100	-	100	-	75	-	75
Cucumbers	50	-	-	50	100	-	-	100	-	-	50	50
Eggplant	50	125	50	225	50	125	25	200	-	25	25	50
Peppers	-	100	50	150	75	100	50	225	-	50	50	100
Potatoes	-	240	-	240	-	-	-	-	-	-	-	-
Tomatoes	100	300	100	500	300	100	-	400	-	25	50	75
Total Vegs.	200	1065	640	1905	725	750	275	1750	100	375	575	1050
OKEECHOBEE												
Tomatoes	-	-	-	-	-	-	-	-	150	-	550	700
ORANGE												
Beans	100	-	50	150	150	-	200	350	600	-	-	600
Cabbage	-	650	-	650	-	-	800	800	-	600	-	600
Carrots	-	-	-	-	-	330	-	330	-	280	-	280
Celery	-	490	675	1165	-	315	380	695	-	325	1040	1365
Cucumbers	-	-	400	400	50	-	350	400	100	-	300	400
Eggplant	50	-	-	50	-	-	-	-	-	-	-	-
Escarole	-	150	-	150	-	190	-	190	-	350	-	350
Lettuce, Boston	-	-	-	-	-	25	-	25	-	-	-	-
" Iceberg	-	50	130	180	-	25	-	25	-	50	-	50
Peas, English	-	50	-	50	-	-	-	-	-	-	-	-
Peppers	350	-	-	350	250	-	-	250	175	-	-	175
Potatoes	-	40	200	240	-	-	150	150	-	-	50	50
Total Vegs.	500	1430	1455	3385	450	885	1880	3215	875	1605	1390	3870
Watermelons	-	-	-	1200	-	-	1100	1100	-	-	100	100
Grand Total	500	1430	1455	4585	450	885	2980	4315	875	1605	1490	3970
OSCEOLA												
Cabbage	-	50	-	50	-	-	-	-	-	-	-	-

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1945-46				1946-47				1947-48			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
PALM BEACH												
Beans	17800	17800	13200	48800	13300	14500	23600	51400	13000	21800	12000	46300
Limas	-	2175	1350	3525	-	1200	650	1850	-	1200	900	2100
Cabbage	-	3000	-	3000	-	3500	-	3500	-	3600	-	3600
Carrots	-	-	-	-	-	50	-	50	-	-	-	-
Celery	-	3750	1425	5175	-	3000	1280	4280	-	1900	2100	4000
Cucumbers	300	350	50	700	1000	200	400	1600	1500	500	400	2400
Eggplant	125	200	450	775	125	250	200	575	-	100	875	975
Escarole	-	1400	-	1400	-	1700	-	1700	-	2000	-	2000
Lettuce, Boston	-	100	-	100	-	125	-	125	-	275	-	275
" Iceberg	-	150	100	250	-	225	50	275	-	100	100	200
Peas, English	-	900	-	900	-	1000	-	1000	-	200	-	200
Peppers	100	1250	550	1900	125	1400	100	1625	-	1200	800	2000
Potatoes	-	5000	4200	9200	-	2800	450	3250	-	500	600	1100
Tomatoes	200	1000	750	1950	200	500	50	750	-	200	700	900
Total Vegs.	18525	37075	22075	77675	14750	30450	26780	71980	14500	33575	18475	66550
Watermelons	-	-	-	200	-	-	200	200	-	-	150	150
Grand Total	18525	37075	22075	77875	14750	30450	26980	72180	14500	33575	18625	66700
PASCO												
Watermelons	-	-	-	200	-	-	750	750	-	-	1200	1200
PINEALLAS												
Watermelons	-	-	-	-	-	-	100	100	-	-	100	100
POLK												
Beans	-	-	200	200	-	-	200	200	-	-	100	100
Cabbage	-	200	-	200	-	150	-	150	-	100	-	100
Cucumbers	-	-	50	50	100	-	100	200	-	-	250	250
Eggplant	-	-	-	-	-	-	-	-	-	-	100	100
Peas, English	-	-	-	-	-	25	-	25	-	25	-	25
Peppers	-	-	300	300	25	-	500	525	-	-	700	700
Potatoes	-	-	50	50	-	-	-	-	-	-	-	-
Tomatoes	-	-	200	200	-	-	175	175	-	-	100	100
Total Vegs.	-	200	800	1000	125	175	975	1275	-	125	1250	1375
Strawberries	-	300	-	300	-	500	-	500	-	500	-	500
Watermelons	-	-	-	200	-	-	350	350	-	-	700	700
Grand Total	-	500	800	1500	125	675	1325	2125	-	625	1950	2575
PUTNAM												
Beans	-	-	240	240	-	-	250	250	-	-	-	-
Cabbage	-	900	-	900	-	1000	-	1000	-	1400	-	1400
Cucumbers	-	-	-	-	-	-	-	-	-	-	200	200
Lettuce, Iceberg	-	-	25	25	-	-	25	25	-	-	-	-
Potatoes	-	-	2600	2600	-	-	2200	2200	-	-	2400	2400
Total Vegs.	-	900	2865	3765	-	1000	2475	3475	-	1400	2600	4000
Watermelons	-	-	-	100	-	-	300	300	-	-	150	150
Grand Total	-	900	2865	3865	-	1000	2775	3775	-	1400	2750	4150
ST. JOHNS												
Cabbage	-	2500	-	2500	-	2700	-	2700	-	2800	-	2800
Potatoes	-	-	7300	7300	-	-	6200	6200	-	-	5750	5750
Total Vegs.	-	2500	7300	9800	-	2700	6200	8900	-	2800	5750	8550
ST. LUCIE												
Beans	100	-	-	100	-	-	-	-	100	-	-	100
Limas	-	125	75	200	-	100	-	100	-	-	-	-
Cabbage	-	50	-	50	-	-	-	-	-	100	-	100
Cucumbers	100	-	50	150	200	-	200	400	150	-	150	300
Eggplant	50	-	-	50	50	50	25	125	-	-	-	-
Peppers	50	50	-	100	75	-	25	100	-	-	25	25
Tomatoes	2700	200	2850	5750	4450	-	3000	7450	1300	800	2900	5000
Total Vegs.	3000	425	2975	6400	4775	150	3250	8175	1550	900	3075	5525
Watermelons	-	-	-	100	-	-	50	50	-	-	300	300
Grand Total	3000	425	2975	6500	4775	150	3300	8225	1550	900	3375	5825

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1945-46				1946-47				1947-48			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
SARASOTA												
Cabbage	-	100	-	100	-	100	-	100	-	75	-	75
Cauliflower	-	-	-	-	-	30	-	30	-	-	-	-
Celery	-	1000	360	1360	-	925	360	1285	-	950	350	1300
Cucumbers	50	-	100	150	100	-	150	250	100	-	125	225
Escarole	-	20	-	20	-	-	-	-	-	-	-	-
Lettuce, Iceberg	-	50	-	50	-	-	-	-	-	-	-	-
Peppers	-	100	-	100	25	-	-	25	25	-	-	25
Potatoes	-	100	180	280	-	-	50	50	-	-	-	-
Tomatoes	-	-	75	75	-	-	-	-	-	-	-	-
Total Vegs.	50	1370	715	2135	125	1055	560	1740	125	1025	475	1625
Watermelons	-	-	-	-	-	-	50	50	-	-	-	-
SEMINOLE												
Beans	100	-	250	350	350	-	200	550	500	-	100	600
Cabbage	-	1000	-	1000	-	1000	-	1000	-	1200	-	1200
Carrots	-	-	-	-	-	50	-	50	-	20	-	20
Cauliflower	-	-	-	-	-	50	-	50	-	25	-	25
Celery	-	3075	1400	4475	-	2700	1450	4150	-	2900	1165	4065
Escarole	-	600	-	600	-	500	-	500	-	450	-	450
Lettuce, Boston	-	150	-	150	-	200	-	200	-	125	-	125
" Iceberg	-	50	-	50	-	50	-	50	-	50	-	50
Peas, English	-	100	-	100	-	50	-	50	-	50	-	50
Peppers	25	-	250	275	25	-	100	125	-	-	125	125
Potatoes	-	-	200	200	-	-	-	-	-	-	-	-
Total Vegs	125	4975	2100	7200	375	4600	1750	6725	500	4820	1390	6710
SUMTER												
Beans	-	-	230	230	-	-	250	250	100	-	500	600
Cabbage	-	50	-	50	-	50	-	50	-	50	-	50
Cucumbers	50	-	1000	1050	200	-	800	1000	200	-	1100	1300
Eggplant	-	-	150	150	-	-	75	75	-	-	50	50
Lettuce, Iceberg	-	-	-	-	-	-	-	-	-	75	-	75
Peppers	25	-	700	725	-	-	800	800	-	-	775	775
Tomatoes	50	-	1250	1300	50	-	600	650	-	-	1000	1000
Total Vegs.	125	50	3330	3505	250	50	2525	2825	300	125	3425	3850
Cantaloupes	-	-	50	50	-	-	50	50	-	-	75	75
Strawberries	-	100	-	100	-	150	-	150	-	150	-	150
Watermelons	-	-	-	2700	-	-	3200	3200	-	-	3500	3500
Grand Total	125	150	3380	6355	250	200	5775	6225	300	275	7000	7575
SUWANNEE												
Cucumbers	-	-	-	-	-	-	200	200	-	-	300	300
Cantaloupes	-	-	-	-	-	-	50	50	-	-	25	25
Watermelons	-	-	-	5500	-	-	3000	3000	-	-	2400	2400
Grand Total	-	-	-	5500	-	-	3250	3250	-	-	2725	2725
TAYLOR												
Watermelons	-	-	-	50	-	-	100	100	-	-	50	50
UNION												
Beans	-	-	240	240	-	-	250	250	50	-	300	350
Limas	-	-	50	50	-	-	150	150	-	-	-	-
Cabbage	-	50	-	50	-	50	-	50	-	150	-	150
Cucumbers	-	-	150	150	50	-	150	200	50	-	300	350
Peppers	-	-	-	-	-	-	-	-	-	-	100	100
Potatoes	-	-	150	150	-	-	50	50	-	-	100	100
Total Vegs.	-	50	590	640	50	50	600	700	100	150	800	1050
Watermelons	-	-	-	100	-	-	50	50	-	-	200	200
VOLUSIA												
Cabbage	-	200	-	200	-	200	-	200	-	200	-	200
Potatoes	-	-	150	150	-	-	-	-	-	-	-	-
Total Vegs.	-	200	150	350	-	200	-	200	-	200	-	200
Watermelons	-	-	-	100	-	-	50	50	-	-	250	250
WALTON												
Watermelons	-	-	-	250	-	-	150	150	-	-	-	-
WASHINGTON												
Cucumbers	-	-	-	-	-	-	-	-	-	-	50	50
Potatoes	-	-	50	50	-	-	-	-	-	-	-	-
Total Vegs.	-	-	50	50	-	-	-	-	-	-	50	50
Watermelons	-	-	-	800	-	-	500	500	-	-	500	500

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1945-46				1946-47				1947-48			
MISCELLANEOUS	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	50	-	460	510	100	100	250	450	50	-	100	150
Limas	-	75	50	125	-	25	25	50	-	-	100	100
Cabbage	-	135	-	135	-	100	-	100	-	100	-	100
Carrots	-	-	-	-	-	-	-	-	-	50	-	50
Cauliflower	-	-	-	-	-	20	-	20	-	25	-	25
Celery	-	-	10	10	-	-	20	20	-	40	25	65
Cucumbers	50	50	100	200	50	50	25	125	50	-	175	225
Eggplant	25	50	100	175	25	25	50	100	-	-	25	25
Escarole	-	-	-	-	-	40	-	40	-	50	-	50
Lettuce, Boston	-	-	-	-	-	25	-	25	-	50	-	50
" Iceberg	-	-	15	15	-	25	-	25	-	75	-	75
Peppers	-	50	50	100	90	25	75	190	60	50	50	160
Potatoes	-	10	90	100	-	200	350	550	-	50	50	100
Tomatoes	50	50	175	275	100	50	175	325	25	50	200	275
Total Vegs.	175	420	1050	1645	365	685	970	2020	185	540	725	1450
Cantaloupes	-	-	50	50	-	-	50	50	-	-	75	75
Strawberries	-	125	-	125	-	150	-	150	-	50	-	50
Watermelons	-	-	-	200	-	-	100	100	-	-	325	325
Grand Total	175	545	1100	2020	365	835	1120	2320	185	590	1125	1900

TOTAL ALL COUNTIES

	1944-45				1945-46			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	20000	37500	23000	80500	22100	38000	20100	80200
Limas	-	2000	2800	4800	-	2675	4325	7000
Cabbage	-	-	-	17500	-	13200	-	13200
Celery	-	6800	4250	11050	-	8550	4900	13450
Cucumbers	1200	400	6100	7700	2700	750	8500	11950
Eggplant	800	800	1650	3250	1400	825	1825	4050
Escarole	-	-	-	2800	-	2600	-	2600
Lettuce, Boston	-	-	-	400	-	500	-	500
" Iceberg	-	850	150	1000	-	1000	450	1450
Peas, English	-	2600	-	2600	-	2000	-	2000
Peppers	750	3800	4800	9350	1700	3800	6500	12000
Potatoes	-	11800	19300	31100	-	13600	21700	35300
Tomatoes	2800	18600	11100	32500	5300	15000	17000	37300
Total Vegetables	25550	65150	73150	204550	33200	102500	85300	221000
Cantaloupes	-	-	-	500	-	-	800	800
Strawberries	-	-	-	2050	-	2800	-	2800
Watermelons	-	-	-	39000	-	-	-	51000
Grand Total	25550	65150	73150	246100	33200	105300	86100	275600

	1946-47				1947-48			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	19700	28500	33500	81700	17200	36500	18000	71700
Limas	-	1600	3600	5200	-	1500	2750	4250
Cabbage	-	14000	-	14000	-	16100	-	16100
Carrots	-	500	-	500	-	450	-	450
Cauliflower	-	600	-	600	-	400	-	400
Celery	-	7300	-	7300	-	6300	5300	11600
Cucumbers	5000	300	8475	13775	5000	1000	9900	15900
Eggplant	1200	1000	1100	3300	400	325	2500	3225
Escarole	-	2800	-	2800	-	3200	-	3200
Lettuce, Boston	-	700	-	700	-	550	-	550
" Iceberg	-	1000	125	1125	-	1000	100	1100
Peas, English	-	1600	-	1600	-	600	-	600
Peppers	1750	3600	5200	10550	500	2600	8350	11450
Potatoes	-	9200	14200	24100	-	7400	13400	20800
Tomatoes	10000	9800	10000	29800	2800	11100	16300	30200
Total Vegetables	37650	83200	80600	201450	25900	89025	76600	191525
Cantaloupes	-	-	800	800	-	-	1200	1200
Strawberries	-	4750	-	4750	-	4200	-	4200
Watermelons	-	-	47000	47000	-	-	45000	45000
Grand Total	37650	87950	128400	254000	25900	93225	122800	241925

UNITED STATES: TOTAL ORANGE AND TANGERINE PRODUCTION-BY STATES FOR SELECTED YEARS

By: H. F. Willson, Federal-State Market News Service, Lakeland, Florida

Crop Year	CALIF.	FLA.	TEX.	ARIZ.	ALA.	LA.	MISS.	TOTAL
			- Thousand	Boxes -				
1889	1,245	3,147	--	--	--	--	---	4,392
1919	16,632	8,000	9	80	20	37	31	24,809
1923	24,153	13,700	6	86	225	75	55	38,300
1928	39,159	16,500	125	99	85	220	30	56,218
1933	28,439	17,900	430	155	3	245	2	47,174
1938	41,420	33,300	2,815	430	96	385	85	78,531
1939	44,404	28,000	2,360	520	75	228	59	75,646
1943	51,961	49,800	3,550	1,100	-	240	-	106,651
1946	53,530	58,400	5,000	1,200	-	410	-	118,540
1947	46,600	62,100	5,800	780	-	300	-	115,580

Oranges include Tangerines for all States.

- - - - - -

FLORIDA PRODUCTION - SEGREGATED - EARLY & MID-SEASON, VALENCIAS & TANGERINES

Crop Year	Early & Mid-season	Valencias	Tangerines	Total Production
	1,000 boxes	1,000 boxes	1,000 boxes	1,000 boxes
1938-39	17,150	12,750	3,400	33,300
1939-40	15,600	10,000	2,400	28,000
1940-41	16,200	12,400	2,700	31,300
1941-42	15,200	12,000	2,100	29,300
1942-43	19,100	18,100	4,200	41,400
1943-44	25,800	20,400	3,600	49,800
1944-45	21,700	21,100	4,000	46,800
1945-46	25,400	24,400	4,200	54,000
1946-47	30,500	23,200	4,700	58,400
1947-48	31,000	27,200	3,900	62,100

This includes any production in any State abandoned for market reasons.

- - - - - -

UNITED STATES: TOTAL GRAPEFRUIT PRODUCTION - BY STATES FOR SELECTED YEARS

Crop Year	FLA.	TEX.	CALIF.	ARIZ.	TOTAL
		Thousand	Boxes		
1889	10	--	--	---	10
1919	5,900	3	363	29	6,295
1923	8,500	65	363	95	9,023
1928	11,300	753	972	211	13,236
1933	10,900	1,200	1,772	800	14,672
1938	23,300	15,670	1,924	2,700	43,594
1939	15,900	14,400	1,975	2,900	35,175
1943	31,000	17,710	3,300	4,080	56,090
1946	29,000	23,300	3,120	4,100	59,520
1947	33,000	24,000	2,860	3,000	62,860

- - - - - -

FLORIDA PRODUCTION - SEGREGATED - SEEDLESS AND OTHER

Crop Year	Seedless	Other	Total Grapefruit Production
	1,000 boxes	1,000 boxes	1,000 boxes
1938-39	7,800	15,500	23,300
1939-40	6,500	9,400	15,900
1940-41	8,200	16,400	24,600
1941-42	7,700	11,500	19,200
1942-43	10,300	17,000	27,300
1943-44	14,000	17,000	31,000
1944-45	8,400	13,900	22,300
1945-46	14,000	18,000	32,000
1946-47	14,000	15,000	29,000
1947-48	15,000	18,000	33,000

TOTAL NUMBER OF ALL CITRUS TREES MOVING FROM NURSERIES IN FLORIDA AS REPORTED TO THE NURSERY INSPECTOR, STATE PLANT BOARD, GAINESVILLE, FLORIDA

1946-47 SEASON

ALL CITRUS

Variety	No. Trees
Orange	728,882
Grapefruit	281,637
Mandarin	128,895
Lime	34,755
Lemon	6,328
Tangelo	6,259
Miscellaneous	10,104
Total	1,196,860

ORANGES

Variety	No. Trees
Valencia	329,089
Pineapple	77,952
Parson Brown	87,517
Hamlin	120,249
Lue Gim Gong	22,459
Navel	11,093
Unnamed	2,196
Miscellaneous	78,327
Total	728,882

GRAPEFRUIT

Variety	No. Trees
Marsh	59,069
Duncan	61,912
Conner's Early	1,924
Foster	2,915
Thompson	81,035
McCarty	7,122
Excelsior	9,804
Henninger Ruby	45,958
Unnamed	6,616
Miscellaneous	5,282
Total	281,637

LIMES, TEMPLES, AND TANGERINES

Variety	No. Trees
Limes:	
Persian	13,373
Unnamed	5,603
Other	15,779
Total	34,755
Temples	92,192
Tangerines	22,349

LEMONS

Variety	No. Trees
Villa Franca	86
Perrine	3
Meyer	1,747
Sperriola	15
Unnamed	661
Others	3,816
Total	6,328

Compiled by the Department of Agricultural Economics, Agricultural Experiment Station, University of Florida.

ESTIMATED FLORIDA INTERSTATE TRUCK SHIPMENTS FOR 1947-48 SEASON

	Oranges	Grapefruit	Tangerines	Total
August	7	18	-	25
September	4	61	-	65
October	675	376	LCL	1,051
November	1,547	309	261	2,117
December	2,376	206	697	3,279
January	1,568	267	559	2,394
February	1,810	306	149	2,265
March	1,990	329	4	2,323
April	1,550	324	LCL	1,874
May	1,583	360	-	1,943
June	944	204	-	1,148
July	214	98	-	312
Total	14,268	2,858	1,670	18,796

The figures above were based on the Inspections for Interstate Truck Shipments for period August 1 to July 31 along with actual reports of Truck Passings October 16 to May 31 at Road Guard Inspection Stations at points leading out of Florida. The figures are substantially correct.

INSPECTIONS FOR INTERSTATE TRUCK SHIPMENTS#

1946-47 Season	Oranges	Grape-fruit	Tang-erines	Total
Aug.	7	18	-	25
Sept.	4	61	-	65
Oct.	675	430	LCL	1,105
Nov.	1,531	325	270	2,126
Dec.	2,349	223	711	3,283
Jan.	1,618	295	572	2,485
Feb.	1,769	322	143	2,234
Mar.	2,046	362	4	2,412
Apr.	1,591	340	LCL	1,931
May	1,584	374	LCL	1,958
June	944	215	-	1,159
July	214	103	-	317
Total	14,332	3,068	1,700	19,100#

PASSINGS THROUGH ROAD GUARD STATIONS

Oct.16-May 31	Oranges	Grape-fruit	Tang-erines	Total
Aug.	-	-	-	A
Sept.	-	-	-	A
Oct. 16-30	578	136	-	714
Nov.	1,547	309	261	2,117
Dec.	2,376	206	697	3,279
Jan.	1,568	267	559	2,394
Feb.	1,810	306	149	2,265
Mar.	1,990	329	4	2,323
Apr.	1,550	324	LCL	1,874
May	1,583	360	-	1,943
June	-	-	-	A
July	-	-	-	A
Total	13,002	2,237	1,670	16,909B

Some fruit inspected for Interstate Truck Shipment does not go out of the State but is consumed within.

A-Road Guard Inspection Stations not open August 1 to October 15, and June 1 to July 31. August 1948 Shipments: Oranges 58, Grapefruit 8, Mixed Citrus 10.

B-Passings through Road Guard Stations include for West Florida: Oranges 295, Grapefruit 59, Tangerines 24, with Total of 379 Carloads.

CITRUS TRUCKED THROUGH FLORIDA ROAD GUARD STATIONS

1947-48 Season - Oct. 16 - May 31

(Tabulated from records of Citrus and Vegetable Inspection Division)

Station	Hwy.	Oranges	Grapefruit	Tangerines	Total
Wilcox	US 19	2,498	252	242	2,992
Branford	Fla.20	368	31	6	405
Ellaville	US 90	477	53	63	593
Suwannee Springs	US 129	67	9	9	85
White Springs	US 41	3,235	532	431	4,198
Hilliard	US 1	1,929	478	250	2,657
Yulee	US 17	4,320	863	664	5,847
Lake City	Fla.47	93	17	5	115
Luraville	Fla.51	15	2	LCL	17
Total		13,002	2,237	1,670	16,909

NOTE: Similar information on Vegetables not available.

HG Clayton

FLORIDA STATE MARKETING BUREAU

ANNUAL FRUIT AND VEGETABLE REPORT

PRODUCTION, TRANSPORTATION AND MARKETING ANALYSIS

1948-49 SEASON

(Also Poultry, Egg, Livestock, Tobacco and Field Crop Statistics)

By Frank H. Scruggs, Market News Specialist

Neill Rhodes, Commissioner
Florida State Marketing Bureau
Division of
Florida State Department of Agriculture
Nathan Mayo, Commissioner

This Annual Report is available free of charge to parties interested

Released October 18, 1949

Florida State Marketing Bureau
505 West Adams Street
P. O. Box 779
Jacksonville 1, Florida

FOREWORD

This may be the foreword but it is the last thing to be written and after getting together 94 pages of facts and figures in a unit, I feel like the little polar bear sitting on the ice which said to its mother "my tale is told." I don't know anything about writing a foreword but I understand that it is the chance that the writer gets to say whatever he has on his mind as long as he keeps it serious.

We have endeavored to give you the best statistical report possible as far as volume goes, not trying to make a pretty report which is expensive. We got out this report during the less active part of the season and there is no extra expense except the paper, stencils, ink and mailing. We try to hold our mailing list down to cut expenses. It might be a headache to a lot of people who will take most anything that is free. This report is free. It goes to most of people in Florida who need it, first of all to farmers, growers, shippers, in Florida, and to most of the larger business corporations, transportation agencies, universities, libraries, and government agencies from coast to coast. They sometimes say some nice things about the report.

The writer is a market news specialist, does not lay claims to being a statistician and is afraid that the market news men call him a statistician and the statisticians call him a market news man, but that is alright just so they don't call him an economist.

Our own Commissioner of Agriculture, Nathan Mayo, says that a statistician is a blind man in a dark closet, looking for a black cat, that's not there.

I don't really like statistics, - I just started this thing in a small way twenty years ago and can't let go. It was a little bear in 1929.

ACKNOWLEDGMENT

We wish to acknowledge the splendid cooperation we received from both official and private sources during the preparation of this rather comprehensive statistical report.

The rail freight and express carlot shipment figures were secured from the Fruit and Vegetable Branch of the Production and Marketing Administration, U.S. Department of Agriculture in Washington, D.C.

Exhaustive vegetable acreage, yield, production and value data and other assistance was supplied by Mr. J. C. Townsend, Jr., Mr. J. B. Owens, and Mr. Paul Shuler, Agricultural Statisticians, and Mr. G. N. Rose, Truck Crop Statistician, U.S. Bureau of Agricultural Economics, Federal Building, Orlando, Florida.

Mr. A. L. Scarborough, Statistician of the Citrus and Vegetable Division, Florida Department of Agriculture, Winter Haven, Florida, supplied us with important record data and other information. Mr. Hugh S. Flynt, Assistant Director of this division, supplied a detailed summary of inspections for the season. The daily reports from their Road Guard Stations, operated by the Citrus and Vegetable Division, showing passings of fruits and vegetables, were very helpful to shippers and growers throughout the season and for record purposes in this report.

Mr. H. F. Willson, Federal-State Citrus Market News Service, also supplied useful data for use in this report.

Mr. William B, Conner, of the Florida Citrus Exchange, Tampa, wholeheartedly complied with our requests for specified citrus information.

Several official and private agencies and individuals not already mentioned supplied information directly or indirectly to us, for which we extend our thanks.

The preparation of this report is tedious and requires long and hard work, and appreciation by the writer is extended to our Bureau staff for their efforts and accomplishments. Commissioner L. Neill Rhodes contributed and Introductory which is information and well worth your reading. Mr. L. H. Lewis, Specialist, Live Stock and Field Crops, and Mr. Gifford N. Rhodes, Specialist, Live Stock Market News, and Mr. F. W. Risher, Specialist, Dairy and Poultry Products, of this Bureau, supplied certain livestock and poultry information.

- - - - - - - - - - -

Comments which would lead to the improvement of this Annual Report would be appreciated. We have never gotten any suggestions for improving this report and therefore we suspect that no one reads this page.

GENERAL TABLE OF CONTENTS

Page Number

CITRUS FRUITS ONLY (Oranges, Grapefruit and Tangerines)

Acreage, Yield, Boxes per Tree and Grove Value 1942-43 to 1948-49 7
Volume, Value and Disposition of Citrus 1948-49 Season 8- 9
Shipments, Volume and Valuations for 22 Years 26-33
Auction Prices in 10 Markets, 1931-32 to 1948-49 34-36
Tree to Auction Costs or Vice Versa for 3 Years 37
F.O.B. Prices, 1909-10 to 1948-49 Season 38
Inspection of Citrus for Shipment by Counties 39
Persian Limes Certified for Shipment for 1948-49 39
Analysis of Citrus Prices from 1932-33 to 1948-49 Season 40-41
Prices Paid by Canners, Volume Processed 1940-41 to 1948-49 42
U.S. Citrus Production and Utilization 1947-48 Season 43
Truck Distribution by States 1947-48 and 1948-49 Seasons 44
Rail Distribution by States 1947-48 and 1948-49 Seasons 45

VEGETABLES AND MISCELLANEOUS FRUITS ONLY

F.O.B. Values by Commodities for 16 Seasons 5
Truck Shipments by Weeks 1948-49 Season 24-25
Acreage, Yield and Value, Fall, Winter, and Spring 1948-49 Season 64-65
Acreage of Principal Truck Crops 24 Seasons 66-67
Acreage, Yield and Value by Seasons 1930-31 to 1948-49 68-72
Acreage, Fall, Winter and Spring by Counties 82-90

ALL FRUITS AND VEGETABLES

Production and Value for 15 Seasons 4
Disposition All Fruits and Vegetables for 1948-49 Season 10-11
Freight, Express, Boat and Truck Shipments 1948-49 12-15
Freight, Express, Boat and Truck Shipments for 10 Seasons 16-19
Freight Shipments by Counties 1948-49 Season 20-23
County Acreage-All Fruits and Vegetables, 3 Seasons 73-81
Avocado and Lime Production for 1929-49 91
Citrus Passings Through Road Guard Stations 91
Unloads of Rail and Truck in New York, Philadelphia and Chicago 1948-49 Season 92
Federal-State Inspections and Car Loadings 94

GENERAL AGRICULTURAL STATISTICS

Florida Agricultural Volume and Value 1948-49 Season 6
Tobacco - Flue Cured, Sun Cured and Shade 1932-1949 46-47
Peanuts - Prices by Months 1920-48 48
General Farm Crops - Volume and Value 1920-1949 49-51
Poultry and Egg Prices -- Jacksonville, Tampa and Miami 52-55
Livestock Prices, Jacksonville (Southeastern Prices) 56-57
Livestock Plants, Markets, Numbers, Value, etc. 58-63
Poultry and Egg Production Facts and County Rankings 93

INTRODUCTORY

By Neill Rhodes, Commissioner, Florida State Marketing Bureau

The Annual Fruit and Vegetable Report for the 1948-49 Season in the main is devoted to the volume and value of products grown by farmers engaged in major agricultural lines of endeavor in Florida. The statistical data included will be expressed in terms of hundreds, thousands and millions. The Florida farmer by and large is successful over the spread of years. He is skilled in his profession, for he must know production from A to Z, he must outmaneuver the weather, conquer crop pests and diseases, and time his planting and harvesting schedule to come within the fall, winter and spring seasons. He must know how, when and where to grow and sell the perishable food products in which he specializes. He must know crops and markets.

The Florida agricultural industry, in its growth and development since the eighteenth century, has become a giant. My hat is off and my bow is low to those who have made all this progress possible. Reading of thousands and hundreds of thousands, millions and hundreds of millions, some might get the impression that Florida agricultural millionaires are common. Such is not the case; no honest, well informed person would make such claim and no truthful person would attempt to substantiate it.

Perhaps such an array of statistics as contained in our Annual Report for the 1948-49 Season should be flavored with a sprinkle of data as to how much the farmer spends, what it costs him to grow these winter crops. There is a big difference in the gross and the net receipts of the largest operations. According to December 1948 release of the Florida Crop and Livestock Reporting Service, U.S.D.A. Orlando, Florida, for the 1947-48 Season, the total crop cost, growing and harvesting of snap beans in five selected areas in Florida ranged from $121.31 to $267.93 per acre. Cabbage, five areas, from $187.17 to $465.34 per acre. Celery, five areas, from $957.57 to $1521.44 per acre. Cucumbers, six selected areas, from $128.17 to $810.86 per acre. Eggplant, four areas, from $251.11 to $802.35 per acre. Peppers, six areas, from $204.56 to $632.93 per acre. Irish potatoes, five areas, from $184.31 to $433.72 per acre. Tomatoes, three areas, from $371.30 to $1002.41 per acre.

Millions of dollars are expended also in the production of Florida crops before millions are spent by the consumer for them. The Florida farmers spend annually approximately $8,750,000 for seeds, $12,000,000 for insecticides and fungicides, $20,000,000 for livestock, dairy, poultry, et cetera feeds, and perhaps $40,000,000 for fertilizers. Verily, Florida farming is big business. True perspective is impossible unless both expenditures and receipts are given consideration.

And the farmer has to live. He does not produce all of his food. Clothing and other necessities of life are bought by the farmer, like every one else in non-agricultural work. Many statistics are devoted to showing the average prices received by farmers for what they sell. Perhaps the tabulation below, giving average prices PAID by farmers for commodities, will better illustrate that there is much capital outgoing before any receipts are incoming. (Source: Crops and Markets 1949 Edition, U.S.D.A.) I have endeavored to so arrange the information that many interesting conclusions can be drawn. One, for instance, that while Florida products may bring very high prices, there are numerous instances where farmers in many other States paid lower average prices for the commodities shown, and several too where average prices in practically all other States were lower than were those paid by Florida farmers for the commodity specified.

(See next two pages)

AVERAGE PRICES PAID BY FARMERS FOR COMMODITIES DEC. 15. 1948 (or as noted).

Commodity	Prices paid by Florida Farmers	The number of other States where prices paid by farmers were in comparison with Florida: Lower	The Same	Higher
Feeds				
All mixed dairy feed, per 100 lbs.	$ 4.25	42	2	3
Laying mash, per 100 lbs.	5.20	47	0	0
Scratch grains, per 100 lbs.	4.45	38	3	6
Grain Products				
Flour, 25-lb. sacks	2.15	38	4	5
Bread, white, per lb.	16.1¢	46	1	0
Corn meal, per lb.	8.5¢	24	1	22
Rolled oats, packaged, per lb.	15¢	37	0	10
Rice, packaged, per lb.	18.3¢	4	2	41
Soda crackers, packaged, per lb. (Sept. 15)	28¢	46	0	1
Corn flakes, packaged, per lb. (June 15)	29¢	46	0	1
Macaroni, packaged, per lb. (Sept. 15)	26¢	46	0	1
Meats				
Round steak, per lb.	74¢	7	0	40
Pork loin, per lb.	61¢	40	1	6
Pork chops, per lb.	64¢	26	1	20
Bacon, sliced, per lb.	72¢	23	7	17
Ham, not sliced, per lb.	69¢	29	4	14
Chuck roast, per lb. (Sept. 15)	61¢	6	7	34
Hamburger, per lb. (Sept. 15)	56¢	6	6	35
Eggs, Milk, Lard, Etc.				
Eggs, per dozen	75¢	36	1	10
Milk, fluid, per quart	24.3¢	46	0	1
Cheese, American, per lb.	60¢	24	6	17
Butter, per lb.	80¢	45	0	2
Lard, per lb.	31¢	40	3	4
Vegetable shortening, per lb.	36¢	8	1	38
Margarine, per lb.	41¢	23	10	14
Fruits				
Apples, per lb.	14.2¢	42	1	4
Bananas, per lb.	13.4¢	0	0	47
Oranges, per dozen	19.4¢	0	0	47
Grapefruit, each	4¢	0	0	47
Lemons, per doz. (Sept. 15)	37¢	1	0	46
Raisins, packaged, per lb.	17.8¢	21	1	25
Prunes, dried, per lb. (Sept. 15)	24¢	39	6	2
Peaches, canned, per lb.	18¢	4	5	38
Pineapples, canned, per lb.	29¢	22	10	15
Vegetables				
Potatoes, per 10-lb. bag	49¢	31	2	14
Dried beans, per lb.	20.4¢	47	0	0
Tomatoes, fresh, per lb. (Sept. 15)	18.3¢	46	0	1
Tomatoes, canned, per lb.	13.4¢	5	2	40
Cabbage, per lb. (Sept. 15)	7¢	42	1	4
Onions, per lb. (Sept. 15)	9.8¢	45	2	0
Lettuce, per lb. (Sept. 15)	15.6¢	36	2	9
Peas, canned, per lb.	15.7¢	31	2	14
Corn, canned, per lb.	16.4¢	27	1	19
String beans, canned, per lb. (Mar. 15)	14.6¢	15	1	31
Sugar, Coffee, Etc.				
Salt, per lb.	6¢	34	4	9
Vinegar, cider, per gal. (Sept. 15)	76¢	47	0	0
Salad dressing, per lb. (Sept. 15)	41¢	30	3	14
Coffee, per lb.	55¢	23	10	24
Tea, per lb.	$1.25	26	7	14
Cocoa, per lb. (Sept. 15)	42¢	23	7	17
Sugar, per 10-lb bag	94¢	5	3	39
Table syrup, per lb.	12.6¢	24	1	22
Candy, per lb.	38¢	38	0	9
Prepared dessert, per lb. (Sept. 15)	41¢	27	9	11
Tobacco and Miscellaneous				
Baking soda, per lb. (Mar. 15)	11.9¢	47	0	0
Baking powder, per lb. (Mar. 15)	19¢	22	3	22
Peanut butter, per lb. jar (Sept. 15)	41¢	32	7	8
Cigarettes, per pkg of 20 (Sept. 15)	21.2¢	42	2	3
Smoking tobacco, per lb.	$1.00	6	8	33

AVERAGE PRICES PAID BY FARMERS FOR COMMODITIES DEC. 15, 1948 (or as noted)

Commodity	Prices paid by Florida Farmers	The number of other States where prices paid by farmers were in comparison with Florida: Lower	The Same	Higher
Men's clothing				
Overalls, each	$ 3.30	33	7	7
Work shirts, cotton, each	$ 2.10	33	6	8
Suits, wool, 1 pair pants, each	$41.00	11	2	34
Extra trousers, woolen, pair	$11.50	25	8	14
Trousers, cotton fabric, pair (Sept.15)	$ 3.60	21	3	23
Sweaters, wool, each	6.00	27	5	15
Winter overcoats, each	39.50	35	3	9
Leather jackets, each	16.50	0	0	47
Wool jackets, each	8.00	1	0	46
Work gloves, canvas, pair	38¢	24	7	16
Work shoes, canvas, pair	5.20	0	0	47
Boots, rubber, knee, pair	5.10	9	4	34
Undershirts or shorts, garment (Sept.15)	75¢	23	6	18
Heavy winter union suits, cotton, each	1.95	0	1	46
Pajamas, broadcloth, cotton, pair (June 15)	4.10	25	5	17
Dress shoes, pair	7.90	14	1	32
Overshoes, rubber, pair	2.05	0	2	45
Hats, straw, work, each (June 15)	73¢	26	0	21
Hats, felt, each	6.00	14	2	31
Shirts, broadcloth, each	3.15	17	0	30
Boys' clothing				
Overalls, pair (Sept. 15)	2.35	45	0	2
Shoes or Oxfords, pair	4.30	6	2	39
Undershirts or shorts, garment (June 15)	60¢	30	11	6
Union suits, heavy, cotton, each	1.50	0	4	43
Women's clothing				
Stepins, rayon, each	72¢	11	4	32
Hose, nylon, pair	1.50	15	10	22
Hose, cotton, pair	44¢	5	1	41
House dresses, percale, each	3.45	27	2	18
Shoes or Oxfords, pair	5.10	11	5	31
Girls' clothing				
Dresses, cotton, 6-12 yrs, each (Sept. 15)	2.70	19	5	23
Shoes or Oxfords, school, pair	3.85	0	1	46
Children's clothing				
Socks, per pair	33¢	14	6	27
Shoes or Oxfords, pair (Sept. 15)	3.30	0	0	47
- - - - - - - - - -				
Sheets, medium quality, 81x99", each	2.90	18	11	18
Bath towels, 20-40", each	58¢	3	2	42
Percale, 36" wide, yard (Sept. 15)	63¢	46	1	0
Muslin, 36" wide, unbleached, yard (Sept.15)	38¢	21	0	26
Toilet soap, per cake	10.9¢	23	5	14
Laundry soap, per bar	10.1¢	13	4	25
House brooms, each (Sept. 15)	1.20	13	8	26
Fruit jars, 1-qt, per doz. (Sept. 15)	1.05	42	4	1
House paint, per gal.	5.50	28	5	14
Nails, per lb.	12.4¢	21	2	24
Axes, with handles, each	3.40	26	4	17
Gasoline, regular, per gal.	27¢	28	8	11
Kerosene, per gal.	18.3¢	15	0	32
Motor oil, per gal.	1.20	11	7	29
Auto tires, 6.00x16, each	16.50	11	25	11
Inner tubes, 6.00-x16, each	3.10	8	16	23
Storage batteries, 15-plate	19.50	7	9	31

May the above in some measure tend to clear the atmosphere, to provide sharper focus of the general picture as you note the figures of hundreds of thousands of units grossing hundreds of millions of dollars, factually and so ably presented by our Market News Specialist.

------ Neill Rhodes,
Commissioner
Florida State Marketing Bureau

FLORIDA DEPARTMENT OF AGRICULTURE
STATE MARKETING BUREAU
1948-49
ANNUAL FRUIT AND VEGETABLE REPORT

By Frank H. Scruggs, Market News Specialist

VOLUME AND VALUE OF ALL FRUITS AND VEGETABLES

Our 1948-49 season was noteworthy for many reasons, including the fairly early start of volume vegetable shipments due to favorable weather conditions, the heavy planting for the late winter and spring with relatively good weather conditions, the heavy shipments for that period, the record heavy production, and near record total value for the season, the record volume of citrus, the reasonably good weather for citrus quality, and the good prices after January for same, the heavy volume of oranges used for concentrates, the threefold increase in table corn production, the increase in transportation costs, the great increase in the total volume of fruits and vegetables moved by truck, and last but not least, the effects on our citrus prices of the extreme freeze loss in Texas and the severe loss in California which saved the 1948-49 season for Florida citrus with great expectations for the 1949-50 season. We made it long.

RECORD VOLUME AND HIGH TOTAL VALUE

The 1948-49 fruit and vegetable season was a humdinger but so far no song has yet been written about it. Florida produced 323,481 carloads, with a grand total gross value of $308,719,000. The volume was 37,054 carloads more than the previous record of 286,427 in the 1945-46 season. Our total value for 1948-49 has been exceeded, once in the 1944-45 war year with a total gross of $309,586,000, and again in 1945-46 with $364,330,000. The growers like to break value records but they don't wish to go to war to do it.

The 1943-49 citrus volume was 219,517 carloads, or 92,900,000 boxes, with a gross value of $182,188,000, compared to 214,045 carloads, or 91,100,000 boxes, with a gross value of $114,925,000 the previous season. The golden record was in the 1945-46 season when we received $236,231,000 for 86,000,000 boxes amounting to 197,050 carloads.

The vegetable production of 87,454 carloads exceed the prior record season of 1945-46 when we had 76,943 carloads sell at $116,239,000. Our total volume in the 1948-49 season was $115,856,000, a mere $383,000 less. We could easily add $4.40 per carload and make up this difference, but Florida can wait for another season to break that record.

Florida did not do so badly on watermelons, strawberries, avocados, limes, mangoes, cantaloupes and minor fruits. We produced and used 16,510 carloads as compared to the 1945-46 season when we had a volume of 12,434 carloads with a gross F.O.B. sales value of $11,860,000. Our value for this group in 1948-49 was $10,675,000.

The more you look at the records the more the 1945-46 season pops up, but Florida the coming 1949-50 season might finish all the records of that year which were not wiped out in the 1948-49 season. Regardless of how you look at it the 1948-49 season broke all peace-time records for total volume and value, not only for citrus but also for vegetables, and also for miscellaneous fruits. It was like a revolving door; anyway you looked it was good all around.

The season brought on an urgent demand for changes in the citrus laws aimed to eliminate poor fruit going out of Florida. The laws were passed by the Legislature in the spring of 1949 against some strong objections of some shippers and some growers. A large number of growers, other factors in the citrus business, and the general public in Florida were in favor of changes being made.

The 1948-49 season was generally favorable to citrus as attested by the 92,900,000-box crop. That is a record estimate even though we have had one or two years when a heavier crop was in prospect but was cut short by hurricane or freeze losses.

Strawberry and watermelon volume was about average with weather not too bad for either.

The storms of September 22 and October 5 in South Florida did some damage to citrus, mostly grapefruit on the Lower East Coast.

We benefited greatly from the freezes in the California citrus belt, which were the most severe January 3, 4, and 5, and the freezes in the Texas citrus belt during late January, mostly on January 29, 30, and 31. The citrus spirit in Florida changed suddenly from one of deep gloom to one of bright cheeriness. It was not because California and Texas together lost millions of boxes of oranges and grapefruit in their freezes sharply cutting supplies, but rather the fact that the impending yolk of disaster had been moved from our necks. Saved by the grace of the weather, we are now fighting over the prospective profits for this year, whereas we were fighting over the prospective lossesin the fall of 1948. C'tampas figit -- I mean tempus fugit.

WEATHER DURING THE 1948-49 SEASON

Our vegetable planting and shipping season extends from August 1 to July 31, and encompasses the time of the planting of the first seed beds in August to the planting of the fields a few weeks later which continues into May, with shipments generally beginning in October and ending in July.

When we think of vegetables we must think first of South Florida, and when we think of South Florida we must think about weather, as they seem to get more of it.

The 1948 fall acreage was considerably greater than in 1947 and the 10-year average. The weather was generally favorable after the storm of September 22, when most of the planted acreage was lost. There was little damage from the storm of October 5 which passed over the southeastern part of Florida. This was followed by ideal growing weather. The unusually warm weather in the Lake Section caused early maturity, with supplies in excess of demand and some abandoned acreage of beans during November and December. The yields and quality were excellent. The freeze of January 1-2 severely damaged the crops which should have been moved January 15 to February 15. The weather in most of South Florida during the spring was considered good, and so it was in all of Florida.

Beans are in the tender classification and are among the first to feel the effects of weather in any form. Other more important vegetables in South Florida are tomatoes, potatoes, cucumbers, peppers, table corn, celery, squash and cabbage. Beans in Palm Beach County alone accounted for 52,300 acres of a State total of 223,150 acres for all officially reported vegetables. Palm Beach County had 74,335 acres of vegetables in 1948-49 season out of a total of 223,150 acres for the entire State. So when you speak of beans and Palm Beach County you are talking about a pair of Kings.

All in all the weather must have been favorable to vegetables as we shipped the largest volume in the history of Florida. We break records almost each succeeding year.

TRANSPORTATION AND DISTRIBUTION

Amazing is the word to describe the phenomenal increase in the shipments by truck to out-of-State markets. The railroads did not do so badly as they hauled more than they ever did except during the war years and immediately following when truckers were handicapped with war restrictions on new trucks, gasoline and manpower, and in getting started again in 1946 and 1947. Just before the war truck shipments had gradually increased to 41,712 and after the war interval got up to 46,155, then wham up to 80,914 carloads in the 1948-49 season just recently concluded. The figures below are revealing with comparisons as follows:

	Carlot Equivalent				
Season	Freight	Express	Boat	Truck	Total
1940-41	78,043	1,732	19,357	41,712	140,844
1941-42	96,787	1,965	1,828	37,539	138,119
1942-43	113,179	3,675	-	19,208	136,062
1943-44	131,252	4,559	-	19,926	155,737
1944-45	119,076	4,279	-	17,161	140,516
1945-46	128,745	4,645	88	25,604	159,082
1946-47	107,178	4,578	4,839	32,007	148,602
1947-48	99,603	3,748	5	46,155	149,511
1948-49	102,146	3,935	35	80,914	187,030

It need not be pointed out that the Florida fruit and vegetable rail and truck shipment volume is steadily increasing and that we shipped 46,191 carloads more in the 1948-49 season than we did in the 1940-41 season and that the trucks got 39,202 carloads, or 85 per cent of this increase.

The writer in previous Annual Reports forecast the return to a heavy and growing truck movement after the war but he never expected 80,914 carloads. It is said by some that the truck rates and rail rates were about the same for long hauls the past season. This may or may not be true but there are said to be other factors in choosing between rail and trucks. Some shippers use rail for one city or purpose and trucks for another city or purpose. We had these rates submitted to us by a large citrus shipper covering rail shipments from Florida:

Boxes	Boston	N.Y,Phila,Balto.	Chi.	Cleveland	Detroit	Pitts.	St.Louis	Cincy.	All
Oranges	$1.20	$1.06	$1.24	$1.26	$1.28	$1.25	$1.19	$1.10	$1.13
Grapefruit	1.19	1.04	1.08	1.13	1.14	1.13	1.07	.98	1.06
Tangerines	1.20	1.08	1.20	1.22	1.24	1.22	1.20	1.06	1.12

The transportation agencies seem to be well equipped to handle all the requirements of Florida shippers and are trying to improve their service each year. Our fruits and vegetables got a wider distribution than in any season prior to the 1948-49 season. We got 20 carloads by truck and 84 rail cars of citrus into California the past season after the swimming pools in Los Angeles froze for the winter.

Sometimes when you think about the phenomenal increase in truck shipments to 80,914 carloads you wonder if this was an apparition which will fade with time or if it is something stable which will grow in size.

GETTING THE RIGHT PERSPECTIVE

Sometimes the writer hears the most amazing things about the ranking or importance of the Florida agricultural commodities or classifications among themselves or among the various States, and when he dares to suggest that the facts are otherwise he is confronted with individuals so sure of their information that he slinks off and takes another look at the Annual Reports he has written for twenty years. Right now he is looking at the 1948-49 book and finds the following facts and rankings:

	Year 1948 or Season 1948-49		Florida Gross Sales
1. Oranges	137,890 carloads	58,300,000 boxes	$127,744,000
2. Grapefruit	71,171 "	30,200,000 "	41,550,000
3. Dairy Cattle	148,000 head Products	600,000,000 lbs.	37,500,000
4. Tomatoes	16,482 carloads	6,975,000 bu.	32,666,000
5. Beef Cattle & Calves	1,265,000 head		31,055,000
6. Poultry	32,000,000 lbs, $13,300,000;	Eggs 19,000,000 doz. $11,700,000	25,000 000
7. Hogs & Pigs	640,000 head		24,687,000
8. Tobacco		20,846,000 lbs.	17,016,000
9. Beans	12,143 carloads	7,235,000 bu.	16,884,000
10. Celery	12,570 carloads	5,337,000 crts.	16,021,000
11. Tangerines	10,456 carloads	4,400,000 boxes	12,894,000
12. Potatoes	9,950 carloads	5,362,000 bu.	12,316,000
13. Field Corn		6,910,000 bu.	12,092,000
14. Gladioli	(Unofficial estimate)		9,500,000
15. Sugar	1,044,000 tons,	Syrup & Molasses 7,980,000 gals.	9,205,000

None of the other items for which we have records had a 1948-49 gross value of less than $8,000,000.

Fruits and vegetables valued at $308,719,000 account for approximately 60 per cent of all agricultural income in Florida, which totaled $504,951,000, excluding the $225,000,000 value of lumber, naval stores, fish and products and minerals sold in Florida last year.

The rankings of citrus States are indicated as follows for 1947-48 season:
Florida 95,570,000; California 61,430,000; Texas 28,400,000; others 4,080,000 boxes.

FLORIDA RANKING IN LIVESTOCK AMONG ALL STATES BY HEAD

Beef 13th. All Cattle 24th. Dairying 36th. Hogs 25th. Sheep 39th.

The following are the heaviest fruit and vegetable producing Counties in Florida: Polk, Palm Beach, Orange, Lake, Hillsboro, Dade, Broward, Seminole, Marion, Volusia, Pinellas, Brevard, Putnam, Manatee, Highlands, Hardee, I.River, Alachua. Many of Florida Counties have a lot of livestock, poultry, general or specialty crops to add to their agricultural production.

FLORIDA PRODUCTION AND VALUE FOR 15 SEASONS

(Includes Canned and Locally Consumed)

ALL CITRUS

Season	Carloads Production	Boxes	Florida Gross Value	Gross	Weighted Average All Production & Marketing	Net*
1934-35	82,865	32,835,854	$42,797,752	$1.33	$1.06	$ .27
1935-36	74,491	29,462,052	53,189,191	1.81	1.12	.69
1936-37	102,827	40,601,208	68,838,758	1.70	1.09	.61
1937-38	103,964	40,939,629	53,285,352	1.30	1.08	.22
1938-39	143,369	56,447,995	58,646,931	1.04	.97	.07
1939-40	109,119	42,973,112	50,365,127	1.17	1.05	.12
1940-41	140,903	55,890,754	64,192,695	1.15	.99	.16
1941-42	120,089	48,400,000	80,572,620	1.65	1.09	.57
1942-43	154,909	68,700,446	153,052,989	2.23	1.12	1.11
1943-44	181,592	80,800,000	199,688,696	2.47	1.31	1.16
1944-45	156,759	69,000,000	201,912,530	2.93	1.31	1.62
1945-46	197,050	86,000,000	236,230,700	2.75	1.29	1.46
1946-47	190,730	83,100,000	146,565,580	1.76	1.32	.44
1947-48	214,045	91,100,000	114,925,000	1.26	1.16	.10
1948-49	219,517	92,900,000	182,188,000	1.96	1.33	.63

	ALL VEGETABLES USED		ALL VEGETABLES & MISCL. FRUITS	
Season	Carloads Production	Florida Gross Value	Carloads Production	Florida Gross Value
1934-35	48,411	$30,134,054	57,306	$33,936,126
1935-36	45,718	30,666,719	52,670	34,144,707
1936-37	51,835	34,445,922	60,118	39,090,756
1937-38	70,000	37,306,680	82,130	41,410,710
1938-39	68,506	38,489,172	77,606	43,573,732
1939-40	65,151	37,962,385	75,404	42,738,720
1940-41	58,560	43,077,816	68,486	48,562,482
1941-42	70,191	57,417,670	80,219	62,706,220
1942-43	63,221	81,823,200	69,445	87,555,990
1943-44	70,219	87,328,394	79,605	94,944,402
1944-45	69,225	99,441,550	81,213	107,673,150
1945-46	76,943	116,239,000	89,377	128,099,000
1946-47	58,049	91,618,000	72,262	102,144,000
1947-48	68,670	89,237,000	83,939	99,817,000
1948-49	87,454	115,856,000	103,964	126,531,000

ALL FRUITS AND VEGETABLES USED

Season	Carloads Production	Florida Gross Value
1934-35	140,171	$ 77,156,615
1935-36	127,181	76,733,879
1936-37	162,945	107,929,514
1937-38	186,094	94,696,062
1938-39	220,975	102,220,663
1939-40	184,563	93,103,847
1940-41	209,389	112,768,552
1941-42	200,308	143,278,840
1942-43	224,554	240,608,979
1943-44	261,197	294,633,098
1944-45	237,912	309,585,680
1945-46	286,427	364,329,700
1946-47	262,992	246,709,580
1947-48	297,984	214,742,000
1948-49	323,481	308,719,000

* Net before deducting for taxes, interest on investment and depreciation if any.

FLORIDA FOB PACKED VALUE OF SELECTED VEGETABLES AND NON-CITRUS FRUITS FOR 16 SEASONS

Season	Beans	Limas	Cabbage	Carrots	Cauliflower
1933-34	$ 5,773,000	$ 236,000	$ 665,000	$	$
1934-35	5,967,000	270,000	1,630,000		
1935-36	6,250,000	202,000	612,000		
1936-37	7,031,000	390,000	456,000		
1937-38	6,272,000	507,000	978,000		
1938-39	7,041,000	720,000	990,000		
1939-40	7,480,000	420,000	2,061,000	Not	Not
1940-41	8,615,000	616,000	2,334,000		
1941-42	11,412,000	704,000	1,602,000	previously	previously
1942-43	17,985,000	1,041,000	6,460,000		
1943-44	19,116,000	1,436,000	4,284,000	reported	reported
1944-45	18,405,000	1,779,000	3,259,000		
1945-46	18,359,000	1,533,000	5,571,000		
1946-47	16,389,000	1,187,000	3,069,000		
1947-48	14,484,000	1,065,000	6,500,000	270,000	176,000
1948-49	16,884,000	946,000	5,530,000	52,000	251,000

Season	Celery	Corn	Cucumbers	Eggplant	Escarole	All Lettuce
1933-34	$ 2,996,000	$	$ 345,000	$ 289,000	$ 267,000	245,000
1934-35	4,368,000		765,000	212,000	235,000	252,000
1935-36	4,488,000		928,000	264,000	207,000	165,000
1936-37	4,532,000		1,101,000	322,000	305,000	170,000
1937-38	3,289,000		1,053,000	356,000	294,000	149,000
1938-39	5,375,000		1,391,000	514,000	264,000	270,000
1939-40	5,869,000	Not	1,928,000	417,000	394,000	612,000
1940-41	8,065,000		1,858,000	373,000	364,000	463,750
1941-42	7,154,000	previously	2,124,000	620,000	324,000	461,000
1942-43	17,158,000		2,592,000	1,294,000	1,142,000	1,240,000
1943-44	16,236,000	reported	2,079,000	1,501,000	645,000	562,000
1944-45	18,553,000		3,637,000	1,814,000	1,352,000	634,000
1945-46	14,260,000		5,277,000	1,805,000	875,000	1,232,220
1946-47	17,535,000		4,984,000	1,758,000	1,183,000	552,000
1947-48	9,778,000	1,320,000	6,203,000	1,151,000	1,165,000	440,000
1948-49	16,021,000	1,536,000	5,557,000	1,456,000	1,680,000	563,000

Season	English Peas	Peppers	Potatoes	Squash	Tomatoes	Total Value Vegetables
1933-34	$ 507,000	$1,676,000	$3,708,000	$	$8,475,000	$25,744,000
1934-35	520,000	1,277,000	2,503,000		6,035,000	24,827,000
1935-36	508,000	1,273,000	3,187,000		8,224,000	25,332,000
1936-37	418,000	1,905,000	5,076,000		7,566,000	29,438,000
1937-38	642,000	1,668,000	2,939,000		8,711,000	26,768,000
1938-39	648,000	2,771,000	3,644,000		13,323,000	35,951,000
1939-40	520,000	2,121,000	3,725,000	Not	9,216,000	33,862,000
1940-41	409,500	2,537,000	2,799,000		8,618,000	37,018,250
1941-42	434,000	2,838,000	6,018,000	previously	13,458,000	47,187,000
1942-43	254,000	5,917,000	5,914,000		11,793,000	72,896,000
1943-44	450,000	5,460,000	7,431,000	reported	20,734,000	79,934,000
1944-45	284,000	6,623,000	12,033,000		20,376,000	89,449,000
1945-46	339,000	6,545,000	11,714,000		22,405,000	90,098,000
1946-47	189,000	2,086,000	5,475,000		19,098,000	76,512,000
1947-48	92,000	5,806,000	10,073,000	1,839,000	22,936,000	83,378,000
1948-49	42,000	7,569,000	12,316,000	2,255,000	32,686,000	105,445,000

Season	Cantaloupes	Strawberries	Watermelons	Total Misc. Fruits	Grand Total Misc. Fruits & Vegetables
1933-34	$ 23,000	$2,646,000	$ 779,000	$3,448,000	$29,192,000
1934-35	18,000	2,236,000	726,000	2,980,000	27,817,000
1935-36	15,000	1,972,000	896,000	2,883,000	28,215,000
1936-37	28,000	2,746,000	1,310,000	4,084,000	33,522,000
1937-38	65,000	2,100,000	945,000	3,110,000	29,878,000
1938-39	44,000	3,175,000	976,000	4,195,000	40,146,000
1939-40	38,000	2,144,000	1,193,000	3,375,000	37,237,000
1940-41	37,500	2,194,000	1,445,850	3,677,350	40,695,600
1941-42	52,000	2,275,000	1,572,000	3,899,000	51,086,000
1942-43	84,500	1,498,000	2,641,000	4,223,500	77,119,500
1943-44	91,000	1,107,000	4,523,000	5,721,000	85,816,000
1944-45	120,000	1,541,000	4,918,000	6,579,000	96,028,000
1945-46	54,000	2,363,000	5,552,000	7,969,000	98,067,220
1946-47	102,000	3,737,000	5,419,000	9,258,000	85,770,000
1947-48	339,000	2,003,000	6,862,000	9,204,000	92,582,000
1948-49	192,000	2,401,000	6,372,000	8,965,000	114,410,000

Source: U.S. Agricultural Statistician, B.A.E., Orlando, Florida. Official estimates on carrots, cauliflower, corn and squash not available prior to 1947-48 season. Other vegetables and miscellaneous fruits probably accounted for 25,000 acres estimated at a gross F.O.B. Florida value of $10,000,000, but not included herein.

FLORIDA AGRICULTURAL VOLUME AND VALUE

ACREAGE IN FLORIDA (Estimated) 1948-49 Season.	TOTAL ACRES
Citrus Bearing 408,900 a.; Other Fruits and Berries 20,000 a.	428,000
Pecans 6,000 a.; Tung Nuts 1,200 a.	18,000
Vegetables - plats 1 acre or more, 247,850 planted. Used Acres	190,000
Total Acres Fruits, Berries, Nuts and Vegetables	636,000
General Crop, 1,500,000 a.; Other Farm Land Usage 6,500,000 a.	8,000,000
Pasture Land 11,000,000 a.; Woodland and Other Land 15,091,680 a.	26,091,680
Total Land Area of Florida	34,727,680

CITRUS PRODUCTION AND VALUE 1948-49 SEASON				FLORIDA FOB SALES
Oranges	Carloads 137,390	Units Used 58,300,000	boxes	$127,744,000
Grapefruit	71,171	30,200,000	"	41,550,000
Tangerines	10,456	4,400,000	"	12,894,000
Carloads 219,517; Boxes Produced 92,900,000; Used 92,900,000				$182,188,000

MISCELLANEOUS FRUITS PRODUCTION AND VALUE 1948-49 SEASON				
Watermelons	Carloads 14,634	Units Used 7,080,000	(2 melons)	$ 6,372,000
Strawberries	645	295,000	Fla. crts.	2,401,000
Others	1,231	584,000		1,902,000
Carloads 16,510; Units Produced 7,959,000; Used 7,959,000				$ 10,675,000

VEGETABLE PRODUCTION AND VALUE 1948-49 SEASON				
Beans	Carloads 12,143	Units Used 7,235,000	bu.	16,884,000
Celery	12,570	5,337,000	crts.	16,021,000
Potatoes	9,950	5,362,000	bu.	12,316,000
Tomatoes	16,482	6,975,000	bu.	32,666,000
Others	36,309	17,955,000		37,969,000
Carloads 87,454; Units Produced 45,545,000; Used 42,864,000				$115,856,000

ALL FRUIT AND VEGETABLE PRODUCTION AND VALUE 1948-49 SEASON	
Carloads 323,481; Units Produced 146,404,000; Used 143,723,000	$308,719,000

LIVESTOCK IN FLORIDA 1948	Head	Gross Value		FLORIDA GROSS SALES
Beef Cattle and Calves	1,265,000	$ 93,863,000	$	31,055,000
Dairy Cattle	148,000	14,060,000	**	35,000,000
Hogs and Pigs	640,000	14,976,000		24,687,000
Sheep and Lamb	14,000	98,000	***	52,000
Goats (estimate)	50,000	65,000		35,000
Total Livestock	2,117,000	$123,062,000	$	90,829,000

*Hides included in Sales; **Dairy Cattle Used for Beef included in Beef Sales.
***Wool included in Sales of Sheep and Lambs.

POULTRY, EGG AND DAIRY PRODUCTS PRODUCED IN FLORIDA IN 1948		FLORIDA SALES GROSS FOB VALUE
Poultry Produced	32,000,000 Nos.	$ 13,300,000
Eggs Produced	19,000,000 doz.	11,700,000
Dairy Products	600,000,000 lbs.	37,500,000
Total Poultry, Eggs and Dairy Products		$ 62,500,000

GENERAL FIELD CROPS 1948	Volume Produced	GROSS FARM VALUE
Corn	6,910,000 bu.	$ 12,092,000
Tobacco	20,846,000 lbs.	17,016,000
Peanuts	85,250,000 lbs.	7,736,000
Sugar-Raw	1,044,000 tons	6,421,000
Sugar-Cane Syrup	1,980,000 gals.	1,584,000
Black Strap Molasses	6,000,000 gals.	1,200,000
Sweet Potatoes	960,000 bu.	2,515,000
Cotton	15,000 bales	2,299,000
Other Field Crops	476,000 bu.	2,297,000
Hay	69,000 tons	1,138,000
Total Field Crop Group		$54,298,000

MISCELLANEOUS CROPS AND SPECIALTIES 1948		FLORIDA SALES GROSS VALUE
Flowers and Bulbs, Hot House and Field, Nursery Products, Specialty Crops under Glass, and Seeds (Gladiola $9,500,000)		$20,000,000
Pecans	5,475,000 lbs.	605,000
Honey and Miscellaneous (estimate) 1949.		3,000,000
Total Miscellaneous Crops and Specialties		$23,605,000

AGRICULTURAL GROUP SALES	
Citrus Fruits	$182,188,000
Miscellaneous Fruits and Melons	10,675,000
Vegetables	115,856,000
Total Fruits and Vegetables	$308,719,000
Livestock	90,829,000
Poultry, Eggs and Dairy Products	62,500,000
General Field Crops	54,298,000
Miscellaneous Crops and Specialties	23,605,000
Total Agricultural Group	$539,951,000

LUMBER AND NAVAL STORES-1948	
Also Wood Pulp, Poles, Piling, Fuel Wood, etc.	$145,000,000
FISH, SHELL FISH AND PRODUCTS-1948	
Food and Non-Food Fish and Shell Fish and Sponges, etc.	35,000,000
MINERAL PRODUCTION-1948	
Phosphate 32,921,000, Limestone 4,512,000, Other Products 7,567,000	45,000,000
	$225,000,000
GRAND TOTAL ABOVE GROUPS	$764,951,000

CITRUS ACREAGE, YIELD, BOXES PER TREE, AND GROVE VALUES

FLORIDA ORANGES Season	Bearing Acres	Total Production in 1-3/5Bu Box	Box Yield Per Acre (66 Trees)	Box Yield per Tree	Gross Return Box	Net Return Box	Abandoned Boxes	Net per Acre before Taxes & Depreciation	Income Value at 10%	Income Value at 13%
1942-43	246,340	37,200,000	151	2.3	$2.72	$1.45	-	$219.	$2190	$ 1685
1943-44	251,340	46,200,000	184	2.8	2.81	1.31	-	241	2410	1850
1944-45	256,340	42,800,000	167	2.5	3.17	1.73	-	289	2890	2223
1945-46	264,900	49,800,000	188	2.8	3.25	1.84	-	346	3460	2661
1946-47	270,000	53,700,000	199	3.0	1.93	.50	900,000	98	980	761
1947-48	280,500	58,400,000	208	3.2	1.41	.15	-	31	310	239
1948-49	289,900	58,300,000	201	3.1	2.79	.79	-	159	1590	1223
GRAPEFRUIT									at 10%	at 16%
1942-43	94,390	27,300,000	289	4.4	1.48	.67	-	$194	$1940	$1212
1943-44	95,100	31,000,000	326	4.9	1.83	.92	-	300	3000	1875
1944-45	90,000	22,300,000	248	3.8	2.24	1.36	-	337	3370	2106
1945-46	90,500	32,000,000	354	5.4	1.77	.78	-	276	2760	1725
1946-47	91,000	29,000,000	319	4.8	1.25	.26	2,600,000	75	750	470
1947-48	93,000	33,000,000	355	5.4	.82	- .01	3,700,000	- 3½	-	-
1948-49	95,000	30,200,000	318	4.8	1.38	.33	-	105	1050	656
TANGERINES									at 10%	at 15%
1942-43	23,419	4,200,000	179	2.7	2.72	.98	-	$175	$1750	$ 1167
1943-44	23,419	3,600,000	154	2.3	3.62	1.36	-	209	2090	1393
1944-45	23,419	4,000,000	171	2.6	4.18	1.91	150,000	315	3150	2100
1945-46	23,549	4,200,000	178	2.7	4.24	2.10	-	374	3740	2493
1946-47	23,705	4,700,000	198	3.0	2.99	.90	800,000	149	1490	993
1947-48	23,800	4,000,000	168	2.5	2.41	.20	600,000	29	290	193
1948-49	24,000	4,400,000	183	2.8	2.93	.74	-	135	1350	900
TOTAL CITRUS										
1942-43	364,149	68,700,000	189	2.9	2.23	1.11	-	$210	$2100	$ -
1943-44	369,949	80,800,000	218	3.3	2.47	1.16	-	253	2530	-
1944-45	369,759	69,100,000	187	2.8	2.93	1.62	150,000	303	3030	-
1945-46	378,949	86,000,000	227	3.4	2.75	1.46	-	331	3310	-
1946-47	384,705	87,400,000	227	3.4	1.76	.44	3,400,000	96	960	-
1947-48	397,300	95,400,000	240	3.6	1.26	.10	4,300,000	23	230	-
1948-49	408,900	92,900,000	227	3.4	1.96	.63	-	143	1430	-

We estimate that the 10% income as shown above on oranges will actually yield 7% and the 13% will actually yield around 10%. During 1945-46 and 1946-47 seasons when $317 was the average net return per acre, orange groves were selling around $2500 per acre showing 15% net return or around 10% after deducting taxes and depreciation. It is doubtful if a prudent investor would buy a grove risk with a near term expectation of less than 10% net above all costs. Prices of oranges in the 1949-50 season are expected to average higher.

Grapefruit prices are expected to average much higher due to the supply lost in the August 26-27 hurricane in Florida and the heavy freeze loss of grapefruit trees in Texas last January and terrific loss in production for the 1949-50season.

Tangerines should do better in sympathy with oranges and grapefruit.

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON-AUGUST 1, 1948-JULY 31, 1949

Carl'd Shipments	Freight Straight & Mixed	Carloads Total Freight	Carloads Express	Boxes Freight Boat, Truck and Express	Gross FOB Returns Florida Points Box	Gross FOB Returns Florida Points For Crop	Production and Marketing Costs Box	Production and Marketing Costs For Crop	Net Return to Florida Growers Box	Net Return to Florida Growers Rail, Truck, Boat
Oranges	26,685	30,717	2,505	28,589,257	$2.80	$80,049,920	$1.90	$54,319,588	$ .90	$25,730,332
Grapefruit	13,818	16,880	858	12,310,011	2.35	28,928,526	1.53	18,834,317	.82	10,094,209
Tangerines	2,924	3,955	69	2,907,856	3.70	10,759,067	2.53	7,356,876	1.17	3,402,191
Mxd.Citrus	8,125	Converted		Converted	--	--	-	-	--	-
Total	51,552	51,552	3,432	43,807,124	$2.74	$119,737,513	$1.84	$80,510,781	$ .90	$ 39,226,732

GENERAL DISPOSITION ANALYSIS OF THE FLORIDA CITRUS CROP FOR SEASON 1948-49

BOXES	StraightCars Freight	Mxd.Cars Freight	Mxd.Cars Express	Tot.Boxes Rail-Boat		Trucked Out	Rail, Boat & Truck	Processed Fresh, Exs.	Consumed Boxes	Total Crop Boxes	Export# Boxes
Oranges	13,385,451	2,059,286	1,002,140	16,446,857		12,142,400	28,589,257	26,851,546	[illegible]	58,300,000	192,582
Grapefruit	6,990,653	1,492,755	343,200	8,826,811		3,483,200	12,310,011	[illegible]	1,564,169	30,200,000	183,783
Tangerines	1,312,047	487,549	27,460	1,827,056		1,080,800	2,907,856	999,354	492,790	4,400,000	--
Total	21,688,336	4,039,588	1,372,800	27,100,724		16,706,400	43,807,124	44,156,820	4,936,156	92,900,000	376,365
CARLOADS				Total Rail	Boat						
Oranges	26,685	4,032	2,505	33222	35	30,356	63,613	67,129	7,148	137,890	481
Grapefruit	13,818	3,062	858	17738	-	8,708	26,446	40,765	3,960	71,171	459
Tangerines	2,924	1,031	69	4024	-	2,702	6,726	2,498	1,232	10,456	-
Total	43,427	8,125	3,432	54984	35	41,766	96,785	110,392	12,340	219,517	940

ESTIMATED COST OF PRODUCING AND MARKETING 43,807,124 BOXES OF ORANGES, GRAPEFRUIT, AND TANGERINES BY RAIL, TRUCK, BOAT.

Cost of production such as fertilizer, spray materials, irrigation, pruning, labor, fuel, etc., but not including interest or taxes on strictly grove acreage, per Standard 1-3/5 bushel boxes.

ORANGES $ .50	GRAPEFRUIT $ .35	TANGERINES $ .68	WEIGHTED AVERAGE $ .47

Cost of picking, hauling, packing, selling, and other average ordinary marketing charges.

ORANGES $1.40	GRAPEFRUIT $1.18	TANGERINES $1.85	WEIGHTED AVERAGE $1.37

Total ordinary and average cost of production and marketing of citrus

ORANGES $1.90	GRAPEFRUIT $1.53	TANGERINES $2.53	WEIGHTED AVERAGE $1.84

---

1. Estimated boxes per car: Straight Freight-Oranges 496.82, Grapefruit 499.22, Tangerines 438.37. Mixed Freight 497.18 Mixed Car Express 400 boxes. Export 400 boxes. Truck 400 boxes, per car.
2. Mixed Car Freight Analysis: Oranges 56.6, Grapefruit 33.9, Tangerines 9.5 per cent.
3. Mixed Car Express Analysis: Oranges 70.0, Grapefruit 25.0, Tangerines 2.0 per cent.
4. Ventilated Box Cars Used: Oranges 1713, Tangerines 10, Grapefruit 308, Mixed 527. Total 2558 cars.
5. Abandoned for Market Reasons: Oranges none, Grapefruit none, Tangerines none.
6. Interstate by-products: Oranges 39,000 boxes (97 carloads) shipped under special permit for out of State processing and included in our Processed Total.

# Exports include 106,071 boxes of oranges and 91,032 boxes of grapefruit. Exports from these out of State ports included in Rail and Truck Shipments, and included in Grand Total of 92,900,000 boxes. Some of these shipment and volume figures are subject to slight revision as of September 20th.

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON 1946-49 (Cont'd.)

TRUCK SHIPMENTS TO OUT-OF-STATE MARKETS (400 boxes to carload) AUGUST 1 - JULY 31

ORANGES:	Carlot equiv.	30,356 or 12,142,400 boxes.	Gross at $2.80	$ 33,998,720	Net* at $ .90	$10,928,160
GRAPEFRUIT:	Carlot equiv.	8,708 or 3,483,200 boxes.	Gross at 2.35	8,185,520	Net* at .82	2,856,224
TANGERINES:	Carlot equiv.	2,702 or 1,080,800 boxes.	Gross at 3.70	3,998,960	Net* at 1.17	1,264,536
ALL CITRUS:	Carlot equiv.	41,766 or 16,706,400 boxes.	Gross at $2.77	$ 46,183,200	Net* at $ .90	$15,048,920

FREIGHT, EXPRESS AND BOAT SHIPMENTS TO OUT-OF-STATE MARKETS, AUGUST 1 - JULY 31

ORANGES:	Carlot equiv.	33,257 or 16,446,857 boxes.	Gross at $2.80	$ 46,051,200	Net* at $ .90	$14,802,171
GRAPEFRUIT:	Carlot equiv.	17,738 or 8,826,811 boxes.	Gross at 2.35	20,743,006	Net* at .82	7,237,985
TANGERINES:	Carlot equiv.	4,024 or 1,827,056 boxes.	Gross at 3.70	6,760,107	Net* at 1.17	2,137,656
ALL CITRUS:	Carlot equiv.	55,019 or 27,100,724 boxes.	Gross at $2.71	$ 73,554,313	Net* at $ .89	$24,177,312

FRESH CITRUS USED FOR PROCESSING IN FLORIDA (400 boxes to carload) AUGUST 1 - JULY 31

ORANGES:	Carlot equiv.	67,129 or 26,851,646 boxes.	Gross at $1.51	$ 40,545,985	Net* at $ .66	$17,772,086
GRAPEFRUIT:	Carlot equiv.	40,765 or 16,305,830 boxes.	Gross at .57	9,294,317	Net* at -.08	-1,304,466
TANGERINES:	Carlot equiv.	2,498 or 999,354 boxes.	Gross at .46	459,703	Net* at -.67	- 669,567
ALL CITRUS:	Carlot equiv.	110,392 or 44,156,820 boxes.	Gross at $1.14	$ 50,300,005	Net* at $ .36	$15,798,053

FRESH CITRUS CONSUMED IN FLORIDA (400 boxes to carload) AUGUST 1 - JULY 31

ORANGES:	Carlot equiv.	7,148 or 2,859,097 boxes.	Gross at $2.50	$ 7,147,743	Net* at $ .72	$ 2,058,550
GRAPEFRUIT:	Carlot equiv.	3,960 or 1,584,169 boxes.	Gross at 2.10	3,326,755	Net* at .77	1,219,810
TANGERINES:	Carlot equiv.	1,232 or 492,790 boxes.	Gross at 3.40	1,675,486	Net* at 1.07	527,285
ALL CITRUS:	Carlot equiv.	12,340 or 4,936,056 boxes.	Gross at $2.46	$ 12,149,984	Net* at $ .78	$ 3,805,645

TOTAL RAIL, BOAT, TRUCK SHIPMENTS, PROCESSED AND LOCALLY CONSUMED CITRUS, AUGUST 1 - JULY 31

ORANGES:	Carlot equiv.	137,890 or 58,300,000 boxes.	Gross at $2.19	$127,743,648	Net* at $ .79	$45,510,967
GRAPEFRUIT:	Carlot equiv.	71,171 or 30,200,000 boxes.	Gross at 1.38	41,549,598	Net* at .35	10,609,355
TANGERINES:	Carlot equiv.	10,456 or 4,400,000 boxes.	Gross at 2.93	12,894,253	Net* at .74	3,259,910
ALL CITRUS:	Carlot equiv.	219,517 or 92,900,000 boxes.	Gross at $1.96	$182,187,502	Net* at $ .63	$58,780,430

NOTE: *Gross refers to returns FOB cars Florida shipping points, and net refers to returns to growers or fruit owners before deducting for interest and taxes, but after deducting for cost of production and marketing.

1: Trucked-out shipment figures were based on inspection certified for interstate movement. Road Guard Stations for checking were open October 15 - June 19. Aug. 1 - Oct. 14th and June 20 - July 31 estimated.

2: Cannery fruit represents average gross price at cannery door, and the net price is the gross less the estimated picking, hauling, and marketing charges.

3: Figures for Consumed in Florida are rough estimates based on population, prices, etc. Any person who does not approve this home consumption estimate may make his own estimate, but this volume, which is probably under estimated, cannot be ignored. This volume includes packed, unpacked, inspected and uninspected.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS BY PRODUCTION UNITS

1948-49 SEASON

COMMODITY	Units	Straight Freight	Mixed Freight	LCL Express	Trucked Out	Boat	Processed	Consumed	Total Production Units Used	Abandoned (not included)
Beans	Bu.	2,150,000	248,000	16,000	3,385,000	-	843,000	593,000	7,235,000	1,154,000
Limas	Bu.	80,000	22,000	2,000	175,000	-	-	40,000	319,000	-
Cabbage	50Lbs	(2,720,000)#	(120,000)	-	(1,760,000)	-	-	(360,000)	(4,960,000)	(1,200,000)
Cabbage	Ton	68,000	3,000	-	144,000	-	-	9,000	124,000	30,000
Celery	Crt.	3,980,000	103,000	4,000	938,000	-	-	312,000	5,337,000	181,000
Corn, Green	Crt.	672,000	71,000	-	721,000	-	-	216,000	1,680,000	-
Cucumbers	Bu.	400,000	60,000	2,000	1,154,000	-	38,000	100,000	1,754,000	46,000
Eggplant	Bu.	42,000	168,000	28,000	576,000	-	-	80,000	894,000	-
Escarole	Bu.	623,000	358,000	-	128,000	-	-	11,000	1,120,000	-
Lettuce, 4-6 doz.	W.Crt	31,000	9,000	3,000	57,000	-	-	88,000	188,000	-
Peppers	Bu.	832,000	396,000	56,000	1,492,000	-	-	196,000	2,972,000	-
Potatoes	Bu.	3,560,000	48,000	-	1,446,000	-	-	308,000	5,362,000	-
Squash	Bu.	112,000	67,000	10,000	494,000	-	-	134,000	817,000	-
Tomatoes	Bu.	2,781,000	61,000	6,000	3,039,000	-	675,000	413,000	6,975,000	-
Miscl. Vegetables	Bu.	166,000	753,000	45,000	1,037,000	-	50,000	1,200,000	3,251,000	100,000
Mixed Cars		Converted	Converted	Converted	-	-	-	-	-	-
TOTAL VEGETABLES	Units	18,149,000	2,484,000	172,000	16,402,000	-	1,606,000	4,051,000	42,864,000	2,681,000
Strawberries	36-pt.Crt.	53,000	-	2,000	186,000	-	8,000	46,000	295,000	-
Watermelons	Crts 2M	(4,199,000)#	-	-	(2,440,000)	-	-	(441,000)	(7,080,000)	-
Watermelons	Melons	8,398,000	-	-	4,880,000	-	-	882,000	14,160,000	-
Avocados	Bu.	6,000	-	20,000	60,000	-	-	24,000	110,000	-
Limes	1-3/5 bu.Box	12,000	-	43,000	102,000	-	18,000	65,000	240,000	-
Miscl. Fruits	Bu.	-	-	16,000	28,000	-	50,000	140,000	234,000	-
TOTAL MISCL. FRTS	Units	4,270,000	-	81,000	2,816,000	-	76,000	716,000	7,959,000	-
Oranges	Boxes	13,265,000	2,060,000	1,002,000	12,142,000	120,000	26,852,000	2,859,000	58,300,000	-
Grapefruit	Boxes	6,991,000	1,493,000	343,000	3,483,000	-	16,306,000	1,584,000	30,200,000	-
Tangerines	Boxes	1,312,000	487,000	28,000	1,081,000	-	999,000	493,000	4,400,000	-
Mixed Citrus		Converted	Converted	Converted	-	-	-	-	-	-
TOTAL CITRUS	Units	21,568,000	4,040,000	1,373,000	16,706,000	120,000	44,157,000	4,936,000	92,900,000	-
GRAND TOTAL	UNITS	43,987,000	6,524,000	1,626,000	35,924,000	120,000	45,839,000	9,703,000	143,723,000	2,681,000

NOTES: (Pages 10 and 11) There is considerable difficulty in working out a detailed disposition sheet for vegetables and miscellaneous fruits as comprehensive data is not as available as for citrus. It was advisable to try to use the U.S. Dept. of Agriculture estimate of total production and work back from there. We have the records on the truck shipments out of State which figures are used. We have the records on straight freight and boat for most of the individual commodities. We have only the totals for mixed freight and LCL express. The Florida consumption figures are only estimates. We had to apportion the mixed freight and mixed express totals as best we could to the various commodities with the handicap of trying to make all of the separate totals check with the total official crop estimate.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS IN CARLOTS, OR EQUIVALENT, AND VALUE

1948-49 SEASON

Commodity	Straight Freight Cars	Mixed Freight Cars	LCL Express Cars	Boat Cars	Trucked Out Cars	Total Shipped Cars	Processed	Florida Consumed Cars	Total Used Carlots	Abandoned (not included)##	Total FOB Gross Value
Beans	3,468	400	40	-	5,642	9,550	1,605	938	12,143	1,924	$ 16,884,000
Limas	160	45	5	-	350	560	-	80	640	-	946,000
Cabbage	5,457	240	-	-	3,543	9,240	-	720	9,960	2,400	5,530,000
Celery	9,345	90	10	-	2,345	11,790	-	780	12,570	425	16,021,000
Corn, Green	1,223	130	-	-	1,803	3,156	-	432	3,588	-	4,536,000
Cucumbers	1,052	150	5	-	2,564	3,771	85	222	4,078	102	5,558,000
Eggplant	70	280	70	-	1,153	1,573	-	160	1,733	-	1,456,000
Escarole	974	560	-	-	284	1,818	-	25	1,843	-	1,680,000
Lettuce	102	30	10	-	142	284	-	284	568	-	583,000
Peppers	1,364	650	140	-	2,983	5,137	-	392	5,529	-	7,569,000
Potatoes	6,593	90	-	-	2,697	9,330	-	570	9,950	-	12,316,000
Squash	250	150	25	-	1,098	1,523	-	300	1,823	-	2,255,000
Tomatoes	6,783	150	15	-	6,907	13,855	1,687	940	16,482	-	32,666,000
Miscl. Vegetables	352	1,507	113	-	2,075	4,047	100	2,400	6,547	200	7,856,000
Mixed Cars	Converted		Converted	-	-	-	-	-	-	-	-
TOTAL VEGETABLES	37,193	4,472	433	-	33,586	75,684	3,477	8,293	87,454	5,051	$ 115,856,000
Strawberries	110	-	5	-	410	525	18	102	645	-	2,401,000
Watermelons	8,864	-	-	-	4,888	13,752	-	882	14,634	-	6,372,000
Avocados	15	-	50	-	150	215	-	60	275	-	495,000
Limes	24	-	86	-	204	314	36	130	480	-	550,000
Miscl. Fruits	-	-	40	-	56	96	100	280	476	-	857,000
TOTAL MISCL. FRTS	9,013	-	181	-	5,708	14,902	154	1,454	16,510	-	$ 10,675,000
TOTAL VEGS. AND MISCL. FRUITS	46,206	4,472	614	-	39,294	90,586	3,631	9,747	103,964	5,051	$ 126,531,000
Oranges	26,685	4,032	2,505	35	30,356	63,613	67,129	7,148	137,890	-	127,744,000
Grapefruit	13,818	3,062	858	-	8,708	26,446	40,765	3,960	71,171	-	41,550,000
Tangerines	2,924	1,031	69	-	2,702	6,726	2,498	1,232	10,456	-	12,894,000
Mixed Citrus	Converted		Converted		-	-	-	-	-	-	-
TOTAL CITRUS	43,427	8,125	3,432	35	41,766	96,785	110,392	12,340	219,517	-	$ 182,188,000
GRAND TOTAL	89,633	12,597	4,046	35	81,060	187,371	114,023	22,087	323,481	5,051	$ 308,719,000

NOTES: (Pages 10 and 11). An additional problem was the disposition of the volume of radishes, cauliflower, carrots, spinach, broccoli, endive, etc., included in the miscellaneous figures for vegetables. Miscellaneous Fruits included mangoes, grapes, guavas, persimmons, blueberries, kumquats, etc. # Ordinarily units of different kinds are not added but if the 50-lb sack is used for cabbage instead of tons and the number of watermelons are divided by two to get crates, we find that all of the units are bushels or the near equivalent of bushels with the exception of citrus which are in 1-3/5 bu boxes. ## Abandoned because of market conditions and not included in the gross FOB Florida value. The gross includes the production, marketing costs, and packing costs if packed, and profit, if any.

FREIGHT CARLOT SHIPMENTS FROM FLORIDA BY COMMODITIES AND MONTHS, FOR 1948-49 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	56	10	1483	2431	3440	3736	3315	3489	3286	3583	1662	133	26,603
Grapefruit	8	868	1753	1102	987	1422	1815	2436	2005	1068	278	25	13,826
Tangerines			65	857	1013	617	56	197	86	16	6		2,923
Mixed Citrus		12	350	989	1331	1128	760	1385	1152	749	275	25	8,155
TOTAL CITRUS	64	890	3651	5379	6771	6903	5995	7507	6529	5416	2221	181	51,507
Strawberries					9	11	76	14					110
Watermelons									104	3614	5109	37	8,864
TOTAL MISCL. FRUITS					9	11	76	14	104	3614	5109	37	8,974
Beans (incl. Limas)			2	551	815	376	413	641	651	143	36		3,628
Cabbage				1	167	510	1446	2457	730	146			5,457
Cauliflower						15	29	6	2				52
Celery				56	398	1031	1904	1825	1815	1909	407		9,345
Corn, Green					1		3	42	536	436	325	8	1,325
Cucumbers			74	312	131	20	7	95	203	199	11		1,052
Eggplant				2	3			18	5	26	14	2	70
Escarole				57	154	121	173	205	151	113			974
Lettuce & Romaine				5	38	30	13	16					102
Peppers				17	20	58	394	219	283	305	67	1	1,364
Potatoes						175	688	1752	3605	373		2	6,593
Tomatoes				318	923	298	607	1571	2202	861	3		6,783
Other Vegetables				1	33	19	27	27	2	1	24	16	150
Mixed Car Vegetables		2	21	131	452	553	942	1054	845	408	64		4,472
TOTAL VEGETABLES		2	97	1451	3135	3206	6549	10028	10880	4937	951	29	41,265
NON-CITRUS & VEGS.		2	97	1451	3144	3217	6625	10042	10984	8551	6060	66	50,239
ALL FRUITS & VEGS.	64	892	3748	6830	9915	10120	12620	17549	17513	13967	8281	247	101,746

PICK-UP-EXPRESS SHIPMENTS FROM FLORIDA STATIONS FOR 1948-49 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Mixed Citrus	8			86	1410	394	474	381	324	257	78		3,412
Mixed Vegetables	8			35	62	50	60	61	63	64	30		433
TOTAL FRUITS & VEGS.	16			121	1472	444	534	442	387	321	108		3,845

NOTE: A revised report too late to use here shows freight; Oranges 26,685, Grapefruit 13,813, Tangerines 2,924, Mixed Citrus 8,125, LCL Express 3,432 for a total 54,984 as compared to a total of 54,919 on this page, a difference of 65 cars. The revised report is used on pages 8-9.

RAIL - FREIGHT & EXPRESS CARLOT SHIPMENTS, FOR 1948-49 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	56	10	1483	2431	3440	3736	3315	3469	3285	3583	1662	133	26,603
Grapefruit	8	338	1755	1102	937	1422	1845	2456	2006	1068	236	25	13,826
Tangerines			65	857	1013	617	66	197	86	16	6		2,923
Mixed Citrus	8	12	350	1075	2741	1522	1243	1766	1476	1006	343	25	11,567
TOTAL CITRUS	72	890	3651	5465	8181	7297	6469	7888	6853	5673	2290	181	54,919
Strawberries					9	11	76	14					110
Watermelons									104	3614	5109	37	8,864
TOTAL MISCL. FRUITS					9	11	76	14	104	3614	5109	37	8,974
Beans(incl.Limas)			2	551	815	375	413	641	651	143	36		3,628
Beets							7	21					28
Cabbage				1	167	510	1449	2457	730	143			5,457
Carrots						2			1	1			4
Cauliflower						15	29	6	2				52
Celery				56	398	1031	1804	1925	1815	1909	407		9,345
Corn, Green					1		3	42	388	456	325	8	1,223
Cucumbers			74	312	131	20	7	95	203	199	11		1,052
Eggplant				2	3			18	5	26	14	2	70
Escarole				57	154	121	173	205	151	113			974
Greens(except Spinach)				1	15	10	20	6					52
Lettuce & Romaine				5	38	30	13	16					102
Peppers				17	20	58	594	219	283	305	67	1	1,364
Potatoes						175	688	1752	3603	373		2	6,593
Spinach					18	7							25
Sweet Potatoes									1		24	16	41
Tomatoes				318	923	298	607	1571	2202	861	3		6,783
Mixed Car Vegetables	8	2	21	166	514	603	1002	1115	908	472	94		4,905
TOTAL VEGETABLES	8	2	97	1486	3197	3256	6609	10089	10943	5001	981	29	41,698
NON-CITRUS & VEGS.	8	2	97	1486	3206	3267	6685	10103	11047	8615	6090	66	50,672
ALL FRUITS & VEGS.	80	892	3748	6951	11387	10564	13154	17991	17900	14288	8389	247	105,591

BOAT SHIPMENTS (Carlot Equivalent FROM FLORIDA PORTS (Does not include initial rail haul exports).

Oranges - 35 carloads of 400 boxes in November. No Vegetables by Boat.

NOTE: English Peas - No Rail Shipments reported for 1948-49 Season.

FLORIDA INTERSTATE TRUCK SHIPMENT PASSINGS 1948-49 SEASON

Actual Check at Nine Road Guard Stations October 15 - June 19
Estimated for August 1-October 14 and June 20-July 31 Periods

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	48	78	1900	2907	4150	4105	4277	4945	4093	2803	1000	50	30,356
Grapefruit	28	520	1000	631	506	882	1275	1678	1306	666	190	26	8,708
Tangerines			78	817	1082	541	58	67	43	12	4		2,702
TOTAL CITRUS	76	598	2978	4355	5738	5528	5610	5690	5442	3481	1194	76	41,766
Avocados	15	25	18	30	9	1cl	1cl	1cl	1cl	1cl	1cl	1cl	97
Limes	15	14	3	3	2	2	1cl	2	2	6	12	50	111
Strawberries				1cl	40	84	133	130	19	4			410
Watermelons									48	1598	3142	100	4,888
Other Non-Citrus Frts	2	1							2	19	29	3	56
TOTAL MISCL. FRUITS	32	40	21	33	51	86	133	132	71	1627	3183	153	5,562
Beans, Snap			23	634	867	674	845	1222	1073	303	1		5,642
Limas & Butterbeans				1	11	33	26	51	87	219	72	3	503
Cabbage				2	134	720	986	1136	444	121	1cl		3,543
Celery				15	120	352	549	516	372	345	76		2,345
Corn, Green			1cl	1cl	4	1	1	82	576	790	339	10	1,803
Cucumbers			97	324	325	176	160	504	492	484	2		2,564
Eggplant	2	1cl	13	48	75	114	141	246	192	183	129	10	1,153
Escarole				4	27	39	70	78	37	23	6		284
Field Peas	4	2	6	12	11	3	3	9	158	439	76	5	728
Lettuce & Romaine				2	9	39	41	38	12	1			142
Okra	25	3	13	17	7	6	4	6	20	79	55	17	252
Peas, English				1	3	2	4	3	3	1cl			16
Peppers	2	1cl	1cl	18	83	403	549	540	575	515	278	20	2,983
Potatoes				1cl	11	91	221	515	1501	357	1		2,697
Squash	1cl	1cl		28	63	123	112	157	283	233	92	7	1cl	1,098
Tomatoes				314	549	439	735	1481	2046	1272	71		6,907
Bunched Vegetables			1cl	3	4	18	16	10	4	1			56
Other Vegetables			1	7	73	165	246	239	99	32	8		870
TOTAL VEGETABLES	33	5	181	1465	2436	3387	4754	6959	7924	5256	1121	65	35,586
VEGS. & MISCL.FRUITS	65	45	202	1498	2487	3473	4887	7091	7995	6883	4304	218	39,148
ALL FRUITS & VEGS.	141	643	3180	5853	8225	9001	10497	13781	13437	10364	5498	294	80,914

CARLOT SHIPMENTS (FREIGHT, EXPRESS, BOAT & TRUCK) FRUITS AND VEGETABLES BY MONTHS FOR SEASON 1948-49

August 1-July 31 (Truck October 15-June 15 except where estimated)

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	104	88	3383	5373	7590	7841	7592	8414	7378	6386	2662	183	56,994
Grapefruit	36	1388	2753	1733	1493	2304	3120	4134	3312	1734	478	49	22,534
Tangerines			143	1674	2095	1158	124	264	129	28	10		5,625
Mixed Citrus	8	12	350	1075	2741	1522	1243	1766	1476	1006	343	25	11,567
TOTAL CITRUS	148	1488	6629	9855	13919	12825	13079	14578	12295	9154	3493	257	96,720
Avocados	15	25	18	30	9	1cl	1cl	1cl	1cl	1cl	1cl		97
Limes	15	14	3	3	2	2	1cl	2	2	6	12	50	111
Strawberries				1cl	49	95	209	144	19	4			520
Watermelons									152	5212	8251	137	13,752
Other Non-Citrus	2	1							2	19	29	3	56
TOTAL MISCL.FRUITS	32	40	21	33	60	97	209	146	175	5241	8292	190	14,536
Beans(incl.Limas)			25	1186	1693	1083	1284	1914	1811	665	108	3	9,773
Cabbage				3	301	1230	2435	3593	1174	264	1cl		9,000
Cauliflower						15	29	6	2				52
Celery				71	518	1383	2353	2441	2187	2254	483		11,690
Corn, Green			1cl	1cl	5	1	4	124	964	1246	664	18	3,026
Cucumbers			171	636	456	196	167	599	695	683	13		3,616
Eggplant	2	1cl	13	50	78	114	141	264	197	209	143	12	1,223
Escarole				61	181	160	243	283	188	136	6		1,258
Lettuce & Romaine				7	47	69	54	54	12	1			244
Peas, English				1	3	2	4	3	3	1cl			16
Peppers	2	1cl	1cl	35	103	461	943	759	858	820	345	21	4,347
Potatoes				1cl	11	266	909	2267	5104	730	1	2	9,290
Tomatoes			1cl	632	1472	737	1342	3052	4248	2133	74		13,690
Other Vegetables	29	5	48	103	251	323	453	574	516	644	170	38	3,154
Mixed Car Vegetables	8	2	21	166	514	603	1002	1115	908	472	94		4,905
TOTAL VEGETABLES	41	7	278	2951	5633	6643	11363	17048	18867	10257	2102	94	75,284
VEGS. & MISCL.FRUITS	73	47	299	2984	5693	6740	11572	17194	19042	15498	10394	234	89,820
ALL FRUITS & VEGS.	221	1535	6928	12839	19612	19565	23651	31772	31337	24652	13887	541	186,540

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS

(These figures have been revised and rearranged and may not agree or seem to agree with some previous tabulations. The totals are substantially the same.)

Commodity	Freight Shipments 1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49
Oranges	24,812	27,084	34,374	43,390	51,405	41,049	41,848	45,390	33,524	26,603
Grapefruit	6,832	12,135	12,650	12,258	13,441	8,534	12,201	12,606	11,801	13,826
Tangerines	1,896	2,171	1,865	5,017	3,856	4,370	3,813	2,974	2,884	2,923
Mixed Citrus	7,249	6,770	10,062	13,162	13,626	11,102	13,573	9,599	6,667	8,155
Total Citrus	40,789	48,160	58,951	73,827	82,326	65,055	71,435	68,569	54,876	51,507
Strawberries	43	4	-	6	22	43	25	99	56	110
Watermelons	4,977	5,028	5,565	3,363	6,116	8,366	7,470	7,963	9,247	8,864
Miscellaneous Fruits	-	2	-	-	16	15	3	9	-	-
Total Non-Citrus	5,020	5,034	5,565	3,369	6,154	8,424	7,498	8,071	9,305	8,974
Beans & Limas	2,910	2,700	3,335	5,943	6,596	4,682	4,538	3,668	3,148	3,628
Cabbage	4,238	2,256	3,568	4,534	6,378	5,157	4,763	2,459	4,934	5,457
Celery	7,769	8,689	9,119	8,557	9,549	11,037	12,489	8,747	8,966	9,345
Corn, Green	22	2	7	17	18	42	104	166	338	1,223
Cucumbers	1,153	981	1,161	461	405	988	1,549	1,138	1,500	1,052
Eggplant	-	36	29	175	246	304	251	81	182	70
Escarole	882	573	818	1,003	1,120	1,347	1,317	827	1,039	974
Lettuce	371	235	147	197	207	152	166	116	90	102
Peas, English	270	80	130	115	153	83	62	14	16	None
Peppers	516	647	863	1,352	1,805	1,622	1,612	744	1,499	1,364
Potatoes	5,116	3,306	5,540	4,756	5,282	7,066	9,591	4,001	4,807	6,593
Tomatoes	5,222	3,679	5,035	4,367	4,592	5,305	5,269	3,249	3,782	6,783
Squash (estimated)	275	275	300	400	400	500	400	400*	500*	400*
Other Variety Vegetables	25	36	86	133	364	426	484	224	181	202**
Mixed Car Vegetables	1,427	1,354	2,113	3,973	5,855	6,884	7,217	4,704	4,442	4,472***
Total Vegetables	30,196	24,849	32,271	35,983	42,770	45,597	49,812	30,538	35,424	41,665
Total Vegs. & Non-Citrus	35,216	29,883	37,836	39,352	48,924	54,021	57,310	38,609	44,727	50,639
ALL FRUITS & VEGETABLES	76,005	78,043	96,787	113,179	131,252	119,076	128,745	107,178	99,603	102,146

NOTE: * Includes an estimated 400 straight cars of Squash not officially reported. Radish straight car shipments estimated at 100 cars.

** Other Vegetables include carloads as follows: Beets 28, Carrots 4, Cauliflower 52, Greens 52, Spinach 25, Sweet Potatoes 41. Total 202 carloads.

*** Mixed Vegetables included eggplant, peppers, escarole, squash, and all other vegetables shipped in mixed cars.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

Commodity	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49
	Express Shipments									
EXPRESS										
Mixed Citrus	972	1,169	1,177	2,571	3,100	3,041	3,376	3,630	3,115	3,412
Strawberries	180	47	58	55	1	-	-	-	-	-
Miscellaneous Fruits	75*	75*	125*	175*	175*	90*	90*	100*	100*	90*
Total Non-Citrus	255	122	183	230	176	90	90	100	100	90*
Beans & Limas	76	45	-	-	-	-	-	-	-	-
Tomatoes	-	-	-	-	-	-	-	-	-	-
Mixed Car Vegetables	388	396	605	1,074	1,283	1,148	1,179	848	533	433
Total Vegetables	464	441	605	1,074	1,283	1,118	1,179	848	533	433
Total Vegs. & Non-Citrus	719	563	788	1,304	1,459	1,148	1,179	948	633	523*
ALL FRUITS & VEGETABLES	1,691	1,732	1,965	3,875	4,559	4,273	4,645	4,578	3.748	3,935*
BOAT					Boat Shipments					
Oranges	8,997	11,169	1,185				76	2,908	-	35
Grapefruit	3,812	5,481	512				12	1,437	-	-
Tangerines	735	1,063	117				-	222	-	-
Mixed Citrus	5	10	3	No record of any			-	-	-	-
Total Citrus	13,549	17,743	1,817				88	4,567	-	35
Strawberries	-	-	-	boat shipments			-	-	-	-
Watermelons	16	-	-				-	-	-	-
Miscellaneous Fruits	10	5	-	during (War Period)			-	-	-	-
Total Non-Citrus	26	5	-				-	-	-	-
Beans & Limas	211	154	1	1942-43 thru			-	-	-	-
Cabbage	21	14	-				-	-	-	-
Celery	117	148	-	1944-45 seasons.			-	100	-	-
Corn, Green	-	-	-				-	3	-	-
Cucumbers	32	40	-				-	3	-	-
Eggplant	11	35	-				-	-	-	-
Escarole	1	-	-				-	-	-	-
Lettuce	-	-	-				-	-	-	-
Peas, English	-	1	-				-	-	-	-
Peppers	241	163	6				-	-	-	-
Potatoes	1,176	898	-				-	164	-	-
Tomatoes	34	13	-				-	-	-	-
Squash	60	40	1				-	-	-	-
Other Variety Vegetables	171	103	3				-	2	5	-
Total Vegetables	2,095	1,609	11				-	272	5	-
Total Vegs. & Non-Citrus	2,121	1,614	11				-	272	5	-
ALL FRUITS & VEGETABLES	15,670	19,357	1,828				88	4,839	5	35

Note: * Miscl.Fruits by L.C.L. Exp. estimated at 90 carloads, including, Avocados 30, Limes 50, Mangoes & Misc.Frts 10 cars.

FLORIDA - SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

Commodity	Trucked Out Shipments									
	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49
Oranges	11,148	14,315	10,248	6,790	5,388	3,641	5,135	8,774	14,268	30,356
Grapefruit	2,546	3,899	2,605	1,532	889	513	851	1,395	2,858	8,708
Tangerines	1,105	1,087	837	1,000	957	819	960	1,096	1,670	2,702
Total Citrus	14,799	19,301	13,690	9,322	7,234	4,973	6,946	11,265	18,796	41,766
Strawberries	1,228	1,073	660	300	164	265	446	615	321	410
Watermelons	838	976	635	190	630	654	2,538	3,278	3,503	1,888
Avocados	307	150	145	60	142	527	42	72	81	37
Limes	70	150	90	20	18	100	63	44	31	111
Miscellaneous Fruits	48	41	17	30	32	25	77	65	38	56
Total Non-Citrus	2,562	2,370	1,805	600	986	1,369	3,166	4,074	3,974	5,562
Beans	4,635	5,149	6,126	2,300	2,405	2,123	2,832	3,219	4,172	5,642
Limas	585	350	500	100	93	134	257	220	543	503
Cabbage	4,959	2,298	3,539	1,900	2,116	1,440	2,063	3,003	3,983	3,545
Celery	1,260	1,681	1,582	360	401	405	566	1,020	1,381	2,345
Corn, Green	399	219	200	150	190	121	392	479	662	1,803
Cucumbers	1,269	1,196	866	265	250	444	741	896	1,999	2,564
Eggplant	301	586	734	300	525	380	682	756	754	1,153
Escarole	257	203	116	15	7	25	20	145	200	284
Lettuce	204	232	150	26	54	51	93	90	103	142
Peas, English	268	221	222	20	77	53	52	26	18	16
Peppers	936	1,445	1,656	900	865	809	1,524	1,586	1,987	2,983
Potatoes	1,289	1,068	1,116	500	426	872	759	701	1,278	2,697
Tomatoes	3,635	3,983	3,904	1,700	3,190	2,826	3,549	2,526	3,826	6,907
Squash	761	560	538	300	440	447	653	645	815	1,098
Butterbeans	59	58	50	20	41	46	142	94	145	*
Field Peas	204	215	200	110	220	288	553	658	804	728
Okra	79	83	63	25	59	76	155	111	186	252
Bunched Vegetables	120	66	70	30	114	45	59	50	110	56
Miscellaneous Vegetables	331	437	422	265	247	225	340	434	619	870
Total Vegetables	21,351	20,041	22,044	9,286	11,706	10,819	15,492	16,668	23,385	33,586
Total Vegs. & Non-Cit.	23,913	22,411	23,849	9,886	12,692	12,188	18,658	20,742	27,359	39,148
ALL FRUITS & VEGS.	38,712	41,712	37,539	19,208	19,926	17,161	25,604	32,007	46,155	80,914

Note: * Included with Limas.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

Commodity	Total Freight, Express, Boat and Truck Shipments from Florida									
	1939-40	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49
Oranges	41,957	52,588	45,775	50,130	56,793	44,690	57,059	55,072	47,802	56,994
Grapefruit	13,190	21,515	15,769	13,750	14,330	9,047	13,064	15,438	14,659	22,534
Tangerines	5,736	4,321	2,849	6,017	4,813	5,187	4,773	4,292	4,554	5,675
Mixed Citrus (Rail)	9,226	7,949	11,242	15,533	16,726	14,145	16,949	13,229	9,782	11,567
Total Citrus	70,109	86,373	75,635	85,520	92,662	73,069	91,845	88,031	76,797	96,770
Strawberries	1,451	1,124	918	301	137	306	471	714	377	520
Watermelons	5,831	6,004	6,260	3,613	6,784	9,020	10,006	11,241	12,750	13,752
Avocados (Truck & Exp.)	357	190	205	150	257	382	77	127	141	127
Limes (Truck & Express)	83	160	145	95	80	130	103	79	63	161
(*)Miscl.Fruits(Exp. & Trk.)	55	48	25	40	42	30	60	84	46	66
Total Miscl. Fruits	7,782	7,526	7,553	4,199	7,300	9,868	10,719	12,245	13,377	14,626
Beans & Limas	8,217	6,384	9,862	8,343	9,100	6,939	7,667	7,116	7,663	9,775
(a)Butterbeans (Truck)	59	58	50	20	41	46	142	94	145	**
Cabbage	9,218	4,568	7,107	6,434	8,404	6,606	6,848	5,462	8,917	9,300
Celery	9,146	10,518	10,701	8,917	9,750	11,442	13,055	9,867	10,347	11,690
Corn, Green	421	221	207	167	208	163	496	648	1,000	3,026
Cucumbers	2,454	2,217	2,017	726	655	1,432	2,290	2,037	3,495	3,616
Eggplant	312	657	733	475	771	684	955	837	959	1,263
Escarole	1,140	776	934	1,018	1,127	1,372	1,337	972	1,239	1,258
Lettuce	575	467	297	223	261	203	259	206	195	244
Peas, English	538	302	352	135	230	136	114	40	34	16
Peppers	1,693	2,255	2,585	2,252	2,670	2,431	3,136	2,330	3,486	4,347
Potatoes	7,561	5,272	6,656	5,266	5,708	7,940	10,350	4,866	6,065	9,250
Tomatoes	8,891	7,680	9,029	6,067	7,782	8,131	8,818	5,775	7,608	13,390
Squash	1,116	875	839	700	840	947	1,053	1,045	1,315	1,498
(a)Field Peas (Truck)	204	215	200	110	220	288	553	658	804	728
(a)Okra (Truck)	79	83	63	25	39	76	155	111	186	252
(a)Bunched Vegetables(Truck)	120	66	70	30	114	45	59	50	110	56
(a)Other Vegetables (Truck)	331	437	422	265	247	225	340	434	619	870
(b)Oth.Vegs. (Freight & Boat)	196	139	89	133	364	426	484	226	185	202
(c)Mixed Vegs(Freight & Exp.)	1,815	1,750	2,718	5,047	7,138	6,032	8,396	5,552	4,975	4,905
Total Vegetables	54,106	46,940	54,931	46,353	55,759	57,564	66,483	48,326	59,347	75,684
Tot. Vegs. & Miscl.Fr.	61,888	54,466	62,484	50,552	63,059	67,432	77,232	60,571	72,724	90,310
ALL FRUITS & VEGETABLES	131,997	140,839	138,119	136,072	155,721	140,501	159,077	148,602	149,511	187,030

(*)Includes estimates for Express Shipments of avocados, limes, mangoes, etc. ** Included with beans & limas.
(a)Truck Shipments only, with small volume included in Miscellaneous or Mixed Cars.
(b)Freight and Boat only. (c) Freight and Express only. Estimated 100 straight cars Radishes not reported or included.

RAIL FREIGHT SHIPMENTS BY COUNTIES
1948-49 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Oranges	Grapefruit	Tangerines	Mixed Citrus	Total Citrus	Beans & Limas	Beets	Cabbage
Alachua	84	2	3	8	97	141		50
Bradford						7		
Brevard	1019	496	2	426	1943			
Broward	13				13	1039		
Citrus	22			9	31			
Clay								77
Collier								
Columbia								26
Dade						38		52
De Soto	298	26	43	110	477			
Dixie								
Duval	1024	199	164	177	1564			
Escambia								
Flagler								159
Gilchrist								
Glades								138
Hamilton								24
Hardee	49	9	23	2	83			
Hendry								327
Hernando	124	42	103	64	333			
Highlands	1510	765	69	221	2565	2		
Hillsborough	993	305	30	510	1838	1		78
Indian River	375	1632	3	560	2570			
Jackson								
Jefferson								
Lafayette								
Lake	2548	609	278	857	4292	8		28
Lee	27	25		10	62			
Leon								
Levy								
Madison								
Manatee	63	196		44	303			139
Marion	1307	131	15	101	1554	62		32
Martin								
Okeechobee								
Orange	6210	916	1012	971	9109	14	28	240
Osceola	64	41	2	12	119			
Pallm Beach	1	5		13	19	2253		1293
Pasco	230	139	32	84	485			
Pinellas	328	1720	49	414	2511			
Polk	7868	4935	803	2659	16265			36
Putnam	116		53	34	203			234
St. Johns								1740
St. Lucie	1160	1353	16	489	3018	1		13
Sarasota								18
Seminole	797	241	159	258	1455	12		508
Sumter						46		
Suwannee								
Taylor								
Union						3		26
Volusia	373	39	64	122	598			219
Walton								
Washington								
Unknown								
Straight Cars	26603	13826	2923	8155	51507	3628	28	5457
Boat	35				35			
Pick-Up-Express				3412	3412			
GRAND TOTAL	26638	13826	2923	11567	54954	3628	28	5457

RAIL FREIGHT SHIPMENTS BY COUNTIES
1948-49 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Carrots	Cauli-flower	Celery	Green Corn	Cucumbers	Eggplant	Escarole
Alachua			160		91	3	
Bradford							
Brevard							
Broward					24	13	
Citrus							
Clay							
Collier					85		
Columbia				25	3		
Dade		2		24	4		
De Soto							
Dixie							
Duval							
Escambia							
Flagler							
Gilchrist							
Glades				56			
Hamilton							
Hardee					164		
Hendry							
Hernando							
Highlands							
Hillsborough		37		4	129	5	3
Indian River					1		
Jackson					20		
Jefferson							
Lafayette							
Lake			976			2	2
Lee				81	139	1	
Leon							
Levy							
Madison							
Manatee		1		2	102	6	56
Marion			133		12		
Martin					29		
Okeechobee							
Orange	2		567	391	70		240
Osceola							
Palm Beach	1		2323	496		29	494
Pasco							
Pinellas							
Polk							
Putnam					1		
St. Johns		1					
St. Lucie	1	7			39		
Sarasota			1487	16	35		22
Seminole		4	3699	120	2	11	157
Sumter					70		
Suwannee					13		
Taylor							
Union				7	5		
Volusia							
Walton					7		
Washington							
Unknown					7		
Straight Cars	4	52	9345	1223	1052	70	974
Boat							
Pick-Up-Express							
GRAND TOTAL	4	52	9345	1223	1052	70	974

RAIL FREIGHT SHIPMENTS BY COUNTIES
1948-49 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Greens	Lettuce & Romaine	Peppers	Potatoes	Spinach	Sweet Potatoes	Tomatoes
Alachua		3	70	62	11	7	
Bradford							
Brevard							
Broward	7		750				669
Citrus							
Clay							
Collier							307
Columbia						1	
Dade			1	2511			1815
De Soto							
Dixie							
Duval			1				
Escambia				15			
Flagler				627			
Gilchrist							
Glades							
Hamilton							
Hardee			1				73
Hendry		18					
Hernando							
Highlands							
Hillsborough		4	289	8			682
Indian River							284
Jackson							
Jefferson							
Lafayette							
Lake					4		
Lee			20	355		1	19
Leon							
Levy							
Madison							
Manatee		17					1032
Marion		6	4			32	58
Martin			1				25
Okeechobee							478
Orange	8	4	52		10		
Osceola							
Palm Beach	5	7	56	218			30
Pasco							
Polk							
Putnam				401			
St. Johns				2396			
St. Lucie	32		2				1311
Sarasota							
Seminole		41	40				
Sumter		2	59				
Suwannee							
Taylor							
Union							
Volusia			18				
Walton							
Washington							
Pinellas							
Unknown							
Straight Cars	52	102	1364	6593	25	41	6783
Boat							
Pick-Up-Express							
GRAND TOTAL	52	102	1364	6593	25	41	6783

RAIL FREIGHT SHIPMENTS BY COUNTIES
1948-49 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Mixed Veg's	Total Vegetables	Strawberries	Watermelons	Total Non-Citrus	Total Veg's & Non-Citrus	GRAND TOTAL
Alachua	56	655		830	830	1485	1582
Bradford	1	8		15	15	23	23
Brevard							1943
Broward	1748	4250				4250	4263
Citrus				54	54	54	85
Clay	1	78				78	78
Collier	3	395		29	29	424	424
Columbia		55		52	52	107	107
Dade	27	4474				4474	4474
De Soto				23	23	23	500
Dixie				25	25	25	25
Duval		1				1	1565
Escambia		15				15	15
Flagler		786				786	786
Gilchrist				1415	1415	1415	1415
Glades	1	195				195	195
Hamilton		24		52	52	76	76
Hardee	6	244	5	4	9	253	336
Hendry	4	349				349	349
Hernando				19	19	19	352
Highlands		2				2	2567
Hillsborough	214	1454	97	213	310	1764	3602
Indian River		285		11	11	296	2866
Jackson		20		83	83	103	103
Jefferson				495	495	495	495
Lafayette				128	128	128	128
Lake	14	1034		1260	1260	2294	6586
Lee	65	681		11	11	692	754
Leon				5	5	5	5
Levy				467	467	467	467
Madison				351	351	351	351
Manatee	29	1384		18	18	1402	1705
Marion	171	510		1157	1157	1667	3221
Martin	89	145				145	145
Okeechobee		478				478	478
Orange	237	1863		46	46	1909	11018
Osceola							119
Palm Beach	1372	8577				8577	8596
Pasco				312	312	312	797
Pinellas							2511
Polk		36	8	105	113	149	16414
Putnam		636		78	78	714	917
St. Johns	8	4145		2	2	4147	4147
St. Lucie	11	1417		16	16	1433	4451
Sarasota	85	1663				1663	1663
Seminole	274	4868				4868	6323
Sumter	56	233		629	629	862	862
Suwannee		13		849	849	862	862
Taylor				9	9	9	9
Union		41		30	30	71	71
Volusia		237		61	61	298	896
Walton		7				7	7
Washington				10	10	10	10
Unknown		7				7	7
Straight Cars	4472	41265	110	8864	8974	50239	101746
Boat							35
Pick-Up-Express	433	433				433	3845
GRAND TOTAL	4905	41698	110	8864	8974	50672	105626

As of September 1, 1949. Subject to Revision.

TRUCK SHIPMENTS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS
BY WEEKS FOR 1948-49 SEASON
(Rail Carload Equivalent)
Oct. 15, 1948-June 19, 1949

Date by Weeks	Beans	Limas-Butter Beans	Cab-bage	Cel-ery	Cukes	Gr. Corn	Egg-plant	Esca-role	Eng. Peas	F. Peas	Let-tuce	Pep-pers	Pota-toes
Aug. 1-31*							2			4		2	
Sept.1-30*							LCL			2		LCL	
Oct. 1-14							-			-		-	
Oct. 15-16	LCL				LCL	LCL	-			LCL		-	
Oct. 17-23	4				27		4			3			
Oct. 24-30	15				53		6			3			
Oct. 31-Nov.6	43	LCL			76		7			3		LCL	
Nov. 7-13	87	LCL			82		10	LCL		4	1	1	
Nov. 14-20	218	LCL	LCL	5	82		16	1	LCL	3	LCL	7	LCL
Nov. 21-27	216	LCL	LCL	7	68		14	2	1	2	1	8	LCL
Nov. 28-Dec.4	228	LCL	3	10	75		15	1	1	1	4	9	1
Dec. 5-11	244	LCL	7	21	86	1	14	9	1	4	3	14	2
Dec. 12-18	207	2	18	32	94	1	18	5	LCL	3	1	16	2
Dec. 19-25	163	4	27	26	65	2	16	5	1	2	1	21	2
Dec. 26-Jan.1	114	4	107	45	42	1	20	9	LCL	2	2	36	6
Jan. 2-8	118	7	130	43	28	LCL	16	2	LCL	1	2	32	20
Jan. 9-15	142	10	167	111	35	LCL	21	19	1	1	11	65	31
Jan. 16-22	132	7	163	75	46		31	3	LCL	1	11	112	19
Jan. 23-29	216	6	189	91	47	LCL	28	12	LCL	LCL	12	141	14
Jan. 30-Feb.5	188	4	198	119	44	LCL	38	19	1	LCL	11	134	26
Feb. 6-12	206	10	266	164	58	LCL	36	15	1	1	13	156	47
Feb. 13-19	191	6	239	127	39	LCL	30	7	1	1	6	145	59
Feb. 20-26	247	7	274	143	26	LCL	39	28	2	LCL	10	127	76
Feb. 27-Mar.5	346	14	318	132	44	2	67	21	1	1	12	149	105
Mar. 6-12	271	6	269	135	63	3	56	28	LCL	1	8	104	95
Mar. 13-19	241	11	220	117	105	8	55	16	1	1	7	101	95
Mar. 20-26	253	15	246	80	154	26	49	9	LCL	2	10	113	119
Mar. 27-Apr.2	238	11	193	93	196	67	53	8	1	5	6	157	195
Apr. 3-9	192	13	129	85	117	103	47	5	LCL	13	5	140	279
Apr. 10-16	291	20	110	94	107	135	40	14	1	28	3	151	405
Apr. 17-23	286	24	76	89	109	143	40	6	1	48	LCL	138	394
Apr. 24-30	244	28	74	82	109	173	45	10	1	67	3	96	348
May 1-7	186	38	61	87	138	175	43	12	LCL	79	1	125	232
May 8-14	73	44	28	89	177	181	49	4	LCL	115		148	93
May 15-21	30	52	22	85	116	217	47	7		113		136	28
May 22-28	12	69	10	69	50	173	35	LCL		103		81	4
May 29-June 4	3	45	1	46	2	152	34	4		61		80	1
June 5-11		29		38	1	136	46	2		29		78	
June 12-18		9		7	1	57	31			8		88	
June 19		1		LCL	LCL	9	7			1		8	
June 20-30*		5			1	30	20			6		50	
July 1-31*		3				10	10			5		20	
Total by Weeks	5645	504	3545	2347	2563	1805	1155	283	16	727	144	2989	2698
Total by Months	5642	503	3543	2345	2564	1803	1153	284	16	728	142	2983	2697
Oct.15-June19	5645	496	3545	2347	2562	1765	1123	283	16	710	144	2917	2698

*Estimated. (1) Passings converted into carload equivalent on basis of: Beans 600 bu; Cabbage 25,000 lbs; Celery 400 crts; Cukes 450 bu; Eggplant 470 pkgs; Escarole 450 pkgs; Lettuce 550 pkgs; English Peas 580 bu; Peppers 480 pkgs; Potatoes 550 pkgs; Tomatoes 500 pkgs; Green Corn 2000 doz. Butterbeans included with Limas 500 bu.

The Weekly Totals differ from, and are usually slightly higher than the Monthly Totals, due to fractional totals by weeks. Notes apply to opposite page and vice versa.

TRUCK SHIPMENTS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS
BY WEEKS FOR 1948-49 SEASON
(Rail Carload Equivalent)

Date by Weeks	Tomatoes	Okra	Squash	Bun. Vegs.	Oth. Vegs.	Tot. Vegs.	Strawberries	W-Mel.	Avocados	Limes	Oth. Fru.	Tot. Misc. Fru.	Grand Total
Aug. 1-31*		25				33			15	15	2	32	65
Sept.1-30*		3	LCL			5			25	14	1	40	45
Oct. 1-14*									1	1		2	2
Oct. 15-16		LCL				LCL			LCL	LCL		LCL	LCL
Oct. 17-23		5	8	LCL	1	52			4	1		5	57
Oct. 24-30		7	13	LCL	LCL	97			10	1		11	108
Oct. 31-Nov.6	3	5	17	LCL	LCL	154			6	1		7	161
Nov. 7-13	17	6	12	LCL	1	221			7	LCL		7	228
Nov. 14-20	76	4	12	1	2	427			13	2		15	442
Nov. 21-27	157	3	23	1	5	508	LCL		5	LCL		5	513
Nov. 28-Dec.4	162	1	22	2	7	542	LCL		5	LCL		5	547
Dec. 5-11	182	1	29	LCL	12	630	2		2	1		5	635
Dec. 12-18	125	3	36	1	19	583	8		3	1		12	595
Dec. 19-25	88	2	27	1	17	470	12		LCL	LCL		12	482
Dec. 26-Jan.1	64	1	18	2	19	492	22		LCL			22	514
Jan. 2-8	72	1	18	3	14	507	16		LCL	LCL		16	523
Jan. 9-15	105	1	22	4	34	780	18		LCL	LCL		18	798
Jan. 16-22	106	2	28	4	49	789	20		LCL	1		21	810
Jan. 23-29	103	2	32	3	54	950	23		LCL	LCL		23	973
Jan. 30-Feb.5	139	1	36	4	52	1014	12		LCL	LCL		12	1026
Feb. 6-12	182	2	41	4	70	1272	25		LCL	LCL		25	1297
Feb. 13-19	172	1	39	4	66	1133	44			LCL		44	1177
Feb. 20-26	209	LCL	42	5	59	1294	48		LCL	LCL		48	1342
Feb. 27-Mar.5	346	2	59	2	81	1702	38		LCL	1		39	1741
Mar. 6-12	307	1	60	2	46	1455	30		LCL	LCL		30	1485
Mar. 13-19	336	1	58	3	41	1417	31		LCL	LCL		31	1448
Mar. 20-26	327	1	66	2	53	1525	25		LCL	1		26	1551
Mar. 27-Apr.2	370	2	62	2	42	1701	15		LCL	LCL		15	1716
Apr. 3-9	387	3	50	1	27	1596	6		LCL	LCL	LCL	6	1602
Apr. 10-16	498	4	57	1	30	1989	5	10	LCL	LCL	LCL	15	2004
Apr. 17-23	563	4	70	1	18	2010	1	9	LCL	LCL	LCL	10	2020
Apr. 24-30	469	7	46	LCL	14	1816	4	29		1	2	36	1852
May 1-7	372	10	36	LCL	7	1602	4	74	LCL	1		79	1681
May 8-14	361	16	32	LCL	11	1421	LCL	141	LCL	1	1	143	1564
May 15-21	325	21	14	1	9	1223	LCL	400	LCL	1	6	407	1630
May 22-28	178	24	8	LCL	5	821		763	LCL	4	10	777	1598
May 29-Jun.4	78	20	5	LCL	4	536		671	LCL	1	9	681	1217
June 5-11	20	17	4	LCL	4	404		961	LCL	2	16	979	1383
June 12-18	6	11	LCL	LCL	LCL	218		838	LCL	9	7	854	1072
June 19	LCL	5	LCL			31		122		1	1	124	155
June 20-30*	3	9				124		769				769	893
July 1-31*		17				65		100		50		150	215
Total by Weeks	6908	251	1102	54	873	33609	409	4887	96	111	55	5558	39167
Total by Months	6907	252	1098	56	870	33586	410	4888	97	111	56	5562	39148
Oct.15-June19	6905	197	1102	54	873	33382	409	4018	55	31	52	4565	37947

(2) Converted into carload equivalent on basis of; Okra 500 pkgs; Squash 500 pkgs; Bnchd Vegetables 2000 doz; Other Vegetables 500 pkgs; Field Peas 500 pkgs; Avocados 700 pkgs; Strawberries 450 pkgs; Limes 800 pkgs; Watermelons 1000 melons; Other Fruits 500 pkgs.
(3) Pre-War carload conversion factors retained for more accurate comparisons with other years. The Shipments are the passings by Road Guard Stations (open Oct. 15 to June 19,1949) and destined for out-of-State points, excepting some carloads to West Florida. Several carloads of West Florida vegetables going out of State were not included. Watermelons originating West of the Suwannee River and going out of State were included in the estimates for period after May 31.

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 22 YEARS

Records Estimates Season ALL ORANGES	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul, Shipped by Boat(1) Carloads	Total Rail&Boat Shipments Boxes	Estimated Trucked out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(2) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	16,437	16,310	127	5,917,320	520,000	12,000	650,000	7,099,320
1928-29	32,428	31,988	440	11,674,080	975,000	33,000	1,062,500	13,744,580
1929-30(3)	21,816	21,635	181	7,489,633	65,000	40,000	780,000	8,374,633
1930-31	40,353	39,354	999	14,000,130	1,584,000	61,351	1,308,582	16,954,065
1931-32	25,725	24,054	1,671	9,904,145	1,486,480	36,362	1,122,000	12,548,987
1932-33	32,580	26,414	6,166	11,728,800	1,854,000	50,000	1,332,000	14,964,800
1933-34	31,799	18,291	13,508	12,401,563	2,322,000	31,433	1,386,000	16,170,996
1934-35	28,213	14,843	13,370	11,094,459	2,891,643	177,937	1,425,000	15,589,039
1935-36	29,746	17,403	12,343	11,714,588	2,510,000	140,000	1,500,000	15,864,588
1936-37	37,208	23,382	13,826	14,580,603	2,560,000	620,185	1,700,000	19,460,788
1937-38	46,061	31,258	14,803	18,005,497	3,442,000	1,055,399	1,800,000	24,302,896
1938-39	55,697	37,380	18,317	21,528,758	5,185,741	1,186,689	2,000,000	29,900,000
1939-40	38,285	29,286	8,999	14,718,568	4,376,000	4,170,134	1,800,000	25,064,702
1940-41	42,597	31,402	11,195	16,609,828	5,726,000	3,941,261	2,475,000	28,752,089
1941-42	41,598	40,443	1,155	16,853,616	4,099,200	4,197,299	2,049,385	27,200,000
1942-43	52,287	52,287	None	25,799,784	2,715,823	6,438,274	2,246,300	37,200,181
1943-44	61,160	61,160	None	30,511,378	2,155,200	11,010,841	2,522,581	46,200,000
1944-45	49,507	49,507	Nono	24,526,000	1,456,400	14,344,000	2,473,600	42,800,000
1945-46	52,665	52,589	76	26,007,541	2,054,000	19,219,412	2,518,747	49,800,000
1946-47	54,421	51,513	2,908	26,787,122	3,509,600	19,825,485	2,677,793	52,800,000
1947-48	39,616	39,616	-	19,659,370	5,707,300	30,376,340	2,656,990	58,400,000
1948-49	33,257	33,222	35	16,446,857	12,142,400	26,851,046	2,859,697	58,300,000

NOTES:

(1) Domestic boat in coastwise trade.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(3) Fruit fly year when production harvest and shipments restricted. Many trees cut down and many so-called host plants destroyed by the federal agencies.

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 22 YEARS

Records & Estimates Season	Cost of Production (2) Before Picked	Cost of Picking, Hauling, Packing, Selling	Estimated Gross FOB Returns Florida Points	Estimated Net Returns to Growers Rail&Boat Shipments	Estimated Net Return (1) Rail & Boat Shipments	Estimated Net Return All Oranges Harvested and Used	Estimated Gross FOB Returns Rail&Boat Shipments	Estimated Gross Return All Oranges Harvested and Used
ALL ORANGES	Per Box	Per Box	Per Box	Per Box	Net Value	Net Value	Gross Value	Gross Value
1927-28	$0.72	$1.30	$4.16	$2.14	$12,663,065	$13,305,825	$24,616,051	$26,804,051
1928-29	.72	1.29	2.13	.12	1,400,890	2,125,630	23,749,050	26,224,450
1929-30 (4)	.80	1.30	3.30	1.20	8,987,560	9,648,310	24,715,789	26,157,789
1930-31	.48	1.10	2.15	.57	7,980,074	8,826,500	30,100,230	32,738,844
1931-32	.60	.95	2.30	.75	7,428,109	8,857,319	22,779,534	25,455,041
1932-33	.47	.90	1.48	.10	1,172,38[illegible]	2,129,300	17,658,624	20,446,424
1933-34	.46	.87	1.71	.38	4,712,594	6,842,686	21,206,673	25,752,219
1934-35	.45	.90	1.85	.50	5,547,228	8,240,123	20,524,740	26,352,060
1935-36	.45	.95	2.30	.90	10,545,129	14,056,129	25,943,552	33,349,552
1936-37	.42	.93	2.50	1.15	16,767,093	20,689,419	33,451,507	44,979,738
1937-38	.38	.88	1.56	.30	5,401,619	6,055,959	28,038,575	34,359,559
1938-39	.34	.84	1.43	.25	5,382,190	6,035,321	30,766,124	39,687,098
1939-40	.42	.91	1.62	.29	4,266,365	4,214,941	23,843,370	33,663,315
1940-41	.40	.87	1.63	.36	5,079,538	9,120,658	27,074,020	42,142,109
1941-42	.44	.90	2.10	.76	12,808,748	18,918,916	35,392,593	51,904,503
1942-43	.40	1.01	2.97	1.56	40,247,695	53,904,492	76,625,358	101,089,208
1943-44	.50	1.25	3.10	1.35	41,190,360	60,688,352	94,585,272	129,867,001
1944-45	.50	1.21	3.50	1.79	43,901,540	74,132,856	85,841,000	135,653,600
1945-46	.48	1.24	3.55	1.83	47,414,330	91,767,53[illegible]	91,979,733	131,618,586
1946-47 *	.53 (3)	1.25	2.62	.84	25,320,348	26,385,989	78,975,370	101,927,124
1947-48 *	.50	1.32	2.10	.28	7,095,000	8,492,216	53,212,501	82,619,360
1948-49*	.50	1.40	2.80	.90	25,730,332	45,510,967	80,049,920	127,743,648

NOTES:

* Truck Shipments included with Rail & Boat, their FOB prices being same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau equivalent "On Tree" average price for rail and boat shipments. This is not necessarily the same as U.S. Dept. of Agri. "On Tree" price.

(3) An allowance was made for unusual cost in grove protection in 1946-47 season. (February freeze).

(4) Fruit fly year when production, harvest and shipments restricted.

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 22 YEARS

Records Estimates Season GRAPE-FRUIT	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul Shipped by Boat(1) Carloads	Total Rail&Boat Shipments Boxes	Estimated Trucked out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(2) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	30,012	29,953	59	7,204,520	245,000	386,000	300,000	8,355,320
1928-29	28,294	28,091	203	10,185,840	450,000	1,489,320	675,000	12,800,160
1929-30(3)	16,415	16,354	61	6,341,913	30,000	1,670,000	360,000	8,401,913
1930-31	30,462	29,809	653	11,841,937	792,000	2,892,705	654,291	16,180,933
1931-32	20,315	17,865	2,450	7,821,313	897,940	930,171	782,000	10,431,424
1932-33	19,639	15,293	4,346	7,266,430	980,500	2,750,000	928,700	11,925,630
1933-34	17,514	11,340	6,174	6,981,916	684,000	2,605,964	841,320	11,113,200
1934-35	19,218	10,418	8,800	7,577,053	1,187,011	5,603,996	875,000	15,243,060
1935-36	15,196	8,838	6,358	5,936,067	1,028,000	3,760,000	780,000	11,504,067
1936-37	23,786	16,142	7,644	9,352,859	1,283,600	6,685,327	800,000	18,121,786
1937-38	16,952	11,511	5,441	6,602,063	1,233,600	5,793,097	750,000	14,378,760
1938-39	25,047	17,051	7,996	9,844,983	1,472,277	8,395,343	950,000	20,662,611
1939-49	12,974	9,160	3,814	5,110,591	1,000,000	8,800,274	740,000	15,650,865
1940-41	19,962	14,478	5,484	7,956,475	1,559,600	13,870,966	1,000,000	24,387,041
1941-42	16,813	16,298	515	6,856,510	1,042,000	10,142,575	1,058,915	19,100,000
1942-43	16,529	16,529	None	8,009,134	612,807	17,584,025	1,094,150	27,300,116
1943-44	18,041	18,041	None	8,984,800	355,600	20,445,648	1,213,952	31,000,000
1944-45	11,742	11,742	None	5,860,000	205,200	15,136,000	1,098,800	22,300,000
1945-46	16,554	16,542	12	8,306,504	340,400	22,136,149	1,216,947	32,000,000
1946-47	17,800	16,363	1,437	8,878,857	558,000	15,864,346	1,098,797	26,400,000
1947-48	14,776	14,776	-	7,497,100	1,143,367	19,448,586	1,210,947	29,300,000
1948-49	17,738	17,738	-	8,826,811	3,483,200	16,305,820	1,584,169	30,200,000

NOTES:

(1) Domestic Boat Shipments in coast-wise trade.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intra-state truck shipments, etc.

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 22 YEARS

Records & Estimates Season GRAPE-FRUIT	Cost of Production (2) Before Picked Per Box	Cost of Picking Hauling Packing Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated Net Returns to Growers Rail&Boat Shipments Per Box	Estimated Net Return (1) Rail&Boat Shipments Net Value	Estimated Net Return All Grapefruit Harvested and Used Net Value	Estimated Gross FOB Returns Rail-Boat Shipments Gross Value	Estimated Gross Return All Grapefruit Harvested and Used Gross Value
1927-28	$0.52	$1.25	$2.28	$1.51	$10,878,523	$11,555,565	$23,630,170	$25,018,170
1928-29	.52	1.25	2.02	.25	2,546,460	3,078,468	20,575,397	22,557,557
1929-30 (4)	.60	1.25	3.05	1.20	7,610,206	8,293,796	19,347,835	21,479,835
1930-31	.36	1.05	1.50	.09	1,065,772	1,109,727	17,762,980	20,366,306
1931-32	.40	.85	1.50	.25	1,955,523	2,012,557	11,731,970	13,522,967
1932-33	.38	.85	1.16	-.07	- 508,650	-1,285,321	8,429,059	10,170,789
1933-34	.39	.83	1.51	.29	2,024,756	2,591,700	10,542,693	13,296,652
1934-35	.37	.84	1.29	.08	606,164	199,847	9,774,397	13,409,984
1935-36	.39	.97	1.87	.61	3,671,001	5,269,881	11,100,445	15,976,445
1936-37	.30	.83	1.48	.35	3,273,500	4,448,605	13,612,231	19,731,121
1937-38	.36	.82	1.53	.35	2,310,742	2,613,465	10,101,156	15,063,803
1938-39	.30	.74	1.04	Zero	Zero	-2,099,526	10,238,765	14,688,400
1939-40	.40	.82	1.42	.20	1,022,120	- 146,121	7,257,052	12,269,942
1940-41	.35	.74	1.21	.12	954,777	- 514,241	9,627,335	17,335,152
1941-42	.40	.80	1.80	.60	4,113,906	6,430,418	12,341,718	22,849,773
1942-43	.35	.88	2.53	1.10	8,810,047	18,156,816	18,661,282	40,527,501
1943-44	.40	1.07	2.47	1.00	8,984,800	28,461,544	22,192,456	56,780,588
1944-45	.40	1.07	3.00	1.53	8,965,800	30,343,516	17,580,000	49,962,240
1945-46	.34	1.10	2.65	1.21	10,039,012	24,983,418	21,986,266	56,604,216
1946-47 *	.37(3)	1.08	2.18	.73	6,440,575	6,883,612	19,640,839	32,971,887
1947-48 *	.35	1.09	1.80	.36	5,107,194	- 342,474	15,535,969	24,102,874
1948-49 *	.35	1.18	2.35	.82	10,094,209	10,009,553	28,928,526	41,549,598(5)

NOTES:

* Truck shipments included with Rail & Boat, their FOB prices being same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(3) An allowance was made for unusual cost in grove protection in 1946-47 season.

(4) Fruit fly year when production, harvest and shipments restricted.

(5) Takes into account a loss of $1,304,466 on Grapefruit sold to canners.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 22 YEARS

Records Estimates Season TANGERINES	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul Shipped by Boat(1) Carloads	Total Rail and Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed (2) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	1,427	1,417	10	513,720	40,000		50,000	603,720
1928-29	2,951	2,917	34	1,062,360	75,000		212,500	1,349,860
1929-30(3)	1,254	1,242	12	333,054	5,000		60,000	448,054
1930-31	3,830	3,786	44	1,387,828	264,000		218,097	1,869,925
1931-32	3,195	3,077	118	1,188,707	141,100		136,000	1,465,807
1932-33	3,282	2,749	533	1,181,520	175,680	No record	162,000	1,519,200
1933-34	3,998	2,657	1,341	1,501,411	243,000	made of the	247,680	1,992,091
1934-35	3,676	2,199	1,477	1,461,049	267,706	very few	275,000	2,003,755
1935-36	3,974	2,549	1,425	1,581,397	232,000	Tangerines	280,000	2,093,397
1936-37	5,885	4,046	1,839	2,288,234	430,000	processed	300,000	3,018,634
1937-38	4,396	3,098	1,298	1,709,973	298,000	prior to	250,000	2,257,973
1938-39	6,323	4,502	1,821	2,553,332	478,541	1944-45	350,000	3,381,873
1939-40	4,051	3,315	736	1,620,345	437,200	Season	200,000	2,257,545
1940-41	4,513	3,449	1,064	1,791,824	434,800		525,000	2,751,624
1941-42	3,534	3,387	147	1,432,144	334,800		333,056	2,100,000
1942-43	7,382	7,382	None	3,407,401	400,048		392,700	4,200,140
1943-44	6,179	6,179	None	2,818,782	382,800		398,418	3,600,000
1944-45	6,847	6,847	None	3,149,000	327,600	3,000	420,400	3,900,000
1945-46	5,728	5,728	None	2,809,372	384,000	515,600	491,028	4,200,000
1946-47	4,545	4,323	222	2,058,146	438,400	930,751	472,703	3,900,000
1947-48	3,610	3,610	-	1,699,815	667,845	598,505	433,835	3,400,000 A
1948-49	4,024	4,024	-	1,827,056	1,080,900	999,354	492,730	4,400,000

NOTES:

(A) Does not include 600,000 boxes abandoned for marketing reasons. Abandonment, if any, for prior years not shown here. No abandonment of any citrus in 1948-49 season.

(1) Domestic Boat Shipments in coast-wide trade.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 22 YEARS

Records & Estimates Season TAN-GERINES	Cost of Production (2) before Picked Per Box	Cost of Picking Hauling Packing Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return(1) Rail & Boat Shipments Net Value	Estimated Net Return All Tangerines Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Tangerines Harvested and Used Gross Value
1927-28	$0.81	$1.70	$5.28	$2.77	$1,423,004	$1,519,104	$ 2,712,442	$ 2,892,442
1928-29	.81	1.70	2.90	.39	414,320	493,945	3,080,844	3,435,814
1929-30(3)	.90	1.70	3.50	.90	344,748	378,498	1,340,689	1,459,689
1930-31	.54	1.50	1.95	-.09	- 124,905	11,345	2,706,265	3,188,362
1931-32	.75	1.25	2.05	.05	59,435	73,290	2,436,849	2,713,949
1932-33	.56	1.16	1.42	-.30	- 354,456	- 281,513	1,677,758	1,999,238
1933-34	.56	1.05	1.80	.19	285,268	574,535	2,702,540	3,352,340
1934-35	.55	.95	1.66	.16	233,768	409,965	2,425,341	3,035,702
1935-36	.55	1.10	2.00	.35	553,489	883,889	3,162,794	3,902,794
1936-37	.50	1.15	1.45	-.20	- 457,646	- 558,726	3,317,939	4,127,899
1937-38	.52	1.16	1.86	.18	307,795	320,975	3,180,550	3,881,990
1938-39	.45	.95	1.34	-.06	- 153,200	- 242,481	3,421,465	4,291,433
1939-40	.50	1.06	2.00	.44	712,952	945,972	3,240,690	4,411,370
1940-41	.50	1.08	1.68	.10	179,182	219,216	3,010,264	4,415,434
1941-42	.58	1.16	2.85	1.11	1,589,680	2,280,955	4,081,610	5,818,344
1942-43	.40	1.35	2.79	1.03	3,509,623	4,223,464	9,472,575	11,436,280
1943-44	.65	1.68	3.70	1.37	3,861,731	4,884,190	10,429,493	13,041,107
1941-45	.65	1.68	4.25	1.92	6,046,080	7,437,192	13,383,250	16,296,690
1945-46	.64	1.71	4.80	2.45	6,882,962	8,800,902	13,484,986	17,807,898
1946-47*	.68	1.72	3.75	1.35	2,778,497	3,522,030	8,310,248	11,666,569
1947-48*	.68	1.82	2.90	.40	947,064	696,420	6,866,214	8,203,662
1948-49*	.68	1.85	3.70	1.17	3,402,191	3,259,910	10,759,067	12,894,256(4)

NOTES:

* Truck shipments included with Rail & Boat, their FOB prices being same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting for taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated. This estimated "On Tree" price is not necessarily the same as the U.S.D.A., "On Tree" price.

(3) Fruit fly year when production, harvest and shipments restricted.

(4) Takes into account a loss of $669,567 on tangerines sold to canners.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 22 YEARS

Records Estimates Season ALL CITRUS	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul Shipped by Boat(1) Carloads	Total Rail & Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(2) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	37,876	37,680	196	15,635,330	800,000	600,000	1,000,000	16,035.360
1928-29	63,673	62,996	677	22,922,280	1,500,000	1,527,320	1,950,000	27,899,600
1929-30(3)	39,485	39,231	254	14,214,600	100,000	1,710,000	1,200,000	17,224,600
1930-31	74,645	72,949	1,696	27,229,945	2,640,000	2,954,056	2,160,970	35,004,971
1931-32	49,235	44,996	4,239	18,914,165	2,525,520	966,533	2,040,000	24,446,218
1932-33	55,501	44,456	11,045	20,376,750	3,010,180	2,800,000	2,427,700	28,409,630
1933-34	53,311	32,288	21,023	20,884,890	3,249,000	2,667,397	2,475,000	29,276,287
1934-35	51,107	27,460	23,647	20,132,561	4,346,360	5,781,933	2,575,000	32,835,854
1935-36	48,916	28,790	20,126	19,232,052	3,770,000	3,900,000	2,560,000	29,462,052
1936-37	66,879	43,570	23,309	26,221,696	4,274,000	7,305,512	2,800,000	40,601,208
1937-38	67,409	45,867	21,542	26,317,533	4,973,600	6,848,496	2,800,000	40,939,629
1938-39	87,067	58,933	28,134	35,927,076	7,126,559	9,582,037	3,300,000	56,447,995
1939-40	55,310	41,761	13,549	21,449,504	5,813,200	12,970,408	2,740,000	42,973,112
1940-41	67,072	49,329	17,743	26,358,127	7,720,400	17,812,227	4,000,000	55,890,754
1941-42	61,945	60,128	1,817	25,142,270	5,476,000	14,339,874	3,441,856	48,100,000
1942-43	76,198	76,198	None	37,216,319	3,728,678	24,022,299	3,733,150	68,700,446
1943-44	85,380	85,380	None	42,314,960	2,893,600	31,456,489	4,134,951	80,800,000
1944-45	68,096	68,096	None	33,535,000	1,989,200	29,483,000	3,992,800	69,000,000
1945-46	74,947	74,859	88	39,902,117	2,778,400	41,871,161	4,226,722	86,000,000
1946-47	76,766	72,199	4,567	37,724,125	4,506,000	36,620,582	4,249,293	83,100,000
1947-48	58,002	58,002	-	28,772,771	7,518,512	50,423,431	4,301,772	91,100,000
1948-49	55,019	54,984	35	27,100,724	10,706,400	44,156,920	4,936,056	92,900,000

NOTES:

(1) Domestic Boat Shipments in Coastwise Trade.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.,

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 22 YEARS

Records & Estimates Season ALL CITRUS	Cost of Production(2) Before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return (1) Rail & Boat Shipments Net Value	Estimated Net Return All Citrus Harvested and Used Net Value	Estimated Gross FOB Returns Rail & Boat Shipments Gross Value	Estimated Gross Return All Citrus Harvested and Used Gross Value
1927-28	$0.63	$1.26	$3.74	$1.83	$24,961,598	$26,980,402	$50,958,063	$54,714,063
1928-29	.64	1.25	2.05	.19	4,361,670	5,698,065	47,405,291	52,217,851
1929-30(3)	.71	1.29	3.19	1.19	16,942,904	18,320,604	45,399,313	49,097,313
1930-31	.45	1.10	1.86	.33	8,320,948	10,037,572	50,839,325	56,293,572
1931-32	.53	.92	1.95	.50	9,442,672	10,943,166	36,048,358	42,691,967
1932-33	.45	.90	1.36	.01½	309,774	532,456	27,405,441	32,616,451
1933-34	.44	.87	1.65	.33½	7,022,618	10,009,011	31,451,906	42,401,191
1934-35	.43	.88	1.63	.32	6,387,160	8,855,935	32,724,487	42,797,752
1935-36	.44	.94	2.14	.76	14,717,619	20,211,899	41,206,791	53,189,191
1936-37	.37	.92	2.04	.75	19,583,547	24,579,298	53,611,677	68,838,758
1937-38	.38	.88	1.57	.30½	8,020,166	8,988,419	41,370,281	53,225,352
1938-39	.34	.82	1.31	.15	5,228,990	3,603,514	44,446,374	58,640,951
1939-40	.42	.90	1.60	.28	6,003,437	5,014,792	34,341,712	50,365,127
1940-41	.39	.85	1.51	.27	7,113,479	8,831,633	39,711,619	64,192,695
1941-42	.43	.89	2.06	.74	18,512,334	27,639,289	51,815,921	80,572,320
1942-43	.39	1.01	2.81	1.41	52,567,333	76,284,772	104,759,215	153,052,989
1943-44	.49	1.24	3.01	1.28	54,036,891	94,032,006	127,207,221	199,688,696
1944-45	.483	1.25	3.483	1.75	58,915,420	111,913,561	116,304,250	201,912,330
1945-46	.46	1.25	3.44	1.73	64,336,904	125,551,850	127,451,065	230,230,700
1946-47*	.50	1.24	2.59	.85	31,591,356	36,791,631	100,679,009	140,565,580
1947-48*	.48	1.29	2.08	.31	11,149,258	8,846,162	75,614,684	114,925,896
1948-49*	.47	1.37	2.74	.90	39,226,732	58,780,430	119,737,513	182,187,502

NOTES:

* Truck Shipments included with Rail & Boat, their FOB prices being the same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting for taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA AUCTION SALES, 1931-32 - 1948-49

Furnished through courtesy of the Statistical Department
Florida Citrus Exchange, Tampa, Fla.

ORANGES

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1931-32	Cars	6517	2228	1182	511	497	776	174	447	179	-	12511
	Average	$3.40	3.21	3.24	3.06	3.20	3.25	2.90	3.14	3.25	-	3.30
1932-33	Cars	9238	2968	1419	579	553	921	273	614	256	-	16721
	Average	$2.43	2.45	2.53	2.35	2.40	2.55	2.30	2.30	2.46	-	2.44
1933-34	Cars	7613	2632	1436	515	526	894	266	495	267	142	14786
	Average	$2.75	2.62	2.69	2.54	[illegible]	2.67	2.46	2.47	2.69	2.38	2.70
1934-35	Cars	8243	2720	1419	[illegible]	578	1070	258	553	260	258	15890
	Average	$2.61	2.47	2.58	[illegible]	[illegible]	2.59	2.34	2.35	2.47	2.44	2.56
1935-36	Cars	7503	2624	1561	[illegible]	599	878	249	555	271	240	14780
	Average	$3.02	2.93	3.02	[illegible]	3.04	3.15	2.72	2.87	3.08	2.82	3.00
1936-37	Cars	9112	3164	1657	[illegible]	824	1080	264	708	412	282	17932
	Average	$3.23	3.15	3.28	[illegible]	3.21	3.33	3.01	3.12	3.27	2.98	3.21
1937-38	Cars	10228	3376	1849	[illegible]	298	1394	413	1181	550	302	20686
	Average	$2.26	2.20	2.24	[illegible]	2.28	2.39	2.05	2.16	2.26	1.98	2.24
1938-39	Cars	12440	4049	2132	[illegible]	[illegible]	1639	511	1555	717	326	25224
	Average	$2.10	1.99	2.16	2.11	2.20	2.26	2.01	2.01	2.16	1.94	2.09
1939-40	Cars	8758	2908	1290	[illegible]	589	1012	318	1031	393	173	16836
	Average	$2.43	2.25	2.47	2.15	2.31	2.41	[illegible]	[illegible]	2.25	2.23	[illegible]
1940-41	Cars	10089	3320	1385	426	647	1020	322	1077	434	261	18971
	Average	$2.37	2.26	2.45	2.31	2.44	2.45	2.25	2.18	2.42	2.22	2.35
1941-42	Cars	9053	3064	1377	[illegible]	568	862	204	1002	353	312	17133
	Average	$2.86	2.76	2.90	[illegible]	2.91	2.86	2.70	2.64	2.88	2.77	2.83
1942-43	Cars	6771	2330	851	439	463	939	359	742	412	277	13603
	Average	[illegible]	3.70	3.32	3.72	3.65	3.77	3.70	3.55	3.87	3.56	3.79
1943-44	Cars	[illegible]	2257	678	522	488	815	476	516	658	200	12849
	Average	$3.98	3.82	4.02	3.86	3.86	3.89	3.67	3.65	3.85	3.71	3.90
1944-45	Cars	[illegible]	1651	425	293	264	552	271	299	365	157	9022
	Average	[illegible]	4.38	4.47	4.27	4.34	4.29	4.17	4.02	4.57	4.39	4.48
1945-46	Cars	4510	1478	363	237	197	345	196	372	262	308	8268
	Average	$4.72	4.44	4.70	4.48	4.43	4.39	4.24	4.17	4.43	4.45	4.58
1946-47	Cars	7824	1930	870	420	539	921	430	801	562	373	14770
	Average	$3.60	3.35	3.52	3.29	3.47	3.38	3.27	3.25	3.47	3.35	3.50
1947-48	Cars	6856	2550	867	342	534	608	249	689	479	234	13406
	Average	$3.40	3.16	3.34	3.12	3.19	3.08	2.91	3.01	3.12	2.96	3.27
1948-49	Cars	6512	2377	[illegible]	393	544	818	416	571	593	137	13133
	Average	$4.35	4.04	[illegible]	4.17	4.17	4.14	4.10	3.86	4.23	3.96	4.23

FLORIDA AUCTION SALES, 1931-32 - 1948-49 (Cont'd.)

GRAPEFRUIT

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1931-32	Cars	4680	1254	935	505	510	805	207	354	328	--	9578
	Average	$2.49	2.34	2.50	2.38	2.49	2.59	2.41	2.31	2.54	-	2.47
1932-33	Cars	5138	1266	892	429	433	738	228	409	330	-	9863
	Average	$2.05	1.95	2.06	2.02	2.21	2.29	1.96	2.01	2.31	--	2.06
1933-34	Cars	3948	1129	696	310	388	634	221	370	298	41	8035
	Average	$2.41	2.25	2.40	2.38	2.39	2.55	2.37	2.29	2.51	2.42	2.39
1934-35	Cars	4893	1326	898	389	403	721	200	444	350	135	9759
	Average	$2.04	1.81	1.93	1.94	2.09	2.19	2.05	1.92	2.10	1.86	2.00
1935-36	Cars	3928	1072	872	262	396	395	132	340	251	117	7765
	Average	$2.67	2.38	2.49	2.40	2.54	2.68	2.40	2.32	2.62	2.28	2.57
1936-37	Cars	5376	1650	956	274	415	494	151	423	307	151	10197
	Average	$2.24	2.06	2.22	2.14	2.29	2.58	2.53	2.24	2.41	2.12	2.23
1937-38	Cars	4881	1244	814	190	313	353	72	342	219	127	8555
	Average	$2.20	2.06	2.13	2.05	2.11	2.28	2.16	2.09	2.21	1.88	2.16
1938-39	Cars	6389	1429	1020	329	394	361	118	432	277	187	10926
	Average	$1.75	1.57	1.73	1.68	1.77	1.95	1.85	1.66	1.60	1.46	1.72
1939-40	Cars	4765	1153	633	181	141	182	62	241	146	35	7423
	Average	$2.21	1.92	2.10	1.92	2.11	2.29	2.10	1.98	2.06	1.73	2.13
1940-41	Cars	5035	1334	805	242	256	313	109	416	215	91	8823
	Average	$1.96	1.75	1.95	1.76	1.92	2.00	1.77	1.74	1.91	1.61	1.91
1941-42	Cars	4519	1166	712	125	136	208	51	222	98	88	7325
	Average	$2.55	2.36	2.55	2.33	2.61	2.83	2.73	2.33	2.64	2.60	2.52
1942-43	Cars	3411	967	487	142	96	114	19	201	85	82	5604
	Average	$3.18	2.97	3.21	2.90	2.90	3.17	2.96	2.67	3.00	2.70	3.10
1943-44	Cars	2628	778	338	128	49	69	44	90	97	43	4264
	Average	$3.63	3.48	3.64	3.36	3.32	3.20	3.51	3.05	3.31	3.14	3.56
1944-45	Cars	2320	498	183	31	23	21	13	16	13	14	3132
	Average	$4.35	4.03	4.11	3.74	3.01	3.31	3.38	3.23	3.25	3.54	4.24
1945-46	Cars	3293	737	213	33	12	19	2	18	14	45	4386
	Average	$3.88	3.67	3.83	3.06	2.60	3.52	3.33	2.91	2.81	3.19	3.82
1946-47	Cars	4894	890	546	63	80	154	31	183	111	142	7094
	Average	$3.39	3.11	3.17	2.69	3.10	3.16--	3.55	2.87	3.18	2.54	3.29
1947-48	Cars	4258	1260	456	73	85	105	34	159	92	138	6660
	Average	$3.22	2.82	2.89	2.55	2.79	2.92	2.97	2.54	3.03	2.31	3.07
1948-49	Cars	4406	1287	464	158	222	355	168	237	308	36	7641
	Average	$3.87	3.58	3.72	3.49	3.86	3.68	3.71	3.33	3.80	2.82	3.77

FLORIDA AUCTION SALES, 1931-32 - 1948-49 (Cont'd.)

TANGERINES

(½ box basis)

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1931-32	Cars	1190	396	203	175	116	161	65	88	60	-	2454
	Average	$1.54	1.44	1.49	1.39	1.41	1.52	1.32	1.41	1.53	-	1.49
1932-33	Cars	1308	375	157	95	108	180	58	102	73	-	2456
	Average	$1.28	1.20	1.28	1.23	1.21	1.22	1.14	1.09	1.22	-	1.24
1933-34	Cars	1134	433	144	142	114	179	67	96	71	1	2381
	Average	$1.21	1.15	1.17	1.25	1.24	1.21	1.21	1.15	1.22	1.43	1.20
1934-35	Cars	1071	356	132	136	71	155	66	108	71	31	2197
	Average	$1.18	1.10	1.12	1.25	1.27	1.25	1.26	1.20	1.28	1.22	1.18
1935-36	Cars	1124	365	157	139	116	217	54	113	87	26	2398
	Average	$1.35	1.32	1.30	1.40	1.42	1.36	1.32	1.34	1.41	1.23	1.35
1936-37	Cars	1557	572	196	210	193	306	103	138	116	33	3424
	Average	$1.12	1.03	1.05	1.19	1.09	1.14	1.10	1.08	1.16	.96	1.10
1937-38	Cars	1311	382	149	95	117	149	74	125	88	23	2513
	Average	$1.26	1.21	1.20	1.28	1.30	1.25	1.10	1.18	1.23	1.08	1.24
1938-39	Cars	1851	551	172	152	189	257	107	203	148	33	3663
	Average	$1.07	.92	.93	.95	.98	.97	.86	.91	.96	.79	1.00
1939-40	Cars	1192	345	66	65	104	142	48	115	57	9	2143
	Average	$1.37	1.34	1.41	1.37	1.47	1.45	1.31	1.27	1.34	1.33	1.37
1940-41	Cars	1425	454	109	77	154	195	59	149	82	13	2717
	Average	$1.23	1.16	1.19	1.07	1.20	1.22	1.09	1.12	1.14	1.06	1.19
1941-42	Cars	1152	359	78	39	106	135	38	105	48	25	2085
	Average	$1.86	1.75	1.75	1.65	1.82	1.66	1.52	1.58	1.76	1.50	1.79
1942-43	Cars	1485	670	143	108	188	303	101	193	151	57	3399
	Average	$1.82	1.84	1.62	1.81	1.86	1.81	1.66	1.80	1.74	1.53	1.80
1943-44	Cars	326	134	22	22	22	40	26	21	31	-	644
	Average	$2.16	2.28	2.27	2.32	2.37	2.27	2.36	2.26	2.40	-	2.23
1944-45	Cars	669	300	32	72	66	150	41	53	73	9	1465
	Average	$2.42	2.38	2.35	2.49	2.45	2.42	2.15	2.40	2.47	2.77	2.41
1945-46	Cars	1188	414	57	70	86	167	46	88	59	26	2201
	Average	$2.67	2.52	2.43	2.58	2.68	2.54	2.32	2.59	2.50	2.61	2.61
1946-47	Cars	1233	335	69	91	139	202	63	128	108	35	2403
	Average	$2.28	2.18	2.11	2.12	1.99	1.90	1.92	1.99	2.04	2.08	2.17
1947-48	Cars	943	433	69	77	147	193	63	120	140	24	2209
	Average	$2.09	2.01	1.87	1.81	1.88	1.91	1.70	1.81	1.73	1.92	1.98
1948-49	Cars	1345	516	86	79	132	230	65	108	163	13	2737
	Average	$2.75	2.48	2.51	2.36	2.39	2.24	2.24	2.09	2.36	1.96	2.55

ESTIMATED COSTS FROM TREE TO AUCTIONS
1946-47, 1947-48 AND 1948-49 SEASONS
(Private Sales not included)

ORANGES	1946-47	1947-48	1948-49	Per Box 1946-47	Per Box 1947-48	Per Box 1948-49
Carloads Sold				14,770	13,406	13,133
Auction Sales at Terminal Markets				$3.50	$3.27	$4.23
Terminal Selling & Expenses				.07	.07	.07
Net at Terminal				3.43	3.20	4.16
Transportation Cost				.80	.95	1.13
Florida F.O.B. Equivalent				$2.63	$2.25	3.03
Florida Marketing Charges	.08	.08	.08	$1.30	$1.32	$1.36
Advertising & Inspection	.04	.04	.04			
Packing & Processing	.84	.86	.89			
Picking, Loading & Hauling	.34	.34	.35			
On Tree Equivalent				$1.33	.93	$1.67
Estimated Production Costs				.53	[illegible]	.56
Net to Grower before Interest, Taxes & Depreciation				$ .80	.35	1.11

GRAPEFRUIT	1946-47	1947-48	1948-49	Per Box 1946-47	Per Box 1947-48	Per Box 1948-49
Carloads Sold				7,094	6,660	7,641
Auction Sales at Terminal Markets				$3.29	$3.07	$3.77
Terminal Selling & Expenses				.07	.06	.06
Net at Terminal				3.22	3.01	3.71
Transportation Cost				.77	.90	1.06
Florida F.O.B. Equivalent				$2.45	$2.11	$2.65
Florida Marketing Charges	.08	.08	.08	1.08	1.09	1.10
Advertising & Inspection	.05	.05	.05			
Packing & Processing	.71	.72	.72			
Picking, Loading & Hauling	.24	.24	.25			
On Tree Equivalent				$1.37	$1.02	$1.55
Estimated Production Costs				.37	.38	.38
Net to Grower before Interest, Taxes & Depreciation				$1.00	$ .64	$1.17

TANGERINES	1946-47	1947-48	1948-49	Per Box 1946-47	Per Box 1947-48	Per Box 1948-49
Carloads Sold				2,403	2,209	2,737
Auction Sales at Terminal Markets				$4.34	$3.96	$5.10
Terminal Selling & Expenses				.09	.08	.08
Net at Terminal				4.25	3.88	5.02
Transportation Cost				.84	.95	1.12
Florida F.O.B. Equivalent				$3.41	2.93	$3.90
Florida Marketing Charges	.08	.08	.08	1.79	1.82	1.83
Advertising & Inspection	.07	.07	.07			
Packing & Processing	1.18	1.20	1.22			
Picking, Loading & Hauling	.46	.47	.46			
On Tree Equivalent				$1.62	$1.11	$2.07
Estimated Production Costs				.68	.68	.68
Net to Grower before Interest, Taxes & Depreciation				$ .94	$ .43	$1.39

Approximate Percentage all freight shipments sold at Auction -

	Oranges	Grapefruit	Tangerines
1940-41	32.6%	36.5%	47.3%
1941-42	32.7%	35.4%	45.5%
1943-43	27. %	36 %	48 %
1943-44	21.2%	24.8%	11.2%
1944-45	18.3%	26.2%	21.5%
1945-46	15.7%	26.8%	35.8%
1946-47	26.9%	43.4%	57.5%
1947-48	26.0%	37.8%	40.5%
1948-49	39.8%	35.3%	41.0%

NOTE: As has been stated above and in other pages of our report for many years, the citrus net prices do not allow any deductions for interest on investment, for taxes, or for depreciation of equipment. Pages 8-9 of this report, which include private as well as auction sales of citrus, should be used along with this page. Private sales of tangerines averaged considerably higher than auction sales in the last few seasons. See pages 40-41 for Citrus Price Analysis

The above marketing and transportation cost figures supplied by a large shipping organization.
These cost figures are slightly lower than this Bureau uses.

See pages 34-36 for Auction Cars and Price Averages - yearly comparison.

THIS DOES NOT INCLUDE ANY PRIVATE SALES.

RAIL AND BOAT SHIPMENTS
F.O.B. PRICES
AVERAGES ON PACKED FRUIT
Florida Citrus Exchange Report
Seasons 1909-10 to 1929-30

SEASONS	ORANGES	GRAPEFRUIT	TANGERINES	ALL CITRUS (Average)
1909-10	$1.15	$2.38	$1.81	$1.54
1910-11	1.51	1.95	2.60	1.65
1911-12	1.93	3.58	1.93	2.21
1912-13	1.97	2.01	1.92	1.96
1913-14	1.69	2.09	2.51	1.83
1914-15	1.47	1.32	1.66	1.42
1915-16	1.99	1.89	2.07	1.96
1916-17	1.94	2.07	2.82	2.01
1917-18	3.92	2.72	4.39	3.46
1918-19	3.69	3.18	4.79	3.52
1919-20	4.20	2.84	5.49	3.37
1920-21	2.57	2.46	4.96	2.65
1921-22	3.77	2.41	5.57	3.17
1922-23	2.96	2.10	4.39	2.62
1923-24	1.86	1.51	4.31	1.82
1924-25	3.51	1.94	4.43	2.74
1925-26	3.58	2.92	4.83	3.36
1926-27	2.78	2.25	3.50	2.58
1927-28	4.39	3.22	5.28	3.90
1928-29	1.99	2.07	2.91	2.09
1929-30	3.22	2.98	3.38	3.13

FLORIDA STATE MARKETING BUREAU AVERAGES
Seasons 1930-31 to 1948-49
(Comparable to above prices)
Gross f.o.b. Florida per box

1930-31	$2.15	$1.50	$1.95	$1.86
1931-32	2.30	1.50	2.05	1.95
1932-33	1.48	1.16	1.42	1.36
1933-34	1.71	1.51	1.80	1.65
1934-35	1.85	1.29	1.65	1.53
1935-36	2.30	1.87	2.00	2.14
1936-37	2.50	1.48	1.45	2.04
1937-38	1.56	1.53	1.86	1.57
1938-39	1.43	1.04	1.34	1.31
1939-40	1.62	1.42	2.00	1.60
1940-41	1.63	1.21	1.68	1.51
1941-42	2.10	1.80	2.85	2.06
1942-43	2.97	2.33	2.78	2.81
1943-44	3.10	2.47	3.70	3.01
1944-45	3.50	3.00	4.25	3.48
1945-46	3.55	2.65	4.80	3.44
1946-47*	2.62	2.18	3.75	2.59
1947-48*	2.10	1.80	2.90	2.08
1948-49*	2.80	2.35	3.70	2.74

See pages 40-41 for the Citrus Price Analysis covering period 1933-34 to 1948-49, inclusive. This analysis shows weighted average prices for truck shipments, Florida local consumption, and for fruit used in canning or other processing. * Rail, Boat and Truck Prices.

INSPECTIONS OF FLORIDA CITRUS FOR SHIPMENT
BY RAIL AND TRUCK BY COUNTIES
SEASON AUGUST 1, 1948 - JULY 31, 1949
BOXES (1-3/5 bushels)

County	Grapefruit	Oranges	Tangerines	Total 1948-49	Total 1947-48	Total 1946-47
Alachua	3,753	53,283	2,467	59,503	66,479	94,625
Brevard	373,392	694,864	11,349	1,079,605	1,307,940	1,031,952
Broward	-	12,160	-	12,160	81,445	131,345
Charlotte	43	121	-	164	-	-
Citrus	2,448	35,732	970	39,150	30,288	32,919
Dade	33,793	79,656	71	113,520	119,659	94,624
De Soto	44,653	562,652	68,551	675,856	730,362	730,778
Duval	92,269	488,905	75,851	657,025	613,340	749,246
Hardee	7,514	48,122	15,129	70,765	39,091	16,553
Hernando	60,021	165,556	90,908	316,485	179,809	322,347
Highlands	622,338	1,235,185	65,413	1,922,936	1,092,804	1,314,509
Hillsborough	380,473	1,150,746	95,745	1,626,964	1,345,913	1,743,932
Indian River	1,070,693	396,720	12,510	1,479,923	1,270,526	1,325,819
Lake	692,860	2,824,160	344,069	3,861,089	3,116,655	3,955,427
Lee	28,164	30,050	292	58,506	81,167	139,440
Manatee	125,300	39,677	40	165,017	198,681	199,464
Marion	172,342	1,323,166	46,297	1,541,805	1,446,657	1,588,329
Orange	988,104	6,410,200	754,805	8,153,109	7,071,162	7,622,162
Osceola	64,387	263,863	39,854	368,104	299,630	323,312
Palm Beach	50,180	70,587	4,354	125,121	111,300	146,280
Pasco	105,193	255,867	34,432	395,492	383,642	369,220
Pinellas	1,192,116	372,745	52,375	1,617,236	1,342,292	1,327,337
Polk	4,995,893	8,925,173	842,597	14,763,663	10,862,013	13,437,088
Putnam	14,890	179,864	42,271	237,025	198,508	260,350
St. Johns	77	16,280	-	16,357	29,291	27,910
St. Lucie	891,633	794,531	33,274	1,719,438	1,796,192	1,943,367
Sarasota	358	921	10	1,289	13,022	93,527
Seminole	304,750	1,283,458	199,809	1,788,017	1,641,566	1,917,621
Sumter	403	2,039	-	2,442	-	-
Volusia	80,422	634,256	124,791	839,469	689,425	865,123
Others	-	-	-	-	1,162	-
TOTAL	12,398,462	28,350,539	2,958,234	43,707,235	36,210,521	41,917,506
Total Crop	30,200,000	58,300,000	4,400,000	92,900,000	91,100,000	83,100,000

NOTE: Some commodities are produced in one County and inspected in another County. These inspections do not include fruit for processing and some other classes of fruit.

PERSIAN LIMES CERTIFIED FOR SHIPMENT 1948-49 SEASON
(In Terms of Equivalent Standard Boxes, 1-3/5 Buxhels)

County by Month	Dade	Highlands	Hillsborough	Pinellas	Polk	Volusia	Totals
July, 1948	38,408	5,169	4,301	504	5,143		53,525
Aug. "	25,061	1,272	225		2,334		28,892
Sept. "	15,439	1,241	472		131		17,283
Oct. "	9,881	517	456	65	1,380		12,299
Nov. "	4,844	785	49		432		6,110
Dec. "	4,908	764	39	38	158		5,907
Jan., 1949	3,723	484		19	228	497	4,951
Feb. "	1,914	311				246	2,471
Mar. "	4,323	78					4,401
Apr. "	3,491	219			172		3,882
May "	8,359	1,983	313	155	1,289		12,099
June "	41,288	2,784	1,506	1,361	3,344	162	50,445
State Total	161,639	15,607	7,361	2,142	14,611	905	202,265
Total 1947-48	129,084	14,133	5,733	1,576	11,161	-	161,687

Source: Citrus and Vegetable Inspection Division, Winter Haven, Florida.

CITRUS PRICE ANALYSIS 1932-33 TO 1948-49

		FLORIDA GROSS FOR MARKET OR EQUIVALENT PER BOX					EQUIV.	NET* TO GROWER		COST	PICKING
	BOX YIELD	RAIL & BOAT	TRUCKED OUT	FLORIDA CONSUMED	FLORIDA CANNED	GROSS ALL	ON TREE ALL	NET ALL	RAIL AND BOAT	PRODUCTION	PACKING MARKETING RAIL&BOAT (Costs)
ORANGES											
1932-33	14,964,800	$1.48	$1.00	$ .90	$ .70	$1.36	$ .62	$ .14	$ .10	$ .48	$ .90
1933-34	16,170,996	1.71	1.25	1.15	.80	1.59	.88	.42	.38	.46	.87
1934-35	15,589,039	1.85	1.35	1.25	.80	1.69	.98	.53	.50	.45	.90
1935-36	15,864,588	2.30	1.60	1.50	1.00	2.10	1.33	.88	.90	.45	.95
1936-37	19,460,788	2.50	1.90	1.70	1.25	2.31	1.48	1.06	1.15	.42	.93
1937-38	24,302,896	1.56	1.12	1.12	.36	1.41	.63	.25	.30	.38	.88
1938-39	30,015,287	1.43	1.15	1.15	.41	1.32	.54	.20	.25	.34	.84
1939-40	25,064,702	1.62	1.52	1.32	.19	1.37	.59	.17	.23	.42	.91
1940-41	28,752,089	1.63	1.58	1.28	.30	1.43	.72	.32	.36	.40	.87
1941-42	27,200,000	2.10	2.05	1.70	1.08	1.91	1.13	.69	.76	.44	.90
1942-43	37,200,181	2.97	2.91	2.50	1.70	2.72	1.35	1.45	1.56	.40	1.01
1943-44	46,200,000	3.10	3.10	2.60	2.02	2.81	1.61	1.31	1.35	.50	1.25
1944-45	42,800,000	3.50	3.50	3.00	2.60	3.17	2.23	1.73	1.79	.50	1.21
1945-46	49,800,000	3.55	3.55	3.10	2.63	3.25	2.32	1.84	1.83	.48	1.24
1946-47	52,800,000	2.62	2.62	2.35	.82	1.93	1.03	.50	.84**	.53	1.25
1947-48	58,400,000	2.10	2.10	1.90	.80	1.41	.65	.15	.28**	.50	1.32
1948-49	58,300,000	2.80	2.80	2.50	1.51	2.19	1.29	.79	.90**	.50	1.40
GRAPEFRUIT											
1932-33	11,925,630	$1.16	$ .50	$ .40	$ .32	$ .86	$ .27	$-.11	$-.07	$ .38	$ .85
1933-34	11,113,200	1.51	.90	.90	.53	1.19	.62	.23	.29	.39	.83
1934-35	15,243,060	1.29	.80	.70	.37	.88	.38	.01	.08	.37	.84
1935-36	11,504,067	1.87	1.20	1.10	.73	1.39	.85	.46	.61	.39	.87
1936-37	18,121,786	1.48	1.10	1.00	.55	1.09	.55	.25	.35	.30	.83
1937-38	14,378,760	1.53	1.10	1.10	.48	1.05	.54	.18	.35	.36	.82
1938-39	23,050,855	1.04	.80	.80	.22	.64	.21	-.09	-	.30	.74
1939-40	15,650,865	1.42	1.30	1.12	.33	.79	.39	-.01	.20	.40	.82
1940-41	24,387,041	1.21	1.10	.86	.37	.71	.33	-.02	.12	.35	.74
1941-42	19,100,000	1.80	1.70	1.45	.71	1.20	.74	.34	.60	.40	.80
1942-43	27,300,116	2.33	2.25	1.85	1.05	1.48	1.02	.67	1.10	.35	.88
1943-44	31,000,000	2.47	2.47	2.00	1.53	1.83	1.32	.92	1.00	.40	1.07
1944-45	22,300,000	3.00	3.00	2.60	1.91	2.24	1.76	1.36	1.53	.40	1.07
1945-46	32,000,000	2.65	2.65	2.40	1.39	1.77	1.12	.78	1.21	.34	1.10
1946-47	26,400,000	2.18	2.18	1.90	.65	1.25	.63	.26	.73**	.37	1.08
1947-48	29,300,000	1.80	1.80	1.60	.34	.82	.34	-.01	.36**	.35	1.09
1948-49	30,000,000	2.35	2.35	2.10	.57	1.38	.68	.33	.82**	.35	1.18

*Net to grower (or fruit owner) indicates the amount per box after deducting production and all other costs except interest, taxes and depreciation. The State Marketing Bureau "On Tree" average price may be obtained by adding Production Costs to "Net to Grower" return for All Fruit. ** Includes Truck Shipments.

CITRUS PRICE ANALYSIS 1932-33 TO 1948-49

		FLORIDA GROSS FOB MARKET OR EQUIVALENT PER BOX					EQUIV.	NET* TO GROWER		COST	PICKING PACKING
	BOX YIELD	RAIL & BOAT	TRUCKED OUT	FLORIDA CONSUMED	FLORIDA CANNED	GROSS ALL	ON TREE ALL	NET ALL	RAIL AND BOAT.	PRODUC-TION	MARKETING RAIL-BOAT
TANGERINES											(Costs)
1932-33	1,519,200	$1.42	$1.00	$ .90	$-	$1.32	$ .38	$-.18	$-.30	$ .56	$1.16
1933-34	1,992,091	1.80	1.40	1.25	-	1.68	.85	.29	.19	.56	1.05
1934-35	2,003,755	1.66	1.15	1.10	-	1.51	.76	.21	.16	.55	.95
1935-36	2,093,397	2.00	1.50	1.40	-	1.66	.97	.42	.35	.55	1.10
1936-37	3,018,634	1.45	1.15	1.05	-	1.37	.32	-.18	-.20	.50	1.15
1937-38	2,257,973	1.86	1.28	1.28	-	1.72	.66	.14	.18	.52	1.16
1938-39	3,381,873	1.34	1.05	1.05	-	1.27	.38	-.07	-.06	.45	.95
1939-40	2,257,545	2.00	1.90	1.70	-	1.95	.92	.42	.44	.50	1.06
1940-41	2,751,624	1.68	1.65	1.31	-	1.60	.58	.08	.10	.50	1.08
1941-42	2,100,000	2.85	2.80	2.40	-	2.77	1.67	1.09	1.11	.58	1.16
1942-43	4,200,149	2.78	2.70	2.25	-	2.72	1.38	.98	1.03	.40	1.35
1943-44	3,600,000	3.70	3.70	3.00	-	3.62	2.01	1.36	1.37	.65	1.68
1944-45	3,900,000	4.25	4.25	3.60	-	4.18	2.56	1.91	1.92	.65	1.68
1945-46	4,200,000	4.80	4.80	4.00	1.00	4.24	2.74	2.10	2.45	.64	1.71
1946-47	3,900,000	3.75	3.75	3.30	.80	2.99	1.58	.90	1.35*	.68	1.72
1947-48	3,400,000	2.90	2.90	2.60	.35	2.41	.88	.20	.40*	.68	1.82
1948-49	4,400,000	3.70	3.70	3.40	.46	2.93	1.42	.74	1.17*	.68	1.85
TOTAL CITRUS (And Average of All Citrus)											
1932-33	28,409,630	1.36	.80	.70	.33	1.15	.47	.02	.015	.45	.90
1933-34	29,276,287	1.65	1.19	1.08	.54	1.45	.78	.34	.336	.44	.87
1934-35	32,835,854	1.63	1.19	1.05	.38	1.33	.70	.27	.32	.43	.88
1935-36	29,462,052	2.14	1.48	1.37	.74	1.81	1.13	.69	.76	.44	.94
1936-37	40,601,208	2.04	1.58	1.43	.61	1.70	.98	.61	.75	.37	.92
1937-38	40,939,629	1.57	1.12	1.13	.46	1.30	.60	.22	.305	.38	.88
1938-39	56,447,995	1.31	1.07	1.04	.24	1.04	.41	.07	.15	.34	.82
1939-40	42,973,112	1.60	1.51	1.29	.28	1.17	.54	.12	.28	.42	.90
1940-41	55,890,754	1.51	1.49	1.18	.47	1.15	.55	.16	.27	.39	.85
1941-42	46,400,000	2.06	2.05	1.69	.83	1.66	1.00	.57	.74	.43	.89
1942-43	68,700,000	2.81	2.78	2.28	1.22	2.23	1.50	1.11	1.41	.39	1.01
1943-44	80,800,000	3.01	3.10	2.37	1.70	2.47	1.65	1.16	1.28	.49	1.24
1944-45	69,000,000	3.48	3.57	2.95	2.25	2.93	2.10	1.62	1.75	.48	1.25
1945-46	86,000,000	3.44	3.61	3.00	2.05	2.75	1.92	1.46	1.73	.46	1.25
1946-47	83,100,000	2.59	2.67	2.21	.75	1.76	.94	.44	.85**	.50	1.24
1947-48	91,100,000	2.08	2.13	1.89	.62	1.26	.58	.10	.31**	.48	1.29
1948-49	92,900,000	2.74	2.77	2.46	1.14	1.96	1.10	.63	.90**	.47	1.37

*Net to grower (or fruit owner) indicates the amount per box after deducting production and all other costs except interest, taxes and depreciation. The State Marketing Bureau "On Tree" average price may be obtained by adding Production Costs to "Net to Grower" return for All Fruits. ** Rail, Boat and Truck.

ESTIMATED PRICES PAID BY CANNERS AND PROCESSORS 1940-1949
(Florida Citrus Delivered to Canner's Door)

	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Average
ORANGES	$	$	$	$	$	$	$	$	$	$	$	$	$
1940-41			.21	.35	.55	.80	.85	.90	1.00	1.04	1.05	-	.80
1941-42				.74	.93	.91	1.10	1.20	1.25	1.35	1.40		1.076
1942-43				1.50	1.25	1.48	1.76	2.00	2.40	2.45	2.50		1.70
1943-44		2.03	2.03	2.03	1.86	1.63	1.87	2.27	2.25	2.20	2.37	2.37	2.02
1944-45		1.98	1.98	1.93	2.18	2.49	2.74	3.11	3.25	3.06	3.06		2.60
1945-46	2.49	2.49	2.41	2.52	2.37	2.31	2.62	3.00	3.66	3.68	3.50		2.83
1946-47	1.33	1.33	1.00	.55	.55	.54	.69	1.17	1.16	1.08	.79	.79	.82
1947-48		.87	.87	.80	.88	1.09	.91	.70	.65	.51	.49	.49	.80
1948-49	.46	.46	.53	.73	.96	1.20	1.70	2.20	3.10	3.40	3.00	LCL	1.51
GRAPEFRUIT													
1940-41			.20	.25	.27	.34	.36	.38	.46	.50	.50		.365
1941-42				.69	.67	.64	.76	.82	.80	.77	.77		.706
1942-43				.92	.96	1.08	1.20	1.32	1.47	1.50	1.50		1.05
1943-44		1.37	1.37	1.45	1.44	1.40	1.50	1.74	1.76	1.66	1.67	1.67	1.53
1944-45		1.83	1.83	1.83	1.85	2.01	2.17	2.19	2.20	1.92			1.91
1945-46	1.30	1.30	1.53	1.51	1.29	1.23	1.22	1.29	1.67	1.76	1.77	1.77	1.39
1946-47	1.18	1.19	1.18	.77	.60	.52	.53	.53	.44	.39	.40	.40	.65
1947-48		.51	.51	.44	.40	.36	.31	.28	.28	.25	.24	.24	.34
1948-49	.39	.39	.42	.42	.48	.60	.75	.83	.92	1.06	1.10	1.10	.57
TANGERINES													
1944-45						Few							
1945-46					1.00	1.00	1.00	1.00	1.00				1.00
1946-47			1.50	1.00	.60	.60	.65	.65					.80
1947-48			.50	.40	.35	.35	.35						.35
1948-49		.46	.46	.46	.46	.46	.46	.46					.46

FLORIDA CITRUS VOLUME CANNED OR PROCESSED
(Carloads of 400 Boxes)

ORANGES	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Total
1943-44		7	412	1,459	2,250	3,683	5,691	4,848	5215	3167	542	7	27,281
1944-45		209	2,233	3,227	5,378	7,131	8,511	6,514	2249	101			35,559
1945-46	LCL	1230	4,928	4,996	5,618	5,182	7,281	7,660	7819	3117	129		47,960
1946-47	LCL	1311	3,188	3,457	6,583	8,076	11,376	5,623	6046	3418	452	34	49,564
1947-48		756	4,537	9,746	13,865	14,100	8,278	7,621	8749	6388	1801	100	75,941
1948-49	4	1586	5,579	8,662	11,408	11,761	10,770	7,509	6871	2808	73	LCL	67,031
G.FRUIT													
1943-44		23	376	6,006	11,104	9,458	8,459	9,861	4347	1280	153	6	51,073
1944-45		908	5,796	10,534	10,759	5,310	2,663	1,292	465	28			37,835
1945-46	131	1236	3,020	5,000	9,194	7,438	9,082	9,395	7539	2899	377	1	55,312
1946-47	218	1983	4,338	4,149	6,558	4,602	6,889	6,304	3238	1206	150	26	39,661
1947-48		745	2,674	5,936	7,074	7,211	7,634	8,253	5178	2529	1161	225	48,620
1948-49	280	2009	5,480	6,183	7,973	7,272	6,676	2,910	1130	668	179	5	40,765
TANG.													
1944-45						7							7
1945-46					264	406	445	166	8				1,289
1946-47			235	845	927	287	32	1					2,327
1947-48			72	549	615	260	1						1,497
1948-49		46	728	818	776	103	18	9	LCL				2,498
TOTAL CITRUS													
1943-44		30	788	7,465	13,354	13,141	14,150	14,709	9562	4447	695	13	78,354
1944-45		1117	8,029	13,761	16,137	12,448	11,174	7,806	2714	129			73,401
1945-46	131	2466	7,948	9,996	15,076	13,026	16,808	17,221	15366	6016	506	1	104,561
1946-47	218	3294	7,761	8,451	14,068	12,965	18,297	11,928	9284	4624	602	60	91,552
1947-48		1501	7,283	16,231	21,554	21,571	15,913	15,874	13927	8917	2962	325	126,058
1948-49	284	3641	11,787	15,663	20,157	19,136	17,464	10,428	8001	3476	252	5	10,294

Note: All volume and value based on standard 1-3/5 bu. box.
See pages 26-33 for other citrus volume and values.

PRODUCTION AND UTILIZATION OF U.S. CITRUS CROP FOR 1947-48 SEASON.

(The 1948-49 comparable figures are not yet available.)

1947-48 ORANGES	Total Production	(a) Abandoned Production	Farm Disposition		Fresh Sales		Loose or Intrastate	Processed
			Farm Use	Total Sold	Total	Packed		
			(Thousand Boxes)					
Florida (b)	58,400	-	400	58,000	27,579	25,322	2,257*	30,421
California (b)	45,830	158	232	44,440	35,621	33,493	2,128	8,819
Texas (b)	5,200	-	70	5,130	4,831	-	-	299
Arizona (b)	780	6	14	760	578	-	-	182
Louisiana (b)	300	-	16	284	274	-	-	10
TOT.ORANGES	110,510	164	732	108,614	68,883			39,731
GRAPEFRUIT								
Florida (c)	33,000	3,700	140	29,160	9,709	8,638	1,071*	19,451
California (c)	2,380	22	20	2,838	2,157	2,147	10	681
Texas (c)	23,200	2,300	65	20,835	12,174	-	-	8,661
Arizona (c)	3,000	944	12	2,044	1,254	-	-	790
TOT.G-FRUIT	62,080	6,966	237	54,677	25,294			29,583
TANGERINES								
Florida	4,000	600	45	3,355	2,794	2,368	388*	599
ORANGES, GRAPEFRUIT, TANGERINES								
Florida	95,400	4,300	585	90,515	40,082	36,328	3,716*	50,471
California	48,710	180	252	47,278	37,778	35,640	2,138	9,500
Texas	28,400	2,300	135	25,965	17,005	-	-	8,960
Arizona	3,780	950	26	2,804	1,832	-	-	972
Louisiana	300	-	16	284	274	-	-	10
GRAND TOTAL	176,590	7,730	1,014	166,846	96,971			69,913
LIMES								
Florida	170	-	2	168	162	144	18	6
LEMONS								
California	12,700	12,700	15	12,685	8,535	8,335	200	4,150

---

* The Florida volumes of oranges, grapefruit and tangerines in this column are intrastate movement for local consumption and are in fact packed in some type of container. California markets in loose form 2,128,000 boxes of oranges, and 10,000 boxes of grapefruit.

(a) Abandoned production is the difference between the final production estimate and the volume used on and sold from the farm. This is presumed to be marketable fruit which could not be sold for one reason or another. It may have gone to charity or otherwise eliminated. It does not include wind blown fruit, drops, or frosted fruit which could not be used.

(b) The following are the estimated net weights per box for oranges: Florida, Texas, Louisiana, 90 pounds; California and Arizona, 77 pounds. (c) For grapefruit: Florida and Texas, 80 pounds; Arizona and California Desert Valleys, 65 pounds; Other California, 68 pounds.

The Production and Utilization figures of the Bureau of Agricultural Economics were used in the above tabulation for oranges, grapefruit and tangerines. Some changes were made in the arrangement and explanation of these figures to make a more compact table.

INTERSTATE TRUCK DISTRIBUTION, FLORIDA CITRUS FRUITS BY STATES - 1948-49 AND 1947-48 SEASONS-OCTOBER TO JUNE

(500 Boxes per Car)*

STATES	ORANGES		GRAPEFRUIT		TANGERINES		GRAND TOTAL	
	48-49 Cars	47-48 Cars	48-49 Cars	47-48 Cars	48-49 Cars	47-48 Cars	48-49 Cars	47-48 Cars
Alabama	1,406	791	176	69	80	61	1,662	921
Arkansas	313	141	54	6	9	2	376	149
California	16	-	4	-	-	-	20	-
Colorado	41	1	24	2	3	-	68	3
Connecticut	54	6	9	-	8	3	71	9
Delaware	37	17	9	1	3	3	49	21
Dist. of Columbia	673	359	242	97	66	41	981	497
Georgia	2,263	1,700	557	342	186	187	3,006	2,229
Illinois	1,833	842	448	89	239	128	2,520	1,059
Indiana	969	522	241	81	96	73	1,306	676
Iowa	137	12	67	-	8	-	212	12
Kansas	68	4	42	1	5	2	115	7
Kentucky	526	215	124	24	41	26	691	265
Louisiana	507	158	48	18	9	1	564	177
Maine	40	10	14	-	1	1	55	11
Maryland	780	349	265	81	93	67	1,138	497
Massachusetts	118	22	20	4	28	7	166	33
Michigan	510	229	177	44	48	36	735	309
Minnesota	144	68	36	1	6	5	186	74
Mississippi	499	303	17	6	12	11	528	321
Missouri	275	49	83	4	18	13	376	66
Nebraska	63	3	65	1	7	4	135	8
New Hampshire	3	-	-	-	-	-	3	-
New Jersey	347	77	67	15	29	10	443	102
New Mexico	6	-	1	-	-	-	7	-
New York	1,873	540	551	81	222	75	2,646	696
North Carolina	1,445	803	354	149	192	144	1,991	1,096
North Dakota	2	-	2	-	-	-	4	-
Ohio	1,073	235	378	48	116	46	1,567	329
Oklahoma	89	2	37	-	7	4	133	6
Pennsylvania	1,881	491	501	92	226	86	2,608	669
Rhode Island	54	13	12	1	12	14	78	28
South Carolina	1,300	871	313	188	124	108	1,737	1,167
South Dakota	2	-	-	-	-	-	2	-
Tennessee	886	395	155	39	56	34	1,097	467
Texas	757	17	123	1	21	9	901	27
Vermont	43	14	9	3	2	1	54	18
Virginia	1,042	620	459	215	104	83	1,605	918
West Virginia	253	168	59	25	27	17	339	210
Wisconsin	179	38	45	-	13	1	237	39
Out of State	30	15	7	4	2	4	39	23
CANADA	70	57	42	12	8	7	120	76
TOTAL CARS	22,607	10,157	5,837	1,744	2,127	1,314	30,571	13,215
N.W. Florida	276	236	58	48	24	19	358	303
GR.TOT.-Cars	22,883	10,393	5,895	1,792	2,151	1,333	30,929	13,518

* The above tabulation is the only place in this report where citrus truck shipments have been converted on basis of 500 boxes to car -- all other conversions of citrus at 400 boxes.

Destinations fairly complete were available for following periods:
1948-49 -- October 15 - June 19
1947-48 -- October 15 - May 31

RECAPITULATION OF RAIL DISTRIBUTION, FLORIDA CITRUS FRUITS
BY STATES - 1948-49 AND 1947-48 SEASONS

(Approximately 500 boxes per car)

STATE	ORANGES		GRAPEFRUIT		TANGERINES		MIXED CITRUS		GRAND TOTAL	
	48-49 Rail Cars	47-48 Rail Cars	48-49 Rail Cars	47-48 Rail Cars	48-49 Rail Cars	47-48 Rail Cars	48-49 Rail Cars	47-48 Rail Cars	48-49 Rail Cars	47-48 Rail Cars
Alabama	228	569	40	97	-	3	16	57	284	726
Arkansas	7	9	-	3	-	2	6	2	13	16
California	55	-	26	-	-	-	3	-	84	-
Colorado	103	9	70	5	4	6	28	1	205	21
Connecticut	851	757	195	169	57	39	45	15	1,148	980
Delaware	9	39	2	-	-	-	-	-	11	39
Dist.of Columbia	332	552	191	245	3	10	11	36	537	843
Florida	-	4	1	-	-	-	-	-	1	4
Georgia *	287*	607*	81*	167*	3*	5*	64*	188*	435*	967*
Idaho	6	-	8	-	-	-	11	-	25	-
Illinois	1,126	1,437	623	283	167	181	113	84	2,029	1,985
Indiana	98	306	46	67	5	13	28	20	177	406
Iowa	73	67	84	5	-	5	9	3	166	80
Kansas	22	11	17	4	-	1	15	1	54	17
Kentucky	200	453	42	64	3	16	17	38	262	571
Louisiana	170	334	20	3	-	1	2	11	192	349
Maine	132	163	38	25	-	4	30	7	200	199
Maryland	732	1,174	393	588	77	91	234	220	1,436	2,073
Massachusetts	2,737	2,603	1,096	957	228	233	519	386	4,580	4,179
Michigan	1,289	1,160	649	340	237	200	175	93	2,350	1,793
Minnesota	176	53	192	44	22	21	53	6	443	124
Mississippi	39	110	-	1	-	-	6	19	45	130
Missouri	710	561	312	82	86	81	99	13	1,207	737
Montana	24	1	15	6	2	-	15	1	56	8
Nebraska	88	44	79	23	1	2	5	1	173	70
New Hampshire	11	15	-	-	-	-	4	8	15	23
New Jersey	587	944	181	268	5	15	23	36	796	1,263
New Mexico	2	-	1	-	-	-	-	-	3	-
New York	8,101	10,034	4,116	4,822	1,059	905	2,128	1,708	15,404	17,469
North Carolina	490	869	239	263	9	20	94	241	832	1,393
North Dakota	1	5	4	-	-	-	17	1	22	6
Ohio	1,755	2,392	634	377	266	286	326	196	2,981	3,251
Oklahoma	76	17	22	5	-	2	1	-	99	24
Oregon	83	1	83	23	12	5	22	-	200	29
Pennsylvania	3,574	4,747	1,673	1,764	591	653	1,052	862	6,890	8,026
Rhode Island	369	434	82	121	28	24	66	7	545	586
South Carolina	151	428	17	29	2	9	39	150	209	616
South Dakota	15	1	15	1	-	-	8	-	38	2
Tennessee	833	1,209	54	109	26	40	135	130	1,048	1,488
Texas	103	30	32	6	1	1	3	-	139	37
Utah	72	10	41	18	3	-	6	-	122	28
Vermont	4	7	-	-	-	-	-	7	4	14
Virginia	365	689	189	319	3	9	47	84	604	1,101
Washington	206	7	149	50	19	10	16	-	390	67
West Virginia	185	252	44	15	5	9	48	61	282	337
Wisconsin	351	293	173	55	13	16	60	32	597	396
Wyoming	1	1	4	-	-	1	5	-	10	2
CANADA	862	375	1,567	360	113	51	338	31	2,880	817
TOTAL	27,691	33,783	13,540	11,783	3,050	2,970	5,942	4,756	50,223	53,292

*Does not include Savannah.

Abstract of tables in Florida 1948-49 Citrus Summary.

FLORIDA TOBACCO

Flue Cured (Bright Leaf) Type No. 14

Year	Acreage	Production	Estimated Farm Value
1932	2,000	1,200,000 Lbs.	$ 132,000 or 11¢ per Lb.
1933	5,000	3,700,000	444,000 " 12¢ " "
1934	4,700	3,408,000	682,000 " 20¢ " "
1935	7,000	6,020,000	1,066,000 " 17.8¢ " "
1936	8,000	7,200,000	1,584,000 " 22¢ " "
1937	16,800	14,112,000	2,978,000 " 21.1¢ " "
1938	16,300	15,892,000	3,226,000 " 20.3¢ " "
1939	29,500	20,650,000	2,540,000 " 12.3¢ " "
1940	12,700	11,748,000	2,056,000 " 17.5¢ " "
1941	11,300	8,192,000	1,745,000 " 21.3¢ " "
1942	13,000	11,180,000	3,611,000 " 32.3¢ " "
1943	13,600	11,832,000	4,827,000 " 40.8¢ " "
1944	19,000	17,100,000	6,190,000 " 36.2¢ " "
1945	19,400	17,169,000	6,662,000 " 38.8¢ " "
1946	20,400	19,176,000	9,147,000 " 47.7¢ " "
1947	22,800	23,256,000	9,070,000 " 39.0¢ " "
1948	16,400	16,564,000	7,391,000 " 47.6¢ " "
1949	18,400	20,240,000	7,610,240 " 37.6¢ " "

Sun Cured (Filler 1932-1939 Binder, 1936-49) Dark Leaf (Types 45 and 56)

Year Summer	Acreage	Type	Production	Estimated Farm Value	Per Pound
1932	200	F	140,000	$ 14,000	10¢
1933	100	F	82,000	9,000	11¢
1934	300	F	360,000	43,000	11.9¢
1935	700	F	770,000	104,000	13.5¢
1936	400	F & B	380,000	51,000	13.4¢
1937	700	F & B	784,000	106,000	13.5¢
1938	900	F & B	1,116,000	151,000	13.5¢
1939	1,000	F & B	960,000	127,000	13.2¢
1940	1,000	B	1,300,000	174,000	13.4¢
1941	600	B	450,000	65,000	14.4¢
1942	600	B	630,000	110,000	17.5¢
1943	200	B	166,000	37,000	22.0¢
1944	100	B	70,000	19,000	27.0¢
1945	100	B	93,000	31,000	33.0¢
1946	100	B	105,000	58,000	55.0¢
1947	200	B	140,000	66,000	47.0¢
1948	100	B	70,000	42,000	60.0¢
1949	100	B	85,000	-	-

NOTE: F: Filler (Type 45) discontinued after 1939. B: Binder (Type 56) started in 1936 and continued to date.

Shade Grown-Air Cured (Dark Leaf) Wrapper Type 62

Year	Acreage	Production	Estimated Farm Value
1932	2,000	1,970,000 Lbs.	$ 690,000 or 35¢ per Lb.
1933	1,100	990,000	317,000 " 32¢ " "
1934	1,600	1,424,000	854,000 " 59.9¢ " "
1935	2,100	1,890,000	1,228,000 " 65¢ " "
1936	2,000	2,050,000	1,414,000 " 69¢ " "
1937	2,100	1,890,000	1,304,000 " 70¢ " "
1938	2,400	2,712,000	1,953,000 " 72¢ " "
1939	2,500	2,150,000	1,570,000 " 73¢ " "
1940	3,200	3,280,000	2,296,000 " 70¢ " "
1941	3,300	3,069,000	2,240,000 " 73¢ " "
1942	2,800	2,968,000	2,879,000 " $1.04 " "
1943	2,600	2,912,000	3,087,000 " 1.49 " "
1944	2,600	2,925,000	4,212,000 " 1.44 " "
1945	2,400	2,820,000	4,230,000 " 1.50 " "
1946	3,000	2,970,000	6,534,000 " 2.20 " "
1947	3,300	3,416,000	9,052,000 " 2.65 " "
1948	3.600	4,212,000	9,056,000 " 2.15 " "
1949	3,900	4,563,000	- - -

NOTE: Flue Cured Type No. 14 is generally known as cigarette tobacco.
Shade Grown Type 62 is generally known as cigar wrapper tobacco.
Sun Cured Type 56 is generally known as cigar filler tobacco.

(Auction Volume and Value on next page.)

FLORIDA AUCTION SALES
(Flue Cured Tobacco - Type 14)

Revised figures of the Tobacco Branch, P.M.A., U.S. Department of Agriculture.

Season	Producer's Sales			Resales		
	Pounds	Value	Average	Pounds	Value	Average
1940	7,903,700	$1,300,069	$16.45	689,982	$107,670	$15.60
1941	5,726,227	1,211,684	21.16	707,736*	143,309*	20.25*
1942	7,269,574	2,381,502	32.76	748,850	227,892	30.43
1943	8,110,475	3,308,024	40.79	1,135,708	470,026	41.39
1944	12,330,566	4,496,293	36.46	1,255,424	417,923	33.29
1945	12,148,104	4,742,528	39.04	1,219,300	452,203	37.09
1946	13,192,482	6,353,484	48.16	1,595,702	706,444	44.27
1947	16,596,141	6,510,858	39.23	2,020,091	740,141	36.64
1948	12,346,106	5,896,173	47.76	1,698,258	782,141	46.06
1949	16,262,984	6,129,689	37.69	1,707,535	579,258	33.92

*Estimated

1949 Sales by Individual Markets

Market	Producers		Resales	
	Pounds	Value	Pounds	Value
Jasper	3,122,799	$1,131,006	369,408	$114,939
Lake City	4,483,162	1,714,472	367,016	117,590
Live Oak	8,657,023	3,284,211	971,111	346,729
Totals	16,262,984	$6,129,689	1,707,535	$579,258

ALL FLORIDA TOBACCO

Season	Acres	Production Pounds	Farm Value	Price per Lb.
1939	33,000	23,760,000	$4,237,000	$.178
1940	16,900	16,328,000	4,526,000	.277
1941	15,200	11,711,000	4,050,000	.345
1942	16,400	14,778,000	6,600,000	.446
1943	16,400	14,910,000	7,951,000	.533
1944	21,700	20,095,000	10,421,000	.518
1945	21,900	20,082,000	10,923,000	.543
1946	23,500	22,251,000	15,739,000	.707
1947	26,300	26,812,000	18,183,000	.678
1948	20,100	20,846,000	17,016,000	.816
1949	22,400	24,888,000	(Not Complete)	

Cigars, Cigarettes, Chewing Tobacco, Smoking Tobacco, and Snuff Manufactured in The United States, by Calendar Years, 1943-47

Year	Cigars		Cigarettes	
	Large Thousands	Small Thousands	Large Thousands	Small Thousands
1943	5,363,027	125,480	6,111	296,173,333
1944	5,198,679	123,340	26,870	323,583,888
1945	5,274,675	98,167	82,416	332,164,670
1946	5,617,700	92,262	1,658	350,038,093
1947	5,280,000	80,000	800	370,200,000

Year	Chewing Tobacco				Smoking Tobacco	Snuff	Total Chewing, Smoking, and Snuff Tobacco
	Plug 1,000 Lb.	Twist 1,000 Lb.	Fine-Cut 1,000 Lb.	Scrap 1,000 Lb.	1,000 Lb.	1,000 Lb.	1,000 Lb.
1943	58,945	6,257	4,460	51,414	162,834	43,179	327,089
1944	61,655	6,498	4,092	52,867	139,861	41,962	306,935
1945	59,704	6,723	3,970	47,748	168,523	43,834	330,502
1946	51,810	5,773	3,756	46,117	106,414	39,361	253,231
1947	47,359	5,152	3,724	42,224	104,578	39,187	242,224

Compiled from annual and monthly reports of the Commissioner of Internal Revenue, except cigars and cigarettes for 1947 which are estimates by the Tobacco Branch, PMA. No later information immediately available.

PEANUTS: PRICE OF FARMERS' STOCK TO GROWERS (x)
SOUTHEASTERN SPANISH
Cents per Pound

Crop Yr 1/	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.
# 1920	5.2	4.2	4.0	2.6	2.9	2.8	2.2	2.2	2.1	2.0	1.8	2.3
# 1921	2.8	-	2.8	2.5	2.6	3.0	3.5	3.3	3.4	3.9	4.6	4.4
# 1922	3.6	-	5.3	5.6	6.4	7.2	7.0	7.4	7.8	8.0	-	-
# 1923	-	-	7.0	6.6	7.0	7.1	6.8	6.4	6.0	6.0	6.8	7.1
# 1924	5.2	4.4	4.4	4.4	4.4	4.6	4.4	4.2	4.0	3.8	3.8	3.6
# 1925	4.0	3.6	3.6	3.4	4.0	4.9	4.8	4.7	4.6	5.2	5.3	5.5
# 1926	5.2	4.6	5.2	5.4	5.9	6.6	6.8	6.7	6.2	5.8	5.8	4.0
# 1927	3.6	3.6	3.9	4.6	4.6	4.3	4.1	4.0	3.8	4.0	3.6	3.4
# 1928	3.6	3.6	4.3	4.4	4.4	4.2	3.8	3.6	3.6	3.5	3.2	3.2
# 1929	3.4	3.2	3.2	3.0	2.6	2.8	3.1	2.9	2.8	2.8	3.0	3.2
# 1930	3.6	3.2	3.1	2.8	3.0	3.4	3.4	3.6	3.6	3.5	3.2	2.8
# 1931	1.5	1.2	1.2	1.2	1.2	1.2	1.4	1.2	1.0	.8	.8	1.3
* 1932	1.7	1.4	1.3	1.1	1.3	1.3	1.4	1.6	2.3	2.6	2.9	2.9
* 1933	2.4	2.6	2.7	2.7	3.0	2.9	2.95	2.8	2.8	2.9	2.9	2.9
* 1934 2/	3.0	2.9	3.2	3.6	4.2	5.2	5.5	4.9	4.8	4.2	3.6	-
* 1935	3.3	3.1	3.1	3.1	2.9	2.9	3.05	3.1	3.2	3.2	3.6	3.5
* 1936	3.4	3.2	3.3	4.0	4.6	4.5	4.7	4.6	4.3	3.7	3.7	3.1
* 1937	2.9	3.2	3.4	3.3	3.4	3.4	3.4	3.1	3.1	3.2	3.2	3.1
* 1938	3.1	3.2	3.2	3.3	3.3	3.2	3.1	3.1	3.0	3.1	3.1	3.2
* 1939	3.3	3.5	3.4	3.4	3.6	3.5	3.4	3.3	3.1	2.9	2.8	2.9
* 1940	3.2	3.2	3.2	3.2	3.3	3.5	3.7	3.7	3.8	3.9	4.2	4.4
* 1941	4.5	4.5	5.0	5.4	5.4	6.2	8.0	8.2	7.5	6.4	6.5	6.5
* 1942	6.4	7.0	7.3	8.4	8.6	8.5	8.45	8.45	8.45	-	-	-
% 1943	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4	7.4
% 1944	8.2	8.4	8.5	8.5	8.7	8.4	8.3	8.2	8.4	8	8	-
% 1945	8.6	8.6	8.6	8.6	8.6	8.6	8.6	8.6	8.6	8.6	8.6	-
% 1946	8.9	9.2	9.5	10.0	8.9	9.1	9.4	9.8	10.0	-	-	-
% 1947	10.5	10.5	10.5	10.5	10.5	10.5	-	-	-	-	-	-
% 1948	11.0	11.1	11.1	11.0	10.6	10.8						

SOUTHEASTERN RUNNERS (x)
Cents per Pound

Crop Yr 1/	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.
# 1920	-	2.2	2.1	1.8	2.0	1.8	1.4	1.2	1.3	1.4	1.5	1.8
# 1921	2.2	-	2.2	2.2	2.3	2.8	3.2	3.0	3.0	-	-	-
# 1922	-	-	3.9	3.8	4.7	5.2	-	-	-	-	-	-
# 1923	-	-	5.2	5.0	5.4	5.3	5.0	4.6	-	4.2	5.6	-
# 1924	-	3.5	3.6	3.2	3.2	3.6	3.5	3.2	3.0	3.3	3.5	3.2
# 1925	-	3.0	3.0	2.9	3.3	3.8	3.8	3.5	-	-	-	-
# 1926	-	-	4.2	4.1	4.8	5.4	-	-	-	-	-	-
# 1927	-	2.8	3.0	3.6	3.7	3.5	3.6	-	-	-	-	-
# 1928	-	-	3.5	3.8	3.6	3.7	3.2	-	2.6	-	-	-
# 1929	-	2.2	2.2	2.0	2.0	2.0	-	-	-	-	-	-
# 1930	-	2.3	2.2	-	-	-	-	-	-	-	-	-
# 1931	-	1.0	1.1	1.0	.8	.8	1.0	.9	.8	.6	.8	-
* 1932	-	1.1	1.0	.8	1.1	1.1	1.2	1.3	1.8	2.0	-	-
* 1933	-	2.3	2.3	2.3	2.6	2.7	2.8	2.7	2.7	2.7	2.7	2.7
* 1934 1/	-	2.6	2.7	3.2	3.5	4.4	4.2	-	-	4	-	-
* 1935	2.6	2.7	2.7	2.7	2.7	2.7	2.6	2.7	2.8	2.7	3.3	3.4
* 1936	2.7	2.6	2.8	3.4	3.7	3.6	3.9	4.2	3.7	3.5	3.0	2.8
* 1937	-	2.8	2.9	2.8	2.8	2.8	2.9	2.5	2.5	2.7	2.8	-
* 1938	2.7	2.8	2.8	2.8	2.8	2.8	2.7	2.6	2.5	2.6	2.6	2.7
* 1939	2.8	2.9	2.9	2.9	2.9	2.9	2.8	2.8	2.6	2.5	2.4	2.4
* 1940	2.7	2.8	2.8	2.9	2.9	3.0	3.1	3.2	3.3	3.4	3.7	3.9
* 1941	3.9	4.0	4.2	4 4	4.4	5.0	6.9	7.0	6.7	5.4	5.5	6.0
* 1942	5.7	6.3	6.5	7.4	7.7	7.7	7.7	7.7	7.7	-	-	-
% 1943	-	6.8	6.8	6.8	6.8	6.8	6.8	6.8	6.8	6.9	6.9	6.9
% 1944	-	7.4	7.7	7.9	7.8	6.3	7.5	7.2	7.7	7.8	8.0	-
% 1945	-	7.8	7.8	7.8	7.8	7.8	7.8	7.8	7.8	7.8	7.8	-
% 1946	7.6	8.1	8.7	9.3	-	-	-	-	-	-	-	-
% 1947	9.6	9.6	9.6	9.6	9.6	9.6	-	-	-	-	-	-
% 1948	10.3	10.3	10.4	10.3	10.3	10.2						

# Price to growers f.o.b. country shipping point basis. (x)B.A.E. U.S.Dept. of Agric.

* Price to growers f.o.b. delivery point basis.

% Most trading based on percentage of sound meat content, damage, foreign material and other factors as shown on the CCC Support Schedule of Prices; delivered to customary or established receiving point.

1/ Crop year begins Nov. 1 in Virginia-North Carolina section; early Sept. in the Southeastern States, or early Aug. in the Southwestern States.

2/ Farmers signing acreage-restriction contracts, as most commercial producers did, were eligible to receive in addition from the U.S. Dept. of Agriculture, 0.4¢ a pound for peanuts harvested in 1934, or not less than $2.00 an acre of the allotted peanut acreage. (Above tabulation prepared by Florida State Marketing Bu.)

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS
(For Selected Years)

	1920			1922		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	8,668,000	$ 9,795,000	Bu.	8,888,000	$ 7,110,000
Cotton	Bale	20,000	1,782,000	Bale	28,000	2,902,000
Tobacco	Lbs.	4,200,000	2,041,000	Lbs.	3,330,000	1,551,000
Peanuts(Picked & Threshed)	Lbs.	40,000,000	2,520,000	Lbs.	26,875,000	1,344,000
Sweet Potatoes	Bu.	2,300,000	3,174,000	Bu.	1,680,000	2,184,000
Cow Peas	Bu.	Included in Other Field Crops				
Oats	Bu.	255,000	230,000	Bu.	180,000	137,000
Velvet Beans	Tons	Included in Other Field Crops				
Hay	Tons	83,000	1,768,000	Tons	64,000	1,254,000
Sugar Cane Syrup	Gals.	3,675,000	3,454,000	Gals.	2,320,000	1,067,000
Sugar-Raw	Tons	No Record		Tons	No Record	
Black Strap Molasses	Gals.	No Record		Gals.	No Record	
Pecans	Lbs.	440,000	141,000	Lbs.	880,000	309,000
Total Incomplete			$24,905,000			$17,858,000
Other Field Crops	Misc.		* 2,000,000	Misc.		* 1,400,000

	1924			1925		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,200,000	$ 7,848,000	Bu.	8,262,000	$ 7,684,000
Cotton	Bale	21,000	2,451,000	Bale	43,000	4,561,000
Tobacco	Lbs.	4,091,000	1,916,000	Lbs.	5,810,000	1,743,000
Peanuts(Picked & Threshed)	Lbs.	28,350,000	1,474,000	Lbs.	23,400,000	1,147,000
Sweet Potatoes	Bu.	1,764,000	2,699,000	Bu.	1,840,000	3,336,000
Cow Peas	Bu.	54,000	170,000	Bu.	36,000	129,000
Oats	Bu.	148,000	138,000	Bu.	125,000	85,000
Velvet Beans	Tons	59,000	844,000	Tons	53,000	753,000
Hay	Tons	58,000	1,119,000	Tons	51,000	1,061,000
Sugar Cane Syrup	Gals.	1,350,000	1,350,000	Gals.	1,650,000	1,732,000
Sugar-Raw	Tons	No Record		Tons	No Record	Very Lightt
Black Strap Molasses	Gals.	No Record		Gals.	No Record	Very Light
Pecans	Lbs.	1,300,000	449,000	Lbs.	1,916,000	609,000
Total Incomplete			$20,458,000			$22,890,000
Other Field Crops	Misc.		* 1,500,000	Misc.		* 1,500,000

	1928			1930		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,073,000	$ 7,427,000	Bu.	5,886,000	$ 5,180,000
Cotton	Bale	22,000	1,091,000	Bale	56,000	2,720,000
Tobacco	Lbs.	8,635,000	2,539,000	Lbs.	9,748,000	2,672,000
Peanuts(Picked & Threshed)	Lbs.	28,175,000	1,352,000	Lbs.	26,520,000	902,000
Sweet Potatoes	Bu.	1,700,000	2,465,000	Bu.	1,360,000	1,646,000
Cow Peas	Bu.	48,000	162,000	Bu.	86,000	233,000
Oats	Bu.	135,000	92,000	Bu.	112,000	87,000
Velvet Beans	Tons	68,000	877,000	Tons	44,000	572,000
Hay	Tons	54,000	1,048,000	Tons	48,000	830,000
Sugar Cane Syrup	Gals.	1,485,000	1,262,000	Gals.	1,530,000	994,000
Sugar-Raw	Tons	1,000	No Record	Tons	27,000	No Record
Black Strap Molasses	Gals.	134,000	No Record	Gals.	2,202,000	No Record
Pecans	Lbs.	2,000,000	545,000	Lbs.	1,150,000	302,000
Total Incomplete			$19,670,000			$16,138,000
Other Field Crops	Misc.		* 2,500,000	Misc.		* 2,000,000

* Estimated by Marketing Bureau

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS (Cont'd.)

(For Selected Years)

	1932			1935		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	6,350,000	$ 2,921,000	Bu.	7,496,000	$ 5,322,000
Cotton	Bale	18,000	556,000	Bale	31,000	1,576,000
Tobacco	Lbs.	3,310,000	836,000	Lbs.	8,680,000	2,398,000
Peanuts(Picked & Threshed)	Lbs.	24,070,000	1,361,000	Lbs.	38,430,000	1,114,000
Sweet Potatoes	Bu.	1,560,000	1,232,000	Bu.	1,610,000	1,368,000
Cow Peas	Bu.	94,000	99,000	Bu.	88,000	154,000
Oats	Bu.	75,000	28,000	Bu.	112,000	77,000
Velvet Beans	Tons	60,000	255,000	Tons	70,000	700,000
Hay	Tons	41,000	369,000	Tons	52,000	582,000
Sugar Cane Syrup	Gals.	1,760,000	634,000	Gals.	2,660,000	984,000
Sugar-Raw	Tons	37,000**	(1,295,000)	Tons	42,000**	(1,470,000)
Black Strap Molasses	Gals.	3,489,000	248,900	Gals.	3,292,000	395,040
Pecans	Lbs.	625,000	80,000	Lbs.	1,400,000	153,000
Total Incomplete			$ 9,914,900			$16,293,040
Other Field Crops	Misc.		* 1,500,000	Misc.		* 2,000,000

	1938			1940		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,760,000	$ 4,656,000	Bu.	8,418,000	$ 5,893,000
Cotton	Bale	26,000	1,158,000	Bale	21,000	1,102,000
Tobacco	Lbs.	19,720,000	5,325,000	Lbs.	16,328,000	4,552,000
Peanuts(Picked & Threshed)	Lbs.	56,250,000	1,688,000	Lbs.	68,400,000	1,915,000
Sweet Potatoes	Bu.	1,400,000	1,274,000	Bu.	900,000	810,000
Cow Peas	Bu.	48,000	75,000	Bu.	40,000	67,000
Oats	Bu.	140,000	69,000	Bu.	154,000	102,000
Velvet Beans	Tons	57,000	661,000	Tons	59,000	649,000
Hay	Tons	70,000	763,000	Tons	70,000	665,000
Sugar Cane Syrup	Gals.	1,815,000	817,000	Gals.	1,120,000	560,000
Sugar-Raw	Tons	**(920,000)	**(3,680,000)	Tons	**(970,000)	**(4,268,000)
Black Strap Molasses	Gals.	5,497,000	** (657,000)	Gals.	5,170,000	**(1,125,000)
Pecans	Lbs.	3,575,000	309,000	Lbs.	3,564,000	341,000
Total Incomplete			$21,132,000			$22,049,000
Other Field Crops	Misc.		* 2,500,000	Misc.		* 3,000,000

	1941			1942		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,200,000	$ 5,904,000	Bu.	7,766,000	$ 8,154,000
Cotton	Bale	18,000	1,461,000	Bale	17,000	1,534,000
Tobacco	Lbs.	11,711,000	4,052,000	Lbs.	14,778,000	6,808,000
Peanuts(Picked & Threshed)	Lbs.	57,800,000	2,312,000	Lbs.	65,550,000	3,343,000
Sweet Potatoes	Bu.	1,260,000	1,399,000	Bu.	1,122,000	1,560,000
Cow Peas	Bu.	45,000	102,000	Bu.	45,000	122,000
Oats	Bu.	160,000	107,000	Bu.	210,000	176,000
Velvet Beans	Tons	65,000	845,000	Tons	53,000	742,000
Hay	Tons	64,000	813,000	Tons	72,000	979,000
Sugar Cane Syrup	Gals.	1,750,000	962,000	Gals.	1,980,000	1,287,000
Sugar-Raw	Tons	949,000	3,768,000	Tons	949,000	3,072,000
Black Strap Molasses	Gals.	5,157,000	**(928,000)	Gals.	4,100,000	**(750,000)
Pecans	Lbs.	4,672,000	474,000	Lbs.	4,600,000	752,000
Total Incomplete			$23,127,000			$29,279,000
Other Field Crops	Misc.		* 3,000,000	Misc.		* 3,500,000

* Estimated by the State Marketing Bureau

** Figures in parenthesis ( ) are estimates from unofficial sources.

PRODUCTION VOLUME AND FARM VALUE OF FLORIDA PRINCIPAL FIELD CROPS

PRODUCTION VOLUME

(Thousands Omitted)

Florida Commodity	Units	1940	1941	1942	1943	1944	1945	1946	1947	1948	(Prelim Estimate) 1949
Corn	Bu.	8,418	7,200	7,766	8,522	7,550	7,755	6,910	8,292	6,910	8,638
Cotton	Bale	21	18	17	16	13	8	6	10	15	18
Tobacco	Lbs.	16,328	11,711	14,778	14,240	20,095	20,082	22,251	6,812	20,846	24,888
Peanuts(Picked & Threshed)	Lbs.	68,400	57,800	65,550	74,800	62,500	66,000	46,500	69,300	85,250	57,376
Sweet Potatoes	Bu.	900	1,260	1,122	1,365	1,165	1,024	1,088	1,275	960	924
Cow Peas	Bu.	40	45	45	36	32	36	40	36	32	#
Oats	Bu.	154	160	210	300	704	900	720	600	399	288
Velvet Beans	Bu.	59	65	53	62	48	56	44	44	45	#
Hay	Tons	70	64	72	66	65	63	57	63	69	58
Sugar Cane **Syrup**	Gals.	1,120	1,750	1,930	2,040	2,400	2,090	1,980	2,400	1,980	#
Sugar-Raw	Tons	970	949	949	694	780	1,042	1,037	920	1,044	1,234
Black Strap Molasses *	Gals.	5,170	5,157	4,100	4,100	5,400	5,700	6,711	5,400	6,000	#
Pecans	Lbs.	3,564	4,672	4,600	4,524	5,100	4,234	4,526	2,774	5,475	4,088

FARM VALUE

(Thousands Omitted)

Florida Commodity	Units	1940	1941	1942	1943	1944	1945	1946	1947	1948	(Prelim Estimate) 1949 #
Corn	Bu.	$ 5,893	$ 5,904	$ 8,154	$13,124	$12,231	$13,339	$13,060	$17,662	$12,092	
Cotton	Bale	1,102	1,461	1,534	1,678	1,343	896	983	1,703	2,299	
Tobacco	Lbs.	4,552	4,052	6,808	9,203	10,421	10,923	15,739	18,188	17,016	
Peanuts(Picked & Threshed)	Lbs.	1,915	2,312	3,343	5,236	4,688	5,280	3,860	6,514	7,736	
Sweet Potatoes	Bu.	810	1,399	1,560	3,044	2,821	2,652	2,959	3,226	2,515	
Cow Peas	Bu.	67	102	122	141	153	174	220	252	179	
Oats	Bu.	102	107	176	342	887	963	994	990	678	
Velvet Beans	Bu.	649	845	742	1,240	1,152	1,568	1,408	1,408	1,440	
Hay	Tons	665	813	979	1,063	1,079	1,147	1,037	1,273	1,138	
Sugar Cane Syrup	Gals	560	962	1,287	2,040	2,280	2,090	3,168	3,000	1,584	
Sugar-Raw	Tons	4,268	3,768	3,072	3,040	3,487	6,387	7,207	6,302	6,421	
Black Strap Molasses *	Gals	1,125	928	750	750	1,000	1,200	1,200	1,080*	1,200*	
Pecans	Lbs.	341	474	752	1,060	1,143	1,010	1,507	628	605	
Group Totals		$22,049	$23,127	$29,279	$41,961	$42,685	$47,629	$53,342	$62,226	$54,903	50,000 a
Other Field Crops (a)		$ 3,000	$ 3,000	$ 3,500	$ 4,500	$ 5,000	$ 5,200	$ 5,500	$ 6,000	$ 5,500	$ 5,000

* Estimates from unofficial sources. All other production and farm value figures supplied by the U.S. Agricultural Statisticians, B.A.E., Federal Building, Orlando, Florida, except

a. Estimated by Florida State Marketing Bureau.

# No estimate by U.S. Bureau of Agricultural Economics as of September 20.

JACKSONVILLE JOBBING MARKET
SALES TO RETAILER OR EQUIVALENT SALES
MONTHLY SIMPLE AVERAGES

EGGS -(Florida White Grade A-24 oz. per Dozen)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1921	74.3	48.6	36.0	31.3	30.5	31.9	42.7	47.9	50.0	59.4	64.8	60.0	48.1
1922	48.0	40.7	26.5	29.4	28.3	34.7	37.5	37.5	52.8	55.0	62.8	53.9	40.6
1923	49.6	36.0	30.0	29.5	29.0	33.8	39.5	42.6	49.8	56.3	59.3	58.0	42.8
1924	47.4	44.6	26.6	25.8	28.5	32.5	39.0	43.6	52.1	62.0	66.2	64.9	44.4
1925	56.8	45.3	30.2	33.5	30.3	38.6	44.4	48.4	55.2	64.0	65.6	67.0	48.3
1926	57.2	42.1	31.3	34.1	32.5	36.1	41.6	44.4	51.8	62.2	61.0	57.1	45.9
1927	47.6	35.9	28.0	29.2	27.9	29.7	33.9	41.4	49.0	52.1	55.0	50.4	40.0
1928	48.0	32.4	30.0	29.7	28.2	33.4	36.5	41.7	48.3	54.8	55.0	48.5	40.4
1929	42.2	34.5	35.1	29.2	30.2	33.7	39.3	43.2	45.2	54.1	55.3	54.0	41.5
1930	47.1	35.4	28.5	27.0	27.0	27.0	30.6	34.9	38.2	45.4	43.9	40.9	35.5
1931	32.0	22.0	23.0	22.0	20.0	21.0	25.0	28.5	32.0	37.5	38.0	33.0	27.9
1932	26.5	16.5	18.0	15.5	14.7	18.3	21.0	25.0	28.2	31.5	32.6	35.2	23.5
1933	23.5	17.0	15.5	15.5	17.3	16.3	22.9	25.5	31.4	33.0	32.0	34.4	23.7
1934	28.7	25.6	19.2	19.8	20.1	23.5	28.0	31.6	36.8	38.0	40.0	40.0	29.3
1935	35.8	31.8	23.0	24.9	26.3	26.8	31.5	35.6	39.0	39.3	37.0	40.6	32.6
1936	33.5	31.2	23.5	22.9	24.1	25.7	31.9	34.0	37.5	38.4	41.9	43.4	32.3
1937	29.8	27.5	25.1	25.5	24.2	25.8	30.1	33.0	37.2	38.1	39.6	38.0	31.2
1938	32.5	26.6	22.2	22.3	25.0	25.7	31.5	32.8	36.3	36.3	36.8	40.1	30.7
1939	30.8	24.3	21.6	21.9	22.6	23.0	29.1	29.6	28.8	32.4	33.9	30.9	27.4
1940	31.4	26.8	20.7	20.8	21.2	23.5	28.8	31.7	34.5	36.4	36.3	38.2	29.2
1941	33.3	25.4	24.1	25.2	28.4	31.2	36.8	39.2	41.4	42.0	44.5	42.2	34.5
1942	40.0	31.5	30.5	31.4	31.4	34.7	39.5	45.0	46.1	48.0*	48.0*	48.0*	39.7
1943	47.6	38.7	38.0	38.4*	43.0*	43.6*	45.9*	51.0*	54.8*	58.0*	57.0*	53.6*	47.6
1944	49.3*	39.7*	37.1*	37.0*	38.2*	41.4*	45.2*	50.3*	55.1*	58.6*	59.9*	59.0*	47.6
1945	50.0*	44.0*	37.8*	42.4*	42.6*	44.9*	49.3*	54.4*	57.8*	58.6*	59.9*	58.8*	50.0
1946	49.7*	40.7*	39.0*	39.1*	42.4*	45.0**	50.7	55.6	60.4	66.2	61.3	62.8	51.1
1947	59.4	52.4	51.1	52.4	56.0	57.4	62.3	64.9	70.1	73.0	74.0	75.5	62.5
1948	68.6	57.2	54.1	55.4	57.7	60.2	63.3	68.2	70.7	74.7	75.8	69.8	64.6
1949	64.3	52.9	53.7	55.2	53.5	60.7	64.1	67.0	69.7				

FRYERS (Heavy Breed)

1921	39.1	39.7	46.9	49.5	46.6	35.0	31.2	30.3	34.0	35.5	29.1	29.0	37.2
1922	29.0	29.5	38.4	40.0	40.0	35.5	31.5	29.0	31.0	29.0	29.0	29.0	32.6
1923	29.5	31.0	36.5	37.0	39.8	36.7	30.0	30.0	33.0	32.4	31.0	31.0	33.1
1924	32.7	36.6	37.8	42.0	42.5	37.4	32.7	30.7	34.0	33.0	31.5	34.3	35.4
1925	41.4	44.0	45.6	45.9	43.7	39.4	36.0	35.0	38.0	39.0	37.0	38.6	40.3
1926	43.5	48.0	49.7	50.0	48.3	38.3	37.8	35.3	35.0	35.0	35.3	37.1	41.1
1927	42.0	45.0	45.0	46.3	43.0	35.1	31.8	30.0	30.0	31.1	33.1	35.8	37.4
1928	37.0	36.2	38.9	39.0	39.0	38.1	34.5	31.2	33.0	35.3	35.3	35.7	36.3
1929	26.0	36.2	39.1	42.8	37.7	37.3	31.0	31.1	35.0	34.2	36.1	36.8	36.1
1930	33.1	32.9	33.6	36.7	32.7	32.8	24.5	27.4	29.0	29.0	29.0	29.0	30.9
1931	30.0	31.0	37.0	40.0	37.0	35.0	29.0	27.0	27.5	26.0	24.5	24.5	30.6
1932	24.4	23.2	27.1	26.8	23.9	23.5	18.0	17.3	18.0	18.7	17.3	14.9	21.0
1933	14.6	20.4	22.2	24.3	22.1	18.0	15.4	16.1	17.0	17.0	15.7	16.1	18.2
1934	17.6	20.2	23.9	25.2	24.9	22.5	20.1	18.7	19.7	20.0	20.5	20.5	21.2

(Cont'd.)

JACKSONVILLE JOBBING MARKET
SALES TO RETAILER OR EQUIVALENT SALES
MONTHLY SIMPLE AVERAGES

FRYERS (Heavy Breed)--(Cont'd.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1935	21.5	24.3	26.1	25.9	22.8	23.1	21.2	20.3	21.0	22.4	23.2	24.5	23.0
1936	25.5	25.6	27.0	27.2	25.7	25.5	23.1	22.6	22.3	21.2	20.5	20.0	23.7
1937	22.3	24.0	24.1	27.0	24.1	25.3	25.5	24.5	25.8	27.1	26.7	27.7	25.4
1938	25.8	24.6	27.2	27.8	24.0	21.8	20.5	21.6	22.9	22.9	23.0	23.6	23.8
1939	23.4	21.6	21.9	24.8	22.0	21.8	22.5	21.9	21.0	22.0	22.3	22.1	22.3
1940	22.0	21.8	22.8	22.6	24.3	23.2	21.4	20.5	21.5	21.9	20.8	21.5	22.0
1941	21.8	22.4	23.8	24.3	23.0	22.8	22.8	22.2	22.6	23.0	23.9	24.0	23.1
1942	24.1	23.7	24.2	25.6	26.8	27.5	27.4	27.5	29.0	30.5	30.5	31.4	27.4
1943	31.8	31.8	31.8	31.9*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	31.0
1944	30.6*	30.6*	30.6*	31.0*	32.6*	31.8*	31.1*	30.6*	30.6*	30.6*	30.6*	30.6*	30.9
1945	30.6*	31.6*	32.0*	32.4*	32.8*	31.6*	31.4*	31.3*	31.3*	31.3*	31.3*	31.3*	31.6
1946	31.6*	32.1*	32.5*	32.9*	33.3*	33.0**	39.1	38.5	43.3	47.1	41.5	41.2	37.2
1947	36.2	32.5	34.5	35.0	37.4	38.0	38.5	39.0	41.2	37.9	34.7	36.8	36.8
1948	40.2	39.4	41.9	42.4	40.3	41.7	39.7	39.0	39.4	38.5	38.4	38.3	39.9
1949	32.9	30.9	32.9	34.6	31.3	30.7	30.2	32.5	32.4				

HENS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1921	33.6	32.6	31.7	29.3	26.9	26.3	25.1	26.2	30.3	31.8	26.0	26.0	28.8
1922	26.0	26.0	26.7	25.5	25.4	24.0	24.0	24.0	27.5	26.0	26.0	26.0	25.6
1923	26.0	26.0	26.0	25.0	23.0	23.0	20.9	21.1	24.7	26.0	24.3	24.7	24.2
1924	27.8	26.0	26.4	26.0	27.0	25.1	24.0	26.6	29.4	30.0	28.6	27.8	27.1
1925	31.6	29.2	29.7	28.0	28.0	26.6	25.9	29.0	30.0	31.0	28.1	29.3	28.7
1926	30.7	30.2	32.5	31.8	31.9	30.0	30.0	29.7	31.0	31.0	30.2	31.1	30.7
1927	30.0	30.0	29.8	29.1	29.0	24.7	23.7	25.6	26.0	26.0	25.0	25.0	26.9
1928	25.0	25.0	25.0	25.0	24.5	23.0	21.9	21.1	23.9	27.2	25.5	24.5	24.3
1929	24.8	26.4	2818	28.8	27.4	29.3	28.0	29.0	31.2	29.5	29.5	29.8	28.5
1930	29.8	30.0	28.5	27.5	26.6	24.5	22.5	22.6	23.0	22.8	23.0	23.0	25.3
1931	23.0	20.0	22.0	24.0	23.0	22.0	21.0	20.0	21.5	23.0	22.5	22.0	22.0
1932	20.5	18.6	18.7	19.0	17.5	16.1	14.5	14.5	15.5	16.7	17.0	14.4	16.9
1933	13.2	13.5	13.0	14.7	14.1	13.1	13.0	14.6	15.8	16.7	15.4	14.0	14.3
1934	14.3	15.5	16.0	15.5	18;8	16.0	15.7	14.8	16.6	17.2	17.8	17.5	16.1
1935	17.5	17.8	18.3	18.0	18.0	18.7	18.2	18.4	19.3	21.0	21.7	20.6	19.0
1936	20.0	19.9	19.5	20.3	20.8	20.5	20.9	20.7	20.2	19.6	19.6	18.7	20.1
1937	18.7	19.3	18.6	18.5	19.0	19.5	16.8	16.0	17.5	18.7	20.2	20.7	18.6
1938	20.1	19.0	19.9	19.7	19.0	19.3	19.4	18.7	20.2	20.2	21.0	21.2	19.8
1989	21.4	20.7	20.4	21.1	19.3	18.8	17.8	18.2	16.9	16.9	17.9	15.3	18.7
1940	16.2	16.7	17.5	17.5	17.1	16.2	15.5	16.1	16.5	18.5	17.8	17.2	16.9
1941	17.6	18.1	19.0	19.9	19.8	20.8	20.7	20.5	21.1	21.5	23.0	23.1	20.4
1942	23.9	22.8	23.0	23.6	23.2	21.5	21.0	21.8	24.9	26.5	26.5	27.8	23.9
1943	29.3	29.3	29.3	29.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.8
1944	27.1*	28.1*	27.1*	27.5*	29.2*	28.4*	27.6*	27.1*	27.1*	27.1*	27.1*	27.1*	27.5
1945	27.1*	28.1*	28.5*	28.9*	29.3*	28.1*	27.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.7
1946	27.6*	28.1*	28.5*	28.9*	29.3*	28.1**	29.1	29.2	35.0	40.6	35.2	35.0	31.2
1947	33.1	34.5	38.1	36.4	34.3	32.6	32.8	33.9	36.4	36.5	37.4	37.9	35.3
1948	40.5	40.2	41.7	42.8	43.0	43.0	40.3	38.0	39.9	40.0	40.0	40.9	40.9
1949	39.4	39.0	39.3	40.0	36.0	30.5	29.4	32.0	34.0				

POULTRY AND EGG WHOLESALE PRICES
TAMPA MARKET (January 1, 1939-September 30, 1949)

WHITE EGGS (Standard 24 oz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1939	31.2	24.5	22.1	23.4	23.4	25.0	30.5	29.0	31.6	34.3	35.8	32.5	28.6
1940	31.5	29.2	21.5	22.1	22.3	24.2	29.5	32.5	35.9	37.5	37.1	38.6	30.2
1941	34.6	26.2	24.2	26.0	28.4	32.0	27.5	40.0	51.1	43.3	45.1	43.5	35.2
1942	41.9	33.2	31.2	33.0	32.4	35.5	41.0	46.1	47.3	49.0C	49.0	49.0	40.7
1943	48.7	40.1	39.0	43.0	43.0	43.1	47.1	51.3	55.0	58.3	57.3	53.8	48.3
1944	46.5	40.5	37.1	37.0	38.6	40.6	44.3	50.5	52.2	58.6	60.0	59.1	47.1
1945	49.3	44.0	38.2	41.8	42.0	44.8	49.3	55.0	57.9	58.7	60.1	59.0	50.0
1946	49.9	41.8	39.0	39.3	42.0	45.1C	51.1	56.0	61.2	67.0	62.8	63.8	51.5
1947	58.7	55.0	52.2	52.3	57.0	58.2	63.3	66.4	70.8	74.0	75.0	76.0	63.2
1948	69.6	58.2	55.2	56.3	58.0	60.5	64.5	68.8	71.2	75.6	76.8	70.3	65.4
1949	64.8	54.3	54.1	56.4	58.6	61.6	64.8	68.0	71.5	-	-	-	-

HENS (Heavy Breed)

1939	19.1#	17.8	17.9	17.9	17.5	17.3	16.9	16.0	16.6	17.2	16.4	16.6	17.2
1940	17.1	17.1	17.3	18.0	17.0	16.5	14.8	14.7	16.8	16.6	17.5	17.5	16.7
1941	17.5	18.9	18.9	19.5	19.0	20.2	21.0	20.5	21.1	23.0	23.7	24.0	20.6
1942	24.5	24.0	23.1	24.4	24.3	22.5	22.3	22.0	23.9	26.0C	26.0	26.0	24.1
1943	28.5	29.5	29.4	29.4	29.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	28.2
1944	27.4	27.4	27.4	27.4	29.6	28.4	27.4	27.4	27.4	27.4	27.4	27.4	27.7
1945	27.5	27.8	28.8	29.2	29.6	28.5	27.6	27.4	27.3	27.3	27.3	27.3	27.9
1946	27.3	28.3	28.5	28.7	29.5	28.7C	24.8	25.1	31.2	35.6	32.1	32.0	29.3
1947	31.4	31.4	36.1	35.5	30.8	30.0	30.8	31.4	31.5	33.0	34.7	37.0	32.8
1948	38.5	36.0	36.0	36.0	36.0	36.0	34.7	33.0	34.3	37.0	38.1	39.0	36.2
1949	39.1	39.0	39.1	38.7	37.2	31.1	30.0	31.1	33.0	-	-	-	-

FRYERS (Heavy Breed)

1939	19.1#	17.3	19.8	20.8	18.6	19.8	19.3	18.2	18.6	19.4	19.1	19.0	18.9
1940	21.5	19.5	19.3	21.5	21.3	22.4	18.6	17.9	19.4	19.5	19.7	19.4	20.0
1941	19.2	20.2	21.4	22.0	19.7	20.7	22.2	22.5	22.7	23.0	23.7	24.0	21.8
1942	25.8	24.0	23.5	25.3	26.7	27.0	27.6	29.0	29.9	31.0C	31.0	31.0	27.7
1943	33.0	31.5	31.6	31.9	31.1	30.9	30.9	30.9	30.9	30.9	30.9	30.9	31.3
1944	30.9	30.9	30.9	31.2	33.1	31.9	30.9	30.9	30.9	30.9	30.9	30.9	31.2
1945	31.0	31.3	32.3	32.7	33.1	32.0	31.7	31.7	31.6	31.6	31.6	31.6	31.8
1946	31.6	32.6	32.8	33.0	33.8	33.5C	35.2	38.1	40.4	47.3	43.0	44.6	37.1
1947	39.9	32.9	34.4	35.5	36.7	37.0	39.3	41.4	41.7	40.0	34.0	38.3	37.6
1948	40.5	40.5	41.6	44.4	42.3	44.0	41.2	39.0	39.6	38.8	39.1	40.0	40.2
1949	34.4	30.8	32.3	34.5	31.0	30.7	29.4	32.2	32.2	-	-	-	-

Tampa prices not officially available prior to 1939.

POULTRY AND EGG WHOLESALE PRICES

MIAMI MARKET (January 1, 1939-September 30, 1949)

WHITE EGGS (Standard 24 oz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1939	35.1	27.3	24.3	25.0	24.9	Unavailable			33.8	37.2	39.5	36.5	31.5
1940	36.5	35.3	26.0	25.8	25.5	25.8	31.8	35.0	38.4	43.1	40.0	42.9	N
1941	38.3	31.7	28.1	29.0	31.6	34.1	38.6	41.5	43.1	45.0	47.8	48.0	N
1942	43.0	41.0	33.0	35.0	35.0	42.0	47.0	49.0	51.0	52.0C	52.0	52.0	44.4
1943	52.0	44.0	42.0	44.5	44.5	46.5	49.6	53.9	57.5	60.9	59.8	55.2	50.9
1944	51.5	47.5	44.5	44.5	44.5	45.5	50.0	54.5	57.6	58.0	60.5	59.3	51.5
1945	50.8	45.6	43.2	43.2	43.2	45.6	49.9	54.7	58.3	59.2	60.5	59.6	51.2
1946	50.7	45.5	43.2	43.2	43.2	45.8C	50.3	52.0	57.0	63.6	61.0	59.2	50.5
1947	53.1	52.0	52.2	57.6	54.5	53.7I	62.6	66.9	72.4	75.6	76.0	77.9	62.9
1948	66.6	52.0	53.9	56.7	54.0	60.0	62.4	66.7	70.0	71.8	75.4	74.3	63.6
1949	68.8	55.5	53.5	55.1	58.3	60.6	63.9	67.0	69.8				

HENS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1939	24.5	23.6	24.0	23.3	21.5	Unavailable			21.7	24.0	23.5	22.8	23.2
1940	22.5	22.0	22.0	22.0	22.0	22.0	22.0	22.3	22.0	23.5	23.0	23.0	22.4
1941	23.0	23.0	23.0	23.0	23.5	24.5	26.5	25.0	25.0	25.0	25.5	26.0	24.4
1942	27.0	27.0	30.0	30.0	30.0	30.0	30.0	30.0	32.0	32.0C	28.0	28.0	29.5
1943	28.0	28.0	28.0	28.0	28.0	28.0	(- - No quotations on account of consider-						
1944	able price ceiling confusion - -)						29.7	29.7	29.7	29.7	29.7	29.7	29.7
1945	29.7	28.5	29.9	31.6	29.1	28.7	27.8	27.5	27.5	27.5	27.5	27.5	28.5
1946	27.5	27.5	27.5	27.5	31.4	32.4C	32.1	32.8	38.7	31.9	38.8	40.0	32.3
1947	41.4	40.6	41.9	41.3	40.9	38.3I	35.6	35.0	37.4	38.6	38.7	39.0	39.1
1948	40.9	43.3	44.4	45.0	42.6	39.3	38.5	39.0	38.3	37.8	37.3	36.7	40.3
1949	32.6	40.4	41.3	43.7	38.6	33.1	31.3	33.3	35.4				

FRYERS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1939	24.3	24.7	26.0	25.0	23.4	Unavilable			23.9	25.0	24.5	23.8	24.5
1940	23.5	22.9	23.0	23.0	23.0	23.0	23.0	24.6	25.0	24.1	24.0	24.0	23.6
1941	25.0	25.0	27.0	26.5	25.0	25.0	26.0	25.0	25.0	25.0	26.0	27.0	25.6
1942	30.0	30.0	30.0	30.0	32.0	35.0	35.0	35.0	37.0	37.0C	32.0	32.0	33.0
1943	32.0	32.0	32.0	32.0	32.0	32.0	(- - No quotations on account of consider-						
1944	able price ceiling confusion - -)						33.2	33.2	33.2	33.2	33.2	33.2	33.2
1945	33.2	32.0	33.4	35.2	32.2	32.5	32.0	32.0	32.0	32.0	32.0	32.0	32.5
1946	32.0	32.0	32.0	32.0	35.9	37.1C	38.7	38.5	44.0	46.3	43.4	45.0	38.1
1947	39.2	35.0	39.6	40.0	41.3	43.0I	43.0	43.0	45.7	42.6	39.6	40.5	41.0
1948	45.1	46.2	46.7	49.4	45.3	44.2	42.3	42.0	41.2	40.1	39.4	38.7	43.3
1949	34.6	30.7	33.1	35.5	31.9	30.5	30.0	32.8	32.7				

JACKSONVILLE LIVESTOCK MARKET
(Substantially Southeastern Prices)

	COWS		CALVES		STEERS		HOGS	
	Medium	Common	Good	Medium	Good	Medium	No. 1	No. 2
	100 Lbs.		100 Lbs.		100 Lbs.		100 Lbs.	
1930								1930
3-4	5.00-6.00	4.00-5.50	7.00-8.25	5.50-7.00	7.00-8.50	6.00-7.00	8.50	7.50
9-5	3.75-4.50	3.25-3.75	5.00-6.50	4.00-5.00	5.00-6.00	4.00-5.00	9.25-9.50	8.25-8.50
1931								1931
3-3	3.50-4.25	2.50-3.50	5.50-6.50	4.75-5.50	5.50-6.75	4.50-5.50	6.00	5.50
9-4	2.50-3.25	2.00-2.75	4.00-5.00	3.00-4.00	4.00-4.75	3.00-4.25	5.25	4.75
1932								1932
3-4	2.50-3.00	1.75-2.50	3.50-4.75	3.00-4.00	3.50-4.25	3.00-3.75	3.50	3.20
9-6	2.25-2.75	1.25-2.00	3.75-4.25	3.00-3.50	4.00-5.25	3.50-4.25	3.75	3.50
1933								1933
3-7	2.00-2.50	1.50-2.00	3.25-3.75	3.00-3.25	3.50-4.25	3.00-3.50	2.65	2.40
9-5	2.00-2.75	1.00-2.00	3.25-3.75	2.50-3.25	3.75-4.25	3.00-3.75	3.75-4.00	3.50-3.75
1934								1934
3-6	2.25-2.75	1.50-2.25	4.00-4.75	3.00-4.00	4.00-4.50	3.50-4.00	3.75-4.00	3.50-3.75
9-4	2.00-2.50	1.00-2.00	3.50-4.25	2.50-3.75	4.00-4.25	3.25-4.00	5.40-5.60	4.90-5.90
1935								1935
3-5	3.50-4.00	1.75-3.25	5.50-6.50	3.75-5.25	6.25-7.25	5.00-6.25	7.00-7.25	6.25-6.50
6-7	3.25-4.50	2.00-3.50	5.25-6.25	4.50-5.50	6.00-7.50	4.75-6.00	7.25-7.50	6.50-6.75
9-6	2.75-4.25	2.00-2.75	5.50-6.50	4.50-5.50	5.50-6.25	4.00-5.25	9.25-9.75	8.75-9.25
12-6	3.25-4.50	2.50-3.25	5.00-5.75	4.00-5.25	5.75-6.75	4.75-6.00	7.75-8.00	7.25-7.50
1936								1936
3-6	4.00-5.00	3.25-4.00	5.75-6.50	4.50-5.75	6.00-7.00	5.00-6.00	7.50-7.75	7.00-7.25
6-5	4.25-5.00	3.50-4.25	5.25-6.00	4.50-5.25	6.25-7.00	5.75-6.50	8.00-8.50	7.50-8.00
9-4	3.75-4.50	3.00-3.75	5.00-6.00	4.25-5.00	5.50-6.00	4.50-5.50	9.00-9.50	8.50-9.00
12-4	3.50-4.00	2.75-3.50	5.00-6.00	4.25-5.25	5.25-6.00	4.50-5.25	8.60-8.90	8.10-8.40
1937								1937
3-12	4.00-4.50	3.25-4.00	5.25-5.75	4.00-5.25	6.00-7.25	5.00-6.50	8.00-8.40	7.60-7.90
6-4	4.50-5.00	3.50-4.25	5.75-6.50	4.75-5.50	7.00-8.00	5.50-6.75	9.50-10	9.00-9.50
9-7	4.00-5.25	3.00-4.00	5.50-6.00	4.50-5.25	6.00-7.25	5.00-6.25	8.75-9.00	8.25-8.50
12-7	4.00-4.50	3.00-4.00	5.00-5.50	4.00-5.25	6.00-7.00	5.00-6.00	6.25-6.65	6.00-6.40
1938								1938
3-4	4.25-5.00	3.25-4.25	5.25-6.50	4.50-5.50	6.25-7.00	5.50-6.50	6.75-7.75	6.25-7.25
6-7	4.50-5.25	3.50-4.25	5.50-7.00	4.50-5.50	6.50-7.50	5.50-6.50	7.70	7.20
9-6	4.00-5.00	3.00-4.00	5.00-6.00	4.50-5.25	6.25-7.00	5.50-6.50	7.00	6.50
12-3	4.00-4.50	3.00-4.00	5.50-6.75	4.50-5.50	6.50-7.50	5.50-6.50	6.00	5.50
1939								1939
3-4	4.75-5.50	3.75-4.75	6.50-7.50	5.00-6.50	7.00-8.00	6.00-7.00	6.85	6.30
6-3	5.00-5.75	4.00-5.00	6.00-7.50	5.00-6.00	6.50-8.00	5.50-6.50	6.00	5.50
9-2	4.50-5.25	4.00-4.75	5.75-7.25	4.75-5.75	6.50-7.50	5.50-6.50	5.90	5.40
12-2	4.50-5.25	3.75-4.50	6.00-7.25	5.00 6.00	7.00-7.75	6.00-7.00	4.90	4.65
1940								1940
3-2	5.00-5.75	4.00-5.00	6.25-7.25	5.25-6.25	7.00-8.00	6.00-7.00	5.00	4.75
6-1	4.75-5.25	3.75-4.75	6.50-7.50	5.50-6.50	7.00-8.25	6.00-7.00	5.25	5.00
9-7	4.25-5.00	3.75-4.50	6.00-7.00	5.00-6.00	6.75-7.75	5.50-6.75	6.75	6.50
12-7	4.25-5.00	4.00-4.50	6.00-7.00	5.00-6.00	7.00-8.25	6.00-7.00	5.65	5.40
1941								1941
3-1	5.25-6.00	4.50-5.25	6.25-7.50	5.25-6.50	7.50-8.75	6.50-7.50	6.50	6.00
6-7	5.25-6.25	4.25-5.25	6.75-7.75	5.50-6.50	7.75-8.50	6.75-7.75	8.90	8.40
9-6	5.50-6.75	4.50-5.50	7.50-8.75	6.50-7.50	8.00-9.00	7.00-8.00	10.25	9.75
12-5	5.50-6.50	4.25-5.50	7.00-8.00	6.00-7.00	7.50-8.50	6.50-7.50	8.25	7.75
1942								1942
3-6	7.50-8.25	5.75-7.25	8.20-10	6.75-8.00	9-10.50	8.00-9.00	11.25	10.75
6-6	7.00-8.50	6.00-7.00	9.00-11	7.00-9.00	10-11.50	8.75-10	12-13.00	11.5-12.5
9-4	7.50-8.50	6.25-7.50	10-11.00	8.00-10	9.75-11¼	8.00-10	12.75-13¼	12¼-12.75
12-4	7.50-8.50	6.00-7.25	10.00-11¼	8.00-10	9.25-11	8.00-9.25	11.50-12	11-11.50
1943								1943
3-5	9.00-11	7.50-8.75	11.00-13	9.00-11	11-13.50	9.00-11	13.75-14¼	13¼-13.75
6-4	9-10.50	7.00-8.75	11.00-13¼	9.50-11	11-13.50	9½-11.25	13¼-13.75	12.75-13¼
Sept	9.00-10.5	8.00-9.00	12-13.50	12.00-13	13.00	12.00-13	13.50-14¼	12.75-13.5
Dec	8.50-10	7.25-8.50	12-12.50	11-11.50	12-15.30	9.50-12	11¼-12.50	10.5-11.75
1944								1944
Mch	9.75-11	9-10.00	12-14.00	11-12.00	13.25-15	11.5-13.5	12-13.25	11¼-12.50
June	9.25-10.5	8.00-9.00	13-14.00	11-12.00	13.5-15	10-13.50	12-13.00	11.25-12¼
Sept	8.25-10	6.75-8.30	12-14.00	9.50-11½	12½-14½	9.50-12¼	13-14.25	12-14.00
Dec.	8.60-10	7.25-8.50	12.50-14	9.75-12	12.50-14½	9.75-13	12-13.25	11¼-13¼

JACKSONVILLE LIVESTOCK MARKET (Cont'd)
(Substantially Southeastern Prices)

	COWS		CALVES		STEERS		HOGS	
	Medium	Common	Good	Medium	Good	Medium	No. 1	No. 2
	100 lbs.		100 lbs.		100 lbs.		100 lbs.	
1945								
Jan	9.25-10½	8.00-9.50	12.75-14½	10.50-13	13.50-15	11.00-13	12-14.35	13¼-13.75
Feb	9.50-10½	9.00-9.50	14-15.50	11.50-14	14-15.25	11.50-14	13.35-14.35	13-14.35
Mch	9.75-11	9.25-9.75	14.00-15	12.00-14	14-15.50	12.00-14	14¼-14.35	13.75-14.35
Apr	10-11.50	9.25-10	14-15.50	12.00-14	14.25-15½	12.00-14	14¼-14.35	14¼-14.35
May	9.75-11½	9.00-10	13.50-14	11.50-13½	14.50-16	12.50-14½	14¼-14.35	14¼-14.35
June	9.50-11	9.00-9.50	13.50-15	11.00-13	14-15.50	12-14.50	14¼-14.35	14¼-14.35
July	10-11.50	9.25-10	13.50-15	11.00-13	14-15.50	11.50-14	14¼-14.35	14¼-14.35
Aug.	9.50-11½	8.50-9.50	13-14.50	9.50-13	14-15.50	11.25-13	14¼-14.35	14¼-14.35
Sept	9.50-11	8.00-9.00	12.00-15	9.50-12¼	13½-15½	11.00-13	14¼-14.35	14¼-14.35
Oct	9.50-11	8.00-9.25	12.50-14	11.00-13	13½-14½	11.50-13	14-14.35	14-14.35
Nov	9.50-11½	8.50-9.50	12.50-14	11½-13½	13.50-15	11-13.50	14-14.35	14-14.35
Dec	9.50-11½	8.50-9.50	13.00-14	11.00-13	13.00-15	11.00-13	13.75-14.35	13.75-14.35
1946								
Jan	10.00-13	8.50-10	13½-14½	11.00-14	14½-16½	12.00-14	14-14.35	13.75-14.35
Feb	11-13.50	9.50-10½	14-15.50	11.50-14½	14.50-17	12.50-15	14¼-14.35	13.75-14.35
Mch	11.00-14	10.00-11	14.00-16	12.50-15	14.50-17	12.50-16	14.35only	14.35only
Apr	11.50-14	10-11.50	14.50-16½	13.50-16	14.50-17	12.50-16	14.35only	14.35only
May	11.50-13½	10.50-11½	14.50-16½	12-15.50	15.00-17	13.00-16	14.35only	14.35only
June	12.00-14	10-12.50	14.50-17	12.00-16	16.00-18	12.50-16	14.35only	14.35only
July	11.50-16	11.50-14½	14.00-18	12-16.50	17.00-19	13.00-17	15.50-19	15.50-19
Aug	11.50-16	9.10-12½	13.25-15½	11.00-16	14.50-16½	12-17.10	14.35-22	14.35-22
Sept	10.20-14	8.50-11½	13-16.50	11-14.50	14-18.25	11-16.50	15.60only	15.10-15.6
Oct*	11.1-15.6	8.40-11.4	13-16.90	11½-16½	14.50-18	12-18.00	15.60-26	15.60-26
Nov.	10.50-14	8.90-12	13.50-18	12.00-17	15.00-19	11½-16½	22-24.50	21.24½
Dec	11.35-14½	9-13.25	14.50-17	13.00-16	15½-22.10	11½-16½	18½-22½	18-22¼
1947								
Jan.	13-15.10	10.00-13	15.50-20	14.00-18	16-24.85	13.00-19	18-22.25	17-21.75
Feb	12½-15.10	10.00-13	16.50-21	13-18.50	16.75-22½	13.50-18	21½-25½	20½-24½
Mch	13½-15.40	11.45-13½	16.50-22½	14-18.90	18.00-23	14.50-20½	22½-26½	22.00-26
Apr	14-16.50	12.40-14	17-23.75	15-19.50	18.00-23	15-21.50	17.50-23	17.00-23
May	14-16.50	11.50-14	18-22.50	15-19.00	18.50-22	15.50-20	19½-23.10	18½-22½
June	14.10-17	11.00-14	18.70-22½	14.00-19	19.00-23	16.00-20	22½-24¼	21½-23½
July	14.00-16	10.00-14	19-22.50	14.00-19	19-23.50	15.00-20	23-25.50	21.50-25
Aug	14.00-16	11.00-14	19-23.00	14.00-19	19.00-23	15-19.50	24-25.50	23.50-25
Sept	14.00-18	11.50-15	19-25.00	15.00-20	19.50-23½	16.50-20	24-26.50	23-25.75
Oct	14.50-17	11-14.50	17-19.00	14-18.50	18.00-22	14.50-18½	22-26.75	21-26.50
Nov	14-16.50	11.50-14½	18-21.00	14-18.50	18.00-23	14-18.50	22.50-24½	21.75-23½
Dec	15-20.00	12.50-16	19-22.00	16-20.00	20.00-26	16.00-22	24-25.25	23-24.50
1948								
Jan	18-21.00	15-18.50	24-28.00	18.50-25	24-28.50	18-24.50	23-25.50	22.50-24¼
Feb	19-24.00	16-19.00	24-28.00	20-25.00	24-26.00	19-24.00	17-22.50	15.75-21.75
Mch	19.50-23	17-20.00	23.50-29	19.50-25	23.50-25	19.50-25	17-20.00	16-19.00
Apr	19.50-24	17.50-20½	24.50-30	20.50-25½	24.50-28½	20-25.50	17-19.25	15-18.50
May	20.50-24½	18.50-21½	26-31.00	21.50-26½	25.50-30	21.50-27	18-22.50	17-21.75
June	20.50-25	18-21.00	27-34.00	23.50-28	27-32.00	23-28.50	22.50-26½	20.75-25.50
July	20.50-24½	19-21.50	26-33.00	22-27.50	27.50-33	23-29.00	26-27.25	24.50-26.50
Aug	19.50-23½	18-20.50	25-29.00	21.50-26½	26.50-31	22.50-27½	25½-27.25	24.25-26.50
Sept	19.50-23	17.50-20½	24.50-28	21.00-25	25.00-29	22-26.50	26-27.50	25-27.00
Oct.	18-20.50	16-18.50	23-27.00	19-24.00	23.50-28	19.50-24½	22.50-25½	21-25.00
Nov.	18.50-21½	16.50-19	23.00-29	19.00-25	23.50-28	19.50-24	20.25-23	20-22.50
Dec.	19.50-22½	17-20.00	24-29.00	20.50-26	24.50-29	20-25.50	19.50-20½	19-20.00
1949								
Jan.	18.50-21½	17-20.00	24-28.50	20.50-25½	24-28.00	20-25.00	18.50-19½	18-19.00
Feb.	18.50-20	16.50-19	24-28.00	20.50-25	22-25.00	20-23.50	17.75-19	17.50-18.50
Mch	19-20.50	17.50-20	24.50-28	22-26.00	23-26.00	21-24.00	18¼-18.75	17.75-18.25
Apr	19-21.50	17.50-20½	24.50-28	22-25.50	23-27.00	21.50-25	17-18.00	16.75-17.75
May	19-21.00	17.50-20	23.50-27	21-25.00	23-25.50	21.50-24	17-20.50	16.75-20.00
June	19-21.00	17-20.00	23.50-26½	21.50-25½	23-26.00	21.50-24	20-21.50	19.50-21.00
July	18-19.50	16-18.50	22-25.00	19.50-24	23-25.00	20-23.50	21-22.00	20.50-22.00
Aug.	16-18.00	14-16.50	20.50-23½	18.50-22	22-24.50	18.50-22	18.75-21.75	18-21.75

NOTE: Where figure shows, for example, 10.5 it means that the animal sold for 10.5¢ per pound or $10.50 per hundred lbs. * Ceilings went off about Oct. 15, 1946. Much of this information furnished through cooperation of Production & Marketing Administration, 218 Post Office Building, Thomasville, Georgia.

FLORIDA SLAUGHTERING PLANTS AND LIVESTOCK MARKETS - 1949

By: L.H. Lewis and Gifford N. Rhodes, Livestock Specialists, State Marketing Bureau

Federally Inspected Packing Plants

Kingan Company	Bartow
Southern Packing Co.	Tallahassee
Swift Company	Ocala

State Inspected Plants

City Abattoir	West Palm Beach
Copeland Sausage Co.	Alachua
Cullison Sausage Co.	Ocala
Farris & Co.	Jacksonville
Fla. Packing Co.	Quincy
Harold R.Gertner Co.	Gainesville
Farmers Meat Pkg Co.	Marianna
Hermann Sausage Co.	Tampa
Lykes Bros. Meat Plant.	Tampa
Jones,Chambliss Co.	Jacksonville
Goldman Packing Co.	Dinsmore
Paul Russell	Tallahassee
Southland Provision Co.	Palatka
Suwannee Cold Storage	Live Oak
National Meat Packers	Tampa

Other Abattoirs- City or not inspected

Central Packing Co.	Center Hill
Fla.State Hospital	Chattahoochee
Riverside Pkg Co.	Daytona beach
Daniels % Co.(Meat Pkrs)	Gainesville
Miami Meat Pkg Co.	Box 273, Hialeah.
Geo. Wakefield	Homestead
S. E. Harrison	Myakka City
Molineaux Pkg Co.	Malabar
Turner & Gee	Orlando
Thomas Pkg Co.	Okeechobee
Fla. Sausage Co.	Pensacola
M. L. McDonald	Daytona Beach
E. G.Bass	Fort Lauderdale
Odom's Sausage Co.	Lake City
Dirr Sausage Co.	Miami
Mades Pkg Co.	Miami
H. S.Camp & Sons	Ocala
McKinnon & Mills	Ocala
D. Z.Ard Pkg Co.	Pensacola
Edwards Meat Pkg Co.	Sarasota
Perry Cameron Pkg Co.	Sanford
C. B. Eiland	Sebring
H. A. Lawson	Starke
S.A.Snyder	St. Augustine
J. H. Turner	Arcadia
Andrews & Wade	Bonifay
Crum Packing Co.	Plant City
C. P. Russ	Panama City
E. M. Hawkins	East Palatka
T. J. Faulkner, Sr.	Perry
Clyde Brogdom	Wewahitchka
Smith,Richardson & Conroy.	West Palm Beach.
Escambia Sausage Co.	Pensacola
Carson A. Platt	Fellsmere
S.E.Register Meat Co.	Cottondale
Tobias Sausage Co.	Chipley

AND OTHERS.

Livestock Auction Markets	Sale held
Gainesville LS Mkt. Gainesville	Mon.
Tindel & Williams LS Mkt.Graceville.	Mon
Monticello LS Mkt. Monticello	Mon
Sebring LS Mkt. Inc. Sebring	Wed
Hillsboro LS Com.Co,Tampa	Mon
State Farmers LS Mkt. Arcadia	Tues
Jacksonville LS Mkt,Inc.Jacksonville	Tues
Hamilton Co.LS Mkt. Jasper	Tues
State Farmers LS Mkt. Jay	Tues
Farmers' Produce Mkt,Inc.Gainesville.	Tues
Madison LS Mkt, Madison	Tues
W.Fla.LS Mkt. Marianna	Tues.
Sumter Co.Farmers'Mkt Inc. Webster	Tues
Kissimmee LS Mkt,Inc. Kissimmee	Wed
Suwannee Co.LS Mkt. Live Oak	Wed
G.E.Sampson & Sons LS Act.Mkt.Miami	Wed
Gadsden Co.LS Auct.Mkt.Quincy	Wed
Davis & Rucker LS Mkt,Chiefland	Wed
State Farmers'LS Mkt.DeFuniak Spgs.	Thurs
Columbia Co.LS Mkt. Lake City	Thurs
E.E.Mills LS Auct.Mkt. Ocala	Thurs
Hardee Co.LS Auct.Mkt. Wauchula	Thurs
Atlanta LS Com. Co. Chipley	Fri
State Farmers' LS Mkt.East Palatka.	Fri
Okeechobee LS Mkt. Okeechobee	Fri

Cooperative Sales

Calhoun Co.Swine Shippers Assn.Altha.	Mon
*Gulf Co-op.LS Com.Co. Bell(Manager-Trenton)	
*Gulf Co-op.LS Com.Co. Newberry(Mgr.- ")	
*Gulf Co-op.LS Com.Co. Trenton	Tues
*D.D.Faircloth, Trenton,Manager.	
Holmes Co. LS Mkt, Bonifay	Wed
E. E. Mills, Williston	Tues

Cash Daily Markets

Frank E.Dennis,Inc.POBox 6066,
% Jones-Chambliss Co., Jacksonville.
Quincy LS Mkt.("Stoney" Edwards)Quincy.
Ted May, Jay.
H. G. Neel, Greenwood.

All meat packing companies and practically all abattoirs furnish cash daily markets.

General Information on Livestock Location.

If one drew a line from Jacksonville to Cedar Keys thru Gainesville, the answer is 72.5% of cattle, 30% of the hogs, 33% of the goats & kids, 30.5% of sheep & lambs, 61.5% of horses & colts, and 22.6% of mules & mule colts (1945 Census) are east and southeast of this line. During the year 1948, 35.78% of the cattle were sold of the number on farms Jan.1st,1948. About 70% cattle fenced, 1949, with Stock Law in effect Sept. 1950. (10/7/49)

PERCENTAGE MONTHLY SLAUGHTER, CATTLE, CALVES & HOGS - FLORIDA, Years 1947 & 1948

Year : Kind:	1947 CATTLE		1947 CALVES		1948 CATTLE		1948 CALVES		1948 HOGS	
Month:	No.Head	Mktd%	No.Head	Mktd%	No.Head	Mktd%	No.Head	Mktd%	No.Head	Mktd%
Jan.	21,200	8.61%	8,000	5.87%	27,000	8.41%	13,900	10.55%	82,000	15.50%
Feb.	16,000	6.50	6,800	4.99	19,000	5.92	9,700	7.37	70,000	13.23
Mar.	14,000	5.69	7,200	5.28	24,000	7.48	9,100	6.91	60,000	11.34
Apr.	15,000	6.09	7,400	5.43	25,000	7.79	9,400	7.14	37,000	7.00
May	19,000	7.72	9,000	6.60	24,000	7.48	8,600	6.53	24,000	4.54
June	19,000	7.72	11,200	8.22	28,000	8.72	10,200	7.74	18,000	3.40
July	23,000	9.34	14,000	10.27	28,000	8.72	11,100	8.43	16,000	3.03
Aug.	22,000	8.94	14,300	10.49	27,000	8.41	13,500	10.25	17,000	3.21
Sept.	23,000	9.34	14,000	10.27	31,000	9.66	12,700	9.64	29,000	5.48
Oct.	27,000	10.97	17,000	12.47	31,000	9.66	11,900	9.04	41,000	7.75
Nov.	23,000	9.34	16,000	11.74	29,000	9.03	11,400	8.66	45,000	8.51
Dec.	24,000	9.74	11,400	8.37	28,000	8.72	10,200	7.74	90,000	17.01
	246,200	100%	136,300	100%	321,000	100%	131,700	100%	529,000	100%

The shipments and sales of cattle are generally heavier from July thru January than from February thru June. As to calves, the shipments are generally heavier per months August thru January as compared with February thru June, and Hog shipments are heavier during the months of December, January, February and March. We suggest adjusting feed conditions to more evenly distribute the marketings or finishing livestock for market so as to feed the markets. (BAE, USDA, G.A.R. of Fla. St. Market Bureau)

LEADING LIVESTOCK COUNTIES IN FLORIDA (Dept of Com. USCensus'45)

County Cattle & Calves	County Hogs & Pigs	County Goats & Kids	County Sheep & Lambs	County Horses & Colts	County Mules & Colts
Polk	Jackson	Jackson	Santa Rosa	Polk	Jackson
Highlands	Suwannee	Marion	Washington	Marion	Gadsden
Osceola	Levy	Alachua	Polk	Hillsborough	Madison
Hardee	Alachua	Levy	Walton	Alachua	Holmes
Hillsborough	Madison	Washington	Osceola	Jackson	Suwannee
Marion	Santa Rosa	Santa Rosa	Duval	Sumter	Alachua
DeSoto	Holmes	Escambia	Alachua	Hardee	Jefferson
Okeechobee	Marion	Taylor	Nassau	Santa Rosa	Washington
Alachua	Gadsden	Suwannee	Calhoun	Levy	Columbia
Levy	Columbia	Union	Escambia	Palm Beach	Santa Rosa
Pasco	Jefferson	*Gadsden	Marion	Escambia	Hillsborough
Jackson	Hamilton	*Columbia	Osceola	Osceola	Leon
Manatee	Washington	Polk	Hillsborough	*Leon	Marion
Sumter	Walton	Holmes	Brevard	*Pasco	Walton
Collier	Gilchrist	Hillsborough	Liberty	Washington	Calhoun

* The same number of head for species by county.

NUMBER OF REGISTERED BEEF HERDS IN FLORIDA - YEAR 1948 (Breeders Record.Assn)

Breed	No. of Registered Herds	-State- P.B. Breeders Ass'n
Aberdeen-Angus	72 herds	Yes
Brahman	269 "	Yes
Hereford and Polled Hereford	175 "	Yes
Shorthorn	22 "	Yes
Devon	8 "	No
Red Polled	3 "	No
Total Registered Beef Herds	549 herds	

Oct. 5, 1949. Fla. State Marketing Bureau. Fla. Cattlemen's Ass'n- Yes.

NUMBER OF CATTLE ON FARMS, VALUE PER HEAD, TOTAL VALUE, USA & FLORIDA, Jan 1, Years indicated.
Florida data shows breeding cows, number of bulls needed & produced. Marketings and Income. USDA, BAE data*

	U S A			F L O R I D A										
Year	No. Head (Omitted 000)	Ave. Value Head	Total Value 000 Omitted	No. Head 000 Omit.	Ave. Value Head	Total Value 000 Omit.	No. Cows Breeding 000 Omit.	No. P.B. Bulls Needed (a)	Supplied	No. Slaughtered Cattle 000 Omitted	Calves	Gross Income 000 omitted	Out-shipments Total	[illegible] Stocker-Feeder
1929	56,877	$ 59.09	$ 3,479,041	600	$23.40	$14,040	335	13,350	250	84	83	$ 3,610		
1930	61,003	57.30	3,495,472	590	29.10	12,571	328	12,600	275	44	72	1,860		
1931	63,030	39.31	2,477,709	620	23.30	14,446	336	12,600	320	38	45	1,148		
1932	65,801	26.39	1,737,000	680	17.90	12,172	345	11,600	362	70	23	1,236		
1933	70,280	19.74	1,387,000	737	14.00	10,318	376	13,445	412	98	39	1,700		
1934	74,369	17.76	1,322,000	773	13.80	10,723	402	14,250	512	113	45	2,210		
1935	68,846	20.20	1,391,000	788	14.60	11,505	416	14,470	600	128	67	3,232		
1936	67,847	34.06	2,311,000	788	18.20	14,342	420	14,200	760	128	59	3,338		
1937	66,098	34.06	2,251,000	796	18.50	14,726	420	13,700	852	151	81	4,392		
1938	65,249	36,58	2,387,000	780	20.00	15,600	413	12,440	1100	107	46	2,937		
1939	66,029	38.44	2,538,000	820	20.50	16,810	429	12,550	1300	118	67	3,589		
1940	68,309	40.60	2,773,000	851	20.90	17,159	451	12,480	1550	109	61	3,546	97,000	
1941	71,755	43.20	3,109,000	902	22.40	20,205	473	12,400	1700	120	77	5,289	103,000	
1942	76,025	55.00	4,181,000	947	28.80	30,010	506	12,770	1820	81	91	5,715	81,000	
1943	81,204	69.30	5,627,000	1042	37.90	41,501	567	14,460	1850	99	92	9,080	93,000	
1944	85,334	68.40	5,837,000	1136	45.10	51,234	615	15,780	1900	172	112	13,572	145,000	
1945	85,573	66.90	5,725,000	1159	42.50	49,258	628	14,750	2100	124	32	16,450	173,000	4,726
1946	82,434	76.20	6,281,000	1205	46.80	56,394	660	16,330	2400	126	28	19,558		5,616
1947	81,207	97.40	7,910,000	1265	54.00	68,310	686	16,540	2650	224	180	22,781		19,016
1948	78,126	116.00	9,063,000	1265	58,70	74,256	718	16,845	2825	241	154	31,055		24,744
1949	78,495	135.00	10,587,000	1265	74.20	93,863								

(a) Bulls at rate 1 bull to 25 cows.

* The above data taken from several sources, combined by the State Marketing Bureau

Of the 35,111,040 acres of lands in Florida, 22,000,000 to 25,000,000 are well adapted to the production of pasture and other feeds for livestock, or 6,000,000 to 8,000,000 acres of land could grow crops as feed for livestock and up to 14,000,000 additional acres could be put into sufficient pastures to support three times as many cattle and three times as many hogs as are now being produced in the State. This would more than supply the needed production to meet present consumption. Florida has the climate- long growing season, coupled together with a well-distributed rainfall and mild temperature; its lands are reasonable cheap and can be secured in small or large acreage. Grade, cross-breeds, and purebreds have done well on pastures-both native and improved and the good kinds have responded to long and short feeding.

Average Rainfall in inches and Temperature in Degrees F. 35 years, by Months.

Months	Jan.	Feb.	March	April	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Ave. Annual
Rainfall	2.79	2.96	3.23	2.83	4.21	6.76	7.17	7.22	6.67	4.37	2.23	2.83	53.27
Temperature	59.6	61.1	65.1	70.0	75.6	79.8	81.3	81.4	79.5	73.3	65.1	60.2	71.00

.CATTLE & CALVES, INVENTORY NUMBERS, CALF CROP & DISPOSITION, PRODUCTION AND INCOME - FLORIDA. USDA, BAE Data**

Year	On hand. Jan 1 All cattle	On hand. Jan 1 All cows 2 yrs up	Calves born Percent calf crop	Calves born Number	Marketings 2/ Cattle	Marketings 2/ Calves	Farm Slaughter Cattle	Farm Slaughter Calves	Deaths Cattle	Deaths Calves	Production sold-lbs. Live Wt.	Price per 100 lbs. Cattle	Price per 100 lbs. Calves	Gross Income
	000 omitted	[illegible]	[illegible]	1,000	000 omitted									000 omitted
1924	740	402	45%	181	82	59	12	10	28	18	45,735	$3.65	$5.80	$2,157
1925	712	391	47	184	89	59	10	10	28	17	49.060	3.90	6.10	2,383
1926	684	382	52	200	110	75	8	10	21	20	60,875	4.50	6.50	3,221
1927	640	358	53	189	102	68	6	10	16	15	56,270	5.00	7.20	3,264
1928	612	343	54	185	88	68	7	3	16	17	49,390	6.50	8.00	3,627
1929	600	335	56	188	77	80	7	3	15	16	45,775	6.60	9.60	3,610
1930	590	328	54	176	34	68	10	4	16	16	42,055	5.20	8.50	1,660
1931	620	336	52	176	30	39	8	6	18	18	42,925	4.00	7.30	1,148
1932	630	345	54	185	63	15	7	8	18	18	54,395	3.20	5.10	1,236
1933	737	376	54	202	88	31	10	8	15	15	67,760	3.10	4.70	1,700
1934*	773	402	53	212	97	36	16	9	20	20	62,295	3.50	5.10	2,210
1935	788	416	57	237	119	62	9	5	20	25	65,290	4.60	6.10	3,232
1936	788	420	54	227	119	53	9	6	17	19	67,565	4.70	6.20	3,338
1937	796	420	58	244	142	74	9	7	16	15	75,960	5.20	6.40	4,392
1938	780	413	53	219	98	41	9	5	15	16	68,635	4.90	6.00	2,937
1939	820	429	58	249	103	60	15	7	23	20	70,825	5.20	6.40	3,589
1940	851	451	55	248	98	54	11	7	27	14	73,140	5.40	6.50	3,545
1941	902	473	58	272	104	63	16	9	33	17	79,520	6.70	7.70	5,289
1942	947	506	60	306	65	83	16	8	35	22	87,830	8.50	9.90	5,715
1943	1,042	567	57	322	82	85	17	7	35	23	102,045	10.60	12.00	9,080
1944	1,136	615	57	348	154	107	18	5	35	22	137,590	9.40	10.60	13,572
1945	1,159	628	65	409	65	120	124	32	33	29	149,895	10.00	11.20	16,450
1946	1,205	660	64	422	76	129	126	28	33	25	155,845	11.20	13.00	19,558
1947	1,265	686	64	438	207	176	17	4	31	27	168,280	12.20	14.00	22,770
1948	1,265	718	59	424	226	150	15	4	26	22	175,880	16.10	19.40	31,055
1949	1,265													

2/ excludes interfarm sales.   * includes Government purchases.

** Above data taken from several sources, combined by the Florida State Marketing Bureau.

Florida's position as a cattle State:- 13th in beef, 24th total, 36th in dairying: 25th in Hogs. Sheep 39th..

Position rated in number of head, not production or income.

Oct. 5, 1949.
L.H.L.

HOGS INVENTORY, NUMBERS, PIG CROPS AND DISPOSITION, PRODUCTION AND INCOME, Years Indicated. USDA,BAF Data *
F L O R I D A

Year	Number Jan.1	No.Sows Farrowing	No.Boars Needed **	No. Pigs Saved	No. Head Slaughtered	No. of Deaths on farms	Production in pounds	Price per 100 lbs.	Gross Income	Out-Shipments	
										Total	Stocker-Feeder
										B A E U S D A	L.Stock Sanitary Board
1924	640,000	92,000	1,700	441,000	504,000	79,000	57,735,000	$ 7.10	$ 5,450,000		
1925	498,000	91,000	1,534	460,000	424,000	76,000	57,670,000	9.10	6,075,000		
1926	458,000	99,000	1,800	534,000	428,000	79,000	64,055,000	9.90	6,658,000		
1927	485,000	110,000	2,067	576,000	439,000	79,000	67,485,000	8.70	5,786,000		
1928	543,000	109,000	1,967	566,000	493,000	85,000	67,500,000	7.10	5,234,000		
1929	531,000	101,000	1,867	514,000	451,000	75,000	64,090,000	7.70	5,303,000		
1930	519,000	103,000	1,934	527,000	458,000	74,000	64,245,000	7.50	5,257,000		
1931	514,000	108,000	1,934	555,000	460,000	75,000	66,645,000	5.50	3,879,000		
1932	534,000	111,000	1,967	571,000	484,000	76,000	69,095,000	3.35	2,483,000		
1933	545,000	111,000	2,133	546,000	504,000	72,000	69,189,000	3.20	2,475,000		
1934	515,000	100,000	1,867	467,000	463,000	72,000	60,695,000	3.85	2,748,000		
1935	447,000	106,000	2,200	526,000	426,000	100,000	62,070,000	6.50	4,197,000		
1936	447,000	126,000	2,434	614,000	472,000	90,000	73,085,000	7.30	5,364,000		
1937	499,000	140,000	2,634	720,000	550,000	150,000	83,050,000	7.50	6,446,000		
1938	519,000	153,000	2,767	815,000	610,000	142,000	98,495,000	6.50	6,320,000		
1939	582,000	158,000	2,934	853,000	655,000	180,000	102,350,000	5.60	5,871,000		
1940	600,000	148,000	2,734	760,000	575,000	155,000	91,425,000	5.10	4,598,000	258,000	
1941	630,000	152,000	2,734	785,000	635,000	150,000	98,245,000	7.30	7,428,000	282,000	
1942	630,000	163,000	3,000	861,000	646,000	145,000	108,945,000	10.40	10,808,000	287,000	
1943	700,000	215,000	3,834	1,116,000	762,000	290,000	125,150,000	12,40	15,657,000	336,000	
1944	770,000	201,000	4,034	895,000	772,000	275,000	118,571,000	11.10	13,876,000	398,000	
1945	716,000	187,000	3,667	941,000	761,000	250,000	116,053,000	13,20	16,896,000	272,000	5,006
1946	650,000	190,000	3,433	941,000	727,000	215,000	119,405,000	15.80	19,312,000		44,911
1947	630,000	189,000	3,500	959,000	695,000	255,000	111,742,000	20,90	24,017,000		1,377
1948	640,000	188,000	3,400	998,000	747,000	225,000	121,751,000	20.30	24,687,000		2,446
1949	660,000										

---

* USDA, BAE Data combined by the Florida State Marketing Bureau

** Number of boars are obtained by using one boar for 50 sows or gilts, -Sows farrowing twice per year.

There are 8,000,000 acres of land adaptable to the production of corn, oats, rye, sorghum grain, peanuts, root crops, and grazing crops for hogs, and/or the production of grains for creep, or short feeding and finishing of cattle. There is available garbage, tubers, acorn mast, and by-products of the field and dairies for hogs. The gross income from hogs, 5-year period 1944-48 inclusive, is about 85% of that from cattle, calves and hides. Florida produces hogs.

NUMBER OF HOGS ON FARMS, VALUE PER HEAD, TOTAL VALUE, USA AND FLORIDA. Jan. 1, Years Indicated
Florida data also shows number slaughtered, Gross Income, and average weight Head Sold. BAE, USDA.*

Year	USA			FLORIDA					
	No. Head	Ave. Value Head	Total Value	No. Head	Ave. Value Head	Total Value	Number Slaughtered	Ave. ** Weight Head, lbs.	Gross Income
1929	59,042,000	$13.05	$770,498,000	531,000	$ 8.10	$ 4,301,000	451,000	142.1	$ 5,303,000
1930	55,705,000	13.76	766,501,000	519,000	7.50	3,893,000	458,000	140.2	5,257,000
1931	54,835,000	11,36	622,926,000	514,000	6.10	3,135,000	460,000	144.9	3,879,000
1932	59,301,000	6.13	363,000,000	534,000	3.60	1,923,000	484,000	142.8	2,483,000
1933	62,127,000	4.21	262,000,000	545,000	2.70	1,472,000	504,000	137.3	2,475,000
1934	58,621,000	4.09	240,000,000	515,000	3.15	1,622,000	463,000	139.2	2,748,000
1935	39,066,000	6.31	247,000,000	447,000	3.35	1,498,000	426,000	145.7	4,197,000
1936	42,975,000	12.71	546,000,000	447,000	5.60	2,503,000	472,000	154.8	5,364,000
1937	43,083,000	11,89	512,000,000	499,000	6.80	3,393,000	550,000	151.0	6,446,000
1938	44,525,000	11.26	501,000,000	519,000	5.90	3,062,000	610,000	161.5	6,320,000
1939	50,012,000	11,18	559,000,000	582,000	5,80	3,376,000	655,000	156.3	5,871,000
1940	61,165,000	7.78	475,000,000	600,000	4.30	2,580,000	575,000	159.0	4,598,000
1941	54,353,000	8.34	453,000,000	630,000	4.45	2,804,000	635,000	154.7	7,428,000
1942	60,607,000	15.60	945,000,000	630,000	6.80	4,284,000	646,000	168.6	10,808,000
1943	73,881,000	22.50	1,662,000,000	700,000	10.90	7,630,000	762,000	164.2	15,657,000
1944	83,741,000	17.50	1,467,000,000	770,000	10.30	7,931,000	772,000	155.8	13,876,000
1945	59,331,000	20.60	1,224,000,000	716,000	10.80	7,733,000	781,000	148.6	16,896,000
1946	61,301,000	23.90	1,468,000,000	630,000	12.70	8,001,000	727,000	164.3	19,312,000
1947	56,921,000	36,00	2,049,000,000	630,000	16.20	10,080,000	695,000	160.8	24,017,000
1948	55,028,000	42.80	2,356,000,000	640,000	23.40	14,976,000	747,000	163.0	24,687,000
1949	57,139,000	38.20	2,184,000,000	666,000	21.70	14,452,000	-	-	-

* Source BAE, USDA Crop Reporting, Crop Reporting & Income. Combined by Florida State Marketing bureau.

** Average weight per head was obtained by dividing total production pounds by total head marketed or slaughtered.

Florida's position as a livestock State, in numbers (not production or income) is as follows:
Hogs 25th, Beef Cattle 13th, Total Cattle 24th, Dairy Cattle 36th, Sheep 39th.
Production vs. Consumption of Meats in Florida with 2,250,061 (1945 census) people Consuming Average Per Capita USA. (10-yr period 1932-1941 or more nearly normal) Pork 68.83 lbs. Beef 54.53 lbs. Veal 7.75 lbs. Mutton & Lamb 6.73 lbs. Lard 12.67 lbs. would require 154,872,000 lbs. Pork, 122,696,000 lbs. Beef, 17,438,000 lbs. Veal, and 15,143,000 lbs. Mutton and Lamb. On basis of production 1948, Florida produced 58.17% of the Pork, 65.26% Beef and Veal, and practically none of the Mutton and Lamb (about 1%) and about 80% of the Lard.
Oct. 5, 1949. L.H.L.

ACREAGE, YIELD, PRODUCTION AND VALUE
FLORIDA VEGETABLES AND MISCELLANEOUS FRUITS
1948-49 SEASON

FLORIDA	Acreaged Planted	 For Harvest	Yield	Production Total	Abandoned A	Production Of Value	Season Avg FOB Price	Total Value Marketed
			Units	Units	Units	Units	Units	Dollars
SNAP BEANS			Bu.					
Fall (Fresh)	22,900	22,500	115	2,588,000	755,000	1,833,000	$ 2.10	$ 3,849,000
(Process)	3,500	3,500	115	397,000	-	397,000	1.50	596,000
" (Total)	26,400	26,000	115	2,985,000	755,000	2,230,000	1.99	4,445,000
Winter (Fresh)	31,000	31,000	100	3,100,000	-	3,100,000	2.75	8,525,000
" (Process)	1,000	1,000	100	100,000	-	100,000	1.90	190,000
" (Total)	32,000	32,000	100	3,200,000	-	3,200,000	2.72	8,715,000
Spring (Fresh)	18,000	17,700	105	1,858,000	399,000	1,459,000	2.15	3,136,000
" (Process)	3,300	3,300	105	346,000	-	346,000	1.70	588,000
(Total	21,300	21,000	105	2,204,000	399,000	1,805,000	2.06	3,724,000
TOTAL FRESH	71,900	71,200	106	7,546,000	1154,000	6,392,000	2.43	15,510,000
TOTAL PROCESS	7,800	7,800	108	843,000	-	843,000	1.63	1,374,000
TOTAL ALL	79,700	79,000	106	8,389,000	1154,000	7,235,000	2.33	16,884,000
LIMA BEANS			Bu.					
Winter	1,150	950	125	119,000	-	119,000	4.00	476,000
Spring	2,100	2,100	95	200,000	-	200,000	2.35	470,000
TOTAL	3,250	3,050	105	319,000	-	319,000	2.97	946,000
CABBAGE			Tons					
Winter	16,000	16,000	9.6	154,000	30,000	124,000	44.60	5,530,000
CARROTS			Bu.					
Winter	500	500	200	100,000	60,000	40,000	1.30	52,000
CAULIFLOWER			Crt					
Winter	600	600	260	156,000	-	156,000	2.25	351,000
CELERY			Crt					
Winter	5,100	5,000	550	2,750,000	-	2,750,000	3.85	10,588,000
Spring	4,500	4,500	615	2,768,000	181,000	2,587,000	2.10	5,433,000
TOTAL	9,600	9,500	581	5,518,000	181,000	5,337,000	3.00	16,021,000
CORN, GREEN			Crt					
Spring	13,000	12,000	140	1,680,000	-	1,680,000	2.70	4,536,000
CUCUMBERS			Bu.					
Fall	5,400	5,000	145	725,000	46,000	679,000	1.90	1,290,000
Winter	1,500	1,500	100	150,000	-	150,000	3.75	562,000
Spring	7,600	6,600	125	825,000	-	825,000	4.25	3,506,000
" Pickling	1,000	1,000	100	100,000	-	100,000	2.00	200,000
TOTAL	15,500	14,100	124	1,800,000	46,000	1,754,000	3.17	5,558,000
EGGPLANT			Bu.					
Fall	1,000	800	115	92,000	-	92,000	2.50	230,000
Winter	700	700	375	262,000	-	262,000	2.00	524,000
Spring	1,800	1,800	300	540,000	-	540,000	1.30	702,000
TOTAL	3,500	3,300	271	894,000	-	894,000	1.63	1,456,000
ESCAROLE			Bu.					
Winter	3,000	2,800	400	1,120,000	-	1,120,000	1.50	1,680,000
LETTUCE			Crt					
Winter	1,700	1,500	125	188,000	-	188,000	3.10	583,000
PEAS, ENGLISH			Bu.					
Winter	600	400	40	16,000	-	16,000	2.62	42,000
PEPPERS			Bu.					
Fall	1,300	900	175	158,000	-	158,000	3.70	585,000
Winter	3,000	2,900	530	1,536,000	-	1,536,000	2.30	3,533,000
Spring	7,300	7,300	175	1,278,000	-	1,278,000	2.70	3,451,000
TOTAL	11,600	11,100	268	2,972,000	-	2,972,000	2.55	7,569,000

A - Abandoned because of poor market price at certain times during the season.

NOTE: It is possible that the acreages for a few commodities here may be slightly different from the acreages by counties shown on other pages. This may be due to slight revisions which are being made at this season of the year.

ACREAGE, YIELD, PRODUCTION AND VALUE
FLORIDA VEGETABLES AND MISCELLANEOUS FRUITS
1948-49 SEASON

FLORIDA	Acreage Planted	Acreage For Harvest	Yield Units	Production Total Units	Abandoned A Units	Production of Value Units	Season Avg FOB Price Units	Total Value Marketed Dollars
POTATOES			Bu.					
Winter	9,000	8,700	270	2,349,000	-	2,349,000	$ 2.35	$ 5,520,000
Spring	11,600	11,600	260	3,013,000	-	3,013,000	2.26	6,796,000
TOTAL	20,600	20,300	264	5,362,000	-	5,362,000	2.30	12,316,000
SQUASH			Bu.					
Fall	2,800	2,500	80	200,000	-	200,000	2.10	420,000
Winter	3,700	3,200	100	320,000	-	320,000	3.60	1,152,000
Spring	3,700	3,300	90	297,000	-	297,000	2.30	683,000
TOTAL	10,200	9,000	91	817,000	-	817,000	2.76	2,255,000
TOMATOES			Bu.					
Fall(Fresh)	9,000	7,500	130	975,000	-	975,000	5.40	5,265,000
" (Process)	1,500	1,500	130	195,000	-	195,000	.68	133,000
" (Total)	10,500	9,000	130	1,170,000	-	1,170,000	4.61	5,398,000
Winter(Fresh)	11,300	11,300	190	2,147,000	-	2,147,000	5.90	12,667,000
" (Process)	700	700	190	133,000	-	133,000	.74	98,000
" (Total)	12,000	12,000	190	2,280,000	-	2,280,000	5.60	12,765,000
Spring(Fresh)	16,300	15,500	205	3,178,000	-	3,178,000	4.50	14,301,000
" (Process)	1,700	1,700	205	347,000	-	347,000	.58	202,000
" (Total)	18,000	17,200	205	3,525,000	-	3,525,000	4.11	14,503,000
TOTAL FRESH	36,600	34,300	184	6,300,000	-	6,300,000	5.12	32,233,000
TOTAL PROCESS	3,900	3,900	173	675,000	-	675,000	.64	433,000
TOTAL ALL	40,500	38,200	183	6,975,000	-	6,975,000	4.68	32,666,000
TOTAL VEGS.	229,850	221,350	(Packed Value per Acre Harvested $490)					$108,445,000
CANTALOUPES			Crt					
Spring	1,600	1,200	40	48,000	-	48,000	4.00	192,000
STRAWBERRIES			Crt.					
24 quarts	4,000	4,000	55	220,000	-	220,000	10.91	2,401,000
36 pints	-	-	73	295,000	-	295,000	8.18	-
WATERMELONS			Melons				1000 M	
Spring	64,000	59,000	240	14,160,000	-	14,160,000	450.00	6,372,000
TOTAL MISCL.FRUITS	69,600	64,200	(Packed Value per Acre Harvested $140)					$ 8,965,000
GRAND TOTAL	299,450	285,550	(Packed Value per Acre Harvested $411)					$117,410,000

A - Abandoned because of poor market price at certain times during the season.

TOTAL ACRES, VALUE PER ACRE AND TOTAL PACKED VALUE IN 1947-48 SEASON

	Acres Used	Per Acre	Total Value
Vegetables	191,525	$420	$ 80,219,000
Miscellaneous Fruits	50,400	183	9,204,000
Grand Total	241,925	370	89,423,000
1946-47 SEASON			
Vegetables	201,450	$400	$ 80,712,000
Miscellaneous Fruits	52,550	176	9,260,000
Grand Total	254,000	$354	$ 89,972,000

The above officially reported acreage does not include a large acreage of miscellaneous vegetables such as radishes, broccoli, collards, turnips, okra, baby limas, field peas, etc., and it does not include avocados, limes, mangoes, guavas, etc., in miscellaneous fruits. Citrus acreage and value is covered elsewhere in this report.

The above tabulation was prepared from data supplied by Mr. J. B. Owens and Mr. G. N. Rose, Agricultural Statisticians, U.S. Bureau of Agricultural Economics, Federal Building, Orlando, Florida. They are the original source for official acreage and production estimates of vegetables and miscellaneous fruits in Florida.

If you have any questions on acreage, production and values not shown in this report you may write directly to the above named statisticians. They have all of the official acreage data for Florida.

Frank H. Scruggs.

(See pages 66-72 for acreage figures for other seasons).

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 24 SEASONS
(For Harvest)

Season	Beans Acreage	Limas Acreage	Cabbage Acreage	Carrots Acreage	Celery Acreage	Cauli-flower Acreage	Cu-cumbers Acreage	Season
1925-26	16,000	(1)	3,660		3,520		7,590	1925-26
1926-27	19,490	(1)	3,010		4,240		7,440	1926-27
1927-28	29,730	(1)	2,900		3,380		9,450	1927-28
1928-29	27,000	(1)	6,500		6,620		11,340	1928-29
1929-30	35,800	(1)	3,700		6,650		12,100	1929-30
1930-31	40,000	(1)	6,500		6,150		9,650	1930-31
1931-32	41,500	(1)	5,500		6,850		7,300	1931-32
1932-33	50,800	(1)	6,200		6,650		5,600	1932-33
1933-34	61,300	1,500	10,700		6,000		5,000	1933-34
1934-35	65,500	1,500	5,600		6,000		5,100	1934-35
1935-36	59,200	1,800	9,000		6,500		5,700	1935-36
1936-37	58,800	2,400	8,500		7,500		5,600	1936-37
1937-38	60,700	4,500	9,400		8,000		7,900	1937-38
1938-39	64,000	4,800	10,000		7,300		7,600	1938-39
1939-40	52,000	4,000	16,000		7,500		8,200	1939-40
1940-41	62,500	7,000	10,000		8,700		8,800	1940-41
1941-42	68,000	5,000	18,000		9,350		9,700	1941-42
1942-43	80,000	5,400	10,000		8,750		6,500	1942-43
1943-44	96,500	4,500	23,500		9,900		6,300	1943-44
1944-45	80,500	4,800	17,500		11,050		7,700	1944-45
1945-46	80,200	6,300	13,200		13,450		11,950	1945-46
1946-47	81,700	5,200	14,000		11,700		13,775	1946-47
1947-48	71,700	4,250	16,100	450	11,600	400	15,900	1947-48
1948-49	79,000	3,050	16,000	500	9,500	600	14,100	1948-49

Note: (1) Limas were included with snap beans prior to the 1933-34 season. The lima figures are for the Fordhook or large variety and do not include acreage of baby limas or butterbeans.

Season	Corn Acreage	Eggplant Acreage	Escarole (2) Acreage	Boston Lettuce (3) Acreage	Iceberg Lettuce (4) Acreage	All Lettuce Acreage	English Peas Acreage	Season
1925-26		1,020	(2)	1,500	-	1,500	760	1925-26
1926-27		630	(2)	1,500	-	1,500	700	1926-27
1927-28		1,550	340	1,500	-	1,500	1,230	1927-28
1928-29		1,320	500	1,500	--	1,500	1,350	1928-29
1929-30		1,680	460	1,100	--	1,100	700	1929-30
1930-31		1,800	850	1,600	--	1,600	2,000	1930-31
1931-32		1,950	700	1,000	--	1,000	3,800	1931-32
1932-33		2,450	700	950	--	950	3,600	1932-33
1933-34		2,050	700	1,100	--	1,100	4,800	1933-34
1934-35		1,500	650	900	(4)	900	5,000	1934-35
1935-36		1,100	700	550	(4)	550	8,200	1935-36
1936-37		1,480	900	800	(4)	800	6,200	1936-37
1937-38		1,800	1,000	900	(4)	900	6,200	1937-38
1938-39		2,100	1,000	750	250	1,000	5,000	1938-39
1939-40		1,400	1,350	900	1,100	2,000	5,000	1939-40
1940-41		1,900	1,000	500	2,000	2,500	3,000	1940-41
1941-42		2,350	1,200	500	3,000	3,500	3,500	1941-42
1942-43		1,950	1,450	800	1,700	2,500	1,500	1942-43
1943-44		3,500	2,350	1,100	1,350	2,450	2,500	1943-44
1944-45		2,850	2,800	400	1,000	1,400	2,600	1944-45
1945-46		3,900	2,500	550	1,300	1,850	1,600	1945-46
1946-47		3,300	2,800	700	1,125	1,825	1,600	1946-47
1947-48	6,000	3,225	3,200	550	1,100	1,650	600	1947-48
1948-49	12,000	3,300	2,600	-	-	1,500(5)	400	1948-49

Notes: (2) Escarole acreage included with lettuce prior to 1927-28 season.
(3) Big Boston figures include Romaine acreage.
(4) Iceberg Lettuce included in Big Boston acreage figures until the 1938-39 season.
(5) Iceberg, Boston and Romaine Lettuce combined.

All 1948-49 acreage figures are preliminary as of September 20, 1949 and are subject to revision.

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 24 SEASONS (Cont'd.)
(For Harvest)

Season	Peppers Acreage	Potatoes Acreage	Squash Acreage	Tomatoes Acreage	Total Vegetables Acreage	Season
1925-26	3,370	23,070		20,700	81,190	1925-26
1926-27	2,700	28,000		27,800	97,510	1926-27
1927-28	6,410	30,000		22,200	115,770	1927-28
1928-29	5,650	22,000		33,700	122,460	1928-29
1929-30	6,550	31,000		31,260	131,000	1929-30
1930-31	8,200	27,000		26,800	130,550	1930-31
1931-32	8,050	21,500		23,700	121,350	1931-32
1932-33	8,300	17,000		24,900	127,150	1932-33
1933-34	6,000	23,500		30,500	153,150	1933-34
1934-35	7,700	24,800		32,500	156,750	1934-35
1935-36	6,500	24,500		32,600	156,350	1935-36
1936-37	7,200	31,300		35,700	166,350	1936-37
1937-38	7,400	31,400		45,300	183,600	1937-38
1938-39	7,300	26,700		40,700	177,500	1938-39
1939-40	6,200	25,600		34,000	163,250	1939-40
1940-41	7,200	26,800		26,500	165,900	1940-41
1941-42	6,500	25,000		43,000	195,100	1941-42
1942-43	7,100	26,200		25,500	176,850	1942-43
1943-44	8,950	28,600		34,200	223,950	1943-44
1944-45	9,350	31,100		32,900	204,150	1944-45
1945-46	11,080	35,300		30,400	211,730	1945-46
1946-47	10,950	24,100		29,800	200,350	1946-47
1947-48	11,450	20,600	7,900	30,200	205,425	1947-48
1948-49	11,100	20,300	9,000	38,200	221,350	1948-49

Season	Cantaloupes (3) Acreage	Strawberries Acreage	Watermelons Acreage	Grand Total Officially Reported Acreage (4)	Season
1925-26	600	2,980	24,150	108,920	1925-26
1926-27	600	3,680	29,420	131,210	1926-27
1927-28	600	4,500	37,840	158,710	1927-28
1928-29	600	6,300	35,900	165,260	1928-29
1929-30	600	8,800	34,700	175,100	1929-30
1930-31	250	9,100	31,000	170,900	1930-31
1931-32	200	7,800	26,500	155,850	1931-32
1932-33	400	10,600	22,500	160,650	1932-33
1933-34	300	8,400	23,400	185,250	1933-34
1934-35	200	8,000	20,000	184,950	1934-35
1935-36	200	8,900	16,000	181,450	1935-36
1936-37	300	8,800	19,500	194,960	1936-37
1937-38	700	7,500	22,500	214,300	1937-38
1938-39	500	9,000	22,600	209,600	1938-39
1939-40	500	7,200	23,500	194,450	1939-40
1940-41	500	5,500	25,500	198,100	1940-41
1941-42	500	5,000	21,500	221,200	1941-42
1942-43	400	2,600	12,500	192,350	1942-43
1943-44	550	1,400	25,500	251,400	1943-44
1944-45	500	2,050	39,000	245,700	1944-45
1945-46	800	2,800	51,000	266,330	1945-46
1946-47	800	4,750	47,000	252,900	1946-47
1947-48	1,200	4,200	45,000	255,825	1947-48
1948-49	1,200	4,000	59,000	285,550	1948-49

Notes: (3) Acreage of cantaloupes for 1926, 1927 and 1928 seasons is estimated the same as for 1929 and 1930 seasons.

(4) These acreage figures do not include acres abandoned in various stages of growth for reasons other than economic marketing, that is, poor markets. Does not include any commodities not reaching harvest stage. Some additional acreage was abandoned for marketing reasons.

All acreage figures are preliminary as of September 20, 1949 and are subject to revision. Years prior to 1947-48 may have been revised slightly.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS

BEANS, SNAP

Season	Harvested Acreage	Yield Bu.	Harvested Production	Abandoned Volume	Volume Used	Price Bu.	Canned	FOB Packed Total Value
1930-31	40,000	84	3,376,000	-	3,376,000	$1.95	$	$ 6,592,000
1931-32	41,500	109	4,508,000	A/(284,000)	4,224,000	1.41		5,958,000
1932-33	50,800	98	5,002,000	A/(144,000)	4,858,000	.90		4,356,000
1933-34	61,300	101	6,216,000	A/(430,000)	5,786,000	1.00		5,773,000
1934-35	65,500	76	4,948,000	-	4,948,000	1.21		5,967,000
1935-36	59,200	71	4,183,000	-	4,183,000	1.49		6,250,000
1936-37	58,800	80	4,688,000	-	4,688,000	1.50		7,037,000
1937-38	60,700	89	5,381,000	-	5,381,000	1.17		6,272,000
1938-39	64,000	111	7,135,000	A/(288,000)	6,847,000	1.03		7,041,000
1939-40	52,000	98	5,090,000	-	5,090,000	1.47		7,480,000
1940-41	62,500	92	5,780,000	-	5,780,000	1.55		8,933,000
1941-42	68,000	105	5,783,000	-	5,783,000	1.84	.91	11,913,000
1942-43	80,000	131	7,795,000	-	7,795,000	2.62	1.27	17,989,000
1943-44	96,500	86	8,273,000	A/(269,000)	8,004,000	2.56	1.29	18,713,000
1944-45	80,500	92	7,440,000	A/(496,000)	6,244,000	2.92	1.67	18,405,000
1945-46	80,200	106	8,469,000	A/(1,240.000)	7,229,000	2.73	1.67	18,359,000
1946-47	81,700	80	6,549,700	A/(561,000)	5,988,700	2.50	1.67	16,389,000
1947-48	71,700	82	5,898,000	A/(225,000)	5.673,000	2.57	1.54	14,484,000
1948-49	79,000	106	8,389,000	A/(1,154,000)	7,235,000	2.43*	1.63*	16,884,000

A - Not harvested, account poor markets. For Canning: 1941-42 bu 1,367,000; 1942-43 bu 2,677,000; 1943-44 bu 1,268,000; 1944-45 bu 1,486,000; 1945-46 bu 1,106,000; 1946-47 bu 800,700; 1947-48 bu 583,000; 1948-49 bu 843,000.1948-49 Avg*Price$2.01.

LIMAS

Season	Harvested Acreage	Yield Bu.	Harvested Production	Abandoned Volume	Volume Used	Price Bu.	FOB Packed Total Value
1935-36	1,800	70	126,000	-	126,000	$1.60	$ 202,000
1936-37	2,400	65	156,000	-	156,000	2.50	390,000
1937-38	4,500	75	338,000	-	338,000	1.50	507,000
1938-39	4,800	100	480,000	-	480,000	1.50	720,000
1939-40	4,000	70	280,000	-	280,000	1.50	420,000
1940-41	7,000	40	280,000	-	280,000	2.20	616,000
1941-42	5,000	65	325,000	-	325,000	2.10	682,000
1942-43	5,400	59	321,000	-	321,000	3.31	1,041,000
1943-44	4,500	77	345,000	-	345,000	4.16	1,436,000
1944-45	4,800	88	420,000	A/(14,000)	406,000	4.38	1,779,000
1945-46	6,300	88	555,000	A/(87,000)	468,000	3.28	1,533,000
1946-47	5,200	65	338,000	-	338,000	3.51	1,187,000
1947-48	4,250	91	387,000	A/(32,000)	419,000	3.00	1,065,000
1948-49	3,050	105	319,000	-	319,000	2.97	946,000

CABBAGE

Season	Harvested Acreage	Yield Tons	Harvested Production	Abandoned Volume	Volume Used	Price Ton	FOB Packed Total Value
1931-32	5,500	4.0	22,100	-	22,100	$32.00	$ 704,000
1932-33	6,200	7.0	43,400	A/(6,500)	36,900	16.00	590,000
1933-34	10,700	6.0	64,200	A/(21,400)	42,800	16.00	685,000
1934-35	5,600	5.2	29,120	-	29,120	56.00	1,630,000
1935-36	9,000	4.0	36,000	-	36,000	17.00	612,000
1936-37	8,500	6.0	51,000	A/(20,000)	31,000	16.00	496,000
1937-38	9,400	6.5	61,000	-	61,000	16.00	978,000
1938-39	10,000	5.5	55,000	-	55,000	18.00	990,000
1939-40	16,000	7.0	112,000	-	112,000	18.40	2,061,000
1940-41	10,000	6.0	60,000	-	60,000	38.90	2,334,000
1941-42	18,000	6.0	108,000	-	108,000	17.80	1,602,000
1942-43	10,000	8.5	85,000	-	85,000	76.00	6,460,000
1943-44	23,500	7.1	166,800	A/(47,100)	119,700	36.00	4,309,000
1944-45	17,500	7.5	131,000	A/(24,000)	107,000	37.00	3,959,000
1945-46	13,200	8.8	116,200	A/(2,500)	113,700	49.00	5,571,000
1946-47	14,000	7.1	99,400	A/(18,200)	81,200	37.00	3,069,000
1947-48	16,100	9.0	144,900	A/(21,100)	123,800	52.50	6,500,000
1948-49	16,000	9.6	154,000	A (30,000)	124,000	44.60	5,530,000

A - Not harvested, due to economic abandonment. Values cover harvested portion of crop.

NOTE: All 1948-49 acreage figures are preliminary as of September 20, 1949 and are subject to revision. Revisions are usually of minor consequence.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd).

CELERY

Season	Harvested Acreage	Yield N.Y.	Crts. Fla.	Harvested Production	Abandoned	Volume Used	Price NY 2/3 Crates	FOB Packed Total Value	Price Fla. Crts.
1931-32	6,850	255	(425)	1,746,000	-	1,746,000	$2.17	$ 3,733,000	$1.30
1932-33	6,650	262	(437)	1,743,000A/	(207,000)	1,536,000	1.27	1,949,000	.76
1933-34	6,000	312	(520)	1,872,000	-	1,872,000	1.60	2,996,000	.96
1934-35	6,000	280	(467)	1,680,000	-	1,680,000	2.60	4,368,000	1.56
1935-36	6,500	265	(442)	1,723,000	-	1,723,000	2.60	4,488,000	1.56
1936-37	7,500	280	(467)	2,097,000	-	2,097,000	2.16	4,532,000	1.30
1937-38	8,000	286	(477)	2,290,000A/	(255,000)	2,035,000	1.62	3,289,000	.97
1938-39	7,300	299	(498)	2,184,000	-	2,184,000	2.46	5,375,000	1.48
1949-40	7,500	304	(507)	2,279,000	-	2,279,000	2.57	5,868,000	1.54
1940-41	9,100	278	(463)	2,531,000	-	2,531,000	3.19	8,066,000	1.91
1941-42	9,350	269	(465)	2,608,000	-	2,608,000	2.74	7,154,000	1.64
1942-43	8,750	-	447	4,175,500	(Fla.Crts)	4,175,500	-	17,156,000	4.11
1943-44	9,900	-	502	4,969,000A/	(400,000)	4,569,000	-	14,530,000	3.18
1944-45	11,050	-	493	5,448,000A/	(102,000)	5,346,000	-	18,553,000	3.47
1945-46	13,450	-	479	6,439,000A/	(151,000)	6,288,000	-	14,260,000	2.27
1946-47	11,700	-	390	4,564,000	-	4,564,000	-	17,535,000	3.84
1947-48	11,600	-	487	5,651,000A/	(892,000)	4,759,000	-	9,778,000	2.05
1948-49	9,500	-	581	5,518,000A	(181,000)	5,337,000	-	16,021,000	3.00

A - Not harvested, due to economic abandonment. Values cover harvested portion crops.
Florida crates are approximately 60 per cent as large as NY 2/3 crates.

CUCUMBERS

Season	Harvested Acreage	Yield Bu.	Harvested Production	Abandoned	Volume Used	Price per Bushel	FOB Packed Total Value
1931-32	7,300	53	390,000	-	390,000	$1.63	$ 655,000
1932-33	5,600	64	361,000	-	361,000	1.75	633,000
1933-34	5,000	95	474,000	-	474,000	1.78	845,000
1934-35	5,100	93	473,000	-	473,000	1.62	765,000
1935-36	5,700	82	468,000	-	468,000	1.98	928,000
1936-37	5,600	65	364,000	-	364,000	3.02	1,101,000
1937-38	7,000	121	850,000	-	850,000	1.24	1,053,000
1938-39	7,600	115	876,000	-	876,000	1.58	1,391,000
1939-40	8,200	145	1,186,000	-	1,186,000	1.63	1,938,000
1940-41	8,800	121	1,064,000	-	1,064,000	1.75	1,858,000
1941-42	9,700	94	912,000	-	912,000	2.24	2,042,000
1942-43	6,500	80	520,000	-	520,000	4.98	2,592,000
1943-44	6,300	73	459,000	-	459,000	4.55	2,079,000
1944-45	7,700	110	844,000	-	844,000	4.31	3,637,000
1945-46	11,150	136	1,520,000	A(76,000)	1,444,000	3.72	5,377,000
1946-47	13,775	87	1,204,000	-	1,204,000	4.14	4,984,000
1947-48	15,900	123	1,957,000	A(50,000)	1,907,000	3.25	6,203,000
1948-49	15,500B	124	1,800,000	A(46,000)	1,754,000	3.24P2.00Av3.17	5,558,000

B - See below.

CARROTS

Season	Harvested Acreage	Yield Crts	Harvested Production	Abandoned	Volume Used	Price per Crate	FOB Packed Total Value
1947-48	450	200	90,000	-	90,000	$3.00	$ 270,000
1948-49	500	200	100,000	60,000	40,000	1.30	52,000

CAULIFLOWER

Season	Harvested Acreage	Yield Crts	Harvested Production	Abandoned	Volume Used	Price per Crate	FOB Packed Total Value
1947-48	400	200	80,000	-	80,000	$2.20	$ 176,000
1948-49	600	260	156,000	-	156,000	2.25	351,000

CORN, GREEN

Season	Harvested Acreage	Yield Crts	Harvested Production	Abandoned	Volume Used	Price per Crate	FOB Packed Total Value
1947-48	6,000	80	480,000	-	480,000	$2.75	$ 1,320,000
1948-49	12,000	140	1,680,000	-	1,680,000	2.70	4,536,000

ESCAROLE

Season	Harvested Acreage	Yield 1½bu hpr	Harvested Production	Abandoned	Volume Used	Price 1½bu.hpr	FOB Packed Total Value
1936-37	900	453	408,000	-	408,000	$ .75	$ 306,000
1937-38	1,000	453	453,000	-	453,000	.45	204,000
1938-39	1,000	440	440,000	-	440,000	.60	264,000
1939-40	1,350	400	540,000	-	540,000	.56	304,000
1940-41	1,000	373	373,000	-	373,000	.98	366,000
1941-42	1,200	400	480,000	-	480,000	.68	326,000
1942-43	1,450	350	507,500	-	507,500	2.25	1,142,000
1943-44	2,350	425	999,000	A(438,000)	561,000	1.15	645,000
1944-45	2,800	310	868,000	A(224,000)	644,000	2.10	1,352,000
1945-46	2,500	374	935,000	-	935,000	1.20	875,000
1946-47	2,800	325Bu.H.	910,000	-	910,000	1.30Bu.H.	1,183,000
1947-48	3,200	430 "	1,376,000	A(266,000)	1,110,000	1.05 "	1,165,000
1948-49	2,800	400 "	1,120,000	-	1,120,000	1.50 "	1,680,000

B Cucumbers 14500A, Pickles 1000A, yield 130bu, Pickles 100bu, price $3.24, Pickles $2.00.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd).

EGGPLANT

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned A	Volume Used	Price per Bushel	FOB Packed Total Value
1931-32	1,950	189	367,000	-	367,000	$ .75	$ 277,000
1932-33	2,450	253	620,000	-	620,000	.58	359,000
1933-34	2,050	187	384,000	-	384,000	.75	289,000
1934-35	1,500	180	270,000	-	270,000	.79	212,000
1935-36	1,100	286	315,000	-	315,000	.85	268,000
1936-37	1,460	283	410,000	-	410,000	.79	323,000
1937-38	1,800	261	470,000	-	470,000	.76	366,000
1938-39	2,100	326	686,000	-	686,000	.75	514,000
1939-40	1,400	207	290,000	-	290,000	1.44	417,000
1940-41	1,800	180	324,000	-	324,000	1.17	378,000
1941-42	2,350	237	556,500	-	556,500	1.16	643,000
1942-43	1,950	278	541,500	-	541,500	2.39	1,294,000
1943-44	3,500	259	908,000	40,000	868,000	1.65	1,501,000
1944-45	3,250	271	880,000	-	880,000	2.06	1,814,000
1945-46	3,900	345	1,344,000	240,000	1,104,000	1.63	1,805,000
1946-47	3,300	220	725,000	-	725,000	2.42	1,758,000
1947-48	3,225	277	894,000	197,000	697,000	1.65	1,151,000
1948-49	3,300	271	894,000	-	894,000	1.63	1,456,000

LETTUCE (Boston and Romaine)

Season	Harvested Acreage	Yield 4-6 doz.Crts	Harvested Production	Abandoned A	Volume Used	Price Crates	FOB Packed Total Value
1938-39	750	180	135,000	-	135,000	$1.50	$ 203,000
1939-40	900	180	162,000	-	162,000	1.10	178,000
1940-41	500	150	75,000	-	75,000	2.00	150,000
1941-42	500	100	50,000	-	50,000	2.60	130,000
1942-43	800	175	140,000	-	140,000	3.05	427,000
1943-44	1,100	150	165,000	59,000	106,000	2.15	228,000
1944-45	400	200	80,000	-	80,000	2.70	216,000
1945-46	550	258	142,000	17,000	125,000	3.00	375,000
1946-47	700	100	70,000	-	70,000	2.95	206,000
1947-48	550	125	69,000	23,000	46,000	2.05	94,000

LETTUCE (Iceberg) 4-6 doz.crates.

1938-39	250	180	45,000	-	45,000	$1.49	$ 67,000
1939-40	1,100	180	198,000	-	198,000	2.30	455,000
1940-41	2,000	75	150,000	-	150,000	1.83	274,000
1941-42	3,000	55	165,000	-	165,000	2.16	356,000
1942-43	1,700	135	230,000	-	230,000	3.97	913,000
1943-44	1,350	143	193,000	78,000	115,000	2.90	334,000
1944-45	1,000	143	143,000	24,000	119,000	3.51	418,000
1945-46	1,300	165	214,000	20,000	194,000	3.72	910,250
1946-47	1,125	107	119,000	-	119,000	2.97	353,000
1947-48	1,100	118	130,000	10,000	120,000	2.88	346,000

LETTUCE (All)

1948-49	1,500	125	188,000	-	188,000	$3.10	$ 583,000

SQUASH

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned A	Volume Used	Price Bushels	FOB Packed Total Value
1947-48	7,900	82	651,000	-	651,000	$2.83	$1,839,250
1948-49	9,000	91	817,000	-	817,000	2.76	2,225,000

PEAS, ENGLISH

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned A	Volume Used	Price Bushels	FOB Packed Total Value
1932-33	3,600	70	252,000	-	252,000	$1.60	$ 403,000
1933-34	4,800	96	461,000	-	461,000	1.10	507,000
1934-35	5,000	80	400,000	-	400,000	1.30	520,000
1935-36	8,200	62	508,000	-	508,000	1.00	508,000
1936-37	6,200	50	310,000	-	310,000	1.35	418,000
1937-38	6,200	90	558,000	-	558,000	1.15	642,000
1938-39	5,000	70	350,000	-	350,000	1.85	648,000
1939-40	5,000	90	450,000	75,000	375,000	1.30	488,000
1940-41	3,000	70	210,000	-	210,000	1.95	410,000
1941-42	3,500	70	245,000	-	245,000	1.55	380,000
1942-43	1,500	65	98,000	-	98,000	2.60	254,000
1943-44	2,500	60	150,000	-	150,000	3.00	450,000
1944-45	2,600	75	195,000	90,000	105,000	2.70	284,000
1945-46	1,600	74	118,000	5,000	113,000	3.00	339,000
1946-47	1,600	40	64,000	-	64,000	2.95	189,000
1947-48	600	60	36,000	-	36,000	2.55	92,000
1948-49	400	40	16,000	-	16,000	2.62	42,000

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd).

PEPPERS, GREEN

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned A	Volume Used	Price per Bushel	FOB Packed Total Value
1930-31	8,200	228	1,869,000	-	1,869,000	$1.23	$ 2,294,000
1931-32	8,050	221	1,782,000	-	1,782,000	1.00	1,780,000
1932-33	8,300	266	2,210,000	-	2,210,000	.58	1,284,000
1933-34	6,000	241	1,446,000	-	1,446,000	1.16	1,676,000
1934-35	7,700	149	1,150,000	-	1,150,000	1.11	1,277,000
1935-36	6,500	226	1,467,000	-	1,467,000	.87	1,273,000
1936-37	7,200	221	1,590,000	-	1,590,000	1.20	1,905,000
1937-38	7,400	295	2,180,000	-	2,180,000	.77	1,668,000
1938-39	7,300	303	2,212,000	-	2,212,000	1.25	2,771,000
1939-40	6,200	224	1,390,000	-	1,390,000	1.53	2,121,000
1940-41	7,200	225	1,621,500	-	1,621,500	1.56	2,527,000
1941-42	6,500	276	1,792,000	-	1,792,000	1.75	3,133,000
1942-43	7,100	284	2,018,000	-	2,018,000	2.93	5,917,000
1943-44	8,950	265	2,371,000	86,000	2,285,000	2.16	4,964,000
1944-45	9,350	287	2,687,000	-	2,687,000	2.46	6,623,000
1945-46	11,080	275	3,050,000	380,000	2,670,000	2.45	6,545,000
1946-47	10,550	208	2,193,000	-	2,193,000	4.14	9,086,000
1947-48	11,450	250	2,860,000	143,000	2,717,000	2.17	5,886,000
1948-49	11,100	268	2,972,000	-	2,972,000	2.55	7,569,000

POTATOES

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned A	Volume Used	Price per Bushel	FOB Packed Total Value
1930-31	27,000	132	3,564,000	-	3,564,000	$1.07	$ 3,818,000
1931-32	21,500	70	1,505,000	-	1,505,000	1.28	1,933,000
1932-33	17,000	132	2,244,000	-	2,244,000	.85	1,908,000
1933-34	23,500	140	3,290,000	-	3,290,000	1.13	3,708,000
1934-35	24,800	97	2,406,000	-	2,406,000	1.04	2,503,000
1935-36	24,500	91	2,235,000	-	2,235,000	1.43	3,187,000
1936-37	31,300	123	3,842,000	-	3,842,000	1.32	5,087,000
1937-38	31,400	133	4,177,000	-	4,177,000	.70	2,939,000
1938-39	26,700	121	3,235,000	-	3,235,000	1.13	3,644,000
1939-40	25,600	157	4,020,000	-	4,020,000	.93	3,725,000
1940-41	26,800	117	3,126,000	-	3,126,000	.90	2,799,000
1941-42	25,000	154	3,848,000	-	3,848,000	1.54	5,924,000
1942-43	26,200	134	3,523,000	-	3,523,000	1.96	5,214,000
1943-44	28,600	112	3,212,000	-	3,212,000	2.00	6,431,000
1944-45	31,100	162	5,035,000	-	5,035,000	2.39	12,033,000
1945-46	35,300	170	6,010,000	-	6,010,000	1.95	11,744,000
1946-47	24,100	114	2,738,000	-	2,738,000	2.00	5,475,000
1947-48	20,800	174	3,614,000	-	3,614,000	2.79	10,073,000
1948-49	20,300	264	5,362,000	-	5,362,000	2.30	12,316,000

TOMATOES

Season	Harvested Acreage	Yield Bu.	Harvested Production		Abandoned	Volume Used	Price Bu.		FOB Packed Total Value
			Fresh	Canning	A		Fresh	Can.	
1930-31	26,800	75	2,020,000	-	-	2,020,000	$1.87	$-	$ 3,778,000
1931-32	23,700	95	2,255,000	-	-	2,255,000	2.55	-	5,748,000
1932-33	24,900	94	2,343,000	-	-	2,343,000	1.87	-	4,377,000
1933-34	30,500	113	2,886,000	557,000	-	3,443,000	2.86	.39	8,476,000
1934-35	32,500	102	2,714,000	589,000	-	3,303,000	2.46	.28	6,835,000
1935-36	32,600	100	2,954,000	321,000	-	3,275,000	2.75	.31	8,224,000
1936-37	35,700	86	2,746,000	314,000	-	3,060,000	2.76	.32	7,683,000
1937-38	45,300	120	4,953,000	500,000	-	5,453,000	1.73	.28	8,711,000
1938-39	40,700	129	4,948,000	312,000	-	5,260,000	2.47	.28	12,323,000
1939-40	34,000	88	3,225,000	232,000	-	3,457,000	2.53	.28	8,216,000
1940-41	26,500	110	2,765,000	165,000	-	2,930,000	3.10	.25	8,618,000
1941-42	43,000	101	3,412,000	951,000	-	4,363,000	3.92	.46	13,821,000
1942-43	25,500	102	2,226,000	*	-	2,226,000	5.30	*	11,795,000
1943-44	34,900	109	3,405,000	395,000	-	3,300,000	5.72	.59	19,712,000
1944-45	32,500	137	4,456,000	289,000	342,000	4,403,000	5.27	.72	20,376,000
1945-46	30,400	154	4,670,000	265,000	221,000	4,714,000	5.25	.74	22,405,000
1946-47	29,800	107	3,198,000	306,000	-	3,504,000	6.50	1.00	19,098,000
1947-48	30,200	130	3,588,000	346,000	-	3,934,000	5.83	.75	22,936,000
1948-49	38,200	183	6,300,000	675,000	-	6,975,000	x5.12	x.64	32,666,000

A - Not harvested, due to economic abandonment (poor markets). x Avg. Price $4.68
All 1948-49 acreage figures are preliminary as of September 20, 1949 and are subject to revision.
* Separate volume and price not available for 1942-43 season.
NOTE: See more details of acreage, yield, volume and value on pages 64-65.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd).

CANTALOUPES

Season	Harvested Production	Yield Crates	Harvested Production	Abandoned A	Volume Used	Price per Crate	FOB Packed Total Value
1930-31	250	50	12,000	-	12,000	$1.50	$ 18,000
1931-32	200	75	15,000	-	15,000	1.00	15,000
1932-33	400	60	24,000	-	24,000	1.00	24,000
1933-34	300	60	18,000	-	18,000	1.30	23,000
1934-35	200	60	12,000	-	12,000	1.50	18,000
1935-36	200	60	12,000	-	12,000	1.25	15,000
1936-37	300	55	16,000	-	16,000	1.75	28,000
1937-38	700	75	52,000	-	52,000	1.25	65,000
1938-39	500	80	40,000	-	40,000	1.10	44,000
1939-40	500	70	35,000	-	35,000	1.10	38,000
1940-41	500	60	30,000	-	30,000	1.25	38,000
1941-42	500	70	35,000	-	35,000	1.50	52,000
1942-43	400	65	26,000	-	26,000	3.25	85,000
1943-44	550	60	33,000	-	33,000	3.75	124,000
1944-45	500	50	25,000	5,000	20,000	6.00	120,000
1945-46	800	45	36,000	18,000	18,000	3.00	54.000
1946-47	800	50	40,000	-	40,000	2.55	102,000
1947-48	1,200	65	78,000	-	78,000	4.35	339,000
1948-49	1,200	40	48,000	-	48,000	4.00	192,000

A - Crates not harvested due to economic abandonment.

STRAWBERRIES

Season	Harvested Production	24-Qt Crts.	Harvested Production	Abandoned A	Volume Used	(48 Pts) 24 Qts*	FOB Packed Total Value	36 Pint Crate
1930-31	9,100	72	655,000	-	655,000	$5.75	$ 3,766,000	$4.31
1931-32	7,800	76	593,000	-	593,000	4.80	2,846,000	3.60
1932-33	10,600	73	774,000	-	774,000	3.00	2,322,000	2.25
1933-34	8,400	75	630,000	-	630,000	4.20	2,646,000	3.15
1934-35	8,000	65	520,000	-	520,000	4.30	2,236,000	3.23
1935-36	8,900	54	481,000	-	481,000	4.10	1,972,000	3.08
1936-37	8,800	65	572,000	-	572,000	4.80	2,746,000	3.60
1937-38	7,500	70	525,000	-	525,000	4.00	2,100,000	3.00
1938-39	9,000	85	765,000	-	765,000	4.15	3,175,000	3.11
1939-40	7,200	70	504,000	-	504,000	4.65	2,344,000	3.49
1940-41	5,500	70	384,000	-	384,000	5.70	2,194,000	4.28
1941-42	5,000	70	350,000	-	350,000	6.50	2,275,000	4.88
1942-43	2,600	60	156,000	-	156,000	9.60	1,498,000	7.20
1943-44	1,400	70	98,000	-	98,000	11.30	1,107,000	8.47
1944-45	2,050	70	144,000	-	144,000	10.70	1,541,000	8.03
1945-46	2,800	80	224,000	-	224,000	10.55	2,363,000	7.92
1946-47	4,750	65	309,000	-	309,000	12.10	3,739,000	9.08
1947-48	4,200	45	189,000	-	189,000	10.60	2,003,000	7.95
1948-49	4,000	55	220,000	-	220,000	10.91	2,401,000	8.18

* Now shipped almost exclusively in 36-pt. crates. The 24-qt. crate was formerly used, and it is continued here for statistical purposes. Florida crate is 75% as large.

WATERMELONS

Season	Harvested Production	Yield Melons	Harvested Production	Abandoned A	Volume Used	Price per 1000 melons	FOB Packed Total Value
1930-31	31,000	330	10,230,000	-	10,230,000	$200	$2,046,000
1931-32	28,500	200	5,700,000	-	5,700,000	160	912,000
1932-33	22,500	220	4,950,000	-	4,950,000	200	990,000
1933-34	23,400	180	4,212,000	-	4,212,000	185	779,000
1934-35	20,000	330	6,600,000	-	6,600,000	110	726,000
1935-36	16,000	280	4,480,000	-	4,480,000	200	896,000
1936-37	19,500	300	5,850,000	390,000	5,460,000	240	1,310,000
1937-38	22,500	310	6,975,000	675,000	6,300,000	150	945,000
1938-39	22,600	240	5,424,000	-	5,424,000	180	976,000
1939-40	23,500	290	6,815,000	-	6,815,000	175	1,193,000
1940-41	25,500	270	6,885,000	-	6,885,000	210	1,445,850
1941-42	22,000	325	7,150,000	-	7,150,000	225	1,609,000
1942-43	12,500	325	4,063,000	-	4,063,000	650	2,641,000
1943-44	25,500	305	7,778,000	-	7,778,000	655	5,095,000
1944-45	39,000	260	10,140,000	-	10,140,000	485	4,918,000
1945-46	47,000	225	10,575,000	-	10,575,000	525	5,552,000
1946-47	47,000	290	13,623,000	-	13,623,000	447	5,419,000
1947-48	45,000	305	13,725,000	-	13,725,000	500	6,862,000
1948-49	59,000	240	14,160,000	-	14,160,000	450	6,372,000

A - Not harvested due to economic abandonment. Not included in total value figures. The average carload is usually figured at 1000 melons but new varieties of round type melons have made a range of 875-1200, averaging 978 melons to car.

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASON 1946-47, 1947-48 AND 1948-49

Florida Counties	Snap Beans			Lima Beans			Cabbage		
	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49
Alachua	1,700	1,325	1,750	1,500	750	1,000	150	200	125
Baker	-	-	-	-	-	-	-	-	-
Bradford	150	100	50	125	50	50	50	50	25
Brevard	-	-	-	-	-	-	50	-	-
Broward	18,300	14,850	12,500	100	325	150	50	50	50
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	200	400	450
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	25	50	50
Dade	2,000	3,000	3,600	100	-	-	350	250	250
De Soto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	100	100	100
Escambia	250	100	100	-	-	-	50	50	75
Flagler	-	-	-	-	-	-	1,000	1,500	1,750
Gadsden	450	350	400	-	-	-	50	50	75
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	450	1,500	1,200
Hamilton	-	-	-	-	-	-	50	50	25
Hardee	50	50	-	-	-	-	50	150	-
Hendry	-	-	-	-	-	-	50	-	-
Hernando	100	-	-	-	-	-	-	-	-
Highlands	550	500	550	-	-	-	25	25	-
Hillsborough	1,850	1,075	1,300	500	100	100	750	350	250
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	50	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	100	300	350	-	-	-	150	200	200
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	50	25	25
Madison	-	-	-	-	-	-	-	-	-
Manatee	550	450	500	-	-	-	200	300	200
Marion	1,300	800	1,150	600	250	165	400	500	400
Martin	600	600	550	125	50	-	100	75	50
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	350	600	375	-	-	-	800	600	600
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	51,400	48,500	52,300	1,850	2,150	1,335	3,500	3,600	3,250
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	200	100	150	-	-	-	150	100	50
Putnam	250	-	-	-	-	-	1,000	1,400	1,600
St. Johns	-	-	-	-	-	-	2,700	2,800	3,100
St. Lucie	-	-	-	100	50	175	-	200	100
Sarasota	-	-	-	-	-	-	100	75	-
Seminole	550	575	1,500	-	-	-	1,000	1,500	1,600
Sumter	250	650	1,150	-	-	-	50	100	50
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	250	275	525	150	50	25	50	150	100
Volusia	-	-	-	-	-	-	200	200	200
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	450	300	200	50	75	50	100	100	50
Total	81,700	74,500	79,000	5,200	3,850	3,050	14,000	16,700	16,000

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASON 1946-47, 1947-48 AND 1948-49

Florida Counties	Carrots 1946-47	Carrots 1947-48	Carrots 1948-49	Cauliflower 1946-47	Cauliflower 1947-48	Cauliflower 1948-49	Celery 1946-47	Celery 1947-48	Celery 1948-49
Alachua	-	-	-	-	-	-	130	100	100
Baker	-	-	-	-	-	-	-	-	-
Bradford	-	-	-	-	-	-	-	-	-
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	-	-	-	-	-	-
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-	-
Dade	25	50	75	-	-	-	-	-	-
De Soto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	-	-	-	-	-	-	-	-	-
Hendry	-	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-	-
Highlands	25	25	-	-	-	-	-	-	-
Hillsborough	-	-	-	300	225	250	-	-	-
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	20	-	-	-	-	-	875	625	875
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-	-
Manatee	-	-	-	200	100	150	75	60	-
Marion	-	-	-	-	-	-	190	500	225
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	330	280	300	-	-	-	695	860	850
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	50	-	75	-	-	-	4,280	4,000	3,100
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	-	-	-	-	-	-
Putnam	-	-	-	-	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	-	-	75	-	-	-
Sarasota	-	-	-	30	-	-	1,285	1,325	975
Seminole	50	20	-	50	25	100	4,150	4,065	3,350
Sumter	-	-	-	-	-	-	-	-	-
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	-	-	-
Volusia	-	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	-	25	50	20	50	25	20	65	25
Total	500	400	500	600	400	600	11,700	11,600	9,500

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASON 1946-47, 1947-48 AND 1948-49

Florida Counties	Green Corn 1946-47	Green Corn 1947-48	Green Corn 1948-49	Cucumbers 1946-47	Cucumbers 1947-48	Cucumbers 1948-49	Eggplant 1946-47	Eggplant 1947-48	Eggplant 1948-49
Alachua	-	200	300	1,900	1,225	1,725	250	150	150
Baker	-	-	75	-	-	-	-	-	-
Bradford	-	250	700	150	75	125	-	-	-
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	200	650	700	200	500	450	350
Calhoun	-	-	-	175	300	250	-	-	-
Charlotte	-	-	-	50	100	50	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	325	400	300	-	-	-
Columbia	-	400	275	-	100	100	-	-	-
Dade	-	65	100	-	125	50	-	-	-
De Soto	-	50	-	125	100	50	25	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	50	50	50	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	25	-	-
Glades	-	100	-	-	-	-	-	-	-
Hamilton	-	-	125	575	350	125	-	-	-
Hardee	-	200	350	1,400	2,100	1,500	150	75	350
Hendry	-	-	-	200	400	475	-	-	-
Hernando	-	-	-	-	-	-	-	15	50
Highlands	-	-	-	50	50	50	25	-	-
Hillsborough	-	650	1,000	975	1,325	1,450	350	845	700
Holmes	-	-	-	200	150	100	-	-	-
Indian River	-	-	-	75	-	-	25	-	-
Jackson	-	-	-	375	800	600	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	-	-	200	275	300	400	-	25	50
Lee	-	100	400	700	550	800	300	215	225
Leon	-	-	-	-	-	-	-	-	-
Levy	-	100	25	50	50	-	-	-	-
Madison	-	-	-	-	-	150	-	-	-
Manatee	-	100	450	725	375	550	375	125	200
Marion	-	-	600	275	275	325	200	200	125
Martin	-	-	-	100	-	475	200	50	50
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	-	1,350	1,600	400	375	400	-	-	-
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	-	1,250	4,400	1,600	1,900	1,150	575	975	700
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	50	50	200	200	200	-	100	100
Putnam	-	-	-	-	200	200	-	-	-
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	25	200	400	200	150	125	-	-
Sarasota	-	-	50	250	200	175	-	-	-
Seminole	-	750	800	-	-	50	-	-	50
Sumter	-	-	-	1,000	950	1,000	75	75	75
Suwannee	-	150	60	200	300	325	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	100	200	200	250	425	-	-	-
Volusia	-	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	50	50	-	-	-
Miscellaneous	-	110	140	125	125	75	100	30	125
Total	-*	6,000	12,300	13,775	14,650	14,100	3,300	3,330	3,300

Note: *Green Corn not officially reported for 1946-47 Season.

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1946-47, 1947-48 AND 1948-49

Florida Counties	Escarole			Lettuce			Peas, English		
	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49
Alachua	-	-	-	25	50	-	150	75	20
Baker	-	-	-	-	-	-	-	-	-
Bradford	-	-	-	-	-	-	-	-	-
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	-	-	-	-	-	-
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-	-
Dade	-	-	-	-	-	-	-	-	-
De Soto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	50	25	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	-	225	325	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	-	-	-	-	-	-	-	-	-
Hendry	-	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	50	25	20
Hillsborough	40	50	50	325	225	150	200	100	50
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	40	-	-	25	25	-	-	-	-
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-	-
Manatee	240	225	150	225	200	100	50	25	-
Marion	50	-	25	225	100	200	25	25	20
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	190	370	350	50	60	200	-	-	-
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	1,700	2,000	1,800	400	415	600	1,000	200	200
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	-	-	-	25	25	20
Putnam	-	-	-	25	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	-	-	-	-	-	-
Sarasota	-	-	25	-	-	-	-	-	20
Seminole	500	405	350	250	200	200	50	50	25
Sumter	-	-	-	-	75	-	-	-	-
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	-	-	-
Volusia	-	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	40	50	50	50	75	50	-	50	25
Total	2,800	3,100	2,800	1,825	1,750	1,500	1,600	600	400

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASON 1946-47, 1947-48 AND 1948-49

Florida Counties	Peppers			Potatoes			Squash		
	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49
Alachua	450	550	700	1,550	1,500	450	-	150	425
Baker	-	-	-	-	-	-	-	-	-
Bradford	50	-	-	100	100	50	-	50	100
Brevard	-	-	25	-	-	-	-	-	50
Broward	2,075	1,675	1,450	-	-	-	-	1,350	1,325
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	50	-	-	-	-	-	-	25
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	50	50	-	-	-	-
Collier	-	-	-	-	-	-	-	-	25
Columbia	-	-	-	-	-	-	-	-	-
Dade	25	-	-	6,000	5,800	6,700	-	600	775
De Soto	25	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	700	600	500	-	-	-
Flagler	-	-	-	2,100	1,950	2,100	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	285	175	450	-	-	-	-	100	225
Hendry	-	-	-	-	-	-	-	75	50
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	-	-	-
Hillsborough	2,600	3,640	3,575	100	150	125	-	1,150	1,050
Holmes	-	-	-	100	-	-	-	-	-
Indian River	25	-	25	-	-	-	-	-	25
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	250	230	225	-	-	-	-	50	50
Lee	400	350	250	900	950	1,075	-	325	200
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	50	50
Madison	-	-	-	-	-	-	-	-	-
Manatee	350	75	100	-	-	-	-	250	100
Marion	150	200	150	50	50	-	-	900	1,300
Martin	225	75	150	-	-	-	-	700	600
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	250	160	200	150	75	-	-	50	75
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	1,625	2,000	1.875	3,250	1,100	1,350	-	1,200	1,600
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	525	650	500	-	-	25	-	250	225
Putnam	-	-	-	2,200	2,400	1,700	-	-	-
St. Johns	-	-	-	6,200	5,800	6,100	-	-	-
St. Lucie	100	-	50	-	-	-	-	100	125
Sarasota	25	25	-	50	-	-	-	-	-
Seminole	125	250	200	-	-	-	-	100	75
Sumter	800	800	800	-	-	-	-	50	100
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	100	75	50	100	50	-	100	225
Volusia	-	100	150	-	-	-	-	50	50
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	190	95	150	550	75	75	-	250	150
Total	10,550	11,200	11,100	24,100	20,700	20,300	-*	7,900	9,000

Note: * Squash not officially reported for 1946-47 Season

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1946-47, 1947-48 AND 1948-49

Florida	Tomatoes			Total Vegetables			Cantaloupes		
Counties	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49
Alachua	25	100	-	7,830	6,375	6,745	250	450	400
Baker	-	-	-	-	-	75	-	-	-
Bradford	25	-	-	650	675	1,100	-	25	25
Brevard	50	50	400	100	50	475	-	-	-
Broward	3,450	1,400	1,800	25,125	20,800	18,025	-	-	-
Calhoun	-	-	-	175	300	250	-	-	-
Charlotte	275	50	50	325	200	125	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	250	450	450	-	-	-
Collier	1,200	775	900	1,525	1,175	1,225	-	-	-
Columbia	-	-	-	25	550	425	-	25	25
Dade	8,200	8,900	11,700	16,700	18,790	23,250	-	-	-
De Soto	175	200	175	350	350	225	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	100	100	100	-	-	-
Escambia	-	-	-	1,000	750	675	-	-	-
Flagler	-	-	-	3,200	3,525	3,900	-	-	-
Gadsden	-	-	-	500	400	475	-	-	-
Gilchrist	-	-	-	25	-	-	-	-	-
Glades	175	860	1,075	850	2,785	2,275	-	-	-
Hamilton	-	-	-	625	400	275	50	50	-
Hardee	1,225	1,850	1,800	3,160	4,700	4,675	-	-	-
Hendry	275	325	1,000	525	800	1,525	-	-	-
Hernando	-	-	-	100	15	50	-	-	-
Highlands	25	200	100	750	825	720	-	-	-
Hillsborough	1,775	2,150	3,350	9,765	12,035	13,400	-	50	25
Holmes	-	-	-	300	150	100	-	-	-
Indian River	550	390	2,700	675	390	2,750	-	-	-
Jackson	-	-	-	375	800	600	100	-	-
Jefferson	-	-	-	50	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	125	200	225	1,860	1,955	2,575	-	50	50
Lee	550	225	175	2,850	2,715	3,125	-	-	50
Leon	-	-	-	-	-	-	-	-	-
Levy	-	50	-	100	275	100	50	75	75
Madison	-	-	-	-	-	150	50	50	25
Manatee	1,450	1,950	3,300	4,440	4,235	5,800	-	-	400
Marion	500	900	1,000	3,965	4,700	5,685	150	300	-
Martin	400	50	450	1,750	1,600	2,325	-	-	-
Okeechobee	-	700	975	-	700	975	-	-	-
Orange	-	-	-	3,215	4,780	4,950	-	-	-
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	750	975	600	71,980	70,265	74,335	-	-	-
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	175	100	100	1,275	1,575	1,420	-	-	-
Putnam	-	-	-	3,475	4,000	3,500	-	-	-
St. Johns	-	-	-	8,900	8,600	9,200	-	-	-
St. Lucie	7,450	4,800	6,500	8,175	5,375	7,375	-	-	-
Sarasota	-	-	-	1,740	1,625	1,245	-	-	-
Seminole	-	50	-	6,725	7,990	8,300	-	-	-
Sumter	650	900	1,050	2,825	3,600	4,225	50	75	25
Suwannee	-	-	-	200	450	385	50	25	25
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	700	1,125	1,625	-	-	25
Volusia	-	-	-	200	350	400	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	50	50	-	-	-
Miscellaneous	325	200	275	2,020	1,675	1,515	50	25	50
Total	29,800	28,350	39,700	201,450	205,050	223,150	800	1,200	1,200

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1946-47, 1947-48 AND 1948-49

Florida Counties	Strawberries			Watermelons			Total Miscellaneous Fruits		
	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49	1946-47	1947-48	1948-49
Alachua	-	-	-	5,000	4,700	5,400	5,250	5,150	5,800
Baker	-	-	-	-	-	-	-	-	-
Bradford	400	200	350	100	50	-	500	275	375
Brevard	-	-	-	-	50	150	-	50	150
Broward	-	-	-	100	150	50	100	150	50
Calhoun	-	-	-	150	150	800	150	150	800
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	200	150	250	200	150	250
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	50	50	50	50	50	50
Columbia	-	-	-	250	300	600	250	325	625
Dade	150	-	50	-	-	-	150	-	50
De Soto	-	-	-	100	400	550	100	400	550
Dixie	-	-	-	100	100	200	100	100	200
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-	-
Gadsden	-	-	-	-	100	-	-	100	-
Gilchrist	-	-	-	5,800	6,200	7,400	5,800	6,200	7,400
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	250	350	450	300	400	450
Hardee	400	325	300	50	75	100	450	400	400
Hendry	-	-	-	-	50	50	-	50	50
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	50	-	-	50	-
Hillsborough	3,000	3,100	2,750	500	600	800	3,500	3,750	3,575
Holmes	-	-	-	400	400	750	400	400	750
Indian River	-	-	-	-	150	200	-	150	200
Jackson	-	-	-	2,500	1,000	1,350	2,600	1,000	1,350
Jefferson	-	-	-	3,200	2,400	2,800	3,200	2,400	2,800
Lafayette	-	-	-	700	1,000	1,950	700	1,000	1,950
Lake	-	-	-	8,500	6,200	6,500	8,500	6,250	6,550
Lee	-	-	-	50	50	50	50	50	100
Leon	-	-	-	50	50	100	50	50	100
Levy	-	-	-	2,400	2,200	3,650	2,450	2,275	3,725
Madison	-	-	-	1,800	1,500	2,900	1,850	1,550	2,925
Manatee	-	-	-	150	100	150	150	100	550
Marion	-	-	-	4,550	6,500	6,800	4,700	6,800	6,800
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	-	-	-	1,100	100	300	1,100	100	300
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	-	-	-	200	150	50	200	150	50
Pasco	-	-	-	750	1,200	1,850	750	1,200	1,850
Pinellas	-	-	-	100	100	-	100	100	-
Polk	500	500	450	350	700	800	850	1,200	1,250
Putnam	-	-	-	300	150	350	300	150	350
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	50	300	350	50	300	350
Sarasota	-	-	-	50	-	-	50	-	-
Seminole	-	-	-	-	-	-	-	-	-
Sumter	150	50	50	3,200	3,500	3,900	3,400	3,625	3,975
Suwannee	-	-	-	3,000	2,400	5,900	3,050	2,425	5,925
Taylor	-	-	-	100	50	100	100	50	100
Union	-	-	-	50	200	250	50	200	275
Volusia	-	-	-	50	250	350	50	250	350
Walton	-	-	-	150	-	-	150	-	-
Washington	-	-	-	500	500	500	500	500	500
Miscellaneous	150	25	50	100	325	250	300	375	350
Total	4,750	4,200	4,000	47,000	45,000	59,000	52,550	50,400	64,200

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1946-47, 1947-48 AND 1948-49

Florida	Total Vegetables & Miscellaneous Fruits 1946-47	1947-48	1948-49	Oranges 1946-47	1947-48	1948-49	Grapefruit 1946-47	1947-48	1948-49
Alachua	13,080	11,525	12,545	-	-	-	-	-	-
Baker	-	-	75	-	-	-	-	-	-
Bradford	1,150	950	1,475	-	-	-	-	-	-
Brevard	100	100	625	11,760	11,950	12,211	3,630	3,780	3,808
Broward	25,225	20,950	18,075	3,070	3,770	3,825	300	400	443
Calhoun	325	450	1,050	-	-	-	-	-	-
Charlotte	325	200	125	-	-	-	-	-	-
Citrus	200	150	250	-	-	-	-	-	-
Clay	250	450	450	-	-	-	-	-	-
Collier	1,575	1,225	1,275	-	-	-	-	-	-
Columbia	275	875	1,050	-	-	-	-	-	-
Dade	16,850	18,790	23,300	3,030	3,230	3,248	3,720	3,760	3,805
De Soto	450	750	775	6,765	6,835	6,933	1,350	1,360	1,383
Dixie	100	100	200	-	-	-	-	-	-
Duval	100	100	100	-	-	-	-	-	-
Escambia	1,000	750	675	-	-	-	-	-	-
Flagler	3,200	3,525	3,900	-	-	-	-	-	-
Gadsden	500	500	475	-	-	-	-	-	-
Gilchrist	5,825	6,200	7,400	-	-	-	-	-	-
Glades	850	2,785	2,275	-	-	-	-	-	-
Hamilton	925	800	725	-	-	-	-	-	-
Hardee	3,610	5,100	5,075	9,090	9,290	9,495	910	910	913
Hendry	525	850	1,575	-	-	-	-	-	-
Hernando	100	150	50	1,585	1,665	1,697	360	360	360
Highlands	750	875	720	9,260	9,460	9,849	4,340	4,340	4,409
Hillsborough	13,265	15,785	16,975	17,170	17,790	18,301	3,720	3,800	3,864
Holmes	700	550	850	-	-	-	-	-	-
Indian River	675	540	2,950	5,050	5,310	5,438	6,600	6,840	7,111
Jackson	2,975	1,800	1,950	-	-	-	-	-	-
Jefferson	3,250	2,400	2,800	-	-	-	-	-	-
Lafayette	700	1,000	1,950	-	-	-	-	-	-
Lake	10,340	8,205	9,125	26,450	27,980	29,157	6,810	6,980	7,147
Lee	2,900	2,765	3,225	3,405	3,445	3,478	2,890	2,900	2,911
Leon	50	50	100	-	-	-	-	-	-
Levy	2,550	2,250	3,825	-	-	-	-	-	-
Madison	1,850	1,550	3,075	-	-	-	-	-	-
Manatee	4,590	4,335	6,350	4,655	4,785	4,866	4,870	4,890	4,924
Marion	8,665	11,500	12,485	9,065	9,335	9,442	720	730	732
Martin	1,750	1,600	2,325	-	-	-	-	-	-
Okeechobee	-	700	975	-	-	-	-	-	-
Orange	4,315	4,880	5,250	36,240	38,040	39,766	3,860	4,010	4,112
Osceola	-	-	-	4,485	4,605	4,690	900	900	903
Palm Beach	72,180	70,415	74,385	-	-	-	-	-	-
Pasco	750	1,200	1,850	7,120	7,420	7,729	1,480	1,510	1,527
Pinellas	100	100	-	7,390	7,800	7,944	7,890	8,040	8,237
Polk	2,125	2,775	2,670	58,890	61,250	63,189	26,250	26,740	27,245
Putnam	3,775	4,150	3,850	4,420	4,450	4,450	450	450	451
St. Johns	8,900	8,600	9,200	-	-	-	-	-	-
St. Lucie	8,225	5,675	7,725	8,620	9,180	10,199	4,460	4,780	5,035
Sarasota	1,790	1,625	1,245	2,610	2,630	2,649	1,080	1,100	1,106
Seminole	6,725	7,990	8,300	6,840	7,110	7,301	720	720	723
Sumter	6,225	7,225	8,200	-	-	-	-	-	-
Suwannee	3,250	2,875	6,310	-	-	-	-	-	-
Taylor	100	50	100	-	-	-	-	-	-
Union	750	1,325	1,900	-	-	-	-	-	-
Volusia	250	600	750	12,745	12,885	13,004	1,350	1,360	1,369
Walton	150	-	-	-	-	-	-	-	-
Washington	500	550	550	-	-	-	-	-	-
Miscellaneous	2,320	2,050	1,865	10,285	10,285	11,039	2,340	2,340	2,482
Total	254,000	255,430	287,350	270,000	280,500	289,900	91,000	93,000	95,000

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASONS 1946-47, 1947-48 AND 1948-49

Florida Counties	Tangerines 1946-47	Tangerines 1947-48	Tangerines 1948-49	Total Citrus 1946-47	Total Citrus 1947-48	Total Citrus 1948-49	Grand Total 1946-47	Grand Total 1947-48	Grand Total 1948-49
Alachua	-	-	-	-	-	-	13,080	11,525	12,545
Baker	-	-	-	-	-	-	-	-	75
Bradford	-	-	-	-	-	-	1,150	950	1,475
Brevard	470	470	471	15,860	16,200	16,490	15,960	16,300	17,115
Broward	100	100	105	3,470	4,270	4,373	28,695	25,220	22,448
Calhoun	-	-	-	-	-	-	325	450	1,050
Charlotte	-	-	-	-	-	-	325	200	125
Citrus	-	-	-	-	-	-	200	150	250
Clay	-	-	-	-	-	-	250	450	450
Collier	-	-	-	-	-	-	1,575	1,225	1,275
Columbia	-	-	-	-	-	-	275	875	1,050
Dade	425	435	445	7,175	7,425	7,498	24,025	26,215	30,798
De Soto	520	520	521	8,635	8,715	8,837	9,085	9,465	9,612
Dixie	-	-	-	-	-	-	100	100	200
Duval	-	-	-	-	-	-	100	100	100
Escambia	-	-	-	-	-	-	1,000	750	675
Flagler	-	-	-	-	-	-	3,200	3,525	3,900
Gadsden	-	-	-	-	-	-	500	500	475
Gilchrist	-	-	-	-	-	-	5,825	6,200	7,400
Glades	-	-	-	-	-	-	850	2,785	2,275
Hamilton	-	-	-	-	-	-	925	800	725
Hardee	660	665	668	10,660	10,865	11,076	14,270	15,965	16,151
Hendry	-	-	-	-	-	-	525	850	1,575
Hernando	830	830	834	2,775	2,855	2,891	2,875	2,870	2,941
Highlands	830	830	832	14,430	14,630	15,090	15,180	15,505	15,810
Hillsborough	1,240	1,255	1,278	22,130	22,845	23,443	35,395	38,630	40,418
Holmes	-	-	-	-	-	-	700	550	850
Indian River	525	525	526	12,175	12,675	13,075	12,850	13,215	16,025
Jackson	-	-	-	-	-	-	2,975	1,800	1,950
Jefferson	-	-	-	-	-	-	3,250	2,400	2,800
Lafayette	-	-	-	-	-	-	700	1,000	1,950
Lake	1,980	1,990	2,004	35,240	36,950	38,308	45,600	45,155	47,433
Lee	120	120	122	6,415	6,465	6,511	9,315	9,230	9,736
Leon	-	-	-	-	-	-	50	50	100
Levy	-	-	-	-	-	-	2,550	2,550	3,825
Madison	-	-	-	-	-	-	1,850	1,550	3,075
Manatee	120	125	133	9,645	9,800	9,223	14,235	14,135	16,273
Marion	400	400	401	10,185	10,465	10,575	18,850	21,965	23,060
Martin	-	-	-	-	-	-	1,750	1,600	2,325
Okeechobee	-	-	-	-	-	-	-	700	975
Orange	3,105	3,115	3,128	43,205	45,165	47,006	47,520	50,045	52,256
Osceola	590	590	591	5,975	6,095	6,184	5,975	6,095	6,184
Palm Beach	-	-	-	-	-	-	72,180	70,415	74,385
Pasco	590	590	592	9,190	9,520	9,848	9,940	10,720	11,698
Pinellas	660	670	683	15,940	16,510	16,864	16,040	16,610	16,864
Polk	5,500	5,515	5,558	90,640	93,505	95,992	92,765	96,280	98,662
Putnam	640	640	641	5,510	5,540	5,542	9,235	9,690	9,392
St. Johns	-	-	-	-	-	-	8,900	8,600	9,200
St. Lucie	900	900	903	13,980	14,860	16,137	22,205	20,535	23,862
Sarasota	-	-	-	3,690	3,730	3,755	5,480	5,355	5,000
Seminole	825	825	826	8,385	8,655	8,850	15,110	16,645	17,150
Sumter	-	-	-	-	-	-	6,225	7,225	8,200
Suwannee	-	-	-	-	-	-	3,250	2,875	6,310
Taylor	-	-	-	-	-	-	100	50	100
Union	-	-	-	-	-	-	750	1,325	1,900
Volusia	1,930	1,940	1,951	16,025	16,185	16,324	16,275	16,785	17,074
Walton	-	-	-	-	-	-	150	-	-
Washington	-	-	-	-	-	-	500	550	550
Miscellaneous	745	750	787	13,370	13,375	14,308	15,690	15,425	16,173
Total	23,705	23,800	24,000	384,705	397,300	408,900	633,705	652,730	696,250

Limes 4,600

NOTE: 1948-49 figures as of September 20 subject to revision.

SOURCE: U.S. Bureau of Agricultural Economics, Orlando, Florida.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE
BY COUNTIES AND SEASONS 1946-47, 1947-48 & 1948-49.

Source: U. S. Agricultural Statisticians, Orlando, Florida.

	1946-47				1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
ALACHUA												
Beans	200	-	1500	1700	75	-	1250	1325	150	-	1600	1750
Limas	-	-	1500	1500	-	-	750	750	-	-	1000	1000
Cabbage	-	150	-	150	-	200	-	200	-	-	-	125
Celery	-	-	130	130	-	-	100	100	-	-	100	100
Corn, Green	-	-	-	-	-	-	-	200	-	-	-	300
Cucumbers	150	-	1750	1900	25	-	1200	1225	25	-	1700	1725
Eggplant	150	-	100	250	50	-	100	150	25	-	125	150
Lettuce	-	-	25	25	-	-	-	50	-	-	-	-
Peas, English	-	150	-	150	-	75	-	75	-	-	-	20
Peppers	-	-	450	450	-	-	550	550	-	-	700	700
Potatoes	-	-	1550	1550	-	-	1500	1500	-	-	450	450
Squash	-	-	-	-	50	-	100	150	225	-	200	425
Tomatoes	-	-	25	25	-	-	100	100	-	-	-	-
Total Vegs.	500	300	7030	7830	200	275	5650	6375	425	-	5875	6745
Cantaloupes	-	-	250	250	-	-	450	450	-	-	-	400
Watermelons	-	-	5000	5000	-	-	4700	4700	-	-	-	5400
Grand Total	500	300	12280	13080	200	275	10800	11525	425	-	5875	12545
BAKER												
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	75
BRADFORD												
Beans	50	-	100	150	25	-	75	100	-	-	50	50
Limas	-	-	125	125	-	-	50	50	-	-	50	50
Cabbage	-	50	-	50	-	50	-	50	-	-	-	25
Corn, Green	-	-	-	-	-	-	-	250	-	-	-	700
Cucumbers	-	-	150	150	-	-	75	75	25	-	100	125
Peppers	-	-	50	50	-	-	-	-	-	-	-	-
Potatoes	-	-	100	100	-	-	100	100	-	-	50	50
Squash	-	-	-	-	-	-	50	50	25	-	75	100
Tomatoes	-	-	25	25	-	-	-	-	-	-	-	-
Total Vegs.	50	50	550	650	25	50	350	675	50	-	325	1100
Cantaloupes	-	-	-	-	-	-	-	25	-	-	-	25
Strawberries	-	400	-	400	-	-	200	200	-	-	-	350
Watermelons	-	-	100	100	-	-	50	50	-	-	-	-
Grand Total	50	450	650	1150	25	50	600	950	50	-	325	1475
BREVARD												
Cabbage	-	50	-	50	-	-	-	-	-	-	-	-
Peppers	-	-	-	-	-	-	-	-	-	25	-	25
Squash	-	-	-	-	-	-	-	-	50	-	-	50
Tomatoes	50	-	-	50	-	-	50	50	200	-	200	400
Total Vegs	50	50	-	100	-	-	50	50	250	25	200	475
Watermelons	-	-	-	-	-	-	50	50	-	-	-	150
BROWARD												
Beans	4500	12000	1800	18300	2400	11800	650	14850	3000	9500	-	12500
Limas	-	100	-	100	-	175	150	325	-	100	50	150
Cabbage	-	50	-	50	-	-	-	50	-	-	-	50
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	200
Cucumbers	300	50	300	650	300	300	100	700	200	-	-	200
Eggplant	50	250	200	500	-	100	350	450	-	250	100	350
Peppers	175	1900	-	2075	-	1000	675	1675	-	1150	300	1450
Squash	-	-	-	-	250	850	250	1350	250	875	200	1325
Tomatoes	500	2150	800	3450	-	1000	400	1400	300	1000	500	1800
Total Vegs.	5525	16500	3100	25125	2950	15225	2575	20800	3750	12875	1150	18025
Watermelons	-	-	100	100	-	-	150	150	-	-	-	50
Grand Total	5525	16500	3200	25225	2950	15225	2725	20950	3750	12875	1150	18075
CALHOUN												
Cucumbers	-	-	175	175	-	-	300	300	-	-	250	250
Watermelons	-	-	150	150	-	-	150	150	-	-	-	800
Grand Total	-	-	325	325	-	-	450	450	-	-	250	1050

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1946-47				1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
CHARLOTTE												
Cucumbers	50	-	-	50	50	-	50	100	50	-	-	50
Peppers	-	-	-	-	-	-	50	50	-	-	-	-
Squash	-	-	-	-	-	-	-	-	25	-	-	25
Tomatoes	150	-	125	275	-	-	50	50	-	25	25	50
Total Vegs.	200	-	125	325	50	-	150	200	75	25	25	125
CITRUS												
Watermelons	-	-	200	200	-	-	150	150	-	-	-	250
CLAY												
Cabbage	-	200	-	200	-	400	-	400	-	-	-	450
Potatoes	-	-	50	50	-	-	50	50	-	-	-	-
Total Vegs.	-	200	50	250	-	400	50	450	-	-	-	450
COLLIER												
Cucumbers	200	-	125	325	200	150	50	400	100	200	-	300
Squash	-	-	-	-	-	-	-	-	-	25	-	25
Tomatoes	250	700	250	1200	-	275	500	775	200	300	400	900
Total Vegs.	450	700	375	1525	200	425	550	1175	300	525	400	1225
Watermelons	-	-	50	50	-	-	50	50	-	-	-	50
Grand Total	450	700	425	1575	200	425	600	1225	300	525	400	1275
COLUMBIA												
Cabbage	-	25	-	25	-	50	-	50	-	-	-	50
Corn, Green	-	-	-	-	-	-	-	400	-	-	-	275
Cucumbers	-	-	-	-	-	-	100	100	-	-	-	100*
Total Vegs.	-	25	-	25	-	50	100	550	-	-	-	425
Cantaloupes	-	-	-	-	-	-	25	25	-	-	-	25
Watermelons	-	-	250	250	-	-	300	300	-	-	-	600
Grand Total	-	25	250	275	-	50	425	875	-	-	-	1050
DADE												
Beans	-	1700	300	2000	200	2500	300	3000	-	3500	100	3600
Limas	-	50	50	100	-	-	-	-	-	-	-	-
Cabbage	-	350	-	350	-	250	-	250	-	-	-	250
Carrots	-	25	-	25	-	50	-	50	-	-	-	75
Corn, Green	-	-	-	-	-	-	-	65	-	-	-	100
Cucumbers	-	-	-	-	-	50	75	125	-	50	-	50
Peppers	-	25	-	25	-	-	-	-	-	-	-	-
Potatoes	-	6000	-	6000	-	5800	-	5800	-	6700	-	6700
Squash	-	-	-	-	50	500	50	600	50	675	50	775
Tomatoes	1500	6200	500	8200	200	6450	2250	8900	200	9600	1900	11700
Total Vegs.	1500	14350	850	16700	450	15600	2675	18790	250	20525	2050	23250
Strawberries	-	150	-	150	-	-	-	-	-	-	-	50
Grand Total	1500	14500	850	16850	450	15600	2675	18790	250	20525	2050	23300
DE SOTO												
Corn, Green	-	-	-	-	-	-	-	50	-	-	-	-
Cucumbers	75	-	50	125	-	-	100	100	-	-	50	50
Eggplant	-	-	-	25	-	-	-	-	-	-	-	-
Peppers	25	-	-	25	-	-	-	-	-	-	-	-
Tomatoes	25	-	150	175	-	-	200	200	-	-	175	175
Total Vegs.	150	-	200	350	-	-	300	350	-	-	225	225
Watermelons	-	-	100	100	-	-	400	400	-	-	-	550
Grand Total	150	-	300	450	-	-	700	750	-	-	225	775
DIXIE												
Watermelons	-	-	100	100	-	-	100	100	-	-	-	200
DUVAL												
Cabbage	-	100	-	100	-	100	-	100	-	-	-	100
ESCAMBIA												
Beans	-	-	250	250	-	-	100	100	-	-	100	100
Cabbage	-	50	-	50	-	50	-	50	-	-	-	75
Potatoes	-	-	700	700	-	-	600	600	-	-	500	500
Total Vegs.	-	50	950	1000	-	50	700	750	-	-	600	675

* Pickles.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1946-47				1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
FLAGLER												
Cabbage	-	1000	-	1000	-	1500	-	1500	-	-	-	1750
Cucumbers	-	-	50	50	-	-	50	50	-	-	50	50
Peas, English	-	50	-	50	-	25	-	25	-	-	-	-
Potatoes	-	-	2100	2100	-	-	1950	1950	-	-	2100	2100
Total Vegs.	-	1050	2150	3200	-	1525	2000	3525	-	-	2150	3900
GADSDEN												
Beans	150	-	300	450	150	-	200	350	200	-	200	400
Cabbage	-	50	-	50	-	50	-	50	-	-	-	75
Total Vegs.	150	50	300	500	150	50	200	400	200	-	200	475
Watermelons	-	-	-	-	-	-	100	100	-	-	-	-
GILCHRIST												
Eggplant	25	-	-	25	-	-	-	-	-	-	-	-
Watermelons	-	-	5800	5800	-	-	6200	6200	-	-	-	7400
Grand Total	25	-	5800	5825	-	-	6200	6200	-	-	-	7400
GLADES												
Cabbage	-	450	-	450	-	1500	-	1500	-	-	-	1200
Corn, Green	-	-	-	-	-	-	-	100	-	-	-	-
Lettuce	-	225	-	225	-	325	-	325	-	-	-	-
Tomatoes	175	-	-	175	150	160	550	860	575	-	500	1075
Total Vegs.	175	675	-	850	150	1985	550	2785	575	-	500	2275
HAMILTON												
Cabbage	-	50	-	50	-	50	-	50	-	-	-	25
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	125
Cucumbers	-	-	575	575	-	-	350	350	-	-	-	125*
Total Vegs.	-	50	575	625	-	50	350	400	-	-	-	275
Cantaloupes	-	-	50	50	-	-	50	50	-	-	-	-
Watermelons	-	-	250	250	-	-	350	350	-	-	-	450
Grand Total	-	50	875	925	-	50	750	800	-	-	-	725

* Pickles

	1946-47				1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
HARDEE												
Beans	-	-	50	50	50	-	-	50	-	-	-	-
Cabbage	-	50	-	50	-	150	-	150	-	-	-	-
Corn, Green	-	-	-	-	-	-	-	200	-	-	-	350
Cucumbers	800	-	600	1400	1200	-	900	2100	1000	-	500	1500
Eggplant	150	-	-	150	75	-	-	75	350	-	-	350
Peppers	260	-	25	285	125	-	50	175	400	-	50	450
Squash	-	-	-	-	50	-	50	100	25	100	100	225
Tomatoes	25	-	1200	1225	-	-	1850	1850	200	-	1600	1300
Total Vegs.	1235	50	1875	3160	1500	150	2850	4700	1975	100	2250	4675
Strawberries	-	400	-	400	-	325	-	325	-	-	-	300
Watermelons	-	-	50	50	-	-	75	75	-	-	-	100
Grand Total	1235	450	1925	3610	1500	475	2925	5100	1975	100	2250	5075
HENDRY												
Cabbage	-	50	-	50	-	-	-	-	-	-	-	-
Cucumbers	150	-	50	200	200	150	50	400	275	200	-	475
Squash	-	-	-	-	25	50	-	75	25	25	-	50
Tomatoes	250	-	25	275	-	125	200	325	500	400	100	1000
Total Vegs.	400	50	75	525	225	325	250	800	800	625	100	1525
Watermelons	-	-	-	-	-	-	50	50	-	-	-	50
HERNANDO												
Beans	-	-	100	100	-	-	-	-	-	-	-	-
Eggplant	-	-	-	-	15	-	-	15	50	-	-	50
Total Vegs.	-	-	100	100	15	-	-	15	50	-	-	50
HIGHLANDS												
Beans	200	-	350	550	-	-	500	500	-	200	350	550
Cabbage	-	25	-	25	-	-	-	25	-	-	-	-
Carrots	-	25	-	25	-	25	-	25	-	-	-	-
Cucumbers	50	-	-	50	-	-	50	50	-	-	50	50
Eggplant	25	-	-	25	-	-	-	-	-	-	-	-
Peas, English	-	50	-	50	-	-	-	25	-	-	-	20
Tomatoes	25	-	-	25	-	-	200	200	-	-	100	100
Total Vegs.	300	100	350	750	-	25	750	825	-	200	500	720
Watermelons	-	-	-	-	-	-	50	50	-	-	-	-
Grand Total	300	100	350	750	-	25	800	875	-	200	500	720

Note: * Pickles

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1946-47				1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
HILLSBOROUGH												
Beans	150	-	1700	1850	200	-	875	1075	200	-	1100	1300
Limas	-	-	500	500	-	-	100	100	-	-	100	100
Cabbage	-	750	-	750	-	350	-	350	-	-	-	250
Cauliflower	-	300	-	300	-	225	-	225	-	-	-	250
Corn,Green	-	-	-	-	-	-	-	650	-	-	-	1000
Cucumbers	275	-	700	975	250	-	1075	1325	600	-	850	1450
Eggplant	75	25	250	350	95	-	750	845	50	-	650	700
Escarole	-	40	-	40	-	50	-	50	-	-	-	50
Lettuce	-	325	-	325	-	225	-	225	-	-	-	150
Peas,English	-	200	-	200	-	100	-	100	-	-	-	50
Peppers	-	-	2600	2600	10	-	3630	3640	75	-	3500	3575
Potatoes	-	-	100	100	-	-	150	150	-	-	125	125
Squash	-	-	-	-	100	-	1050	1150	250	-	800	1050
Tomatoes	425	-	1350	1775	450	250	1450	2150	1400	200	1750	3350
Total Vegs.	925	1640	7200	9765	1105	1200	9080	12035	2575	200	8875	13400
Cantaloupes	-	-	-	-	-	-	-	50	-	-	-	25
Strawberries	-	3000	-	3000	-	3100	-	3100	-	-	-	2750
Watermelons	-	-	500	500	-	-	600	600	-	-	-	800
Grand Total	925	4640	7700	13265	1105	4300	9680	15785	2575	200	8875	16975
HOLMES												
Cucumbers	-	-	200	200	-	-	150	150	-	-	-	100*
Potatoes	-	-	100	100	-	-	-	-	-	-	-	-
Total Vegs.	-	-	300	300	-	-	150	150	-	-	-	100
Watermelons	-	-	400	400	-	-	400	400	-	-	-	750
									* pickles			
INDIAN RIVER												
Cucumbers	-	-	75	75	-	-	-	-	-	-	-	-
Eggplant	-	25	-	25	-	-	-	-	-	-	-	-
Peppers	-	-	25	25	-	-	-	-	-	25	-	25
Squash	-	-	-	-	-	-	-	-	25	-	-	25
Tomatoes	350	-	200	550	50	40	300	390	1300	-	1400	2700
Total Vegs.	350	25	300	675	50	40	300	390	1325	25	1400	2750
Watermelons	-	-	-	-	-	-	150	150	-	-	-	200
JACKSON												
Cucumbers	-	-	375	375	-	-	800	800	-	-	250	600*
Cantaloupes	-	-	100	100	-	-	-	-	-	-	-	-
Watermelons	-	-	2500	2500	-	-	1000	1000	-	-	-	1350
Grand Total	-	-	2975	2975	-	-	1800	1800	-	-	250	1950
									* Includes 350 pickles			
JEFFERSON												
Beans	-	-	50	50	-	-	-	-	-	-	-	-
Watermelons	-	-	3200	3200	-	-	2400	2400	-	-	-	2800
LAFAYETTE												
Watermelons	-	-	700	700	-	-	1000	1000	-	-	-	1950
LAKE												
Beans	-	-	100	100	150	-	150	300	50	-	300	350
Cabbage	-	150	-	150	-	200	-	200	-	-	-	200
Carrots	-	20	-	20	-	-	-	-	-	-	-	-
Celery	-	225	650	875	-	125	500	625	-	125	750	875
Corn,Green	-	-	-	-	-	-	-	-	-	-	-	200
Cucumbers	75	-	200	275	50	-	250	300	200	-	200	400
Eggplant	-	-	-	-	-	-	25	25	25	-	25	50
Escarole	-	40	-	40	-	-	-	-	-	-	-	-
Lettuce	-	25	-	25	-	25	-	25	-	-	-	-
Peppers	100	-	150	250	30	-	200	230	25	-	200	225
Squash	-	-	-	-	-	-	50	50	-	-	50	50
Tomatoes	25	-	100	125	-	-	200	200	25	-	200	225
Total Vegs.	200	460	1200	1860	230	350	1375	1955	325	125	1725	2575
Cantaloupes	-	-	-	-	-	-	-	50	-	-	-	50
Watermelons	-	-	8500	8500	-	-	6200	6200	-	-	-	6500
Grand Total	200	460	9700	10360	230	350	7575	8205	325	125	1725	9125

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1946-47				1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
LEE												
Corn, Green	-	-	-	-	-	-	-	100	-	-	-	400
Cucumbers	500	-	200	700	300	200	50	550	600	200	-	800
Eggplant	100	150	50	300	15	100	100	215	50	100	75	225
Peppers	250	150	-	400	50	250	50	350	50	200	-	250
Potatoes	-	900	-	900	-	950	-	950	-	1050	25	1075
Squash	-	-	-	-	75	250	-	325	50	150	-	200
Tomatoes	450	100	-	550	75	150	-	225	100	75	-	175
Total Vegs.	1300	1300	250	2850	515	1900	200	2715	850	1775	100	3125
Cantaloupes	-	-	-	-	-	-	-	-	-	-	-	50
Watermelons	-	-	50	50	-	-	50	50	-	-	-	50
Grand Total	1300	1300	300	2900	515	1900	250	2765	850	1775	100	3225
LEON												
Watermelons	-	-	50	50	-	-	50	50	-	-	-	100
LEVY												
Cabbage	-	50	-	50	-	25	-	25	-	-	-	25
Corn, Green	-	-	-	-	-	-	-	100	-	-	-	25
Cucumbers	-	-	50	50	-	-	50	50	-	-	-	-
Squash	-	-	-	-	-	-	50	50	-	-	50	50
Tomatoes	-	-	-	-	-	-	50	50	-	-	-	-
Total Vegs.	-	50	50	100	-	25	150	275	-	-	50	100
Cantaloupes	-	-	50	50	-	-	75	75	-	-	-	75
Watermelons	-	-	2400	2400	-	-	2200	2200	-	-	-	3650
Grand Total	-	50	2500	2550	-	25	2425	2550	-	-	50	3825
MADISON												
Cucumbers	-	-	-	-	-	-	-	-	-	-	-	150*
Cantaloupes	-	-	50	50	-	-	50	50	-	-	-	25
Watermelons	-	-	1800	1800	-	-	1500	1500	-	-	-	2900
Grand Total	-	-	1850	1850	-	-	1550	1550	-	-	-	3075
MANATEE												
Beans	50	-	500	550	200	-	250	450	250	-	250	500
Cabbage	-	200	-	200	-	300	-	300	-	-	-	300
Cauliflower	-	200	-	200	-	100	-	100	-	-	-	150
Celery	-	75	-	75	-	60	-	60	-	-	-	-
Corn, Green	-	-	-	-	-	-	-	100	-	-	-	450
Cucumbers	500	-	225	725	100	-	275	375	200	-	350	550
Eggplant	150	100	125	375	75	-	50	125	100	-	100	200
Escarole	-	240	-	240	-	225	-	225	-	-	-	150
Lettuce	-	225	-	225	-	200	-	200	-	-	-	100
Peas, English	-	50	-	50	-	25	-	25	-	-	-	-
Peppers	250	-	100	350	25	-	50	75	100	-	-	100
Squash	-	-	-	-	50	-	200	250	50	-	50	100
Tomatoes	700	-	750	1450	400	250	1300	1950	1300	300	1700	3300
Total Vegs.	1650	1090	1700	4440	850	1160	2125	4235	2000	300	2450	5800
Cantaloupes	-	-	-	-	-	-	-	-	-	-	-	400
Watermelons	-	-	150	150	-	-	100	100	-	-	-	150
Grand Total	1650	1090	1850	4590	850	1160	2225	4335	2000	300	2450	6350
MARION												
Beans	300	-	1000	1300	200	-	600	800	350	-	800	1150
Limas	-	-	600	600	-	-	250	250	-	15	150	165
Cabbage	-	-	400	400	-	500	-	500	-	-	-	400
Celery	-	60	130	190	-	-	500	500	-	-	225	225
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	600
Cucumbers	25	-	250	275	25	-	250	275	75	-	250	325
Eggplant	200	-	-	200	150	-	50	200	100	-	25	125
Escarole	-	50	-	50	-	-	-	-	-	-	-	25
Lettuce	-	200	25	225	-	-	-	100	-	-	-	200
Peas, English	25	-	-	25	-	25	-	25	-	-	-	20
Peppers	-	-	150	150	-	-	200	200	-	-	150	150
Potatoes	-	-	50	50	-	-	50	50	-	-	-	-
Squash	-	-	-	-	400	-	500	900	600	-	700	1300
Tomatoes	-	-	500	500	-	-	900	900	-	-	1000	1000
Total Vegs.	550	310	3105	3965	775	525	3300	4700	1125	15	3300	5685
Cantaloupes	-	-	150	150	-	-	300	300	-	-	-	-
Watermelons	-	-	4550	4550	-	-	6500	6500	-	-	-	6800
Grand Total	550	310	7805	8665	775	525	10100	11500	1125	15	3300	12485

* Pickles

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1946-47				1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
MARTIN												
Beans	200	200	200	600	200	-	400	600	-	200	350	550
Limas	-	125	-	125	-	50	-	50	-	-	-	-
Cabbage	-	100	-	100	-	75	-	75	-	-	-	50
Cucumbers	100	-	-	100	-	-	-	-	175	300	-	475
Eggplant	50	125	25	200	-	25	25	50	-	50	-	50
Peppers	75	100	50	225	-	50	25	75	25	100	25	150
Squash	-	-	-	-	200	400	100	700	250	300	50	600
Tomatoes	300	100	-	400	-	-	50	50	300	-	150	450
Total Vegs.	725	750	275	1750	400	600	600	1600	750	950	575	2325
OKEECHOBEE												
Tomatoes	-	-	-	-	150	-	550	700	425	-	550	975
ORANGE												
Beans	150	-	200	350	600	-	-	600	375	-	-	375
Cabbage	-	-	800	800	-	600	-	600	-	-	-	600
Carrots	-	330	-	330	-	280	-	280	-	-	-	300
Celery	-	315	380	695	-	310	550	860	-	325	525	850
Corn, Green	-	-	-	-	-	-	-	1350	-	-	-	1600
Cucumbers	50	-	350	400	100	-	275	375	100	-	300	400
Escarole	-	190	-	190	-	370	-	370	-	-	-	350
Lettuce	-	50	-	50	-	60	-	60	-	-	-	200
Peppers	250	-	-	250	160	-	-	160	200	-	-	200
Potatoes	-	-	150	150	-	-	75	75	-	-	-	-
Squash	-	-	-	-	-	-	50	50	25	-	50	75
Total Vegs.	450	885	1880	3215	860	1620	950	4780	700	325	875	4950
Watermelons	-	-	1100	1100	-	-	100	100	-	-	-	300
Grand Total	450	885	2980	4315	860	1620	1050	4880	700	325	875	5250
PALM BEACH												
Beans	13300	14500	23600	51400	16000	19900	12600	48500	20000	18500	13800	52300
Limas	-	1200	650	1850	-	1200	950	2150	-	685	650	1335
Cabbage	-	3500	-	3500	-	3600	-	3600	-	-	-	3250
Carrots	-	50	-	50	-	-	-	-	-	-	-	75
Celery	-	3000	1280	4280	-	1900	2100	4000	-	1550	1550	3100
Corn, Green	-	-	-	-	-	-	-	1250	-	-	-	4400
Cucumbers	1000	200	400	1600	900	700	300	1900	600	550	-	1150
Eggplant	125	250	200	575	-	100	875	975	-	250	450	700
Escarole	-	1700	-	1700	-	2000	-	2000	-	-	-	1800
Lettuce	-	350	50	400	-	-	-	415	-	-	-	600
Peas, English	-	1000	-	1000	-	200	-	200	-	-	-	200
Peppers	125	1400	100	1625	-	1100	900	2000	-	1300	575	1875
Potatoes	-	2800	450	3250	-	500	600	1100	-	900	450	1350
Squash	-	-	-	-	250	800	150	1200	400	1000	200	1600
Tomatoes	200	500	50	750	25	250	700	975	200	-	400	600
Total Vegs.	14750	30450	26780	71980	17175	32250	19175	70265	21200	24735	18075	74335
Watermelons	-	-	200	200	-	-	150	150	-	-	-	50
Grand Total	14750	30450	26980	72180	17175	32250	19325	70415	21200	24735	18075	74385
PASCO												
Watermelons	-	-	750	750	-	-	1200	1200	-	-	-	1850
PINELLAS												
Watermelons	-	-	100	100	-	-	100	100	-	-	-	-
POLK												
Beans	-	-	200	200	-	-	100	100	-	-	150	150
Cabbage	-	150	-	150	-	100	-	100	-	-	-	50
Corn, Green	-	-	-	-	-	-	-	50	-	-	-	50
Cucumbers	100	-	100	200	-	-	200	200	-	-	200	200
Eggplant	-	-	-	-	-	-	100	100	-	-	100	100
Peas, English	-	25	-	25	-	25	-	25	-	-	-	20
Peppers	25	-	500	525	-	-	650	650	-	-	500	500
Potatoes	-	-	-	-	-	-	-	-	-	-	25	25
Squash	-	-	-	-	-	-	250	250	-	-	225	225
Tomatoes	-	-	175	175	-	-	100	100	-	-	100	100
Total Vegs.	125	175	975	1275	-	125	1400	1575	-	-	1300	1420
Strawberries	-	500	-	500	-	500	-	500	-	-	-	450
Watermelons	-	-	350	350	-	-	700	700	-	-	-	800
Grand Total	125	675	1325	2125	-	625	2100	2775	-	-	1300	2670

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1946-47				1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
PUTNAM												
Beans	-	-	250	250	-	-	-	-	-	-	-	-
Cabbage	-	1000	-	1000	-	1400	-	1400	-	-	-	1600
Cucumbers	-	-	-	-	-	-	200	200	-	-	200	200
Lettuce	-	-	25	25	-	-	-	-	-	-	-	-
Potatoes	-	-	2200	2200	-	-	2400	2400	-	-	1700	1700
Total Vegs.	-	1000	2475	3475	-	1400	2600	4000	-	-	1900	3500
Watermelons	-	-	300	300	-	-	150	150	-	-	-	350
Grand Total	-	1000	2775	3775	-	1400	2750	4150	-	-	1900	3850
ST. JOHNS												
Cabbage	-	2700	-	2700	-	2800	-	2800	-	-	-	3100
Potatoes	-	-	6200	6200	-	-	5800	5800	-	-	6100	6100
Total Vegs.	-	2700	6200	8900	-	2800	5800	8600	-	-	6100	9200
ST.LUCIE												
Limas	-	100	-	100	-	50	-	50	-	150	25	175
Cabbage	-	-	-	-	-	200	-	200	-	-	-	100
Cauliflower	-	-	-	-	-	-	-	-	-	-	-	75
Corn,Green	-	-	-	-	-	-	-	25	-	-	-	200
Cucumbers	200	-	200	400	150	-	50	200	150	-	-	150
Eggplant	50	50	25	125	-	-	-	-	-	-	-	-
Peppers	75	-	25	100	-	-	-	-	-	50	-	50
Squash	-	-	-	-	-	-	100	100	25	-	100	125
Tomatoes	4450	-	3000	7450	1300	600	2900	4800	3200	-	3300	6500
Total Vegs.	4775	150	3250	8175	1450	850	3050	5375	3375	200	3425	7375
Watermelons	-	-	50	50	-	-	300	300	-	-	-	350
Grand Total	4775	150	3300	8225	1450	850	3350	5675	3375	200	3425	7725
SARASOTA												
Cabbage	-	100	-	100	-	75	-	75	-	-	-	-
Cauliflower	-	30	-	30	-	-	-	-	-	-	-	-
Celery	-	925	360	1285	-	975	350	1325	-	775	200	975
Corn,Green	-	-	-	-	-	-	-	-	-	-	-	50
Cucumbers	100	-	150	250	75	-	125	200	75	-	100	175
Escarole	-	-	-	-	-	-	-	-	-	-	-	25
Peas,English	-	-	-	-	-	-	-	-	-	-	-	20
Peppers	25	-	-	25	-	25	-	25	-	-	-	-
Potatoes	-	-	50	50	-	-	-	-	-	-	-	-
Total Vegs.	125	1055	560	1740	75	1075	475	1625	75	775	300	1245
Watermelons	-	-	50	50	-	-	-	-	-	-	-	-
SEMINOLE												
Beans	350	-	200	550	500	-	75	575	1000	-	500	1500
Cabbage	-	1000	-	1000	-	1500	-	1500	-	-	-	1600
Carrots	-	50	-	50	-	20	-	20	-	-	-	-
Cauliflower	-	50	-	50	-	25	-	25	-	-	-	100
Celery	-	2700	1450	4150	-	2915	1150	4065	-	2200	1150	3350
Corn,Green	-	-	-	-	-	-	-	750	-	-	-	800
Cucumbers	-	-	-	-	-	-	-	-	-	-	50	50
Eggplant	-	-	-	-	-	-	-	-	-	-	50	50
Escarole	-	500	-	500	-	405	-	405	-	-	-	350
Lettuce	-	250	-	250	-	-	-	200	-	-	-	200
Peas,English	-	50	-	50	-	50	-	50	-	-	-	25
Peppers	25	-	100	125	-	-	250	250	-	-	200	200
Squash	-	-	-	-	50	-	50	100	25	-	50	75
Tomatoes	-	-	-	-	-	-	50	50	-	-	-	-
Total Vegs.	375	4600	1750	6725	550	4915	1575	7990	1025	2200	2000	8300
SUMTER												
Beans	-	-	250	250	100	-	550	650	150	-	1000	1150
Cabbage	-	50	-	50	-	100	-	100	-	-	-	50
Cucumbers	200	-	800	1000	200	-	750	950	300	-	700	1000
Eggplant	-	-	75	75	25	-	50	75	25	-	50	75
Lettuce	-	-	-	-	-	75	-	75	-	-	-	-
Peppers	-	-	800	800	-	-	800	800	-	-	800	800
Squash	-	-	-	-	-	-	50	50	25	-	75	100
Tomatoes	50	-	600	650	-	-	900	900	-	-	1050	1050
Total Vegs.	250	50	2525	2825	325	175	3100	3600	500	-	3675	4225
Cantaloupes	-	-	50	50	-	-	75	75	-	-	-	25
Strawberries	-	150	-	150	-	50	-	50	-	-	-	50
Watermelons	-	-	3200	3200	-	-	3500	3500	-	-	-	3900
Grand Total	250	200	5775	6225	325	225	6675	7225	500	-	3675	8200

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS.

	1946-47				1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
SUWANNEE												
Corn, Green	-	-	-	-	-	-	-	150	-	-	-	60
Cucumbers	-	-	200	200	-	-	300	300	-	-	200	325*
Total Vegs.	-	-	200	200	-	-	300	450	-	-	200	385
Cantaloupes	-	-	50	50	-	-	25	25	-	-	-	25
Watermelons	-	-	3000	3000	-	-	2400	2400	-	-	-	5900
Grand Total	-	-	3250	3250	-	-	2725	2875	-	-	200	6310
TAYLOR												
Watermelons	-	-	100	100	-	-	50	50	-	-	-	100
UNION												
Beans	-	-	250	250	50	-	225	275	275	-	250	525
Limas	-	-	150	150	-	-	50	50	-	-	25	25
Cabbage	-	50	-	50	-	150	-	150	-	-	-	100
Corn, Green	-	-	-	-	-	-	-	100	-	-	-	200
Cucumbers	50	-	150	200	50	-	200	250	225	-	200	425
Peppers	-	-	-	-	-	-	100	100	-	-	75	75
Potatoes	-	-	50	50	-	-	100	100	-	-	50	50
Squash	-	-	-	-	50	-	50	100	50	-	175	225
Total Vegs.	50	50	600	700	150	150	725	1125	550	-	775	1625
Cantaloupes	-	-	-	-	-	-	-	-	-	-	-	25
Watermelons	-	-	50	50	-	-	200	200	-	-	-	250
Grand Total	50	50	650	750	150	150	925	1325	550	-	775	1900
VOLUSIA												
Cabbage	-	200	-	200	-	200	-	200	-	-	-	200
Peppers	-	-	-	-	-	-	100	100	-	-	150	150
Squash	-	-	-	-	-	-	50	50	-	-	50	50
Total Vegs.	-	200	-	200	-	200	150	350	-	-	200	400
Watermelons	-	-	50	50	-	-	250	250	-	-	-	350
Grand Total	-	200	50	250	-	200	400	600	-	-	200	750
WALTON												
Watermelons	-	-	150	150	-	-	-	-	-	-	-	-
WASHINGTON												
Cucumbers	-	-	-	-	-	-	50	50	-	-	-	50*
Watermelons	-	-	500	500	-	-	500	500	-	-	-	500
Grand Total	-	-	500	500	-	-	550	550	-	-	-	550
MISCELLANEOUS												
Beans	100	100	250	450	100	100	100	300	-	100	100	200
Limas	-	25	25	50	25	-	50	75	-	-	50	50
Cabbage	-	100	-	100	-	100	-	100	-	-	-	50
Carrots	-	-	-	-	-	25	-	25	-	-	-	50
Cauliflower	-	20	-	20	-	50	-	50	-	-	-	25
Celery	-	-	20	20	-	15	50	65	-	25	-	25
Corn, Green	-	-	-	-	-	-	-	110	-	-	-	140
Cucumbers	50	50	25	125	25	-	100	125	25	-	50	75
Eggplant	25	25	50	100	-	5	25	30	25	50	50	125
Escarole	-	40	-	40	-	50	-	50	-	-	-	50
Lettuce	-	50	-	50	-	-	-	75	-	-	-	50
Peas, English	-	-	-	-	-	-	-	50	-	-	-	25
Peppers	90	25	75	190	50	25	20	95	25	50	75	150
Potatoes	-	200	350	550	-	50	25	75	-	50	25	75
Squash	-	-	-	-	100	50	100	250	50	50	50	150
Tomatoes	100	50	175	325	50	50	100	200	75	100	100	275
Total Vegs.	365	685	970	2020	350	520	570	1675	200	425	500	1515
Cantaloupes	-	-	50	50	-	-	25	25	-	-	-	50
Strawberries	-	150	-	150	-	25	-	25	-	-	-	50
Watermelons	-	-	100	100	-	-	325	325	-	-	-	250
Grand Total	365	835	1120	2320	350	545	920	2050	200	425	500	1865

*Includes 125 pickles (Suwannee)

* pickles (Washington)

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

TOTAL ALL COUNTIES

	1945-46				1946-47			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	22100	38000	20100	80200	19700	28500	33500	81700
Limas	-	2675	4325	7000	-	1600	3600	5200
Cabbage	-	13200	-	13200	-	14000	-	14000
Carrots	-	-	-	-	-	500	-	500
Cauliflower	-	-	-	-	-	600	-	600
Celery	-	8550	4900	13450	-	7300	-	7300
Cucumbers	2700	750	8500	11950	5000	300	8475	13775
Eggplant	1400	825	1825	4050	1200	1000	1100	3300
Escarole	-	2600	-	2600	-	2800	-	2800
Lettuce	-	1500	450	1950	-	1700	125	1825
Peas, English	-	2000	-	2000	-	1600	-	1600
Peppers	1700	3800	6500	12000	1750	3600	5200	10550
Potatoes	-	13600	21700	35300	-	9900	14200	24100
Tomatoes	5300	15000	17000	37300	10000	9800	10000	29800
Total Vegetables	33200	102500	85300	221000	37650	83200	80600	201450
Cantaloupes	-	-	800	800	-	-	800	800
Strawberries	-	2800	-	2800	-	4750	-	4750
Watermelons	-	-	-	51000	-	-	47000	47000
Grand Total	33200	105300	86100	275600	37650	87950	128400	254000

	1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	21200	34300	19000	74500	26000	32000	21000	79000
Limas	-	1500	2350	3850	-	950	2100	3050
Cabbage	-	16700	-	16700	-	-	-	16000
Carrots	-	400	-	400	-	-	-	500
Cauliflower	-	400	-	400	-	-	-	600
Celery	-	6300	5300	11600	-	5000	4500	9500
Corn, Green	-	-	-	6000	-	-	-	12300
Cucumbers	4200	1550	8900	14650	5000	1500	6600	14100*
Eggplant	500	330	2500	3330	800	700	1800	3300
Escarole	-	3100	-	3100	-	-	-	2800
Lettuce	-	-	-	1750	-	-	-	1500
Peas, English	-	600	-	600	-	-	-	400
Peppers	450	2450	8300	11200	900	2900	7300	11100
Potatoes	-	7300	13400	20700	-	8700	11600	20300
Squash	1700	2900	3300	7900	2500	3200	3300	9000
Tomatoes	2850	9600	15900	28350	10500	12000	17200	39700
Total Vegetables	30900	87430	78950	205030	45700	66950	75400	223150
Cantaloupes	-	-	1200	1200	-	-	-	1200
Strawberries	-	4200	-	4200	-	-	-	4000
Watermelons	-	-	45000	45000	-	-	-	59000
Grand Total	30900	91630	125150	255430	45700	66950	75400	287350

Note: * Includes 1,000 acres pickles.

PRODUCTION AND VALUE OF AVOCADOS AND LIMES 1929-1949

	AVOCADOS					LIMES (Persian Type)			Avocados & Persian Limes Combined Gross FOB Value
	Crop Volume Tons	Bu. 50 Lbs.	Value Ton	Value Bu.	Gross FOB Value	Crop Volume 1-3/5 bu. Boxes	Value Box	Gross FOB Value	
1929	420	16,800	$142	$3.55	$ 59,640	$ 8,000	$4.50	$ 36,000	$ 95,640
1930	620	24,800	192	4.80	119,040	8,000	4.00	32,000	151,040
1931	820	32,800	145	3.63	118,900	9,000	3.50	31,500	150,400
1932	1400	56,000	88	2.20	123,200	10,000	3.00	30,000	153,200
1933	2200	88,000	98	2.45	215,600	12,000	2.50	30,000	245,600
1934	2000	80,000	75	1.88	150,000	15,000	3.00	45,000	195,000
1935	1000(a)	40,000	95	2.38	95,000	12,000	3.75	45,000	140,000
1936	600(b)	24,000	120	3.00	72,000	45,000(f)	3.25	146,250	218,250
1937	2100	84,000	95	2.38	199,500	70,000	3.25	227,500	427,000
1938	2200	88,000	64	1.60	140,800	95,000	2.60	247,000	387,800
1939	2500	100,000	68	1.70	170,000	95,000	2.80	266,000	436,000
1940	880(c)	35,200	98	2.45	86,240	80,000	2.85	228,000	314,240
1941	1250	50,000	100	2.50	125,000	150,000	2.10	315,000	440,000
1942	2100	84,000	136	3.40	285,600	175,000	2.36	413,000	698,600
1943	4600(d)	184,000	120	3.00	552,000	190,000	4.79(g)	910,100	1,462,100
1944	5800	232,000	140	3.50	812,000	250,000	4.86(g)	1,215,000	2,027,000
1945	3200	128,000	144	3.60	460,800	200,000	3.58	716,000	1,176,800
1946	1600(e)	64,000	336	8.40	537,600	170,000	3.95	671,500	1,209,100
1947	2300	92,000	200	5.00	460,000	170,000	3.34	567,800	1,027,800
1948	3100	124,000	180	4.50	558,000	200,000	2.80	560,000	1,118,000
1949	Probably Lower	-	-	Approx. Same	-	250,000	Probably Lower	-	-

NOTES: (a) Lower yield account freeze December 9, 1934.
(b) Lower yield account hurricane in November 1935.
(c) Lower yield account freeze of January 26-30. Extremely severe.
(d) Higher yield account good crop and care with full harvesting, affected by higher prices.
(e) Lower yield account hurricane November 15-16, 1945.
(f) Heavy increase in yield account new acreage in Polk County coming into production.
(g) High prices due to shortage and high prices of California lemons.

CITRUS TRUCKED THROUGH ROAD GUARD STATIONS 1948-49 SEASON

Open October 15, 1948 to June 19, 1949

(Tabulated from Records of Citrus & Vegetable Inspection Division,
Winter Haven, Florida)

Carloads of 400 Boxes

STATION	HIGHWAY	ORANGES	GRAPEFRUIT	TANGERINES	TOTAL CITRUS
GROUP 1					
Wilcox	U.S. 19	7,618	1,506	411	9,535
Luraville	Fla. 51	1	LCL	LCL	1
Branford	Fla. 20	190	32	13	235
Ellaville	U.S. 90	787	152	64	1,003
Suwannee Springs	U.S. 129	95	24	7	126
White Springs	U.S. 41	6,509	1,709	667	8,885
GROUP 2					
Hilliard	U.S. 1	4,827	1,495	412	6,734
Yulee	U.S. 17	9,416	2,635	1,126	13,177
Lake City	Fla. 47*	49	13	3	65
Total		29,492	7,566	2,703	39,761

Stations in Group 1 are at bridges over Suwannee River; those in Group 2 are at bridges over St.Marys River.

* Lake City Station covers a minor road and is in a separate group.

FLORIDA TRUCK UNLOADS IN 3 MARKETS 1948-49 SEASON

August 1-July 31

Commodity	NEW YORK		LCL(a)	PHILADELPHIA		LCL(a)	(c) CHICAGO		Florida Straight	Florida Truck
	Freight	Truck(b)	Express	Freight	Truck(b)	Express	Freight& Express	Truck(b)	Shipments	Shipments
Oranges	7,455	999	-	2,750	370	-	1,034	1,890	26,685	30,356
Grapefruit	4,213	221	-	1,317	94	-	579	528	13,818	8,708
Tangerines	1,036	138	-	334	62	-	165	316	2,924	2,702
Mixed Citrus	1,962	-	857	757	-	-	90	-	8,125	-
Total Citrus	14,666	1,358	857	5,158	526	-	1,868	2,734	51,552	41,766
Beans & Limas	1,573	891	1	540	554	-	321	271	3,628	5,992
Cabbage	1,009	110	-	513	112	-	339	11	5,457	3,543
Celery	1,551	419	-	571	135	-	927	85	9,345	2,345
Cucumbers	395	790	4	71	239	1	150	255	1,052	2,564
Corn, Green	563	289	-	112	144	-	88	27	1,223	1,803
Eggplant	65	266	2	7	121	1	1	49	70	1,153
Escarole	658	112	-	69	32	-	62	17	974	284
Lettuce	82	33	-	5	13	-	-	1	102	142
Peppers	869	563	8	126	265	3	94	193	1,364	2,983
Potatoes	676	183	-	481	177	-	416	10	6,593	2,697
Tomatoes	1,476	400	1	680	327	-	749	210	6,783	6,907
Cauliflower	20	21	-	6	16	-	*	-	d	d
Dandelions, Green	36	9	-	*	-	-	*	-	d	d
Endive-Chicory	61	18	-	16	13	-	7	3	d	d
Broccoli	*	12	-	*	-	-	*	-	d	d
Spinach	9	-	2	*	1	-	*	-	d	d
Squash	132	200	17	1	34	2	6	18	250	1,098
Celery-Cabbage	*	32	8	*	6	-	8	19	d	d
Okra	*	63	9	*	8	2	*	9	d	d
Radishes	29	35	2	8	17	-	6	19	d	d
Sweet Potatoes	8	5	-	*	-	-	10	1	d	d
Miscl. Vegetables	5	19	7	1	8	-	4	8	352	2,075
Mixed Vegetables	755	-	1	250	-	-	279	-	4,472	-
Total Vegetables	9,972	4,470	62	3,257	2,222	9	3,467	1,206	41,665	33,586
Strawberries	47	142	2	-	52	-	22	28	110	410
Watermelons	1,614	38	-	601	21	-	519	40	8,864	4,838
Avocados	-	58	4	-	6	-	7	18	15	150
Limes	1	66	5	-	11	-	1	26	24	204
Mangoes	-	4	18	-	-	-	-		-	2
Miscl. Fruits	-	1	2	-	19	1	-	3	-	54
Total Miscl. Fruits	1,662	309	31	601	109	1	549	115	9,013	5,708
GRAND TOTAL	26,300	6,137	950	9,016	2,857	10	5,884	4,059	102,230	81,060

* Included in Mixed Vegetables if any received.

(a) If no receipts shown it is presumed there were no receipts, or else included in freight, or else not reported.

(b) Small amounts less than ½ carload may have been omitted.

(c) Chicago reported rail receipts which probably included express.

(d) Included in Mxd or Miscl. Vegs.

NEW DEVELOPMENTS IN FLORIDA EGG AND POULTRY PRODUCTION

By F. W. Risher, Marketing Specialist, Dairy and Poultry Products

Only a few years ago most people looked upon Florida as a white egg market, and most commercial poultrymen kept white Leghorn hens. Then just prior to the World War Number Two, poultrymen began to develop flocks of heavy breed layers mostly of the New Hampshire breed. As a result consumers began to find brown eggs on the market that were of just as good quality as the white eggs from commercial poultry farms. Today there are many more commercial brown eggs on the market than white eggs.

POULTRY COOPERATIVES TO GRADE, PACK AND MARKET EGGS

There are four egg cooperatives operating very successfully at the present time; one of them operating in Duval County; one in Bristol, Florida, covering Liberty and Calhoun Counties; one in Orlando, covering the central part of the State; and one located in Hernando County. These associations have all the modern equipment found in commercial egg plants. The one at Bristol has a cooler with an egg holding capacity of 700 cases.

BROILER PRODUCTION INCREASING

Broiler production began in a small way around cities where there was a ready market years ago. Recently areas of heavy production away from the cities began to develop in West Florida in Walton County, and in North Florida around Palatka. Today more fryers are produced by commercial plants than by general farmers.

LEADING EGG PRODUCING COUNTIES 1943

RANK	COUNTY	RANK	COUNTY
1	Hillsboro	5	Polk
2	Pasco	6	Jackson
3	Nassau	7	Marion
4	Duval	8	Orange

TURKEYS

1	Gilchrist	5	Marion
2	Levy	6	Alachua
3	Suwannee	7	Sumter
4	Gadsden	8	Lake

GEESE

1	Jackson
2	Duval
3	Madison
4	Pasco

LEADING COMMERCIAL BROILER COUNTIES

RANK	COUNTY	RANK	COUNTY
1	Walton	5	Dade
2	Putnam	6	Pasco
3	Duval	7	Polk
4	Hillsboro	8	Holmes

DUCKS

1	Duval	5	Orange
2	Dade	6	Volusia
3	Hillsboro	7	Marion
4	Pasco	8	Alachua

GUINEAS

1	Polk	5	Gilchrist
2	Jackson	6	Marion
3	Hillsboro	7	Levy
4	Gadsden	8	Alachua

LOCATION OF LARGEST COMMERCIAL POULTRY STOCKS

WHITES

RANK	COUNTY
1	Nassau
2	Columbia
3	Manatee
4	Alachua

REDS

RANK	COUNTY
1	Hillsboro
2	Hernando
3	Pasco
4	Duval

TURKEYS

RANK	COUNTY
1	Gadsden
2	Marion
3	Sumter
4	Lake

POULTRY AND EGG MARKET NEWS REPORTS

The Florida State Marketing Bureau issues a daily report on Florida poultry and eggs which is carried over the Associated Press to most Florida daily newspapers, and a twice weekly mail report.

The Production and Marketing Administration of the U.S. Department of Agriculture, 449 West Peachtree Street, Atlanta, Georgia, issues a daily report on the North Georgia shipping point broiler market, and other shipping point markets from Delaware to Arkansas. Egg and poultry terminal market prices are shown for New York, Chicago, Atlanta and other markets.

FEDERAL-STATE INSPECTION SERVICE
July 1, 1948 - June 30, 1949

FLORIDA Commodities	Type of Container	Rail Cars Inspected	No. of Units or Containers	Average Containers (or Units per Car)				
				1948-49	47-48	46-47	45-46	44-45
Oranges	Std 1-3/5 Bu	25,217	12,528,281	497	499	503	502	505
Grapefruit	Box Equiv.	12,945	6,462,372	499	515	515	514	514
Tangerines	"	2,848	1,246,487	438	437	442	449	452
Mixed Citrus	"	8,307	4,130,110	497	494	505	497	494
Total Citrus		49,317	24,369,250	492	498	503	500	500
Beans	Bu hprs.	73	45,516	624	636	641	633	620
Cabbage	50# sks.	1,214	609,462	502	501	503	501	508
"	W.B.Crts.	2,696	1,292,842	480	481	-	-	-
Celery	Std.Fla.Crts.	7,873	3,358,345	427	423	425	445	443
Corn	Std Crts.	649	359,762	554	510	442	-	-
"	50# sks.	2	1,092	546	-	-	696	620
Cucumbers	Bu.	95	35,993	379	373	459	437	570
Escarole	Bu. hprs.	2	1,280	640	640	612	642	610
Peppers	Bu.	94	56,145	597	526	672	652	782
Potatoes	Coml.50#sks.	2,853	1,936,396	679	641	651	619	638
"	Bu.	5	3,292	658	-	563	-	642
"	Com.100# sks.	2,378	715,037	301	297	307	300	300
"	Gov. 50#sks.	234	145,506	622	-	-	-	-
"	Gov.100#sks.	169	55,030	326	360	355	300	-
Tomatoes	30# Lugs	3,405	2,292,292	673	681	693	689	691
"	Bu.	68	28,303	416	-	-	-	-
"	40# Box	6	3,763	627	-	-	-	-
Mxd or Miscl.	Various	111	55,440	499	407	602	-	578
Sweet Potatoes	Bu.	-	-	-	539	527	552	539
Total Vegetables		21,927	10,925,496					
Watermelons	Melons	7,906	14,160,000*	978	985	938	1008	1058
Limes	1-3/5Bu Box	-	-	-	399	-	364	397
Total Rail Fruits & Vegs		29,833	18,723,623*					
		Car Equiv. by Truck						
Citrus,Com'l	Std 1-3/5 Bu	39,846	18,395,723	500	400	400	400	400
" Processing	"	24,276	12,138,723	500	400	400	400	400
Vegetables	Various	6,724	3,239,065	-	-	-	-	-
Miscl.Fruits	Various	410	201,261	-	-	-	-	-
Total Trucked Out Fruits and Vegetables		71,258	33,974,772					
Rail & Truck Grand Total		150,408	77,667,545*	512 average				

* By using 2 watermelons as a unit.

NOTE: Except for citrus, celery, cabbage, corn, potatoes, tomatoes and watermelons, the inspection sample was too limited to show the average rail carlot loadings. Loadings are sometimes different in different sections of Florida. For some vegetables the official inspections are little used.

The above is tabulated from a report made by Mr. Hugh S. Flynt, Assistant Director, Vegetable Branch, Citrus and Vegetable Inspection Division, Florida Department of Agricultur, Room 305, Post Office Building, Orlando, Florida.

This Table is last in our report but it is not the least valuable. We have it where it can best be found for frequent use.

Frank H. Scruggs
Market News Specialist
Florida State Marketing Bureau

END

FLORIDA STATE MARKETING BUREAU

ANNUAL FRUIT AND VEGETABLE REPORT

PRODUCTION, TRANSPORTATION AND MARKETING ANALYSIS

1949-50 SEASON

(Also Poultry, Egg, Livestock, Tobacco and Field Crop Statistics)

See outline map on back cover

By Frank H. Scruggs, Market News Specialist

Neill Rhodes, Commissioner
Florida State Marketing Bureau
Division of
Florida State Department of Agriculture
Nathan Mayo, Commissioner

This Annual Report is available free of charge to parties interested

Released October 23, 1950

Florida State Marketing Bureau
505 West Adams Street
P. O. Box 779
Jacksonville 1, Florida

ACKNOWLEDGMENT

We wish to acknowledge the splendid cooperation we received from both official and private sources during the preparation of this rather comprehensive statistical report.

The rail freight and express carlot shipment figures were secured from the Fruit and Vegetable Branch of the Production and Marketing Administration, U.S. Department of Agriculture in Washington, D.C.

Exhaustive vegetable acreage, yield, production and value data and other assistance was supplied by Mr. J. C. Townsend, Jr., Mr. J. B. Owens, and Mr. Paul Shuler, Agricultural Statisticians, and Mr. G. N. Rose, Truck Crop Statistician, U.S. Bureau of Agricultural Economics, Federal Building, Orlando, Florida.

Mr. A. L. Scarborough, Statistician of the Citrus and Vegetable Division, Florida Department of Agriculture, Winter Haven, Florida, supplied us with important record data and other information. Mr. Hugh S. Flynt, Assistant Director of this division, supplied a detailed summary of inspections for the season. The daily reports from their Road Guard Stations, operated by the Citrus and Vegetable Division, showing passings of fruits and vegetables, were very helpful to shippers and growers throughout the season and for record purposes in this report.

Mr. H. F. Willson, Federal-State Citrus Market News Service, also supplied useful data for use in this report. Mr. Willson is located in Lakeland, Florida.

Mr. William B. Conner, of the Florida Citrus Exchange, Tampa, wholeheartedly complied with our requests for specified citrus information.

Several official and private agencies and individuals not already mentioned supplied information directly or indirectly to us, for which we extend our thanks.

The preparation of this report is tedious and requires long and hard work, and appreciation by the writer is extended to our Bureau staff for their efforts and accomplishments. Commissioner L. Neill Rhodes contributed and Introductory which is information and well worth your reading. Mr. L. H. Lewis, Specialist, Live Stock and Field Crops, and Mr. Gifford N. Rhodes, Specialist, Live Stock Market News, and Mr. F. W. Risher, Specialist, Dairy and Poultry Products, of this Bureau, supplied certain livestock and poultry information.

FOREWORD

Inasmuch as this Annual Report has just been completed I am full of the subject and will tell some of the younger generation a few things about the Florida fruit and vegetable business and Florida statistics. Several days ago I read that some sort of a research economist had made a study which brought out the fact that 43 percent of the people did not remember anything about the affairs of the nation prior to 1941. Many of our foremost economists have no recollection of business affairs prior to 1930, and still fewer remember 1923, and even fewer were worrying about marketing or other business affairs in 1916. Just to set the record straight, I gave such things no thought before 1920.

The Federal Market News service and Inspection service was started in 1916 and in a very limited way. The late Commissioner L. M. Rhodes helped to get the bill through Congress to start the old U.S. Bureau of Markets.

Commissioner Rhodes came to Florida in 1917 to start off the Florida State Marketing Bureau, and headed it until his decease in 1946.

I went with the Federal Market News service in 1923 and came to Sanford on the celery deal in January 1924, and back again in 1925 to operate the Federal-State Market News service for celery. In those days the Market News service and the Inspection service in the United States was very young but vigorous. Crop estimates on fruits and vegetables was very limited. Mr. H. A. Marks, who later established the Crop and Livestock Reporting service in Orlando for Florida, was a roving crop reporter who covered all of the states from North Carolina to Florida to Arkansas.

Carlot shipment figures were not complete as the system for collecting these daily shipments was not well established. All shipment figures prior to 1925 were incomplete and cannot be considered accurate. As a matter of fact no statistics prior to 1925 were anything like as complete and accurate as they are today. Remarkable pregress has been made in the collection of statistics during the last twenty years.

Back in 1924 Florida had very poor roads, just as most other states did. A great road building program began in 1925 and has continued to this day. No one had any any thoughts at that time of a truck transportation system for long hauls of Florida fruits and vegetables. There were no large trailer trucks on the roads.

After the Florida real estate boom and collapse in 1925 and the improvement in the Florida and Southern highways, the truck movement of citrus first started and it gained impetus during the early part of the national depression in 1930-31. Many men with no jobs started hauling fruit to large and small markets to make a living. Vegetable movement by truck did not catch on until later.

We had a pretty good life back in 1923 even though we did not have radios or canned or concentrated citrus, and not much income tax either. I remember back in 1925 when some of the more inventive minds in Orlando and Sanford were trying to find some perfect method of putting up citrus segments and juice in a vacuum container in order to preserve the real flavor of the natural fruit. They said we did not have over-production but under-consumption of citrus and that we needed to reach the consumer in the summer months when we did not have fresh fruit. In those years the citrus season was practically over at the end of April and did not get started good before November 15. These foresignted men saw most of the uses to which present canned citrus and concentrates have been put but they did not realize that a less perfect method would do. Someone came along later and canned citrus juice and segments just as canned tomatoes and juice had been put up. The canned products did not have the natural fruit taste but they were well liked and became almost indispensable. It has been said that drier sections of the West could never have been settled without canned tomatoes as a food source, as a thirst quencher, and as a source of vitamins. Just think how much faster and better the West could have been settled with the aid of citrus juices. A drink of Florida citrus juice would have made even the wildest Indian jump with joy and lay down his tomahawk. Citrus juices have replaced tomato juice on most shelves. Citrus juices in fact have top priority among juices.

Citrus concentrates were a development during World War II to preserve transportation space, in being sent to our service men overseas and to our undernourished civilian allies in other lands. Concentrates gained wide popularity and with constant improvements have now become the talk of the world along with the war in Korea.

When I came with the State Marketing Bureau August 1929 it was just the right time to prepare the Annual Report of the previous year's fruit and vegetable business. At that time the report was a four-page report and I think that I increased it to ten pages that first year. The next year it had more pages and it has been increased year by year as more basic information became available, until now it covers 106 pages of tabulations without an inch of waste space. In fact, it should be spread out better over 200 pages. The Annual Report has been a report which grew from year to year just like Topsy -- or whoever it was. Sometimes people ask me, "How in Heaven's name did you ever get all those figures together?" We simply have grown old along with the industry and we just put our accumulated knowledge in statistical form from year to year. We have a wonderful source of information in the Florida Crop and Livestock Service (U.S. Bureau of Agricultural Economics), in Orlando. The head of that office, Mr. J. C. Townsend, has been in Florida fruit and vegetables for 27 years, and in the statistical office for almost that long. Mr. J. B. Owens, his first assistant, has been there many years. Commissioner Neill Rhodes of this Bureau has 33 years consecutive service in this Bureau. I have been in Florida fruit and vegetable marketing information service for 26 years. Neither the U.S. Department of Agriculture or the Florida Department of Agriculture ever relieves a man they think is doing a good job in Florida. The U.S. Department of Agriculture recognizes, quite rightly, the importance of the Florida fruit and vegetable industry. Mr. H. F. Willson, a Federal Market News man, who operates the Federal-State Citrus Market News service in Lakeland, has been there for many, many years.

Florida statistics are not just statistics to us, as we have seen, and have been a part of the events which brought on the statistics.

This leads me to say that my sweat and tears, if not blood, have gone into this Annual Report for the past 21 years, and I feel a little like it's mine; and this reminds me of a storey I heard as a boy in Sweetwater, Tennessee. The Mt. Harmony Baptist Church was looking for a new location for a new church and decided to ask Mr. Boller, a well to do farmer, to donate a corner of his land. Mr. Boller replied, saying he would not only give them the land but would build them a church too. Soon afterwards there was a Sunday School convention in Chattanooga and the church asked Mr. Boller, who was a good but not very reverent man, to go as one of their delegates. He agreed to go, and did go. When the moderator called the meeting to order he proceeded to introduce the delegates and ask them to stand. When he came to the Monroe County delegation he asked Mr. Boller to stand, saying, "Mr. Boller, I understand you belong to the Mt. Harmony Church;" whereupon Mr. Boller replied, "Hell, no! The damn thing belongs to me." With that he sat down, and with this I sit down too.

HOLD EVERYTHING! A late report on Hurricane Damage.

Orlando, October 21--A preliminary report of the Bureau of Agricultural Economics of the U.S. Department of Agriculture today placed Florida citrus losses in the hurricane of Wednesday and Thursday at from 2,500,000 to 3,000,000 boxes.

Grapefruit losses were heaviest, J. C. Townsend, statistician for the Bureau said, with an estimated 1,500,000 to 2,000,000 boxes knocked off trees and orange losses were estimated at 1,000,000 boxes.

The Indian River section, and Indian River County in particular, appeared to have sustained the greatest loss, Townsend said. The State citrus crop will be resurveyed as of November 1 and adjustments in the present estimate made in the November 10 report.

The State's crop picture changed drastically during the week, the U.S. office here said. Heavy rain and strong winds caught the important Pompano and Everglades farming sections as the storm swept the length of the State from Miami to Jacksonville. The Federal report said planting of Fall crops was well advanced in the Pompano section and therefore losses were quite heavy to snap beans, lima beans, cucumbers, eggplant, pepper and squash. Most will have to be replanted.

In the Everglades, most important Fall snap bean area, loss was heavy to acreage ready for harvest late this month and early November. Only light harvesting is expected from the surviving acreage. Reseeding started almost immediately after the storm. Other Sections had some damage too.

INTRODUCTORY

By

Neill Rhodes

Commissioner, State Marketing Bureau

Preliminary figures of Florida Census indicate a population of nearly 2-3/4 million. If the total Florida production of fruits and vegetables, the greater proportion shipped interstate plus home consumption, had to be marketed within the State, the obvious solution in the minds of many to the greatest need for disposing of such volume as indicated by Mr. Scruggs' report, would be PEOPLE. Stretching the imagination still further, if the total Florida agricultural production were shifted to China where the total population is estimated at 400 to 450 million people, or India and Pakistan where the population is estimated at around 420 million, in the minds of many the obvious solution to the profitable marketing of a given Florida agricultural production would be MONEY. It might appear on first analysis that there are either too many people or too little food, since the two are badly out of balance, but the greatest need, were food abundant, would be the wherewithal to purchase it. The plain facts are that while the best fed nations are becoming better fed, some of the worst-fed nations have become worse fed.

According to United Nations Educational, Scientific and Cultural Organization, the increase of the world population is about 1 percent a year, which means about 2 million per month, 475,000 a week, nearly 68,000 a day. The 2.3 billion people on earth, increased by about 1 percent per year, on a world-wide basis provides sufficient consuming population. In the United States where we have surpluses and support programs, we also have people on relief, welfare agencies, with plenty domestic and foreign competition. A very large segment of our own population is unable to purchase the top grades of our products. All of our population does not have all the food desired or needed, even though there are surpluses of some food products. Unless the consumer has the money to purchase even the surplus placed before him, the surplus will go begging and the consumer without. Even if production were sufficient to abundantly feed the people of the world and distribution facilities existed to transport world-wide production to remote bartering posts, the average consumption would not increase without increased purchasing power, or gratis disposition.

It is not easy for the farmers of Florida and much of the general American public, who know of the United States surplus production, price levels for some of which are dangerously near or below production cost, to realize there is not enough food to go around in other parts of the world. UNESCO points out that half of the

(Cont'd.)

world's people are ill-fed and undernourished; another one-sixth do not have enough food for good nutrition, and only one-third have enough food on the average.

If all of the people were able to buy all the food that could be produced, certainly the earth could feed the present or the future population. Given an assured net profit sufficient to stimulate productive endeavor on all the land tillable in Florida, the potential production possibilities of this State alone are almost beyond estimate. Of the world's land surface of 36 billion acres, according to estimates given only half can be tilled, only one-tenth or about 3.6 billion acres are under cultivation which can be made to produce 20 percent more. It is estimated that an additional 1.3 billion acres, mostly in tropical regions, can be opened to cultivation. Part of the sea area, 89 billion acres, of the world contributes significantly to the food supply. The greatest new land potential lies in the tropics, but with more already produced than can be profitably sold now through market outlets, our growers will manifest little excitement about the development of land in tropical regions for increasing food production. They well remember that from 1929 to 1941 Brazil burned 75 million bags of coffee, 1/3 of its total output, because there was no market. They will recall that in the 1930's the world witnessed the destruction of vast food surpluses while people starved.

Introductory to the comprehensive summary tabulations in this Annual Report efficiently and untiringly prepared by Mr. F. H. Scruggs, covering statistically so many different phases of Florida's commercial and total production of food products, some might like to take a quick gander at the world-wide picture which I have briefly outlined. I have also emphasized that marketing does not depend exclusively on either production or population -- even hungry millions -- or distribution, but also on money or its purchase equivalent. Whether we look at global conditions or pin-point our focus upon individuals, we can find undernourished and ill-fed people not only in other parts of the world but also in the United States, in our own state, county, and city. The probabilities are that you can recall one or more in your own vicinity who do not have a sufficient diet of say 3250 calories per day.

So long as we have hungry American citizens, we have not perfected our system of food distribution and marketing at home, much less exports to foreign lands. In delving into interesting data spread upon the pages following, may you see both the "trees and the forest," in perspective of the "wilderness" overseas.

GENERAL TABLE OF CONTENTS

CITRUS FRUITS ONLY (Oranges, Grapefruit and Tangerines)

	Page Number
Acreage, Yield, Boxes per Tree and Grove Value 1942-43 to 1949-50	7
Volume, Value and Disposition of Citrus 1949-50 Season	8 - 9
Citrus Acreage and Production in Florida, California, Texas and Arizona	26
Citrus Trees by Age Groups	27
Growth in Production Citrus Juices and Concentrates	28 - 31
Shipments, Volume and Valuations for 22 Years	32 - 39
Auction Prices in 10 Markets, 1932-33 to 1949-50	40 - 42
Prices Paid by Canners, Volume Processed 1940-41 to 1949-50	43
Analysis of Citrus Prices from 1932-33 to 1949-50 Season	44 - 45
Tree to Auction Costs or Vice Versa for 3 Years	46
Auction Prices for Indian River Citrus	47
Truck Distribution by States 1948-49 and 1949-50 Seasons	48
Rail Distribution by States 1948-49 and 1949-50 Seasons	49
F.O.B. Prices, 1909-10 to 1949-50 Season	71
Persian Limes Certified for Shipment for 1949-50	104
Inspection of Citrus for Shipment by Counties, 1949-50 Season	105

VEGETABLES AND MISCELLANEOUS FRUITS ONLY

F.O.B. Values by Commodities for 16 Seasons	5
Truck Shipments of Vegetables by Weeks 1949-50 Season	24 - 25
Acreage, Yield and Value, Fall, Winter, and Spring 1949-50 Season	60 - 61
Acreage, Fall, Winter and Spring by Counties, 1947-48 & 1948-49 & 1949-50.	62 - 70
Acreage, Yield and Value by Seasons 1931-32 to 1949-50	81 - 85
Acreage of Principal Truck Crops 25 Seasons	86 - 87

ALL FRUITS AND VEGETABLES

Summary	1 - 3
Production and Value for 15 Seasons	4
Disposition All Fruits and Vegetables for 1949-50 Season	10 - 11
Freight, Express, Boat and Truck Shipments 1949-50 Season	12 - 15
Freight, Express, Boat and Truck Shipments for 10 Seasons	16 - 19
Freight Shipments by Rail, by Counties 1949-50 Season	20 - 23
County Acreage-All Fruits and Vegetables, 3 Seasons	72 - 80
Avocado and Lime Production for 1929-1950 Seasons	104
Citrus Passings Through Road Guard Stations, 1949-50 Season	105
Federal-State Inspections and Car Loadings, 1949-50 Season	106

GENERAL AGRICULTURAL STATISTICS

Florida Agricultural Volume and Value 1949-50 Season	6
Poultry and Egg Prices - Jacksonville, Tampa and Miami, by Years and Months	50 - 53
General Farm Crops - Volume and Value 1930-1950	54 - 56
Average Prices Received for Florida Farm Products September 15, 1950	57
Tobacco - Flue Cured, Sun Cured and Shade 1932-1950. Auction Prices also.	58 - 59
Livestock Prices, Jacksonville (Southeastern Prices), by Years and Months	88 - 89
Livestock Plants, Markets, Numbers, Value, etc.	90 -101
Poultry and Egg Production Facts and County Rankings	102 -103

OUTLINE MAP OF FLORIDA. See back cover of this Annual Report.

FLORIDA DEPARTMENT OF AGRICULTURE
STATE MARKETING BUREAU
1949-50
ANNUAL FRUIT AND VEGETABLE REPORT
By Frank H. Scruggs, Market News Specialist

The 1949-50 season which ended officially with the July shipments was noteworthy in one important respect and that was the unușually favorable citrus prices for the season after disappointing sales in the fall. Most of the citrus industry had expected a very good grapefruit year in Florida because of the considerably lower volume in Florida, also the lower volume in Texas and Arizona as a result of freezes the year before. The heavy demand for oranges and a reasonably good demand for grapefruit by the concentrators and other processors took more citrus out of fresh fruit sales channels than had ever been taken before and at high average prices. This improved the fresh fruit market.

The vegetable season was not exciting to the general public as we had no severe freezes to wipe out the production. There were several light to fairly heavy frosts in spots and there were numerous heavy rains and high winds which did considerable damage in certain sections. We also had the dry spells which were bad at certain times in certain sections.

Altogether the weather was as good or better than normal for vegetables. It must have been, as we produced more carloads than ever before. This brings to mind the city fellow who was hunting in the farm country and came to a rather wide stream which he had to cross. He couldn't swim and he was concerned about the depth. He spied a young boy sitting on the bank fishing and said, "Son, is this stream shallow?" to which the boy replied, "It must be shallow;" whereupon the city huntsman jumped into the stream, went down under a couple of times, and finally managed to get back on the bank. He was wet, and he was made with the boy, and he said, "Dumbhead, you said this stream was shallow." The boy said, "I didn't say it was shallow. I said it must be shallow because I just saw a duck walk across."

This brings us up to the facts and figures for the 1949-50 season. We produced 288,357 carloads of fruits and vegetables, with a gross Florida value of $361,706,000, or approximately $1254 per carload. The volume and price includes fruit and vegetables shipped out of Florida, that processed and that consumed in Florida. The volume of 288,357 compares favorably with the record volume of 323,481 carloads in 1948-49; and the gross value of $361,706,000 in 1949-50 compares with the record high value of $364,330,000 in the 1945-46 season. The 1935-36 season volume of 127,181 carloads with a gross value of $76,734,000 or $603 per carload shows that we have more than doubled our production and prices. Please see page 4.

If you progress to page 5 of this report you come to the f.o.b. packed value of vegetables for the last 16 seasons. You may notice that tomatoes in 1949-50 accounted for 32 percent of the total for vegetables. A better picture which shows acreage, yield per acre, total production and unit price, can be found on pages 81-85.

We reserved page 6 to show the agricultural volume and value of fruits, vegetables, livestock, dairy and poultry and products, general field crops, nuts, nursery and hothouse and specialty crops. The total value for 1949-50 season or the latest season available was $547,782,000 as compared with the previous report of $504,951,000. We added figures for lumber, naval stores, fishery products, and mineral production, to give you $268,877,000 and a rounded out picture of the products of Florida land and nearby waters, for a grand total of $816,659,000 as compared to the previous report of $729,896,000.

Some people in Florida and in other states have no yardstick for measuring the value of a grove. On page 7 we have set forth figures which show the value of the average grove based on the average yield and the average gross return per box on fruit sold for all purposes.

We do not think it advisable to buy a grove solely on the record it had the previous year. Crop volumes in other states and many other factors enter into the calculations. The study of page 7 will help anyone who wishes to know more about grove values. We have been told that, so it must be so.

Two pages to which the writer has to refer most during the year are pages 8 and 9, showing the disposition and the gross and net values of citrus.

Following you will find a disposition tabulation for vegetables. We do not recommend these figures as we had to make too many estimates and compromises to make our component parts equal the total production figures supplied by other sources.

Pages 12-15 are devoted to the shipments by months, and pages 16-19 by years for the various means of transportation. Our total carlot shipment of 166,757 in 1949-50 was higher than any previous season except that of 1948-49 when we had 187,030 carloads.

Rail shipments by counties are next shown. It should be pointed out that one county may have some of its production shipped from, and credited to another county.

Truck shipments of vegetables by weeks are shown on pages 24-25 and it is the best means of seeing when the season begins and ends, and the volume between.

For those of you who use comparative acreage and production citrus figures for Florida, California, Texas and Arizona, pages 26-27 will be of interest.

We have prepared or reproduced some very interesting information on citrus concentrates and canned products on pages 28-31. We have a lot of inquiries on this.

On pages 32-37 can be found, if you look, comprehensive citrus shipment and value figures for the last 23 seasons. These figures are followed by citrus auction prices in 10 markets for all of the seasons beginning in 1932-33.

Inasmuch as canners and processors take so much of our fruit it should be interesting to compare the 1949-50 prices with those for preceding years. We have these prices by months beginning in the 1941-42 season. We do not have them for prior years. See page 43; also see Citrus Price Analysis on page 44.

We have the estimated cost from tree to auction on page 46. We inadvertently omitted the details of marketing charges for the 1949-50 season. We make a good many mistakes but we generally have to wait for someone to tell us about them. We sometimes get both dizzy and woozy before we get through with all these figures. In the lower tabulation the initials RBT means Rail, Boat, and Truck, if anyone is in doubt about it. Truck shipments did not play much of a part in carload movement to auctions prior to 1946-47 season. See pages 46-47.

We have truck and rail distribution of citrus to other states on pages 48-49 but we have no present way of obtaining similar accurate information for vegetables.

POULTRY AND EGGS

Although many of our readers may be interested only in fruits and vegetables, we have other agricultural business in Florida. We have a good size poultry business and on pages 50-53 are the prices of eggs, hens and fryers in Jacksonville, Tampa, Miami and Orlando. Yes, we have worries other than fruits and vegetables. All of these price quotations are made by representatives of the State Marketing Bureau and play an important part in the marketing of poultry and eggs. Our quotations serve as the basis of trading and we get plenty of grief. This work is really ulcerating at times. While pondering the subject of poultry please turn to pages 102-103, which will show you where the poultry and eggs come from. We positively do not know which came first.

The production and values of Florida field crops are not neglected, as you can see on pages 54-57. The two following pages are devoted to tobacco. I would like to tell you the story of the tobacco farmer who was figuring 2½ percent of $6500 but space will not permit. He got some unexpected and interesting assistance, as well as a new car.

Detailed figures for acreage, yield, products, and value of vegetables and miscellaneous fruits can be found on pages 60-70. The acreage by counties and commodities is included, and on pages 72-80 follow fruit and vegetable acreages by commodities and counties. We give it to you both ways. More of the same on pages 81-87.

LIVESTOCK

Our livestock industry is very important and is growing every day, month and year. We now may have more good bulls than good men -- that is, with pedigrees. We have 14 pages of the livestock facts and figures. Florida has 2,243,000 head of livestock, with a gross farm value of $128,329,000 after sales in 1949 amounting to $45,576,000. Florida livestock has a great future and has been showing remarkable growth during the past twenty years with accelerated growth during past ten years.

We have devoted page 104 to avocados and limes for the benefit of the agricultural students and economists. They have in the past asked for these figures.

Page 105 was used to show the inspections of citrus for rail and truck shipment in the various counties. The actual shipments were substantially the same as the inspections for shipment, which included intrastate as well as interstate. Most, if not all of these inspections were made at packing houses. Some fruit may be grown in one county and hauled to a packing house in another county, perhaps just a short distance away. At times fruit may go a long distance, 100--150 miles from one county to a packing house in another county. Once a truck is loaded in the grove it's only a matter of two or three hours more time and more gasoline to go to a packing house 100-150 miles away. On page 105 we also show the passings of citrus through the various Florida Citrus Road Guard Stations.

The Federal-State Inspection service in Florida inspected a total of 155,256 carloads of commodities. See page 6.

CITRUS

ORANGES: Our production of 58,500,000 boxes in 1949-50 was almost equalled in 1947-48 and in 1948-49, but not exceeded. Polk, Orange, Lake, Hillsboro, and Volusia are the leading orange counties, according to bearing acreage.

GRAPEFRUIT: The production of 24,200,000 boxes in 1949-50 has been exceeded in every year since the end of World War II. The record production was the 1943-44 season with 31,000,000. Polk, Pinellas, Lake, Indian River, and St. Lucie are the leading counties in point of acreage.

TANGERINES: The tangerine production in 1949-50 was estimated at 5,000,000 boxes, which was higher than any previous season. Leading counties were Polk, Orange, Lake, Volusia, and Hillsboro.

ALL CITRUS: The leading counties in point of orange, grapefruit, and tangerine acreage were: Polk, Orange, Lake, Hillsboro, Pinellas, Brevard, Volusia, St. Lucie, Highlands, and Indian River.

VEGETABLES

BEANS: The production of 7,082,000 was less than the record year of 8,004,000 bushels in 1943-44. The gross value of $17,354,000 was about the average for the last eight seasons. Palm Beach, Broward, and Dade, with Alachua and Marion tied for fourth place, closely followed by Seminole, are the leading counties in point of acreage. Palm Beach had more than 60 percent of the state acreage last season.

CABBAGE: Production of 183,600 tons, of which 56,900 tons were abandoned because of poor markets, was the heaviest production on record. Palm Beach, St. Johns, Flagler, Putnam and Glades were the leading counties.

CORN: Production in 1947-48 was only 480,000 crates, 1,680,000 crates in 1948-49, and 3,480,000 crates in 1949-50, of which 530,000 crates were abandoned. Palm Beach, Orange, Hillsboro, Seminole and Marion were the leading counties.

CELERY: Production of 6,170,000 crates was a little below normal, prices lower, Leading counties were Palm Beach, Seminole, Sarasota, Lake, and Orange.

CUCUMBERS: Leading counties in production were Hardee, Alachua, Manatee, Collier, and Hillsboro.

PEPPERS: Hillsboro, Palm Beach, Broward, Sumter, and Alachua were the leading counties, according to 1949-50 acreages reported.

POTATOES: The leading counties were Dade, St. Johns, Flagler, Putnam, and Palm Beach, closely followed by Lee.

TOMATOES: Tomatoes, with a production of 6,917,000 bushels and a gross value of $32,247,000, was by far our most valuable vegetable crop, approximately 32 percent of the total value of all vegetables. Leading counties were Dade, St. Lucie, Manatee, Hillsboro, and Indian River.

WATERMELONS: Leading in acreage was Gilchrist, followed by Marion and Lake. Alachua and Suwannee tied for fourth and fifth places.

STRAWBERRIES: Leaders were Hillsboro, Bradford, Polk, and Hardee Counties.

EGGPLANT: Leaders were Palm Beach, Hillsboro, Broward, Manatee, and Lee.

ESCAROLE: Leaders were Palm Beach, Orange, and Seminole.

SQUASH: Leaders were Palm Beach, Hillsboro, Broward, with Dade and Marion tied for next rank.

ALL VEGETABLES: Palm Beach led by a wide margin, followed by Dade, Broward, Hillsboro, St. Johns, Seminole, Orange, Alachua, Manatee, Marion,St.Lucie,& Hardee.

FLORIDA PRODUCTION AND VALUE FOR 15 SEASONS

(Includes Canned and Locally Consumed)

	ALL CITRUS					
Season	Carloads Production	Boxes	Florida Gross Value	Gross	Weighted Average All Production & Marketing	Net*
1935-36	74,491	29,462,052	$53,189,191	$1.81	$1.12	$ .69
1936-37	102,827	40,601,208	68,838,758	1.70	1.09	.61
1937-38	103,964	40,939,629	53,285,352	1.30	1.08	.22
1938-39	143,369	56,447,995	58,646,931	1.04	.97	.07
1939-40	109,119	42,973,112	50,365,127	1.17	1.05	.12
1940-41	140,903	55,890,754	64,192,695	1.15	.99	.16
1941-42	120,089	48,400,000	80,572,620	1.66	1.09	.57
1942-43	154,909	68,700,446	153,052,989	2.23	1.12	1.11
1943-44	181,592	80,800,000	199,688,696	2.47	1.31	1.16
1944-45	156,759	69,000,000	201,912,530	2.93	1.31	1.62
1945-46	197,050	86,000,000	236,230,700	2.75	1.29	1.46
1946-47	190,730	83,100,000	146,565,580	1.76	1.32	.44
1947-48	214,045	91,100,000	114,925,000	1.26	1.16	.10
1948-49	219,517	92,900,000	182,188,000	1.96	1.33	.63
1949-50	176,725	87,700,000	241,964,000	2.76	1.29	1.47

	ALL VEGETABLES USED		ALL VEGETABLES & MISCL. FRUITS	
Season	Carloads Production	Florida Gross Value	Carloads Production	Florida Gross Value
1935-36	45,718	$30,666,719	52,670	$34,144,707
1936-37	51,885	34,445,922	60,118	39,090,756
1937-38	70,000	37,306,680	82,130	41,410,710
1938-39	68,506	38,489,172	77,606	43,573,732
1939-40	65,151	37,962,385	75,404	42,738,720
1940-41	58,560	43,077,816	68,486	48,562,482
1941-42	70,191	57,417,670	80,219	62,706,220
1942-43	63,221	81,823,200	69,445	87,555,990
1943-44	70,219	87,328,394	79,605	94,944,402
1944-45	69,225	99,441,550	81,213	107,673,150
1945-46	76,943	116,239,000	89,377	128,099,000
1946-47	58,049	91,618,000	72,262	102,144,000
1947-48	68,670	89,237,000	83,939	99,817,000
1948-49	87,454	115,856,000	103,964	126,531,000
1949-50	93,538	108,613,000	111,632	119,742,000

	ALL FRUITS AND VEGETABLES USED		
Season	Carloads Production	Florida Gross Value	Value Per Carload
1935-36	127,181	$ 76,733,879	$ 603
1936-37	162,945	107,929,514	662
1937-38	186,094	94,696,062	509
1938-39	220,975	102,220,663	463
1939-40	184,563	93,103,847	504
1940-41	209,389	112,768,552	539
1941-42	200,308	143,278,840	715
1942-43	224,554	240,608,979	1071
1943-44	261,197	294,633,098	1128
1944-45	237,912	309,585,680	1301
1945-46	286,427	364,329,700	1272
1946-47	262,992	248,709,580	946
1947-48	297,984	214,742,000	721
1948-49	323,481	308,719,000	954
1949-50	288,357	361,706,000	1254

* Net before deducting for taxes, interest on investment and depreciation if any.

FLORIDA FOR PACKED VALUE OF SELECTED VEGETABLES AND NON-CITRUS FRUITS FOR 16 SEASONS

Season	Beans	Limas	Cabbage	Carrots	Cauliflower
1934-35	$ 5,967,000	$ 270,000	$1,630,000	$	$
1935-36	6,250,000	202,000	612,000		
1936-37	7,031,000	390,000	496,000		
1937-38	6,272,000	507,000	978,000		
1938-39	7,041,000	720,000	990,000		
1939-40	7,480,000	420,000	2,061,000	Not	Not
1940-41	8,615,000	616,000	2,334,000		
1941-42	11,412,000	704,000	1,602,000	previously	previously
1942-43	17,989,000	1,041,000	6,460,000		
1943-44	19,116,000	1,436,000	4,284,000	reported	reported
1944-45	18,405,000	1,779,000	3,959,000		
1945-46	18,359,000	1,533,000	5,571,000		
1946-47	16,389,000	1,187,000	3,069,000		
1947-48	14,484,000	1,065,000	6,500,000	270,000	176,000
1948-49	16,884,000	946,000	5,530,000	52,000	351,000
1949-50	17,354,000	707,000	3,864,000	-	472,000

Season	Celery	Corn	Cucumbers	Eggplant	Escarole	All Lettuce
1934-35	$ 4,368,000	$	$ 765,000	$ 212,000	$ 235,000	$ 255,000
1935-36	4,488,000		928,000	268,000	207,000	185,000
1936-37	4,532,000		1,101,000	323,000	306,000	170,000
1937-38	3,289,000		1,053,000	356,000	204,000	149,000
1938-39	5,375,000		1,391,000	514,000	264,000	270,000
1939-40	5,868,000	Not	1,938,000	417,000	304,000	612,000
1940-41	8,066,000		1,858,000	378,000	364,000	423,750
1941-42	7,154,000	previously	2,124,000	628,000	324,000	481,000
1942-43	17,158,000		2,592,000	1,294,000	1,142,000	1,340,000
1943-44	16,236,000	reported	2,079,000	1,501,000	645,000	562,000
1944-45	18,553,000		3,637,000	1,814,000	1,352,000	634,000
1945-46	14,260,000		5,377,000	1,805,000	875,000	1,285,220
1946-47	17,535,000		4,984,000	1,758,000	1,183,000	559,000
1947-48	9,778,000	1,320,000	6,203,000	1,151,000	1,165,000	440 000
1948-49	16,021,000	4,536,000	5,558,000	1,456,000	1,680,000	583,000
1949-50	12,295,000	6,342,000	7,263,000	1,178,000	1,273,000	806,000

Season	English Peas	Peppers	Potatoes	Squash	Tomatoes	Total Value Vegetables
1934-35	$ 520,000	$1,277,000	$2,503,000	$	$6,835,000	$24,837,000
1935-36	508,000	1,273,000	3,187,000		8,224,000	26,332,000
1936-37	418,000	1,905,000	5,078,000		7,688,000	29,438,000
1937-38	642,000	1,668,000	2,939,000		8,711,000	26,768,000
1938-39	648,000	2,771,000	3,644,000		12,323,000	35,951,000
1939-40	520,000	2,121,000	3,725,000	Not	8,216,000	33,682,000
1940-41	409,500	2,537,000	2,799,000		8,618,000	37,018,250
1941-42	434,000	2,838,000	6,018,000	previously	13,468,000	47,187,000
1942-43	254,000	5,917,000	5,914,000		11,795,000	72,896,000
1943-44	450,000	5,460,000	7,431,000	reported	20,734,000	79,934,000
1944-45	284,000	6,623,000	12,033,000		20,376,000	89,449,000
1945-46	339,000	6,545,000	11,744,000		22,405,000	90,098,000
1946-47	189,000	9,086,000	5,475,000		19,098,000	80,512,000
1947-48	92,000	5,886,000	10,073,000	1,839,000	22,936,000	83,378,000
1948-49	42,000	7,569,000	12,316,000	2,255,000	32,666,000	108,445,000
1949-50	67,000	7,188,000	9,609,000	2,060,000	32,247,000	102,725,000

Season	Cantaloupes	Strawberries	Watermelons	Total Misc. Fruits	Grand Total Misc. Fruits* & Vegetables
1934-35	$ 18,000	$2,236,000	$ 726,000	$2,980,000	$27,817,000
1935-36	15,000	1,972,000	896,000	2,883,000	29,215,000
1936-37	28,000	2,746,000	1,310,000	4,084,000	33,522,000
1937-38	65,000	2,100,000	945,000	3,110,000	29,878,000
1938-39	44,000	3,175,000	976,000	4,195,000	40,146,000
1939-40	38,000	2,344,000	1,193,000	3,575,000	37,257,000
1940-41	37,500	2,194,000	1,445,850	3,677,350	40,695,600
1941-42	52,000	2,275,000	1,572,000	3,899,000	51,086,000
1942-43	84,500	1,498,000	2,641,000	4,223,500	77,119,500
1943-44	91,000	1,107,000	4,593,000	5,791,000	85,816,000
1944-45	120,000	1,541,000	4,918,000	6,579,000	96,028,000
1945-46	54,000	2,363,000	5,552,000	7,969,000	98,067,220
1946-47	102,000	3,737,000	5,419,000	9,258,000	89,770,000
1947-48	339,000	2,003,000	6,862,000	9,204,000	92,582,000
1948-49	192,000	2,401,000	6,372,000	8,965,000	117,410,000
1949-50	189,000	3,737,000	5,530,000	9,456,000	112,181,000

Source: U.S. Agricultural Statistician, B.A.E., Orlando, Florida. Official estimates on carrots, cauliflower, corn and squash not available prior to 1947-48 season. Other vegetables and miscellaneous fruits probably accounted for 25,000 acres estimated at a gross F.O.B. Florida value of $9,000,000, but not included herein.

FLORIDA AGRICULTURAL VOLUME AND VALUE

ACREAGE IN FLORIDA (Estimated for 1949-50 Season)	TOTAL ACRES
Citrus Bearing 423,500 a.; Other Fruits, Melons and Berries 78,400 a.	501,900
Vegetables - plats 1 acre or more, reported 245,510 (unreported 14,850)	260,000
Pecans 6,000 acres, Tung Trees 12,000 acres	18,000
Total Acres Fruits, Berries, Nuts and Vegetables	779,900
General Crop 1,500,000 a.; Other Farm Land Usage 6,500,000 a.	8,000,000
Pasture Land 11,000,000 a.; Woodland and Other Land 14,947,780 a.	25,947,780
Total Land Area of Florida	34,727,680

CITRUS PRODUCTION AND VALUE 1949-50 SEASON								FLORIDA FOB SALES
Oranges	Acres	300,900	Carloads	117,882	Units used	58,500,000	boxes	$166,271,000
Grapefruit	"	98,500	"	48,525	" "	24,200,000	"	61,333,000
Tangerines	"	24,100	"	10,318	" "	5,000,000	"	14,360,000
Total	"	423,500	"	176,725	" "	87,700,000	"	$241,964,000

MISCELLANEOUS FRUITS PRODUCTION AND VALUE 1949-50 SEASON								
Watermelons	Acres	63,000	Carloads	15,507	Units used	14,000,000	melons	$ 5,530,000
Strawberries	"	5,400	"	1,274	" "	576,000	crts	3,737,000
Other Fruits	"	10,000	"	1,313	" "	692,000	pkgs	1,862,000
Total	"	78,400	"	18,094	" "	-		$11,129,000

VEGETABLE PRODUCTION AND VALUE 1949-50 SEASON								
Beans	Acres	73,300	Carloads	11,813	Units used	7,082,000	bu.	$ 17,354,000
Celery	"	9,500	"	10,336	" "	6,170,000	crts.	12,295,000
Potatoes	"	23,200	"	9,757	" "	5,370,000	bu.	7,188,000
Tomatoes	"	42,500	"	16,893	" "	6,917,000	bu.	32,247,000
Others	"	96,650	"	44,739	" "	-		39,529,000
Total	"	245,150	"	93,538	" "	-		$108,613,000

ALL FRUIT AND VEGETABLE PRODUCTION AND VALUE 1949-50 SEASON				
Total Acres	747,050	Carloads	288,357	$361,706,000

LIVESTOCK IN FLORIDA 1949	Head	Gross Value		FLORIDA SALES GROSS FOB VALUE
*Beef Cattle and Calves	1,392,000	$ 99,667,000		$ 24,153,000
**Dairy Cattle	148,000	14,060,000		(See Dairy Products)
Hogs and Pigs	660,000	14,452,000		21,355,000
Sheep & Lambs	12,000	100,000	(including wool)	38,000
Goats (estimate)	30,000	50,000		30,000
Total Livestock	2,242,000	$128,329,000		$ 45,576,000

* Hides included in sales. ** Dairy cattle used for beef included in beef sales.

POULTRY, EGG AND DAIRY PRODUCTS PRODUCED IN FLORIDA IN 1949		FLORIDA GROSS VALUE
Chickens Produced	37,000,000 head (hens, roosters, fryers)	$ 13,700,000
Eggs "	20,000,000 dozen.	12,000,000
Turkeys "	2,500,000 lbs.	1,000,000
Dairy Products	650,000,000 lbs. (mostly milk)	39,000,000
Total Poultry, Eggs and Dairy Products		$ 65,700,000

GENERAL FIELD CROP 1949	Volume Produced		
Corn	8,983,000 bu.	691,000 acres	$ 11,678,000
Tobacco	25,061,000 lbs.	23,000 "	17,320,000
Peanuts	51,255,000 lbs.	70,000 "	5,425,000
Sugar-Raw	1,124,000 tons	36,400 "	7,137,000
Sugar-Cane Syrup	1,620,000 gals.	9,000 "	1,134,000
Black Strap Molasses	6,896,000 gals (Incl. above) at 10¢?		690,000
Sweet Potatoes	980,000 bu.	14,000 "	2,597,000
Cotton	16,000 bales	44,000 "	2,339,000
Cow Peas, Oats, Velvet Beans		199,000 "	2,654,000
Hay	53,000 tons	88,000 "	906,000
Total Field Crop Group 1949		1,174,400 "	$51,880,000

MISCELLANEOUS CROPS AND SPECIALTIES 1949	FLORIDA GROSS VALUE
Flowers and Bulbs, Hot House and Field, Nursery Products, Specialty Crops under Glass, and Seeds (Gladiola $9,500,000)	$20,000,000
Pecans 3,650,000 lbs.	652,000
Honey 189,000 colonies 11,340,000 lbs. (1950 15,850,000 lbs.)	2,268,000
Total Miscellaneous Crops and Specialties	$22,920,000

AGRICULTURAL GROUP SALES	
Citrus Fruits	$241,964,000
Miscellaneous Fruits and Melons	11,129,000
Vegetables	108,613,000
Total Fruits and Vegetables	$361,706,000
Livestock	45,576,000
Poultry, Eggs and Dairy Products	65,700,000
General Field Crops	51,880,000
Miscellaneous Crops and Specialties	22,920,000
Total Agricultural Group	$547,782,000

LUMBER AND NAVAL STORES - 1949	
Also Wood Pulp, Poles, Piling, Fuel Wood, etc.	$180,000,000
FISH, SHELL FISH AND PRODUCTS 1948	
Food and Non-Food Fish and Shell Fish and Sponges, etc.	$ 35,000,000
MINERAL PRODUCTION 1949	
Phosphate 37,732,894, Limestone 5,115,974, Other Products 11,028,132	$ 53,877,000
	$268,877,000
GRAND TOTAL ABOVE GROUPS	$816,659,000

CITRUS ACREAGE, YIELD, BOXES PER TREE, AND GROVE VALUES

FLORIDA ORANGES Season	Bearing Acres	Production in 1-3/5Bu Box	Box Yield Per Acre (66 Trees)	Box Yield per Tree	Gross Return Box	Net Return Box	Abandoned Boxes	Net per Acre before Taxes & Depreciation	Income Value per Acre at 10%	Income Value per Acre at 13%
1942-43	246,340	37,200,000	151	2.3	$2.72	$1.45	-	$219	$2190	$ 1685
1943-44	251,340	46,200,000	184	2.8	2.81	1.31	-	241	2410	1850
1944-45	256,340	42,800,000	167	2.5	3.17	1.73	-	289	2890	2223
1945-46	264,900	49,800,000	188	2.8	3.25	1.84	-	346	3460	2661
1946-47	270,000	53,700,000	199	3.0	1.93	.50	900,000	98	980	761
1947-48	280,500	58,400,000	208	3.2	1.41	.15	-	31	310	239
1948-49	289,900	58,300,000	201	3.1	2.19	.79	-	159	1590	1223
1949-50	300,900	58,500,000	194	2.9	2.84	1.51	-	293	2930	2254
GRAPEFRUIT									at 10%	at 16%
1942-43	94,390	27,300,000	289	4.4	1.48	.67	-	$194	$1940	$1212
1943-44	95,190	31,000,000	326	4.9	1.83	.92	-	300	3000	1875
1944-45	90,000	22,300,000	248	3.8	2.24	1.36	-	337	3370	2106
1945-46	90,500	32,000,000	354	5.4	1.77	.78	-	276	2760	1725
1946-47	91,000	29,000,000	319	4.8	1.25	.26	2,600,000	75	750	470
1947-48	93,000	33,000,000	355	5.4	.82	- .01	5,700,000	- 3½	-	-
1948-49	95,000	30,200,000	318	4.8	1.38	.33	-	105	1050	656
1949-50	98,500	24,200,000	246	3.7	2.53	1.52	-	378	3780	2362
TANGERINES									at 10%	at 15%
1942-43	23,419	4,200,000	179	2.7	2.72	.98	-	$175	$1750	$1167
1943-44	23,419	3,600,000	154	2.3	3.62	1.36	-	209	2090	1393
1944-45	23,419	4,000,000	171	2.6	4.18	1.91	150,000	315	3150	2100
1945-46	23,549	4,200,000	178	2.7	4.24	2.10	-	374	3740	2493
1946-47	23,705	4,700,000	198	3.0	2.99	.90	800,000	149	1490	993
1947-48	23,800	4,000,000	168	2.5	2.41	.20	600,000	29	290	193
1948-49	24,000	4,400,000	183	2.8	2.93	.74	-	135	1350	900
1949-50	24,100	5,000,000	207	3.1	2.87	.80	-	166	1660	1167
TOTAL CITRUS										
1942-43	364,149	68,700,000	189	2.9	2.23	1.11	-	$210	$2100	$ -
1943-44	369,949	80,800,000	218	3.3	2.47	1.16	-	253	2530	-
1944-45	369,759	69,100,000	187	2.8	2.93	1.62	150,000	303	3030	-
1945-46	378,949	86,000,000	227	3.4	2.75	1.46	-	331	3310	-
1946-47	384,705	87,400,000	227	3.4	1.76	.44	3,400,000	96	960	-
1947-48	397,300	95,400,000	240	3.6	1.26	.10	4,300,000	23	230	-
1948-49	408,900	92,900,000	227	3.4	1.96	.63	-	143	1430	-
1949-50	423,500	87,700,000	207	3.1	2.76	1.47	-	304	3040	-

We estimate that the 10% income as shown above on oranges will actually yield 7% and the 13% will actually yield around 10%. It is doubtful if a prudent investor would buy a grove risk with a near term expectation of less than 10% net above all costs. High prices paid by processors account for 1949-50 citrus prosperity.

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON-AUGUST 1, 1949-JULY 31, 1950

Carlot Shipment	Freight Straight & Mixed	Carloads Total Freight	Carloads Express	Boxes Freight Boat, Truck and Express	Gross FOB Returns Florida Points Box	Gross FOB Returns Florida Points For Crop	Production and Marketing Costs Box	Production and Marketing Costs For Crop	Net Return to Florida Growers Box	Net Return to Florida Growers Rail, Truck, Boat
Oranges	14,393	16,964	2,249	20,994,233	$3.55	$ 74,529,527	$1.90	$39,889,043	$1.65	$ 34,640,484
Grapefruit	7,708	9,312	736	9,357,265	3.41	31,908,274	1.50	14,035,898	1.91	17,872,376
Tangerines	2,205	2,855	77	2,877,547	3.85	11,078,556	2.55	7,337,745	1.30	3,740,811
Mxd.Citrus	4,805	Converted		Converted	-	-	-	-	-	-
Total	29,111	29,111	3,062	33,229,045	3.54	$117,516,357	$1.84	$61,262,686	$1.70	$ 56,253,671

GENERAL DISPOSITION ANALYSIS OF THE FLORIDA CITRUS CROP FOR SEASON 1949-50

BOXES	StraightCars Freight	Mxd.Cars Freight	Mxd.Cars Express	Total Boxes Rail-Boat		Trucked Out	Rail, Boat & Truck	Processed Fresh, Bxs.	Consumed Boxes	Total Crop Boxes
Oranges	7,042,569	1,251,231	899,600	10,710,718		10,283,515	20,994,233	34,659,323	2,848,444	58,500,000
Grapefruit	3,890,584	780,271	294,400	5,792,144		3,565,121	9,357,265	13,486,200	1,356,535	24,200,000
Tangerines	962,765	306,371	30,800	1,500,955		1,376,592	2,877,547	1,594,928	527,525	5,000,000
Total	11,895,918	2,337,873	1,224,800	18,003,817		15,225,228	33,229,045	49,738,451	4,732,504	87,700,000
CARLOADS (Converted)				Tot.Rail	Boat			Carloads		Tot.Carloads
Oranges	14,393	2,571	2,249	19,213	3,091	20,567	42,871	69,314	5,697	117,882
Grapefruit	7,708	1,604	736	10,048	1,662	7,130	18,840	26,972	2,713	48,525
Tangerines	2,205	630	77	2,912	409	2,753	6,074	3,190	1,054	10,318
Total	24,306	4,805	3,062	32,173	5,162	30,450	67,785	99,476	9,464	176,725

ESTIMATED COST OF PRODUCING AND MARKETING 33,229,045 BOXES OF ORANGES, GRAPEFRUIT AND TANGERINES BY RAIL, TRUCK, BOAT.

Cost of production such as fertilizer, spray materials, irrigation, pruning, labor, fuel, etc., but not including interest or taxes on strictly grove acreage, per Standard 1-3/5 bushel boxes.

ORANGES $ .52 GRAPEFRUIT $ .37 TANGERINES $ .70 WEIGHTED AVERAGE $ .49

Cost of picking, hauling, packing, selling, and other average ordinary marketing charges.

ORANGES $1.38 GRAPEFRUIT $1.13 TANGERINES $1.85 WEIGHTED AVERAGE $1.35

Total ordinary and average cost of production and marketing of citrus.

ORANGES $1.90 GRAPEFRUIT $1.50 TANGERINES $2.55 WEIGHTED AVERAGE $1.84

1. Estimated boxes per car: Straight Freight: Oranges 489.3, Grapefruit 504.7, Tangerines 436.6, Mixed Fruit 486.54; Mixed Express 400; Truck 500; Boat approximately 493 boxes per car, but usually 500 boxes per car.
2. Mixed Car Freight Analysis: Oranges 53.5, Grapefruit 33.4, Tangerines 13.1 per cent.
3. Mixed Car Express Analysis: Oranges 73.4, Grapefruit 24.0, Tangerines 2.6 per cent.
4. Ventilated Box Cars Used: Oranges 1827, Tangerines 309, Tangerines 33, Mixed 919. Total 3088 cars.
5. Interstate Shipments for By-products Manufacture Included in Rail Shipments: Oranges 49,275, Grapefruit 925 boxes.
6. Exports: (Boxes)

	Oranges	Grapefruit		Oranges	Grapefruit
Government Rail	65,827	69,391	Commercial Rail	-	160
Government Truck	2,217	1,058	Commercial Truck	1,902	863
Boat	-	-	Commercial Boat	-	2,500

Total Oranges 69,946; Grapefruit 73,972. All exports included in freight or truck shipments to out-of-State ports.

7. Boat Shipments in Boxes: Oranges 1,517,318; Grapefruit 826,889; Tangerines 201,019. Total 2,545,226.

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON 1949-50 (Cont'd.)

TRUCK SHIPMENTS TO OUT-OF-STATE MARKETS (400 boxes to carload) AUGUST 1 - July 31										
ORANGES:	Carlot equiv.	20,567 or	10,283,515 boxes.	Gross at	$3.55	$ 36,506,478	Net* at	$1.65	$ 16,967,800
GRAPEFRUIT:	Carlot equiv.	7,130 or	3,565,121 boxes.	Gross at	3.41	12,157,063	Net* at	1.91	6,809,381
TANGERINES:	Carlot equiv.	2,753 or	1,376,592 boxes.	Gross at	3.85	5,299,879	Net* at	1.30	1,789,570
ALL CITRUS:	Carlot equiv.	30,450 or	15,225,228 boxes.	Gross at	$3.54	$ 53,963,420	Net* at	$1.68	$ 25,566,751
FREIGHT, EXPRESS AND BOAT SHIPMENTS TO OUT-OF-STATE MARKETS, AUGUST 1 - JULY 31									
ORANGES:	Carlot equiv.	22,304 or	10,710,718 boxes.	Gross at	$3.55	$ 38,023,049	Net* at	$1.65	$ 17,672,684
GRAPEFRUIT:	Carlot equiv.	11,710 or	5,792,144 boxes.	Gross at	3.41	19,751,211	Net* at	1.91	11,062,995
TANGERINES:	Carlot equiv.	3,321 or	1,500,955 boxes.	Gross at	3.85	5,778,677	Net* at	1.30	1,951,241
ALL CITRUS:	Carlot equiv.	37,335 or	18,003,817 boxes.	Gross at	$3.53	$ 63,552,937	Net* at	$1.70	$ 30,686,920
FRESH CITRUS USED FOR PROCESSING IN FLORIDA (400 boxes to carload) AUGUST 1 - JULY 31									
ORANGES:	Carlot equiv.	69,314 or	34,657,323 boxes.	Gross at	$2.38	$ 82,484,429	Net* at	$1.43	$ 49,559,972
GRAPEFRUIT:	Carlot equiv.	26,972 or	13,486,200 boxes.	Gross at	1.87	25,219,194	Net* at	1.22	16,453,164
TANGERINES:	Carlot equiv.	3,190 or	7,594,928 boxes.	Gross at	.90	1,435,435	Net* at	- .23	- 366,833
ALL CITRUS:	Carlot equiv.	99,476 or	49,738,451 boxes.	Gross at	$2.19	$109,139,058	Net* at	$1.32	$ 65,646,303
FRESH CITRUS CONSUMED IN FLORIDA (400 boxes to carload) AUGUST 1 - JULY 31									
ORANGES:	Carlot equiv.	5,697 or	2,848,444 boxes.	Gross at	$3.25	9,257,443	Net* at	$1.47	$ 4,187,213
GRAPEFRUIT:	Carlot equiv.	2,713 or	1,356,535 boxes.	Gross at	3.10	4,205,259	Net* at	1.77	2,401,067
TANGERINES:	Carlot equiv.	1,054 or	527,525 boxes.	Gross at	3.50	1,846,338	Net* at	1.17	617,204
ALL CITRUS:	Carlot equiv.	9,464 or	4,732,504 boxes.	Gross at	$3.24	$ 15,309,040	Net* at	$1.52	$ 7,205,484
TOTAL RAIL, BOAT, TRUCK SHIPMENTS, PROCESSED AND LOCALLY CONSUMED CITRUS, AUGUST 1 - JULY 31									
ORANGES:	Carlot equiv.	117,882 or	58,500,000 boxes.	Gross at	$2.84	$166,271,399	Net* at	$1.51	$ 88,387,669
GRAPEFRUIT:	Carlot equiv.	48,525 or	24,200,000 boxes.	Gross at	2.53	$ 61,332,727	Net* at	1.52	36,726,607
TANGERINES:	Carlot equiv.	10,318 or	5,000,000 boxes.	Gross at	2.87	14,360,329	Net* at	.80	3,991,182
ALL CITRUS:	Carlot equiv.	176,725 or	87,700,000 boxes.	Gross at	$2.76	$241,964,455	Net* at	$1.47	$129,105,458

NOTE: * Gross refers to returns FOB cars Florida shipping points, and net refers to returns to growers or fruit owners before deducting for interest and grove taxes, but after deducting for cost of production and marketing.

1: Trucked out shipment figures were based on inspections certified for interstate movement. Road Guard Stations for checking were open October 16 thru June 17. August 1-31, October 1-31, June 18-30, and July 1-31 were estimated.

2: Cannery fruit represents average gross price at cannery door, and the net price is the gross less the estimated picking, hauling, and other marketing charges.

3: Figures for Consumed in Florida are rough estimates based on population, prices, etc. Any person who does not approve this home consumption estimate may make his own estimate, but this volume, which is probably under estimated, has to be counted. This locally consumed volume of citrus includes packed, unpacked, inspected and uninspected. No study of local or Florida consumption of fresh citrus has ever been made.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS BY PRODUCTION UNITS, 1949-50 SEASON

Commodity	Units	Straight Freight	Mixed Freight	LCL Express	Boat	Interstate Truck	Total ShippedOut	Processed	Florida Consumed	Total Production Used	Abandoned (Not Included)
Beans	Bu.	1,446,000	240,000	12,000	-	4,021,000	5,719,000	878,000	485,000	7,082,000	286,000
Limas	Bu.	70,000	17,000	2,500	-	130,000	219,500	*	38,500	258,000	-
Cabbage	50 lb.	(1,927,520#	(115,200)		(1,440)	(2,663,520)	(4,707,680)	-	(360,320)	(5,068,000)	(2,276,000)
Cabbage	Tons	48,188	2,880	*	36	66,588	117,692	*	9,008	126,700	56,900
Celery	Crts.	4,254,000	37,800	4,200	112,000	1,462,000	5,870,000	*	300,000	6,170,000	-
Corn, Sweet	Crts.	1,292,000	147,000	3,000	-	1,240,000	2,682,000	*	268,000	2,950,000	530,000
Cucumbers	Bu.	331,000	42,000	2,000	600	1,665,000	2,040,600	60,000	89,400	2,190,000	-
Eggplant	Bu.	29,000	186,000	24,000	-	411,000	650,000	*	76,000	726,000	-
Escarole	Bu.	597,000	481,000	*	-	252,000	1,330,000	*	10,000	1,340,000	145,000
Lettuce	Crts.	40,000	14,000	3,000	-	166,000	223,000	*	65,000	288,000	64,000
Peppers	Bu.	1,289,000	560,000	40,000	25,000	1,721,000	3,635,000	*	205,000	3,840,000	175,000
Potatoes	Bu.	2,927,000	48,000	3,000	115,000	1,960,000	5,053,000	*	317,000	5,370,000	-
Squash	Bu.	120,000	40,000	10,000	-	576,000	746,000	*	114,000	860,000	-
Tomatoes	Bu.	2,341,000	48,000	4,000	-	3,738,000	6,131,000	469,000	317,000	6,917,000	-
Misc. Vegs.	Bu.	122,000	680,000	38,000	3,500	(a)1,200,000	2,043,500	25,000	1,200,000	3,268,500	-
Mxd. Car. Vegs	Pkgs	Converted	Converted	Converted							
TOT. VEGETABLES-Units		16,785,520	2,656,000	145,700	257,540	21,205,520	41,050,280	1,432,000	3,845,220	46,327,500	3,476,000
Strawberries	36PtCrt	81,900	-	4,500	-	326,000	412,400	13,500	150,100	576,000	-
Watermelons(	2M Crt)	(4,273,000#	-	(500)	-	(2,250,000)	(6,523,500)	-	(476,500)	(7,000,000)	2,450,000
Watermelons	Melons	8,546,000	-	1,000	-	4,500,000	13,047,000	*	953,000	14,000,000	4,900,000
Avocados	Bu.	7,500	-	20,000	-	140,000	167,500	*	25,000	192,500	-
Limes	St. Crt.	7,000	-	37,000	-	145,000	189,000	24,828	45,000	258,828	-
Misc. Fruits	Pkgs.	-	-	16,000	-	80,000	96,000	20,000	125,000	241,000	-
TOT. MISC. FRT.		4,369,400	-	78,000	-	2,941,000	7,388,400	58,328	821,600	8,268,328	2,450,000
Oranges	Box	7,042,569	1,251,231	899,600	1,517,318	10,283,515	20,994,233	34,657,323	2,848,444	58,500,000	-
Grapefruit	Box	3,890,584	780,271	294,400	826,889	3,565,121	9,357,265	13,486,200	1,356,535	24,200,000	-
Tangerines	Box	962,765	306,371	30,800	201,019	1,376,592	2,877,547	1,594,928	527,525	5,000,000	-
TOTAL CITRUS	Boxes	11,895,918	2,337,873	1,224,800	2,545,226	15,225,228	33,229,045	49,738,451	4,732,504	87,700,000	-
GRAND TOTAL	Units	33,050,838	4,993,873	1,448,500	2,802,766	39,371,748	81,667,725	51,228,779	9,399,324	142,295,828	5,926,000

NOTES: * Included in Miscellaneous, if any. (a) An estimated 140,000 bushels of butterbeans included in Miscellaneous. (Pages 10 and 11). There is considerable difficulty in working out a detailed disposition sheet for vegetables and miscellaneous fruits as comprehensive data is not as avalable as for citrus. It was advisable to try to use the U.S. Department of Agriculture estimate of total production and work back from there. We have the records on the truck shipments out of State, which figures are used. We have the records on straight freight and boat for most of the individual commodities. We had only the totals for mixed freight and LCL express. The Florida consumption figures are only estimates. We had to apportion the mixed freight and mixed express totals as best we could to the various commodities with the handicap of trying to make all of the separate totals check with the total official crop estimate.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS IN CARLOTS, OR EQUIVALENT, AND VALUE 1949-50 SEASON

Commodity	Straight Freight Cars	Mixed Freight Cars	LCL Express Cars	Boat	Inter-state Truck Carlots	Total ShippedOut Carlots	Florida Processed	Florida Consumed Carlots	Total Used Carlots	Abandoned (Not In-cluded)##	Total FOB GrossValue
Beans	2,410	400	30	-	6,702	9,542	1,463	808	11,813	477	$ 17,354,000
Limas	140	34	5	-	265	439	*	77	516	-	707,000
Cabbage	4,016	240	*	3	5,327	9,586	*	750	10,336	4,660	3,864,000
Celery	10,011	90	10	248	3,481	13,840	*	750	14,590	-	12,295,000
Corn, Sweet	2,191	250	5	-	2,735	5,181	*	454	5,635	930	6,342,000
Cucumbers	787	100	5	1	4,121	5,014	143	213	5,370	-	7,263,000
Eggplant	47	300	40	-	955	1,342	*	127	1,469	-	1,178,000
Escarole	919	740	*	-	421	2,080	*	17	2,097	223	1,273,000
Lettuce	123	40	10	-	355	528	*	200	728	200	806,000
Peppers	1,842	800	100	7	2,775	5,524	*	330	5,854	250	7,188,000
Potatoes	5,322	80	5	191	3,629	9,227	*	530	9,757	-	9,609,000
Squash	300	100	25	-	1,358	1,783	*	270	2,053	-	2,060,000
Tomatoes	6,003	120	10	-	8,797	14,930	1,170	793	16,893	-	32,247,000
Miscl. Vegetables	244	1,360	96	7	2,270	3,977	50	2,400	6,427	-	6,427,000
Mixed Car Vegetables	Converted		Converted		Converted						
TOTAL VEGETABLES	34,355	4,654	341	457	43,186	82,993	2,826	7,719	93,538	6,740	$108,613,000
Strawberries	182	-	5	-	724	911	30	333	1,274	-	$ 3,737,000
Watermelons	10,054	-	*	-	4,500	14,554	*	953	15,507	5,445	5,530,000
Avocados	15	-	50	-	138	203	*	50	253	-	481,000
Limes	14	-	74	-	290	378	50	90	518	-	771,000
Miscl. Fruits	2	-	40	-	200	242	50	250	542	-	610,000
TOTAL MISCL.FRUITS	10,267	-	169	-	5,852	16,288	130	1,676	18,094	5,445	$ 11,129,000
Oranges	14,393	2,571	2,249	3,091	20,567	42,871	69,314	5,697	117,882	-	$166,271,399
Grapefruit	7,708	1,604	736	1,662	7,130	18,840	26,972	2,713	48,525	-	61,332,727
Tangerines	2,205	630	77	409	2,753	6,074	3,190	1,054	10,318	-	14,360,329
Mixed Citrus	Converted		Converted		Converted					-	
TOTAL CITRUS	24,306	4,805	3,062	5,162	30,450	67,785	99,476	9,464	176,725	-	$241,964,455
GRAND TOTAL	68,928	9,459	3,572	5,619	79,488	167,066	102,432	18,859	288,357	12,185	$361,706,455

NOTES: (Pages 10 and 11). An additional problem was the disposition of the volume of radishes, cauliflower, carrots, spinach, broccoli, endive, etc., included in the miscellaneous figures for vegetables. Miscellaneous fruits included mangoes, grapes, guavas, persimmons, pears, blueberries, etc. # Ordinarily units of different kinds are not added but if the 50# sack is used for cabbage, instead of tons, and the number of watermelons are divided by two to get a crate, we find that all of the units are bushels or the near equivalent of bushels, with the exception of citrus which are in 1-3/5 bushel boxes. ## Abandoned because of market conditions and not included in the gross FOB Florida value. The estimated gross includes the production, marketing costs, and packing costs if packed, and profit, if any. Some truck passings in packages have been changed to better reflect comparisons with rail loadings.

Are these tabulations any good to you? They are very troublesome for us.

FREIGHT CARLOT SHIPMENTS FROM FLORIDA BY COMMODITIES AND MONTHS, FOR 1949-50 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges			242	1619	2398	1745	1408	1873	1687	1982	1173	218	14,345
Grapefruit		24	619	684	616	850	914	1364	1169	1103	321	7	7,671
Tangerines			1	154	905	580	411	152	2				2,205
Mixed Citrus			77	462	1056	678	576	714	525	509	195	12	4,804
TOTAL CITRUS		24	939	2919	4975	3853	3309	4103	3383	3594	1689	237	29,025
Strawberries					1	76	101	4					182
Watermelons								2	31	1042	8223	756	10,054
Other Non-Citrus			1								1		2
TOTAL MISCL.FRUITS			1		1	76	101	6	31	1042	8224	756	10,238
Beans(incl.Limas)			31	313	211	270	275	656	541	228	25		2,550
Cabbage					129	700	982	1303	657	230	15		4,016
Cauliflower					1	62	18	16					97
Celery				28	395	1396	1595	2127	1696	2330	444		10,011
Corn,Green				7	2		2	77	462	794	814	33	2,191
Cucumbers			42	161	149	34	43	52	5	253	48		787
Eggplant					1		3			18	23	2	47
Escarole				35	167	190	158	163	130	76			919
Greens(ex.Spinach)				3	12	23	24	19	13	11			105
Lettuce & Romaine				8	30	50	24	10	1				123
Peppers				15	70	300	210	243	292	512	200		1,842
Potatoes					36	327	605	1483	1579	1283	9		5,322
Tomatoes				113	1102	462	1101	1201	1053	820	151		6,003
Other Vegetables	2					1	9	11	7		7	5	42
Mixed Car Vegetables			34	60	403	789	902	1075	779	521	91		4,654
TOTAL VEGETABLES	2		107	743	2708	4604	5951	8436	7215	7076	1827	40	38,709
NON-CITRUS & VEGS.	2		108	743	2709	4680	6052	8442	7246	8118	10051	796	48,947
ALL FRUITS & VEGS.	2	24	1047	3662	7684	8533	9361	12545	10629	11712	11740	1033	77,972

PICK-UP-EXPRESS SHIPMENTS FROM FLORIDA STATIONS FOR 1949-50 SEASON

COMMODITY.	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Mixed Citrus				93	1226	538	445	374	238	100	48		3,062
Mixed Vegetables				25	50	33	33	36	38	54	51	16	336
TOTAL FRUITS & VEGS.				118	1276	571	478	410	276	154	99	16	3,398

RAIL - FREIGHT & EXPRESS CARLOT SHIPMENTS, FOR 1949-50 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges			242	1619	2398	1745	1408	1873	1687	1982	1173	218	14,345
Grapefruit		24	619	684	616	850	914	1364	1169	1103	321	7	7,671
Tangerines			1	154	905	580	411	152	2				2,205
Mixed Citrus			77	555	2282	1216	1021	1088	763	609	243	12	7,866
TOTAL CITRUS		24	939	3012	6201	4391	3734	4477	3621	3694	1737	237	32,087
Strawberries					1	76	101	4					182
Watermelons								2	31	1042	8223	756	10,054
Other Non-Citrus			1								1		2
TOTAL MISCL. FRUITS			1		1	76	101	6	31	1042	8224	756	10,238
Beans (Incl. Limas)			31	313	211	270	275	656	541	228	25		2,550
Cabbage					129	700	982	1303	657	230	15		4,016
Cauliflower					1	62	18	16					97
Celery				28	395	1396	1595	2127	1696	2330	444		10,011
Corn, Green				7	2		2	77	462	794	814	33	2,191
Cucumbers			42	161	149	34	43	52	5	253	48		787
Eggplant					1		3			18	23	2	47
Escarole				35	167	190	158	163	130	76			919
Greens(except Spinach)				3	12	23	24	19	13	11			105
Lettuce & Romaine				8	30	50	24	10	1				123
Peppers				15	70	300	210	243	292	512	200		1,842
Potatoes					36	327	605	1483	1579	1283	9		5,322
Tomatoes				113	1102	462	1101	1201	1053	820	151		6,003
Other Vegetables	2					1	9	11	7		7	5	42
Mixed Car Vegetables			34	85	453	822	035	1111	817	575	142	16	4,990
TOTAL VEGETABLES	2		107	768	2758	4637	5984	8472	7253	7130	1878	56	39,045
NON-CITRUS & VEGS.	2		108	768	2759	4713	6085	8478	7284	8172	10102	812	49,283
ALL FRUITS & VEGS.	2	24	1047	3780	8960	9104	9839	12955	10905	11866	11839	1049	81,370

BOAT SHIPMENTS (Carlot Equivalent FROM FLORIDA PORTS (Does not include initial rail haul exports).

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges				114	329	439	451	470	494	489	301		3,087
Grapefruit				106	183	215	275	302	292	208	81		1,662
Tangerines				34	151	110	76	35	3				409
TOTAL CITRUS				254	663	764	802	807	789	697	382		5,158
Celery					9	25	61	81	50	21	1		248
Potatoes									90	101			191
Other Vegetables						1	2	9	2	1	3		18*
TOTAL VEGETABLES					9	26	63	90	143	123	4		457
ALL FRUITS & VEGS.				254	672	790	865	897	931	824	386		5,615

Note: * Other Vegetables by Boat include- Cabbage 3, Cucumbers 1, Greens (Ex.Spinach)7, and Peppers 7 carloads.

FLORIDA INTERSTATE TRUCK SHIPMENT PASSINGS 1949-50 SEASON

Actual Check at Nine Road Guard Stations October 16 - June 17
Estimated for August 1-October 15 and June 18-July 31 Periods

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	1	lcl	1208	3231	3628	2355	2010	2536	2320	2161	945	56	20,451
Grapefruit	8	23	765	698	485	671	779	1329	1077	836	239	21	6,931
Tangerines			lcl	250	1198	647	429	175	7	lcl			2,706
TOTAL CITRUS	9	23	1973	4179	5311	3673	3218	4040	3404	2997	1184	77	30,088
Avocados	15	25	58	80	32	11	4	lcl	lcl	lcl	1	4	230
Limes	30	14	4	2	4	3	1	2	1	13	50	40	164
Strawberries					11	209	299	121	69	15			724
Watermelons									25	530	3645	300	4,500
Other Non-Citrus Frts									1	12	172	15	200
TOTAL MISCL. FRUITS	45	39	62	82	47	223	304	123	96	570	3868	359	5,818
Beans, Snap			92	782	669	833	977	1483	1263	588	15		6,702
Limas & Butter Beans				1	12	59	32	44	88	187	108	9	540
Cabbage				2	133	1031	1514	1571	910	161	5		5,327
Celery				46	180	530	632	645	725	581	142		3,481
Corn, Green				35	11	18	23	208	680	920	800	40	2,735
Cucumbers			193	512	503	395	444	647	399	878	150		4,121
Eggplant	3	lcl	11	28	47	107	159	178	149	167	93	13	955
Escarole				33	77	69	48	64	69	56	5		421
Field Peas	4	2	9	16	5	7	6	13	61	301	194	12	630
Lettuce & Romaine				12	48	127	77	48	33	10			355
Okra	15	3	30	11	4	10	10	8	16	61	77	20	265
Peas, English				lcl	4	9	7	1	4	2			27
Peppers			2	18	95	310	374	513	563	608	287	5	2,775
Potatoes					24	162	257	549	1296	1317	24		3,629
Squash			26	92	146	129	219	257	257	223	9		1,358
Tomatoes			lcl	213	917	691	1461	1752	1958	1402	397	6	8,797
Bunched Vegetables			lcl	2	4	10	8	9	4	1			38
Other Vegetables			lcl	38	110	311	300	307	184	48	8	4	1,310
TOTAL VEGETABLES	22	5	363	1841	2989	4808	6548	8297	8659	7511	2314	109	43,466
VEGS. & MISCL.FRUITS	67	44	425	1923	3036	5031	6852	8420	8755	8081	6182	468	49,284
ALL FRUITS & VEGS.	76	67	2398	6102	8347	8704	10070	12460	12159	11078	7366	545	79,372

CARLOT SHIPMENTS (FREIGHT, EXPRESS, BOAT & TRUCK) FRUITS AND VEGETABLES BY MONTHS FOR SEASON 1949-50

August 1-July 31 (Truck October 16-June 17 except where estimated)

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	1	lcl	1450	4964	6355	4539	3869	4879	4501	4632	2419	274	37,383
Grapefruit	8	47	1384	1488	1284	1736	1968	2995	2538	2147	641	28	16,264
Tangerines			1	438	2254	1337	916	362	12	1xl			5,320
Mixed Citrus			77	555	2282	1216	1021	1088	763	609	243	12	7,866
TOTAL CITRUS	9	47	2912	7445	12175	8828	7774	9324	7814	7388	3303	314	67,333
Avocados	15	25	58	80	32	11	4	lcl	lcl	lcl	1	4	230
Limes	30	14	4	2	4	3	1	2	1	13	50	40	164
Strawberries					12	285	400	125	69	15			906
Watermelons								2	56	1572	11868	1056	14,554
Other Non-Citrus Frts.			1						1	12	173	15	202
TOTAL MISCL. FRUITS	45	39	63	82	48	299	405	129	127	1612	12092	1115	16,056
Beans(incl.Limas)			123	1096	892	1162	1284	2183	1892	1003	148	9	9,792
Cabbage				2	262	1731	2496	2877	1567	391	20		9,346
Cauliflower					1	62	18	16					97
Celery				74	584	1951	2288	2853	2471	2932	587		13,740
Corn, Green				42	13	18	25	285	1142	1714	1614	73	4,926
Cucumbers			235	673	652	429	487	699	404	1132	198		4,909
Eggplant	3	lcl	11	28	48	107	162	178	149	185	116	15	1,002
Escarole				68	244	259	206	227	199	132	5		1,340
Lettuce & Romaine				20	78	177	101	58	34	10			478
Peas, English				lcl	4	9	9	1	4	2			29
Peppers			2	33	165	611	584	758	856	1120	490	5	4,624
Potatoes					60	489	862	2032	2965	2701	33		9,142
Tomatoes			lcl	326	2019	1153	2562	2953	3011	2222	548	6	14,800
Other Vegetables	21	5	65	124	171	180	276	321	359	597	287	37	2,443
Mixed Car Vegetables			34	123	563	1133	1235	1418	1001	623	150	20	6,300
TOTAL VEGETABLES	24	5	470	2609	5756	9471	12595	16859	16054	14764	4196	165	82,968
VEGS. & MISCL.FRUITS	69	44	533	2691	5804	9770	13000	16988	16181	16376	16288	1280	99,024
ALL FRUITS & VEGS.	78	91	3445	10136	17979	18598	20774	26312	23995	23764	19591	1594	166,357

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS

(These figures have been revised and rearranged and may not agree or seem to agree with some previous tabulations. The totals are substantitally the same.)

	Freight Shipments									
Commodity	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49	1949-50
Oranges	27,084	34,374	43,390	51,405	41,049	41,848	43,390	33,524	26,603	14,345
Grapefruit	12,135	12,650	12,258	13,441	8,534	12,201	12,606	11,801	13,826	7,671
Tangerines	2,171	1,865	5,017	3,856	4,370	3,813	2,974	2,884	2,923	2,205
Mixed Citrus	6,770	10,062	13,162	13,626	11,102	13,573	9,599	6,667	8,155	4,804
Total Citrus	48,160	58,951	73,827	82,328	65,055	71,435	68,569	54,876	51,507	29,025
Strawberries	4	-	6	22	43	25	99	56	110	182
Watermelons	5,028	5,565	3,363	6,116	8,366	7,470	7,963	9,247	8,864	10,054
Miscellaneous Fruits	2	-	-	16	15	3	9	-	-	2
Total Non-Citrus	5,034	5,565	3,369	6,154	8,424	7,498	8,071	9,303	8,974	10,238
Beans & Limas	2,700	3,335	5,943	6,596	4,682	4,538	3,668	3,148	3,628	2,550
Cabbage	2,256	3,568	4,534	6,378	5,157	4,763	2,459	4,934	5,457	4,016
Celery	8,689	9,119	8,557	9,349	11,037	12,489	8,747	8,966	9,345	10,011
Corn, Green	2	7	17	18	42	104	166	338	1,223	2,191
Cucumbers	981	1,181	461	405	988	1,549	1,138	1,500	1,052	787
Eggplant	36	29	175	246	304	251	81	182	70	47
Escarole	573	818	1,003	1,120	1,347	1,317	827	1,039	974	919
Lettuce	235	147	197	207	152	166	116	90	102	123
Peas, English	80	130	115	153	83	62	14	16	None	2
Peppers	647	863	1,352	1,805	1,622	1,612	744	1,499	1,364	1,842
Potatoes	3,306	5,540	4,756	5,282	7,068	9,591	4,001	4,807	6,593	5,322
Tomatoes	3,679	5,035	4,367	4,592	5,305	5,269	3,249	3,782	6,783	6,003
Squash (estimated)	275	300	400	400	500	400	400	500	400	300*
Other Variety Vegetables	36	86	133	364	426	484	224	181	202	242**
Mixed Car Vegetables	1,354	2,113	3,973	5,855	6,884	7,217	4,704	4,442	4,472	4,654***
Total Vegetables	24,849	32,271	35,983	42,770	45,597	49,812	30,538	35,424	41,665	39,009
Total Vegs. & Non-Citrus	29,883	37,836	39,352	48,924	54,021	57,310	38,609	44,727	50,639	49,247
ALL FRUITS & VEGETABLES	78,043	96,787	113,179	131,252	119,076	128,745	107,178	99,603	102,146	78,272

NOTE: * Includes an estimated 300 straight cars of Squash not officially reported.

** Other Vegetables include carloads as follows: Beets 6, Broccoli 2, Carrots 2, Cauliflower 97, Spinach 9, Sweet Potatoes 21, Greens (except Spinach) 105. Total 242 carloads.

*** Mixed Vegetables includes eggplant, peppers, escarole, squash, and all other vegetables shipped in mixed cars.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

Commodity	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49	1949-50
					Express Shipments					
EXPRESS										
Mixed Citrus	1,169	1,177	2,371	3,100	3,041	3,376	3,630	3,115	3,412	3,062
Strawberries	47	58	55	1	-	-	-	-	-	-
Miscellaneous Fruits	75*	125*	175*	175*	90*	90*	100*	100*	90*	100*
Total Non-Citrus	122	183	230	176	90	90	100	100	90*	100*
Beans & Limas	45	-	-	-	-	-	-	-	-	-
Mixed Car Vegetables	396	605	1,074	1,283	1,148	1,179	848	533	433	336
Total Vegetables	441	605	1,074	1,283	1,148	1,179	848	533	433	336
Total Vegs. & Non-Citrus	563	788	1,304	1,459	1,238	1,269	948	633	523	436
ALL FRUITS & VEGETABLES	1,732	1,965	3,675	4,559	4,279	4,645	4,578	3,748	3,935	3,498
BOAT					Boat Shipments					
Oranges	11,189	1,153				76	2,908	-	35	3,087
Grapefruit	5,481	514				12	1,437	-	-	1,662
Tangerines	1,063	147				-	222	-	-	409
Mixed Citrus	10	3	No record of any			-	-	-	-	-
Total Citrus	17,743	1,817				88	4,567	-	35	5,158
Watermelons	-	-	boat shipments			-	-	-	-	-
Miscellaneous Fruits	5	-				-	-	-	-	-
Total Non-Citrus	5	-	during (War Period)			-	-	-	-	-
Beans & Limas	154	1				-	-	-	-	-
Cabbage	14	-	1942-43 thru			-	-	-	-	3
Celery	148	-				-	100	-	-	248
Corn, Green	-	-	1944-45 Seasons			-	3	-	-	-
Cucumbers	40	-				-	3	-	-	1
Eggplant	35	-				-	-	-	-	-
Peas, English	1	-				-	-	-	-	-
Peppers	163	6				-	-	-	-	7
Potatoes	898	-				-	164	-	-	191
Tomatoes	13	-				-	-	-	-	-
Squash	40	1				-	-	-	-	-
Other Variety Vegetables	103	3				-	2	5	-	7
Total Vegetables	1,609	11				-	272	5	-	457
Total Vegs. & Non-Citrus	1,614	11				-	272	5	-	457
ALL FRUITS & VEGETABLES	19,357	1,828				88	4,839	5	35	5,615

Note: * Miscl.Fruits by L.C.L. Exp. estimated at 100 carloads, including Avocados 40, Limes 45, Mangoes & Misc.Frts 15 cars.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

	Trucked Out Shipments									
Commodity	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49	1949-50
Oranges	14,315	10,248	6,790	5,388	3,641	5,135	8,774	14,268	30,356	20,451
Grapefruit	3,899	2,605	1,532	889	513	851	1,395	2,858	8,708	6,931
Tangerines	1,087	837	1,000	957	819	960	1,096	1,670	2,702	2,706
Total Citrus	19,301	13,690	9,322	7,234	4,973	6,946	11,265	18,796	41,766	30,088
Strawberries	1,073	860	300	164	263	446	615	321	410	724
Watermelons	976	695	190	630	654	2,538	3,278	3,503	4,888	4,500
Avocados	150	143	60	142	327	42	72	81	97	230
Limes	130	90	20	18	100	63	44	31	111	164
Miscellaneous Fruits	41	17	30	32	25	77	65	38	56	200
Total Non-Citrus	2,370	1,805	600	986	1,369	3,166	4,074	3,974	5,562	5,818
Beans	5,149	6,026	2,300	2,405	2,123	2,832	3,219	4,172	5,642	6,702
Limas	336	500	100	99	134	297	229	343	503	540
Cabbage	2,298	3,539	1,900	2,116	1,449	2,083	3,003	3,983	3,543	5,327
Celery	1,681	1,582	360	401	405	566	1,020	1,381	2,345	3,481
Corn, Green	219	200	150	190	121	392	479	662	1,803	2,735
Cucumbers	1,196	866	265	250	444	741	896	1,999	2,564	4,121
Eggplant	586	734	300	525	380	682	756	754	1,153	955
Escarole	203	116	15	7	25	20	145	200	284	421
Lettuce	232	150	26	54	51	93	90	103	142	355
Peas, English	221	222	20	77	53	52	26	18	16	27
Peppers	1,445	1,656	900	865	809	1,524	1,586	1,987	2,983	2,775
Potatoes	1,068	1,116	500	426	872	759	701	1,278	2,697	3,629
Tomatoes	3,988	3,994	1,700	3,190	2,826	3,549	2,526	3,826	6,907	8,797
Squash	560	538	300	440	447	653	645	815	1,098	1,358
Butterbeans	58	50	20	41	46	142	94	145	*	*
Field Peas	215	200	110	220	288	553	658	804	728	630
Okra	83	63	25	39	76	155	111	186	252	265
Bunched Vegetables	66	70	30	114	45	59	50	110	56	38
Miscellaneous Vegetables	437	422	265	247	225	340	434	619	870	1,310
Total Vegetables	20,041	22,044	9,286	11,706	10,819	15,492	16,668	23,385	33,586	43,466
Total Vegs. & Non-Citrus	22,411	23,849	9,886	12,692	12,188	18,658	20,742	27,359	39,148	49,284
ALL FRUITS & VEGETABLES	41,712	37,539	19,208	19,926	17,161	25,604	32,007	46,155	80,914	79,372

Note: * Included with Limas.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd.)

Commodity	1940-41	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49	1949-50
	Total Freight, Express, Boat and Truck Shipments from Florida									
Oranges	52,588	45,775	50,180	56,793	44,690	47,059	55,072	47,792	56,994	37,883
Grapefruit	21,515	15,769	13,790	14,330	9,047	13,064	15,438	14,659	22,534	16,264
Tangerines	4,321	2,849	6,017	4,813	5,189	4,773	4,292	4,554	5,625	5,320
Mixed Citrus (Rail)	7,949	11,242	15,533	16,726	14,143	16,949	13,229	9,782	11,567	7,866
Total Citrus	86,373	75,635	85,520	92,662	73,069	81,845	88,031	76,787	96,720	67,333
Strawberries	1,124	918	361	187	306	471	714	377	520	906
Watermelons	6,004	6,260	3,553	6,746	9,020	10,008	11,241	12,750	13,752	14,554
Avocados (Truck & Exp.)	190	205	150	237	382	77	127	141	127	230
Limes (Truck & Express*	160	145	95	88	130	103	79	63	161	164
(*)Miscl.Fruits(Exp.& Truck)	48	25	40	42	30	90	84	46	66	302
Total Miscl. Fruits	7,526	7,553	4,199	7,300	9,868	10,749	12,245	13,377	14,626	16,156
Beans & Limas	8,384	9,862	8,343	9,100	6,939	7.667	7,116	7,663	9,773	9,792
(a)Butterbeans (truck)	58	50	20	41	46	142	94	145	**	**
Cabbage	4,568	7,107	6,434	8,494	6,606	6,846	5,462	8,917	9,000	9,346
Celery	10,518	10,701	8,917	9,750	11,442	13,055	9,867	10,347	11,690	13,740
Corn,Green	221	207	167	208	163	496	648	1,000	3,026	4,926
Cucumbers	2,217	2,047	726	655	1,432	2,290	2,037	3,499	3,616	4,909
Eggplant	657	763	475	771	684	933	837	936	1,223	1,002
Escarole	776	934	1,018	1,127	1,372	1,337	972	1,239	1,258	1,340
Lettuce	467	297	223	261	203	259	206	193	244	478
Peas,English	302	352	135	230	136	114	40	34	16	29
Peppers	2,255	2,525	2,252	2,670	2,431	3,136	2,330	3,486	4,347	4,624
Potatoes	5,272	6,656	5,266	5,708	7,940	10,350	4,866	6,085	9,290	9,142
Tomatoes	7,680	9,029	6,067	7,782	8,131	8,818	5,775	7,608	13,690	14,800
Squash	875	839	700	840	947	1,053	1,045	1,315	1,498	1,658
(a)Field Peas (Truck)	215	200	110	220	288	553	658	804	728	630
(a)Okra (Truck)	83	63	25	39	76	155	111	186	252	265
(a)Bunched Vegetables (Truck)	66	70	30	114	45	59	50	110	56	38
(a)Other Vegetables (Truck)	437	422	265	247	225	340	434	619	870	1,310
(b)Oth.Vegs(Freight & Boat)	139	89	133	364	426	484	226	186	202	249
(c)Mixed Vegs.(Freight & Exp.)	1,750	2,718	5,047	7,138	8,032	8,396	5,552	4,975	4,905	4,990
Total Vegetables	46,940	54,931	46,353	55,759	57,564	66,483	48,326	59,347	75,684	83,268
Total Vegs. & Miscl.Frts	54,466	62,484	50,552	63,059	67,432	77,232	60,571	72,724	90,310	99,424
ALL FRUITS & VEGETABLES	140,839	138,119	136,072	155,721	140,501	159,077	148,602	149,511	187,030	166,757

(*)Includes estimates for Express Shipments of avocados, limes, mangoes, etc. ** Included with beans & limas.
(a)Truck Shipments only, with small volume included in Miscellaneous or Mixed Cars.
(b)Freight and Boat only. (c) Freight and Express only. Estimated 100 straight cars Radishes not reported or included.

RAIL FREIGHT SHIPMENTS BY COUNTIES
1949-50 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Oranges	Grapefruit	Tangerines	Mixed Citrus	Total Citrus	Beans & Limas	Beets	Broccoli
Alachua	85	3	1	8	97	67		
Bradford								
Brevard	661	480		219	1360			
Broward						721		
Citrus	6	2		1	9			
Clay								
Collier								
Columbia								
Dade	1				1	79		
De Soto	194	36	21	78	329			
Dixie								
Duval	340	47	47	57	491			
Escambia								
Flagler								
Gilchrist								
Glades								
Hamilton								
Hardee	2				2			
Hendry								
Hernando	107	28	132	27	294			
Highlands	943	294	36	139	1412			
Hillsborough	443	172	50	215	880			
Indian River	216	532	1	127	876			
Jackson								
Jefferson								
Lafayette								
Lake	1760	605	216	764	3345	5		
Lee	27	48		20	95			
Leon								
Levy								
Madison								
Manatee	62	55		3	120	3		
Marion	669	160	6		835	38		
Martin				45	45			
Okeechobee								
Orange	4092	971	892	944	6899	35	6	2
Osceola	9	10	4	7	30			
Palm Beach						1555		
Pasco	141	77	4	35	257			
Pinellas	153	1492	19	122	1786			
Polk	3342	2171	563	1419	7495			
Putnam	103	1	33	48	185			
St. Johns								
St. Lucie	62	145	4	56	267			
Sarasota	23	114		32	169			
Seminole	598	154	138	237	1127	19		
Sumter	3		1		4	28		
Suwannee								
Union								
Volusia	303	74	37	201	615			
Walton								
Washington								
Unknown								
Straight Cars	14345	7671	2205	4804	29025	2550	6	2
Boat	3087	1662	409		5158			
Pick-Up-Express				3062	3062			
GRAND TOTAL	17432	9333	2614	7866	37245	2550	6	2

RAIL FREIGHT SHIPMENTS BY COUNTIES
1949-50 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Cabbage	Carrots	Cauliflower	Celery	Green Corn	Cucumbers	Eggplant	Escarole	Greens
Alachua	59			296	14	79	2		
Bradford					17				
Brevard					23				
Broward						20	7		9
Citrus									
Clay	10								
Collier						62			
Columbia	3				2				
Dade	40				33	1			
De Soto									
Dixie									
Duval									
Escambia									
Flagler	209								
Gilchrist									
Glades	98				51				
Hamilton	21								
Hardee						149			
Hendry	274								
Hernando									
Highlands		1							
Hillsborough	45		85		37	130	10	5	
Indian River									
Jackson	2					13			
Jefferson					8				
Lafayette									
Lake				766	159			12	
Lee					3	119	1		
Leon									
Levy									
Madison									
Manatee	123				9	92	12	40	
Marion	13			196	3	9			
Martin					32	20	1	4	
Okeechobee									
Orange	194			483	482	23		147	22
Osceola									
Palm Beach	839	1		2836	1092		14	524	27
Pasco									
Pinellas									
Polk	9								
Putnam	113								
St. Johns	1180		8		2				
St. Lucie	7		1		3	14			47
Sarasota	10			1699	21	13		2	
Seminole	469		3	3735	186	5		185	
Sumter						20			
Suwannee	12					8			
Taylor									
Union	9				14	1			
Volusia	277								
Walton						7			
Washington									
Unknown						2			
Straight Cars	4016	2	97	10011	2191	787	47	919	105
Boat	3			248		1			7
Pick-Up-Express									
GRAND TOTAL	4019	2	97	10259	2191	788	47	919	112

RAIL FREIGHT SHIPMENTS BY COUNTIES
1949-50 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Lettuce & Romaine	English Peas	Peppers	Potatoes	Spinach	Sweet Potatoes	Tomatoes	Mixed Veg's
Alachua	6		77	85		1		59
Bradford								
Brevard								
Broward			886				411	1450
Citrus								
Clay								
Collier							366	
Columbia								
Dade				1942			2037	19
De Soto								
Dixie								
Duval								
Escambia				1				
Flagler				399				2
Gilchrist								
Glades								1
Hamilton			7					
Hardee			3				30	15
Hendry	37							1
Hernando								
Highlands								65
Hillsborough	4		467	18			487	168
Indian River							271	
Jackson								
Jefferson								
Lafayette								
Lake							2	9
Lee			64	566		13	6	54
Leon								
Levy								
Madison								
Manatee	13			2			1065	54
Marion			5	9	3		60	159
Martin			11	3		7	2	106
Okeechobee							290	
Orange	12		34		6			301
Osceola								
Palm Beach	14	2	71	216			69	1575
Pasco								
Pinellas								
Polk			2					8
Putnam				292				1
St. Johns				1783				30
St. Lucie			15				900	29
Sarasota				6				156
Seminole	37		68					353
Sumter			107				7	34
Suwannee								
Taylor								
Union								
Volusia			25					5
Walton								
Washington								
Unknown								
Straight Cars	123	2	1842	5322	9	21	6003	4654
Boat			7	191				
Pick-Up-Express								336
GRAND TOTAL	123	2	1849	5513	9	21	6003	4990

RAIL FREIGHT SHIPMENTS BY COUNTIES
1949-50 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Total Veg's	Straw's-berries	Water-melons	Other Non-Citrus	Total Non-Citrus	Total Veg's & Non-Citrus	GRAND TOTAL
Alachua	745		1135	1	1136	1881	1978
Bradford	17		43		43	60	60
Brevard	23					23	1383
Broward	3504		2		2	3506	3506
Citrus			37		37	37	46
Clay	10					10	10
Collier	428		55		55	483	483
Columbia	5		41		41	46	46
Dade	4151					4151	4152
De Soto			12	1	13	13	342
Dixie			45		45	45	45
Duval							491
Escambia	1					1	1
Flagler	610					610	610
Gilchrist			1294		1294	1294	1294
Glades	150					150	150
Hamilton	28		18		18	46	46
Hardee	197	9	13		22	219	221
Hendry	312					312	312
Hernando			53		53	53	347
Highlands	66					66	1478
Hillsborough	1456	147	356		503	1959	2839
Indian River	271		73		73	344	1220
Jackson	15		18		18	33	33
Jefferson	8		456		456	464	464
Lafayette			133		133	133	133
Lake	953		1383		1383	2336	5681
Lee	826					826	921
Leon			5		5	5	5
Levy			386		386	386	386
Madison			196		196	196	196
Manatee	1413		53		53	1466	1586
Marion	495		1544		1544	2039	2874
Martin	186					186	231
Okeechobee	290					290	290
Orange	1747		83		83	1830	8729
Osceola							30
Palm Beach	8835					8835	8835
Pasco			551		551	551	808
Pinellas			1		1	1	1787
Polk	19	26	64		90	109	7604
Putnam	406		137		137	543	728
St. Johns	3003		3		3	3006	3006
St. Lucie	1016		42		42	1058	1325
Sarasota	1907		10		10	1917	2086
Seminole	5060					5060	6187
Sumter	196		784		784	980	984
Suwannee	20		961		961	981	981
Union	24		28		28	52	52
Volusia	307		38		38	345	960
Walton	7					7	7
Washington			1		1	1	1
Unknown	2					2	2
Straight Cars	38709	182	10054	2	10238	48947	77972
Boat	457					457	5615
Pick-Up-Express	336					336	3398
GRAND TOTAL	39502	182	10054	2	10238	49740	86985

As of September 1, 1950. Subject to Revision.

TRUCK SHIPMENTS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS BY WEEKS FOR 1949-50 SEASON

(Rail Carload Equivalent)

Oct. 16, 1949-June 17, 1950

Date by Weeks	Beans	Limas Butter Beans	Cabbage	Celery	Cukes	Gr. Corn	Eggplant	Escarole	Eng. Peas	F. Peas	Lettuce	Peppers	Potatoes
Aug. 1-30*							3			4			
Sept.1-30*							LCL			2			
Oct. 1-15*	3				25		2			4		LCL	
Oct. 16-22	4				33		2			1		LCL	
Oct. 23-29	66				96		6			4		1	
Oct. 30-Nov.5	152				166		7			5		1	
Nov. 6-12	195				102	8	5			5		3	
Nov. 13-19	185		LCL	21	174	19	9	9		5	2	5	
Nov. 20-26	183	LCL	1	8	71	6	5	7	LCL	2	6	4	
Nov. 27-Dec.3	129	2	1	26	73	6	6	25	LCL	1	10	8	LCL
Dec. 4-10	160	1	7	22	113	4	7	23	LCL	1	10	10	1
Dec. 11-17	201	3	22	51	140	2	12	18	1	1	9	28	6
Dec. 18-24	186	5	38	38	114	LCL	12	18	1	1	7	28	9
Dec. 25-31	81	2	67	60	100	1	12	10	2	1	17	26	8
Jan. 1-7	151	18	152	111	93	6	24	16	2	1	30	69	29
Jan. 8-14	149	17	248	118	74	5	19	14	4	2	40	91	37
Jan. 15-21	206	11	245	128	83	5	22	19	1	2	26	63	38
Jan. 22-28	240	10	270	134	99	2	27	16	3	2	23	60	44
Jan. 29-Feb.4	220	15	336	160	114	4	47	12	2	2	20	88	48
Feb. 5-11	226	7	365	173	113	3	42	12	2	1	22	107	53
Feb. 12-18	219	6	413	164	113	5	37	8	3	2	26	99	68
Feb. 19-25	247	6	376	120	97	8	33	16	1	2	12	77	75
Feb. 26-Mar.4	345	7	414	169	122	13	40	14	LCL	2	13	91	92
Mar. 5-11	365	6	387	142	129	26	43	19	LCL	1	11	98	86
Mar. 12-18	383	10	368	146	169	26	43	13	LCL	2	10	120	110
Mar. 19-25	325	14	303	124	161	65	41	10	1	3	10	132	139
Mar. 26-Apr.1	253	16	298	150	149	103	37	15	1	6	9	130	189
Apr. 2-8	252	30	283	180	118	138	36	21	1	10	4	130	203
Apr. 9-15	245	19	208	189	86	143	31	16	1	13	11	121	263
Apr. 16-22	369	17	198	158	70	175	34	18	1	18	8	110	334
Apr. 23-29	313	14	137	150	80	182	33	11	1	15	10	157	431
Apr. 30-May 6	290	16	99	162	103	179	39	12	LCL	25	8	161	316
May 7-13	228	17	39	137	160	199	37	19	LCL	39	1	142	307
May 14-20	79	42	25	115	235	201	37	8	1	73	1	122	352
May 21-27	29	78	16	126	251	221	32	7		87		145	316
May 28-June 3	14	60	9	100	210	244	47	10		125		83	70
June 4-10	10	34	2	75	64	221	27	4		93		118	3
June 11-17	1	21	LCL	22	14	128	21			31		100	2
June 18-30*		30		2	8	350	25			25		40	3
July 1-31 *		9				40	13			12		5	
Total by Weeks Aug.1-July 31	6704	543	5327	3481	4122	2738	955	420	29	631	356	2773	3632
Total by Mos. Aug.1-July 31	6702	540	5327	3481	4121	2735	955	421	27	630	355	2775	3629
Oct.16-June 17	6701	504	5327	3479	4089	2348	912	420	29	584	356	2728	3629

*Estimated. (1) Passings converted into carload equivalent on basis of: Beans 600 bu; Cabbage 25,000 lbs; Celery 420 crts; Cukes 420 bu; Eggplant 600 pkgs; Escarole 600 pkgs; Lettuce 550 pkgs; English Peas 580 bu; Peppers 620 pkgs; Potatoes 600 pkgs; Tomatoes 500 pkgs; Green Corn 2500 doz. Butterbeans included with Limas 500 bu.

The Weekly Totals differ from, and are usually slightly higher than the Monthly Totals, due to fractional totals by weeks. Notes apply to opposite page and vice versa.

TRUCK SHIPMENTS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS
BY WEEKS FOR 1949-50 SEASON
(Rail Carload Equivalent)

Date by Weeks	Tomatoes	Okra	Squash	Bun. Vegs.	Oth. Vegs.	Tot. Vegs.	Strawberries	W-Mel.	Avocados	Limes	Oth. Misc. Fru.	Tot. Misc. Fru.	Grand Total
Aug. 1-30*		15				22			15	30		45	67
Sept.1-30*		3				5			25	14		39	44
Oct. 1-15*		10	5			49			28	2		30	79
Oct. 16-22		10	5	LCL		55			18	1		19	74
Oct. 23-29		9	11	LCL		193			12	1	LCL	13	206
Oct. 30-Nov.5	3	6	16	LCL	1	357			11	LCL		11	368
Nov. 6-12	12	2	20	LCL	1	353			22	LCL		22	375
Nov. 13-19	56	2	28	LCL	11	526			30	LCL		30	556
Nov. 20-26	81	2	19	1	15	411			10	1		11	422
Nov. 27-Dec.3	134	1	25	1	16	464			13	1		14	478
Dec. 4-10	206	LCL	34	1	26	626	LCL		10	LCL		10	636
Dec. 11-17	279	2	49	2	26	852	1		9	1		11	863
Dec. 18-24	226	1	29	LCL	28	741	3		6	1		10	751
Dec. 25-31	134	1	23	1	25	571	7		2	1		10	581
Jan. 1-7	138	1	15	2	56	914	18		3	1		22	936
Jan. 8-14	146	4	20	3	68	1059	34		4	1		39	1098
Jan. 15-21	147	2	27	3	75	1103	49		3	LCL		52	1155
Jan. 22-28	196	2	47	2	88	1265	73		LCL	LCL		73	1338
Jan. 29-Feb.4	271	3	53	2	76	1473	90		1	LCL		91	1564
Feb. 5-11	351	3	58	3	83	1624	90		2	LCL		92	1716
Feb. 12-18	381	3	58	3	87	1695	79		1	LCL		80	1775
Feb. 19-25	398	1	47	1	52	1569	61		1	1		63	1632
Feb. 26-Mar.4	419	2	58	2	71	1874	40		LCL	LCL		40	1914
Mar. 5-11	413	1	73	3	80	1883	40		LCL	LCL		40	1923
Mar. 12-18	391	2	56	2	83	1934	21		LCL	LCL		21	1955
Mar. 19-25	349	2	53	2	62	1796	22		LCL	1		23	1819
Mar. 26-Apr.1	382	3	49	1	46	1837	15		LCL	LCL		15	1852
Apr. 2-8	395	4	42	2	51	1900	15		LCL	LCL		15	1915
Apr. 9-15	489	2	40	1	41	1919	15	2	LCL	LCL		17	1936
Apr. 16-22	473	4	70	LCL	39	2096	19	6	LCL	LCL	LCL	25	2121
Apr. 23-29	454	5	81	1	42	2117	16	14	LCL	LCL	1	31	2148
Apr. 30-May 6	417	6	89	LCL	17	1939	9	17		2	1	29	1968
May 7-13	356	8	65	LCL	14	1768	4	40	LCL	2	1	47	1815
May 14-20	310	11	45	LCL	8	1665	3	97	LCL	2	2	104	1769
May 21-27	272	19	26	LCL	6	1631	1	231	LCL	5	6	243	1874
May 28-June 3	223	26	15	LCL	6	1242	LCL	293	LCL	6	7	306	1548
June 4-10	165	27	5	LCL	4	852		523	1	10	37	571	1423
June 11-17	97	22	1		1	461		919	LCL	11	48	978	1439
June 18-30*	30	20	1		3	537		2058		26	82	2166	2703
July 1-31 *	6	20			4	109		300	4	40	15	359	468
Total by Weeks Aug.1-July 31	8800	267	1358	39	1312	43487	725	4500	231	161	200	5817	49304
Total by Mos. Aug.1-July 31	8797	265	1358	38	1310	43466	724	4500	230	164	200	5818	49284
Oct.16-Jun.17	8764	199	1352	39	1305	42765	725	2142	159	49	103	3178	45943

(2) Converted into carload equivalent on basis of: Okra 500 pkgs; Squash 500 pkgs; Bunched Vegetables 2000 doz; Other Vegetables 500 pkgs; Field peas 600 pkgs; Avocados 900 pkgs; Strawberries 450 pkgs; Limes 1000 pkgs; Watermelons 1000 melons; Other Fruits 500 pkgs.

(3) The Shipments are the passings by Road Guard Stations (open October 16 to June 17, 1950) and destined for out-of-State points, excepting some carloads to West Florida. Several carloads of West Florida vegetables going out of State were not included. Watermelons originating West of the Suwannee River and going out of State were included in the estimates for period after May 31.

CITRUS - ACREAGE AND PRODUCTION IN STANDARD BOXES (1) (In Thousands)

Crop Season	FLORIDA Acreage	FLORIDA Production	CALIFORNIA Acreage	CALIFORNIA Production	TEXAS Acreage	TEXAS Production	ARIZONA Acreage	ARIZONA Production	OTHER STATES Acreage	OTHER STATES Production	TOTAL UNITED STATES Acreage	TOTAL UNITED STATES Production
ORANGES												ORANGES
1919-20	52.8	7,550	155.8	16,632	.2	9	.5	80	3.0	88	212.3	24,359
1924-25	106.2	10,400	173.0	18,506	1.0	17	.9	60	3.5	77	284.6	29,060
1929-30	133.0	8,950(A)	190.1	21,195	5.1	261	1.1	137	5.1	436	334.4	30,979
1934-35	187.3	15,600	206.7	45,047	20.9	650	4.1	170	6.6	521	425.6	61,988
1939-40	216.2	25,600	229.2	44,425	24.2	2,360	7.3	595	8.3	362	485.2	73,342
1944-45	256.3	42,800	237.8	60,500	28.4	4,400	7.1	1,150	4.5	360	534.1	109,210
1948-49	289.9	58,300	239.2	36,910	40.5	3,400(B)	8.3(B)	710(B)	4.5	300	582.4	99,620
GRAPEFRUIT												GRAPEFRUIT
1919-20	25.9	5,900	2.6	363	.1	3	.2	29	-	-	28.8	6,295
1924-25	45.7	8,900	3.8	387	2.4	301	.5	105	-	-	52.4	9,693
1929-30	58.0	8,300(A)	10.1	1,000	11.1	1,550	2.1	365	-	-	81.3	11,215
1934-35	78.3	15,200	13.7	2,167	57.9	2,740	7.2	1,240	-	-	157.1	21,347
1939-40	87.5	15,900	16.4	1,992	73.1	14,400	13.8	2,900	-	-	190.8	35,192
1944-45	90.0	22,300	14.6	3,830	77.0	22,300	13.0	3,750	-	-	194.6	52,180
1948-49	95.0	30,200	13.2	2,140	82.0	11,300(B)	10.3	1,880(B)	-	-	200.5	45,520

	FLORIDA TANGERINES Acreage	FLORIDA TANGERINES Production	FLORIDA LIMES Acreage	FLORIDA LIMES Production	TOTAL FLORIDA TANGERINES, LIMES Acreage	TOTAL FLORIDA TANGERINES, LIMES Production	CALIFORNIA LEMONS Acreage	CALIFORNIA LEMONS Production	TOTAL TANGERINES LIMES, LEMONS Acreage	TOTAL TANGERINES LIMES, LEMONS Production
1919-20	3.9	450	1.5	28	5.4	478	35.6	4,532	41.0	5,010
1924-25	6.2	900	2.5	36	8.7	936	41.3	5,301	50.0	6,237
1929-30	15.4	850(A)	1.8	8	17.2	858	40.5	6,109	57.7	6,967
1934-35	24.1	2,000	2.1	15	26.2	2,015	40.4	10,747	66.6	12,762
1939-40	25.1	2,400	3.7	95	28.8	2,495	52.0	11,983	80.8	14,478
1944-45	23.4	4,000	5.1	250	28.5	4,250	62.7	12,550	91.2	16,800
1948-49	24.0	4,400	4.6	200	28.6	4,600	64.7	9,930	93.3	14,530

ALL CITRUS	FLORIDA Acreage	FLORIDA Production	CALIFORNIA Acreage	CALIFORNIA Production	TEXAS Acreage	TEXAS Production	ARIZONA Acreage	ARIZONA Production	OTHER STATES Acreage	OTHER STATES Production	TOTAL UNITED STATES Acreage	TOTAL UNITED STATES Production
1919-20	84.1	13,928	194.0	21,527	.3	12	.7	109	3.0	88	282.1	35,664
1924-25	160.1	20,236	218.1	24,194	3.4	318	1.4	165	3.5	77	387.0	44,990
1929-30	208.2	18,108(A)	240.7	28,304	16.2	1,811	3.2	502	5.1	436	473.4	49,161
1934-35	291.8	32,815	260.8	57,961	78.8	3,390	11.3	1,410	6.6	521	649.3	96,097
1939-40	332.5	43,995	297.6	58,400	97.3	16,760	21.1	3,495	8.3	362	756.8	123,012
1944-45	374.8	69,350	315.1	76,880	105.4	26,700	20.1	4,900	4.5	360	819.9	178,190
1948-49(2)	413.5	93,100	317.1	48,980(B)	122.5	14,700(B)	18.6	2,590(B)	4.5	300	876.2	159,670

(1) Thousand of bearing acres, and thousand of boxes. Florida and Texas boxes 1-3/5 bu., Calif. & Arizona slightly smaller.
(2) Last figure available. 1949-50 unavailable for all of the States.
(A) Fruit Fly Season. (B) Freezes. (C) Fruit Fly and also previous hurricane damage.

ESTIMATED BEARING ORANGE, GRAPEFRUIT AND TANGERINE TREES IN FLORIDA IN 1949 (In Thousands)

BY RANK: ALL CITRUS FLORIDA COUNTIES	ORANGES: Early & Mid-Sea. Bearing Trees	Percent by Age Group 4-5	6-10	11-15	16 up	Late Type Bearing Trees	Percent by Age Group 4-5	6-10	11-15	16 up	GRAPEFRUIT: Seedless Bearing Trees	Percent by Age Group 4-5	6-10	11-15	16 up	Seeded Bearing Trees	Percent by Age Group 4-5	6-10	11-15	16 up
Polk	1,912	8	19	16	57	2,227	5	8	4	83	648	4	8	7	81	1,178	3	3	4	90
Orange	1,772	7	16	20	57	1,039	9	18	13	60	126	10	14	22	54	164	3	3	9	85
Lake	1,377	9	14	16	61	741	8	15	13	64	285	6	6	10	78	292	2	3	5	90
Hillsboro	592	7	13	16	64	411	4	12	13	71	89	6	8	9	77	114	3	3	10	84
St.Lucie	318	19	22	18	41	392	11	19	12	58	284	10	27	12	51	113	7	1	5	87
Highlands	244	8	10	14	68	438	4	7	4	85	129	4	5	3	88	200	-	-	2	98
Indian Ri.	224	4	23	31	42	240	7	14	32	47	392	8	21	18	53	179	1	3	13	83
Volusia	548	2	3	9	86	232	1	5	13	81	25	3	11	27	59	67	1	1	7	91
Brevard	506	3	9	11	77	256	4	6	14	76	100	8	12	22	58	116	-	4	7	89
Pinellas	221	7	12	11	70	242	7	7	8	78	196	7	4	9	80	281	2	2	3	93
Pasco	317	6	29	24	41	318	7	26	14	53	62	9	12	17	62	71	1	6	23	70
Marion	594	3	4	10	83	59	-	-	-	-	16	2	2	27	69	40	1	3	5	91
Hardee	446	4	10	11	75	192	4	7	15	74	9	4	9	16	71	45	1	1	3	95
Seminole	360	3	6	10	81	106	17	10	11	62	13	2	4	6	88	34	-	3	7	90
Manatee	136	6	12	9	73	130	3	4	19	74	66	3	13	20	64	225	1	1	4	94
DeSoto	306	1	3	7	89	124	2	5	8	85	8	-	-	-	-	80	2	1	4	93
Putnam	234	1	5	11	83	43	-	-	-	-	-	-	-	-	-	25	-	-	-	-
Lee	85	3	8	9	80	103	1	5	10	84	39	2	2	11	85	101	1	1	2	96
Osceola	164	6	9	14	71	72	4	10	16	70	11	1	6	19	74	31	-	2	2	96
Other Co.	532					591					122					199				
TOTAL	10,888					7,956					2,620					3,555				

TANGERINES

COUNTIES	Bearing Trees	Percent by Age Group 4-5	6-10	11-15	16 up
Polk	353	1	1	2	96
Orange	204	2	2	1	95
Lake	154	2	2	4	92
Hillsboro	78	2	2	4	92
St.Lucie	54	-	2	1	97
Highlands	52	2	-	1	97
Indian Ri.	27	-	2	2	96
Volusia	154	1	-	1	98
Brevard	32	-	1	1	98
Pinellas	38	2	4	3	91
Pasco	32	-	1	5	94
Marion	45	-	-	4	96
Hardee	46	-	-	1	99
Seminole	56	3	-	1	96
Manatee	7	-	-	-	-
DeSoto	38	-	-	1	99
Putnam	40	-	-	1	99
Lee	6	-	-	-	-
Osceola	28	-	1	1	98
Other Co.	116				
TOTAL	1,560				

COUNTIES	TOTAL BEARING TREES
Polk	6,318
Orange	3,305
Lake	2,849
Hillsboro	1,284
St. Lucie	1,161
Highlands	1,063
Indian River	1,062
Volusia	1,026
Brevard	1,010
Pinellas	978
Pasco	800
Marion	754
Hardee	738
Seminole	569
Manatee	564
DeSoto	556
Putnam	342
Lee	334
Osceola	306
Other Co.	1,560
TOTAL STATE	26,579

1/State Plant Board records of truck movement from nurseries 1928-29 thru 1945-46, adjusted for replacements by Bu. of Agri. Econ., Univ. of Fla.; with allowance for trees planted prior to 1928-29, based on Fla. Citrus Tree Survey, U.S.D.A, 1934.

ANNUAL PACKS OF GRAPEFRUIT AND ORANGE SEGMENTS AND JUICE FOR SELECTED YEARS

(Some Years Omitted for Lack of Space)(In Thousands)

	FLORIDA	TEXAS	CALIF.& ARIZONA	TOTAL U.S.	GOV. PUR.	COMM. EXP.	FOR DOM.MKTS.
		(1,000 cases of 24 No. 2 Cans)					
GRAPEFRUIT SEGMENTS							
1934-35	3,588	7	4	3,599	#	1,159	2,440
1939-40	4,134	57	-	4,191	#	1,397	2,794
1942-43	888	87	-	975	832	2	141
1945-46	2,407	289	-	2,696	7	7	2,689
1947-48	3,158	242	-	3,400	#	#	#
1948-49	4,238	189	-	4,427	#	#	#
GRAPEFRUIT JUICE							
1934-35	2,237	361	442	3,040	0	#	3,040
1939-40	4,682	5,955	296	10,933	0	574	10,359
1942-43	15,193	7,360	1,049	23,602	7,556	105	1,591
1945-46	15,089	9,601	1,372	26,062	397	467	25,198
1947-48	7,987	9,000	400	17,387	#	#	#
1948-49	8,843	4,944	518	14,305	#	#	#
ORANGE JUICE							
1934-35	241	0	704	945	0	0	945
1939-40	2,851	0	744	3,595	0	110	3,485
1942-43	2,429	0	394	2,823	1,544	43	1,236
1945-46	18,421	56	3,705	22,182	2	247	21,933
1947-48	25,593	165	1,500	27,258	#	#	#
1948-49	16,757	296	2,209	19,262	#	#	#
BLENDED JUICE							
1935-36	85	-	-	85	0	-	85
1939-40	1,403	30	-	1,433	0	-	1,433
1942-43	3,676	25	1	3,702	2,388	-	1,314
1945-46	12,267	626	568	13,461	96	-	13,365
1947-48	11,894	300	50	12,244	#	-	#
1948-49	10,252	229	348	10,829	#	-	#

FLORIDA PRODUCTION OF CERTAIN CITRUS PRODUCTS AND BY-PRODUCTS

	CONCENTRATED ORANGE JUICE					GRAPEFRUIT JUICE			
	(1) FROZEN GALS. (000)	(2) PROCESSED GALS. (000)	CITRUS FEED TONS (000)	MO- LASSES TONS (000)	CITRUS OILS LBS. (000)	CONCENTRATED FROZ. (000)	PROC. (000)	BLENDED FROZ. (000)	PROC. (000)
1940-41	-	66(1)	33	#	#	-	-	-	-
1941-42	-	94(1)	30	#	#	-	-	-	-
1942-43	-	1,882(2)	47	#	227	-	-	-	-
1943-44	-	1,283(3)	67	14	275	-	-	-	-
1944-45	-	240	69	19	290	-	-	-	-
1945-46	226	244	108	44	372	-	-	-	-
1946-47	559	1,447	96	58	#	-	-	-	-
1947-48	1,910	1,798	154	66	#	1.4	1,440	-	-
1948-49	10,233	1,898	134	41	#	116	19	112	.4

# Data unavailable. Source: Florida Citrus Fruit Annual Summary 1949 by Florida Crop and Livestock Reporting Service, Orlando, Florida. For missing years and other information pertaining to the above subjects, please write to Mr. J. C. Townsend, Jr., U.S. Bureau Agricultural Economist, Federal Bldg., Orlando, Fla.

1. Estimated on basis of .588 gals. of concentrate per 1-3/5 bu. box.
2. Includes Government Purchases - 65° Brix - 1,832,245 gals. in 1942-43 and 1,232,742 gals. in 1943-44 season.

The original source of most information for Florida was the Florida Canners Association.

GROWTH IN OUTPUT OF FROZEN CONCENTRATED CITRUS JUICES

From The Fruit Situation, U.S.D.A., June, 1950

Started on a small scale in 1945-46, production of frozen concentrated orange juice has since increased rapidly to become a major outlet for oranges. The early success achieved with oranges has led to the more recent manufacture of frozen concentrated grapefruit juice, blended orange and grapefruit juice, and even lemonade. Among non-citrus juices, frozen concentrated grape juice is also being manufactured commercially. Experiments are being carried on with other fruit juices.

Commercial manufacture of frozen concentrated orange juice began in Florida in 1945-46, when about 226,000 gallons of 4 to 1 concentrate were produced (see accompanying table). Production in this State more than doubled in 1946-47. The orange concentrate made in these two seasons was distributed largely thru the hotel, restaurant, and soda fountain trades, where response was so favorable as to point to its widespread use by household consumers.

Frozen Concentrated Citrus Juices: Production in Florida
and California-Arizona, 1945-46 to 1949-50

Season	Florida (Gals.)	Calif.-Ariz. (Gals.)	Total Gals.
Orange Juice			
1945-46	225,684	0	225,684
1946-47	559,309	0	559,309
1947-48	1,935,868	437,376	2,373,244
1948-49	10,232,831	1,963,035	12,195,866
1949-50*	21,419,802		
Grapefruit Juice			
1947-48	402	0	402
1948-49	116,123	0	116,123
1949-50*	1,582,274	0	
Orange-Grapefruit Blend			
1948-49	111,836	0	111,836
1949-50*	1,290,085		

* Season up to and including June 17, 1950. Florida pack only.

Production of orange concentrate in California did not get started until 1947-48, and the combined output of this State and Florida more than quadrupled that of Florida in 1946-47. Output again expanded greatly in 1948-49, amounting to more than five times that of the preceding season. Of the 12.2 million gallons produced in 1948-49, over 10 million were made in Florida and nearly 2 million in California and Arizona. The frozen orange concentrate manufactured during the 1947-48 and 1948-49 seasons was packed mainly in 6-ounce cans for sale by retail stores.

Manufacture of frozen concentrated orange juice in Florida in the 1949-50 season, now about completed, is more than double the 1948-49 output. Thru June 17 this season over 21 million gallons were produced in that State. Production in California and Arizona, drawing from the Valencia crop, will run thru the summer and also may double the preceding year's output.

Production of frozen citrus concentrate was extended to grapefruit juice in 1947-48, when 402 gallons were made in Florida. In 1948-49 production was over 116,000 gallons, and in 1949-50 it again increased sharply to about 1,582,000 gallons. In 1948-49 nearly 112,000 gallons of frozen concentrated blended orange and grapefruit juice were made in Florida, and in 1949-50 output soared to about 1,290,000 gallons.

The amazing growth in output of frozen citrus concentrate over the past five years stands out as a record that can be matched by few other industries. Output during the fourth year of operation was more than 50 times that of the first year, and output during the fifth year probably will be about 100 times. In 1945-46, the first year of manufacture, frozen orange concentrate provided an outlet for about one-fifth of 1 percent of the orange crop of the United States. In 1948-49, the fourth year, it took about 10 million boxes of oranges or 10 percent of the crop. Canning took about 30 percent of the 1948-49 orange crop, and fresh use accounted for nearly 60 percent. This frozen concentrate outlet is expected to take about 20

GROWTH IN OUTPUT OF FROZEN CONCENTRATED CITRUS JUICES (Cont'd.)

percent of the 1949-50 orange crop and about 5 percent of the grapefruit crop. With the 1949-50 orange season in Florida nearly completed in mid-June, frozen orange concentrate took about 31 percent of the Florida oranges, canning about 29 percent and fresh use about 40 percent. Of the 1948-49 crop in Florida, these three uses took 14, 32, and 54 percent, respectively.

In 1948-49, the last full season of production, the 12 million gallons of 4 to 1 frozen orange concentrate were equivalent to about 48 million gallons of single-strength orange juice, or about 14 million cases of 24 No. 2 cans. In the same season, the canned pack of orange juice amounted to about 19 million cases of 24 No. 2 cans, that of blended orange and grapefruit juice to 11 million cases, and that of grapefruit juice to 14 million cases.

Although part of the increasing output of frozen concentrated citrus juices has been utilized in filling the broadening channels of the distributive trade, most of the production has quickly moved into consumption. Per capita consumption of frozen orange concentrate during the 1948-49 season was nearly 3 pounds, single-strength basis. In the same season, per capita consumption of canned single-strength orange juice was about 4 pounds, and that of all canned citrus juices combined was about 10.7 pounds. The increase in consumption of the frozen orange concentrate in the 1948-49 season about offset a decrease in canned citrus juices.

With the growth in output and popularity of the frozen citrus concentrate, distribution of the product has become more widespread. A nationwide survey conducted in 1949 by Industrial Surveys Co., Inc., for the United States Department of Agriculture revealed that frozen concentrated orange juice was being handled by a sharply increasing percentage of retail stores. Of the stores surveyed about 17 percent carried the product in April, 24 percent in August, and 31 percent in November, 1949. In contrast, 84 percent of the stores carried canned orange juice in November 1949. This survey showed that the frozen orange concentrate was least available in stores doing a relatively small volume of business, in stores located in small cities and towns, and in stores in the South. But even among such stores, the percentage carrying the frozen orange concentrate doubled during 1949.

More than twice as many household consumers purchased frozen concentrated orange juice in April 1950 than in April 1949, according to a survey of a national sample of household consumers conducted by the above company. The proportion (14 percent) of consumers who bought the product in April 1950 was the highest so far recorded. Such consumers were reported to have paid an average of 27.8 cents per 6-ounce can, compared with 24.2 cents in April 1949. Diluted to single strength, the juice cost a little over 1 cent per ounce, a cost in line with that of other fruit juices.

Frozen concentrated citrus juice is manufactured by a process developed by the Florida Citrus Commission and the United States Department of Agriculture. In making the orange product, for example, fresh orange juice is passed thru a low temperature, high vacuum evaporating system, which moves enough water to reduce the juice to about one-sixth its original volume. This product is then mixed with about half as much fresh juice, giving a 4 to 1 concentrate (42° Brix). The fresh juice tends to restore the original fresh flavor. The concentrate is then chilled to a slush, sealed in cans, and frozen to zero or lower. It is stored at zero until sold. The exact process of manufacture varies with the sugar-acid ratio, percentage solids in the juice, and other factors. In preparing the concentrate for the table, it is mixed with three times as much cold water, which brings it back to single strength. In this form, it cannot easily be distinguished, if at all, from fresh orange juice.

The astounding growth of the frozen orange concentrate industry is the result largely of the favorable reception accorded the new product by consumers. The ease and quickness with which the new juice could be prepared for consumption and its fresh-like flavor together with prices in line with those of other fruit juices rapidly won it a place on the breakfast menu. On the production end, the cost of tin cans was less than one-fourth the cost of packing an equivalent amount of single-strength juice in 18-ounce cans. Less storage space was required and the smaller

GROWTH IN OUTPUT OF FROZEN CONCENTRATED CITRUS JUICE (Cont'd.)

volume could be transported at a considerable saving. Expansion in production, distribution, and hence consumption has grown with the construction of new concentrating plants, installation of frozen food cabinets in retail stores, and more and better refrigerators in homes. For the same reasons, further expansion in production and consumption seems likely.

With increased plant capacity, production in Florida reached a peak weekly output of more than 1.3 million gallons of frozen orange concentrate in the 1949-50 season. Additional plants will be available in California this summer to process Valencia oranges, and the first plant in Texas will be ready next winter to handle Texas citrus fruits. However, the period of rapid growth in the industry may soon be over, leaving the frozen citrus concentrate firmly established as an important outlet for citrus fruits. (END)

PROCESSING FLORIDA CITRUS - BY MONTHS - SEASON 1949-50

(Juices, Sections and Concentrates)

Standard 1-3/5 Bushel Boxes of Fresh Fruit Used

Month	Oranges		Grapefruit		Tangerines	
	Boxes	Carloads	Boxes	Carloads	Boxes	Carloads
September	-	-	10,821	22	-	-
October	117,887	236	80,171	160	-	-
November	2,528,078	5,056	575,629	1,151	24,227	48
December	6,666,586	13,333	1,404,349	2,809	255,443	511
January	7,022,059	14,044	2,937,417	5,875	543,130	1,086
February	4,422,090	8,844	2,934,928	5,870	604,920	1,210
March	2,838,201	5,676	2,413,102	4,826	166,752	334
April	3,968,732	7,938	1,037,713	2,075	448	1
May	5,003,463	10,007	1,049,642	2,099	-	-
June	2,067,625	4,135	1,005,117	2,010	-	-
July	23,421	47	37,311	75	-	-
Total Boxes	34,658,142		13,486,200		1,594,920	
Total Carloads*		69,316		26,972		3,190

*Converted on basis of 500 boxes to carload.

FREIGHT RATES OF CITRUS PER BOX TO AUCTION MARKETS

(Prepared by Florida Citrus Exchange in Tampa)

Auction Markets	Oranges			Grapefruit			Tangerines		
	Rate	Cars	Per Box	Rate	Cars	Per Box	Rate	Cars	Per Box
New York, Baltimore, Philadelphia	98.02	2420	$1.02	98.02	1660	$1.02	98.02	390	$1.02
Boston	114.95	213	1.18	112.05	97	1.15	114.12	8	1.17
Cincinnati	105.09	164	1.08	93.79	45	.97	101.70	30	1.04
Cleveland	120.90	335	1.24	107.90	117	1.11	117.00	83	1.20
Detroit	122.76	291	1.27	109.56	87	1.13	118.80	74	1.22
Pittsburgh	119.97	134	1.23	107.07	29	1.10	116.10	37	1.19
St. Louis	115.32	134	1.18	102.92	11	1.07	111.60	18	1.15
Chicago	98.58	151	1.02	98.77	23	1.02	98.10	45	1.02
Total Cars		3842			2069			685	
Average All Auctions			1.08			1.04			1.08

Note: (1) Truck and boat auction receipts are not included.
(2) New York, Philadelphia and Baltimore rates were cheaper than in 1948-49 Season, account of water competition. Chicago cheaper due to truck competition.

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 23 YEARS

Records Estimates Season	Total Carloads Rail&Boat Shipped	Portion Carloads Shipped by Rail	With No. Rail Haul, Shipped by Boat(1)	Total Rail&Boat Shipments	Estimated Trucked out of Florida	Estimated Canned in Florida	Estimated Consumed(2) in Florida	Estimated Florida Production Utilized
ALL ORANGES	Carloads	Cars	Carloads	Boxes	Boxes	Boxes	Boxes	Total Boxes
1927-28	16,437	16,310	127	5,917,320	520,000	12,000	650,000	7,099,320
1928-29	32,428	31,988	440	11,674,080	975,000	38,000	1,062,500	13,749,580
1929-30(3)	21,816	21,635	181	7,489,633	65,000	40,000	780.000	8,374,633
1930-31	40,353	39,354	999	14,000,130	1,584,000	61,351	1,308,582	16,954,063
1931-32	25,725	24,054	1,671	9,904,145	1,486,480	36,362	1,122,000	12,548,987
1932-33	32,580	26,414	6,166	11,728,800	1,854,000	50,000	1,332,000	14,964,800
1933-34	31,799	18,291	13,508	12,401,563	2,322,000	61,433	1,386,000	16,170,996
1934-35	28,213	14,843	13,370	11,094,459	2,891,643	177,937	1,425,000	15,589,039
1935-36	29,746	17,403	12,343	11,714,588	2,510,000	140,000	1,500,000	15,864,588
1936-37	37,208	23,382	13,826	14,580,603	2,560,000	620,185	1,700,000	19,460,788
1937-38	46,061	31,258	14,803	18,005,497	3,442,000	1,055,399	1,800,000	24,302,896
1938-39	55,697	37,380	18,317	21,528,758	5,175,741	1,186,689	2,000,000	29,900,000
1939-40	38,285	29,286	8,999	14,718,568	4,376,000	4,170,134	1,800,000	25,064,702
1940-41	42,597	31,402	11,195	16,609,828	5,726,000	3,941,261	2,475,000	28,752,089
1941-42	41,598	40,443	1,155	16,853,616	4,099,200	4,197,299	2,049,885	27,200,000
1942-43	52,287	52,287	None	25,799,784	2,715,823	6,438,274	2,246,300	37,200,181
1943-44	61,160	61,160	None	30,511,378	2,155,200	11,010,841	2,522,581	46,200,000
1944-45	49,507	49,507	None	24,526,000	1,456,400	14,344,000	2,473,600	42,800,000
1945-46	52,665	52,589	76	26,007,841	2,054,000	19,219,412	2,518,747	49,800,000
1946-47	54,421	51,513	2,908	26,787,122	3,509,600	19,825,485	2,677,793	52,800,000
1947-48	39,616	39,616	-	19,659,370	5,707,300	30,376,340	2,656,990	58,400,000
1948-49	33,257	33,222	35	16,446,857	12,142,400	26,851,646	2,859,097	58,300,000
1949-50	22,304	19,213	3,091	10,710,718	10,283,515	34,657,323	2,848,444	58,500,000

NOTES:

(1) Domestic boat in coastwise trade.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(3) Fruit fly year when production harvest and shipments restricted. Many trees cut down and many so-called host plants destroyed by the Federal agencies.

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 23 YEARS

Records & Estimates Season ALL ORANGES	Cost of Produc-tion (2) Before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated Net Returns to Growers Rail&Boat Shipments Per Box	Estimated Net Return (1) Rail & Boat Shipments Net Value	Estimated Net Return All Oranges Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Oranges Harvested and Used Gross Value
1927-28	$0.72	$1.30	$4.16	$2.14	$12,663,065	$13,905,825	$24,616,051	$26,804,051
1928-29	.72	1.28	2.12	.12	1,400,890	2,125,630	23,749,050	26,224,450
1929-30 (4)	.80	1.30	3.30	1.20	8,987,560	9,648,310	24,715,789	26,157,789
1930-31	.48	1.10	2.15	.57	7,980,074	8,826,500	30,100,280	32,738,844
1931-32	.60	.95	2.30	.75	7,428,109	8,857,319	22,779,534	26,455,041
1932-33	.47	.90	1.48	.10	1,172,880	2,129,300	17,858,624	20,446,424
1933-34	.46	.87	1.71	.38	4,712,594	6,842,686	21,206,673	25,752,219
1934-35	.45	.90	1.85	.50	5,547,228	8,246,123	20,524,749	26,352,066
1935-36	.45	.95	2.30	.90	10,543,129	14,058,129	26,943,552	33,349,552
1936-37	.42	.93	2.50	1.15	16,767,693	20,689,419	36,451,507	44,979,738
1937-38	.38	.88	1.56	.30	5,401,649	6,053,959	28,088,575	34,339,559
1938-39	.34	.84	1.43	.25	5,382,190	6,035,321	30,786,124	39,687,098
1939-40	.42	.91	1.62	.29	4,268,365	4,214,941	23,843,970	33,663,815
1940-41	.40	.87	1.63	.36	5,979,538	9,126,658	27,074,020	42,442,109
1941-42	.44	.90	2.10	.76	12,808,748	18,918,916	35,392,593	51,904,503
1942-43	.40	1.01	2.97	1.56	40,247,695	53,904,492	76,625,358	101,089,208
1943-44	.50	1.25	3.10	1.35	41,190,360	60,688,332	94,585,272	129,867,001
1944-45	.50	1.21	3.50	1.79	43,901,540	74,132,856	85,841,000	135,653,600
1945-46	.48	1.24	3.55	1.83	47,414,930	91,767,533	91,979,783	161,818,586
1946-47 *	.53 (3)	1.25	2.62	.84	25,320,348 RTB	26,385,989	78,975,370RTB	101,927,124
1947-48 *	.50	1.32	2.10	.28	7,095,000 "	8,492,216	53,212,501 "	82,619,360
1948-49 *	.50	1.40	2.80	.90	25,730,332 "	45,510,967	80,049,920 "	127,743,648
1949-50 *	.52	1.38	3.55	1.65	34,640,484 "	88,387,669	74,529,527 "	166,271,399

NOTES:

* Truck Shipments included with Rail & Boat, their FOB prices being same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau equivalent "On Tree" average price for rail and boat shipments. This is not necessarily the same as U.S. Dept.of Agri. "On Tree" price.
(3) An allowance was made for unusual cost in grove protection in 1946-47 season. (February freeze.)
(4) Fruit fly year when production, harvest and shipments restricted.

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 23 YEARS

Records Estimates Season GRAPE-FRUIT	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul Shipped by Boat(1) Carloads	Total Rail&Boat Shipments Boxes	Estimated Trucked out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(2) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	20,012	19,953	59	7,204,320	240,000	588,000	300,000	8,332,320
1928-29	28,294	28,091	203	10,185,840	450,000	1,489,320	675,000	12,800,160
1929-30(3)	16,415	16,354	61	6,341,913	30,000	1,670,000	360,000	8,401,913
1930-31	30,462	29,809	653	11,841,987	792,000	2,892,705	654,291	16,180,983
1931-32	20,315	17,865	2,450	7,821,313	897,940	930,171	782,000	10,431,424
1932-33	19,639	15,293	4,346	7,266,430	980,500	2,750,000	928,700	11,925,630
1933-34	17,514	11,340	6,174	6,981,916	684,000	2,605,964	841,320	11,113,200
1934-35	19,218	10,418	8,800	7,577,053	1,187,011	5,603,996	875,000	15,243,060
1935-36	15,196	8,838	6,358	5,936,067	1,028,000	3,760,000	780,000	11,504,067
1936-37	23,786	16,142	7,644	9,352,859	1,283,600	6,685,327	800,000	18,121,786
1937-38	16,952	11,511	5,441	6,602,063	1,233,600	5,793,097	750,000	14,378,760
1938-39	25,047	17,051	7,996	9,844,986	1,472,277	8,395,348	950,000	20,662,611
1939-40	12,974	9,160	3,814	5,110,591	1,000,000	8,800,274	740,000	15,650,865
1940-41	19,962	14,478	5,484	7,956,475	1,559,600	13,870,966	1,000,000	24,387,041
1941-42	16,813	16,298	515	6,856,510	1,042,000	10,142,575	1,058,915	19,100,000
1942-43	16,529	16,529	None	8,009,134	612,807	17,584,025	1,094,150	27,300,116
1943-44	18,041	18,041	None	8,984,800	355,600	20,445,648	1,213,952	31,000,000
1944-45	11,742	11,742	None	5,860,000	205,200	15,136,000	1,098,800	22,300,000
1945-46	16,554	16,542	12	8,306,504	340,400	22,136,149	1,216,947	32,000,000
1946-47	17,800	16,363	1,437	8,878,857	558,000	15,864,346	1,098,797	26,400,000
1947-48	14,776	14,776	-	7,497,100	1,143,367	19,448,586	1,210,947	29,300,000
1948-49	17,738	17,738	-	8,826,811	3,483,200	16,305,820	1,584,169	30,200,000
1949-50	11,710	10,048	1,662	5,792,144	3,565,121	13,486,200	1,356,535	24,200,000

NOTES:

(1) Domestic Boat Shipments in coast-wise trade.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intra-state truck shipments, etc.

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 23 YEARS

Records & Estimates Season GRAPE-FRUIT	Cost of Production (2) Before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated Net Returns to Growers Rail&Boat Shipments Per Box	Estimated Net Return (1) Rail&Boat Shipments Net Value	Estimated Net Return All Grapefruit Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Grapefruit Harvested and Used Gross Value
1927-28	$0.52	$1.25	$3.28	$1.51	$10,878,523	$11,555,563	$23,630,170	$25,018,170
1928-29	.52	1.25	2.02	.25	2,546,460	3,078,488	20,575,397	22,557,557
1929-30 (4)	.60	1.25	3.05	1.20	7,610,296	8,293,796	19,342,835	21,479,835
1930-31	.36	1.05	1.50	.09	1,065,779	1,199,727	17,762,980	20,366,366
1931-32	.40	.85	1.50	.25	1,955,326	2,012,557	11,731,970	13,522,967
1932-33	.38	.85	1.16	-.07	- 508,650	-1,285,321	8,429,059	10,170,789
1933-34	.39	.83	1.51	.29	2,024,756	2,591,790	10,542,693	13,296,632
1934-35	.37	.84	1.29	.08	606,164	199,847	9,774,397	13,409,984
1935-36	.39	.87	1.87	.61	3,621,001	5,269,881	11,100,445	15,936,845
1936-37	.30	.83	1.48	.35	3,273,500	4,448,605	13,842,231	19,731,121
1937-38	.36	.82	1.53	.35	2,310,722	2,613,485	10,101,156	15,063,803
1938-39	.30	.74	1.04	Zero	Zero	-2,099,526	10,238,785	14,688,400
1939-40	.40	.82	1.42	.20	1,022,120	- 146,121	7,257,052	12,289,942
1940-41	.35	.74	1.21	.12	954,777	- 514,241	9,627,335	17,335,152
1941-42	.40	.80	1.80	.60	4,113,906	6,439,418	12,341,718	22,849,773
1942-43	.35	.88	2.33	1.10	8,810,047	18,156,816	18,661,282	40,527,501
1943-44	.40	1.07	2.47	1.00	8,984,800	28,461,544	22,192,456	56,780,588
1944-45	.40	1.07	3.00	1.53	8,965,800	30,343,516	17,580,000	49,962,240
1945-46	.34	1.10	2.65	1.21	10,039,012	24,983,418	21,986,266	56,604,216
1946-47 *	.37(3)	1.08	2.18	.73	6,847,915 RTB	6,883,612	20,449,939 RTB	32,971,887
1947-48 *	.35	1.09	1.80	.36	3,107,194 "	- 342,474	15,535,969 "	24,102,874
1948-49 *	.35	1.18	2.35	.82	10,094,209 "	10,009,553	28,928,526 "	41,549,598(5)
1949-50 *	.37	1.13	3.41	1.91	17,872,376 "	36,726,607	31,908,274 "	61,332,727

NOTES:

* Truck Shipments included with Rail & Boat, their FOB prices being same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(3) An allowance was made for unusual cost in grove protection in 1946-47 season.

(4) Fruit fly year when production, harvest and shipments restricted.

(5) Takes into account a loss of $1,304,466 on Grapefruit sold to canners.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 23 YEARS

Records Estimates Season TAN-GERINES	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul Shipped by Boat(1) Carloads	Total Rail and Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Canned in Florida Boxes	Estimated Consumed(2) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1927-28	1,427	1,417	10	513,720	40,000		50,000	603,720
1928-29	2,951	2,917	34	1,062,360	75,000		212,500	1,349,860
1929-30(3)	1,254	1,242	12	383,054	5,000		60,000	448,054
1930-31	3,830	3,786	44	1,387,828	264,000		218,097	1,869,925
1931-32	3,195	3,077	118	1,188,707	141,100		136,000	1,465,807
1932-33	3,282	2,749	533	1,181,520	175,680	No record	162,000	1,519,200
1933-34	3,998	2,657	1,341	1,501,411	243,000	made of the	247,680	1,992,091
1934-35	3,676	2,199	1,477	1,461,049	267,706	very few	275,000	2,003,755
1935-36	3,974	2,549	1,425	1,581,397	232,000	Tangerines	280,000	2,093,397
1936-37	5,885	4,046	1,839	2,288,234	430,000	processed	300,000	3,018,634
1937-38	4,396	3,098	1,298	1,709,973	298,000	prior to	250,000	2,257,973
1938-39	6,323	4,502	1,821	2,553,332	478,541	1944-45	350,000	3,381,873
1939-40	4,051	3,315	736	1,620,345	437,200	Season	200,000	2,257,545
1940-41	4,513	3,449	1,064	1,791,824	434,800		525,000	2,751,624
1941-42	3,534	3,387	147	1,432,144	334,800		333,056	2,100,000
1942-43	7,382	7,382	None	3,407,401	400,048		392,700	4,200,149
1943-44	6,179	6,170	None	2,818,782	382,800		398,418	3,600,000
1944-45	6,847	6,847	None	3,149,000	327,600	3,000	420,400	3,900,000
1945-46	5,728	5,728	None	2,809,372	384,000	515,600	491,028	4,200,000
1946-47	4,545	4,323	222	2,058,146	438,400	930,751	472,703	3,900,000
1947-48	3,610	3,610	-	1,699,815	667,845	598,505	433,835	3,400,000 A
1948-49	4,024	4,024	-	1,827,056	1,080,800	999,354	492,790	4,400,000
1949-50	3,321	2,912	409	1,500,955	1,376,592	1,594,928	527,525	5,000,000

NOTES:

(A) Does not include 600,000 boxes abandoned for marketing reasons. . Abandonment, if any, for prior years not shown here. No abandonment of any citrus in 1948-49 season.

(1) Domestic Boat Shipments in coast-wide trade.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 23 YEARS

Records & Estimates Season TANGERINES	Cost of Production (2) before Picked Per Box	Cost of Picking Hauling Packing Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return(1) Rail & Boat Shipments Net Value	Estimated Net Return All Tangerines Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Tangerines Harvested and Used Gross Value
1927-28	$0.81	$1.70	$5.28	$2.77	$1,423,004	$1,519,104	$ 2,712,442	$ 2,892,442
1928-29	.81	1.70	2.90	.39	414,320	493,945	3,080,844	3,435,844
1929-30(3)	.90	1.70	3.50	.90	344,748	378,498	1,340,689	1,459,689
1930-31	.54	1.50	1.95	-.09	- 124,905	11,345	2,706,265	3,188,362
1931-32	.75	1.25	2.05	.05	59,435	73,290	2,436,849	2,713,949
1932-33	.56	1.16	1.42	-.30	- 354,456	- 281,513	1,677,758	1,999,238
1933-34	.56	1.05	1.80	.19	285,268	574,535	2,702,540	3,352,340
1934-35	.55	.95	1.66	.16	235,768	409,965	2,425,341	3,035,702
1935-36	.55	1.10	2.00	.35	553,489	883,889	3,162,794	3,902,794
1936-37	.50	1.15	1.45	-.20	- 457,646	- 558,726	3,317,939	4,127,899
1937-38	.52	1.16	1.86	.18	307,795	320,975	3,180,550	3,881,990
1938-39	.45	.95	1.34	-.06	- 153,200	- 242,481	3,421,465	4,291,433
1939-40	.50	1.06	2.00	.44	712,952	945,972	3,240,690	4,411,370
1940-41	.50	1.08	1.68	.10	179,182	219,216	3,010,264	4,415,434
1941-42	.58	1.16	2.85	1.11	1,589,680	2,280,955	4,081,610	5,818,344
1942-43	.40	1.35	2.79	1.03	3,509,623	4,223,464	9,472,575	11,436,280
1943-44	.65	1.68	3.70	1.37	3,861,731	4,884,190	10,429,493	13,041,107
1944-45	.65	1.68	4.25	1.92	6,046,080	7,437,192	13,383,250	16,296,690
1945-46	.64	1.71	4.80	2.45	6,882,962	8,800,902	13,484,986	17,807,898
1946-47 *	.68	1.72	3.75	1.35	3,370,337 RTB	3,522,030	9,362,048 RTB	11,666,569
1947-48 *	.68	1.82	2.90	.40	947,064 "	696,420	6,866,214 "	8,203,662
1948-49 *	.68	1.85	3.70	1.17	3,402,191 "	3,259,910	10,759,067 "	12,894,256(4)
1949-50 *	.70	1.85	3.85	1.30	3,740,811 "	3,991,182	11,078,556 "	14,360,329(4)

NOTES:

* Truck shipments included with Rail & Boat, their FOB prices being same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting for taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated. This estimated "On Tree" price is not necessarily the same as the U.S.D.A. "On Tree" price.

(3) Fruit fly year when production, harvest and shipments restricted.

(4) Takes into account a loss of $669,567 on tangerines sold to canners in 1948-49 and $366,833 in 1949-50.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 23 YEARS

Records Estimates Season	Total Carloads Rail&Boat Shipped	Portion Carloads Shipped by Rail	With No. Rail Haul Shipped by Boat(1)	Total Rail & Boat Shipments	Estimated Trucked Out of Florida	Estimated Canned in Florida	Estimated Consumed(2) in Florida	Estimated Florida Production Utilized
ALL CITRUS	Carloads	Cars	Carloads	Boxes	Boxes	Boxes	Boxes	Total Boxes
1927-28	37,876	37,680	196	13,635,360	800,000	600,000	1,000,000	16,035,360
1928-29	63,673	62,996	677	22,922,280	1,500,000	1,527,320	1,950,000	27,899,600
1929-30(3)	39,485	39,231	254	14,214,500	100,000	1,710,000	1,200,000	17,224,600
1930-31	74,645	72,949	1,696	27,229,945	2,640,000	2,954,056	2,180,970	35,004,971
1931-32	49,235	44,996	4,239	18,914,165	2,525,520	966,533	2,040,000	24,446,218
1932-33	55,501	44,456	11,045	20,176,750	3,010,180	2,800,000	2,422,700	28,409,630
1933-34	53,311	32,288	21,023	20,884,890	3,249,000	2,667,397	2,475,000	29,276,287
1934-35	51,107	27,460	23,647	20,132,561	4,346,360	5,781,933	2,575,000	32,835,854
1935-36	48,916	28,790	20,126	19,232,052	3,770,000	3,900,000	2,560,000	29,462,052
1936-37	66,879	43,570	23,309	26,221,696	4,274,000	7,305,512	2,800,000	40,601,208
1937-38	67,409	45,867	21,542	26,317,533	4,973,600	6,848,496	2,800,000	40,939,629
1938-39	87,067	58,933	28,134	33,927,076	7,126,559	9,582,037	3,300,000	56,447,995
1939-40	55,310	41,761	13,549	21,449,504	5,813,200	12,970,408	2,740,000	42,973,112
1940-41	67,072	49,329	17,743	26,358,127	7,720,400	17,812,227	4,000,000	55,890,754
1941-42	61,945	60,128	1,817	25,142,270	5,476,000	14,339,874	3,441,856	48,400,000
1942-43	76,198	76,198	None	37,216,319	3,728,678	24,022,299	3,733,150	68,700,446
1943-44	85,380	85,380	None	42,314,960	2,893,600	31,456,489	4,134,951	80,800,000
1944-45	68,096	68,096	None	33,535,000	1,989,200	29,483,000	3,992,800	69,000,000
1945-46	74,947	74,859	88	39,902,117	2,778,400	41,871,161	4,226,722	86,000,000
1946-47	76,766	72,199	4,567	37,724,125	4,506,000	36,620,582	4,249,293	83,100,000
1947-48	58,002	58,002	-	28,772,771	7,518,512	50,423,431	4,301,772	91,100,000
1948-49	55,019	54,984	35	27,100,724	16,706,400	44,156,820	4,936,056	92,900,000
1949-50	37,335	32,173	5,162	18,003,817	15,225,228	49,738,451	4,732,504	87,700,000

NOTES:

(1) Domestic Boat Shipments in Coastwise Trade.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 23 YEARS

Records & Estimates Season ALL CITRUS	Cost of Production(2) Before Picked Per Box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return (1) Rail & Boat Shipments Net Value		Estimated Net Return All Citrus Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value		Estimated Gross Return All Citrus Harvested and Used Gross Value
1927-28	$0.63	$1.28	$3.74	$1.83	$24,964,592		$26,980,492	$50,958,663		$54,714,663
1928-29	.64	1.25	2.08	.19	4,361,670		5,698,063	47,405,291		52,217,851
1929-30(3)	.71	1.29	3.19	1.19	16,942,604		18,320,604	45,399,313		49,097,313
1930-31	.43	1.10	1.86	.33	8,920,948		10,037,572	50,569,525		56,293,572
1931-32	.53	.92	1.95	.50	9,442,872		10,943,166	36,948,353		42,691,957
1932-33	.45	.90	1.36	.01½	309,774		562,466	27,465,441		32,616,451
1933-34	.44	.87	1.65	.33½	7,022,618		10,009,011	34,451,906		42,401,191
1934-35	.43	.88	1.63	.32	6,387,160		8,855,935	32,724,487		42,797,752
1935-36	.44	.94	2.14	.76	14,717,619		20,211,899	41,206,791		53,189,191
1936-37	.37	.92	2.04	.75	19,583,547		24,579,298	53,611,677		68,838,758
1937-38	.38	.88	1.57	.30½	8,020,166		8,988,419	41,370,281		53,285,352
1938-39	.34	.82	1.31	.15	5,228,990		3,693,314	44,446,374		58,646,931
1939-40	.42	.90	1.60	.28	6,003,437		5,014,792	34,341,712		50,365,127
1940-41	.39	.85	1.51	.27	7,113,479		8,831,633	39,711,619		64,192,695
1941-42	.43	.89	2.06	.74	18,512,334		27,639,289	51,815,921		80,572,620
1942-43	.39	1.01	2.81	1.41	52,567,333		76,284,772	104,759,215		153,052,989
1943-44	.49	1.24	3.01	1.28	54,036,891		94,032,066	127,207,221		199,688,696
1944-45	.483	1.25	3.483	1.75	58,913,420		111,913,564	116,804,250		201,912,530
1945-46	.46	1.25	3.44	1.73	64,336,904		125,551,850	127,451,035		236,230,700
1946-47 *	.50	1.24	2.59	.85	35,538,600	RTB	36,791,631	108,787,717	RTB	146,565,580
1947-48 *	.48	1.29	2.08	.31	11,149,258	"	8,846,162	75,614,684	"	114,925,896
1948-49 *	.47	1.37	2.74	.90	39,226,732	"	58,780,430	119,737,513	"	182,187,502
1949-50 *	.49	1.35	3.54	1.70	56,253,671	"	129,105,458	117,516,357	"	241,964,455

NOTES:

* Truck Shipments included with Rail & Boat, their FOB prices being the same.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting for taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA AUCTION SALES, 1932-33 - 1949-50

Furnished through courtesy of the Statistical Department
Florida Citrus Exchange, Tampa, Fla.

ORANGES

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1932-33	Cars	9238	2868	1419	579	553	921	273	614	256	-	16721
	Average	$2.43	2.45	2.53	2.35	2.40	2.55	2.30	2.30	2.46	-	2.44
1933-34	Cars	7613	2632	1436	515	526	894	266	495	267	142	14786
	Average	$2.75	2.62	2.69	2.54	2.63	2.67	2.46	2.47	2.69	2.88	2.70
1934-35	Cars	8243	2720	1419	511	578	1070	258	553	280	258	15890
	Average	$2.61	2.47	2.58	2.44	2.53	2.59	2.34	2.35	2.47	2.44	2.56
1935-36	Cars	7503	2624	1561	340	559	878	249	555	271	240	14780
	Average	$3.02	2.93	3.02	2.95	3.04	3.15	2.72	2.87	3.08	2.82	3.00
1936-37	Cars	9112	3164	1657	429	824	1080	264	708	412	282	17932
	Average	$3.23	3.15	3.28	3.12	3.21	3.33	3.01	3.12	3.27	2.98	3.21
1937-38	Cars	10228	3376	1849	495	298	1394	413	1181	550	302	20686
	Average	$2.26	2.20	2.24	2.18	2.28	2.39	2.05	2.16	2.26	1.98	2.24
1938-39	Cars	12440	4049	2132	694	1091	1639	511	1555	717	396	25224
	Average	$2.10	1.99	2.16	2.11	2.20	2.26	2.01	2.01	2.16	1.94	2.09
1939-40	Cars	8758	2908	1290	364	589	1012	318	1031	393	173	16836
	Average	$2.43	2.25	2.47	2.16	2.31	2.41	2.09	2.05	2.25	2.23	2.35
1940-41	Cars	10089	3320	1385	426	647	1020	312	1077	434	261	18971
	Average	$2.37	2.26	2.45	2.31	2.44	2.45	2.25	2.18	2.42	2.22	2.35
1941-42	Cars	9053	3064	1377	337	568	863	204	1002	353	312	17133
	Average	$2.86	2.76	2.90	2.73	2.91	2.88	2.70	2.64	2.88	2.77	2.83
1942-43	Cars	6771	2330	851	439	483	939	359	742	412	277	13603
	Average	$3.85	3.70	3.82	3.72	3.85	3.77	3.70	3.55	3.87	3.56	3.79
1943-44	Cars	6239	2257	678	522	488	815	476	516	658	200	12849
	Average	$3.98	3.82	4.02	3.86	3.86	3.89	3.67	3.65	3.85	3.71	3.90
1944-45	Cars	4765	1651	425	293	264	532	271	299	365	157	9022
	Average	$4.62	4.38	4.47	4.27	4.34	4.29	4.17	4.02	4.37	4.39	4.48
1945-46	Cars	4510	1478	363	237	197	345	196	372	262	308	8268
	Average	$4.72	4.44	4.70	4.48	4.43	4.39	4.24	4.17	4.43	4.45	4.58
1946-47	Cars	7824	1930	870	420	639	921	430	801	562	373	14770
	Average	$3.60	3.35	3.62	3.29	3.47	3.38	3.27	3.25	3.47	3.35	3.50
1947-48	Cars	6856	2550	867	342	534	608	249	689	479	234	13406
	Average	$3.40	3.16	3.34	3.12	3.19	3.08	2.91	3.01	3.12	2.96	3.27
1948-49	Cars	6512	2377	772	393	544	818	416	571	593	137	13133
	Average	$4.35	4.04	4.35	4.17	4.17	4.14	4.10	3.86	4.23	3.96	4.23
1949-50	Cars	5364	1727	516	244	401	635	278	421	448	31	10065
	Average	$5.10	4.85	5.10	4.65	4.78	4.71	4.44	4.46	4.85	4.23	4.95

FLORIDA AUCTION SALES, 1932-33 - 1949-50 (Cont'd.)

GRAPEFRUIT

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1932-33	Cars	5138	1266	892	429	433	738	228	409	330	-	9863
	Average	$2.05	1.95	2.06	2.02	2.21	2.29	1.96	2.01	2.31	-	2.06
1933-34	Cars	3948	1129	696	310	388	684	221	370	298	41	8085
	Average	$2.41	2.25	2.40	2.38	2.39	2.55	2.37	2.29	2.51	2.42	2.39
1934-35	Cars	4893	1326	898	389	403	721	200	444	350	135	9759
	Average	$2.04	1.81	1.93	1.94	2.09	2.19	2.05	1.92	2.10	1.86	2.00
1935-36	Cars	3928	1072	872	262	396	395	132	340	251	117	7765
	Average	$2.67	2.38	2.49	2.40	2.54	2.68	2.40	2.32	2.62	2.28	2.57
1936-37	Cars	5376	1650	956	274	415	494	151	423	307	151	10197
	Average	$2.24	2.06	2.22	2.14	2.29	2.58	2.53	2.24	2.41	2.12	2.23
1937-38	Cars	4881	1244	814	190	313	353	72	342	219	127	8555
	Average	$2.20	2.06	2.13	2.05	2.11	2.28	2.16	2.09	2.21	1.88	2.16
1938-39	Cars	6389	1429	1020	329	384	361	118	432	277	187	10926
	Average	$1.75	1.57	1.73	1.68	1.77	1.95	1.85	1.66	1.80	1.46	1.72
1939-40	Cars	4765	1153	633	181	141	182	62	241	140	85	7483
	Average	$2.21	1.92	2.10	1.92	2.11	2.29	2.10	1.98	2.06	1.73	2.13
1940-41	Cars	5035	1334	805	249	256	313	109	416	215	91	8823
	Average	$1.96	1.75	1.95	1.76	1.92	2.00	1.77	1.74	1.91	1.61	1.91
1941-42	Cars	4519	1166	712	125	136	208	51	222	98	88	7325
	Average	$2.55	2.36	2.55	2.33	2.61	2.83	2.73	2.33	2.64	2.60	2.52
1942-43	Cars	3411	967	487	142	96	114	19	201	85	82	5604
	Average	$3.18	2.97	3.21	2.90	2.90	3.17	2.96	2.67	3.00	2.70	3.10
1943-44	Cars	2628	778	338	128	49	69	44	90	97	43	4264
	Average	$3.63	3.48	3.64	3.36	3.32	3.20	3.51	3.05	3.31	3.14	3.56
1944-45	Cars	2320	498	183	31	23	21	13	16	13	14	3132
	Average	$4.35	4.03	4.11	3.74	3.01	3.31	3.38	3.13	3.15	3.54	4.24
1945-46	Cars	3293	737	213	33	12	19	2	18	14	45	4386
	Average	$3.88	3.67	3.88	3.06	2.60	3.62	3.33	2.91	2.81	3.19	3.82
1946-47	Cars	4894	890	546	63	80	154	31	183	111	142	7094
	Average	$3.39	3.11	3.17	2.89	3.10	3.16	3.55	2.87	3.18	2.54	3.29
1947-48	Cars	4258	1260	456	73	85	106	34	158	92	138	6660
	Average	$3.22	2.82	2.89	2.55	2.99	2.92	2.97	2.54	3.03	2.31	3.07
1948-49	Cars	4406	1287	464	158	222	355	168	237	308	36	7641
	Average	$3.87	3.58	3.72	3.49	3.86	3.68	3.71	3.33	3.80	2.82	3.77
1949-50	Cars	3387	923	237	106	189	324	120	223	245	18	5772
	Average	$5.38	4.75	4.86	4.54	4.97	4.66	4.32	4.56	4.77	3.54	5.10

TANGERINES

(½ box basis)

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
1932-33	Cars	1308	375	157	95	108	180	58	102	73	-	2456
	Average	$1.28	1.20	1.28	1.23	1.21	1.22	1.14	1.09	1.22	-	1.24
1933-34	Cars	1134	433	144	142	114	179	67	96	71	1	2381
	Average	$1.21	1.15	1.17	1.25	1.24	1.21	1.21	1.15	1.22	1.48	1.20
1934-35	Cars	1071	356	132	136	71	155	66	108	71	31	2197
	Average	$1.18	1.10	1.12	1.25	1.27	1.25	1.26	1.20	1.28	1.22	1.18
1935-36	Cars	1124	365	157	139	116	217	54	113	87	26	2398
	Average	$1.35	1.32	1.30	1.40	1.42	1.36	1.32	1.34	1.41	1.23	1.35
1936-37	Cars	1557	572	196	210	193	306	103	138	116	33	3424
	Average	$1.12	1.03	1.05	1.19	1.09	1.14	1.10	1.08	1.16	.96	1.10
1937-38	Cars	1311	382	149	95	117	149	74	125	88	23	2513
	Average	$1.26	1.21	1.20	1.28	1.30	1.25	1.10	1.18	1.23	1.08	1.24
1938-39	Cars	1851	551	172	152	189	257	107	203	148	33	3663
	Average	$1.07	.92	.93	.95	.98	.97	.86	.91	.96	.79	1.00
1939-40	Cars	1192	345	66	65	104	142	48	115	57	9	2143
	Average	$1.37	1.34	1.41	1.37	1.47	1.45	1.31	1.27	1.34	1.33	1.37
1940-41	Cars	1425	454	109	77	154	195	59	149	82	13	2717
	Average	$1.23	1.16	1.19	1.07	1.20	1.22	1.09	1.12	1.14	1.06	1.19
1941-42	Cars	1152	359	78	39	106	135	38	105	48	25	2085
	Average	$1.86	1.75	1.75	1.65	1.82	1.66	1.52	1.58	1.76	1.50	1.79
1942-43	Cars	1485	670	143	108	188	303	101	193	151	57	3399
	Average	$1.82	1.84	1.62	1.81	1.86	1.81	1.66	1.80	1.74	1.53	1.80
1943-44	Cars	326	134	22	22	22	40	26	21	31	-	644
	Average	$2.16	2.28	2.27	2.32	2.37	2.27	2.36	2.26	2.40	-	2.23
1944-45	Cars	669	300	32	72	66	150	41	53	73	9	1465
	Average	$2.42	2.38	2.35	2.49	2.45	2.42	2.15	2.40	2.47	2.77	2.41
1945-46	Cars	1188	414	57	70	86	167	46	88	59	26	2201
	Average	$2.67	2.52	2.43	2.58	2.68	2.54	2.32	2.59	2.50	2.61	2.61
1946-47	Cars	1233	335	69	91	139	202	63	128	108	35	2403
	Average	$2.28	2.18	2.11	2.12	1.99	1.90	1.92	1.99	2.04	2.08	2.17
1947-48	Cars	943	433	69	77	147	193	63	120	140	24	2209
	Average	$2.09	2.01	1.87	1.81	1.88	1.91	1.70	1.81	1.73	1.92	1.98
1948-49	Cars	1345	516	86	79	132	230	65	108	163	13	2737
	Average	$2.75	2.48	2.51	2.36	2.39	2.24	2.24	2.09	2.36	1.96	2.55
1949-50	Cars	1279	452	51	71	140	248	53	78	171	7	2550
	Average	$2.74	2.62	2.53	2.48	2.62	2.44	2.32	2.30	2.51	2.60	2.63

ESTIMATED PRICES PAID BY CANNERS AND PROCESSORS 1941-1950

(Florida Citrus Delivered to Canner's Door)

	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Average
ORANGES	$	$	$	$	$	$	$	$	$	$	$	$	$
1941-42				.74	.93	.91	1.10	1.20	1.25	1.35	1.40		1.076
1942-43				1.50	1.25	1.48	1.76	2.00	2.40	2.45	2.50		1.70
1943-44		2.03	2.03	2.03	1.86	1.63	1.87	2.27	2.25	2.20	2.37	2.37	2.02
1944-45		1.98	1.98	1.93	2.18	2.49	2.74	3.11	3.25	3.06	3.06		2.60
1945-46	2.49	2.49	2.41	2.52	2.37	2.31	2.62	3.00	3.66	3.68	3.50		2.83
1946-47	1.33	1.33	1.00	.55	.55	.54	.69	1.17	1.16	1.08	.79	.79	.82
1947-48		.87	.87	.80	.80	1.09	.91	.70	.65	.51	.49	.49	.80
1948-49	.46	.46	.53	.73	.96	1.20	1.70	2.20	3.10	3.40	3.00	LCL	1.51
1949-50		1.70	1.20	1.53	2.36	3.10	3.30	2.77	2.60	2.55	2.55		2.38
GRAPEFRUIT													
1941-42				.69	.67	.64	.76	.82	.80	.77	.77		.706
1942-43				.92	.96	1.08	1.20	1.32	1.47	1.50	1.50		1.05
1943-44		1.37	1.37	1.45	1.44	1.40	1.50	1.74	1.76	1.66	1.67	1.67	1.53
1944-45		1.83	1.83	1.83	1.85	2.01	2.17	2.19	2.20	1.92			1.91
1945-46	1.30	1.30	1.53	1.51	1.29	1.23	1.22	1.29	1.67	1.76	1.77	1.77	1.39
1946-47	1.18	1.19	1.18	.77	.60	.52	.53	.53	.44	.39	.40	.40	.65
1947-48		.51	.51	.44	.40	.36	.31	.28	.28	.25	.24	.24	.34
1948-49	.39	.39	.42	.42	.48	.60	.75	.83	.92	1.06	1.10	1.10	.57
1949-50	1.29	1.29	1.72	1.90	2.05	1.98	1.95	1.93	1.42	1.43	1.43		1.87
TANGERINES													
1945-46					1.00	1.00	1.00	1.00	1.00				1.00
1946-47			1.50	1.00	.60	.60	.65	.65					.80
1947-48			.50	.40	.35	.35	.35						.35
1948-49		.46	.46	.46	.46	.46	.46	.46					.46
1949-50			.50	.80	.80	.80	1.05						.90

FLORIDA CITRUS VOLUME CANNED OR PROCESSED

(Carloads of 500 Boxes)

ORANGES	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug	Total
1944-45		167	1786	2582	4302	5705	6809	5211	1799	81			28,442
1945-46	LCL	984	3942	3997	4494	4146	5825	6128	6255	2494	103		38,368
1946-47		1049	2550	2766	5266	6461	9101	4498	4837	2734	362	27	39,651
1947-48		605	3630	7797	11092	11280	6622	6097	6999	5110	1441	80	60,753
1948-49	3	1269	4463	6930	9126	9409	8616	6007	5497	2246	59		53,625
1949-50		236	5056	13333	14044	8844	5676	7938	10007	4135	47		69,316
G.FRUIT													
1944-45		726	4637	8427	8607	4248	2131	1034	372	22			30,204
1945-46	105	989	2416	4000	7355	5950	7266	7516	6031	2319	302	LCL	44,249
1946-47	174	1586	3470	3319	5246	3682	5511	5043	2590	965	120	21	31,727
1947-48		596	2139	4749	5659	5769	6107	6602	4142	2023	929	180	38,895
1948-49	224	1607	4384	4946	6378	5818	5341	2328	904	534	143	4	32,611
1949-50	22	160	1151	2809	5875	5870	4826	2075	2099	2010	75		26,972
TANG.													
1945-46					211	325	356	133	6				1,031
1946-47			188	676	742	220	26	LCL					1,852
1947-48			58	439	492	208	LCL						1,197
1948-49		37	582	654	621	83	14	7					1,998
1949-50			48	511	1086	1210	334	1					3,190
TOTAL CITRUS													
1944-45		893	6423	11009	12909	9953	8940	6245	2171	103			58,646
1945-46	105	1973	6358	7997	12060	10421	13447	13777	12292	4813	405	LCL	83,648
1946-47	174	2635	6208	6761	11254	10363	14638	9541	7427	3699	482	48	73,230
1947-48		1201	5827	12985	17243	17257	12729	12699	11141	7133	2370	260	100845
1948-49	227	2913	9429	12530	16125	15310	13971	8342	6401	2780	202	4	88,234
1949-50	22	396	6255	16653	21005	15924	10836	10014	12106	6145	122		99,478

CITRUS PRICE ANALYSIS 1933-34 TO 1949-50

	FLORIDA GROSS FOB MARKET OR EQUIVALENT PER BOX						EQUIV. ON TREE	NET* TO GROWER		COST	PICKING PACKING MARKETING
	BOX YIELD	RAIL & BOAT	TRUCKED OUT	FLORIDA CONSUMED	CANNED	GROSS ALL	ALL.	NET ALL.	RAIL AND BOAT	PRODUCTION	RAIL&BOAT (Costs)
ORANGES											
1933-34	16,170,996	$1.71	$1.25	$1.15	$ .80	$1.59	$ .88	$ .42	$ .38	$ .46	$ .87
1934-35	15,589,039	1.85	1.35	1.25	.80	1.69	.98	.53	.50	.45	.90
1935-36	15,864,588	2.30	1.60	1.50	1.00	2.10	1.33	.88	.90	.45	.95
1936-37	19,460,788	2.50	1.90	1.70	1.25	2.31	1.48	1.06	1.15	.42	.93
1937-38	24,302,896	1.56	1.12	1.12	.36	1.41	.63	.25	.30	.38	.88
1938-39	30,015,287	1.43	1.15	1.15	.41	1.32	.54	.20	.25	.34	.84
1939-40	25,064,702	1.62	1.52	1.32	.19	1.37	.59	.17	.29	.42	.91
1940-41	28,752,089	1.63	1.58	1.28	.80	1.48	.72	.32	.36	.40	.87
1941-42	27,200,000	2.10	2.05	1.70	1.08	1.91	1.13	.69	.76	.44	.90
1942-43	37,200,181	2.97	2.91	2.50	1.70	2.72	1.85	1.45	1.56	.40	1.01
1943-44	46,200,000	3.10	3.10	2.60	2.02	2.81	1.81	1.31	1.35	.50	1.25
1944-45	42,800,000	3.50	3.50	3.00	2.60	3.17	2.23	1.73	1.79	.50	1.21
1945-46	49,800,000	3.55	3.55	3.10	2.83	3.25	2.32	1.84	1.83	.48	1.24
1946-47	52,800,000	2.62	2.62	2.35	.82	1.93	1.03	.50	.84**	.53	1.25
1947-48	58,400,000	2.10	2.10	1.90	.80	1.41	.65	.15	.28**	.50	1.32
1948-49	58,300,000	2.80	2.80	2.50	1.51	2.19	1.29	.79	.90**	.50	1.40
1949-50	58,500,000	3.55	3.55	3.25	2.38	2.84	2.03	1.51	1.65**	.52	1.38
GRAPEFRUIT											
1933-34	11,113,200	$1.51	$ .90	$ .90	$ .53	$1.19	$ .62	$ .23	$ .29	$ .39	$ .83
1934-35	15,243,060	1.29	.80	.70	.37	.88	.38	.01	.08	.37	.84
1935-36	11,504,067	1.87	1.20	1.10	.73	1.39	.85	.46	.61	.39	.87
1936-37	18,121,786	1.48	1.10	1.00	.55	1.09	.55	.25	.35	.30	.83
1937-38	14,378,760	1.53	1.10	1.10	.48	1.05	.54	.18	.35	.36	.82
1938-39	23,050,835	1.04	.80	.80	.22	.64	.21	-.09	-	.30	.74
1939-40	15,650,865	1.42	1.30	1.12	.33	.79	.39	-.01	.20	.40	.82
1940-41	24,387,041	1.21	1.10	.86	.37	.71	.33	-.02	.12	.35	.74
1941-42	19,100,000	1.80	1.70	1.45	.71	1.20	.74	.34	.60	.40	.80
1942-43	27,300,116	2.33	2.25	1.85	1.05	1.48	1.02	.67	1.10	.35	.88
1943-44	31,000,000	2.47	2.47	2.00	1.53	1.83	1.32	.92	1.00	.40	1.07
1944-45	22,300,000	3.00	3.00	2.60	1.91	2.24	1.76	1.36	1.53	.40	1.07
1945-46	32,000,000	2.65	2.65	2.40	1.39	1.77	1.12	.78	1.21	.34	1.10
1946-47	26,400,000	2.18	2.18	1.90	.65	1.25	.63	.26	.73**	.37	1.08
1947-48	29,300,000	1.80	1.80	1.60	.34	.82	.34	-.01	.36**	.35	1.09
1948-49	30,200,000	2.35	2.35	2.10	.57	1.38	.68	.33	.82**	.35	1.18
1949-50	24,200,000	3.41	3.41	3.10	1.87	2.53	1.89	1.52	1.91**	.37	1.13

*Net to grower (or fruit owner) indicates the amount per box after deducting production and all other costs except interest, taxes and depreciation. The State Marketing Bureau "On Tree" average price may be obtained by adding Production Costs to "Net to Grower" return for All Fruit. **Includes Truck Shipments.

*Net to grower(or fruit owner) indicates the amount per box after deducting production and all other costs except interest, taxes and depreciation. The State Marketing Bureau "On Tree" average price may be obtained by adding Production Costs to "Net to Grower" return for All Fruit. **Indicates Truck Shipments.

CITRUS PRICE ANALYSIS 1933-34 TO 1949-50

	FLORIDA GROSS FOB MARKET OR EQUIVALENT PER BOX						EQUIV. ON TREE ALL	NET* TO GROWER		COST PRODUCTION	PICKING PACKING MARKETING RAIL&BOAT (Costs)
	BOX YIELD	RAIL & BOAT	TRUCKED OUT	FLORIDA CONSUMED	FLORIDA CANNED	GROSS ALL		NET ALL	RAIL AND BOAT		
TANGERINES											
1933-34	1,992,091	$1.80	$1.40	$1.25	$ -	$1.68	$ .85	$ .29	$ .19	$ .56	$1.05
1934-35	2,003,755	1.66	1.15	1.10	-	1.51	.76	.21	.16	.55	.95
1935-36	2,093,397	2.00	1.50	1.40	-	1.86	.97	.42	.35	.55	1.10
1936-37	3,018,634	1.45	1.15	1.05	-	1.37	.32	-.18	-.20	.50	1.15
1937-38	2,257,973	1.86	1.28	1.28	-	1.72	.66	.14	.18	.52	1.16
1938-39	3,381,873	1.34	1.05	1.05	-	1.27	.38	-.07	-.06	.45	.95
1939-40	2,257,545	2.00	1.90	1.70	-	1.95	.92	.42	.44	.50	1.06
1940-41	2,751,624	1.68	1.65	1.31	-	1.60	.58	.08	.10	.50	1.08
1941-42	2,100,000	2.85	2.80	2.40	-	2.77	1.67	1.09	1.11	.58	1.16
1942-43	4,200,149	2.78	2.70	2.25	-	2.72	1.38	.98	1.03	.40	1.35
1943-44	3,600,000	3.70	3.70	3.00	-	3.62	2.01	1.36	1.37	.65	1.68
1944-45	3,900,000	4.25	4.25	3.60	-	4.18	2.56	1.91	1.92	.65	1.68
1945-46	4,200,000	4.80	4.80	4.00	1.00	4.24	2.74	2.10	2.45	.64	1.71
1946-47	3,900,000	3.75	3.75	3.30	.80	2.99	1.58	.90	1.35*	.68	1.72
1947-48	3,400,000	2.90	2.90	2.60	.35	2.41	.88	.20	.40*	.68	1.82
1948-49	4,400,000	3.70	3.70	3.40	.40	2.93	1.42	.74	1.17*	.68	1.85
1949-50	5,000,000	3.85	3.85	3.50	.90	2.87	1.50	.80	1.30*	.70	1.85
TOTAL CITRUS (And Average of All Citrus)											
1933-34	29,276,287	$1.65	$1.19	$1.08	$ .54	$1.45	$ .78	$ .34	$ .336	$ .44	$ .87
1934-35	32,835,854	1.63	1.19	1.05	.38	1.33	.70	.27	.32	.43	.88
1935-36	29,462,052	2.14	1.48	1.37	.74	1.81	1.13	.69	.76	.44	.94
1936-37	40,601,208	2.04	1.58	1.43	.61	1.70	.98	.61	.75	.37	.92
1937-38	40,939,629	1.57	1.12	1.13	.46	1.30	.60	.22	.305	.38	.88
1938-39	56,447,995	1.31	1.07	1.04	.24	1.04	.41	.07	.15	.34	.82
1939-40	42,973,112	1.60	1.51	1.29	.28	1.17	.54	.12	.28	.42	.90
1940-41	55,890,754	1.51	1.49	1.18	.47	1.15	.55	.16	.27	.39	.85
1941-42	46,400,000	2.06	2.05	1.69	.83	1.66	1.00	.57	.74	.43	.89
1942-43	68,700,000	2.81	2.78	2.28	1.22	2.23	1.50	1.11	1.41	.39	1.01
1943-44	80,800,000	3.01	3.10	2.37	1.70	2.47	1.65	1.16	1.28	.49	1.24
1944-45	69,000,000	3.48	3.57	2.95	2.25	2.93	2.10	1.62	1.75	.48	1.25
1945-46	86,000,000	3.44	3.61	3.00	2.05	2.75	1.92	1.46	1.73	.46	1.25
1946-47	83,100,000	2.59	2.67	2.21	.75	1.76	.94	.44	.85**	.50	1.24
1947-48	91,100,000	2.08	2.13	1.89	.62	1.26	.58	.10	.31**	.48	1.29
1948-49	92,900,000	2.74	2.77	2.46	1.14	1.96	1.10	.63	.90**	.47	1.37
1949-50	87,700,000	3.54	3.54	3.24	2.19	2.76	1.96	1.47	1.70**	.49	1.65

ESTIMATED COSTS FROM TREE TO AUCTIONS
1947-48, 1948-49 AND 1949-50 SEASONS
(Private Sales not Included)

		1947-48	1948-49	1949-50	1947-48	1948-49	1949-50
ORANGES	Carloads Sold				13,406	13,133	10,065
Auction Sales at Terminal Markets					$ 3.27	$ 4.23	$ 4.95
Terminal Selling & Expenses					.07	.07	.07
Net at Terminal					3.20	4.16	4.88
Transportation Cost					.95	1.13	1.08
Florida F.O.B. Equivalent					$ 2.25	$ 3.03	3.80
Florida Marketing Charges		.08	.08		$ 1.32	$ 1.36	$ 1.39
Advertising & Inspection		.04	.04				
Packing & Processing		.86	.89				
Picking, Loading & Hauling		.34	.35				
On Tree Equivalent					$ .93	$ 1.67	$ 2.41
Estimated Production Costs					.55	.56	.58
Net to Grower before Interest, Taxes & Depreciation					$ .38	$ 1.11	$ 1.83
GRAPEFRUIT	Carloads Sold				6,660	7,641	6,190
Auction Sales at Terminal Markets					$ 3.07	$ 3.77	$ 5.04
Terminal Selling & Expenses					.06	.06	.06
Net at Terminal					3.01	3.71	4.98
Transportation Cost					.90	1.06	1.04
Florida F.O.B. Equivalent					$ 2.11	$ 2.65	$ 3.94
Florida Marketing Charges		.08	.08		$ 1.09	$ 1.10	$ 1.12
Advertising & Inspection		.05	.05				
Packing & Processing		.72	.72				
Picking, Loading & Hauling		.24	.25				
On Tree Equivalent					$ 1.02	$ 1.55	$ 2.82
Estimated Production Costs					.38	.38	.40
Net to Grower before Interest, Taxes & Depreciation					$ .64	$ 1.17	$ 2.42
TANGERINES	Carloads Sold				2,209	2,737	2,550
Auction Sales at Terminal Markets					$ 3.96	$ 5.10	$ 5.26
Terminal Selling & Expenses					.08	.08	.08
Net at Terminal					3.88	5.02	5.18
Transportation Cost					.95	1.12	1.08
Florida F.O.B. Equivalent					$ 2.93	$ 3.90	$ 4.10
Florida Marketing Charges		.08	.08		$ 1.82	$ 1.83	$ 1.87
Advertising & Inspection		.07	.07				
Packing & Processing		1.20	1.22				
Picking, Loading & Hauling		.47	.46				
On Tree Equivalent					$ 1.11	$ 2.07	$ 2.23
Estimated Production Costs					.68	.68	.70
Net to Grower before Interest, Taxes & Depreciation					$ .43	$ 1.39	$ 1.53

Percentage of all freight, express, boat and truck shipments sold at auction:

	Oranges			Grapefruit			Tangerines		
SEASON	RBT Carloads	Auction Carloads	% Auction	RBT Carloads	Auction Carloads	% Auction	RBT Carloads	Auction Carloads	% Auction
1940-41	52,588	18,971	.36	21,515	8,823	.41	4,321	2,717	.62
1941-42	45,775	17,133	.37	15,769	7,325	.46	2,849	2,085	.73
1942-43	50,180	13,613	.27	13,790	5,604	.40	6,017	3,399	.56
1943-44	56,793	12,849	.22	14,330	4,264	.29	4,813	644	.13
1944-45	44,690	9,022	.20	9,047	3,132	.34	5,189	1,465	.27
1945-46	47,059	8,268	.17	13,064	4,386	.33	4,773	2,201	.46
1946-47	55,072	14,770	.26	15,438	7,094	.45	4,292	2,403	.55
1947-48	47,792	13,406	.28	14,659	6,660	.45	4,554	2,209	.48
1948-49	56,994	13,133	.23	22,534	7,641	.33	5,625	2,737	.48
1949-50	42,871	10,065	.23	18,840	5,772	.30	6,074	2,550	.38

NOTE: The above figures on Estimated Costs From "Tree to Auction" were supplied by the Florida Citrus Exchange. Indian River Section supplied 27.8 per cent of the oranges and 38.3 per cent of the grapefruit sold on auction markets. The production, packing and marketing costs represent their ideas as to costs for the industry and are not necessarily the same as the State Marketing Bureau estimates. The production costs above may reflect the production cost for the Indian River fruit which may be higher than the State average.

FLORIDA CARS TO AUCTION FOR SEASON 1937-38 TO 1949-50 INCLUSIVE

(Including Freight, Boat and Truck)
Weighted Average Prices and Per Cent Indian River Fruit

SEASONS	INTERIOR		INDIAN RIVER		COMBINED		% IND. RIV.
	CARS	AVG.	CARS	AVG.	CARS	AVG.	
1937-38							
Oranges	17,605	$2.19	3,081	$2.53	20,686	$2.24	14.9
Grapefruit	6,101	2.01	2,454	2.54	8,555	2.16	28.7
Tang's, ½ Bx(not segregated)	0	0	0	0	2,513	1.24	-
1938-39							
Oranges	22,008	$2.05	3,216	$2.35	25,224	$2.09	12.7
Grapefruit	6,794	1.58	4,132	1.95	10,926	1.72	37.8
Tang's, ½ Bx(not segregated)	0	0	0	0	3,663	1.00	-
1939-40							
Oranges	14,151	$2.27	2,694	$2.82	16,845	$2.36	16.0
Grapefruit	4,631	1.90	2,962	2.50	7,593	2.13	39.0
Tang's, ½ Bx(not segregated)	0	0	0	0	2,143	1.37	-
1940-41							
Oranges	15,931	$2.28	3,040	$2.69	18,971	$2.35	16.0
Grapefruit	5,314	1.76	3,509	2.12	8,823	1.91	39.8
Tang's, ½ Bx(not segregated)	0	0	0	0	2,717	1.19	-
1941-42							
Oranges	13,603	$2.80	3,530	$2.94	17,133	$2.83	20.6
Grapefruit	4,037	2.41	3,288	2.65	7,325	2.52	44.9
Tang's, ½ Bx(not segregated)	0	0	0	0	2,085	1.79	-
1942-43							
Oranges	11,030	$3.71	2,576	$4.12	13,606	$3.79	18.9
Grapefruit	2,985	2.77	2,619	3.48	5,604	3.11	46.7
Tang's, ½ Bx(not segregated)	0	0	0	0	3,399	1.80	-
1943-44							
Oranges	9,880	$3.77	2,969	$4.31	12,849	$3.89	23.1
Grapefruit	1,583	3.18	2,681	3.79	4,264	3.56	62.9
Tang's, ½ Bx(not segregated)	0	0	0	0	644	2:23	-
1944-45							
Oranges	6,550	$4.30	2,472	$4.97	9,022	$4.48	27.4
Grapefruit	1,079	3.72	2,053	4.51	3,132	4.24	65.5
Tang's, ½ Bx(not segregated)	0	0	0	0	1,465	2.41	-
1945-46							
Oranges	6,038	$4.41	2,230	$5.05	8,268	$4.58	27.0
Grapefruit	1,469	3.21	2,917	4.12	4,386	3.82	66.1
Tang's, ½ Bx(not segregated)	0	0	0	0	2,201	2.61	-
1946-47							
Oranges	11,826	$3.37	2,982	$4.03	14,808	$3.50	20.2
Grapefruit	3,215	2.90	3,884	3.61	7,099	3.29	54.8
Tang's, ½ Bx(not segregated)	0	0	0	0	2,403	2.17	-
1947-48							
Oranges	9,424	$3.08	3,982	$4.68	13,406	$3.27	29.7
Grapefruit	3,430	2.53	3,230	3.64	6,660	3.07	48.5
Tang's, ½ Bx(not segregated)	0	0	0	0	2,209	1.98	-
1948-49							
Oranges	9,830	$4.15	3,303	$4.46	13,133	$4.23	25.2
Grapefruit	3,894	3.42	3,747	4.13	7,641	3.77	49.0
Tang's, ½ Bx(not segregated)	0	0	0	0	2,737	2.55	-
1949-50							
Oranges	6,747	$4.68	2,594	$5.29	9,341	$4.85	27.8
Grapefruit	3,821	4.45	2,369	5.99	6,190	5.04	38.3
Tang's, ½ Bx(not segregated)	0	0	0	0	2,550	2.63	-

NOTE: It appears that Temple oranges were omitted for 1949-50 season as the total of all oranges was 1,065 carloads.

INTERSTATE TRUCK DISTRIBUTION, FLORIDA CITRUS FRUITS
BY STATES - 1949-50 AND 1948-49 SEASONS-OCTOBER TO JUNE

CARLOAD EQUIV. (500 Boxes per Car for Both Seasons)

STATES	ORANGES		GRAPEFRUIT		TANGERINES		GRAND TOTAL	
	49-50	48-49	49-50	48-49	49-50	48-49	49-50	48-49
	Cars	Cars	Cars	Cars	Cars	Cars	Cars	Cars
Alabama	940	1,406	190	176	69	80	1,199	1,662
Arkansas	189	313	41	54	7	9	237	376
California	13	16	3	4	5	-	21	20
Colorado	17	41	31	24	14	3	62	68
Connecticut	88	54	42	9	22	8	152	71
Delaware	38	37	8	9	3	3	49	49
Dist.of Columbia	401	673	233	242	47	66	681	981
Georgia	1,581	2,263	390	557	157	186	2,128	3,006
Illinois	1,214	1,833	582	448	274	239	2,070	2,520
Indiana	747	969	211	241	107	96	1,065	1,306
Iowa	107	137	67	67	9	8	183	212
Kansas	61	68	37	42	9	5	107	115
Kentucky	382	526	109	124	37	41	528	691
Louisiana	337	507	127	48	7	9	471	564
Maine	41	40	14	14	-	1	55	55
Maryland	505	780	168	265	88	93	761	1,138
Massachusetts	200	118	205	20	115	28	520	166
Michigan	512	510	171	177	65	48	748	735
Minnesota	262	144	96	36	30	6	388	186
Mississippi	336	499	26	17	14	12	376	528
Missouri	363	275	167	83	55	18	585	376
Nebraska	66	63	63	65	9	7	138	135
New Hampshire	--	3	-	-	-	-	-	3
New Jersey	360	347	119	67	26	29	505	443
New Mexico	2	6	2	1	-	-	4	7
New York	2,510	1,873	702	551	375	222	3,587	2,646
North Carolina	1,034	1,445	281	354	151	192	1,466	1,991
North Dakota	7	2	8	2	1	-	16	4
Ohio	947	1,073	356	378	119	116	1,422	1,567
Oklahoma	66	89	44	37	7	7	117	133
Pennsylvania	2,170	1,881	624	501	360	226	3,154	2,608
Rhode Island	77	54	14	12	14	12	105	78
South Carolina	880	1,300	222	313	123	124	1,225	1,737
South Dakota	8	2	9	-	-	-	17	2
Tennessee	679	886	163	155	64	56	906	1,097
Texas	597	757	168	123	90	21	855	901
Vermont	22	43	7	9	1	2	30	54
Virginia	822	1,042	350	459	118	104	1,290	1,605
West Virginia	255	253	73	59	23	27	351	339
Wisconsin	234	179	68	45	40	13	342	237
States not Specified*	22	30	24	7	7	2	53	39
CANADA	188	70	100	42	28	8	316	120
TOTAL CARLOADS	19,280	22,607	6,315	5,837	2,690	2,127	28,285	30,571
N.W. Florida	146	276	31	58	21	24	198	358
GRAND TOTAL-CARS	19,426	22,883	6,346	5,895	2,711	2,151	28,483	30,929

* Includes: Oranges--Idaho 2, Montana 1, Oregon 2, Utah 6, Washington 4, Wyoming 1.
Grapefruit--Idaho 4, Montana 1, Oregon 1, Utah 5, Washington 5, Wyoming 1.
Tangerines--Oregon 1, Utah 1, Washington 2.

Destinations, fairly complete, were available for following periods: 1948-49--Oct.15-June 19, inclusive; 1949-50--Oct. 17-June 17, inclusive.

State Marketing Bureau figures show 30,088 carloads of 500 boxes shipped out Aug. 1 to July 31. Destinations shown for period Oct. 1 to June 17, inclusive, accounted for 28,285 carloads.

RECAPITULATION OF RAIL DISTRIBUTION, FLORIDA CITRUS FRUITS
BY STATES - 1949-50 AND 1948-49 SEASONS

CARLOADS (Approximately 500 Boxes per Car for Both Seasons)

STATES	ORANGES		GRAPEFRUIT		TANGERINES		MIXED CITRUS		GRAND TOTAL	
	49-50	48-49	49-50	48-49	49-50	48-49	49-50	48-49	49-50	48-49
	Rail-Bt.	Rail	Rail-Bt.	Rail	Rail-Bt.	Rail	Rail-Bt.	Rail	Rail-Bt.	Rail
Alabama	145	228	6	40	-	-	84	16	235	284
Arkansas	3	7	-	-	-	-	1	6	4	13
California	9	55	25	26	6	-	3	3	43	84
Colorado	57	103	60	70	8	4	2	28	127	205
Connecticut	326	851	91	195	24	57	13	45	454	1,148
Delaware	6	9	1	2	1	-	1	-	9	11
Dist.of Columbia	113	332	53	191	5	3	10	11	181	537
Florida	-	-	-	1	-	-	-	-	-	1
Georgia*	279*	287*	67*	81*	4*	3*	107*	64*	457	435*
Idaho	3	6	5	8	-	-	6	11	14	25
Illinois	994	1,126	493	623	205	167	152	113	1,844	2,029
Indiana	48	98	17	46	1	5	15	28	81	177
Iowa	11	73	27	84	1	-	9	9	48	166
Kansas	3	22	15	17	1	-	2	15	21	54
Kentucky	165	200	43	42	6	3	14	17	228	262
Louisiana	96	170	9	20	2	-	26	2	133	192
Maine	52	132	10	38	1	-	31	30	94	200
Maryland	524	732	221	393	68	77	154	234	967	1,436
Massachusetts	1,740	2,737	561	1,096	191	228	339	519	2,831	4,580
Michigan	753	1,289	515	649	218	237	150	175	1,636	2,350
Minnesota	10	176	75	192	28	22	8	53	121	443
Mississippi	46	39	-	-	-	-	11	6	57	45
Missouri	442	710	208	312	59	86	82	99	791	1,207
Montana	4	24	25	15	2	2	4	15	35	56
Nebraska	27	88	31	79	1	1	1	5	60	173
New Hampshire	-	11	-	-	-	-	3	4	3	15
New Jersey	323	587	75	181	1	5	9	23	408	796
New Mexico	1	2	1	1	-	-	-	-	2	3
New York	6,088	8,101	3,717	4,116	1,025	1,059	1,234	2,128	12,064	15,404
North Carolina	373	490	122	239	19	9	153	94	667	832
North Dakota	1	1	2	4	-	-	6	17	9	22
Ohio	1,086	1,755	569	634	223	266	229	326	2,107	2,981
Oklahoma	24	76	18	22	-	-	-	1	42	99
Oregon	42	83	81	83	8	12	15	22	146	200
Pennsylvania	1,994	3,574	939	1,673	398	591	695	1,052	4,026	6,890
Rhode Island	199	369	75	82	25	28	58	66	357	545
South Carolina	178	151	7	17	-	2	76	39	261	209
South Dakota	-	15	4	15	-	-	-	8	4	38
Tennessee	677	833	91	54	18	26	254	135	1,040	1,048
Texas	9	103	5	32	-	1	-	3	14	139
Utah	16	72	25	41	-	3	-	6	41	122
Vermont	-	4	-	-	-	-	3	-	3	4
Virginia	234	365	154	189	1	3	38	47	427	604
Washington	72	206	151	149	26	19	1	16	250	390
West Virginia	88	185	6	44	4	5	30	48	128	282
Wisconsin	158	351	90	173	8	13	43	60	299	597
Wyoming	-	1	2	4	-	-	-	5	2	10
CANADA	389	862	745	1,567	56	113	102	338	1,292	2,880
TOT.CARLOADS	17,808	27,691	9,437	13,540	2,644	3,050	4,174	5,942	34,063	50,223

* Does not include Savannah, Georgia, a transfer point.

Note: Boat shipments for 1948-49 were only 35 carloads of oranges, for which no distribution by States was made. Boat shipments 1949-50 were: Oranges 3,091, Grapefruit 1,662, Tangerines 409, Total 5,162 carloads.

Truck and Rail Distribution represents abstracts of tables in the Florida 1949-50 Citrus Summary, by Federal-State Market News Service, Lakeland, Florida.

JACKSONVILLE JOBBING MARKET
SALES TO RETAILER OR EQUIVALENT SALES
MONTHLY SIMPLE AVERAGES

EGGS (Florida White Grade A - 24 oz. per Doz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1921	74.3	48.6	36.0	31.3	30.5	31.9	42.7	47.9	50.0	59.4	64.8	60.0	48.1
1922	48.0	40.7	26.5	29.4	28.3	34.7	37.5	37.5	52.8	55.0	62.8	53.9	40.6
1923	49.6	36.0	30.0	29.5	29.0	33.8	39.5	42.6	49.8	56.3	59.3	58.0	42.8
1924	47.4	44.6	26.6	25.8	28.5	32.5	39.0	43.6	52.1	62.0	66.2	64.9	44.4
1925	56.8	45.3	30.2	33.5	30.3	38.6	44.4	48.4	55.2	64.0	65.6	67.0	48.3
1926	57.2	42.1	31.3	34.1	32.5	36.1	41.6	44.4	51.8	62.2	61.0	57.1	45.9
1927	47.6	35.9	28.0	29.2	27.9	29.7	33.9	41.4	49.0	52.1	55.0	50.4	40.0
1928	48.0	32.4	30.0	29.7	28.2	33.4	36.5	41.7	48.3	54.8	55.0	48.5	40.4
1929	42.2	34.5	35.1	29.2	30.2	33.7	39.3	43.2	45.2	54.1	55.3	54.0	41.5
1930	47.1	35.4	28.5	27.0	27.0	27.0	30.6	34.9	38.2	45.4	43.9	40.9	35.5
1931	32.0	22.0	23.0	22.0	20.0	21.0	25.0	28.5	32.0	37.5	38.0	33.0	27.9
1932	26.5	16.5	18.0	15.5	14.7	18.3	21.0	25.0	28.2	31.5	32.6	35.2	23.5
1933	23.5	17.0	15.5	15.5	17.3	16.3	22.9	25.5	31.4	33.0	32.0	34.4	23.7
1934	28.7	25.6	19.2	19.8	20.1	23.5	28.0	31.6	36.8	38.0	40.0	40.0	29.3
1935	35.8	31.8	23.0	24.9	26.3	26.8	31.5	35.6	39.0	39.3	37.0	40.6	32.6
1936	33.5	31.2	23.5	22.9	24.1	25.7	31.9	34.0	37.5	38.4	41.9	43.4	32.3
1937	29.8	27.5	25.1	25.5	24.2	25.8	30.1	33.0	37.2	38.1	39.6	38.0	31.2
1938	32.5	26.6	22.2	22.3	25.0	25.7	31.5	32.8	36.3	36.3	36.8	40.1	30.7
1939	30.8	24.3	21.6	21.9	22.6	23.0	29.1	29.6	28.8	32.4	33.9	30.9	27.4
1940	31.4	26.8	20.7	20.8	21.2	23.5	28.8	31.7	34.5	36.4	36.3	38.2	29.2
1941	33.3	25.4	24.1	25.2	28.4	31.2	36.8	39.2	41.4	42.0	44.5	42.2	34.5
1942	40.0	31.5	30.5	31.4	31.4	34.7	39.5	45.0	46.1	48.0*	48.0*	48.0*	39.7
1943	47.6	38.7	38.0	38.4*	43.0*	43.6*	46.9*	51.0*	54.8*	58.0*	57.0*	53.6*	47.6
1944	49.3*	39.7*	37.1*	37.0*	38.2*	41.4*	45.2*	50.3*	55.1*	58.6*	59.9*	59.0*	47.6
1945	50.0*	44.0*	37.8*	42.4*	42.6*	44.9*	49.3*	54.4*	57.8*	58.6*	59.9*	58.8*	50.0
1946	49.7*	40.7*	39.0*	39.1*	42.4*	45.0**	50.7	55.6	60.4	66.2	61.3	62.8	51.1
1947	59.4	52.4	51.1	52.4	56.0	57.4	62.3	64.9	70.1	73.0	74.0	75.5	62.5
1948	68.6	57.2	54.1	55.4	57.7	60.2	63.3	68.2	70.7	74.7	75.8	69.8	64.6
1949	64.3	52.9	53.7	55.2	58.5	60.7	64.1	67.0	69.7	67.0	60.6	52.8	60.5
1950	45.5	40.0	44.7	44.1	42.3	46.3	52.7	55.1					

FRYERS (Heavy Breed)

1921	39.1	39.7	46.9	49.5	46.6	35.0	31.2	30.3	34.0	35.5	29.1	29.0	37.2
1922	29.0	29.5	38.4	40.0	40.0	35.5	31.5	29.0	31.0	29.0	29.0	29.0	32.6
1923	29.5	31.0	36.5	37.0	39.8	36.7	30.0	30.0	33.0	32.4	31.0	31.0	33.1
1924	32.7	36.6	37.8	42.0	42.5	37.4	32.7	30.7	34.0	33.0	31.5	34.3	35.4
1925	41.4	44.0	45.6	45.9	43.7	39.4	36.0	35.0	38.0	39.0	37.0	38.6	40.3
1926	43.5	48.0	49.7	50.0	48.3	38.3	37.8	35.3	35.0	35.0	35.3	37.1	41.1
1927	42.0	45.0	45.0	46.3	43.0	36.1	31.8	30.0	30.0	31.1	33.1	35.8	37.4
1928	37.0	36.2	38.9	39.0	39.0	38.1	34.5	31.2	33.0	35.3	36.3	35.7	36.3
1929	26.0	36.2	39.1	42.8	37.7	37.3	31.0	31.1	35.0	34.2	36.1	36.8	36.1
1930	33.1	32.9	33.6	36.7	32.7	32.8	24.5	27.4	29.0	29.0	29.0	29.0	30.9
1931	30.0	31.0	37.0	40.0	37.0	35.0	29.0	27.0	27.5	26.0	24.5	24.5	30.6
1932	24.4	23.2	27.1	26.8	23.9	23.5	18.0	17.3	18.0	18.7	17.3	14.9	21.0
1933	14.6	20.4	22.2	24.3	22.1	18.0	15.4	16.1	17.0	17.0	15.7	16.1	18.2
1934	17.6	20.2	23.9	25.2	24.9	22.5	20.1	18.7	19.7	20.0	20.5	20.5	21.2
1935	21.5	24.3	26.1	25.9	22.8	23.1	21.2	20.3	21.0	22.4	23.2	24.5	23.0

(Cont'd.)

JACKSONVILLE JOBBING MARKET
SALES TO RETAILER OR EQUIVALENT SALES
MONTHLY SIMPLE AVERAGES

FRYERS (Heavy Breed)(Cont'd.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1936	25.5	25.6	27.0	27.2	25.7	25.5	23.1	22.6	22.3	21.2	20.5	20.0	23.7
1937	22.3	24.0	24.1	27.0	24.1	25.3	25.5	24.5	25.8	27.1	26.7	27.7	25.4
1938	25.8	24.6	27.2	27.8	24.0	21.8	20.5	21.6	22.9	22.9	23.0	23.6	23.8
1939	23.4	21.6	21.9	24.8	22.0	21.8	22.5	21.9	21.0	22.0	22.3	22.1	22.3
1940	22.0	21.8	22.8	22.6	24.3	23.2	21.4	20.5	21.5	21.9	20.8	21.5	22.0
1941	21.8	22.4	23.8	24.3	23.0	22.8	22.8	22.2	22.6	23.0	23.9	24.0	23.1
1942	24.1	23.7	24.2	25.6	26.8	27.5	27.4	27.5	29.0	30.5	30.5	31.4	27.4
1943	31.8	31.8	31.8	31.9*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	31.0
1944	30.6*	30.6*	30.6*	31.0*	32.6*	31.8*	31.1*	30.6*	30.6*	30.6*	30.6*	30.6*	30.9
1945	30.6*	31.6*	32.0*	32.4*	32.8*	31.6*	31.4*	31.3*	31.3*	31.3*	31.3*	31.3*	31.6
1946	31.6*	32.1*	32.5*	32.9*	33.3*	33.0**	39.1	38.5	43.3	47.1	41.5	41.2	37.2
1947	36.2	32.5	34.5	35.0	37.4	38.0	38.5	39.0	41.2	37.9	34.7	36.8	36.8
1948	40.2	39.4	41.9	42.4	40.3	41.7	39.7	39.0	39.4	38.5	38.4	38.3	39.9
1949	32.9	30.9	32.9	34.6	31.3	30.7	30.2	32.5	32.4	32.7	34.1	28.5	32.0
1950	23.5	29.2	35.5	33.5	30.1	29.7	34.1	34.9					

HENS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1921	33.6	32.6	31.7	29.3	26.9	26.3	25.1	26.2	30.3	31.8	26.0	26.0	28.8
1922	26.0	26.0	26.7	25.5	25.4	24.0	24.0	24.0	27.5	26.0	26.0	26.0	25.6
1923	26.0	26.0	26.0	25.0	23.0	23.0	20.9	21.1	24.7	26.0	24.3	24.7	24.2
1924	27.8	26.0	26.4	26.0	27.0	25.1	24.0	26.6	29.4	30.0	28.6	27.8	27.1
1925	31.6	29.2	29.7	28.0	28.0	26.6	25.9	29.0	30.0	31.0	28.1	29.3	28.7
1926	30.7	30.2	32.5	31.8	31.9	30.0	30.0	29.7	31.0	31.0	30.2	31.1	30.7
1927	30.0	30.0	29.8	29.1	29.0	24.7	23.7	25.6	26.0	26.0	25.0	25.0	26.9
1928	25.0	25.0	25.0	25.0	24.5	23.0	21.9	21.1	23.9	27.2	25.5	24.5	24.3
1929	24.8	26.4	28.8	28.8	27.4	29.3	28.0	29.0	31.2	29.5	29.5	29.8	28.5
1930	29.8	30.0	28.5	27.5	26.6	24.5	22.5	22.6	23.0	22.8	23.0	23.0	25.3
1931	23.0	20.0	22.0	24.0	23.0	22.0	21.0	20.0	21.5	23.0	22.5	22.0	22.0
1932	20.5	18.6	18.7	19.0	17.5	16.1	14.5	14.5	15.5	16.7	17.0	14.4	16.9
1933	13.2	13.5	13.0	14.7	14.1	13.1	13.0	14.6	15.8	16.7	15.4	14.0	14.3
1934	14.3	15.5	16.0	15.5	18.8	16.0	15.7	14.8	16.6	17.2	17.8	17.5	16.1
1935	17.5	17.8	18.3	18.0	18.0	18.7	18.2	18.4	19.3	21.0	21.7	20.6	19.0
1936	20.0	19.9	19.5	20.3	20.8	20.5	20.9	20.7	20.2	19.6	19.6	18.7	20.1
1937	18.7	19.3	18.6	18.5	19.0	19.5	16.8	16.0	17.5	18.7	20.2	20.7	18.6
1938	20.1	19.0	19.9	19.7	19.0	19.3	19.4	18.7	20.2	20.2	21.0	21.2	19.8
1939	21.4	20.7	20.4	21.1	19.3	18.8	17.8	18.2	16.9	16.9	17.9	15.3	18.7
1940	16.2	16.7	17.5	17.5	17.1	16.2	15.5	16.1	16.5	18.5	17.8	17.2	16.9
1941	17.6	18.1	19.0	19.9	19.8	20.8	20.7	20.5	21.1	21.5	23.0	23.1	20.4
1942	23.9	22.8	23.0	23.6	23.2	21.5	21.0	21.8	24.9	26.5	26.5	27.8	23.9
1943	29.3	29.3	29.3	29.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.8
1944	27.1*	28.1*	27.1*	27.5*	29.2*	28.4*	27.6*	27.1*	27.1*	27.1*	27.1*	27.1*	27.5
1945	27.1*	28.1*	28.5*	28.9*	29.3*	28.1*	27.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.7
1946	27.6*	28.1*	28.5*	28.9*	29.3*	28.1**	29.1	29.2	35.0	40.6	35.2	35.0	31.2
1947	33.1	34.5	38.1	36.4	34.3	32.6	32.8	33.9	36.4	36.5	37.4	37.9	35.3
1948	40.5	40.2	41.7	42.8	43.0	43.0	40.3	38.0	39.9	40.0	40.0	40.9	40.9
1949	39.4	39.0	39.3	40.4	36.0	30.5	29.4	32.0	34.0	34.4	34.8	33.7	35.2
1950	27.5	29.2	28.4	28.0	26.1	25.5	25.5	29.8					

POULTRY AND EGG WHOLESALE PRICES

TAMPA MARKET (January 1, 1939-June 30, 1950)

WHITE EGGS (Grade A 24 Oz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1939	31.2	24.5	22.1	23.4	23.4	25.0	30.5	29.0	31.6	34.3	35.8	32.5	28.6
1940	31.5	29.2	21.5	22.1	22.3	24.2	29.5	32.5	35.9	37.5	37.1	38.6	30.2
1941	34.6	26.2	24.2	26.0	28.4	32.0	27.5	40.0	51.1	43.3	45.1	43.5	35.2
1942	41.9	33.2	31.2	33.0	32.4	35.5	41.0	46.1	47.3	49.0C	49.0	49.0	40.7
1943	48.7	40.1	39.0	43.0	43.0	43.1	47.1	51.3	55.0	58.3	57.3	53.8	48.3
1944	46.5	40.5	37.1	37.0	38.6	40.6	44.3	50.5	52.2	58.6	60.0	59.1	47.1
1945	49.3	44.0	38.2	41.8	42.0	44.8	49.3	55.0	57.9	58.7	60.1	59.0	50.0
1946	49.9	41.8	39.0	39.3	42.0	45.1C	51.1	56.0	61.2	67.0	62.8	63.8	51.5
1947	58.7	55.0	52.2	52.3	57.0	58.2	63.3	66.4	70.8	74.0	75.0	76.0	63.2
1948	69.6	58.2	55.2	56.3	58.0	60.5	64.5	68.8	71.2	75.6	76.8	70.3	65.4
1949	64.5	54.3	54.1	56.4	58.6	61.6	64.8	68.0	71.5	67.0	61.2	53.9	61.4
1950	48.3	41.5	46.0	43.4	41.3	46.3							

HENS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1939	19.1#	17.8	17.9	17.9	17.5	17.3	16.9	16.0	16.6	17.2	16.4	16.6	17.2
1940	17.1	17.1	17.3	18.0	17.0	16.5	14.8	14.7	16.8	16.6	17.5	17.5	16.7
1941	17.5	18.9	18.9	19.5	19.0	20.2	21.0	20.5	21.1	23.0	23.7	24.0	20.6
1942	24.5	24.0	23.1	24.4	24.3	22.5	22.3	22.0	23.9	26.0C	26.0	26.0	24.1
1943	28.5	29.5	29.4	29.4	29.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	28.2
1944	27.4	27.4	27.4	27.4	29.6	28.4	27.4	27.4	27.4	27.4	27.4	27.4	27.7
1945	27.5	27.8	28.8	29.2	29.6	28.5	27.6	27.4	27.3	27.3	27.3	27.3	27.9
1946	27.3	28.3	28.5	28.7	29.5	28.7C	24.8	25.1	31.2	35.6	32.1	32.0	29.3
1947	31.4	31.4	36.1	35.5	30.8	30.0	30.8	31.4	31.5	33.0	34.7	37.0	32.8
1948	38.5	36.0	36.0	36.0	36.0	36.0	34.7	33.0	34.3	37.0	38.1	39.0	36.2
1949	39.1	39.0	39.1	38.7	37.2	31.1	30.0	31.1	33.0	33.0	33.0	33.0	34.7
1950	29.0	28.8	31.9	29.0	26.0	23.7							

FRYERS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1939	19.1#	17.3	19.8	20.8	18.6	19.8	19.3	18.2	18.6	19.4	19.1	19.0	18.9
1940	21.5	19.5	19.3	21.5	21.3	22.4	18.6	17.9	19.4	19.5	19.7	19.4	20.0
1941	19.2	20.2	21.4	22.0	19.7	20.7	22.2	22.5	22.7	23.0	23.7	24.0	21.8
1942	25.8	24.0	23.5	25.3	26.7	27.0	27.6	29.0	29.9	31.0C	31.0	31.0	27.7
1943	33.0	31.5	31.6	31.9	31.1	30.9	30.9	30.9	30.9	30.9	30.9	30.9	31.3
1944	30.9	30.9	30.9	31.2	33.1	31.9	30.9	30.9	30.9	30.9	30.9	30.9	31.2
1945	31.0	31.3	32.3	32.7	33.1	32.0	31.7	31.7	31.6	31.6	31.6	31.6	31.8
1946	31.6	32.6	32.8	33.0	33.8	33.5C	35.2	38.1	40.4	47.3	43.0	44.6	37.1
1947	39.9	32.9	34.4	35.5	36.7	37.0	39.3	41.4	41.7	40.0	34.0	38.3	37.6
1948	40.5	40.5	41.6	44.4	42.3	44.0	41.2	39.0	39.6	38.8	39.1	40.0	40.2
1949	34.4	30.8	32.3	34.5	31.0	30.7	29.4	32.2	32.2	32.6	35.0	30.6	32.1
1950	24.6	29.7	36.0	34.7	30.3	29.7							

ORLANDO POULTRY AND EGG PRICES

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1948	(Started)		58.0	61.8	62.8	64.5	67.9	73.5	75.1	77.6	78.0	72.5	69.2
1949	69.4	54.0	53.9	56.2	60.0	61.0	64.6	67.0	69.4	65.5	61.1	55.9	60.7
1950	48.3	42.0	47.1	46.5	44.3	47.9	54.3	57.1					

HENS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1948	(Started)		36.2	37.0	35.5	34.5	33.0	33.1	34.1	35.1	37.9	40.9	35.7
1949	41.8	38.0	38.0	38.0	32.9	29.9	29.4	30.0	30.6	31.1	30.0	30.0	33.3
1950	25.8	25.0	28.1	27.1	23.0	23.0	23.0	24.2					

FRYERS (Heavy Breed)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1948	(Started)		44.6	44.6	41.1	41.0	38.3	38.6	40.1	38.9	39.1	37.8	40.4
1949	34.0	30.2	32.7	34.1	29.5	30.5	29.3	32.5	32.2	32.3	34.1	28.8	31.7
1950	23.4	27.4	34.8	32.2	29.9	30.0	33.3	34.7					

POULTRY AND EGG WHOLESALE PRICES
MIAMI MARKET (January 1, 1939 - August 31, 1950)
WHITE EGGS (Grade A 24 oz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1939	35.1	27.3	24.3	25.0	24.9	Unavailable			33.8	37.2	39.5	36.5	31.5
1940	36.5	35.3	26.0	25.8	25.5	25.8	31.8	35.0	38.4	43.1	40.0	42.9	N
1941	38.3	31.7	28.1	29.0	31.6	34.1	38.6	41.5	43.1	45.0	47.8	48.0	N
1942	43.0	41.0	33.0	35.0	35.0	42.0	47.0	49.0	51.0	52.0C	52.0	52.0	44.4
1943	52.0	44.0	42.0	44.5	44.5	46.5	49.6	53.9	57.5	60.9	59.8	55.2	50.9
1944	51.5	47.5	44.5	44.5	44.5	45.5	50.0	54.5	57.6	58.0	60.5	59.3	51.5
1945	50.8	45.6	43.2	43.2	43.2	45.6	49.9	54.7	58.3	59.2	60.5	59.8	51.2
1946	50.7	45.5	43.2	43.2	43.2	45.8C	50.3	52.0	57.0	63.6	61.0	59.2	50.5
1947	53.1	52.0	52.2	57.6	54.5	53.7I	62.6	66.9	72.4	75.6	76.0	77.9	62.9
1948	66.6	52.0	53.9	56.7	54.0	60.0	62.4	66.7	70.0	71.8	75.4	74.8	63.6
1949	69.0	55.5	53.5	55.1	58.7	60.7	63.9	67.0	69.8	67.4	60.3	52.4	61.1
1950	44.7	39.9	44.6	44.0	41.2	46.0	52.3	54.9					

HENS (Heavy Breed)

1939	24.5	23.6	24.0	23.3	21.5	Unavailable			21.7	24.0	23.5	22.8	23.2
1940	22.5	22.0	22.0	22.0	22.0	22.0	22.0	22.3	22.0	23.5	23.0	23.0	22.4
1941	23.0	23.0	23.0	23.0	23.5	24.5	26.5	25.0	25.0	25.0	25.5	26.0	24.4
1942	27.0	27.0	30.0	30.0	30.0	30.0	30.0	30.0	32.0	32.0C	28.0	28.0	29.5
1943	28.0	28.0	28.0	28.0	28.0	28.0	(- - No quotations on account of consider-						
1944	able price celing confusion - -)						29.7	29.7	29.7	29.7	29.7	29.7	29.7
1945	29.7	28.5	29.9	31.6	29.1	28.7	27.8	27.5	27.5	27.5	27.5	27.5	28.5
1946	27.5	27.5	27.5	27.5	31.4	32.4C	32.1	32.8	38.7	31.9	38.8	40.0	32.3
1947	41.4	40.6	41.9	41.3	40.9	38.3I	35.6	35.0	37.4	38.6	38.7	39.0	39.1
1948	40.9	43.3	44.4	45.0	42.6	39.3	38.5	39.0	38.3	37.8	37.3	36.7	40.3
1949	32.7	40.4	41.2	43.7	38.6	33.1	31.4	33.3	35.6	37.0	35.9	33.6	36.4
1950	30.3	29.8	29.9	29.9	26.5	25.0	25.4	28.8					

FRYERS (Heavy Breed)

1939	24.3	24.7	26.0	25.0	23.4	Unavailable			23.9	25.0	24.5	23.8	24.5
1940	23.5	22.9	23.0	23.0	23.0	23.0	23.0	24.6	25.0	24.1	24.0	24.0	23.6
1941	25.0	25.0	27.0	26.5	25.0	25.0	26.0	25.0	25.0	25.0	26.0	27.0	25.6
1942	30.0	30.0	30.0	30.0	32.0	35.0	35.0	35.0	37.0	37.0C	32.0	32.0	33.0
1943	32.0	32.0	32.0	32.0	32.0	32.0	(- - No quotations on account of consider-						
1944	able price ceiling confusion - -)						33.2	33.2	33.2	33.2	33.2	33.2	33.2
1945	33.2	32.0	33.4	35.2	32.2	32.5	32.0	32.0	32.0	32.0	32.0	32.0	32.5
1946	32.0	32.0	32.0	32.0	35.9	37.1C	38.7	38.5	44.0	46.3	43.4	45.0	38.1
1947	39.2	35.0	39.6	40.0	41.3	43.0I	43.0	43.0	45.7	42.6	39.6	40.5	41.0
1948	45.1	46.2	46.7	49.4	45.3	44.2	42.3	42.0	41.2	40.1	39.4	38.7	43.3
1949	34.7	30.8	33.2	35.6	31.9	30.6	30.0	32.9	32.7	32.5	35.5	29.5	32.4
1950	24.0	30.6	36.1	33.6	30.3	29.5	33.9	35.5					

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS
(For Selected Years)

	1920			1922		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	8,668,000	$ 9,795,000	Bu.	8,888,000	$ 7,110,000
Cotton	Bale	20,000	1,782,000	Bale	28,000	2,902,000
Tobacco	Lbs.	4,200,000	2,041,000	Lbs.	3,330,000	1,551,000
Peanuts (Picked & Threshed)	Lbs.	40,000,000	2,520,000	Lbs.	26,875,000	1,344,000
Sweet Potatoes	Bu.	2,300,000	3,174,000	Bu.	1,680,000	2,184,000
Cow Peas	Bu.	Included in Other Field Crops				
Oats	Bu.	255,000	230,000	Bu.	180,000	137,000
Velvet Beans	Tons	Included in Other Field Crops				
Hay	Tons	83,000	1,768,000	Tons	64,000	1,254,000
Sugar Cane Syrup	Gals.	3,675,000	3,454,000	Gals.	2,320,000	1,067,000
Sugar-Raw	Tons	No Record		Tons	No Record	
Black Strap Molasses	Gals.	No Record		Gals.	No Record	
Pecans	Lbs.	440,000	141,000	Lbs.	880,000	309,000
Total Incomplete			$24,905,000			$17,858,000
Other Field Crops	Misc.		* 2,000,000	Misc.		* 1,400,000

	1924			1925		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,200,000	$ 7,848,000	Bu.	8,262,000	$ 7,684,000
Cotton	Bale	21,000	2,451,000	Bale	43,000	4,561,000
Tobacco	Lbs.	4,091,000	1,916,000	Lbs.	5,810,000	1,743,000
Peanuts (Picked & Threshed)	Lbs.	28,350,000	1,474,000	Lbs.	23,400,000	1,147,000
Sweet Potatoes	Bu.	1,764,000	2,699,000	Bu.	1,340,000	3,386,000
Cow Peas	Bu.	54,000	170,000	Bu.	36,000	129,000
Oats	Bu.	148,000	138,000	Bu.	125,000	85,000
Velvet Beans	Tons	59,000	844,000	Tons	53,000	753,000
Hay	Tons	58,000	1,119,000	Tons	51,000	1,061,000
Sugar Cane Syrup	Gals.	1,350,000	1,350,000	Gals.	1,650,000	1,732,000
Sugar-Raw	Tons	No Record		Tons	No Record	Very Light
Black Strap Molasses	Gals.	No Record		Gals.	No Record	Very Light
Pecans	Lbs.	1,300,000	449,000	Lbs.	1,916,000	609,000
Total Incomplete			$20,458,000			$22,890,000
Other Field Crops	Misc.		* 1,500,000	Misc.		* 1,500,000

	1928			1930		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,073,000	$ 7,427,000	Bu.	5,886,000	$ 5,180,000
Cotton	Bale	22,000	1,091,000	Bale	56,000	2,720,000
Tobacco	Lbs.	8,635,000	2,539,000	Lbs.	9,748,000	2,672,000
Peanuts (Picked & Threshed)	Lbs.	28,175,000	1,352,000	Lbs.	26,520,000	902,000
Sweet Potatoes	Bu.	1,700,000	2,465,000	Bu.	1,360,000	1,646,000
Cow Peas	Bu.	48,000	162,000	Bu.	86,000	233,000
Oats	Bu.	135,000	92,000	Bu.	112,000	87,000
Velvet Beans	Tons	68,000	877,000	Tons	44,000	572,000
Hay	Tons	54,000	1,048,000	Tons	48,000	830,000
Sugar Cane Syrup	Gals.	1,485,000	1,262,000	Gals.	1,530,000	994,000
Sugar-Raw	Tons	1,000	No Record	Tons	27,000	No Record
Black Strap Molasses	Gals.	134,000	No Record	Gals.	2,202,000	No Record
Pecans	Lbs.	2,000,000	545,000	Lbs.	1,150,000	302,000
Total Incomplete			$19,670,000			$16,138,000
Other Field Crops	Misc.		* 2,500,000	Misc.		* 2,000,000

* Estimated by Marketing Bureau

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS (Cont'd.)

(For Selected Years)

Commodity	1932 Unit	1932 Production	1932 Farm Value	1935 Unit	1935 Production	1935 Farm Value
Corn	Bu.	6,350,000	$ 2,921,000	Bu.	7,496,000	$ 5,322,000
Cotton	Bale	18,000	556,000	Bale	31,000	1,576,000
Tobacco	Lbs.	3,310,000	836,000	Lbs.	8,680,000	2,398,000
Peanuts(Picked & Threshed)	Lbs.	24,070,000	1,361,000	Lbs.	38,430,000	1,114,000
Sweet Potatoes	Bu.	1,560,000	1,232,000	Bu.	1,610,000	1,368,000
Cow Peas	Bu.	94,000	99,000	Bu.	88,000	154,000
Oats	Bu.	75,000	28,000	Bu.	112,000	77,000
Velvet Beans	Tons	60,000	255,000	Tons	70,000	700,000
Hay	Tons	41,000	369,000	Tons	52,000	582,000
Sugar Cane Syrup	Gals.	1,760,000	634,000	Gals.	2,660,000	984,000
Sugar-Raw	Tons	37,000	**(1,295,000)	Tons	42,000	**(1,470,000)
Black Strap Molasses	Gals.	3,489,000	248,900	Gals.	3,292,000	395,040
Pecans	Lbs.	625,000	80,000	Lbs.	1,400,000	153,000
Total Incomplete			$ 9,914,900			$16,293,040
Other Field Crops	Misc.		* 1,500,000	Misc.		* 2,000,000

Commodity	1938 Unit	1938 Production	1938 Farm Value	1940 Unit	1940 Production	1940 Farm Value
Corn	Bu.	7,760,000	$ 4,656,000	Bu.	8,418,000	$ 5,893,000
Cotton	Bale	26,000	1,158,000	Bale	21,000	1,102,000
Tobacco	Lbs.	19,720,000	5,325,000	Lbs.	16,328,000	4,552,000
Peanuts(Picked & Threshed)	Lbs.	56,250,000	1,688,000	Lbs.	68,400,000	1,915,000
Sweet Potatoes	Bu.	1,400,000	1,274,000	Bu.	900,000	810,000
Cow Peas	Bu.	48,000	75,000	Bu.	40,000	67,000
Oats	Bu.	140,000	69,000	Bu.	154,000	102,000
Velvet Beans	Tons	57,000	661,000	Tons	59,000	649,000
Hay	Tons	70,000	763,000	Tons	70,000	665,000
Sugar Cane Syrup	Gals.	1,815,000	817,000	Gals.	1,120,000	560,000
Sugar-Raw	Tons	**(920,000)	**(3,680,000)	Tons	**(970,000)	**(4,268,000)
Black Strap Molasses	Gals.	5,497,000	** (657,000)	Gals.	5,170,000	**(1,125,000)
Pecans	Lbs.	3,575,000	309,000	Lbs.	3,564,000	341,000
Total Incomplete			$21,132,000			$22,049,000
Other Field Crops	Misc.		* 2,500,000	Misc.		* 3,000,000

Commodity	1941 Unit	1941 Production	1941 Farm Value	1942 Unit	1942 Production	1942 Farm Value
Corn	Bu.	7,200,000	$ 5,904,000	Bu.	7,766,000	$ 8,154,000
Cotton	Bale	18,000	1,461,000	Bale	17,000	1,534,000
Tobacco	Lbs.	11,711,000	4,052,000	Lbs.	14,778,000	6,808,000
Peanuts(Picked & Threshed)	Lbs.	57,800,000	2,312,000	Lbs.	65,550,000	3,343,000
Sweet Potatoes	Bu.	1,260,000	1,399,000	Bu.	1,122,000	1,560,000
Cow Peas	Bu.	45,000	102,000	Bu.	45,000	122,000
Oats	Bu.	160,000	107,000	Bu.	210,000	176,000
Velvet Beans	Tons	65,000	845,000	Tons	53,000	742,000
Hay	Tons	64,000	813,000	Tons	72,000	979,000
Sugar Cane Syrup	Gals.	1,750,000	962,000	Gals.	1,980,000	1,287,000
Sugar-Raw	Tons	949,000	3,768,000	Tons	949,000	3,072,000
Black Strap Molasses	Gals.	5,157,000	**(928,000)	Gals.	4,100,000	**(750,000)
Pecans	Lbs.	4,672,000	474,000	Lbs.	4,600,000	752,000
Total Incomplete			$23,127,000			$29,279,000
Other Field Crops	Misc.		* 3,000,000	Misc.		* 3,500,000

* Estimated by the State Marketing Bureau

** Figures in parenthesis ( ) are estimates from unofficial sources.

PRODUCTION VOLUME AND FARM VALUE OF FLORIDA PRINCIPAL FIELD CROPS

PRODUCTION VOLUME

Florida Commodity	Units	1941	1942	1943	1944	1945	1946	1947	1948	1949	(Prelim Estimate) 1950
				(Thousands	Omitted)						
Corn	Bu.	7,200	7,766	8,522	7,550	7,755	6,910	8,292	6,910	8,983	9,256
Cotton	Bale	18	17	16	13	8	6	10	15	16	11
Tobacco	Lbs.	11,711	14,778	14,240	20,095	20,082	22,251	6,812	20,846	25,061	23,580
Peanuts(Picked & Threshed)	Lbs.	57,800	65,550	74,800	62,500	66,000	46,500	69,300	85,250	51,255	50,250
Sweet Potatoes	Bu.	1,260	1,122	1,365	1,165	1,024	1,088	1,275	960	980	1,050
Cow Peas	Bu.	45	45	36	32	36	40	36	32	40	#
Oats	Bu.	160	210	300	704	900	720	600	399	288	288
Velvet Beans	Bu.	65	53	62	48	56	44	44	45	58	#
Sugan Cane Syrup	Gals.	1,750	1,960	2,040	2,400	2,090	1,980	2,400	1,980	1,620	#
Sugar Cane for Sugar	Tons	949	949	694	780	1,042	1,037	920	1,010	1,124	1,328
Black Strap Molasses	Gals	5,157*	4,100*	4,100*	5,400*	5,700*	6,711	5,400	7,136	6,896	#
Pecans	Lbs.	4,672	4,600	4,524	5,100	4,234	4,526	2,774	5,475	3,650	4,526
Hay	Tons	64	72	66	65	63	57	63	69	53	50

FARM VALUE

Florida Commodity	Units	1941	1942	1943	1944	1945	1946	1947	1948	1949	1950 # (Prelim Estimate)
				(Thousands	Omitted)						
Corn	Bu.	$ 5,904	$ 8,154	$13,124	$12,231	$13,339	$13,060	$17,662	$11,747	$11,678	
Cotton	Bale	1,461	1,534	1,678	1,343	896	983	1,703	2,303	2,339	
Tobacco	Lbs.	4,052	6,608	9,203	10,421	10,923	15,739	18,188	18,279	17,320	
Peanuts(Picked & Threshed)	Lbs.	2,312	3,343	5,236	4,688	5,280	3,860	6,514	8,440	5,425	
Sweet Potatoes	Bu.	1,399	1,560	3,044	2,821	2,652	2,959	3,226	2,544	2,597	
Cow Peas	Bu.	102	122	141	153	174	220	252	191	224	
Oats	Bu.	107	176	342	887	963	994	990	674	400	
Velvet Beans	Bu.	845	742	1,240	1,152	1,568	1,408	1,408	1,440	2,030	
Hay	Tons	813	979	1,063	1,079	1,147	1,037	1,266	1,270	906	
Sugar Cane Syrup	Gals.	962	1,287	2,040	2,280	2,090	3,168	3,000	1,584	1,134	
Sugar-Raw	Tons	3,768	3,072	3,040	3,487	6,387	7,207	6,302	5,212	7,137	
Black Strap Molasses	Gals.	928	750	750	1,000	1,200	1,200	1,080*	1,472*	1,380*	
Pecans	Lbs.	474	752	1,060	1,143	1,010	1,507	628	605	652	
Group Totals		$23,127	$29,279	$41,961	$42,685	$47,629	$53,342	$62,219	$55,761	$53,222	
Other Field Crops (a)		$ 3,000	$ 3,500	$ 4,500	$ 5,000	$ 5,200	$ 5,500	$ 6,000	$ 5,500	$ 5,000	

* Estimates from unofficial sources. All other production and farm value figures supplied by the U.S. Agricultural Statisticians, B.A.E., Federal Building, Orlando, Florida, except

No estimate by U.S. Bureau of Agricultural Economics as of September 15.

AVERAGE PRICES RECEIVED FOR FARM PRODUCTS BY FARMERS

		FLORIDA			UNITED STATES			
		Farm Products			Farm Products			
Commodity	Unit	Sept.15 1949	Aug. 15 1950	Sept.15 1950	Average Aug.'09 to July'14	Sept.15 1949	Aug. 15 1950	Sept.15 1950
Corn	Bu.	$ 1.40	1.55	1.50	.642	1.16	1.44	1.44
Oats	Bu.	$ 1.20	1.50	1.50	.399	.613	.706	.728
Potatoes	Bu.	$ 2.60	1.50	1.50	.697	a/1.37	1.22	1.05
Sweet Potatoes	Bu.	$ 2.60	2.50	2.50	.878	2.30	2.18	1.92
Cotton	Lb.	¢ 29.8	34.6	39.3	12.4	29.70	36.95	39.98
Cottonseed	Ton	$ 44.00	60.00	76.00	22.55	43.50	70.90	78.80
Tobacco	Lb.	¢ -	49.0	-	10.0	48.7	53.1	55.4
Peanuts	Lb.	¢ 10.4	10.4	10.1	4.8	10.2	11.0	10.9
Cowpeas	Bu.	$ 4.50	5.80	6.00	-	3.29	3.87	3.57
Hogs	Cwt.	$ 18.50	18.50	19.00	7.27	a/19.80	21.60	21.10
Beef Cattle	Cwt.	$ 14.60	19.10	19.90	5.42	a/19.70	24.10	24.70
Veal Calves	Cwt.	$ 17.40	23.80	24.90	6.75	a/21.90	27.40	28.00
Sheep	Cwt.	$ 9.40	11.00	11.00	4.53	a/8.61	10.90	11.70
Lambs	Cwt.	$ 19.50	19.00	19.50	5.88	21.60	24.90	25.60
Milk Cows	Head	$ 135	145	150	48	177	202	209
Chickens	Lb.	¢ 33.5	33.0	33.0	11.4	24.4	25.4	24.5
Turkeys	Lb.	¢ 43.0	46.0	50.0	14.4	34.3	33.8	33.5
Eggs	Doz.	¢ 64.0	50.0	52.0	21.5	a/52.4	38.0	40.4
Butter	Lb.	¢ 64.0	58.0	59.0	25.5	58.1	56.9	57.3
Butterfat	Lb.	¢ 59.0	57.0	57.0	26.3	61.7	60.3	60.9
Milk, wholesale	Cwt.	$a/6.90	a/6.50	6.70	1.60	a/4.02	a/3.75	3.94
Milk, retail b/	Qt.	¢ 22.0	21.7	21.7	6.8	18.5	18.5	18.7
Wool	Lb.	¢ 45.0	50.0	50.0	18.3	a/47.9	58.3	62.2
Hay, baled	Ton	$ 18.90	19.20	17.60	-	21.00	20.20	20.30
Oranges on tree c/	Box	$ -	-	-	-	.68	.72	1.23
Tangerines " c/	Box	$ -	-	-	(Included in Oranges)			
Grapefruit " c/	Box	$ -	-	1.92	-	1.17	.51	1.62
Limes on tree c/	Box	$ 1.02	1.58	.98	-	-	-	-
Honey, ext. retail	Lb.	¢ 23.0	22.0	22.0	-	-	-	-

a/ Revised. b/ Sold by farmers directly to consumers. c/ All citrus, including limes, 1-3/5 bushel box.

FARM VALUE OF PRINCIPAL PRODUCTS

	FLORIDA				UNITED STATES		
	Aug. 1909-July 1914 = 100				Jan.1910-Dec.1914=100		
	Sept.15 1949	Aug. 15 1950	Sept.15 1950	Average Aug.'09 to July'14	Sept.15 1949	Aug. 15 1950	Sept.15 1950
ALL FARM PRODUCTS	220	219	230	100	247	267	272
Grain	160	178	172	-	-	-	-
Food Grain	-	-	-	100	211	224	221
Feed Grain and Hay	-	-	-	100	166	193	194
Cotton and Cottonseed	189	222	255	-	-	-	-
Cotton	-	-	-	100	250	311	336
Dairy Products	208	200	205	100	251	240	248
Poultry and Eggs	248	206	212	100	236	191	196
Meat Animals	298	362	374	100	319	369	372
Citrus	224	195	218	-	-	-	-
Fruits	-	-	-	100	160	200	217
Truck Crops	189	210	210	100	188	164	126
Miscellaneous	312	324	323	-	-	-	-

NOTE: The above tabulations arranged from material furnished by the Bureau of Agricultural Economics, Orlando, Florida.

FLORIDA TOBACCO

Flue Cured (Bright Leaf) Type No. 14

Year	Acreage	Production	Estimated Farm Value				
1932	2,000	1,200,000 Lbs.	$ 132,000	or	11¢	per	Lb.
1933	5,000	3,700,000	444,000	"	12¢	"	"
1934	4,700	3,408,000	682,000	"	20¢	"	"
1935	7,000	6,020,000	1,066,000	"	17.8¢	"	"
1936	8,000	7,200,000	1,584,000	"	22¢	"	"
1937	16,800	14,112,000	2,978,000	"	21.1¢	"	"
1938	16,300	15,892,000	3,226,000	"	20.3¢	"	"
1939	29,500	20,650,000	2,540,000	"	12.3¢	"	"
1940	12,700	11,748,000	2,056,000	"	17.5¢	"	"
1941	11,300	8,192,000	1,745,000	"	21.3¢	"	"
1942	13,000	11,180,000	3,611,000	"	32.3¢	"	"
1943	13,600	11,832,000	4,827,000	"	40.8¢	"	"
1944	19,000	17,100,000	6,190,000	"	36.2¢	"	"
1945	19,400	17,169,000	6,662,000	"	38.8¢	"	"
1946	20,400	19,176,000	9,147,000	"	47.7¢	"	"
1947	22,800	23,256,000	9,070,000	"	39.0¢	"	"
1948	16,400	16,564,000	7,918,000	"	47.8¢	"	"
1949	18,900	20,223,000	7,610,240	"	37.6¢	"	"
1950 Est.	18,900	18,900,000	(9,793,980)*		51.82	"	"

Sun Cured (Filler 1932-1939 Binder, 1936-50) Dark Leaf
(Types 45 and 56)

Year Summer	Acreage	Type	Production	Estimated Farm Value	Per Pound
1932	200	F	140,000	$ 14,000	10¢
1933	100	F	82,000	9,000	11¢
1934	300	F	360,000	43,000	11.9¢
1935	700	F	770,000	104,000	13.5¢
1936	400	F & B	380,000	51,000	13.4¢
1937	700	F & B	784,000	106,000	13.5¢
1938	900	F & B	1,116,000	151.000	13.5¢
1939	1,000	F & B	960,000	127,000	13.2¢
1940	1,000	B	1,300,000	174,000	13.4¢
1941	600	B	450,000	65,000	14.4¢
1942	600	B	630,000	110,000	17.5¢
1943	200	B	166,000	37,000	22.0¢
1944	100	B	70,000	19,000	27.0¢
1945	100	B	93,000	31,000	33.0¢
1946	100	B	105,000	58,000	55.0¢
1947	200	B	140,000	66,000	47.0¢
1948	100	B	70,000	42,000	60.0¢
1949	100	B	85,000	(Estimates Discontinued)	

1950 Less than 100 Acres. No importance, practically discontinued.

NOTE: F: Filler (Type 45) discontinued after 1939. B: Binder (Type 56) started in 1936 and continued to date.

Shade Grown-Air Cured (Dark Leaf) Wrapper Type 62

Year	Acreage	Production	Estimated Farm Value				
1932	2,000	1,970,000 Lbs.	$ 690,000	or	35¢	per	Lb.
1933	1,100	990,000	317,000	"	32¢	"	"
1934	1,600	1,424,000	854,000	"	59.9¢	"	"
1935	2,100	1,890,000	1,228,000	"	65¢	"	"
1936	2,000	2,050,000	1,414,000	"	69¢	"	"
1937	2,100	1,890,000	1,304,000	"	70¢	"	"
1938	2,400	2,712,000	1,953,000	"	72¢	"	"
1939	2,500	2,150,000	1,570,000	"	73¢	"	"
1940	3,200	3,280,000	2,296,000	"	70¢	"	"
1941	3,300	3,069,000	2,240,000	"	73¢	"	"
1942	2,800	2,968,000	2,879,000	"	$1.04	"	"
1943	2,600	2,912,000	3,087,000	"	1.49	"	"
1944	2,600	2,925,000	4,212,000	"	1.44	"	"
1945	2,400	2,820,000	4,230,000	"	1.50	"	"
1946	3,000	2,970,000	6,534,000	"	2.20	"	"
1947	3,300	3,416,000	9,052,000	"	2.65	"	"
1948	3,600	4,212,000	10,319,000	"	2.45	"	"
1949	4,100	4,838,000	9,676,000	"	2.00	"	"
1950	3,900	4,680,000	(Not Available)				

NOTE: Flue Cured Type No. 14 is generally known as cigarette tobacco.
Shade Grown Type 62 is generally known as cigar wrapper tobacco.
Sun Cured Type 56 is generally known as cigar filler tobacco.
* Farm value based on production estimate and auction price average.
(Auction Volume and Value on next page.)

FLORIDA AUCTION SALES

(Flue Cured Tobacco - Type 14)

Revised figures of the Tobacco Branch, P.M.A., U.S. Department of Agriculture

	Producer's Sales			Resales		
Season	Pounds	Value	Average(1)	Pounds	Value	Average
1940	7,903,700	$1,300,069	$16.45	689,982	$107,670	$15.60
1941	5,726,227	1,211,684	21.16	707,736*	143,309*	20.25*
1942	7,269,574	2,381,502	32.76	748,650	227,892	30.43
1943	8,110,475	3,308,024	40.79	1,135,708	470,026	41.39
1944	12,330,566	4,496,293	36.46	1,255,424	417,923	33.29
1945	12,148,104	4,742,528	39.04	1,219,300	452,203	37.09
1946	13,192,482	6,353,484	48.16	1,595,702	706,444	44.27
1947	16,596,141	6,510,858	39.23	2,020,091	740,141	36.64
1948	12,346,106	5,896,173	47.76	1,698,258	782,141	46.06
1949	16,262,984	6,129,689	37.69	1,707,535	579,258	33.92
1950	13,773,151	7,137,519	51.82	1,704,686	837,736	49.14

*Estimated (1) Average Price per 100 Lbs.

1949-50 Sales by Individual Markets

		Producers		Resales	
		Pounds	Value	Pounds	Value
Jasper	1949)	3,122,799	$1,131,006	369,408	$114,939
	1950)	2,612,372	1,378,365	388,442	204,666
Lake City	1949)	4,483,162	1,714,472	367,016	117,590
	1950)	4,099,281	2,077,067	268,832	106,186
Live Oak	1949)	8,657,023	3,284,211	971,111	346,729
	1950)	7,061,498	3,682,087	1,047,412	526,885
Totals	1949	16,262,984	$6,129,689	1,707,535	$579,258
	1950	13,773,151	7,137,519	1,704,686	837,736

ALL FLORIDA TOBACCO

Season	Acres	Production Pounds	Farm Value	Price per Lb.
1939	33,000	23,760,000	$ 4,237,000	$ .178
1940	16,900	16,328,000	4,526,000	.277
1941	15,200	11,711,000	4,050,000	.345
1942	16,400	14,778,000	6,600,000	.446
1943	16,400	14,910,000	7,951,000	.533
1944	21,700	20,095,000	10,421,000	.518
1945	21,900	20,082,000	10,923,000	.543
1946	23,500	22,251,000	15,732,000	.707
1947	26,300	26,812,000	18,188,000	.678
1948	20,100	20,846,000	17,016,000	.816
1949	23,000	25,061,000	17,286,000	.689
1950	22,800	24,903,000	(Not Complete)	-

Cigars, Cigarettes, Chewing Tobacco, Smoking Tobacco, and Snuff Manufactured in the United States, by Calendar Years, 1943-48

	Cigars		Cigarettes	
	Large	Small	Large	Small
Year	Thousands	Thousands	Thousands	Thousands
1943	5,363,027	125,480	6,111	296,173,333
1944	5,198,679	123,340	26,870	323,583,888
1945	5,274,675	98,167	82,416	332,164,670
1946	5,617,700	92,262	1,658	350,038,093
1947	5,487,656	79,670	537	369,682,769
1948	5,700,000	90,000	700	387,000,000

	Chewing Tobacco				Smoking Tobacco	Snuff	Total Chewing, Smoking, and Snuff Tobacco
Year	Plug 1,000 Lb.	Twist 1,000 Lb.	Fine-Cut 1,000 Lb.	Scrap 1,000 Lb.	1,000 Lb.	1,000 Lb.	1,000 Lb.
1943	58,945	6,257	4,460	51,414	162,834	43,179	327,089
1944	61,655	6,498	4,092	52,867	139,861	41,962	306,935
1945	59,704	6,723	3,970	47,748	168,523	43,834	330,502
1946	51,810	5,773	3,756	46,117	106,414	39,361	253,231
1947	47,306	5,152	3,793	42,189	104,680	39,163	242,283
1948	45,345	5,635	3,200	42,350	107,575	40,810	244,915

Compiled from annual and monthly reports of the Commissioner of Internal Revenue, except cigars and cigarettes, which are estimates by the Tobacco Branch, PMA. No later information immediately available for 1949 and 1950.

ACREAGE, YIELD, PRODUCTION AND VALUE
FLORIDA VEGETABLES AND MISCELLANEOUS FRUITS
1949-50 SEASON

FLORIDA	Acreage Planted	Acreage For Harvest	Yield Units	Production Total Units	Abandoned A Units	Production of Value Units	Season Avg FOB Price PerUnit	Total Value Marketed Dollars
SNAP BEANS			Bu.					
Fall (Fresh)	26,000	16,000	90	1,440,000		1,440,000	$2.95	$ 4,248,000
(Process)	2,000	2,000	90	180,000		180,000	1.40	252,000
(Total)	28,000	18,000	90	1,620,000		1,620,000	2.78	4,500,000
Winter (Fresh)	34,500	28,500	107	3,050,000		3,050,000	2.60	7,930,000
(Process)	2,500	2,500	107	268,000		268,000	1.50	402,000
(Total)	37,000	31,000	107	3,318,000		3,318,000	2.51	8,332,000
Spring (Fresh)	25,300	20,000	100	2,000,000	286,000	1,714,000	2.30	3,942,000
(Process)	4,300	4,300	100	430,000		430,000	1.35	580,000
(Total)	29,600	24,300	100	2,430,000	286,000	2,144,000	2.11	4,522,000
TOTAL FRESH	85,800	64,500	101	6,490,000	286,000	6,204,000	2.49	16,120,000
TOTAL PROCESS	8,800	8,800	100	878,000		878,000	1.41	1,234,000
TOTAL ALL	94,600	73,300	101	7,368,000	286,000	7,082,000	2.45	$17,354,000
LIMA BEANS			Bu.					
Winter	1,600	1,400	70	98,000		98,000	3.30	323,000
Spring	2,100	2,000	80	160,000		160,000	2.40	384,000
TOTAL	3,700	3,400	76	258,000		258,000	2.74	$ 707,000
CABBAGE			Tons					
Winter	17,500	17,000	10.8	183,600	56,900	126,700	30.50	3,864,000
			Crt.					
CAULIFLOWER	850	850	300	255,000		255,000	1.85	472,000
CELERY			Crt.					
Winter	6,000	5,800	630	3,654,000		3,654,000	1.85	6,760,000
Spring	3,700	3,700	680	2,516,000		2,516,000	2.20	5,535,000
TOTAL	9,700	9,500	649	6,170,000		6,170,000	1.99	$12,295,000
			Crt.					
CORN, GREEN	33,000	29,000	120	3,480,000	530,000	2,950,000	2.15	6,342,000
CUCUMBERS			Bu.					
Fall	4,400	4,100	180	738,000		738,000	2.30	1,697,000
Winter	2,200	2,100	200	420,000		420,000	3.70	1,554,000
Spring-Fresh	8,700	7,200	135	972,000		972,000	4.05	3,937,000
" Pickling	900	800	75	60,000		60,000	1.25	75,000
TOTAL	16,200	14,200	154	2,190,000		2,190,000	3.32	$ 7,263,000
EGGPLANT			Bu.					
Fall	650	550	115	63,000		63,000	2.10	132,000
Winter	950	900	375	338,000		338,000	1.65	558,000
Spring	1,000	1,000	325	325,000		325,000	1.50	488,000
TOTAL	2,600	2,450	296	726,000		726,000	1.62	$ 1,178,000
ESCAROLE			Bu.					
Winter	3,800	3,300	450	1,485,000	145,000	1,340,000	.95	1,273,000
LETTUCE			Crt.					
Winter	2,400	2,200	160	352,000	64,000	288,000	2.80	806,000
PEAS, ENGLISH			Bu.					
Winter	400	400	60	24,000		24,000	2.80	67,000
PEPPERS			Bu.					
Fall	1,200	950	195	185,000		185,000	1.85	342,000
Winter	4,800	4,200	400	1,680,000		1,680,000	1.90	3,192,000
Spring	8,600	8,600	250	2,150,000	175,000	1,975,000	1.85	3,654,000
TOTAL	14,600	13,750	292	4,015,000	175,000	3,840,000	1.87	$ 7,188,000
POTATOES			Bu.					
Winter	10,400	10,000	240	2,400,000		2,400,000	1.90	4,560,000
Spring	13,200	13,200	225	2,970,000		2,970,000	1.70	5,049,000
TOTAL	23,600	23,200	231	5,370,000		5,370,000	1.79	$ 9,609,000
SQUASH			Bu.					
Fall	2,400	2,400	70	168,000		168,000	2.15	361,000
Winter	4,000	3,700	95	352,000		352,000	2.75	968,000
Spring	4,000	4,000	85	340,000		340,000	2.15	731,000
TOTAL	10,400	10,100	85	860,000		860,000	2.40	$ 2,060,000

A - Abandoned because of poor market prices at certain times during the season.

ACREAGE, YIELD, PRODUCTION AND VALUE FLORIDA VEGETABLES AND MISCELLANEOUS FRUITS 1949-50 SEASON

FLORIDA	Acreage Planted	Acreage For Harvest	Yield Units	Production Total Units	Abandoned A Units	Production of Value Units	Season Avg FOB Price PerUnit	Total Value Marketed Dollars
TOMATOES			Bu.					
Fall(Fresh)	8,000	8,000	145	1,160,000		1,160,000	$4.60	$ 5,336,000
(Process)	1,000	1,000	145	145,000		145,000	.60	87,000
(Total)	9,000	9,000	145	1,305,000		1,305,000	4.16	5,423,000
Winter(Fresh)	14,000	13,500	185	2,498,000		2,498,000	4.35	10,866,000
(Process)	500	500	185	92,000		92,000	.60	55,000
(Total)	14,500	14,000	185	2,590,000		2,590,000	4.22	10,921,000
Spring(Fresh)	18,500	18,000	155	2,790,000		2,790,000	5.65	15,764,000
(Process)	1,500	1,500	155	232,000		232,000	.60	139,000
(Total)	20,000	19,500	155	3,022,000		3,022,000	5.26	15,903,000
TOTAL FRESH	40,500	39,500	163	6,448,000		6,448,000	4.96	31,966,000
TOTAL PROCESS	3,000	3,000	156	469,000		469,000	.50	281,000
TOTAL ALL	43,500	42,500	163	6,917,000		6,917,000	4.66	32,247,000
TOTAL VEGS.	276,850	245,150	(Packed Value per Acre Harvested $419.00)					$102,725,000
CANTALOUPES			Crt.					
Spring	1,600	1,400	60	84,000		84,000	2.25	$ 189,000
)			(107)	36pt. (576,000)		(576,000)	(6.49)	-
STRAWBERRIES)	5,400	5,400	80	24qt. (432,000)		432,000	8.65	3,737,000
			Melons				Per Melon	
WATERMELONS	65,000	63,000	300	18,900,000	4,900,000	14,000,000	.39½	5,530,000
TOTAL MISCL. FRUITS	72,000	69,800	(Packed Value per Acre Harvested $135					9,456,000
GRAND TOTAL	348,850	314,950	(Packed Value per Acre Harvested $356)					$112,181,000

A - Abandoned because of poor market price at certain times during the season.

- -

ACREAGE, YIELD, PRODUCTION AND VALUE OF ALL FRUITS AND VEGETABLES -- 1949-50 SEASON

	Acres Planted	Abandoned	Acres Harves.	Yield per Acre	Unit	Production Units(000)			Price per Unit	Total Value
						Total	Abandoned	Used		
Beans	94,600	21,300	73,300	101	Bu.	7,368	286	7,082	$2.45	$ 17,354,000
Limas	3,700	300	3,400	76	Bu.	258	-	258	2.74	707,000
Cabbage	17,500	500	17,000	10.8	Ton	184	57	127	30.50	3,864,000
Cauliflower	850	-	850	300	Crt.	255	-	255	1.85	472,000
Celery	9,700	200	9,500	649	½Crt.	6,170	-	6,170	1.99	12,295,000
Corn,Sweet	33,000	4,000	29,000	120	Crt.	3,480	530	2,950	2.15	6,342,000
Cucumbers	16,200	2,000	14,200	154	Bu.	2,190	-	2,190	3.32	7,263,000
Eggplant	2,600	150	2,450	296	Bu.	726	-	726	1.62	1,178,000
Escarole	3,800	500	3,300	450	Bu.	1,485	145	1,340	.95	1,273,000
Lettuce	2,400	200	2,200	160	Crt.	352	64	288	2.80	806,000
Peas, Eng.	400	-	400	60	Bu.	24	-	24	2.80	67,000
Peppers	14,600	850	13,750	292	Bu.	4,015	175	3,840	1.87	7,188,000
Potatoes,Coml.	23,600	400	23,200	231	Bu.	5,370	-	5,370	1.79	9,609,000
Squash	10,400	300	10,100	85	Bu.	860	-	860	2.40	2,060,000
Tomatoes	43,500	1,000	42,500	163	Bu.	6,917	-	6,917	4.66	32,247,000
TOTAL VEGS.	276,850	31,700	245,150	(Packed Value per Acre Harvested $419)						$102,725,000
Cantaloupes	1,600	200	1.400	60	Crt.	84	-	84	2.25	$ 189,000
Strawberries)					(36 pt.)	576	-	576	6.49	
")	5,400	-	5,400	80	24 qt.Cr	432	-	432	8.65	3,737,000
Watermelons	65,000	2,000	63,000	300	Melon	18,900	4,900	14,000	.39½	5,530,000
TOT.MISCL.FR.	72,000	2,200	69,800	(Packed Value per Acre Harvested $135)						$ 9,456,000
TOT.VEGS.AND MISCL.FRTS.	348,850	33,900	314,950	(Packed Value per Acre Harvested $356)						$112,181,000
Oranges	-	-	300,900	194*	Box	58,500	-	58,500	$2.84	$166,271,399
Grapefruit	-	-	98,500	246*	"	24,200	-	24,200	2.53	61,332,727
Tangerines	-	-	24,100	207*	"	5,000	-	5,000	2.87	14,360,329
TOTAL CITRUS	-	-	423,500	207*	"	87,700	-	87,700	2.76	241,964,455
			Citrus(Packed Value per Acre Harvested $571)							
GRAND TOTAL	-	-	738,450	(Packed Value per Acre Harvested $479)						$354,145,455

* On basis of 66 trees to acre, box yields would be: Oranges 194, Grapefruit 246, Tangerines 207. All 207 boxes.

Note: The above does not include an estimated 10,000-15,000 acres of miscellaneous vegetables such as radishes, collards, turnips, okra, etc., and does not include acreage figures for avocados, limes, mangoes and other miscellaneous fruits. The official acreage, volume and value figures supplied by the U.S. Bureau of Agricultural Economics, Orlando, Florida.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS 1947-48, 1948-49 & 1949-50.

Source: U.S. Agricultural Statisticians, Orlando, Florida.

	1947-48				1948-49				1949-50			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
ALACHUA												
Beans	75	-	1250	1325	100	-	1600	1700	50	-	1600	1650
Limas	-	-	750	750	-	-	900	900	-	-	1000	1000
Cabbage	-	200	-	200	-	-	-	125	-	-	-	150
Celery	-	-	100	100	-	-	100	100	-	50	120	170
Corn,Green	-	-	-	200	-	-	-	300	-	-	450	450
Cucumbers	25	-	1200	1225	25	-	1700	1725	25	-	1450	1475
Eggplant	50	-	100	150	50	-	100	150	25	-	75	100
Lettuce	-	-	-	50	-	-	-	40	-	-	-	25
Peas,English	-	75	-	75	-	-	-	20	-	-	-	25
Peppers	-	-	550	550	-	-	800	800	-	-	800	800
Potatoes	-	-	1500	1500	-	-	400	400	-	-	550	550
Squash	50	-	100	150	225	-	200	425	200	-	200	400
Tomatoes	-	-	100	100	-	-	-	-	-	-	-	-
Total Vegs.	200	275	5650	6375	400	-	5800	6685	300	50	6245	6795
Cantaloupes	-	-	450	450	-	-	-	400	-	-	-	600
Watermelons	-	-	4700	4700	-	-	-	6200	-	-	-	5900
Grand Total	200	275	10800	11525	400	-	5800	13285	300	50	6245	13295
BAKER												
Corn,Green	-	-	-	-	-	-	-	100	-	-	-	100
BRADFORD												
Beans	25	-	75	100	-	-	200	200	-	-	250	250
Limas	-	-	50	50	-	-	75	75	-	-	150	150
Cabbage	-	50	-	50	-	-	-	25	-	-	-	25
Corn,Green	-	-	-	250	-	-	-	600	-	-	-	650
Cucumbers	-	-	75	75	25	-	100	125	25	-	75	100
Peppers	-	-	-	-	-	-	75	75	-	-	250	250
Potatoes	-	-	100	100	-	-	75	75	-	-	80	80
Squash	-	-	50	50	25	-	75	100	-	-	150	150
Total Vegs.	25	50	350	675	50	-	600	1275	25	-	955	1655
Cantaloupes	-	-	-	25	-	-	-	25	-	-	-	-
Strawberries	-	-	200	200	-	-	-	400	-	-	-	550
Watermelons	-	-	50	50	-	-	-	100	-	-	-	150
Grand Total	25	50	600	950	50	-	600	1800	25	-	955	2355
BREVARD												
Corn,Green	-	-	-	-	-	-	50	50	-	-	-	150
Squash	-	-	-	-	50	-	-	50	50	-	350	400
Tomatoes	-	-	50	50	200	-	200	400	250	-	50	300
Total Vegs.	-	-	50	50	250	-	250	500	300	-	400	850
Watermelons	-	-	50	50	-	-	-	150	-	-	-	-
BROWARD												
Beans	2400	11800	650	14850	3500	8800	-	12300	2600	9000	500	12100
Limas	-	175	150	325	-	100	50	150	-	200	100	300
Cabbage	-	-	-	50	-	-	-	50	-	-	-	-
Corn,Green	-	-	-	-	-	-	50	50	-	-	-	100
Cucumbers	300	300	100	700	150	125	50	325	125	200	-	325
Eggplant	-	100	350	450	-	225	125	350	25	250	100	375
Peas,English	-	-	-	-	-	-	-	-	-	-	-	25
Peppers	-	1000	675	1675	-	1100	400	1500	150	1900	500	2550
Squash	250	850	250	1350	250	900	200	1350	350	1000	-	1350
Tomatoes	-	1000	400	1400	-	1000	500	1500	350	850	400	1600
Total Vegs	2950	15225	2575	20800	3900	12250	1375	17575	3600	13400	1600	18725
Watermelons	-	-	150	150	-	-	-	50	-	-	-	-
CALHOUN												
Cucumbers	-	-	300	300	-	-	225	225	-	-	75	75
Peppers	-	-	-	-	-	-	-	-	-	75	-	75
Watermelons	-	-	150	150	-	-	-	700	-	-	-	900
Grand Total	-	-	450	450	-	-	225	925	-	75	75	1050
CHARLOTTE												
Cucumbers	50	-	50	100	50	50	-	100	75	75	100	250
Peppers	-	-	50	50	25	25	-	50	25	-	-	25
Squash	-	-	-	-	25	-	-	25	25	-	-	25
Tomatoes	-	-	50	50	25	25	-	50	-	-	-	-
Grand Total	50	-	150	200	125	100	-	225	125	75	100	300

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1947-48				1948-49				1949-50			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
CITRUS												
Watermelons	-	-	150	150	-	-	-	250	-	-	-	900
CLAY												
Cabbage	-	400	-	400	-	-	-	300	-	-	-	350
Potatoes	-	-	50	50	-	-	-	-	-	-	40	40
Total Vegs.	-	400	50	450	-	-	-	300	-	-	40	390
COLLIER												
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	50
Cucumbers	200	150	50	400	100	200	-	300	150	600	350	1100
Squash	-	-	-	-	-	25	-	25	-	100	-	100
Tomatoes	-	275	500	775	-	600	450	1050	600	400	750	1750
Total Vegs.	200	425	550	1175	100	625	450	1375	750	1100	1100	3000
Cantaloupes	-	-	-	-	-	-	-	-	-	-	-	50
Watermelons	-	-	50	50	-	-	-	50	-	-	-	600
Grand Total	200	425	600	1225	100	825	450	1425	750	1100	1100	3650
COLUMBIA												
Cabbage	-	50	-	50	-	-	-	75	-	-	-	125
Corn, Green	-	-	-	400	-	-	-	550	-	-	-	350
Cucumbers	-	-	100	100	-	-	75	75	-	-	75	75
Squash	-	-	-	-	-	-	-	-	-	50	-	50
Total Vegs.	-	50	100	550	-	-	75	700	-	50	75	600
Cantaloupes	-	-	25	25	-	-	-	25	-	-	-	-
Watermelons	-	-	300	300	-	-	-	600	-	-	-	800
Grand Total	-	50	425	875	-	-	75	1325	-	50	75	1400
DADE												
Beans	200	2500	300	3000	-	3000	-	3000	-	5400	800	6200
Cabbage	-	250	-	250	-	-	-	250	-	-	-	300
Carrots	-	50	-	50	-	-	-	75	-	-	-	-
Corn, Green	-	-	-	65	-	-	-	350	-	-	-	750
Cucumbers	-	50	75	125	-	125	-	125	-	250	-	250
Eggplant	-	-	-	-	-	25	-	25	-	25	-	25
Peppers	-	-	-	-	-	150	25	175	-	-	-	-
Potatoes	-	5800	-	5800	-	6700	-	6700	-	6900	-	6900
Squash	50	500	50	600	50	700	50	800	-	1200	100	1300
Tomatoes	200	6450	2250	8900	50	10200	1750	12000	300	11200	1000	12500
Total Vegs.	450	15600	2675	18790	100	20900	1825	23500	300	24975	1900	28225
Strawberries	-	-	-	-	-	-	-	50	-	-	-	50
DE SOTO												
Corn, Green	-	-	-	50	-	-	-	-	-	-	-	-
Cucumbers	-	-	100	100	100	-	40	140	200	-	100	300
Tomatoes	-	-	200	200	-	-	150	150	25	-	300	325
Total Vegs.	-	-	300	350	100	-	190	290	225	-	400	625
Watermelons	-	-	400	400	-	-	-	550	-	-	-	850
Grand Total	-	-	700	750	100	-	190	840	225	-	400	1475
DIXIE												
Watermelons	-	-	100	100	-	-	-	200	-	-	-	100
DUVAL												
Cabbage	-	100	-	100	-	-	-	100	-	-	-	100
ESCAMBIA												
Beans	-	-	100	100	-	-	100	100	-	-	100	100
Cabbage	-	50	-	50	-	-	-	-	-	-	-	150
Cucumbers	-	-	-	-	-	-	200	200	-	-	25	25
Potatoes	-	-	600	600	-	-	500	500	-	-	750	750
Total Vegs.	-	50	700	750	-	-	800	800	-	-	875	1025
FLAGLER												
Cabbage	-	1500	-	1500	-	-	-	1750	-	-	-	1750
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	150
Cucumbers	-	-	50	50	-	-	25	25	-	-	-	-
Peas, English	-	25	-	25	-	-	-	-	-	-	-	25
Potatoes	-	-	1950	1950	-	-	2100	2100	-	-	2300	2300
Total Vegs.	-	1525	2000	3525	-	-	2125	3875	-	-	2300	4225

1949-50 figures subject to revision as of September 20, 1950.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1947-48				1948-49				1949-50			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
GADSDEN												
Beans	150	-	200	350	200	-	200	400	400	-	200	600
Cabbage	-	50	-	50	-	-	-	-	-	-	-	50
Total Vegs.	150	50	200	400	200	-	200	400	400	-	200	650
Watermelons	-	-	100	100	-	-	-	-	-	-	-	-
GILCHRIST												
Cantaloupes	-	-	-	-	-	-	-	25	-	-	-	-
Watermelons	-	-	6200	6200	-	-	-	8500	-	-	-	9900
GLADES												
Beans	-	-	-	-	-	-	-	-	-	-	50	50
Cabbage	-	1500	-	1500	-	-	-	1200	-	-	-	1400
Corn, Green	-	-	-	100	-	-	-	500	-	-	-	600
Lettuce	-	325	-	325	-	-	-	200	-	-	-	400
Tomatoes	150	160	550	860	300	-	500	800	300	-	550	850
Total Vegs.	150	1985	550	2785	300	-	500	2700	300	-	600	3300
HAMILTON												
Cabbage	-	50	-	50	-	-	-	100	-	-	-	100
Corn, Green	-	-	-	-	-	-	-	100	-	-	-	100
Cucumbers	-	-	350	350	-	-	75	75	-	-	175	175
Total Vegs.	-	50	350	400	-	-	75	275	-	-	175	375
Cantaloupes	-	-	50	50	-	-	-	-	-	-	-	75
Watermelons	-	-	350	350	-	-	-	450	-	-	-	500
Grand Total	-	50	750	800	-	-	75	725	-	-	175	950
HARDEE												
Beans	50	-	-	50	-	-	50	50	-	-	-	-
Cabbage	-	150	-	150	-	-	-	-	-	-	-	-
Corn, Green	-	-	-	200	-	-	-	300	-	-	-	650
Cucumbers	1200	-	900	2100	800	-	525	1325	1000	-	800	1800
Eggplant	75	-	-	75	150	-	25	175	125	-	25	150
Peppers	125	-	50	175	350	-	50	400	200	-	50	250
Squash	50	-	50	100	25	-	100	125	150	-	100	250
Tomatoes	-	-	1850	1850	100	-	1300	1400	75	-	2200	2275
Total Vegs.	1500	150	2850	4700	1425	-	2050	3775	1550	-	3175	5375
Strawberries	-	325	-	325	-	-	-	250	-	-	-	350
Watermelons	-	-	75	75	-	-	-	100	-	-	-	300
Grand Total	1500	475	2925	5100	1425	-	2050	4125	1550	-	3175	6025
HENDRY												
Cucumbers	200	150	50	400	200	150	-	350	100	-	-	100
Squash	25	50	-	75	25	25	-	50	25	75	-	100
Tomatoes	-	125	200	325	75	400	200	675	400	300	350	1050
Total Vegs.	225	325	250	800	300	575	200	1075	525	375	350	1250
Watermelons	-	-	50	50	-	-	-	50	-	-	-	-
HERNANDO												
Eggplant	15	-	-	15	50	-	-	50	-	-	-	-
Watermelons	-	-	-	-	-	-	-	100	-	-	-	100
HIGHLANDS												
Beans	-	-	500	500	50	-	350	400	75	-	150	225
Cabbage	-	-	-	25	-	-	-	-	-	-	-	-
Carrots	-	25	-	25	-	-	-	-	-	-	-	-
Cucumbers	-	-	50	50	-	-	50	50	100	-	100	200
Peas, English	-	-	-	25	-	-	-	20	-	-	-	-
Tomatoes	-	-	200	200	150	-	100	250	-	-	-	-
Total Vegs.	-	25	750	825	200	-	500	720	175	-	250	425
Watermelons	-	-	50	50	-	-	-	-	-	-	-	50
HOLMES												
Cucumbers	-	-	150	150	-	-	100	100	-	-	100	100
Watermelons	-	-	400	400	-	-	-	750	-	-	-	850
INDIAN RIVER												
Cucumbers	-	-	-	-	25	-	-	25	-	-	-	-
Squash	-	-	-	-	25	-	-	25	25	-	-	25
Tomatoes	50	40	300	390	1000	-	1400	2400	1500	-	1700	3200
Total Vegs.	50	40	300	390	1050	-	1400	2450	1525	-	1700	3225
Watermelons	-	-	150	150	-	-	-	200	-	-	-	400

1949-50 figures subject to revision as of September 20, 1950.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1947-48				1948-49				1949-50			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
HILLSBOROUGH												
Beans	200	-	875	1075	250	-	1100	1350	150	-	650	800
Limas	-	-	100	100	-	-	100	100	-	-	100	100
Cabbage	-	350	-	350	-	-	-	300	-	-	-	300
Cauliflower	-	225	-	225	-	-	-	200	-	-	-	350
Corn, Green	-	-	-	650	-	-	-	2350	-	-	-	2550
Cucumbers	250	-	1075	1325	475	-	625	1100	350	-	700	1050
Eggplant	95	-	750	845	50	-	650	700	75	-	325	400
Escarole	-	50	-	50	-	-	-	40	-	-	-	75
Lettuce	-	225	-	225	-	-	-	250	-	-	-	250
Peas, English	-	100	-	100	-	-	-	60	-	-	-	100
Peppers	10	-	3630	3640	50	-	2715	2765	-	-	3300	3300
Potatoes	-	-	150	150	-	-	375	375	-	-	250	250
Squash	100	-	1050	1150	250	-	800	1050	275	-	1100	1375
Tomatoes	450	250	1450	2150	850	150	2100	3100	1000	400	1950	3350
Total Vegs.	1105	1200	9080	12035	1925	150	8465	13740	1850	400	8375	14250
Cantaloupes	-	-	-	50	-	-	-	25	-	-	-	-
Strawberries	-	3100	-	3100	-	-	-	2750	-	-	-	3900
Watermelons	-	-	600	600	-	-	-	800	-	-	-	900
Grand Total	1105	4300	9680	15785	1925	150	8465	17315	1850	400	8375	19050
JACKSON												
Cucumbers	-	-	800	800	-	-	600	600	-	-	225	225
Watermelons	-	-	1000	1000	-	-	-	1350	-	-	-	1550
Grand Total	-	-	1800	1800	-	-	600	1950	-	-	225	1775
JEFFERSON												
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	300
Watermelons	-	-	2400	2400	-	-	-	2000	-	-	-	2050
LAFAYETTE												
Watermelons	-	-	1000	1000	-	-	-	1000	-	-	-	1500
LAKE												
Beans	150	-	150	300	75	-	250	325	50	-	300	350
Cabbage	-	200	-	200	-	-	-	175	-	-	-	125
Celery	-	125	500	625	-	135	745	880	-	125	575	700
Corn, Green	-	-	-	-	-	-	-	300	-	-	-	500
Cucumbers	50	-	250	300	150	-	200	350	75	-	150	225
Eggplant	-	-	25	25	25	-	25	50	-	-	-	-
Lettuce	-	25	-	25	-	-	-	-	-	-	-	-
Peppers	30	-	200	230	20	-	125	145	-	-	250	250
Squash	-	-	50	50	-	-	50	50	-	-	50	50
Tomatoes	-	-	200	200	-	-	250	250	-	-	250	250
Total Vegs.	230	350	1375	1955	270	135	1645	2525	125	125	1575	2450
Cantaloupes	-	-	-	50	-	-	-	50	-	-	-	-
Watermelons	-	-	6200	6200	-	-	-	6500	-	-	-	6800
Grand Total	230	350	7575	8205	270	135	1645	9075	125	125	1575	9250
LEE												
Corn, Green	-	-	-	100	-	-	-	200	-	-	-	300
Cucumbers	300	200	50	550	400	250	125	775	300	150	-	450
Eggplant	15	100	100	215	50	250	50	350	50	125	-	175
Peppers	50	250	50	350	75	300	-	375	100	200	-	300
Potatoes	-	950	-	950	-	1050	80	1130	-	1700	-	1700
Squash	75	250	-	325	50	150	-	200	50	100	-	150
Tomatoes	75	150	-	225	50	100	-	150	150	150	-	300
Total Vegs.	515	1900	200	2715	625	2100	255	3160	650	2425	-	3375
Cantaloupes	-	-	-	-	-	-	-	60	-	-	-	-
Watermelons	-	-	50	50	-	-	-	100	-	-	-	-
Grand Total	515	1900	250	2765	625	2100	255	3340	650	2425	-	3375
LEON												
Watermelons	-	-	50	50	-	-	-	100	-	-	-	300

1949-50 figures subject to revision as of September 20, 1950.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1947-48				1948-49				1949-50			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
LEVY												
Beans	-	-	-	-	-	-	-	-	-	-	100	100
Limas	-	-	-	-	-	-	50	50	-	-	-	-
Cabbage	-	25	-	25	-	-	-	25	-	-	-	25
Corn, Green	-	-	-	100	-	-	-	-	-	-	-	50
Cucumbers	-	-	50	50	-	-	-	-	-	-	25	25
Peppers	-	-	-	-	-	-	50	50	-	-	50	50
Squash	-	-	50	50	-	-	50	50	50	-	50	100
Tomatoes	-	-	50	50	-	-	50	50	-	-	-	-
Total Vegs.	-	25	150	275	-	-	200	225	50	-	225	350
Cantaloupes	-	-	75	75	-	-	-	75	-	-	-	75
Watermelons	-	-	2200	2200	-	-	-	4200	-	-	-	3000
Grand Total	-	25	2425	2550	-	-	200	4500	50	-	225	3425
MADISON												
Cucumbers	-	-	-	-	-	-	125	125	-	-	100	100
Cantaloupes	-	-	50	50	-	-	-	25	-	-	-	-
Watermelons	-	-	1500	1500	-	-	-	2300	-	-	-	2450
Grand Total	-	-	1550	1550	-	-	125	2450	-	-	100	2550
MANATEE												
Beans	200	-	250	450	200	-	250	450	150	-	150	300
Cabbage	-	300	-	300	-	-	-	200	-	-	-	250
Cauliflower	-	100	-	100	-	-	-	150	-	-	-	100
Celery	-	60	-	60	-	-	-	-	-	-	-	-
Corn, Green	-	-	-	100	-	-	-	100	-	-	-	500
Cucumbers	100	-	275	375	175	-	300	475	150	175	900	1225
Eggplant	75	-	50	125	100	-	100	200	100	100	50	250
Escarole	-	225	-	225	-	-	-	100	-	-	-	75
Lettuce	-	200	-	200	-	-	-	100	-	-	-	100
Peas, English	-	25	-	25	-	-	-	-	-	-	-	-
Peppers	25	-	50	75	90	-	50	140	50	75	-	125
Squash	50	-	200	250	50	-	50	100	100	-	150	250
Tomatoes	400	250	1300	1950	1000	450	2200	3650	1000	600	2000	3600
Total Vegs.	850	1160	2125	4235	1615	450	2950	5665	1550	950	3250	6775
Cantaloupes	-	-	-	-	-	-	-	25	-	-	-	-
Watermelons	-	-	100	100	-	-	-	50	-	-	-	200
Grand Total	850	1160	2225	4335	1615	450	2950	5740	1550	950	3250	6975
MARION												
Beans	200	-	600	800	300	-	1200	1500	350	-	1300	1650
Limas	-	-	250	250	-	-	150	150	-	-	100	100
Cabbage	-	500	-	500	-	-	-	300	-	-	-	300
Celery	-	-	500	500	-	-	235	235	-	50	280	330
Corn, Green	-	-	-	-	-	-	-	700	-	-	-	800
Cucumbers	25	-	250	275	100	-	225	325	100	-	250	350
Eggplant	150	-	50	200	150	-	50	200	75	-	50	125
Lettuce	-	-	-	100	-	-	-	80	-	-	-	25
Peas, English	-	25	-	25	-	-	-	20	-	-	-	-
Peppers	-	-	200	200	-	-	75	75	-	-	150	150
Potatoes	-	-	50	50	-	-	-	-	-	-	50	50
Squash	400	-	500	900	600	-	700	1300	550	-	750	1300
Tomatoes	-	-	900	900	-	-	1000	1000	-	-	1300	1300
Total Vegs.	775	525	3300	4700	1150	-	3635	5885	1075	50	4230	6480
Cantaloupes	-	-	300	300	-	-	-	300	-	-	-	300
Watermelons	-	-	6500	6500	-	-	-	7200	-	-	-	7000
Grand Total	775	525	10100	11500	1150	-	3635	13385	1075	50	4230	13780
MARTIN												
Beans	200	-	400	600	500	200	400	1100	25	-	500	525
Limas	-	50	-	50	-	15	-	15	-	25	-	25
Cabbage	-	75	-	75	-	-	-	50	-	-	-	50
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	500
Cucumbers	-	-	-	-	100	150	75	325	200	200	300	700
Eggplant	-	25	25	50	-	50	-	50	-	50	-	50
Peppers	-	50	25	75	-	150	50	200	25	125	-	150
Squash	200	400	100	700	250	300	50	600	50	200	50	300
Tomatoes	-	-	50	50	250	-	200	450	250	50	100	400
Total Vegs.	400	600	600	1600	1100	865	775	2790	550	650	950	2700
OKEECHOBEE												
Tomatoes	150	-	550	700	300	-	550	850	400	-	1300	1700

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1947-48				1948-49				1949-50			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
ORANGE												
Beans	600	-	-	600	300	-	-	300	700	-	125	825
Cabbage	-	600	-	600	-	-	-	600	-	-	-	400
Carrots	-	280	-	280	-	-	-	325	-	-	-	-
Celery	-	310	550	860	-	315	510	825	-	350	300	650
Corn, Green	-	-	-	1350	-	-	-	1700	-	-	-	3000
Cucumbers	100	-	275	375	100	-	300	400	125	-	250	375
Escarole	-	370	-	370	-	-	-	475	-	-	-	450
Lettuce	-	60	-	60	-	-	-	160	-	-	-	175
Peppers	160	-	-	160	200	-	25	225	125	-	-	125
Potatoes	-	-	75	75	-	-	-	-	-	-	-	-
Squash	-	-	50	50	25	-	50	75	-	-	-	-
Tomatoes	-	-	-	-	-	-	50	50	-	-	50	50
Total Vegs.	860	1620	950	4780	625	315	935	5135	950	350	725	6850
Watermelons	-	-	100	100	-	-	-	300	-	-	-	400
Grand Total	860	1620	1050	4880	625	315	935	5435	950	350	725	7250
PALM BEACH												
Beans	16000	19900	12600	48500	20000	19500	12300	51800	12500	16600	15500	44600
Limas	-	1200	950	2150	-	685	650	1335	-	1100	500	1600
Cabbage	-	3600	-	3600	-	-	-	3250	-	-	-	4350
Carrots	-	-	-	-	-	-	-	80	-	-	-	-
Celery	-	1900	2100	4000	-	1550	1525	3075	-	2200	1200	3400
Corn, Green	-	-	-	1250	-	-	-	4400	-	-	-	11500
Cucumbers	900	700	300	1950	350	250	75	675	200	400	200	800
Eggplant	-	100	875	975	-	225	400	625	-	325	250	575
Escarole	-	2000	-	2000	-	-	-	1950	-	-	-	2300
Lettuce	-	-	-	415	-	-	-	400	-	-	-	900
Peas, English	-	200	-	200	-	-	-	200	-	-	-	100
Peppers	-	1100	900	2000	-	1400	650	2050	150	1750	1100	3000
Potatoes	-	500	600	1100	-	900	470	1370	-	1350	425	1775
Squash	250	800	150	1200	400	1050	200	1650	300	1000	300	1600
Tomatoes	25	250	700	975	150	-	450	600	50	50	700	800
Total Vegs.	17175	32250	19175	70265	20900	25560	16720	73460	13200	24775	20175	77300
Watermelons	-	-	150	150	-	-	-	50	-	-	-	-
Grand Total	17175	32250	19325	70415	20900	25560	16720	73510	13200	24775	20175	77300
PASCO												
Watermelons	-	-	1200	1200	-	-	-	1850	-	-	-	1600
PINELLAS												
Watermelons	-	-	100	100	-	-	-	-	-	-	-	-
POLK												
Beans	-	-	100	100	-	-	150	150	-	-	175	175
Cabbage	-	100	-	100	-	-	-	75	-	-	-	75
Corn, Green	-	-	-	50	-	-	-	400	-	-	-	400
Cucumbers	-	-	200	200	50	-	50	100	-	-	50	50
Eggplant	-	-	100	100	-	-	100	100	-	-	50	50
Peas, English	-	25	-	25	-	-	-	-	-	-	-	-
Peppers	-	-	650	650	-	-	500	500	-	-	600	600
Potatoes	-	-	-	-	-	-	25	25	-	-	-	-
Squash	-	-	250	250	-	-	225	225	-	-	200	200
Tomatoes	-	-	100	100	-	-	150	150	-	-	150	150
Total Vegs.	-	125	1400	1575	50	-	1200	1725	-	-	1225	1700
Strawberries	-	500	-	500	-	-	-	450	-	-	-	450
Watermelons	-	-	700	700	-	-	-	800	-	-	-	600
Grand Total	-	625	2100	2775	50	-	1200	2975	-	-	1225	2750
PUTNAM												
Cabbage	-	1400	-	1400	-	-	-	1600	-	-	-	1650
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	200
Cucumbers	-	-	200	200	-	-	100	100	-	-	-	-
Peas, English	-	-	-	-	-	-	-	20	-	-	-	-
Potatoes	-	-	2400	2400	-	-	2000	2000	-	-	2050	2050
Total Vegs.	-	1400	2600	4000	-	-	2100	3720	-	-	2050	3900
Watermelons	-	-	150	150	-	-	-	400	-	-	-	600
Grand Total	-	1400	2750	4150	-	-	2100	4120	-	-	2050	4500

1949-50 figures subject to revision as of September 20, 1950.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1947-48				1948-49				1949-50			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
ST. JOHNS												
Cabbage	-	2800	-	2800	-	-	-	3100	-	-	-	3000
Cauliflower	-	-	-	-	-	-	-	25	-	-	-	200
Corn, Green	-	-	-	-	-	-	-	-	-	-	-	450
Potatoes	-	-	5800	5800	-	-	5800	5800	-	-	6600	6600
Total Vegs.	-	2800	5800	8600	-	-	5800	8925	-	-	6600	10250
ST. LUCIE												
Limas	-	50	-	50	-	150	25	175	-	-	-	-
Cabbage	-	200	-	200	-	-	-	100	-	-	-	50
Cauliflower	-	-	-	-	-	-	-	75	-	-	-	40
Corn, Green	-	-	-	25	-	-	-	150	-	-	-	700
Cucumbers	150	-	50	200	100	-	125	225	300	-	200	500
Peppers	-	-	-	-	-	50	-	50	25	25	100	150
Squash	-	-	100	100	25	-	100	125	25	-	100	125
Tomatoes	1300	600	2900	4800	3100	-	3250	6350	2300	-	2600	4900
Total Vegs.	1450	850	3050	5375	3225	200	3500	7250	2650	25	3000	6465
Cantaloupes	-	-	-	-	-	-	-	-	-	-	-	50
Watermelons	-	-	300	300	-	-	-	350	-	-	-	400
Grand Total	1450	850	3350	5675	3225	200	3500	7600	2650	25	3000	6915
SARASOTA												
Cabbage	-	75	-	75	-	-	-	-	-	-	-	50
Celery	-	975	350	1325	-	775	165	940	-	825	150	975
Corn, Green	-	-	-	-	-	-	-	75	-	-	-	200
Cucumbers	75	-	125	200	75	-	100	175	75	50	200	325
Eggplant	-	-	-	-	-	-	25	25	-	-	-	-
Escarole	-	-	-	-	-	-	-	50	-	-	-	25
Peas, English	-	-	-	-	-	-	-	20	-	-	-	-
Peppers	-	25	-	25	-	-	-	-	-	-	-	-
Total Vegs.	75	1075	475	1625	75	775	290	1285	75	875	350	1575
Watermelons	-	-	-	-	-	-	-	-	-	-	-	300
SEMINOLE												
Beans	500	-	75	575	700	-	500	1200	600	-	750	1350
Cabbage	-	1500	-	1500	-	-	-	1600	-	-	-	1200
Carrots	-	20	-	20	-	-	-	-	-	-	-	-
Cauliflower	-	25	-	25	-	-	-	100	-	-	-	100
Celery	-	2915	1150	4065	-	2200	1120	3320	-	2200	1075	3275
Corn, Green	-	-	-	750	-	-	-	900	-	-	-	1400
Cucumbers	-	-	-	-	-	-	60	60	-	-	50	50
Eggplant	-	-	-	-	25	-	50	75	-	-	25	25
Escarole	-	405	-	405	-	-	-	350	-	-	-	350
Lettuce	-	-	-	200	-	-	-	200	-	-	-	125
Peas, English	-	50	-	50	-	-	-	25	-	-	-	25
Peppers	-	-	250	250	-	-	200	200	25	-	250	275
Squash	50	-	50	100	25	-	50	75	-	-	50	50
Tomatoes	-	-	50	50	-	-	-	-	-	-	-	-
Total Vegs.	550	4915	1575	7990	750	2200	1980	8105	625	2200	2200	8225
SUMTER												
Beans	100	-	550	650	150	-	900	1050	150	-	700	850
Cabbage	-	100	-	100	-	-	-	50	-	-	-	50
Cucumbers	200	-	750	950	250	-	650	900	300	-	500	800
Eggplant	25	-	50	75	25	-	50	75	25	-	-	25
Lettuce	-	75	-	75	-	-	-	50	-	-	-	50
Peppers	-	-	800	800	-	-	675	675	-	-	950	950
Squash	-	-	50	50	25	-	75	100	-	-	50	50
Tomatoes	-	-	900	900	-	-	1250	1250	-	-	1500	1500
Total Vegs.	325	175	3100	3600	450	-	3600	4150	475	-	3700	4275
Cantaloupes	-	-	75	75	-	-	-	75	-	-	-	50
Strawberries	-	50	-	50	-	-	-	50	-	-	-	50
Watermelons	-	-	3500	3500	-	-	-	3900	-	-	-	3400
Grand Total	325	225	6675	7225	450	-	3600	8175	475	-	3700	7775

1949-50 figures subject to revision as of September 20, 1950.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

	1947-48				1948-49				1949-50			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
SUWANNEE												
Cabbage	-	-	-	-	-	-	-	-	-	-	-	125
Corn, Green	-	-	-	150	-	-	-	75	-	-	-	100
Cucumbers	-	-	300	300	-	-	225	225	-	-	75	75
Total Vegs.	-	-	300	450	-	-	225	300	-	-	75	300
Cantaloupes	-	-	25	25	-	-	-	25	-	-	-	50
Watermelons	-	-	2400	2400	-	-	-	5300	-	-	-	5900
Grand Total	-	-	2725	2875	-	-	225	5625	-	-	75	6250
TAYLOR												
Watermelons	-	-	50	50	-	-	-	100	-	-	-	300
UNION												
Beans	50	-	225	275	175	-	250	425	200	-	150	350
Limas	-	-	50	50	-	-	25	25	-	-	-	-
Cabbage	-	150	-	150	-	-	-	100	-	-	-	150
Corn, Green	-	-	-	100	-	-	-	200	-	-	-	400
Cucumbers	50	-	200	250	150	-	150	300	100	-	150	250
Peas, English	-	-	-	-	-	-	-	-	-	-	-	25
Peppers	-	-	100	100	-	-	100	100	-	-	50	50
Potatoes	-	-	100	100	-	-	25	25	-	-	70	70
Squash	50	-	50	100	50	-	175	225	100	-	50	150
Total Vegs.	150	150	725	1125	375	-	725	1400	400	-	470	1445
Watermelons	-	-	200	200	-	-	-	200	-	-	-	200
Grand Total	150	150	925	1325	375	-	725	1600	400	-	470	1645
VOLUSIA												
Cabbage	-	200	-	200	-	-	-	350	-	-	-	250
Lettuce	-	-	-	-	-	-	-	-	-	-	-	100
Peppers	-	-	100	100	-	-	100	100	-	-	100	100
Squash	-	-	50	50	-	-	50	50	-	-	50	50
Total Vegs.	-	200	150	350	-	-	150	500	-	-	150	500
Watermelons	-	-	250	250	-	-	-	400	-	-	-	350
Grand Total	-	200	400	600	-	-	150	900	-	-	150	850
WALTON												
Cucumbers	-	-	-	-	-	-	-	-	-	-	200	200
WASHINGTON												
Cucumbers	-	-	50	50	-	-	25	25	-	-	-	-
Watermelons	-	-	500	500	-	-	-	500	-	-	-	600
Grand Total	-	-	550	550	-	-	25	525	-	-	-	600
MISCELLANEOUS												
Beans	100	100	100	300	-	-	200	200	-	-	250	250
Limas	25	-	50	75	-	-	75	75	-	75	50	125
Cabbage	-	100	-	100	-	-	-	150	-	-	-	100
Carrots	-	25	-	25	-	-	-	20	-	-	-	-
Cauliflower	-	50	-	50	-	-	-	50	-	-	-	60
Celery	-	15	50	65	-	25	-	25	-	-	-	-
Corn, Green	-	-	-	110	-	-	-	250	-	-	-	250
Cucumbers	25	-	100	125	50	-	250	300	25	-	50	75
Eggplant	-	5	25	30	25	25	50	100	50	25	50	125
Escarole	-	50	-	50	-	-	-	35	-	-	-	25
Lettuce	-	-	-	75	-	-	-	20	-	-	-	50
Peas, English	-	-	-	50	-	-	-	15	-	-	-	75
Peppers	50	25	20	95	40	25	35	100	75	50	100	225
Potatoes	-	50	25	75	-	50	50	100	-	50	35	85
Squash	100	50	100	250	50	50	50	150	25	25	150	200
Tomatoes	50	50	100	200	-	75	150	225	50	-	300	350
Total Vegs.	350	520	570	1675	165	250	860	1815	225	225	985	1995
Cantaloupes	-	-	25	25	-	-	-	65	-	-	-	150
Strawberries	-	25	-	25	-	-	-	50	-	-	-	50
Watermelons	-	-	325	325	-	-	-	250	-	-	-	300
Grand Total	350	545	920	2050	165	250	860	2180	225	225	985	2495

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

TOTAL ALL COUNTIES

	1946-47				1947-48			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	19700	28500	33500	81700	21200	34300	19000	74500
Limas	-	1600	3600	5200	-	1500	2350	3850
Cabbage	-	14000	-	14000	-	16700	-	16700
Carrots	-	500	-	500	-	400	-	400
Cauliflower	-	600	-	600	-	400	-	400
Celery	-	7300	-	7300	-	6300	5300	11600
Corn, Green	-	-	-	-	-	-	-	6000
Cucumbers	5000	300	8475	13775	4200	1550	8900	14650
Eggplant	1200	1000	1100	3300	500	330	2500	3330
Escarole	-	2800	-	2800	-	3100	-	3100
Lettuce	-	1700	125	1825	-	-	-	1750
Peas, English	-	1600	-	1600	-	600	-	600
Peppers	1750	3600	5200	10550	450	2450	8300	11200
Potatoes	-	9900	14200	24100	-	7300	13400	20700
Squash	-	-	-	-	1700	2900	3300	7900
Tomatoes	10000	9800	10000	29800	2850	9600	15900	28350
Total Vegetables	37650	83200	80600	201450	30900	87430	78950	205030
Cantaloupes	-	-	800	800	-	-	1200	1200
Strawberries	-	4750	-	4750	-	4200	-	4200
Watermelons	-	-	47000	47000	-	-	45000	45000
Grand Total	37650	87950	128400	254000	30900	91630	125150	255430

	1948-49				1949-50			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	26500	31500	20000	78000	18000	31000	24300	73300
Limas	-	950	2100	3050	-	1400	2000	3400
Cabbage	-	-	-	16000	-	-	-	17000
Carrots	-	-	-	500	-	-	-	-
Cauliflower	-	-	-	600	-	-	-	850
Celery	-	5000	4400	9400	-	5800	3700	9500
Corn, Green	-	-	-	14700	-	-	-	29000
Cucumbers	4000	1300	7550	12850	4100	2100	8000	14200
Eggplant	700	800	1800	3300	550	900	1000	2450
Escarole	-	-	-	3000	-	-	-	3300
Lettuce	-	-	-	1500	-	-	-	2200
Peas, English	-	-	-	400	-	-	-	400
Peppers	850	3200	6700	10750	950	4200	8600	13750
Potatoes	-	8700	11900	20600	-	10000	13200	23200
Squash	2500	3200	3300	9000	2400	3700	4000	10100
Tomatoes	7600	13000	18200	38800	9000	14000	19500	42500
Total Vegetables	42150	67650	75950	222450	35000	73100	84300	245150
Cantaloupes	-	-	-	1200	-	-	-	1400
Strawberries	-	-	-	4000	-	-	-	5400
Watermelons	-	-	-	59000	-	-	-	63000
Grand Total	42150	67650	75950	286650	35000	73100	84300	314950

1949-50 figures subject to revision as of September 20, 1950.

FLORIDA FOB PRICES 1909-1950
AVERAGES ON PACKED FRUIT--RAIL AND BOAT
(Florida Citrus Exchange Report)
Seasons 1909-10 to 1929-30

SEASONS	ORANGES	GRAPEFRUIT	TANGERINES	(Average) ALL CITRUS
1909-10	$1.15	$2.38	$1.81	$1.34
1910-11	1.51	1.95	2.60	1,65
1911-12	1.93	3.58	1.93	2.21
1912-13	1.97	2.01	1.92	1.96
1913-14	1.69	2.09	2.51	1.83
1914-15	1.47	1.32	1.66	1.42
1915-16	1.99	1.89	2.07	1.96
1916-17	1.94	2.07	2.82	2.01
1917-18	3.92	2.72	4.39	3.46
1918-19	3.69	3.18	4.79	3.52
1919-20	4.20	2.84	5.49	3.37
1920-21	2.57	2.46	4.96	2.65
1921-22	3.77	2.41	5.57	3.17
1922-23	2.96	2.10	4.39	2.62
1923-24	1.86	1.51	4.31	1.82
1924-25	3.51	1.94	4.43	2.74
1925-26	3.58	2.92	4.83	3.36
1926-27	2.78	2.25	3.50	2.58
1927-28	4.39	3.22	5.28	3.90
1928-29	1.99	2.07	2.91	2.09
1929-30	3.22	2.78	3.38	3.13

FLORIDA STATE MARKETING BUREAU AVERAGES
Seasons 1930-31 to 1949-50
(Comparable to above prices)
Gross f.o.b. Florida per Box

SEASONS	ORANGES	GRAPEFRUIT	TANGERINES	(Average) ALL CITRUS
1930-31	$2.15	$1.50	$1.95	$1.66
1931-32	2.30	1.50	2.05	1.95
1932-33	1.48	1.16	1.42	1.36
1933-34	1.71	1.51	1.80	1.65
1934-35	1.85	1.29	1.66	1.63
1935-36	2.30	1.87	2.00	2.14
1936-37	2.50	1.48	1.45	2.04
1937-38	1.56	1.53	1.86	1.57
1938-39	1.43	1.04	1.34	1.31
1939-40	1.62	1.42	2.00	1.60
1940-41	1.63	1.21	1.68	1.51
1941-42	2.10	1.80	2.85	2.06
1942-43	2.97	2.33	2.78	2.81
1943-44	3.10	2.47	3.70	3.01
1944-45	3.50	3.00	4.25	3.48
1945-46	3.55	2.65	4.80	3.44
1946-47*	2.62	2.18	3.75	2.59
1947-48*	2.10	1.80	2.90	2.08
1948-49*	2.80	2.35	3.70	2.74
1949-50*	3.55	3.41	3.85	3.54

* Rail, Boat and Truck prices.

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASON 1947-48, 1948-49 AND 1949-50

Florida Counties	Snap Beans 1947-48	Snap Beans 1948-49	Snap Beans 1949-50	Lima Beans 1947-48	Lima Beans 1948-49	Lima Beans 1949-50	Cabbage 1947-48	Cabbage 1948-49	Cabbage 1949-50
Alachua	1,325	1,700	1,650	750	900	1,000	200	125	150
Baker	-	-	-	-	-	-	-	-	-
Bradford	100	200	250	50	75	150	50	25	25
Brevard	-	-	-	-	-	-	-	-	-
Broward	14,850	12,300	12,100	325	150	300	50	50	-
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	400	300	350
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	50	75	125
Dade	3,000	3,000	6,200	-	-	-	250	250	300
De Soto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	100	100	100
Escambia	100	100	100	-	-	-	50	-	150
Flagler	-	-	-	-	-	-	1,500	1,750	1,750
Gadsden	350	400	600	-	-	-	50	-	50
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	50	-	-	-	1,500	1,200	1,400
Hamilton	-	-	-	-	-	-	50	100	100
Hardee	50	50	-	-	-	-	150	-	-
Hendry	-	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-	-
Highlands	500	400	225	-	-	-	25	-	-
Hillsborough	1,075	1,350	800	100	100	100	350	300	300
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	300	325	350	-	-	-	200	175	125
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	100	-	50	-	25	25	25
Madison	-	-	-	-	-	-	-	-	-
Manatee	450	450	300	-	-	-	300	200	250
Marion	800	1,500	1,650	250	150	100	500	300	300
Martin	600	1,100	525	50	15	25	75	50	50
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	600	300	825	-	-	-	600	600	400
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	48,500	51,800	44,600	2,150	1,335	1,600	3,600	3,250	4,350
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	100	150	175	-	-	-	100	75	75
Putnam	-	-	-	-	-	-	1,400	1,600	1,650
St. Johns	-	-	-	-	-	-	2,800	3,100	3,000
St. Lucie	-	-	-	50	175	-	200	100	50
Sarasota	-	-	-	-	-	-	75	-	50
Seminole	575	1,200	1,350	-	-	-	1,500	1,600	1,200
Sumter	650	1,050	850	-	-	-	100	50	50
Suwannee	-	-	-	-	-	-	-	-	125
Taylor	-	-	-	-	-	-	-	-	-
Union	275	425	350	50	25	-	150	100	150
Volusia	-	-	-	-	-	-	200	350	250
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	300	200	250	75	75	125	100	150	100
Total	74,500	78,000	73,300	3,850	3,050	3,400	16,700	16,000	17,000

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASON 1947-48, 1948-49 AND 1949-50

Florida Counties	Carrots			Cauliflower			Celery		
	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50
Alachua	-	-	-	-	-	-	100	100	170
Baker	-	-	-	-	-	-	-	-	-
Bradford	-	-	-	-	-	-	-	-	-
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	-	-	-	-	-	-
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-	-
Dade	50	75	-	-	-	-	-	-	-
De Soto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	-	-	-	-	-	-	-	-	-
Hendry	-	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-	-
Highlands	25	-	-	-	-	-	-	-	-
Hillsborough	-	-	-	225	200	350	-	-	-
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	-	-	-	-	-	-	625	880	700
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-	-
Manatee	-	-	-	100	150	100	60	-	-
Marion	-	-	-	-	-	-	500	235	330
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	280	325	-	-	-	-	860	825	650
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	-	80	-	-	-	-	4,000	3,075	3,400
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	-	-	-	-	-	-
Putnam	-	-	-	-	-	-	-	-	-
St. Johns	-	-	-	-	25	200	-	-	-
St. Lucie	-	-	-	-	75	40	-	-	-
Sarasota	-	-	-	-	-	-	1,325	940	975
Seminole	20	-	-	25	100	100	4,065	3,320	3,275
Sumter	-	-	-	-	-	-	-	-	-
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	-	-	-
Volusia	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	25	20	-	50	50	60	65	25	-
Total	400	500	*-	400	600	850	11,600	9,400	9,500

Note: * Carrots not officially reported for 1949-50 Season.

FRUITS AND VEGETABLES
COUNTY ACREAGE SEASON 1947-48, 1948-49 AND 1949-50

Florida Counties	Green Corn			Cucumbers			Eggplant		
	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50
Alachua	200	300	450	1,225	1,725	1,475	150	150	100
Baker	-	100	100	-	-	-	-	-	-
Bradford	250	600	650	75	125	100	-	-	-
Brevard	-	50	150	-	-	-	-	-	-
Broward	-	50	100	700	325	325	450	350	375
Calhoun	-	-	-	300	225	75	-	-	-
Charlotte	-	-	-	100	100	250	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	50	400	300	1,100	-	-	-
Columbia	400	550	350	100	75	75	-	-	-
Dade	65	350	750	125	125	250	-	25	25
De Soto	50	-	-	100	140	300	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	200	25	-	-	-
Flagler	-	-	150	50	25	-	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	100	500	600	-	-	-	-	-	-
Hamilton	-	100	100	350	75	175	-	-	-
Hardee	200	300	650	2,100	1,325	1,800	75	175	150
Hendry	-	-	-	400	350	100	-	-	-
Hernando	-	-	-	-	-	-	15	50	-
Highlands	-	-	-	50	50	200	-	-	-
Hillsborough	650	2,350	2,550	1,325	1,100	1,050	845	700	400
Holmes	-	-	-	150	100	100	-	-	-
Indian River	-	-	-	-	25	-	-	-	-
Jackson	-	-	-	800	600	225	-	-	-
Jefferson	-	-	300	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	-	300	500	300	350	225	25	50	-
Lee	100	200	300	550	775	450	215	350	175
Leon	-	-	-	-	-	-	-	-	-
Levy	100	-	50	50	-	25	-	-	-
Madison	-	-	-	-	125	100	-	-	-
Manatee	100	100	500	375	475	1,225	125	200	250
Marion	-	700	800	275	325	350	200	200	125
Martin	-	-	500	-	325	700	50	50	50
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	1,350	1,700	3,800	375	400	375	-	-	-
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	1,250	4,400	11,500	1,900	675	800	975	625	575
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	50	400	400	200	100	50	100	100	50
Putnam	-	-	200	200	100	-	-	-	-
St. Johns	-	-	450	-	-	-	-	-	-
St. Lucie	25	150	700	200	225	500	-	-	-
Sarasota	-	75	200	200	175	325	-	25	-
Seminole	750	900	1,400	-	60	50	-	75	25
Sumter	-	-	-	950	900	800	75	75	25
Suwannee	150	75	100	300	225	75	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	100	200	400	250	300	250	-	-	-
Volusia	-	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	200	-	-	-
Washington	-	-	-	50	25	-	-	-	-
Miscellaneous	110	250	250	125	300	75	30	100	125
Total	6,000	14,700	29,000	14,650	12,850	14,200	3,330	3,300	2,450

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASON 1947-48, 1948-49 AND 1949-50

Florida Counties	Escarole			Lettuce			Peas, English		
	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50
Alachua	-	-	-	50	40	25	75	20	25
Baker	-	-	-	-	-	-	-	-	-
Bradford	-	-	-	-	-	-	-	-	-
Brevard	-	-	-	-	-	-	-	-	-
Broward	-	-	-	-	-	-	-	-	25
Calhoun	-	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-	-
Dade	-	-	-	-	-	-	-	-	-
De Soto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	25	-	25
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	-	325	200	400	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	-	-	-	-	-	-	-	-	-
Hendry	-	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	25	20	-
Hillsborough	50	40	75	225	250	250	100	60	100
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	-	-	-	25	-	-	-	-	-
Lee	-	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-	-
Manatee	225	100	75	200	100	100	25	-	-
Marion	-	-	-	100	80	25	25	20	-
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	370	475	450	60	160	175	-	-	-
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	2,000	1,950	2,300	415	400	900	200	200	100
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	-	-	-	-	-	-	25	-	-
Putnam	-	-	-	-	-	-	-	20	-
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	-	-	-	-	-	-
Sarasota	-	50	25	-	-	-	-	20	-
Seminole	405	350	350	200	200	125	50	25	25
Sumter	-	-	-	75	50	50	-	-	-
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	-	-	25
Volusia	-	-	-	-	-	100	-	-	-
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	50	35	25	75	20	50	50	15	75
Total	3,100	3,000	3,300	1,750	1,500	2,200	600	400	400

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASON 1947-48, 1948-49 AND 1949-50

Florida	Peppers			Potatoes			Squash		
Counties	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50
Alachua	550	800	800	1,500	400	550	150	425	400
Baker	-	-	-	-	-	-	-	-	-
Bradford	-	75	250	100	75	80	50	100	150
Brevard	-	-	-	-	-	-	-	50	400
Broward	1,675	1,500	2,550	-	-	-	1,350	1,350	1,350
Calhoun	-	-	75	-	-	-	-	-	-
Charlotte	50	50	25	-	-	-	-	25	25
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	50	-	40	-	-	-
Collier	-	-	-	-	-	-	-	25	100
Columbia	-	-	-	-	-	-	-	-	50
Dade	-	175	-	5,800	6,700	6,900	600	800	1,300
De Soto	-	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	600	500	750	-	-	-
Flagler	-	-	-	1,950	2,100	2,300	-	-	-
Gadsden	-	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-	-
Hardee	175	400	250	-	-	-	100	125	250
Hendry	-	-	-	-	-	-	75	50	100
Hernando	-	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	-	-	-
Hillsborough	3,640	2,765	3,300	150	375	250	1,150	1,050	1,375
Holmes	-	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	25	25
Jackson	-	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	230	145	250	-	-	-	50	50	50
Lee	350	375	300	950	1,130	1,700	325	200	150
Leon	-	-	-	-	-	-	-	-	-
Levy	-	50	50	-	-	-	50	50	100
Madison	-	-	-	-	-	-	-	-	-
Manatee	75	140	125	-	-	-	250	100	250
Marion	200	75	150	50	-	50	900	1,300	1,300
Martin	75	200	150	-	-	-	700	600	300
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	160	225	125	75	-	-	50	75	-
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	2,000	2,050	3,000	1,100	1,370	1,775	1,200	1,650	1,600
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-	-
Polk	650	500	600	-	25	-	250	225	200
Putnam	-	-	-	2,400	2,000	2,050	-	-	-
St. Johns	-	-	-	5,800	5,800	6,600	-	-	-
St. Lucie	-	50	150	-	-	-	100	125	125
Sarasota	25	-	-	-	-	-	-	-	-
Seminole	250	200	275	-	-	-	100	75	50
Sumter	800	675	950	-	-	-	50	100	50
Suwannee	-	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-	-
Union	100	100	50	100	25	70	100	225	150
Volusia	100	100	100	-	-	-	50	50	50
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-	-
Miscellaneous	95	100	225	75	100	85	250	150	200
Total	11,200	10,750	13,750	20,700	20,600	23,200	7,900	9,000	10,100

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49 AND 1949-50

Florida Counties	Tomatoes			Total Vegetables			Cantaloupes		
	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50
Alachua	100	-	-	6,375	6,685	6,795	450	400	600
Baker	-	-	-	-	100	100	-	-	-
Bradford	-	-	-	675	1,275	1,655	25	25	-
Brevard	50	400	300	50	500	850	-	-	-
Broward	1,400	1,500	1,600	20,800	17,575	18,725	-	-	-
Calhoun	-	-	-	300	225	150	-	-	-
Charlotte	50	50	-	200	225	300	-	-	-
Citrus	-	-	-	-	-	-	-	-	-
Clay	-	-	-	450	300	390	-	-	-
Collier	775	1,050	1,750	1,175	1,375	3,000	-	-	50
Columbia	-	-	-	550	700	600	25	25	-
Dade	8,900	12,000	12,500	18,790	23,500	28,225	-	-	-
De Soto	200	150	325	350	290	625	-	-	-
Dixie	-	-	-	-	-	-	-	-	-
Duval	-	-	-	100	100	100	-	-	-
Escambia	-	-	-	750	800	1,025	-	-	-
Flagler	-	-	-	3,525	3,875	4,225	-	-	-
Gadsden	-	-	-	400	400	650	-	-	-
Gilchrist	-	-	-	-	-	-	-	25	-
Glades	860	800	850	2,785	2,700	3,300	-	-	-
Hamilton	-	-	-	400	275	375	50	-	75
Hardee	1,850	1,400	2,275	4,700	3,775	5,375	-	-	-
Hendry	325	675	1,050	800	1,075	1,250	-	-	-
Hernando	-	-	-	15	50	-	-	-	-
Highlands	200	250	-	825	720	425	-	-	-
Hillsborough	2,150	3,100	3,350	12,035	13,740	14,250	50	25	-
Holmes	-	-	-	150	100	100	-	-	-
Indian River	390	2,400	3,200	390	2,450	3,225	-	-	-
Jackson	-	-	-	800	600	225	-	-	-
Jefferson	-	-	-	-	-	300	-	-	-
Lafayette	-	-	-	-	-	-	-	-	-
Lake	200	250	250	1,955	2,525	2,450	50	50	-
Lee	225	150	300	2,715	3,180	3,375	-	60	-
Leon	-	-	-	-	-	-	-	-	-
Levy	50	50	-	275	225	350	75	75	75
Madison	-	-	-	-	125	100	50	25	-
Manatee	1,950	3,650	3,600	4,235	5,665	6,775	-	25	-
Marion	900	1,000	1,300	4,700	5,885	6,480	300	300	300
Martin	50	450	400	1,600	2,790	2,700	-	-	-
Okeechobee	700	850	1,700	700	850	1,700	-	-	-
Orange	-	50	50	4,780	5,135	6,850	-	-	-
Osceola	-	-	-	-			-	-	-
Palm Beach	975	600	800	70,265	[illegible],460	77,[illegible]	-	-	-
Pasco	-	-	-	-	-	-	-	-	-
Pinellas	-	-	-	=	-	-	-	-	-
Polk	100	150	150	1,575	1,725	1,700	-	-	-
Putnam	-	-	-	4,000	3,720	3,900	-	-	-
St. Johns	-	-	-	8,600	8,925	10,250	-	-	-
St. Lucie	4,800	6,350	4,900	5,375	7,250	6,465	-	-	50
Sarasota	-	-	-	1,625	1,285	1,575	-	-	-
Seminole	50	-	-	7,990	8,105	8,225	-	-	-
Sumter	900	1,250	1,500	3,600	4,150	4,275	75	75	50
Suwannee	-	-	-	450	300	300	25	25	50
Taylor	-	-	-	-	-	-	-	-	-
Union	-	-	-	1,125	1,400	1,445	-	-	-
Volusia	-	-	-	350	500	500	-	-	-
Walton	-	-	-	-	-	200	-	-	-
Washington	-	-	-	50	25	-	-	-	-
Miscellaneous	200	225	350	1,675	1,815	1,995	25	65	150
Total	28,350	38,800	42,500	205,030	222,450	245,150	1,200	1,200	1,400

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49 AND 1949-50

Florida Counties	Strawberries			Watermelons			Total Miscellaneous Fruits		
	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50
Alachua	-	-	-	4,700	6,200	5,900	5,150	6,600	6,500
Baker	-	-	-	-	-	-	-	-	-
Bradford	200	400	550	50	100	150	275	525	700
Brevard	-	-	-	50	150	-	50	150	-
Broward	-	-	-	150	50	-	150	50	-
Calhoun	-	-	-	150	700	900	150	700	900
Charlotte	-	-	-	-	-	-	-	-	-
Citrus	-	-	-	150	250	900	150	250	900
Clay	-	-	-	-	-	-	-	-	-
Collier	-	-	-	50	50	600	50	50	650
Columbia	-	-	-	300	600	800	325	625	800
Dade	-	50	50	-	-	-	-	50	50
De Scto	-	-	-	400	550	850	400	550	850
Dixie	-	-	-	100	200	100	100	200	100
Duval	-	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-	-
Gadsden	-	-	-	100	-	-	100	-	-
Gilchrist	-	-	-	6,200	8,500	9,900	6,200	8,525	9,900
Glades	-	-	-	-	-	-	-	-	-
Hamilton	-	-	-	350	450	500	400	450	575
Hardee	325	250	350	75	100	300	400	350	650
Hendry	-	-	-	50	50	-	50	50	-
Hernando	-	-	-	-	100	100	-	100	100
Highlands	-	-	-	50	-	50	50	-	50
Hillsborough	3,100	2,750	3,900	600	800	900	3,750	3,575	4,800
Holmes	-	-	-	400	750	850	400	750	850
Indian River	-	-	-	150	200	400	150	200	400
Jackson	-	-	-	1,000	1,350	1,550	1,000	1,350	1,550
Jefferson	-	-	-	2,400	2,000	2,050	2,400	2,000	2,050
Lafayette	-	-	-	1,000	1,000	1,500	1,000	1,000	1,500
Lake	-	-	-	6,200	6,500	6,800	6,250	6,550	6,800
Lee	-	-	-	50	100	-	50	160	-
Leon	-	-	-	50	100	300	50	100	300
Levy	-	-	-	2,200	4,200	3,000	2,275	4,275	3,075
Madison	-	-	-	1,500	2,300	2,450	1,550	2,325	2,450
Manatee	-	-	-	100	50	200	100	75	200
Marion	-	-	-	6,500	7,200	7,000	6,800	7,500	7,300
Martin	-	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-	-
Orange	-	-	-	100	300	400	100	300	400
Osceola	-	-	-	-	-	-	-	-	-
Palm Beach	-	-	-	150	50	-	150	50	-
Pasco	-	-	-	1,200	1,850	1,600	1,200	1,850	1,600
Pinellas	-	-	-	100	-	-	100	-	-
Polk	500	450	450	700	800	600	1,200	1,250	1,050
Putnam	-	-	-	150	400	600	150	400	600
St. Johns	-	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	300	350	400	300	350	450
Sarasota	-	-	-	-	-	300	-	-	300
Seminole	-	-	-	-	-	-	-	-	-
Sumter	50	50	50	3,500	3,900	3,400	3,625	4,025	3,500
Suwannee	-	-	-	2,400	5,300	5,900	2,425	5,325	5,950
Taylor	-	-	-	50	100	300	50	100	300
Union	-	-	-	200	200	200	200	200	200
Volusia	-	-	-	250	400	350	250	400	350
Walton	-	-	-	-	-	-	-	-	-
Washington	-	-	-	500	500	600	500	500	600
Miscellaneous	25	50	50	325	250	300	375	365	500
Total	4,200	4,000	5,400	45,000	59,000	63,000	50,400	64,200	69,800

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49 AND 1949-50

Florida Counties	Total Vegetables & Miscellaneous Fruits			Oranges			Grapefruit		
	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50
Alachua	11,525	13,285	13,295	-	-	-	-	-	-
Baker	-	100	100	-	-	-	-	-	-
Bradford	950	1,800	2,355	-	-	-	-	-	-
Brevard	100	650	850	11,950	12,211	12,211	3,780	3,808	3,808
Broward	20,950	17,625	18,725	3,770	3,825	3,825	400	443	443
Calhoun	450	925	1,050	-	-	-	-	-	-
Charlotte	200	225	300	-	-	-	-	-	-
Citrus	150	250	900	-	-	-	-	-	-
Clay	450	300	390	-	-	-	-	-	-
Collier	1,225	1,425	3,650	-	-	-	-	-	-
Columbia	875	1,325	1,400	-	-	-	-	-	-
Dade	18,790	23,550	28,275	3,230	3,248	3,248	3,760	3,805	3,805
De Soto	750	840	1,475	6,835	6,933	6,933	1,360	1,383	1,383
Dixie	100	200	100	-	-	-	-	-	-
Duval	100	100	100	-	-	-	-	-	-
Escambia	750	800	1,025	-	-	-	-	-	-
Flagler	3,525	3,875	4,225	-	-	-	-	-	-
Gadsden	500	400	650	-	-	-	-	-	-
Gilchrist	6,200	8,525	9,900	-	-	-	-	-	-
Glades	2,785	2,700	3,300	-	-	-	-	-	-
Hamilton	800	725	950	-	-	-	-	-	-
Hardee	5,100	4,125	6,025	9,290	9,495	9,495	910	913	913
Hendry	850	1,125	1,250	-	-	-	-	-	-
Hernando	15	150	100	1,665	1,697	1,697	360	360	360
Highlands	875	720	475	9,460	9,849	9,849	4,340	4,409	4,409
Hillsborough	15,785	17,315	19,050	17,790	18,301	18,301	3,800	3,864	3,864
Holmes	550	850	950	-	-	-	-	-	-
Indian River	540	2,650	3,625	5,310	5,438	5,438	6,840	7,111	7,111
Jackson	1,800	1,950	1.775	-	-	-	-	-	-
Jefferson	2,400	2,000	2,350	-	-	-	-	-	-
Lafayette	1,000	1,000	1,500	-	-	-	-	-	-
Lake	8,205	9,075	9,250	27,980	29,157	29,157	6,980	7,147	7,147
Lee	2,765	3,340	3,375	3,445	3,478	3,478	2,900	2,911	2,911
Leon	50	100	300	-	-	-	-	-	-
Levy	2,550	4,500	3,425	-	-	-	-	-	-
Madison	1,550	2,450	2,550	-	-	-	-	-	-
Manatee	4,335	5,740	6,975	4,785	4,866	4,866	4,890	4,924	4,924
Marion	11,500	13,385	13,780	9,335	9,442	9,442	730	732	732
Martin	1,600	2,790	2,700	-	-	-	-	-	-
Okeechobee	700	850	1,700	-	-	-	-	-	-
Orange	4,880	5,435	7,250	38,040	39,766	39,766	4,010	4,112	4,112
Osceola	-	-	-	4,605	4,690	4,690	900	903	903
Palm Beach	70,415	73,510	77,300	-	-	-	-	-	-
Pasco	1,200	1,850	1,600	7,420	7,729	7,729	1,510	1,527	1,527
Pinellas	100	-	-	7,800	7,944	7,944	8,040	8,237	8,237
Polk	2,775	2,975	2,750	61,250	63,189	63,189	26,740	27,245	27,245
Putnam	4,150	4,120	4,500	4,450	4,450	4,450	450	451	451
St. Johns	8,600	8,925	10,250	-	-	-	-	-	-
St. Lucie	5,675	7,600	6,915	9,180	10,199	10,199	4,780	5,035	5,035
Sarasota	1,625	1,285	1,875	2,630	2,649	2,649	1,100	1,106	1,106
Seminole	7,990	8,105	8,225	7,110	7,301	7,301	720	723	723
Sumter	7,225	8,175	7,775	-	-	-	-	-	-
Suwannee	2,875	5,625	6,250	-	-	-	-	-	-
Taylor	50	100	300	-	-	-	-	-	-
Union	1,325	1,600	1,645	-	-	-	-	-	-
Volusia	600	900	850	12,885	13,004	13,004	1,360	1,369	1,369
Walton	-	-	200	-	-	-	-	-	-
Washington	550	525	600	-	-	-	-	-	-
Miscellaneous	2,050	2,180	2,495	10,285	11,039	11,039	2,340	2,482	2,482
Not apportioned	-	-	-	-	-	11,000	-	-	3,500
Total	255,430	286,650	314,950	280,500	289,900	300,900	93,000	95,000	98,500

Note: The 1948-49 citrus acreage figures by counties are being checked for probable revisions and no change is made for 1949-50. The State total for 1948-49 is assumed correct. The 11,000 acres of oranges, 3,500 acres of grapefruit and 100 acres of tangerines came into bearing in 1949-50 season, but were not apportioned by counties.

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49 AND 1949-50

Florida Counties	Tangerines			Total Citrus			Grand Total		
	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50	1947-48	1948-49	1949-50
Alachua	-	-	-	-	-	-	11,525	13,285	13,295
Baker	-	-	-	-	-	-	-	100	100
Bradford	-	-	-	-	-	-	950	1,800	2,355
Brevard	470	471	471	16,200	16,490	16,490	16,300	17,140	17,340
Broward	100	105	105	4,270	4,373	4,373	25,220	21,998	23,098
Calhoun	-	-	-	-	-	-	450	925	1,050
Charlotte	-	-	-	-	-	-	200	225	300
Citrus	-	-	-	-	-	-	150	250	900
Clay	-	-	-	-	-	-	450	300	390
Collier	-	-	-	-	-	-	1,225	1,425	3,650
Columbia	-	-	-	-	-	-	875	1,325	1,400
Dade	435	445	445	7,425	7,498	7,498	26,215	31,048	35,773
De Soto	520	521	521	8,715	8,837	8,837	9,465	9,677	10,312
Dixie	-	-	-	-	-	-	100	200	100
Duval	-	-	-	-	-	-	100	100	100
Escambia	-	-	-	-	-	-	750	800	1,025
Flagler	-	-	-	-	-	-	3,525	3,875	4,225
Gadsden	-	-	-	-	-	-	500	400	650
Gilchrist	-	-	-	-	-	-	6,200	8,525	9,900
Glades	-	-	-	-	-	-	2,785	2,700	3,300
Hamilton	-	-	-	-	-	-	800	725	950
Hardee	665	668	668	10,865	11,076	11,076	15,965	15,201	17,101
Hendry	-	-	-	-	-	-	850	1,125	1,250
Hernando	830	834	834	2,855	2,891	2,891	2,870	3,041	2,991
Highlands	830	832	832	14,630	15,090	15,090	15,505	15,810	15,565
Hillsborough	1,255	1,278	1,278	22,845	23,443	23,443	38,630	40,758	42,493
Holmes	-	-	-	-	-	-	550	850	950
Indian River	525	526	526	12,675	13,075	13,075	13,215	15,725	16,700
Jackson	-	-	-	-	-	-	1,800	1,950	1,775
Jefferson	-	-	-	-	-	-	2,400	2,000	2,350
Lafayette	-	-	-	-	-	-	1,000	1,000	1,500
Lake	1,990	2,004	2,004	36,950	38,308	38,308	45,155	47,383	47,558
Lee	120	122	122	6,465	6,511	6,511	9,230	9,851	9,886
Leon	-	-	-	-	-	-	50	100	300
Levy	-	-	-	-	-	-	2,550	4,500	3,425
Madison	-	-	-	-	-	-	1,550	2,450	2,550
Manatee	125	133	133	9,800	9,923	9,923	14,135	15,663	16,898
Marion	400	401	401	10,465	10,575	10,575	21,965	23,960	24,355
Martin	-	-	-	-	-	-	1,600	2,790	2,700
Okeechobee	-	-	-	-	-	-	700	850	1,700
Orange	3,115	3,128	3,128	45,165	47,006	47,006	50,045	52,441	54,256
Osceola	590	591	591	6,095	6,184	6,184	6,095	6,184	6,184
Palm Beach	-	-	-	-	-	-	70,415	73,510	77,300
Pasco	590	592	592	9,520	9,848	9,848	10,720	11,698	11,448
Pinellas	670	683	683	16,510	16,864	16,864	16,610	16,864	16,864
Polk	5,515	5,558	5,558	93,505	95,992	95,992	96,280	98,967	98,742
Putnam	640	641	641	5,540	5,542	5,542	9,690	9,662	10,042
St. Johns	-	-	-	-	-	-	8,600	8,925	10,250
St. Lucie	900	903	903	14,860	16,137	16,137	20,535	23,737	23,052
Sarasota	-	-	-	3,730	3,755	3,755	5,355	5,040	5,630
Seminole	825	826	826	8,655	8,850	8,850	16,645	16,955	17,075
Sumter	-	-	-	-	-	-	7,225	8,175	7,775
Suwannee	-	-	-	-	-	-	2,375	5,625	6,250
Taylor	-	-	-	-	-	-	50	100	300
Union	-	-	-	-	-	-	1,325	1,600	1,645
Volusia	1,940	1,951	1,951	16,185	16,324	16,324	16,785	17,224	17,174
Walton	-	-	-	-	-	-	-	-	200
Washington	-	-	-	-	-	-	550	525	600
Miscellaneous	750	787	787	13,375	14,308	14,308	15,425	16,488	16,803
Not apportioned	-	-	100	-	-	14,600	-	-	14,600
Total	23,800	24,000	24,100	397,300	408,900	423,500	652,730	695,550	738,450

NOTE: 1949-50 figures subject to revision as of September 20, 1950.

SOURCE: U.S. Bureau of Agricultural Economics, Orlando, Florida.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS

BEANS, SNAP

Season	Harvested Acreage	Yield Bu.	Harvested Production	Abandoned Volume(A)	Volume Used	Price per Bu. Fresh	Price per Bu. Canned	FOB Packed Total Value
1931-32	41,500	109	4,508,000	284,000	4,224,000	$1.41	$	$ 5,958,000
1932-33	50,800	98	5,002,000	144,000	4,858,000	.90		4,356,000
1933-34	61,300	101	6,216,000	430,000	5,786,000	1.00		5,773,000
1934-35	65,500	76	4,948,000	-	4,948,000	1.21		5,967,000
1935-36	59,200	71	4,183,000	-	4,183,000	1.49		6,250,000
1936-37	58,800	80	4,688,000	-	4,688,000	1.50		7,037,000
1937-38	60,700	89	5,381,000	-	5,381,000	1.17		6,272,000
1938-39	64,000	111	7,135,000	288,000	6,847,000	1.03		7,041,000
1939-40	52,000	98	5,090,000	-	5,090,000	1.47		7,480,000
1940-41	62,500	92	5,780,000	-	5,780,000	1.55		8,933,000
1941-42	68,000	105	5,783,000	-	5,783,000	1.84	.91	11,913,000
1942-43	80,000	131	7,795,000	-	7,795,000	2.62	1.27	17,989,000
1943-44	96,500	86	8,273,000	269,000	8,004,000	2.56	1.29	18,713,000
1944-45	80,500	92	7,440,000	496,000	6,244,000	2.92	1.67	18,405,000
1945-46	80,200	106	8,469,000	1,240,000	7,229,000	2.73	1.67	18,359,000
1946-47	81,700	80	6,549,700	561,000	5,988,700	2.90	1.67	16,389,000
1947-48	71,700	82	5,898,000	225,000	5,673,000	2.57	1.54	14,484,000
1948-49	79,000	106	8,389,000	1,154,000	7,235,000	(F)2.43	(C)1.63(Av)2.01	16,884,000
1949-50	73,300	101	7,368,000	286,000	7,082,000	(F)2.49	(C)1.41(Av)2.45	17,354,000

For Canning: 1941-42 bu. 1,367,000; 1942-43 bu. 2,677,000; 1943-44 bu. 1,268,000; 1944-45 bu. 1,486,000; 1945-46 bu. 1,106,000; 1946-47 bu. 800,700; 1947-48 bu. 583,000; 1948-49 bu. 843,000; 1949-50 bu. 878,000.

LIMAS

Season	Harvested Acreage	Yield Bu.	Harvested Production	Abandoned Volume(A)	Volume Used	Price Bu.	FOB Packed Total Value
1935-36	1,800	70	126,000	-	126,000	$1.60	$ 202,000
1936-37	2,400	65	156,000	-	156,000	2.50	390,000
1937-38	4,500	75	338,000	-	338,000	1.50	507,000
1938-39	4,800	100	480,000	-	480,000	1.50	720,000
1939-40	4,000	70	280,000	-	280,000	1.50	420,000
1940-41	7,000	40	280,000	-	280,000	2.20	616,000
1941-42	5,000	65	325,000	-	325,000	2.10	682,000
1942-43	5,400	59	321,000	-	321,000	3.31	1,041,000
1943-44	4,500	77	345,000	-	345,000	4.16	1,436,000
1944-45	4,800	88	420,000	14,000	406,000	4.38	1,779,000
1945-46	6,300	88	555,000	87,000	468,000	3.28	1,533,000
1946-47	5,200	65	338,000	-	338,000	3.51	1,187,000
1947-48	4,250	91	387,000	32,000	419,000	3.00	1,065,000
1948-49	3,050	105	319,000	-	319,000	2.97	946,000
1949-50	3,400	76	258,000	-	258,000	2.74	707,000

CABBAGE

Season	Harvested Acreage	Yield Tons	Harvested Production	Abandoned Volume(A)	Volume Used	Price Ton	FOB Packed Total Value
1931-32	5,500	4.0	22,100	-	22,100	$32.00	$ 704,000
1932-33	6,200	7.0	43,400	6,500	36,900	16.00	590,000
1933-34	10,700	6.0	64,200	21,400	42,800	16.00	685,000
1934-35	5,600	5.2	29,120	-	29,120	56.00	1,630,000
1935-36	9,000	4.0	36,000	-	36,000	17.00	612,000
1936-37	8,500	6.0	51,000	20,000	31,000	16.00	496,000
1937-38	9,400	6.5	61,000	-	61,000	16.00	978,000
1938-39	10,000	5.5	55,000	-	55,000	18.00	990,000
1939-40	16,000	7.0	112,000	-	112,000	18.40	2,061,000
1940-41	10,000	6.0	60,000	-	60,000	38.90	2,334,000
1941-42	18,000	6.0	108,000	-	108,000	17.80	1,602,000
1942-43	10,000	8.5	85,000	-	85,000	76.00	6,460,000
1943-44	23,500	7.1	166,800	47,100	119,700	36.00	4,309,000
1944-45	17,500	7.5	131,000	24,000	107,000	37.00	3,959,000
1945-46	13,200	8.8	116,200	2,500	113,700	49.00	5,571,000
1946-47	14,000	7.1	99,400	18,200	81,200	37.80	3,069,000
1947-48	16,100	9.0	144,900	21,100	123,800	52.50	6,500,000
1948-49	16,000	9.6	154,000	30,000	124,000	44.60	5,530,000
1949-50	17,000	10.8	183,600	56,900	126,700	30.50	3,864,000

(A) Not harvested, due to economic abandonment. Values cover harvested portion of crop.

NOTE: All 1949-50 acreage figures are preliminary as of September 20, 1950 and are subject to revision. Revisions are usually of minor consequence.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

CELERY

Season	Harvested Acreage	Yield N.Y.	Crts. Fla.	Harvested Production	(A) Abandoned	Volume Used	PRICE NY 2/3 Crates	FOB Packed Total Value	Price Fla. Crts.
1932-33	6,650	262	(437)	1,743,000	207,000	1,536,000	$1.27	$ 1,949,000	$ .76
1933-34	6,000	312	(520)	1,872,000	-	1,872,000	1.60	2,996,000	.96
1934-35	6,000	280	(467)	1,680,000	-	1,680,000	2.60	4,368,000	1.56
1935-36	6,500	265	(442)	1,723,000	-	1,723,000	2.60	4,488,000	1.56
1936-37	7,500	280	(467)	2,097,000	-	2,097,000	2.16	4,532,000	1.30
1937-38	8,000	286	(477)	2,290,000	255,000	2,035,000	1.62	3,289,000	.97
1938-39	7,300	299	(498)	2,184,000	-	2,184,000	2.46	5,375,000	1.48
1939-40	7,500	304	(507)	2,279,000	-	2,279,000	2.57	5,868,000	1.54
1940-41	9,100	278	(463)	2,531,000	-	2,531,000	3.19	8,066,000	1.91
1941-42	9,350	269	(465)	2,608,000	-	2,608,000	2.74	7,154,000	1.64
1942-43	8,750	-	447	4,175,500	(Fla.Crts.)	4,175,000	-	17,158,000	4.11
1943-44	9,900	-	502	4,969,000	400,000	4,569,000	-	14,530,000	3.18
1944-45	11,050	-	493	5,448,000	102,000	5,346,000	-	18,553,000	3.47
1945-46	13,450	-	479	6,439,000	151,000	6,288,000	-	14,260,000	2.27
1946-47	11,700	-	390	4,564,000	-	4,564,000	-	17,535,000	3.84
1947-48	11,600	-	487	5,651,000	892,000	4,759,000	-	9,778,000	2.05
1948-49	9,500	-	581	5,518,000	181,000	5,337,000	-	16,021,000	3.00
1949-50	9,500	-	649	6,170,000	-	6,170,000	-	12,295,000	1.99

(A) Not harvested, due to economic abandonment. Values cover harvested portion crops. Florida crates are approximately 60 per cent as large as NY 2/3 crates.

CUCUMBERS

Season	Harvested Acreage	Yield Bu.	Harvested Production	(A) Abandoned	Volume Used	Price per Bushel	FOB Packed Tot.Value
1932-33	5,600	64	361,000	-	390,000	$1.75	$ 633,000
1933-34	5,000	95	474,000	-	474,000	1.78	845,000
1934-35	5,100	93	473,000	-	473,000	1.62	765,000
1935-36	5,700	82	468,000	-	468,000	1.98	928,000
1936-37	5,600	65	364,000	-	364,000	3.02	1,101,000
1937-38	7,000	121	850,000	-	850,000	1.24	1,053,000
1938-39	7,600	115	876,000	-	876,000	1.58	1,391,000
1939-40	8,200	145	1,186,000	-	1,186,000	1.63	1,938,000
1940-41	8,800	121	1,064,000	-	1,064,000	1.75	1,858,000
1941-42	9,700	94	912,000	-	912,000	2.24	2,042,000
1942-43	6,500	80	520,000	-	520,000	4.98	2,592,000
1943-44	6,300	73	459,000	-	459,000	4.55	2,079,000
1944-45	7,700	110	844,000	-	844,000	4.31	3,637,000
1945-46	11,150	136	1,520,000	76,000	1,444,000	3.72	5,377,000
1946-47	13,775	87	1,204,000	-	1,204,000	4.14	4,984,000
1947-48	15,900	123	1,957,000	50,000	1,907,000	3.25	6,203,000
1948-49	15,500	124	1,800,000	46,000	1,754,000	F3.24P2.00Av3.17	5558000
1949-50	14,200	154	2,190,000	-	2,190,000	F3.38P1.25Av3.32	7263000

F indicates Fresh; P indicates Pickles.

CARROTS

Season	Harvested Acreage	Yield Crts.	Harvested Production	Abandoned	Volume Used	Price per Crate	FOB Packed Tot.Value
1947-48	450	200	90,000	-	90,000	$3.00	$ 270,000
1948-49	500	200	100,000	60,000	40,000	1.30	52,000
1949-50	None Reported	-	-	-	-	-	-

CAULIFLOWER

Season	Harvested Acreage	Yield Crts.	Harvested Production	Abandoned	Volume Used	Price per Crate	FOB Packed Tot.Value
1947-48	400	200	80,000	-	80,000	$2.20	$ 176,000
1948-49	600	260	156,000	-	156,000	2.25	351,000
1949-50	850	300	255,000	-	255,000	1.85	472,000

CORN, GREEN

Season	Harvested Acreage	Yield Crts.	Harvested Production	Abandoned	Volume Used	Price per Crate	FOB Packed Tot.Value
1947-48	6,000	80	480,000	-	480,000	$2.75	$1,320,000
1948-49	12,000	140	1,680,000	-	1,680,000	2.70	4,536,000
1949-50	29,000	120	3,480,000	530,000	2,950,000	2.15	6,342,000

ESCAROLE

Season	Harvested Acreage	Yield 1½bu.hpr.	Harvested Production	(A) Abandoned	Volume Used	Price 1½bu.hpr.	FOB Packed Tot.Value
1937-38	1,000	453	453,000	-	453,000	$ .45	$ 204,000
1938-39	1,000	440	440,000	-	440,000	.60	264,000
1939-40	1,350	400	540,000	-	540,000	.56	304,000
1940-41	1,000	373	373,000	-	373,000	.98	366,000
1941-42	1,200	400	480,000	-	480,000	.68	326,000
1942-43	1,450	350	507,500	-	507,500	2.25	1,142,000
1943-44	2,350	425	999,000	438,000	561,000	1.15	645,000
1944-45	2,800	310	868,000	224,000	644,000	2.10	1,352,000
1945-46	2,500	374	935,000	-	935,000	1.20	875,000
1946-47	2,800	325Bu.Hp.	910,000	-	910,000	1.30Bu.Hp.	1,183,000
1947-48	3,200	430 " "	1,376,000	266,000	1,110,000	1.05 " "	1,165,000
1948-49	2,800	400 " "	1,120,000	-	1,120,000	1.50 " "	1,680,000
1949-50	3,300	450 " "	1,485,000	145,000	1,340,000	.95 " "	1,273,000

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

EGGPLANT

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price per Bushel	FOB PACKED TOTAL VALUE
1932-33	2,450	253	620,000	-	620,000	$ .58	$ 359,000
1933-34	2,050	187	384,000	-	384,000	.75	289,000
1934-35	1,500	180	270,000	-	270,000	.79	212,000
1935-36	1,100	286	315,000	-	315,000	.85	268,000
1936-37	1,460	283	410,000	-	410,000	.79	323,000
1937-38	1,800	261	470,000	-	470,000	.76	366,000
1938-39	2,100	326	686,000	-	686,000	.75	514,000
1939-40	1,400	207	290,000	-	290,000	1.44	417,000
1940-41	1,800	180	324,000	-	324,000	1.17	378,000
1941-42	2,350	237	556,500	-	556,500	1.16	643,000
1942-43	1,950	278	541,500	-	541,500	2.39	1,294,000
1943-44	3,500	259	908,000	40,000	868,000	1.65	1,501,000
1944-45	3,250	271	880,000	-	880,000	2.06	1,814,000
1945-46	3,900	345	1,344,000	240,000	1,104,000	1.63	1,805,000
1946-47	3,300	220	725,000	-	725,000	2.42	1,758,000
1947-48	3,225	277	894,000	197,000	697,000	1.65	1,151,000
1948-49	3,300	271	894,000	-	894,000	1.63	1,456,000
1949-50	2,450	296	726,000	-	726,000	1.62	1,178,000

LETTUCE (Boston and Romaine)

Season	Harvested Acreage	Yield 4-6 doz.Crts	Harvested Production	Abandoned (A)	Volume Used	Price Crates	FOB PACKED TOTAL VALUE
1939-40	900	180	162,000	-	162,000	$1.10	$ 178,000
1940-41	500	150	75,000	-	75,000	2.00	150,000
1941-42	500	100	50,000	-	50,000	2.60	130,000
1942-43	800	175	140,000	-	140,000	3.05	427,000
1943-44	1,100	150	165,000	59,000	106,000	2.15	228,000
1944-45	400	200	80,000	-	80,000	2.70	216,000
1945-46	550	258	142,000	17,000	125,000	3.00	375,000
1946-47	700	100	70,000	-	70,000	2.95	206,000
1947-48	550	125	69,000	23,000	46,000	2.05	94,000

LETTUCE (Iceberg) 4-6 doz. crates

Season	Harvested Acreage	Yield	Harvested Production	Abandoned (A)	Volume Used	Price	FOB PACKED TOTAL VALUE
1939-40	1,100	180	198,000	-	198,000	$2.30	$ 455,000
1940-41	2,000	75	150,000	-	150,000	1.83	274,000
1941-42	3,000	55	165,000	-	165,000	2.16	356,000
1942-43	1,700	135	230,000	-	230,000	3.97	913,000
1943-44	1,350	143	193,000	78,000	115,000	2.90	334,000
1944-45	1,000	143	143,000	24,000	119,000	3.51	418,000
1945-46	1,300	165	214,000	20,000	194,000	3.72	910,250
1946-47	1,125	107	119,000	-	119,000	2.97	353,000
1947-48	1,100	118	130,000	10,000	120,000	2.88	346,000

LETTUCE (All)

Season	Harvested Acreage	Yield	Harvested Production	Abandoned (A)	Volume Used	Price	FOB PACKED TOTAL VALUE
1948-49	1,500	125	188,000	-	188,000	3.10	583,000
1949-50	2,200	160	352,000	64,000	288,000	2.80	806,000

SQUASH

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price Bushels	FOB Packed Total Value
1947-48	7,900	82	651,000	-	651,000	$2.83	$1,839,250
1948-49	9,000	91	817,000	-	817,000	2.76	2,225,000
1949-50	10,100	85	860,000	-	860,000	2.40	2,060,000

PEAS, ENGLISH

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price Bushels	FOB Packed Total Value
1933-34	4,800	96	461,000	-	461,000	$1.10	$ 507,000
1934-35	5,000	80	400,000	-	400,000	1.30	520,000
1935-36	8,200	62	508,000	-	508,000	1.00	508,000
1936-37	6,200	50	310,000	-	310,000	1.35	418,000
1937-38	6,200	90	558,000	-	558,000	1.15	642,000
1938-39	5,000	70	350,000	-	350,000	1.85	648,000
1939-40	5,000	90	450,000	75,000	375,000	1.30	488,000
1940-41	3,000	70	210,000	-	210,000	1.95	410,000
1941-42	3,500	70	245,000	-	245,000	1.55	380,000
1942-43	1,500	65	98,000	-	98,000	2.60	254,000
1943-44	2,500	60	150,000	-	150,000	3.00	450,000
1944-45	2,600	75	195,000	90,000	105,000	2.70	284,000
1945-46	1,600	74	118,000	5,000	113,000	3.00	339,000
1946-47	1,600	40	64,000	-	64,000	2.95	189,000
1947-48	600	60	36,000	-	36,000	2.55	92,000
1948-49	400	40	16,000	-	16,000	2.62	42,000
1949-50	400	60	24,000	-	24,000	2.80	67,000

(A) Not harvested, due to economic abandonment.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

PEPPERS, GREEN

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price per Bushel	FOB Packed Total Value
1931-32	8,050	221	1,782,000	-	1,782,000	$1.00	$1,780,000
1932-33	8,300	266	2,210,000	-	2,210,000	.58	1,284,000
1933-34	6,000	241	1,446,000	-	1,446,000	1.16	1,676,000
1934-35	7,700	149	1,150,000	-	1,150,000	1.11	1,277,000
1935-36	6,500	226	1,467,000	-	1,467,000	.87	1,273,000
1936-37	7,200	221	1,590,000	-	1,590,000	1.20	1,905,000
1937-38	7,400	295	2,180,000	-	2,180,000	.77	1,668,000
1938-39	7,300	303	2,212,000	-	2,212,000	1.25	2,771,000
1939-40	6,200	224	1,390,000	-	1,390,000	1.53	2,121,000
1940-41	7,200	225	1,621,500	-	1,621,500	1.56	2,537,000
1941-42	6,500	276	1,792,000	-	1,792,000	1.75	3,133,000
1942-43	7,100	284	2,018,000	-	2,018,000	2.93	5,917,000
1943-44	8,950	265	2,371,000	86,000	2,285,000	2.16	4,964,000
1944-45	9,350	287	2,687,000	-	2,687,000	2.46	6,623,000
1945-46	11,080	275	3,050,000	380,000	2,670,000	2.45	6,545,000
1946-47	10,550	208	2,193,000	-	2,193,000	4.14	9,086,000
1947-48	11,450	250	2,860,000	143,000	2,717,000	2.17	5,886,000
1948-49	11,100	268	2,972,000	-	2,972,000	2.55	7,569,000
1949-50	13,750	292	4,015,000	175,000	3,840,000	1.87	7,188,000

POTATOES

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price per Bushel	FOB.Packed Total Value
1931-32	21,500	70	1,505,000	-	1,505,000	$1.28	$1,933,000
1932-33	17,000	132	2,244,000	-	2,244,000	.85	1,908,000
1933-34	23,500	140	3,290,000	-	3,290,000	1.13	3,708,000
1934-35	24,800	97	2,406,000	-	2,406,000	1.04	2,503,000
1935-36	24,500	91	2,235,000	-	2,235,000	1.43	3,187,000
1936-37	31,300	123	3,842,000	-	3,842,000	1.32	5,087,000
1937-38	31,400	133	4,177,000	-	4,177,000	.70	2,939,000
1938-39	26,700	121	3,235,000	-	3,235,000	1.13	3,644,000
1939-40	25,600	157	4,020,000	-	4,020,000	.93	3,725,000
1940-41	26,800	117	3,126,000	-	3,126,000	.90	2,799,000
1941-42	25,000	154	3,848,000	-	3,848,000	1.54	5,924,000
1942-43	26,200	134	3,523,000	-	3,523,000	1.96	5,914,000
1943-44	28,600	112	3,212,000	-	3,212,000	2.00	6,431,000
1944-45	31,100	162	5,035,000	-	5,035,000	2.39	12,033,000
1945-46	35,300	170	6,010,000	-	6,010,000	1.95	11,744,000
1946-47	24,100	114	2,738,000	-	2,738,000	2.00	5,475,000
1947-48	20,800	174	3,614,000	-	3,614,000	2.79	10,073,000
1948-49	20,300	264	5,362,000	-	5,362,000	2.30	12,316,000
1949-50	23,200	231	5,370,000	-	5,370,000	1.79	9,609,000

TOMATOES

Season	Harvested Acreage	Yield Bu.	Harvested Prod. Fresh	Harvested Prod. Canning	Abandoned (A)	Volume Used	Price Bu. Fresh	Price Bu. Canned	FOB Packed Tot. Value
1931-32	23,700	95	2,255,000	-	-	2,255,000	$2.55	$ -	$ 5,748,000
1932-33	24,900	94	2,343,000	-	-	2,343,000	1.87	-	4,377,000
1933-34	30,500	113	2,886,000	557,000	-	3,443,000	2.86	.39	8,476,000
1934-35	32,500	102	2,714,000	589,000	-	3,303,000	2.46	.28	6,835,000
1935-36	32,600	100	2,954,000	321,000	-	3,275,000	2.75	.31	8,224,000
1936-37	35,700	86	2,746,000	314,000	-	3,060,000	2.76	.32	7,688,000
1937-38	45,300	120	4,953,000	500,000	-	5,453,000	1.73	.28	8,711,000
1938-39	40,700	129	4,948,000	312,000	-	5,260,000	2.47	.28	12,323,000
1939-40	34,000	88	3,225,000	232,000	-	3,457,000	2.53	.28	8,216,000
1940-41	26,500	110	2,765,000	165,000	-	2,930,000	3.10	.28	8,618,000
1941-42	43,000	101	3,412,000	951,000	-	4,363,000	3.92	.46	13,821,000
1942-43	25,500	102	2,226,000	*	-	2,226,000	5.30	*	11,795,000
1943-44	34,900	109	3,405,000	395,000	-	3,800,000	5.72	.59	19,712,000
1944-45	32,500	137	4,456,000	289,000	342,000	4,403,000	5.27	.72	20,376,000
1945-46	30,400	154	4,670,000	265,000	221,000	4,714,000	5.25	.74	22,405,000
1946-47	29,800	107	3,198,000	306,000	-	3,504,000	6.50	1.00	19,098,000
1947-48	30,200	130	3,588,000	346,000	-	3,934,000	5.83	.75	22,936,000
1948-49	38,200	183	6,300,000	675,000	-	6,975,000	F5.12	C.64Av4.68	32,666,000
1949-50	42,500	163	6,448,000	469,000	-	6,917,000	F4.96	C.50Av4.66	32,247,000

A - Not harvested, due to economic abandonment (poor markets).
All 1949-50 acreage figures are preliminary as of September 20, 1950, and are subject to revision.

* Separate volume and price not available for 1942-43 season.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

CANTALOUPES

Season	Harvested Production	Yield Crates	Harvested Production	Abandoned (A)	Volume Used	Price per Crate	FOB Packed Tot. Value
1931-32	200	75	15,000	-	15,000	$1.00	$ 15,000
1932-33	400	60	24,000	-	24,000	1.00	24,000
1933-34	300	60	18,000	-	18,000	1.30	23,000
1934-35	200	60	12,000	-	12,000	1.50	18,000
1935-36	200	60	12,000	-	12,000	1.25	15,000
1936-37	300	55	16,000	-	16,000	1.75	28,000
1937-38	700	75	52,000	-	52,000	1.25	65,000
1938-39	500	80	40,000	-	40,000	1.10	44,000
1939-40	500	70	35,000	-	35,000	1.10	38,000
1940-41	500	60	30,000	-	30,000	1.25	38,000
1941-42	500	70	35,000	-	35,000	1.50	52,000
1942-43	400	65	26,000	-	26,000	3.25	85,000
1943-44	550	60	33,000	-	33,000	3.75	124,000
1944-45	500	50	25,000	5,000	20,000	6.00	120,000
1945-46	800	45	36,000	18,000	18,000	3.00	54,000
1946-47	800	50	40,000	-	40,000	2.55	102,000
1947-48	1,200	65	78,000	-	78,000	4.35	339,000
1948-49	1,200	40	48,000	-	48,000	4.00	192,000
1949-50	1,400	60	84,000	-	84,000	2.25	189,000

(A) Crates not harvested due to economic abandonment.

STRAWBERRIES

Season	Harvested Production	24-Qt. Crates	Harvested Production	Abandoned (A)	Volume Used	(48 Pts.) 24 Qts.*	FOB Packed Total Value	36 Pt. Crate
1931-32	7,800	76	593,000	-	593,000	$4.80	$2,846,000	$3.60
1932-33	10,600	73	774,000	-	774,000	3.00	2,322,000	2.25
1933-34	8,400	75	630,000	-	630,000	4.20	2,646,000	3.15
1934-35	8,000	65	520,000	-	520,000	4.30	2,236,000	3.23
1935-36	8,900	54	481,000	-	481,000	4.10	1,972,000	3.08
1936-37	8,800	65	572,000	-	572,000	4.80	2,746,000	3.60
1937-38	7,500	70	525,000	-	525,000	4.00	2,100,000	3.00
1938-39	9,000	85	765,000	-	765,000	4.15	3,175,000	3.11
1939-40	7,200	70	504,000	-	504,000	4.65	2,344,000	3.49
1940-41	5,500	70	384,000	-	384,000	5.70	2,194,000	4.28
1941-42	5,000	70	350,000	-	350,000	6.50	2,275,000	4.88
1942-43	2,600	60	156,000	-	156,000	9.60	1,498,000	7.20
1943-44	1,400	70	98,000	-	98,000	11.30	1,107,000	8.47
1944-45	2,050	70	144,000	-	144,000	10.70	1,541,000	8.03
1945-46	2,800	80	224,000	-	224,000	10.55	2,363,000	7.92
1946-47	4,750	65	309,000	-	309,000	12.10	3,739,000	9.08
1947-48	4,200	45	189,000	-	189,000	10.60	2,003,000	7.95
1948-49	4,000	55	220,000	-	220,000	10.91	2,401,000	8.18
1949-50	5,400	80	432,000	-	432,000	8.69	3,737,000	6.49

* Now shipped almost exclusively in 36-pt. crates. The 24-qt.crate was formerly used, and it is continued here for statistical purposes. Florida crate is 75% as large.

WATERMELONS

Season	Harvested Production	Yield Melons	Harvested Production	Abandoned (A)	Volume Used	Price per 1000 melons	FOB Packed Tot. Value
1931-32	28,500	200	5,700,000	-	5,700,000	$160	$ 912,000
1932-33	22,500	220	4,950,000	-	4,950,000	200	990,000
1933-34	23,400	180	4,212,000	-	4,212,000	185	779,000
1934-35	20,000	330	6,600,000	-	6,600,000	110	726,000
1935-36	16,000	280	4,480,000	-	4,480,000	200	896,000
1936-37	19,500	300	5,850,000	390,000	5,460,000	240	1,310,000
1937-38	22,500	310	6,975,000	675,000	6,300,000	150	945,000
1938-39	22,600	240	5,424,000	-	5,424,000	180	976,000
1939-40	23,500	290	6,815,000	-	6,815,000	175	1,193,000
1940-41	25,500	270	6,885,000	-	6,885,000	210	1,445,850
1941-42	22,000	325	7,150,000	-	7,150,000	225	1,609,000
1942-43	12,500	325	4,063,000	-	4,063,000	650	2,641,000
1943-44	25,500	305	7,778,000	-	7,778,000	655	5,095,000
1944-45	39,000	260	10,140,000	-	10,140,000	485	4,918,000
1945-46	47,000	225	10,575,000	-	10,575,000	525	5,552,000
1946-47	47,000	290	13,623,000	-	13,623,000	447	5,419,000
1947-48	45,000	305	13,725,000	-	13,725,000	500	6,862,000
1948-49	59,000	240	14,160,000	-	14,160,000	450	6,372,000
1949-50	63,000	300	18,900,000	-	14,000,000	395	5,530,000

A - Not harvested due to economic abandonment. Not included in total value figures. The average carload is usually figured at 1000 melons but new varieties of round type melons have made a range of 875-1200, averaging 978 melons to car.

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 25 SEASONS
(For Harvest)

Season	Beans Acreage	Limas Acreage	Cabbage Acreage	Carrots Acreage	Celery Acreage	Cauli-flower Acreage	Cu-cumbers Acreage	Season
1925-26	16,000	(1)	3,660		3,520		7,590	1925-26
1926-27	19,490	(1)	3,010	Not	4,240		7,440	1926-27
1927-28	29,730	(1)	2,900	Reported	3,380		9,450	1927-28
1928-29	27,000	(1)	6,500	"	6,620		11,340	1928-29
1929-30	35,800	(1)	3,700	"	6,650		12,100	1929-30
1930-31	40,000	(1)	6,500	"	6,150		9,650	1930-31
1931-32	41,500	(1)	5,500	"	6,850		7,300	1931-32
1932-33	50,800	(1)	6,200	"	6,650		5,600	1932-33
1933-34	61,300	1,500	10,700	"	6,000		5,000	1933-34
1934-35	65,500	1,500	5,600	"	6,000		5,100	1934-35
1935-36	59,200	1,800	9,000	"	6,500		5,700	1935-36
1936-37	58,800	2,400	8,500	"	7,500		5,600	1936-37
1937-38	60,700	4,500	9,400	"	8,000		7,000	1937-38
1938-39	64,000	4,800	10,000	"	7,300		7,600	1938-39
1939-40	52,000	4,000	16,000	"	7,500		8,200	1939-40
1940-41	62,500	7,000	10,000	"	8,700		8,800	1940-41
1941-42	68,000	5,000	18,000	"	9,350		9,700	1941-42
1942-43	80,000	5,400	10,000	"	8,750		6,500	1942-43
1943-44	96,500	4,500	23,500	"	9,900		6,300	1943-44
1944-45	80,500	4,800	17,500	"	11,050		7,700	1944-45
1945-46	80,200	6,300	13,200	"	13,450		11,950	1945-46
1946-47	81,700	5,200	14,000	"	11,700		13,775	1946-47
1947-48	71,700	4,250	16,100	450	11,600	400	15,900	1947-48
1948-49	79,000	3,050	16,000	500	9,500	600	14,100	1948-49
1949-50	73,300	3,400	17,000	Not reported	9,500	850	14,200	1949-50

NOTE: (1) Limas were included with snap beans prior to the 1933-34 season. The lima figures are for the Fordhook or large variety and do not include acreage of baby limas or butterbeans.

Season	Corn Acreage	Eggplant Acreage	Escarole (2) Acreage	Boston Lettuce (3) Acreage	Iceberg Lettuce (4) Acreage	All Lettuce Acreage	English Peas Acreage	Season
1925-26		1,020	(2)	1,500	-	1,500	760	1925-26
1926-27		630	(2)	1,500	-	1,500	700	1926-27
1927-28		1,550	340	1,500	-	1,500	1,230	1927-28
1928-29		1,320	500	1,500	-	1,500	1,350	1928-29
1929-30		1,680	460	1,100	-	1,100	700	1929-30
1930-31		1,800	850	1,600	-	1,600	2,000	1930-31
1931-32		1,950	700	1,000	-	1,000	3,800	1931-32
1932-33		2,450	700	950	-	950	3,600	1932-33
1933-34		2,050	700	1,100	-	1,100	4,800	1933-34
1934-35		1,500	650	900	(4)	900	5,000	1934-35
1935-36		1,100	700	550	(4)	550	8,200	1935-36
1936-37		1,480	900	800	(4)	800	6,200	1936-37
1937-38		1,800	1,000	900	(4)	900	6,200	1937-38
1938-39		2,100	1,000	750	250	1,000	5,000	1938-39
1939-40		1,400	1,350	900	1,100	2,000	5,000	1939-40
1940-41		1,900	1,000	500	2,000	2,500	3,000	1940-41
1941-42		2,350	1,200	500	3,000	3,500	3,500	1941-42
1942-43		1,950	1,450	800	1,700	2,500	1,500	1942-43
1943-44		3,500	2,350	1,100	1,350	2,450	2,500	1943-44
1944-45		2,850	2,800	400	1,000	1,400	2,600	1944-45
1945-46		3,900	2,500	550	1,300	1,850	1,600	1945-46
1946-47		3,300	2,800	700	1,125	1,825	1,600	1946-47
1947-48	6,000	3,225	3,200	550	1,100	1,650	600	1947-48
1948-49	12,000	3,300	2,800	-	-	1,500(5)	400	1948-49
1949-50	29,000	2,450	3,300	-	-	2,200(5)	400	1949-50

NOTES: (2) Escarole acreage included with lettuce prior to 1927-28 season.
(3) Big Boston figures include Romaine acreage.
(4) Iceberg Lettuce included in Big Boston acreage figures until the 1938-39 season.
(5) Iceberg, Boston and Romaine Lettuce combined.

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 25 SEASONS (Cont'd.)
(For Harvest)

Season	Peppers Acreage	Potatoes Acreage	Squash Acreage	Tomatoes Acreage	Total Vegetables Acreage	Season
1925-26	3,370	23,070		20,700	81,190	1925-26
1926-27	2,700	28,000		29,800	97,510	1926-27
1927-28	6,410	30,000		29,280	115,770	1927-28
1928-29	5,650	22,000		38,700	122,480	1928-29
1929-30	6,550	31,000		31,260	131,000	1929-30
1930-31	8,200	27,000		26,800	130,550	1930-31
1931-32	8,050	21,500		23,700	121,850	1931-32
1932-33	8,300	17,000		24,900	127,150	1932-33
1933-34	6,000	23,500		30,500	153,150	1933-34
1934-35	7,700	24,800		32,500	156,750	1934-35
1935-36	6,500	24,500		32,600	156,350	1935-36
1936-37	7,200	31,300		35,700	166,380	1936-37
1937-38	7,400	31,400		45,300	183,600	1937-38
1938-39	7,300	26,700		40,700	177,500	1938-39
1939-40	6,200	25,600		34,000	163,250	1939-40
1940-41	7,200	26,800		26,500	165,900	1940-41
1941-42	6,500	25,000		43,000	195,100	1941-42
1942-43	7,100	26,200		25,500	176,850	1942-43
1943-44	8,950	28,600		34,900	223,950	1943-44
1944-45	9,350	31,100		32,500	204,150	1944-45
1945-46	11,080	35,300		30,400	211,730	1945-46
1946-47	10,550	24,100		29,800	200,350	1946-47
1947-48	11,450	20,800	7,900	30,200	205,425	1947-48
1948-49	11,100	20,300	9,000	38,200	221,350	1948-49
1949-50	13,750	23,200	10,100	42,500	245,150	1949-50

Season	Cantaloupes (1) Acreage	Strawberries Acreage	Watermelons Acreage	Grand Total Officially Reported Acreage (2)	Season
1925-26	600	2,980	24,150	108,920	1925-26
1926-27	600	3,680	29,420	131,210	1926-27
1927-28	600	4,500	37,840	158,710	1927-28
1928-29	600	6,300	35,900	165,280	1928-29
1929-30	600	8,800	34,700	175,100	1929-30
1930-31	250	9,100	31,000	170,900	1930-31
1931-32	200	7,800	28,500	158,350	1931-32
1932-33	400	10,600	22,500	160,650	1932-33
1933-34	300	8,400	23,400	185,250	1933-34
1934-35	200	8,000	20,000	184,950	1934-35
1935-36	200	8,900	16,000	181,450	1935-36
1936-37	300	8,800	19,500	194,980	1936-37
1937-38	700	7,500	22,500	214,300	1937-38
1938-39	500	9,000	22,600	209,600	1938-39
1939-40	500	7,200	23,500	194,450	1939-40
1940-41	500	5,500	25,500	198,100	1940-41
1941-42	500	5,000	21,500	221,200	1941-42
1942-43	400	2,600	12,500	192,350	1942-43
1943-44	550	1,400	25,500	251,400	1943-44
1944-45	500	2,050	39,000	245,700	1944-45
1945-46	800	2,800	51,000	266,330	1945-46
1946-47	800	4,750	47,000	252,900	1946-47
1947-48	1,200	4,200	45,000	255,825	1947-48
1948-49	1,200	4,000	59,000	285,550	1948-49
1949-50	1,400	5,400	63,000	314,950	1949-50

NOTES: (1) Acreage of cantaloupes for 1926, 1927 and 1928 seasons is estimated the same as for 1929 and 1930 seasons.

(2) These acreage figures do not include acres abandoned in various stages of growth for reasons other than economic marketing, that is, poor markets. Does not include any commodities not reaching harvest stage. Some additional acreage was abandoned for marketing reasons.

All acreage figures are preliminary as of September 20, 1950 and are subject to revision. Years prior to 1947-48 may have been revised slightly.

FLORIDA LIVESTOCK MARKET

(Substantially Southeastern Price Ranges Per Cwt)

	COWS		CALVES		STEERS		HOGS	
	Medium	Common	Good	Medium	Good	Medium	No. 1	No. 2
	100 Lbs.		100 Lbs.		100 Lbs.		100 Lbs.	
1930								1930
3-4	5.00-6.00	4.00-5.50	7.00-8.25	5.50-7.00	7.00-8.50	6.00-7.00	8.50	7.50
9-5	3.75-4.50	3.25-3.75	5.00-6.50	4.00-5.00	5.00-6.00	4.00-5.00	9.25-9.50	8.25-8.50
1931								1931
3-3	3.50-4.25	2.50-3.50	5.50-6.50	4.75-5.50	5.50-6.75	4.50-5.50	6.00	5.50
9-4	2.50-3.25	2.00-2.75	4.00-5.00	3.00-4.00	4.00-4.75	3.00-4.25	5.25	4.75
1932								1932
3-4	2.50-3.00	1.75-2.50	3.50-4.75	3.00-4.00	3.50-4.25	3.00-3.75	3.50	3.20
9-6	2.25-2.75	1.25-2.00	3.75-4.25	3.00-3.50	4.00-5.25	3.50-4.25	3.75	3.50
1933								1933
3-7	2.00-2.50	1.50-2.00	3.25-3.75	3.00-3.25	3.50-4.25	3.00-3.50	2.65	2.40
9-5	2.00-2.75	1.00-2.00	3.25-3.75	2.50-3.25	3.75-4.25	3.00-3.75	3.75-4.00	3.50-3.75
1934								1934
3-6	2.25-2.75	1.50-2.25	4.00-4.75	3.00-4.00	4.00-4.50	3.50-4.00	3.75-4.00	3.50-3.75
9-4	2.00-2.50	1.00-2.00	3.50-4.25	2.50-3.75	4.00-4.25	3.25-4.00	5.40-5.60	4.90-5.90
1935								1935
3-5	3.50-4.00	1.75-3.25	5.50-6.50	3.75-5.25	6.25-7.25	5.00-6.25	7.00-7.25	6.25-6.50
6-7	3.25-4.50	2.00-3.50	5.25-6.25	4.50-5.50	6.00-7.50	4.75-6.00	7.25-7.50	6.50-6.75
9-6	2.75-4.25	2.00-2.75	5.50-6.50	4.50-5.50	5.50-6.25	4.00-5.25	9.25-9.75	8.75-9.25
12-6	3.25-4.50	2.50-3.25	5.00-5.75	4.00-5.25	5.75-6.75	4.75-6.00	7.75-8.00	7.25-7.50
1936								1936
3-6	4.00-5.00	3.25-4.00	5.75-6.50	4.50-5.75	6.00-7.00	5.00-6.00	7.50-7.75	7.00-7.25
6-5	4.25-5.00	3.50-4.25	5.25-6.00	4.50-5.25	6.25-7.00	5.75-6.50	8.00-8.50	7.50-8.00
9-4	3.75-4.50	3.00-3.75	5.00-6.00	4.25-5.00	5.50-6.00	4.50-5.50	9.00-9.50	8.50-9.00
12-4	3.50-4.00	2.75-3.50	5.00-6.00	4.25-5.25	5.25-6.00	4.50-5.25	8.60-8.90	8.10-8.40
1937								1937
3-12	4.00-4.50	3.25-4.00	5.25-5.75	4.00-5.25	6.00-7.25	5.00-6.50	8.00-8.40	7.60-7.90
6-4	4.50-5.00	3.50-4.25	5.75-6.50	4.75-5.50	7.00-8.00	5.50-6.75	9.50-10	9.00-9.50
9-7	4.00-5.25	3.00-4.00	5.50-6.00	4.50-5.25	6.00-7.25	5.00-6.25	8.75-9.00	8.25-8.50
12-7	4.00-4.50	3.00-4.00	5.00-5.50	4.00-5.25	6.00-7.00	5.00-6.00	6.25-6.65	6.00-6.40
1938								1938
3-4	4.25-5.00	3.25-4.25	5.25-6.50	4.50-5.50	6.25-7.00	5.50-6.50	6.75-7.75	6.25-7.25
6-7	4.50-5.25	3.50-4.25	5.50-7.00	4.50-5.50	6.50-7.50	5.50-6.50	7.70	7.20
9-6	4.00-5.00	3.00-4.00	5.00-6.00	4.50-5.25	6.25-7.00	5.50-6.50	7.00	6.50
12-3	4.00-4.50	3.00-4.00	5.50-6.75	4.50-5.50	6.50-7.50	5.50-6.50	6.00	5.50
1939								1939
3-4	4.75-5.50	3.75-4.75	6.50-7.50	5.00-6.50	7.00-8.00	6.00-7.00	6.85	6.30
6-3	5.00-5.75	4.00-5.00	6.00-7.50	5.00-6.00	6.50-8.00	5.50-6.50	6.00	5.50
9-2	4.50-5.25	4.00-4.75	5.75-7.25	4.75-5.75	6.50-7.50	5.50-6.50	5.90	5.40
12-2	4.50-5.25	3.75-4.50	6.00-7.25	5.00-6.00	7.00-7.75	6.00-7.00	4.90	4.65
1940								1940
3-2	5.00-5.75	4.00-5.00	6.25-7.25	5.25-6.25	7.00-8.00	6.00-7.00	5.00	4.75
6-1	4.75-5.25	3.75-4.75	6.50-7.50	5.50-6.50	7.00-8.25	6.00-7.00	5.25	5.00
9-7	4.25-5.00	3.75-4.50	6.00-7.00	5.00-6.00	6.75-7.75	5.50-6.75	6.75	6.50
12-7	4.25-5.00	4.00-4.50	6.00-7.00	5.00-6.00	7.00-8.25	6.00-7.00	5.65	5.40
1941								1941
3-1	5.25-6.00	4.50-5.25	6.25-7.50	5.25-6.50	7.50-8.75	6.50-7.50	6.50	6.00
6-7	5.25-6.25	4.25-5.25	6.75-7.75	5.50-6.50	7.75-8.50	6.75-7.75	8.90	8.40
9-6	5.50-6.75	4.50-5.50	7.50-8.75	6.50-7.50	8.00-9.00	7.00-8.00	10.25	9.75
12-5	5.50-6.50	4.25-5.50	7.00-8.00	6.00-7.00	7.50-8.50	6.50-7.50	8.25	7.75
1942								1942
3-6	7.50-8.25	5.75-7.25	8.20-10	6.75-8.00	9-10.50	8.00-9.00	11.25	10.75
6-6	7.00-8.50	6.00-7.00	9.00-11	7.00-9.00	10-11.50	8.75-10	12-13.00	11.5-12.5
9-4	7.50-8.50	6.25-7.50	10-11.00	8.00-10	9.75-11¼	8.00-10	12.75-13¼	12¼-12.75
12-4	7.50-8.50	6.00-7.25	10.00-11¼	8.00-10	9.25-11	8.00-9.25	11.50-12	11-11.50
1943								1943
3-5	9.00-11	7.50-8.75	11.00-13	9.00-11	11-13.50	9.00-11	13.75-14¼	13¼-13.75
6-4	9-10.50	7.00-8.75	11.00-13¼	9.50-11	11-13.50	9½-11.25	13¼-13.75	12.75-13¼
Sept	9.00-10.5	8.00-9.00	12-13.50	12.00-13	13.00	12.00-13	13.50-14¼	12.75-13.5
Dec	8.50-10	7.25-8.50	12-12.50	11-11.50	12-15.30	9.50-12	11¼-12.50	10.5-11.75
1944								1944
Mch	9.75-11	9-10.00	12-14.00	11-12.00	13.25-15	11.5-13.5	12-13.25	11¼-12.50
June	9.25-10.5	8.00-9.00	13-14.00	11-12.00	13.50-15	10-13.50	12-13.00	11.25-12¼
Sept	8.25-10	6.75-8.30	12-14.00	9.50-11½	12½-14½	9.50-12¼	13-14.25	12-14.00
Dec.	8.60-10	7.25-8.50	12.50-14	9.75-12	12.50-14½	9.75-13	12-13.25	11¼-13¼
1945								1945
1-4	9.25-11.5	8-10.00	12.75-15½	10½-14	13½-15½	11-14.00	12-14.35	11¼-14.35
5-8	9.50-11½	9-10.00	13-15.00	9.50-13½	14-16.00	11¼-14½	14¼-14.35	14¼-14.35
9-12	9.50-11½	8-9.50	12-15.00	9½-13.50	13-15.50	11-13.50	13.75-14.35	13.75-14.35

FLORIDA LIVESTOCK MARKET

(Substantially Southeastern Price Ranges Per Cwt)

	COWS		CALVES		STEERS		HOGS
	Medium	Common	Good	Medium	Good	Medium	
	100 lbs		100 lbs.		100 lbs.		180-240 lbs.
1946							
1-4	10.00-14.00	8.50-11.50	13.50-16.50	11.00-16.00	14.50-17.	12-16.00	14.00-14.35
5-8	11.50-15.00	9.10-14.50	14.00-18.00	11.00-16.50	14.50-19	12-17.00	14.35-22.00
9-12	10.20-15.60	8.40-14.40	13.00-18.00	11.00-17.00	14.00-19	11-18.00	15.00-26.00
1947							
1-4	12.50-16.50	10.00-14.00	15.50-23.75	13.00-19½	15.75-24.85	13-21½	17.50-26.25
5-8	14.00-17.00	10.00-14.00	18.00-23.00	14.00-19.00	18½-23.50	15-20.00	19.00-25.50
9-12	14.00-20.00	11.00-16.00	17.00-25.00	14.00-20.00	18 -26.00	14-22.00	22.00-26.75
1948							
1-4	18.00-24.00	15.00-20.50	23.50-30.00	18.50-25.50	23½-28½	18-25.50	17.00-25.50
5-8	19.50-25.00	18.00-21.50	25.00-34.00	21.50-28.00	25¾-33.00	21½-29	18.00-27.25
9-12	18.00-23.00	16.00-20.50	23.00-29.00	19.00-26.00	23½-29.00	19½-26½	20.25-27.50
1949							
Jan	18.50-22.00	17.00-20.50	24.00-29.00	20.00-25.50	24-28.50	20-25.00	18.50-19.50
Feb	18.00-20.50	16.50-19.50	23.50-28.50	20.00-26.00	21-26.00	19½-24½	17.75-19.00
Mar	18.50-21.00	17.00-20.00	24.00-28.50	22.00-26.50	22-26.00	20-24.50	18.25-18.75
Apr	19.00-21.50	17.50-20.50	24.50-28.00	22.00-25.50	23-27.00	21½-25	17.00-18.00
May	19.00-21.00	17.50-20.00	23.50-27.00	21.00-25.00	23-27.00	21½-24	17.00-20.50
June	19.00-21.00	17.00-20.00	23.50-27.50	21.50-25.50	23-27.00	21½-24½	20.00-21.50
July	18.00-19.50	16.00-18.50	22.00-25.00	19.50-24.00	23-25.00	20-23.50	21.00-22.00
Aug	16.00-18.00	14.00-16.50	20.50-23.50	18.50-22.00	22-24.50	18½-22	18.75-21.75
Sept	16.50-18.50	14.00-17.50	20.00-24.00	18.00-23.00	22½-25.00	18½-22½	18.00-20.00
Oct	16.00-18.00	14.00-17.00	19.00-23.00	17.50-21.50	22-24.50	18-22.50	15.00-17.50
Nov	16.00-17.50	14.00-16.50	19.50-23.50	18.00-21.50	22-24.50	18-22.50	14.50-17.00
Dec	17.00-19.00	15.50-18.00	22.00-26.00	19.00-25.00	22½-25.00	19½-23	15.00-15.75
1950							
Jan	18.00-20.00	16.50-19.00	24.00-28.00	20.50-27.00	23-26.00	20-24.50	15.00-16.25
Feb	18.50-21.00	16.50-20.00	25.00-30.00	21.50-28.00	23.50-27.	20½-25	15.50-16.50
Mar	19.00-22.00	17.50-21.00	25.00-33.00	22.00-30.00	24½-27½	22-26.00	14.50-16.00
Apr	19.50-22.00	18.00-21.00	25.00-30.00	22.50-28.00	24½-27.00	22½-25½	14.75-16.00
May	21.00-23.00	18.50-22.00	25.50-34.00	23.00-33.00	25-28.00	23-26.50	16.25-19.50
June	21.00-24.00	19.50-22.50	26.50-34.00	23.50-33.00	26½-29.00	23½-27½	18.75-20.25
July	20.50-24.50	21.00-23.50	27.00-31.00	23.50-28.50	27-29.50	23½-28	20.50-23.75
Aug	21.00-24.50	20.00-23.00	27.00-31.00	23.00-28.50	27-29.50	23-28.00	21.25-23.25
Sept	21.50-25.00	20.50-23.50	27.00-33.00	23.50-31.00	26½-29½	23-27.50	18.00-21.00

LEADING LIVESTOCK COUNTIES IN FLORIDA (Dept. of Commerce US Census '45)

County Cattle & Calves	County Hogs & Pigs	County Goats & Kids	County Sheep & Lamb	County Horses & Colts	County Mules & Colts
Polk	Jackson	Jackson	Santa Rosa	Polk	Jackson
Highlands	Suwannee	Marion	Washington	Marion	Gadsden
Osceola	Levy	Alachua	Polk	Hillsborough	Madison
Hardee	Alachua	Levy	Walton	Alachua	Holmes
Hillsborough	Madison	Washington	Osceola	Jackson	Suwannee
Marion	Santa Rosa	Santa Rosa	Duval	Sumter	Alachua
DeSoto	Holmes	Escambia	Alachua	Hardee	Jefferson
Okeechobee	Marion	Taylor	Nassau	Santa Rosa	Washington
Alachua	Gadsden	Suwannee	Calhoun	Levy	Columbia
Levy	Columbia	Union	Escambia	Palm Beach	Santa Rosa
Pasco	Jefferson	*Gadsden	Marion	Escambia	Hillsborough
Jackson	Hamilton	*Columbia	Osceola	Osceola	Leon
Manatee	Washington	Polk	Hillsborough	*Leon	Marion
Sumter	Walton	Holmes	Brevard	*Pasco	Walton
Collier	Gilchrist	Hillsborough	Liberty	Washington	Calhoun

*The same number of head for species by county

Florida's Rank in Number of Livestock- 1950 (USDA, BAE Preliminary Estimate): Beef cattle 1,099,000 head(rank 12th);Milk cows 293,000(34th); Total cattle (24th) Hogs & Pigs 619,000(26th);Sheep & Lambs 12,000(41st);Horses & colts 23,000 (41st) Mules & colts 28,000(13th);Chickens 2,942,000(38th);Turkeys 25,000(38th).

It is difficult to make a statement as to the exact losses incurred to livestock in the USA as it involves (1)bruises, injuries, cripples and deaths on the farm, to market, in yards, and at packing plants. It is estimated that bruises and injuries take a toll of about $14,000,000 annually(USA),and possibly $450,000 in Florida annually. (2) External and internal parasite damage is very difficult to arrive at; but would probably be near $125,000,000(USA) and possibly $500,000 in Florida. (3) The loss in calf and pig crop from malnutrition,improper feeding,care and management at birth and during the feed period possibly amounts to in Florida some $4,000,000 annually on hogs and possibly $5,000,000 on cattle due to low crop of pigs and calves born and raised. The calf crop has been from 57 to 64% annually when it should have been 85% or more. The number of pigs raised is about 60% of the total born. These losses could and should be corrected.

These losses happen (1) on the farm,(2)in transit,(3)at public markets and(4) at slaughtering plants. They are caused by inferior breeding stock as to bone, conformation, quality and ability to finish. Often it is caused by lack of suitable minerals, protein supplements combined with sufficient good feed and grazing crops to keep the animals thrifty and growing.

Animals should be given the proper amount of feeds to properly develop them. Grazing crops make up a large portion of the low cost feeds and these crops are very important as they help to reduce losses from parasites by (1) cutting the mortality rate,(2)reducing the parasitic infection,(3)improving general thriftiness of the animal; at the same time these grazing crops help to prevent(1) waste in time,(2) waste in feed,(3) waste of animal life and (4) waste of income.

Some of the biggest losses are caused by(1) defective shipping equipment such as broken boards, protruding nails,holes in the floor in cars and trucks and non-installed bull-boards in cars,etc;(2) poor bedding(and there is only one good bedding- 4 inches of sand);(3) clubs,prod-poles, sharp corners, unnecessary obstructions in the feed lots and yards;(4) slippery footing, rush loading, overcrowding;(5)loss of temper, sharp horns on cattle, sharp tusks on hogs; (6) internal injuries caused by swallowed-wire, feeding clips, etc;(7) preventable diseases such as T.B.,Bang's, blackleg, anthrax, cholera, etc; (8) poor feed conditions due to lack of balanced diet(lack of mineral and protein supplements,etc.)-resulting in emaciation, reduced calf, pig or lamb crop, and often resulting in death prior to, during and after shipments;(9) shipping-colds or shipping-fever caused by insanitary conditions often produced by 4-overs- Over-fatigue, over-exposure,over-crowding and over-filling;(10) insanitary conditions resulting in the production of a number of species of worms in cattle, hogs, sheep,poultry,etc.,and the loss of thousands of dollars in livers, kidneys and casings;(11) the lack of good shipping equipment including corrals, chutes, squeezes, loading and unloading pens;(12)the lack of shade and water;(13) irregular driving speed or jerky driving, and taking curves too fast;(14) mixing species in loads, such as horses, cattle, hogs,and sheep, and/or mixing classes, such as cows, steers, heifers, calves and bulls, or mixing a class within a load where there is a great difference in age,condition or weight;(15) not stopping for rest and water often enough to preclude "downers", and if "downers" occur get them up on their feet as soon as possible to prevent trampling; and(16) or other means which may lessen the comfort and/or add to the losses from bruises, injuries, cripples and deaths.

Many of these losses can be prevented by(1) feeding mineral for strength of bone to help carry the animal to market,(2) sufficient protein to properly balance the feed and to give strength,(3)by providing sufficient feeds to properly grow out the animal,(4) by proper care and management practices and (5) by exercising proper care,good judgment and practices at shipping time. Other practices include adequate feeding trough and feed rack space when feeding, comfortable shelters, dehorning of calves destined for feed lots, ample and convenient sorting pens or corrals and chutes and loading facilities on the farm and at shipping point. It is important to see that the equipment used in transportation is in good condition,free of nails, broken boards, wire, or other sharp objects; avoid striking and kicking of animals. If one decides to kick an animal, let him first remove his shoe. Do not feed just prior to shipment and water sparingly. Handle animals quietly -not in haste or excitement; segregate classes within a species or do not ship bulls and cows and calves in the same car unless amply partitioned. Likewise do not ship cattle and hogs and/or calves mixed in trucks or cars except partitioned. Use 3 to 4 inches of sand as bedding, never use sawdust or straw as it may cause slipping. Do not overcrowd, overheat, overtax or overload. Use canvas slappers but never use clubs or canes. Slow down on sharp curves and do not start or stop suddenly.

Losses from disease and foreign objects take a tremendous toll. Greater sanitary conditions will help eliminate waste at market time. All breeding animals should be tested for Bang's, and Tuberculosis, and calves treated for Blackleg and pigs for Cholera. Often shipped cattle will rapidly overcome shipping colds if they are given one pound of baking soda to 12 gallons of water for cattle to drink when unloaded or after they have had time to eat some hay after unloading. Insanitary conditions lead to increased tuberculosis among hogs, cattle and sheep, and increase worms in cattle, hogs and sheep. Pericarditis (puncture of heart or heart membrane by foreign objects) causing death, occurs by wires, nails, stones, clips, and other foreign objects often found in feeds. Be careful in this respect.

Internal and external parasites take a tremendous toll. Each producer should have Agricultural Year Book,1942,"Keeping Livestock Healthy". Write U.S.Senator.

Shipping fever is generally caused by (1)over-fatigue; (2)over-exposure,(3) over-crowding,(4)over-filling. The use of baking soda as outlined above as the first water after being unloaded will do much to preclude shipping fever and/or overcome it. The amount of soda may be reduced gradually until after a period of 4 or 5 days they are on water without it. The length of time the soda would be given would depend on how serious the cold. All cattle destined for feed lots should have it when unloaded. If the cold is not serious, do not give them soda water over 1 to 2 days. If the cold is serious, animals should be isolated from others and treated until over the cold,and/or see your Veterinarian.

Grubs in cattle are caused by heel flies, warbles, and/or cattle grubs. They are causing from $1 to $3 a head loss annually wherever the grubs are found.

Improper branding of hides or branding on the upper portion of the animal's body where the higher prices of the hide are found, decreased the value of cattle hides and calf skins from 1¢ to 3¢ per lb.,depending upon the location and extent of the brand.

In loading cattle one should keep in mind that the length of the car,average weight per head, the condition of the animal, etc. has much to do with the number of head loaded per car. If cattle or calves are in good condition,normally it will take about 56 head of 300 lbs.weight each or 45 head of 400 lbs. each or 40 head of 500 lbs. each, 36 head of 600 lbs. each, 31 head of 700 lbs. each, 28 head of 800 lbs. each, 25 head of 900 lbs. each or 22 head of 1,000 lbs. each to fill and/or properly load a 36 ft. car. Normally a 40 ft. car would carry about 2500 lbs.live weight more than the 36 ft. car. Thin and/or emaciated cattle must be loaded according to condition. It is difficult to state how many such cattle can be loaded in a car. One must therefore take into account condition of animals when determining the number to load in the car, or,the length of the car, condition of the animal, average weight per head, and other factors will help to determine how many animals to load in car. One should not overload,but should load snugly-not tight.
Hogs: 80 hogs 200 lbs or 90 hogs 160 lbs or 16,000 lbs fat hogs will fill 36 ft car.

Every producer should know grades of livestock and should sell by grade and weight. Some benefits of classifying and grading are - Animals can be sold according to their value, will be accepted by buyers when not present, can be accurately reported as Market News, be a guide for production, breeding and feeding operations, makes for comparisons of markets by grade and price, and provides the basis for statistical study of supplies, demand, prices, and movement.

L.H.Lewis, Marketing Specialist,Livestock and Field Crops,Fla.State Marketing Bureau
Gifford N.Rhodes, Livestock Market News Specialist, Florida State Marketing Bureau.

1949 SLAUGHTER-FLORIDA- CATTLE & HOGS(USDA,BAE Preliminary Estimates)

1949 Month	CATTLE & CALVES Number	Pct. by Months	Live Weight Total (000)	Live Weight Ave.	HOGS Number	Pct. by Months	Live Weight Total (000)	Live Weight Ave.
Jan	36,000	10.04	20.002	556	94,000	17.94	13,074	139
Feb	25,000	6,97	13,824	553	61,000	11.64	9,566	157
Mar.	28,700	8.00	16,861	587	53,000	10.12	8,541	161
Apr	27,600	7.70	16,035	581	32,000	6.11	5,504	172
May	26,900	7.50	14,650	545	19,000	3.63	3,255	170
June	30,600	8.53	17,000	556	17,000	3.24	2,902	172
July	30,000	8.37	15,869	529	16,000	3.05	2,889	184
Aug	31,500	8.78	16,668	529	19,000	3.63	3,263	176
Sept	32,900	9.18	17,557	534	29,000	5.53	4,725	162
Oct	30,700	8.56	15,881	517	48,000	9.16	7,906	164
Nov	30,600	8.53	18,781	614	62,000	11.83	9,058	146
Dec	28,100	7.84	15,756	561	74,000	14.12	11,442	154
TOTAL:	358,600	100%	198,884	555	524,000	100%	82,125	157

Estimated Receipts
Florida Livestock Auctions, 1949

Cattle & Calves Number	Pct.	Hogs Number	Pct.
16,436	6.77	44,356	10.61
11,667	4.81	26,281	6.29
18,523	7.63	23,054	5.51
19,074	7.86	14,328	3.43
22,346	9.21	13,446	3.22
21,522	8.87	20,913	5.00
23,741	9.79	28,961	6.93
24,716	10.19	43,281	10.35
25,869	10.66	44,008	10.53
23,814	9.82	53,657	12.83
21,951	9.05	60,653	14.51
12,968	5.34	45,120	10.79
242,627	100%	418,058	100%

The shipments and sales of cattle are generally heavier from July thru January than from February thru June. As to calves, the shipments are generally heavier per months August thru January as compared with February thru June, and Hog shipments are heavier during the months of Deember, January, February and March, with 75% October - March. We suggest adjusting feed conditions to more evenly distribute the marketings or finishing livestock for market so as to feed the markets.

POINTS IN A BEEF CATTLE PROGRAM FOR FLORIDA

(1) Know desirable animals as to conformation, type and quality and the productive breeding history of each animal. In cows select good milkers, thrifty and good doers. Cull out shy-breeders, bad udders, poor conformation and quality, unthrifty and slow growing kind. Cows should be fast breeders and have a tendency to calve each year,- be docile. (2) The bulls should be better than the best cow in the cow herd - be highly desirable in conformation and quality,have natural ability to grow fast, docile yet a hustler. (3) Heifers should not be bred until 2 years old but before 3 yrs old. (4) In buying, buy off of farms and/or thru facilities which are kept clean of disease and parasites. Keep a clean herd or test regularly for Bangs and TB and inoculate for Blackleg. (5) Segregate classes in pastures according to purpose,- have pastures (a) for bulls, (b) for the breeding herd, (c) for steers, (d) for heifers not breedable age,etc. (e) Steers of different weights should be separated by groups so not over 150 lbs. in extreme weights.(6) Provide plenty of feed as pastures, cakes and pellets.(7)Go after and get a calf crop.(8)Eliminate bruises & use best markets.

Month	NUMBER OF HEAD							
	CATTLE AND CALVES				HOGS			
	Truck	Rail	Total	Pct.by Months	Truck	Rail	Total	Pct. by Months
Jan.	3,657	424	4,081	4.3	14,018	3,015	17,033	12.0
Feb.	2,599	764	3,363	3.5	7,033	2,638	9,671	6.8
March	6,090	3,310	9,400	9.8	6,484	283	6,767	4.8
April	9,393	6,110	15,503	16.2	3,985	-	3,985	2.8
May	7,768	3,225	10,993	11.5	3,145	-	3,145	2.2
June	7,692	340	8,032	8.4	6,755	-	6,755	4.8
July	7,600	891	8,491	8.9	10,379	-	10,379	7.3
Aug.	7,365	1,867	9,232	9.6	13,937	94	14,031	9.9
Sept.	6,619	1,782	8,401	8.8	15,303	1,225	16,528	11.7
Oct.	6,075	1,061	7,136	7.4	20,310	2,167	22,477	15.9
Nov.	5,953	891	6,844	7.1	16,151	1,602	17,753	12.6
Dec.	3,519	764	4,283	4.5	11,845	1,131	12,976	9.2
Total	74,330	21,429	95,759	100%	129,345	12,155	141,500	100%
Percent	77.6	22.4	100%		91.4	8.6	100%	

Of the 95,759 cattle and calves, an estimated 34,019 head were shipped out for slaughter, 56,849 as stockers and 4,891 milk . Of the 141,500 head of hogs, an estimated 116,242 were for slaughter, 25,258 as feeders.
Sources: Truck: For counties east and south of Suwannee River,(Jan.1-June 19, 1949, Oct.19-Dec.31,1949), from daily reports sent in by Florida State Dept. of Agriculture Truck Passing Stations. Figures for June 19-Oct.19 estimated. For counties west of Suwannee River, from data tallied on Markets by USDA,PMA, Livestock Market News Office, Thomasville, Ga. Rail: Combined numbers of carlots supplied by J.C.Townsend, Jr., Agricultural Statistician, USDA, BAE, Orlando,Fla.

FLORIDA CITRUS BY-PRODUCT FEEDS

Season Year	Citrus Pulp Tons	Citrus Meal Tons	Citrus Pellets Tons	Citrus Molassos Tons
1949-50	150,611.92	12,575.74	203.55	41,388.73
1948-49	129,570.45	-	-	39,263.97
1947-48	154,181.62	-	-	65,887.38
1946-47	96,224.60	-	-	58,034.30
1945-46	108,470.41	-	-	44,168.63
1944-45	63,724.52	-	-	19,260.55
1943-44	67,130.50	-	-	14,496.21
1942-43	47,367.10	-	-	-
1941-42	29,696.73	-	-	-
1940-41	32,730.64	-	-	-
Last 5 yrs	127,612 Average			49,748.6
10 yrs	88,471 "			-

Source Data- Citrus Processors Association,Inc., Lakeland,Fla.

FLORIDA CORN PRODUCTION

The average corn production in Florida for the past 12 years , 7,560,000 bushels. produced on 7,275,000 acres. During the past 2 years the average production and indicated production(years 1949 & 1950) about 12 bushels per acre. In grain or corn equivalent we need about 35,000,000 bushels to properly develop our livestock-not including finishing cattle in feed lots. The citrus by-product above will help supply some of this need-still we need more corn.

FLORIDA'S POSITION AS A CATTLE STATE
(Total Cattle, Dairy and Beef Cattle)
LIVESTOCK ON FARMS, JANUARY 1, 1950

STATE	Total Cattle No. (000)	Rank	Number Milk Cattle Cows&Hfrs 2 yrs&over (000)	Hfrs 1-2yr. (000)	Hfrs Cfs (000)	Total No. MilkCattle (000)	Rank	Beef Cattle Number (000)	Rank
Maine	214	43	121	35	38	194	38	20	41
New Hampshire	118	46	70	17	21	108	42	10	44 & 45*
Vermont	433	40	288	61	65	414	28	19	42
Mass.	179	44	123	22	25	170	40	9	46
Rhode Island	27	48	21	2	3	26	48	1	48
Connecticut	174	45	118	21	25	164	41	10	44 & 45*
New York	2,226	12	1,483	305	322	2,110	3	116	38
New Jersey	226	42	162	27	26	215	36	11	43
Penna.	1,790	15	1,020	252	276	1,548	9	242	35
Ohio	2,149	13	1,060	264	279	1,603	6	546	27
Indiana	1,760	16	728	156	187	1,071	13	689	22
Illinois	3,159	7	992	252	322	1,566	7	1,593	7
Michigan	1,914	14	1,016	260	288	1,564	8	350	33
Wisconsin	3,804	4	2,432	529	545	3,506	1	298	34
Minnesota	3,276	6	1,486	374	397	2,257	2	1,019	14
Iowa	5,007	2	1,182	275	320	1,777	5	3,230	2
Missouri	3,107	8	975	180	227	1,382	11	1,725	6
No.Dakota	1,542	21	421	94	154	669	23	873	17
So.Dakota	2,479	11	379	97	186	662	24	1,817	5
Nebraska	3,920	3	477	119	206	802	18	3,118	3
Kansas	3,627	5	628	134	185	947	14	2,680	4
Delaware	61	47	37	9	9	55	46	6	47
Maryland	449	39	245	55	59	359	31	90	40
Virginia	1,108	29	497	87	120	704	21	404	30
W.Virginia	559	37	234	45	46	325	32	234	36
No.Carolina	710	35	387	75	94	556	25	154	37
So.Carolina	367	41	172	37	48	257	35	110	39
Georgia	1,220	26	406	113	151	670	22	550	26
FLORIDA	1,392	24	152	56	85	293	34	1,099	12
Kentucky	1,608	20	634	102	129	865	16	743	20
Tennessee	1,462	22	640	117	142	899	15	563	25
Alabama	1,330	25	430	134	182	746	19	584	23
Miss.	1,674	19	543	121	171	835	17	839	18
Arkansas	1,209	27	444	109	160	713	20	496	29
Louisiana	1,439	23	331	78	124	533	26	906	16
Oklahoma	2,655	10	654	165	255	1,074	12	1,581	8
Texas	8,658	1	1,296	277	398	1,971	4	6,687	1
Montana	1,731	18	128	29	50	207	37	1,524	9
Idaho	939	32	222	59	82	363	30	576	24
Wyoming	1,001	31	56	14	15	85	44	916	15
Colorado	1,746	17	202	42	58	302	33	1,444	10
New Mex.	1,166	28	60	12	18	90	43	1,076	13
Arizona	849	34	47	12	13	72	45	777	19
Utah	560	36	116	27	40	183	39	377	31
Nevada	552	38	21	7	13	41	47	511	28
Washington	885	33	329	77	103	509	27	376	32
Oregon	1,107	30	240	58	85	383	29	724	21
Calif.	2,709	9	920	217	283	1,420	10	1,289	11
U.S.	80,277		24,625	5,610	7,030	37,265		43,012	

Data taken from Crop Reporting Board statistics, BAE, USDA. Released Feb. 15, 1950.

FLORIDA'S POSITION AS A HOG, SHEEP, HORSE AND MULE STATE
LIVESTOCK ON FARMS, JANUARY 1, 1950

STATE	Hogs & Pigs		Sheep & Lambs		Horses & Colts		Mules & Colts	
	Number (000)	Rank	Number (000)	Rank	Number (000)	Rank	Number (000)	Rank
Maine	32	42	22	37(38)	25	40		
New Hampshire	13	47	7	44	10	45		
Vermont	21	46	12	40(41)	30	39		
Massachusetts	94	36	8	43	13	43		
Rhode Island	9	48	2	47(48)	1	48		
Connecticut	30	43	6	45	9	46		
New York	212	31	178	30	145	14	2	30
New Jersey	72	40	10	42	11	44	1	33
Pennsylvania	704	24	217	29	110	21	11	17(18)
Ohio	3,176	6	1,195	8	132	16	6	22(23)
Indiana	4,611	3	454	19	107	23	11	17(18)
Illinois	6,285	2	585	18	180	9	16	15
Michigan	927	19	425	21	100	25	1	34
Wisconsin	1,666	11	267	27	224	6	1	35
Minnesota	3,498	5	732	14	264	3	1	36
Iowa	11,920	1	949	11	242	4	6	22(23)
Missouri	4,429	4	1,194	9	347	2	79	11
No.Dakota	413	27	388	23	153	12(13)	1	37
So.Dakota	1,442	12	874	12	170	11	1	38
Nebraska	2,475	7	588	17	236	5	9	20
Kansas	1,253	14	786	13	206	8	14	16
Delaware	37	41	2	47(48)	7	47	3	28(29)
Maryland	270	29	47	35	41	36	8	21
Virginia	752	22	293	25	129	17	66	12
W.Virginia	256	30	296	26	86	26(27)	5	24(25-26)
No.Carolina	1,120	16	40	36	82	28	248	2
So.Carolina	663	25	3	46	21	42	151	6
Georgia	1,700	9	13	39	34	38	224	3
FLORIDA	619	26	12	40(41)	23	41	28	13
Kentucky	1,668	10	700	15	177	10	136	8
Tennessee	1,371	13	265	28	120	18	205	4
Alabama	1,225	15	22	37(38)	56	34	190	5
Mississippi	965	18	104	33	104	24	276	1
Arkansas	974	17	51	34	135	15	135	9
Louisiana	731	23	140	32	109	22	117	10
Oklahoma	835	21	155	31	213	7	27	14
Texas	1,701	8	6,821	1	352	1	139	7
Montana	192	33	1,735	4	153	12(13)	1	39
Idaho	209	32	1,065	10	86	26(27)	3	28(29)
Wyoming	85	38	2,063	2	80	30	1	40
Colorado	351	28	1,731	5	112	19	4	27
New Mexico	73	39	1,392	6	81	29	5	24(25-26)
Arizona	24	45	392	22	65	32	5	24(25-26)
Utah	88	37	1,332	7	57	33	1	41
Nevada	28	44	442	20	35	37	1	42
Washington	160	35	324	24	54	35	2	31
Oregon	166	34	689	16	72	31	2	32
California	879	20	1,769	3	111	20	10	19
United States	60,424		30,797		5,310		2,153	

Data taken from USDA, BAE, Crop Reporting Board statistics, released Feb. 15, 1950.

NUMBER OF CATTLE ON FARMS, VALUE PER HEAD, TOTAL VALUE, USA & FLORIDA, Jan. 1, Years indicated.
Florida data shows breeding cows, number of bulls needed & produced, Marketings and Income, USDA, BAE data.

	U S A			F L O R I D A										
Year	No. Head (000)	Avg. Value Head	Total Value (000)	No. Head (000)	Avg. Value Head	Total Value (000)	No. Cows Breeding (000)	No. P.B. Bulls Needed (a)	No. P.B. Bulls Supplied	No. Slaughtered Cattle (000)	No. Slaughtered Calves (000)	Gross Income (000)	Out-shipments Total	Out-shipments Stocker-Feeder
1929	58,877	$ 59.09	$3,479,041	600	$23.40	$14,040	335	13,350	250	84	83	$ 3,610		
1930	61,003	57.30	3,495,472	590	29.10	12,571	328	12,600	275	44	72	1,860		
1931	63,030	39.31	2,477,709	620	23.30	14,446	336	12,600	320	38	45	1,148		
1932	65,801	26.39	1,737,000	680	17.90	12,172	345	11,600	362	70	23	1,236		
1933	70,280	19.74	1,387,000	737	14.00	10,313	376	13,445	412	98	39	1,700		
1934	74,369	17.78	1,322,000	773	13.80	10,723	402	14,250	512	113	45	2,210		
1935	68,846	20.20	1,391,000	788	14.60	11,505	416	14,470	600	128	67	3,232		
1936	67,847	34.06	2,311,000	788	18.20	14,342	420	14,200	760	128	59	3,338		
1937	66,098	34.06	2,251,000	796	18.50	14,726	420	13,700	852	151	81	4,392		
1938	65,249	36.53	2,387,000	780	20.00	15,600	413	12,440	1,100	107	46	2,937		
1939	66,029	38.44	2,538,000	820	20.50	16,810	429	12,550	1,300	118	67	3,589		
1940	68,309	40.60	2,773,000	851	20.90	17,159	451	12,480	1,550	109	61	3,546	97,000	
1941	71,755	43.20	3,109,000	902	22.40	20,205	473	12,400	1,700	120	77	5,289	103,000	
1942	76,025	55.00	4,181,000	947	28.80	30,010	506	12,770	1,820	81	91	5,715	81,000	
1943	81,204	69.30	5,627,000	1042	37.90	41,501	567	14,460	1,850	99	92	9,080	93,000	
1944	85,334	68.40	5,837,000	1136	45.10	51,234	615	15,780	1,900	172	112	13,572	145,000	
1945	85,573	66.90	5,725,000	1159	42.50	49,258	628	14,750	2,100	124	32	16,450	173,000	726
1946	82,434	76.20	6,281,000	1205	46.80	56,394	660	16,330	2,400	126	28	19,558		5,616
1947	81,207	97.40	7,910,000	1265	54.00	68,310	686	16,540	2,650	224	180	22,781		19,016
1948	78,126	116.00	9,063,000	1265	58.70	74,256	718	16,845	2,825	241	154	31,055		24,744
1949	78,495	135.00	10,587,000	1265	74.20	93,863	668			159	133	22,295		
1950	80,277	123.00	9,873,710	1392	71.60	99,667	637							

(a) Bulls at rate 1 bull to 25 cows.

Of the 35,111,040 acres of lands in Florida, 22,000,000 to 25,000,000 are well adapted to the production of pasture and other feeds for livestock, or 6,000,000 to 8,000,000 acres of land could grow crops as feed for livestock and up to 14,000,000 additional acres could be put into sufficient pastures to support three times as many cattle and three times as many hogs as are now being produced in the State. This would more than supply the needed production to meet present consumption. Florida has the climate - long growing season, coupled together with a well-distributed rainfall and mild temperature; its lands are reasonably cheap and can be secured in small or large acreage. Grade, cross-breeds, and purebreds have done well on pastures-both native & improved and the good kinds have responded to long and short feeding.

AVERAGE RAINFALL in inches and TEMPERATURE in Degrees F. 35 years, by Months (Data from Weather Bureau)

Months	Jan.	Feb.	March	April	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Ave. Annual
Rainfall	2.79	2.96	3.23	2.83	4.21	6.76	7.17	7.22	6.67	4.37	2.23	2.83	53.27
Temperature	59.6	61.1	65.1	70.0	75.6	79.8	81.3	81.4	79.5	73.3	65.1	60.2	71.00

CATTLE & CALVES, INVENTORY NUMBERS, CALF CROP & DISPOSITION, PRODUCTION AND INCOME - FLORIDA, USDA, BAE Data**

Year	On hand Jan. 1 All Cattle (000)	On hand Jan. 1 All Cows 2 yrs.up (000)	Calves born Calf Crop	Calves born Number (000)	Marketings 2/ Cattle (000)	Marketings 2/ Calves (000)	Farm Slaughter Cattle (000)	Farm Slaughter Calves (000)	Deaths Cattle (000)	Deaths Calves (000)	Production Sold-Lbs. Live Wgt.	Price per 100 Lbs. Cattle	Price per 100 Lbs. Calves	Gross Income (000)
1924	740	402	45%	181	82	59	12	10	28	13	45,735	$ 3.65	$ 6.80	$ 2,157
1925	712	391	47	184	89	59	10	10	28	17	49,060	3.90	6.10	2,383
1926	684	382	52	200	110	75	8	10	21	20	60,875	4.50	6.50	3,221
1927	640	358	53	189	102	63	6	10	16	15	56,270	5.00	7.20	3,264
1928	612	343	54	185	88	66	7	3	16	17	49,390	6.50	8.00	3,627
1929	600	335	56	188	77	80	7	3	15	16	45,775	6.60	9.60	3,610
1930	590	328	54	176	54	68	10	4	16	16	42,055	5.20	8.50	1,860
1931	620	336	52	176	30	39	8	6	18	18	42,925	4.00	7.30	1,148
1932	680	345	54	185	63	15	7	8	18	18	54,395	3.20	5.10	1,236
1933	737	376	54	202	88	31	10	8	15	15	67,760	3.10	4.70	1,700
1934*	773	402	53	212	97	36	16	9	20	20	62,295	3.50	5.10	2,210
1935	783	416	57	237	119	62	9	5	20	25	65,290	4.60	6.10	3,232
1936	788	420	54	227	119	53	9	6	17	19	67,585	4.70	6.20	3,338
1937	796	420	58	244	142	74	9	7	16	15	75,960	5.20	6.40	4,392
1938	760	413	53	219	96	41	9	5	15	16	68,635	4.90	6.00	2,937
1939	820	429	58	249	103	60	15	7	23	20	70,825	5.20	6.40	3,589
1940	851	451	55	248	98	54	11	7	27	14	73,140	5.40	6.50	3,545
1941	902	473	58	272	104	68	16	9	33	17	79,520	6.70	7.70	5,289
1942	947	506	60	306	65	83	16	8	35	22	87,830	8.50	9.90	5,715
1043	1,042	567	57	322	82	85	17	7	38	23	102,045	10.60	12.00	9,080
1944	1,136	615	57	348	154	107	18	5	35	22	137,590	9.40	10.60	13,572
1945	1,159	628	65	409	65	120	124	32	33	29	149,895	10.00	11.20	16,450
1946	1,205	660	64	422	76	129	126	28	33	25	155,845	11.20	13.00	19,558
1947	1,265	686	64	438	207	176	17	4	31	27	168,280	12.20	14.00	22,770
1948	1,265	718	59	424	226	150	15	4	26	22	175,880	16.10	18.40	31,055
1949	1,265	668	64	428	143	128	16	5	19	22	124,695	15.60	18.20	22,295
1950	1,392	736	-	-	-	-	-	-	-	-	-	-	-	-

2/ excludes interfarm sales. *Includes Government purchases.

** Above data taken from several sources, combined by the Florida State Marketing Bureau.

Florida's position as Livestock State: 12th in beef; 24th total; 34th in dairying; Hogs 26th, Sheep 40, Horses 24, Mules 13th.
Position rated in number of head, not production or income. Note how the gross income has increased each 5 years starting 1930 -1935-1940-1945-1949. This increase in value was largely due to increase in numbers, quality and price.
There are two great needs: (1) Increase the calf and pig crop (pigs saved) and (2) feed to properly develop the Livestock.

NUMBER OF HOGS ON FARMS, VALUE PER HEAD, TOTAL VALUE, USA AND FLORIDA. JAN. 1, Years Indicated

Florida Data also Shows Number Slaughtered, Gross Income, and Average Weight Head Sold. BAE, USDA.*

	U S A			F L O R I D A					
Year	No. Head	Avg. Value Head	Total Value	No. Head	Avg. Value Head	Total Value	Number Slaughtered	Avg.** Weight Pounds	Gross Income
1929	59,042,000	$13.05	$ 770,498,000	531,000	$ 8.10	$ 4,301,000	451,000	142.1	$ 5,303,000
1930	55,705,000	13.76	766,501,000	519,000	7.50	3,893,000	458,000	140.2	5,257,000
1931	54,835,000	11.36	622,926,000	514,000	6.10	3,135,000	460,000	144.9	3,879,000
1932	59,301,000	6.13	363,000,000	534,000	3.60	1,923,000	484,000	142.8	2,483,000
1933	62,127,000	4.21	262,000,000	545,000	2.70	1,472,000	504,000	137.3	2,475,000
1934	58,621,000	4.09	240,000,000	515,000	3.15	1,622,000	463,000	139.2	2,748,000
1935	39,066,000	6.31	247,000,000	447,000	3.35	1,498,000	426,000	145.7	4,197,000
1936	42,975,000	12.71	546,000,000	447,000	5.60	2,503,000	472,000	154.8	5,364,000
1937	43,083,000	11.89	512,000,000	499,000	6.80	3,393,000	550,000	151.0	6,446,000
1938	44,525,000	11.26	501,000,000	519,000	5.90	3,062,000	610,000	161.5	6,320,000
1939	50,012,000	11.18	559,000,000	582,000	5.80	3,376,000	655,000	156.3	5,871,000
1940	61,165,000	7.78	476,000,000	600,000	4.30	2,580,000	575,000	159.0	4,598,000
1941	54,353,000	8.34	453,000,000	630,000	4.45	2,804,000	635,000	154.7	7,428,000
1942	60,607,000	15.60	945,000,000	630,000	6.80	4,284,000	646,000	163.6	10,808,000
1943	73,881,000	22.50	1,662,000,000	700,000	10.90	7,630,000	762,000	164.2	15,657,000
1944	83,741,000	17.50	1,467,000,000	770,000	10.30	7,931,000	772,000	153.8	13,876,000
1945	59,331,000	20.60	1,224,000,000	716,000	10.80	7,733,000	781,000	148.6	16,896,000
1946	61,301,000	23.90	1,468,000,000	630,000	12.70	8,001,000	727,000	164.3	19,312,000
1947	56,921,000	36.00	2,049,000,000	630,000	16.20	10,080,000	695,000	160.8	24,017,000
1948	55,028,000	42.80	2,356,000,000	640,000	23.40	14,976,000	747,000	163.0	24,687,000
1949	57,139,000	38.20	2,184,000,000	666,000	21.70	14,452,000	789,000	140.0 all)	21,355,000
1950	60,424,000	27.10	1,638,964,000	619,000	19.50	12,070,000	-	-	-

* Source BAE, USDA Crop Reporting, Crop Reporting & Income. Combined by Florida State Marketing Bureau.

** Average weight per head was obtained by dividing total production pounds by total head marketed or slaughtered.

Production vs. Consumption of Meats in Florida with 2,250,061 (1945 census) people consuming average per capita USA (10-yr period 1932-1941 or more nearly normal) Pork 68.83 lbs. Beef 54.53 lbs. Veal 7.75 lbs. Mutton & Lamb 6.73 lbs. Lard 12.67 lbs. would require 154,872,000 lbs. pork, 122,696,000 lbs. beef, 17,438,000 lbs. veal, and 15,143,000 lbs. mutton and lamb. On basis of production 1948, Florida produced58.17% of the Pork, 65.28% Beef and Veal, and practically none of the Mutton and Lamb (about 1%) and about 80% of the Lard. A good breeding program for hogs would include (1) selected sows of desired conformation and quality - intermediate type with 10 to 14 evenly spaced udders. (2) Breeding stock to be quiet and docile and adapted to local conditions. (3) Only good purebred boars should head up the herd. (4) Gilts replacing sows to be better than sows replaced. (5) Go after, get and save the pig crop. (6) Segregate classes as to size, age and weight. (7) Breed no gilts under 6 months of age. (8) Treat the herd including pigs for hog cholera and use measures to prevent disease and parasites. (9) Provide a year-round supply of feed. (10) Boar pigs should be castrated when from 2-4 weeks of age or before weaning. (10) Practice selling thru good markets.

HOGS INVENTORY, NUMBERS, PIG CROPS AND DISPOSITION, PRODUCTION AND INCOME, Years Indicated. USDA, BAE Data*

FLORIDA

Year	Number Jan. 1	No. Sows Farrowing	No. Boars Needed **	No. Pigs Saved	No. Head Slaughtered	No. Deaths on Farms	Production In Pounds	Price per 100 Lbs.	Gross Income	Out-Shipments Total	Out-Shipments Stocker-Feeder
1924	640,000	92,000	1,700	441,000	504,000	79,000	57,735,000	7.10	$ 5,450,000		
1925	498,000	91,000	1,534	460,000	424,000	76,000	57,670,000	9.10	6,075,000		
1926	458,000	99,000	1,800	534,000	428,000	79,000	64,055,000	9.90	6,658,000	BAE USDA	L.Stock Sanitary Board
1927	485,000	110,000	2,067	576,000	439,000	79,000	67,485,000	8.70	5,786,000		
1928	543,000	109,000	1,967	566,000	493,000	85,000	67,500,000	7.10	5,234,000		
1929	531,000	101,000	1,867	514,000	451,000	75,000	64,090,000	7.70	5,303,000		
1930	519,000	103,000	1,934	527,000	458,000	74,000	64,245,000	7.50	5,257,000		
1931	514,000	108,000	1,934	555,000	460,000	75,000	66,645,000	5.50	3,879,000		
1932	534,000	111,000	1,967	571,000	484,000	76,000	69,095,000	3.35	2,483,000		
1933	545,000	111,000	2,133	546,000	504,000	72,000	69,189,000	3.20	2,475,000		
1934	515,000	100,000	1,867	467,000	463,000	72,000	60,695,000	3.85	2,748,000		
1935	447,000	106,000	2,200	526,000	426,000	100,000	62,070,000	6.50	4,197,000		
1936	447,000	126,000	2,434	614,000	472,000	90,000	73,085,000	7.30	5,364,000		
1937	499,000	140,000	2,634	720,000	550,000	150,000	83,030,000	7.50	6,446,000		
1938	519,000	153,000	2,767	815,000	610,000	142,000	98,495,000	6.50	6,320,000		
1939	582,000	158,000	2,934	853,000	655,000	180,000	102,350,000	5.60	5,871,000		
1940	600,000	148,000	2,734	760,000	575,000	155,000	91,425,000	5.10	4,598,000	258,000	
1941	630,000	152,000	2,734	735,000	635,000	150,000	93,245,000	7.30	7,428,000	282,000	
1942	630,000	163,000	3,000	861,000	646,000	145,000	108,945,000	10.40	10,808,000	287,000	
1943	700,000	215,000	3,834	1,116,000	762,000	290,000	125,150,000	12.40	15,657,000	336,000	
1944	770,000	201,000	4,034	895,000	772,000	275,000	118,571,000	11.10	13,876,000	398,000	
1945	716,000	187,000	3,667	941,000	781,000	250,000	116,053,000	13.20	16,896,000	272,000	5,006
1946	630,000	190,000	3,433	941,000	727,000	215,000	119,405,000	15.80	19,312,000		4,911
1947	630,000	189,000	3,500	959,000	695,000	255,000	111,742,000	20.90	24,017,000		1,377
1948	640,000	188,000	3,400	998,000	747,000	225,000	121,751,000	20.30	24,687,000		2,446
1949	660,000	189,000	3,500	991,000	789,000	225,000	116,986,000	17.20	21,355,000		
1950	619,000	-	-	-	-	-	-	-	-		

* USDA, BAE Data combined by the Florida State Marketing Bureau.

** Number of boars are obtained by using one boar for 30 sows or gilts,- Sows farrowing twice per year.

There are 8,000,000 acres of land adaptable to the production of corn, oats, rye, sorghum grain, peanuts, root crops, and grazing crops for hogs, and/or the production of grains for creep, or short feeding and finishing of cattle. There is available garbage, tubers, acorn mast, and by-products of the field and dairies for hogs. The gross income from hogs, 5-year period 1944-48 inclusive, is about 85% of that from cattle, calves and hides. Florida produces hogs.

CATTLE: NUMBER ON FLORIDA FARMS BY CLASSES JANUARY 1 (USDA, BAE)

Years	Total	Kept for Milk			Total Cows & Calves for Milk	OTHER					Total Beef Cattle & Calves
		Cows 2 yrs +	Heifers 1-2 yrs.	Heifer Calves		Cows 2 yrs +	Heifers 1-2 yrs.	Other Calves	Steers 1 yr +	Bulls 1 yr +	
	Thousands										
1920	880	73	19	22	114	405	82	144	118	17	766
1921	840	75	21	20	116	385	80	132	110	17	724
1922	810	78	19	22	119	360	78	131	105	17	691
1923	770	82	21	20	123	340	76	114	100	17	647
1924	740	82	19	16	117	320	74	114	98	17	623
1925	712	86	18	20	124	305	71	94	102	16	588
1926	684	89	19	22	130	293	69	81	96	15	554
1927	640	91	21	25	137	267	64	70	88	14	503
1928	612	92	24	28	144	251	65	60	79	13	468
1929	600	94	27	30	151	241	64	61	71	12	449
1930	590	95	29	31	155	233	68	58	64	12	435
1931	620	95	30	36	161	241	68	54	83	13	459
1932	680	98	34	38	170	247	72	77	99	15	510
1933	737	101	36	40	177	275	76	103	89	17	560
1934	773	106	37	37	180	296	78	110	90	19	593
1935	788	110	35	36	181	306	82	111	87	21	607
1936	788	111	35	38	184	309	83	107	84	21	604
1937	796	112	36	39	187	308	84	110	86	21	609
1938	780	110	34	44	188	303	80	104	84	21	592
1939	820	113	39	45	197	316	91	112	84	20	623
1940	851	113	40	43	196	338	93	119	85	20	655
1941	902	120	42	46	208	353	105	127	88	21	694
1942	947	121	43	48	212	385	110	130	89	21	735
1943	1,042	123	41	50	214	444	124	143	94	23	828
1944	1,136	128	45	55	228	487	135	152	110	24	908
1945	1,159	133	43	56	232	495	135	158	114	25	927
1946	1,205	140	43	60	243	520	130	168	118	26	962
1947	1,265	148	40	65	253	538	146	175	125	28	1,012
1948	1,265	148	42	65	255	570	134	166	112	28	1,010
1949	1,265	148	35	75	258	520	136	173	149	29	1,007
1950	1,392	152	56	85	293	584	132	188	163	32	1,099

FLORIDA SLAUGHTERING PLANTS:

Federally Inspected Packing Plants

Kingan & Company	Bartow
Southern Packing Co.	Tallahassee
Swift & Company	Ocala

State Inspected Plants

City Abattoir	W. Palm Beach
Copeland Sausage Co.	Alachua
Cullison Sausage Co.	Ocala
Farris & Co.	Jacksonville
Fla. Packing Co.	Quincy
Harold R. Gertner Co.	Gainesville
Farmers Meat Pkg. Co.	Marianna
Hermann Sausage Co.	Tampa
Lykes Bros. Meat Plant	Tampa
Jones, Chambliss Co.	Jacksonville
Goldman Packing Co.	Dinsmore
Paul Russell	Tallahassee
Southland Provision Co.	Palatka
Suwannee Cold Storage	Live Oak
National Meat Packers	Tampa

Other Abattoirs-City or not inspected

Central Packing Co.	Center Hill
Fla. State Hospital	Chattahoochee
Riverside Pkg. Co.	Daytona Beach
Daniels & Co.(Meat Pkrs.)	Gainesville
Miami Meat Pkg. Co.	Hialeah
George Wakefield	Homestead
S. E. Harrison	Myakka City
Molineaux Pkg. Co.	Malabar
Turner & Gee	Orlando
Thomas Pkg. Co.	Okeechobee
Fla. Sausage Co.	Pensacola
M. L. McDonald	Daytona Beach
E. G. Bass	Ft. Lauderdale
Odom's Sausage Co.	Lake City
Dirr Sausage Co.	Miami
Mades Pkg. Co.	Miami
H. S. Camp & Sons	Ocala
McKinnon & Mills	Ocala
D. Z. Ard Pkg. Co.	Pensacola
Edwards Meat Pkg. Co.	Sarasota
Perry Cameron Pkg. Co.	Sanford
C. B. Eiland	Sebring
H. A. Lawson	Starke
S. A. Snyder	St. Augustine
J. H. Turner	Arcadia
Andrews & Wade	Bonifay
Crum Packing Co.	Plant City
C. P. Russ	Panama City
E. M. Hawkins	East Palatka
T. J. Faulkner, Sr.	Perry
Clyde Brogdom	Wewahitchka
Smith, Richardson & Conroy	W. Palm Beach
Escambia Sausage Co.	Pensacola
Carson A. Platt	Fellsmere
S. E. Register Meat Co.	Cottondale
Tobias Sausage Co.	Chipley

LIVESTOCK AUCTION MARKETS

Beebe Auction Mkt.,W.Palm Beach.	Mon.
Central Fla.L/S Co-op. Bithlo.	Tues.
Paxton L/S Mkt. Paxton	Wed.
Gainesville L/S Mkt., Gainesville	Mon.
Tindel & Williams L/S Mkt., Graceville	Mon.
Monticello L/S Mkt., Monticello	Mon.
Hillsboro L/S Com. Co., Tampa	Mon.
Jacksonville L/S Mkt.Inc.,Jacksonville-	Tues.
Hamilton Co. L/S Mkt., Jasper	Tues.
State Farmers L/S Mkt., Jay	Tues.
Farmers' Produce Mkt.,Inc.,Gainesville-	Tues.
Madison L/S Mkt., Madison	Tues.
West Florida L/S Mkt., Marianna	Tues.
Cattlemen's L/S Mkt., Lakeland	Tues.
Sumter Co. Farmers' Mkt.,Inc.,Webster	Tues.
Okeechobee L/S Mkt., Okeechobee	Tues.
Kissimmee L/S Mkt., Inc., Kissimmee	Wed.
Suwannee Co. L/S Mkt., Live Oak	Wed.
State Farmers' L/S Mkt., Arcadia	Wed.
Gadsden Co. L/S Auction Mkt., Quincy	Wed.
State Farmers' L/S Mkt.,DeFuniak Spgs.-	Thur.
Columbia Co. L/S Mkt., Lake City	Thur.
E. E. Mills L/S Auction Mkt., Ocala	Thur.
Hardee Co. L/S Auction Mkt., Wauchula	Thur.
Atlanta L/S Comm. Co., Chipley	Fri.
Glades L/S Mkt., Belle Glade	Mon.
Robertson & Champion L/S Auct. Mkt., Orlando	Fri.
Goff L/S Comm.Co. Lakeland	Sat.

Cooperative Sales

Calhoun Co.Swine Shipp.Assn.,Altha	Mon.
Gulf Co-op. L/S Com. Co., Trenton	Tues.
Holmes Co. L/S Mkt., Bonifay	Wed.

Cash Daily Markets

Frank E. Dennis, Inc., c/o Jones-Chambliss Co., Jacksonville
Quincy L/S Mkt.("Stoney" Edwards, Quincy.
Ted May, Jay
H. G. Neel, Greenwood

All meat packing companies and practically all abattoirs furnish cash daily markets.

Number of Registered Beef Herds in Fla.-Year 1948(Breeders Record Assn.)

Aberdeen-Angus	72 herds
Brahman	269 "
Hereford & Polled Hereford	175 "
Shorthorn	22 "
Devon	8 "
Red Polled	3 "
Total Registered Beef Herds	549 herds

Breeders Associations for Cattle include: Angus, Brahman, Hereford, Shorthorn for beef breed; and Guernsey and Jersey breeds. The Florida State Cattlemen's Assn., Kissimmee, Fla., represents cattlemen's interests generally. The Mark and Brand Law enforcing officer, John M. Scott, Seagle Bldg., Gainesville, Fla. Hog Breeder Organizations include Duroc-Jersey, Hampshire;and all Fla. Purebred Swine Breeders Association.

NEW DEVELOPMENTS IN FLORIDA EGG AND POULTRY PRODUCTION.

By F. W. Risher, Marketing Specialist, Dairy and Poultry Products.

Only a few years ago most people looked upon Florida as a white egg market, and most commercial poultrymen kept white Leghorn hens. Then just prior to the World War Number Two, poultrymen began to develop flocks of heavy breed layers mostly of the New Hampshire breed. As a result consumers began to find brown eggs on the market that were of just as good quality as the white eggs from commercial poultry farms. Today there are many more commercial brown eggs on the market than white eggs. Browns account for approximately 65 per cent of egg production in the State. Nassau and nearby counties produce most of the State's white eggs.

POULTRY COOPERATIVES TO GRADE, PACK AND MARKET EGGS

There are four egg cooperatives operating very successfully at the present time; one of them operating in Marion County; one in Bristol, Florida, covering Liberty and Calhoun Counties; one in Orlando, covering the central part of the State; and one located in Hernando County. These associations have all the modern equipment found in commercial egg plants. The one at Bristol has a cooler with an egg holding capacity of 700 cases.

BROILER PRODUCTION INCREASING

Broiler production began in a small way around cities like Jacksonville, Tampa and Miami , where there was a ready market years ago. Recently areas of heavy production away from the cities began to develop in West Florida in Walton County, and in North Florida around Palatka. Today more fryers are produced by commercial plants than by general farmers.

LEADING PRODUCING COUNTIES WITH LARGEST CITY OR PRODUCING POINT 1949

EGGS

County Rank	Leading City or Shipping Point
1. Hillsborough	Tampa
2. Pasco	Dade City
3. Nassau	Callahan
4. Duval	Jacksonville
5. Polk	Lakeland
6. Jackson	Marianna
7. Marion	Ocala
8. Orange	Orlando

COMMERCIAL BROILERS

County Rank	Leading City or Shipping Point
1. Walton	Defuniak Springs
2. Putnam	Palatka
3. Duval	Jacksonville
4. Hillsborough	Tampa
5. Dade	Miami
6. Pasco	Dade City
7. Polk	Lakeland
8. Holmes	Bonifay

TURKEYS

1. Gilchrist	Trenton
2. Levy	Chiefland
3. Suwannee	Live Oak
4. Gadsden	Havana
5. Marion	Ocala
6. Alachua	Gainesville
7. Sumter	Bushnell
8. Lake	Leesburg

DUCKS

1. Duval	Jacksonville
2. Dade	Miami
3. Hillsborough	Tampa
4. Pasco	Dade City
5. Orange	Orlando
6. Volusia	Deland
7. Marion	Ocala
8. Alachua	Gainesville

GEESE

1. Jackson	Marianna
2. Duval	Jacksonville
3. Madison	Madison
4. Pasco	Dade City

GUINEAS

1. Polk	Lakeland
2. Jackson	Marianna
3. Hillsborough	Tampa
4. Gadsden	Quincy
5. Gilchrist	Trenton
6. Marion	Ocala
7. Levy	Williston
8. Alachua	Gainesville

LOCATION OF LARGEST COMMERCIAL POULTRY FLOCKS

WHITES

1. Nassau	Callahan
2. Columbia	Lake City
3. Manatee	Pradenton
4. Alachua	Gainesville

REDS

1. Hillsborough	Tampa
2. Pasco	Dade City
3. Hernando	Brooksville
4. Duval	Jacksonville

TURKEYS

1. Gadsden	Havana
2. Marion	Ocala
3. Sumter	Bushnell
4. Duval	Jacksonville

POULTRY AND EGG MARKET NEWS REPORTS

The Florida State Marketing Bureau issues a daily report in Jacksonville on Florida poultry and eggs which is carried over the Associated Press to most Florida daily newspapers, and a twice weekly mail report, which includes poultry and egg prices for Jacksonville, Tampa, Miami, Orlando, and Tallahassee. The daily report to the press and the twice weekly report carry the North Georgia fryer market as well as the New York and Atlanta egg markets.

Poultry and Eggs Sold in Florida

More and more eggs are sold in the one-dozen carton because it is convenient for the housewife to take home and acts as a good package to keep eggs in when placed in the ice box, or refrigerator.

It is of interest to note that in the 12 months July 1,1949, to June 30, 1950,there were sold 24,015,600 dozen of eggs in cartons with State grade and size labels on them. Of this number 8,102,900 dozen were produced in Florida and 15,912,700 dozen were shipped in from some other State. In the same 12 months the year before 16,000,000 dozen eggs were sold at retail in one dozen cartons.

In the 12 months ending June 30, 1950 there were 564,254 cases (containing 30 dozen eggs) sold and divided as follows: 273,926 cases Florida eggs and 280,330 cases of shipped-in eggs.

Poultry sold according to grade in period July 1, 1949 to June 30, 1950 was approximately 49,000,000 pounds, approximatly 50 per cent Florida.

Poultry and Eggs Produced in Florida in 1949

From the best sources available the production of poultry meat (most of it by commercial broiler plants) was estimated at 39,000,000 pounds and in the same 12 months Florida poultry flocks produced 249,000,000 eggs (over 20,000,000 dozen). The value of poultry and eggs produced in this 12-month period ending June 30 was a little under $26,000,000.

Hatcheries in Florida

The commercial broiler and commercial egg production has been responsible for a great expansion in hatcheries to supply baby chix. The hatcheries produce more than 20,000,000 baby chix with a value of more than $3,000,000. Many of these chix are shipped to foreign countries, mostly by air express.

Turkey Production 1949

There are 131,000 heads which produced close to $1,000,000 dollars worth of turkey meat. Many flocks with 1,000 to 5,000 head are now to be found in Florida. They are grown very much like broilers and fryers are in commercial lots.

The Poultryman's Investment

The Extension Service of the University of Florida and the Marketing Bureau, and other Educational Agencies in the State estimate poultrymen have $50,000,000 invested in land, houses, equipment and stocks of birds. No one knows how many million dollars are invested by the dealers in houses, processing plants and refrigerator equipment.

Trucks Imports- Poultry (lbs) and Eggs (cases)

In the nine months, October 1949 to June 1950, there were hauled into Florida by trucks 779,004 cases of eggs and 17,593,764 pounds of poultry. The reason reports are not available for the other months is because there is no road guard service maintained then.

- - - - - - - - - - - - - - - - - -

Mr. F. W. Risher is in charge of the poultry marketing work of the Florida State Marketing Bureau in Jacksonville, located at 505 West Adams Street.

Our egg and poultry market news service is quite willing to supply any interested party with a wire collect whenever there is a change in the Jacksonville prices which we quote. At this time there are more than 70 poultry dealers, truckers, and producers who get this special service at no cost other than the wire cost. Our mailing list includes 1,560 dealers, truckers and producers who receive our twice weekly report covering Jacksonville, Tampa, Miami, Orlando and Tallahassee eggs and poultry. New York and Atlanta egg markets as well as the North Georgia fryer market are also quoted.

PRODUCTION AND VALUE OF AVOCADOS AND LIMES 1929-1950

	AVOCADOS					LIMES (Persian Type)			Avocados & Persian Limes Combined Gross FOB Value
	Crop Volume Tons	Bu. 50 Lbs.	Value Ton	Value Bu.	Gross FOB Value	Crop Volume 1-3/5 bu. Boxes	Value Box	Gross FOB Value	
1929	420	16,800	$142	$3.55	$ 59,640	$ 8,000	$4.50	$ 36,000	$ 95,640
1930	620	24,800	192	4.80	119,040	8,000	4.00	32,000	151,040
1931	820	32,800	145	3.63	118,900	9,000	3.50	31,500	150,400
1932	1400	56,000	88	2.20	123,200	10,000	3.00	30,000	153,200
1933	2200	88,000	98	2.45	215,600	12,000	2.50	30,000	245,600
1934	2000	80,000	75	1.88	150,000	15,000	3.00	45,000	195,000
1935	1000(a)	40,000	95	2.38	95,000	12,000	3.75	45,000	140,000
1936	600(b)	24,000	120	3.00	72,000	45,000(f)	3.25	146,250	218,250
1937	2100	84,000	95	2.38	199,500	70,000	3.25	227,500	427,000
1938	2200	88,000	64	1.60	140,800	95,000	2.60	247,000	387,800
1939	2500	100,000	68	1.70	170,000	95,000	2.80	266,000	436,000
1940	880(c)	35,200	98	2.45	86,240	80,000	2.85	228,000	314,240
1941	1250	50,000	100	2.50	125,000	150,000	2.10	315,000	440,000
1942	2100	84,000	136	3.40	285,600	175,000	2.36	413,000	698,600
1943	4600(d)	184,000	120	3.00	552,000	190,000	4.79(g)	910,100	1,462,100
1944	5800	232,000	140	3.50	812,000	250,000	4.86(g)	1,215,000	2,027,000
1945	3200	128,000	144	3.60	460,800	200,000	3.58	716,000	1,176,800
1946	1600(e)	64,000	336	8.40	537,600	170,000	3.95	671,500	1,209,100
1947	2300	92,000	200	5.00	460,000	170,000	3.34	567,800	1,027,800
1948	3100	124,000	180	4.50	558,000	200,000	3.14	628,000	1,186,000
1949	3900	156,000	150	3.75	585,000	260,000	3.50	910,000	1,460,000
1950	(No Estimate)					300,000	(No Estimate)		

NOTES: (a) Lower yield account freeze December 9, 1934.
(b) Lower yield account hurricane in November 1935.
(c) Lower yield account freeze of January 26-30. Extremely severe.
(d) Higher yield account good crop and care with full harvesting, affected by higher prices.
(e) Lower yield account hurricane November 15-16, 1945.
(f) Heavy increase in yield account new acreage in Polk County coming into production.
(g) High prices due to shortage and high prices of California lemons.

PERSIAN LIMES CERTIFIED FOR SHIPMENT - BY COUNTIES, BY MONTHS
AUGUST 1, 1949-JULY 31, 1950
(In Terms of 1-3/5 Bushel Boxes)

County	Dade	Highlands	Hills-borough	Pinellas	Polk	Volusia	Total
August, 1949	35,215	3,526	2,630	856	2,536		44,763
September, 1949	15,804	410					16,214
October, 1949	11,683	177	351	66			12,277
November, 1949	6,467	102					6,569
December, 1949	6,629	182			94		6,905
January, 1950	6,590	626				12	7,228
February, 1950	4,217	360					4,577
March, 1950	4,934	517					5,451
April, 1950	3,320	120					3,440
May, 1950	22,826	1,202		176	365		24,569
June, 1950	51,297	8,919		973	3,537		64,726
July, 1950	36,270	10,601		1,100	8,234		56,205
STATEWIDE TOTAL	205,252	26,742	2,981	3,171	14,766	12	252,924
% of State Totals	81.16%	10.57%	1.18%	1.25%	5.84%	0.00%	100%
July, 1949	42,510	7,970	3,480	370	7,387	0	61,717
State Total 1948-49							202,265
State Total 1947-48							161,687

INSPECTIONS OF FLORIDA CITRUS FOR SHIPMENT BY RAIL AND TRUCK BY COUNTIES

SEASON AUGUST 1, 1949 - JULY 31, 1950

B O X E S (1-3/5 bushels)

County	Grapefruit	Oranges	Tangerines	Total 1949-50	Total 1948-49	Total 1947-48
Alachua	3,976	62,993	2,787	69,756	59,503	66,479
Brevard	499,164	798,552	12,743	1,310,459	1,079,605	1,307,940
Citrus	8,026	28,141	3,046	39,213	39,150	30,288
Dade	26,155	42,754	-	68,909	113,520	119,659
DeSoto	57,733	336,866	31,073	425,672	675,856	780,362
Duval	100,171	385,683	96,694	582,548	657,025	613,840
Hardee	-	14,319	3,245	17,564	70,765	39,091
Hernando	34,740	121,473	84,041	240,254	316,485	179,809
Highlands	338,599	947,216	46,455	1,332,270	1,922,936	1,092,604
Hillsborough	261,183	659,204	100,527	1,020,914	1,626,964	1,345,913
Indian River	647,642	337,795	6,392	991,829	1,479,923	1,270,526
Lake	816,493	2,547,941	421,963	3,786,397	3,861,089	3,116,655
Lee	48,537	44,332	234	93,103	58,506	81,167
Manatee	30,310	18,510	-	48,820	165,017	198,681
Marion	172,050	963,318	30,171	1,165,539	1,541,805	1,446,657
Orange	1,249,380	5,263,510	753,014	7,265,904	8,153,109	7,071,162
Osceola	38,938	136,990	24,881	200,809	368,104	299,630
Palm Beach	3	224	-	227	125,121	111,300
Pasco	84,400	215,090	20,443	319,933	395,492	383,642
Pinellas	1,192,895	185,414	28,936	1,407,245	1,617,236	1,342,292
Polk	2,898,404	4,971,689	715,257	8,585,350	14,763,663	10,862,013
Putnam	18,128	157,645	43,217	218,990	237,025	198,508
St. Johns	-	26,756	-	26,756	16,357	29,291
St. Lucie	189,339	271,307	8,488	469,134	1,719,438	1,796,192
Sarasota	83,534	22,056	164	105,754	1,289	13,022
Seminole	309,949	1,169,486	217,726	1,697,161	1,788,017	1,641,566
Sumter	-	490	-	490	2,442	-
Volusia	104,657	703,329	229,538	1,037,524	839,469	689,425
Others	1,117	16,359	124	17,600	-	1,162
TOTAL ABOVE	9,215,523	20,449,442	2,881,159	32,546,124	43,707,235	36,219,521
TOTAL CROP	24,200,000	58,500,000	5,000,000	87,700,000	92,900,000	91,100,000

NOTE: Some commodities are produced in one county and inspected in another county. These inspections do not include fruit for processing and some other classes of fruit.

CITRUS TRUCKED THROUGH ROAD GUARD STATIONS 1949-50 SEASON

Open October 16, 1949 to June 17, 1950

(Tabulated from Records of Citrus & Vegetable Inspection Division, Winter Haven, Fla)

STATION	HIGHWAY	ORANGES	GRAPEFRUIT	TANGERINES	TOTAL CITRUS
GROUP 1					
Wilcox	U.S. 19	2,202,719	665,928	219,477	3,088,124
Luraville	Fla. 51	677	104	37	818
Branford	Fla. 20	46,120	12,569	3,667	62,356
Ellaville	U.S. 90	222,117	60,610	23,275	306,002
Suwannee Springs	U.S. 129	19,100	4,166	1,806	25,072
White Springs	U.S. 41	1,984,112	641,322	271,648	2,897,082
Lake City	Fla. 47	22,856	6,853	2,548	32,257
GROUP 2					
Hilliard	U.S. 1	2,235,494	803,667	313,715	3,352,876
Yulee	U.S. 17	3,241,857	1,021,535	516,830	4,780,222
TOTAL ALL STATIONS		9,975,052	3,216,754	1,353,003	14,544,809

Stations in Group 1 are at bridges over Suwannee River; those in Group 2 are at bridges over St. Marys River.

TOTAL ALL STATIONS

Date	Oranges	Grapefruit	Tangerines	Total
October 16-31	505,867	203,266	186	709,319
November.	1,615,640	349,129	124,745	2,089,514
December.	1,813,892	242,167	599,184	2,655,243
January	1,178,349	335,321	323,363	1,837,033
February.	1,005,000	389,517	214,328	1,608,845
March	1,267,941	664,394	87,736	2,020,071
April	1,159,733	538,492	3,366	1,701,591
May	1,045,131	398,809	95	1,444,035
June 1-17	383,499	95,659	-	479,158
TOTAL	9,975,052	3,216,754	1,353,003	14,544,809

The above Road Guard Stations also report on vegetables and miscellaneous fruits but the volume is not shown by stations. Such vegetable and miscellaneous fruit passings for October 16, 1949 to June 17, 1950, inclusive, were 45,943 carloads. Citrus box figures may be divided by 500 to get carload equivalent.

FEDERAL-STATE INSPECTION SERVICE

July 1, 1949 - June 30, 1950

FLORIDA Commodities	Type of Container	Rail Cars Inspected	No. of Units or Containers	Average Containers (or Units per Car) 1949-50	48-49	47-48	46-47	45-46
Oranges	Std 1-3/5 Bu	14,020	6,794,217	485	497	499	503	502
Grapefruit	Std Box Equiv.	7,771	3,870,514	498	499	515	515	514
Tangerines	" " "	2,231	985,647	442	438	437	442	449
Mixed Citrus	" " "	4,303	2,336,887	487	497	494	505	497
Total Citrus		28,825	13,987,265	485	492	498	503	500
Beans	Bu hprs.	45	26,564	590	624	636	641	638
Cabbage	50# sks.	392	194,350	496	502	501	503	501
"	W.B.Crts.	1,912	896,608	469	480	481	--	-
Celery	Std.Fla.Crts.	8,552	3,496,359	409	427	426	425	445
Corn	Std.Crts.	1,488	870,464	585	554	510	442	-
"	50# sks.	34	24,011	706	546	-	-	696
Cucumbers	Bu.	25	13,673	547	379	373	459	437
Escarole	Bu.hprs.	56	35,574	635	640	640	612	642
Peppers	Bu.	214	140,444	656	597	526	672	652
Potatoes	Coml.50# sks.	2,723	1,790,678	658	679	641	651	619
"	Coml.Bu.	14	8,248	589	658	-	563	-
"	Coml.100# sks.	1,880	564,725	300	301	297	307	300
"	Gov. 50# sks.	46	28,880	628	622	-	-	-
"	Gov.100# sks.	42	15,213	362	326	360	355	300
Tomatoes	30# lugs	2,402	1,600,253	666	673	681	693	689
"	Bu.	456	178,345	391	416	-	-	-
Chicory-Endive	Bu.	8	5,093	636	-	-	-	-
Mxd or Mscl.	Various	238	106,135	446	499	407	602	-
Sweet Potatoes	Bu.	6	3,480	580	-	539	527	552
Total Vegetables		20,533	9,999,097					
Strawberries	36 Pt.Crates	10	4,498	450	-	-	-	-
Watermelons	Melons	8,842	7,481,200*	846	978	985	938	1008
Limes	1-3/5bu Box	1	392	392	-	399	-	364
Total Miscl.Fruits		8,853	3,745,490					
Total Rail All Fruits and Vegetables		58,211	27,731,852					

* Divide Watermelons by 2 to get units comparable to packages or units.

INSPECTION FOR TRUCK SHIPMENTS IN CARLOT EQUIVALENTS

Oranges,Com'l	Boxes	15,309	7,419,204
Grapefruit	Boxes	5,471	2,724,765
Tangerines	Boxes	1,711	756,000
Mixed Citrus	Boxes	14,573	7,090,520
Total Citrus	Boxes	37,064	17,990,489
Citrus for Processing	Bxs	97,791	48,895,896
All Citrus for Trucks		134,855	66,886,385
Watermelons	Melons	184	155,459*
Strawberries	Crts	372	167,344
Limes	Crts	9	3,509
Total Miscl.Fruits		565	248,583
Celery	Crts	4,636	1,895,196
Corn	Crts	1,805	1,056,196
Potatoes	Pkgs	3,402	1,634,958
Tomatoes	Pkgs	5,371	2,139,921
Other Vegs.	Pkgs	1,427	758,089
Total Vegetables		16,641	7,484,360
		Cars	Tons
Peanuts,Farmers Stock		2,189	26,269
Peanuts, Shelled		951	23,773
Lupine		55	1,385

GRAND TOTAL CARS 155,256

Note: Except for citrus, celery, cabbage, corn, potatoes,tomatoes and watermelons, the inspection sample was too limited to show the average rail carlot loadings.

The above inspection figures were supplied by Mr. Hugh S. Flynt, Ass't Director, Vegetable Branch, Citrus & Inspection Division, Florida Dept. of Agriculture, 305 Post Office Bldg., Orlando, Florida.

The arrangement of these figures was by F.H. Scruggs, who takes the blame for all errors, if any.



This outline map of Florida has been requested by numerous firms and individuals in Florida and in other states. The map is a reproduction of a larger map reduced in size to meet the requirements of this Annual Report. The county designation is therefore in very small print. The cities and towns were superimposed on this map and are in much larger print.

Most of the larger cities of the state are shown. The locations of our field market news stations are shown as well as most of the leading livestock markets. There are a few cities to represent general agricultural sections.

Tallahassee is the Capitol of the state, and the Florida State Department of Agriculture is located there. The Florida State Marketing Bureau is in Jacksonville. The Agricultural Extension Service and College of Agriculture are located at Gainesville. The U. S. Bureau of Agricultural Economics (Florida agricultural statistics) is in Orlando. Winter Haven, Fla., in Polk County, is the headquarters of the Florida Fruit and Vegetable Inspection Service, with a branch office in Orlando. The office of the State Agricultural Marketing Board (State Markets) is located in Jacksonville.

The Federal-State Shipping Point Market News offices are located as follows: (1) Lakeland for citrus; (2) Plant City for strawberries and vegetables; (3) Hastings for potatoes and cabbage; (4) Sanford-Oviedo for celery, corn and vegetables; (5) Leesburg and Gainesville for watermelons and corn; (6) Belle Glade for beans, celery, corn and vegetables; (7) Pompano for beans, peppers and vegetables. Florida City, Ft. Pierce, Ft. Myers, Palmetto and Ruskin, Zellwood and Weirsdale vegetables are reported in field Market News reports.

FLORIDA STATE MARKETING BUREAU

ANNUAL FRUIT AND VEGETABLE REPORT

PRODUCTION, TRANSPORTATION AND MARKETING ANALYSIS

1950-51 SEASON

(Also Poultry, Egg, Livestock, Tobacco and Field Crop Statistics)

See outline map on back cover

By Frank H. Scruggs, Market News Specialist

Neill Rhodes, Commissioner
Florida State Marketing Bureau
Division of
Florida State Department of Agriculture
Nathan Mayo, Commissioner

This Annual Report is available free of charge to parties interested

Released October 29, 1951

Florida State Marketing Bureau
505 West Adams Street
P. O. Box 779
Jacksonville 1, Florida

INDEX

CITRUS FRUITS ONLY (ORANGES, GRAPEFRUIT AND TANGERINES)

	Page Number
Records and Estimates - Volume, Value and Disposition	-7
Florida Citrus F.O.B. Averages 1909 to 1951	24
Shipments, Valuations and Other Data for 10 Years	25-29
Auction Sales at 10 Markets 1942-43 to 1950-51	30
Tree to Auction Costs or Vice Versa for 3 Years	31
Analysis of Citrus Prices and Costs	32-33
Inspections by Counties For Rail And Truck Shipments	34
Truck Passings Through Road Guard Stations 1950-51 Season	34
Rail Distribution by State 1949-50 And 1950-51 Seasons	36
Truck Distribution by States 1949-50 And 1950-51 Seasons	37
Prices Paid by Canners And Volume Processed 1941-42 to 1950-51	38
Annual Packs by Years And States, Frozen and Unfrozen	39-40
Freight Rates to Auction Markets	40
Acreage And Production in Florida And Other States 1924-25 to 1949-50	42
Grove Value--Acreage, Yield Per Acre And Tree 1943-44 to 1950-51	43
Cars to Auction And Average Price Per Box Interior And Indian River	44
Florida Citrus F.O.B. Prices by Weeks 1950-51 Season	45

VEGETABLE AND MISCELLANEOUS FRUITS ONLY

Shipments--1950-51 Season--Truck Passings by Weeks	22-23
Avocado And Lime Production And F.O.B. Value 1930 to 1951	35
Persian Lime Inspections For Shipment by Month 1950-51	35
Acreage, Yield, Production And Value 1950-51 Season	46-47
Acreage, Yield, Production And Value 1932-33 to 1950-51 Seasons	48-52
Acreage--Fall, Winter And Spring By Counties 1950-51 Season	53-57
Acreage--Principal Truck Crops for 26 Seasons	58-59
F.O.B. Packed Value for 16 Seasons	60
F.O.B. Sales Prices At Shipping Point 1950-51	88-91
Shipments--Truck Passings by Months And Road Guard Stations	109
Shipments--Truck Destinations by States and Markets	110-115

ALL FRUITS AND VEGETABLES

Summary of The 1950-51 Season	1-3
Production And Value for 15 Seasons	5
Disposition of All Fruits And Vegetables for 1950-51 Season	8-9
Shipments--1950-51 Season--Freight, Express, Boat And Truck	10-13
Shipments--10 Seasons--Freight, Express, Boat And Truck	14-17
Shipments--1950-51 Season--Rail Freight by Counties	18-21
Federal-State Inspections--Rail And Truck	41
Acreage by Counties for 4 Seasons	61-73

INDEX (Continued)

GENERAL AGRICULTURAL STATISTICS

Page Number
Florida Agricultural Volume And Value (Resources) 4
Poultry And Egg Market for Jacksonville 74
Poultry And Egg Market for Tampa 75
Poultry And Egg Market for Tallahassee 75
Poultry And Egg Market for Miami 76
Florida Floriculture--Facts And Figures 77-78
Florida Farm Statistics--General Summary 79-80
Average Prices Received September 15, 1951 81
Volume And Value of General Farm Crops 1920 to 1950 82-84
Turkey Crop--Facts And Figures 85
Florida Tobacco--Production 86
Florida Tobacco--Auction Sales 87
Florida Forests--Facts And Figures 92-93

LIVESTOCK

Florida Livestock Prices From 1930 to 1951 94-95
Leading Livestock Counties 95
Preventable Livestock Losses 96-97
Slaughter for Livestock in 1950 by Months 98
Rail And Truck Shipments of Florida Cattle And Hogs in 1950 by Months 99
Citrus By-Product Feeds by Value 1940 to 1951 99
Florida's Position As A Cattle State--12th in Beef Cattle, 23rd in All Cattle 100
Florida's Position As A Hog, Sheep, Horse And Mule State 101
Number of Cattle on Farms, Value Per Head 1929 to 1951 102-103
Number of Hogs on Farms, Value Per Head 1929 to 1951 104-105
Cattle: Number on Florida Farms by Classes 1920 to 1950 106
Florida Slaughtering Plants And Auction Markets--Names And Addresses 107
Cattle And Calves on Hand by States for 1940 and 1950--Percent Increase 108

- -

Page
Index for Fruits And Vegetables A
Index for General Agricultural Statistics And Livestock B
Foreword, or Lastword C
Acknowledgment D
Introductory E
I Like Florida (An Article) F

THE LASTWORD

This report is not really important enough for a Foreword, so I am going to call it the Lastword. It's the last page written. I am afraid that you readers will suspect that I wrote the Introductory as well as the Lastword.

The Introductory, by Commissioner Rhodes, says such nice things about me that it creates the feeling that I am about to be retired. This is the 23rd Annual Report.

Each year these reports get a little thicker as we add more information of the same kind and new data. This leads me to think that I might be giving some of the readers more stuff than they want or can digest at one sitting, and this leads up to a story.

It seems that a young preacher, full of energy and long sermons, had gotten his congregation to redecorate the church inside and out from top to bottom, and to do justice to the occasion he prepared a special sermon for the next Sunday. Sunday came, as it always does, 11 A.M. came, the preacher came, but the congregation did not come, except for one old man who took a seat at the rear. The young preacher waited and waited but no others came. Finally he walked back to the old man and asked what he should do. "If I had spent all week preparing a sermon I would go on and deliver it," was the reply. So the young man went back to the pulpit and preache and preached for two hours. After he had finished he walked back to the old man with the question, "Did you enjoy my sermon?" to which he got this answer, "Well, young man, if I was a farmer and had a cow which could eat only one bale of hay I wouldn't give her a wagonload."

One of the regular readers of these annual reports asked that I tell a joke or two to take some of the monotony out of these many pages of statistics which follow. These jokes were invited, which reminds me of the Commissioner of Agricultur in another state who was invited to a farm meeting of men and women. He acknowledged his introduction by saying that he felt like the poor country boy who went into town on circus day, hoping that he could in some way get into the big tent. He had no money, so around the tent he walked to see if there was some way he could slip under the tent without being seen. Seeing a jackass tied to a stake with his rear to the tent the boy said to himself, "I'll get down on my knees behind this jackass where I can't be seen, raise the tent, and try to slip under." This he did, but at the same time the jackass in a spirit of full cooperation let go with both heels and the boy landed fifty feet inside the tent in the middle of the ring, in the middle of an act. The circus people, very aggravated, grabbed and shook the boy, saying, "How come you butt right into our act?" The poor country boy replied, "I did not butt into your act -- I was assed in." P.S. They ushered him to a seat but he couldn't sit down.

Here's one for the youngest children. Why did the moron take a piece of toast and a knife to the Florida-Georgia football game? Well, he heard there would be a lot of traffic jam there.

Now that you are in a serious frame of mind I would like to point out that we have some new types of information in the report.

We have for the first time Florida f.o.b. shipping point prices showing the prices of several of the leading Florida vegetables. See pages 88-90.

We have for the first time some very good comments and statistics on Florida cut flowers sold in New York City. The cut flower industry in Florida is now of major importance. See pages 77-78.

We have a page on turkey production with particular emphasis on the Beltsville turkeys which have become so popular in the last three years. See page 85.

For the first time we have an article of Florida forest resources together with some very good questions and answers. See pages 92-93.

We have the truck distribution by states and markets for vegetables and miscellaneous fruits. These tabulations of our daily reports were made by the U.S. Department of Agriculture in Washington and were assembled by the State Marketing Bureau, and are found on pages 109-115.

From here on you will need your bi-focals.

ACKNOWLEDGMENT

We wish to acknowledge the splendid cooperation we received from both official and private sources during the preparation of this rather comprehensive statistical report.

The rail freight, boat and express carlot shipment figures were secured from the Fruit and Vegetable Branch of the Production and Marketing Administration, U.S. Department of Agriculture in Washington, D.C.

Exhaustive vegetable acreage, yield, production and value data and other assistance was supplied by Mr. J. C. Townsend, Jr., Mr. J. B. Owens, Mr. Paul Shuler, Mr. James A. Langford, Agricultural Statisticians, and Mr. G. N. Rose, Truck Crop Statistician, U.S. Bureau of Agricultural Economics, Federal Building, Orlando, Florida.

Mr. A. L. Scarborough, Statistician of the Citrus and Vegetable Division, Florida Department of Agriculture, Winter Haven, Florida, supplied us with important record data and other information. Mr. Hugh S. Flynt, Assistant Director of this division, supplied a detailed summary of inspections for the season. The daily reports from Road Guard Stations, operated by the Citrus and Vegetable Division, showing passings of fruits and vegetables, were very helpful to shippers and growers throughout the season and for record purposes in this report.

Mr. H. F. Willson, Federal-State Citrus Market News Service, also supplied useful data for use in this report. Mr. Willson is located in Lakeland, Florida.

Mr. William B. Conner, of the Florida Citrus Mutual, Lakeland, wholeheartedly complied with our requests for much specific citrus information. Much of this information would be difficult to obtain from other sources.

Several official and private agencies and individuals not already mentioned supplied information directly or indirectly to us, for which we extend our thanks.

The preparation of this report is tedious and requires long and hard work, and appreciation by the writer is extended to our Bureau staff for their efforts and accomplishments. Commissioner L. Neill Rhodes contributed several important pages in this report, all of which was new to this report. Mr. L. H. Lewis, Specialist, Livestock and Field Crops, and Mr. Gifford N. Rhodes, Specialist, Livestock Market News, and Mr. F. W. Risher, Specialist, Dairy and Poultry Products, of this Bureau, supplied certain livestock and poultry information.

Mrs. Dena Snodgrass, Research Statistician, State Chamber of Commerce, supplied certain miscellaneous statistics on Specialty Crops, and the mining, lumber and seafood industries. Her office is in the Hildebrandt Building, Jacksonville, Florida.

A few other persons gave us items of information which are not obtainable from official sources.

INTRODUCTORY

The regular Annual Fruit and Vegetable Report of the Florida State Marketing Bureau, covering the State's 1950-51 shipping season, provides an album of records of familiar products and prices. Statistically speaking, the report parades the star performers - citrus fruit, vegetables and others - bearing placards of individual volume and value. The statistical spotlight has also been turned upon relatively minor crops, and other lines of Florida agriculture - livestock, poultry and miscellaneous summations.

According to U.S. Department of Agriculture summary of fruit and vegetable shipments by commodities and states during 1950, Florida shipped better than 12% of the rail and boat total for the United States. Florida over-ranked all states in carlot shipments of grapefruit, tangerines, mixed citrus, watermelons, green beans, corn, cucumbers, eggplant, escarole and peppers.

This report presents factual data, collected from the most authoritative sources, verified by conference comparison with the highest official tabulations. It is not glamorous, spectacular or exaggerated. It follows Bureau policy that: The truth is good enough, and fair to one and all who use our service.

Just as this annual report basically summarizes daily volume to present the seasonal total, it adds another to the many annual fruit and vegetable reports preceding it. Over the years these reports necessarily have increased in size, and we hope have as measurably improved in usefulness.

The tedious preparation of the 1950-51 report is credited, and justly so, to our Market News Specialist, Mr. F. H. Scruggs. The laborer is worthy of his hire. I believe you will agree with me that Mr. Scruggs deserves our saying, "Well done,thy good and faithful servant." So gentlemen producers and shippers, and members of the "agricultural fraternity", may I present to you the Annual Fruit and Vegetable Report of the Florida State Marketing Bureau for the 1950-51 Season by our Market News Specialist, Mr. F. H. Scruggs:

---Neill Rhodes, Commissioner
FLORIDA STATE MARKETING BUREAU

I LIKE FLORIDA

(By Neill Rhodes, Commissioner)

I like Florida because it has a pleasing mixture of climate enjoyed by few other states and surpassed in none of them. I like Florida because there is a little bite in the air in the winter months, yet the warmest summer months are tempered by thunder showers and cool breezes. There are enough warm days in the winter, and enough cool nights in the summer to break any monotony of unchanging weather. I like Florida because of its fine native citizenship, along with resident natives of other states that couldn't help being born elsewhere, but rectified the matter by choosing Florida when they reached maturity. Here in Florida will be found less snobbishness in every-day social life, and more sympathy and help in trouble and distress than in any of the states I have visited. I like Florida because it has a delightful combination of not too few large cities and not too many mid-point cities and smaller towns, for in the very large cities it sometimes seems no one cares to know quite enough about our business, and in the very small towns it sometimes seems everybody knows more about our business than they should. I like the congeniality existing between the urban and rural people; there is little if any holier-than-thou or richer-than-he attitude in Florida. In about all of the leading agricultural sections you can hardly tell where the city ends or the country begins by judging from the way the residents of each mix and mingle.

I like "roughing it" and Florida hunting and fishing, since one or the other is available the year around, fulfills every yearning I may have for the wilds. I like variety in nature's enchantments. Florida has it. I like the wide level expanse of land, and Florida has it. I like the sprawling hills, big bumpy ones, that lazily emerge from sea-level but never grow up to mountain stature, and Florida has them. I like the ridges, the cypress ponds and swamps, and the night wild life that explores them - all the better with a good pack of coon hounds verifying a hot trail stitching ridge to swamp, and Florida has them. I like the nightly soughing of the Florida pines as I apply amateur astronomy to the star-lit heavens. I like a lot of green on trees and shrubbery throughout the year, but the outline mottled a little by massive tree tops left destitute of foliage by changing seasons, and nature has so patterned Florida forests to my idea of perfection.

I like to hear the whistle of the bob-white, the chatter of the squirrel, the hoot of the owl, the night call of the whippoorwill, the gobble of the wild turkey, the changing songs of the mocking-bird, the bellow of the alligator, the quack of the wild duck, the bark of the fox, the chant of the frog, - and all of these and many more I have heard around hunting camps in Florida.

I like Florida because of its comprehensive, continually improving educational system; and because of its fine, well attended churches of so many religious faiths. I like the fraternal spirit and general atmosphere of tolerant brotherhood prevalent in Florida. Here luxuriant natural splendor strikes chords within that attune the human mechanism to close communion with the Almighty. There is freedom in Florida - freedom of press, freedom of initiative and action, freedom of industry, freedom of vote, freedom of assembly, freedom of space, freedom of thought, freedom of speech, freedom of worship, freedom from intolerance, and freedom from fear. I like Florida because this state has received such an abundance of natural endowments and has protected them, has so many of the most enviable customs, characteristics and habits of peoples from other states and lands, and so few of the objectionable ways of life.

I like the azure sky overhanging Florida, the ocean fronts with their slanting beaches fringed by palm-spiked sand dunes. I like Florida lakes, proud jewels upon our land fingering into the sea, blue-mirrored reflections of the azure yonder, their changing splendor made more enthralling by the prismatic tints of sunrise and the red glow of lingering sunset. I also like to hear Old Man Weather lose his temper once in a while, slap sheets of lightening out of threatening clouds, snort around a bit in thunderous tones, roll a few angry waves out on the shore, and dash a few rainstorms here and there before he cools off, and often enough he behaves that way in Florida.

I like the varied Florida agriculture, where grain and hay, cotton, tobacco, and sugar cane are common in many sections; where citrus and non-citrus, berries, grapes, pecans, - in short, almost any tropical or semi-tropical products from corn to coconuts are produced within the state's boundaries. Florida's soils grow these many products, and one might think the 1200 miles of loopy coast line had permanently encircled field and truck crops from other states as they sought warmer retreats upon the Florida mainland. And one might imagine that upon the inbound winds and tides from the tropics were borne the many fruits and vegetables common to more southerly countries and islands, that were buffed back from colder soils by the ridges and hills of Central and North Florida. Florida provides one of the few final common merging grounds for products native considerably to the north and far to the south of us.

I LIKE FLORIDA!

FLORIDA DEPARTMENT OF AGRICULTURE

STATE MARKETING BUREAU

1950-51

ANNUAL FRUIT AND VEGETABLE REPORT

By Frank H. Scruggs, Market News Specialist

SUMMARY

Almost everybody likes money, and if they are not getting it they like to know who is, and if there is any possibility of their getting some of it, directly or indirectly. That is why the people like to hear about a successful tourist season or a successful agricultural year.

1950-51 Season Not Bad

The 1950-51 season was very good and the fruit and vegetable industry fared very well indeed; livestock numbers and values per head were greater than ever; dairy and poultry products held their own very nicely; while general field crops held their own in volume, with prices considerably higher. Flowers, bulbs and nursery products maintained their consistent growth, which has been marked in recent years. Many more pecans brought more money per pound. Honey was just as sweet as ever.

Cold Statistics

We are not going into the tourist statistics as this is an agricultural summary, but the tourist stay was reported longer with more money spent per person pe day.

The fruit and vegetable volume of 331,989 carloads produced, of which 211,276 carloads was citrus, was the greatest ever although we have had good volume for eight years. The volume for the 1950-51 season was just double what it was prior to 1937-38 season. The gross f.o.b. Florida value of $385,116,000 was $21,000,000 more than for 1945-46 season, which was a banner year. The gross value of $1160 per carload of all fruits and vegetables has been exceeded three times, including the 1944-45 and the 1945-46 seasons, when the consumers of nations with plenty of money in their pockets bid higher for anything they wanted. The 1949-50 value of $1254 per carload produced and used was excellent, also due principally to the higher prices paid by the canners and concentrators for fresh citrus. This was a special situation which may or may not recur.

Record 1950-51 Citrus Crop

The volume of 109,100,000 boxes used was 12,200,000 above that of the highest previous season in 1948-49. The forecast for the 1951-52 season is estimated at more than 112,000,000 boxes. We were right proud of 55,000,000 boxes just ten years ago and 30,000,000 boxes just twenty years ago. How time and volume do move! The citrus business is big business and it is run to a large extent by big business men. An amateur getting into this business can get hurt just like he can get hurt in any big and highly competitive business.

Record Vegetable and Miscellaneous Fruit Crop

The vegetable industry is right big business also when it is realized that 120,813 carloads were produced and sold during the past season. The volume exceeded the 1949-50 volume by 8,981 carloads. We thought we were doing well with 60,486 carloads ten years ago. This industry does not get a lot of publicity but it moves ahead just the same. The citrus and vegetable growers seem to have a different philosophy of business life. The citrus grower's money prospects are largely shaped for them. The acreage and the trees are there and if Mother Nature gives them a bounteous bloom which sets well he knows he will have a lot of citrus to dispose of and that all the other growers will too. So he starts worrying in May or sooner and worries all summer. In the fall he worries lest hurricanes will strike his groves. The citrus business is so competitive and complicated that the growers and shippers are impelled to cooperate with each other and to regulate themselves by State and Federal laws. This is another worry the citrus growers have.

The grower of vegetables has many worries too but his next season's prospects are not determined so far in advance. Most growers are through with one season by June 1 and do not do much planting before September 15. The heavy plantings are not made until November and for each month following through March. If he does not make any money in the fall he expects to make some in the winter. If he does not make any money in the winter due to freezes he is likely to increase the size of his spring crop, hoping to make good for the year. Often enough he does. Some growers will make money in any kind of a season but it is often not the same set of growers. A frost can kill a hundred acres in one section and other acreage nearby may be saved to bring higher prices. They gamble and play for high stakes but if they lose their shirt there is always another season

Tomato Sales $47,523,000

Very few of the general public realize that the tomato business is so big in Florida. Tomatoes rank right behind oranges and grapefruit. Tomatoes in 1950-51 season had a gross f.o.b. value larger than beans, celery and potatoes combined. The tomato crop value was one-third of the value of all the 1950-51 vegetable crop and was nearly 20 percent of the volume. Some idea of the money value of tomatoes may be shown by comparisons. Oranges led with $156,526,000, followed by grapefruit $57,849,000, tomatoes $47,523,000, beef cattle sales $38,317,000, dairy products $39,219,000, hog sales $21,040,000, tobacco $19,387,000, beans $17,282,000, celery $16,021,000, and tangerines $14,884,000. The total agricultural production amounted to $589,350,000.

Corn On The Cob

This is an old crop which has taken on new life in Florida. We have been producing green corn for out-of-state markets for at least 35 years but never made much progress in volume until the new insecticides and treatments developed during the war. The secret of marketing success was the ability to produce worm-free corn. Our corn shipments for several seasons prior to the war averaged around 400 carloads. Shipments in 1947-48 reached 1000 carloads and for 1950-51 we shipped 5,185 carloads. The quality of our corn has been excellent and topping the market most of the time. We have taken much of the green corn market away from Texas during late spring and early summer. California offers only moderate competition. We have the corn market pretty much to ourselves from November to May 15. March, April, May and June are our best shipping months for volume and quality. Some of our finest corn is shipped from the cooler muck soils in June.

Celery Is Dependable

The celery crop is not too susceptible to cold damage and we ship celery in volume from January 1 to June 15. We shipped 14,954 carloads by rail and truck last season and the heaviest month was March with 3,338 carloads.

Celery is not widely produced in Florida as it is an expensive crop to grow. The land on which it grows, particularly in Seminole County, is generally costly as it requires artesian wells and underground tile for irrigation and drainage. Some of the muck land acreage is not so expensive. The muck lands in the Lake Okeechobee area of Palm Beach County in very recent years has led Seminole County in acreage by a small margin.

Most people in Florida over a period of thirty years recognized Sanford as the celery capital of Florida, and even of the United States. It has lost some of its prestige in recent years to the Salinas Section of California and the Lake Okeechobee Section of Florida. My father-in-law, Henry H. Chappell of Sanford, was a pioneer in the first production of commercial celery in Florida. Sanford celery growers pioneered in the techniques of growing and marketing celery. Mr. F. F. Dutton was the first to build a washing, packing and pre-cooling plant. Washing and pre-cooling is now an almost national practice in all celery growing sections of the nation. Sanford shippers a good many years ago moved into the New York celery sections during the summer months and changed that from a rough dirty deal to a washed and pre-cooled deal.

Florida Goes To North Carolina

North Carolina mountains have always been a favorite vacation spot for a large number of Florida people but for more than ten years we have had a lot of Florida shippers and farmers growing and marketing North Carolina vegetables and some fruits.

The growing and marketing methods were very crude in the North Carolina mountains less than twenty years ago. That area is now the principal source of many green vegetables for many of the states during July, August and September. Florida shippers and growers were an important factor in improving the growing, packing and marketing of North Carolina vegetables.

Florida fruit and vegetable growers are progressive. They are anxious to experiment with new materials and machines and marketing methods which seem to show promise. Florida growers have developed entirely new machines or equipment for special uses in growing and harvesting their crops. They believe in spending money to make money. They believe in good fertilizer, good machinery, good insecticides and good drainage. They believe in scientific research by the agricultural experiment stations and by themselves.

If you have been in close touch with agricultural accomplishments in Florida for twenty years you no longer say something cannot be done, for about that time somebody does it.

Livestock On The Upgrade

Both the number of cattle and the quality have been going up for twenty years. In 1931 we had 620,000 head of all classes of cattle, in 1941, 902,000, and in 1951 we had 1,503,000 cattle, and are likely to have more than 2,000,000 in 1956 at the present rate of increase. The quality of the herds was increased by the number of purebred bulls brought into Florida or produced here. In 1931 we had 320 purebred bulls, and just ten years later 1,700, while now we have 3,400. The best livestock authorities say we need 17,000 purebred bulls if we are to have the best herds obtainable. It is obvious that there is considerable room for improvement but as long as the need for more purebred bulls is generally recognized the bulls will be here in a few years, both brought into as well as produced in Florida. Our goal is not to produce just as good beef cattle as any other state but to do better than other beef cattle states.

Our rank among the states is now twelfth for beef cattle and twenty-third in number of all cattle. California is the eleventh ranking state with 1,461,000 beef cattle, but Florida with 1,200,000, will likely take their place within two or three years. Florida's cattle production has increased 64%, and California 17%, and all states 17% from 1940 to 1950.

More Hogs Are Needed

We need more good hogs. We need many thousand hogs. It is said that less than 50% of Florida pork consumption is produced in Florida. It is also claimed that the production of hogs in Florida could be made just as profitable as cattle, yet the production of hogs has not increased to much extent since 1940. We had 600,000 head in 1940 and 631,000 head in 1951. The reason for lack of increase in Florida hog production is mostly the lack of cheaper feeds produced in Florida. Considerable research has been made into this problem and better results will be obtained in the future. We will soon have a population of 3,000,000 people and we will need 1,500,000 hogs to feed them. In other words, a car in the garage, a Florida chicken in the pot, and half a Florida hog in the freezer.

A Letter

We have a little space on this stencil and we are going to put in a letter just received which says something very nice about this report. The letter from Donald A. Butts, Business Manager of the Florida Fruit and Vegetable Association, located in Orlando, is quoted as follows:

We have a letter from Austin E. Anson, Executive Manager of the Texas Citrus and vegetable Growers and Shippers Association of Harlingen, Texas, one paragraph of which reads as follows:

> "While we are spreading bouquets for reports, the yearly vegetable report that is put out by your Department of Agriculture in the State of Florida tops them all. Wish you would see to it that we are on the mailing list and that we do not miss any copies as we are going to pester our Department of Agriculture until they get into the harness and issue a similar report."

In view of Mr. Anson's high regard for your report, we are certain that you will want to check your mailing list to make sure that he receives a copy again this season.

Thank you, Mr. Anson and Mr. Butts!

FLORIDA AGRICULTURAL VOLUME AND VALUE

ACREAGE IN FLORIDA (Estimated for 1950-51 Season)	TOTAL ACRES
Citrus Bearing 433,700 a.; Other Fruits, Melons and Berries 79,000 a.	513,700
Vegetables - plats 1 acre or more, reported 255,200 (unreported 12,500)	267,700
Pecans 6,000 acres, Tung Trees 12,000 acres	18,000
Total Acres Fruits, Berries, Nuts and Vegetables	799,400
General Crop 1,500,000 a.; Other Farm Land Usage 6,500,000 a.	8,000,000
Pasture Land 11,000,000 a.; Woodland and Other Land 14,928,280 a.	25,928,280
Total Land Area of Florida	34,727,680

CITRUS PRODUCTION AND VALUE 1950-51 SEASON								FLORIDA FOB SALES
Oranges	Acres	309,500	Carloads	135,509	Units used	67,300,000	boxes	$156,526,000
Grapefruit	"	100,000	"	66,367	" "	33,200,000	"	57,849,000
Tangerines	"	24,200	"	9,500	" "	4,600,000	"	14,884,000
Total	"	433,700	"	211,376	" "	105,100,000	"	$229,259,000

MISCELLANEOUS FRUITS PRODUCTION AND VALUE 1950-51 SEASON								
Watermelons	Acres	62,000	Carloads	17,902	Units used	18,600,000	melons	$8,649,000
Strawberries	"	6,500	"	1,104	" "	520,000	crts.	4,134,000
Other Fruits	"	10,500	"	1,717	" "	779,950	pkgs	2,112,000
Total		79,000	"	20,723	" "			$14,895,000

VEGETABLE PRODUCTION AND VALUE 1950-51 SEASON (Officially reported acreage)								
Beans	Acres	75,000	Carloads	9,996	Units used	6,218,000	bu.	$ 17,282,000
Celery	"	10,650		15,109	" "	6,671,000	crts.	16,021,000
Potatoes	"	23,100		11,343	" "	6,004,000	bu.	12,188,000
Tomatoes	"	50,900		19,500	" "	8,217,000	bu.	47,523,000
Others	"	95,550		43,942	" "	-		47,848,000
Total		255,200		99,890	" "	-		$140,962,000

ALL FRUIT AND VEGETABLE PRODUCTION AND VALUE 1950-51 SEASON				
Total Acres	767,900	Carloads	331,989	$385,116,000

LIVESTOCK IN FLORIDA 1950	Head	Gross Value		FLORIDA SALES GROSS FOB VALUE
*Beef Cattle and Calves	1,503,000	$146,392,000		$38,317,000
**Dairy Cattle	152,000	23,256,000		(See Dairy Products)
Hogs and Pigs	631,000	14,955,000		21,040,000
Sheep & Lambs	12,000	100,000	(including wool)	35,000
Goats (estimate)	30,000	50,000		30,000
Total Livestock	2,328,000	$184,753,000		$59,422,000

* Hides$3,000,000 included. ** Dairy cattle used for beef included in beef sales.

POULTRY, EGG AND DAIRY PRODUCTS PRODUCED IN FLORIDA IN 1950			FLORIDA GROSS VALUE
Chickens Produced	39,000,000	pounds (hens, roosters, fryers)	$12,090,000
Eggs "	21,000,000	dozen at 60¢	12,600,000
Turkeys "	2,500,000	pounds at 34¢	850,000
Dairy Products	650,000,000	pounds (mostly milk) approx. 6¢ lb.	39,219,000
Total Poultry, Eggs and Dairy Products			$64,759,000

GENERAL FIELD CROP 1950	Volume Produced				
Corn	9,968,000	bu.	712,000	acres	$13,955,000
Tobacco	23,268,000	lbs.	22,200	"	19,387,000
Peanuts	59,040,000	lbs.	72,000	"	5,609,000
Sugar-Cane for Sugar	1,233,000	tons	38,700	"	9,347,000
Sugar-Cane Syrup	1,360,000	gals.	8,000	"	1,428,000
Black Strap Molasses	7,685,000	gals.(Incl.above) at 19.6¢			1,516,000
Sweet Potatoes	1,050,000	bu.	15,000	acres	2,468,000
Cotton	13,000	bales	32,000	"	2,569,000
Cow Peas 4,000, Oats 16,000, Velvet Beans 172,000, or Total 192,000 a.					2,675,000
Hay	53,000	tons	88,000	acres	928,000
Total Field Crop Group 1950			1,179,900	"	$59,882,000

MISCELLANEOUS CROPS AND SPECIALTIES 1950		FLORIDA GROSS VALUE
Flowers and Bulbs, Hot House and Field, Nursery Products, Specialty Crops under Glass, and Seeds (Gladiola estimated $9,500,000)		$ 16,429,000
Pecans	5,200,000 Lbs. at 27.6¢	1,438,000
Honey 208,000 colonies	16,224,000 Lbs. at 14.2¢	2,304,000
Total Miscellaneous Crops and Specialties		$ 20,171,000

AGRICULTURAL GROUP SALES	
Citrus Fruits	$229,259,000
Miscellaneous Fruits and Melons	14,895,000
Vegetables	140,962,000
Total Fruits and Vegetables	$385,116,000
Livestock	59,422,000
Poultry, Eggs and Dairy Products	64,759,000
General Field Crops	59,882,000
Miscellaneous Crops and Specialties	20,171,000
Total Agricultural Group	$589,350,000
LUMBER AND NAVAL STORES - 1949 (No later statistics obtainable)	
Also Wood Pulp, Poles, Piling, Fuel Wood, etc.	$180,000,000
FISH, SHELL FISH AND PRODUCTS 1948 (No later statistics obtainable)	
Food and Non-Food Fish and Shell Fish and Sponges, etc.	35,000,000
MINERAL PRODUCTION 1949 (No later statistics obtainable)	
Phosphate 37,732,894, Limestone 5,115,974, Other Products 11,028,132	53,877,000
	$268,877,000
GRAND TOTAL ABOVE GROUPS	$858,227,000
GRAND TOTAL ABOVE GROUPS - ONE YEAR AGO	$816,659,000
Tung Nuts (Add to Above) 16,200 tons at $60.00 (1949 Season)	$ ~~672~~,000
	972

FLORIDA PRODUCTION AND VALUE FOR 15 SEASONS
(Includes Canned and Locally Consumed)

	ALL CITRUS USED					
Season	Carloads Production	Boxes	Florida Gross Value	Gross	Weighted Average All Production & Marketing	Net*
1936-37	102,827	40,601,208	$68,838,758	$1.70	$1.09	$ .61
1937-38	103,964	40,939,629	53,285,352	1.30	1.08	.22
1938-39	143,369	56,447,995	58,646,931	1.04	.97	.07
1939-40	109,119	42,973,112	50,365,127	1.17	1.05	.12
1940-41	140,903	55,890,754	64,192,695	1.15	.99	.16
1941-42	120,089	48,400,000	80,572,620	1.66	1.09	.57
1942-43	154,909	68,700,446	153,052,989	2.23	1.12	1.11
1943-44	181,592	80,800,000	199,688,696	2.47	1.31	1.16
1944-45	156,759	69,000,000	201,912,530	2.93	1.31	1.62
1945-46	197,050	86,000,000	236,230,700	2.75	1.29	1.46
1946-47	190,730	83,100,000	146,565,580	1.76	1.32	.44
1947-48	214,045	91,100,000	114,925,000	1.26	1.16	.10
1948-49	219,517	92,900,000	182,188,000	1.96	1.33	.63
1949-50	176,725	87,700,000	241,964,000	2.76	1.29	1.47
1950-51	211,376	105,100,000	229,259,424	2.18	1.36	.82

* Net before deducting for taxes, interest on investment and depreciation, if any.

	ALL VEGETABLES USED		ALL VEGETABLES & MISCL. FRUITS	
Season	Carloads Production	Florida Gross Value	Carloads Production	Florida Gross Value
1936-37	51,885	$34,445,922	60,118	$39,090,756
1937-38	70,000	37,306,680	82,130	41,410,710
1938-39	68,506	38,489,172	77,606	43,575,732
1939-40	65,151	37,962,385	75,404	42,738,720
1940-41	58,560	43,077,816	68,486	48,562,482
1941-42	70,191	57,417,670	60,219	62,706,220
1942-43	63,221	81,823,200	69,445	87,555,990
1943-44	70,219	87,328,394	79,605	94,944,402
1944-45	69,225	99,441,550	81,213	107,673,150
1945-46	76,943	116,239,000	89,377	128,099,000
1946-47	58,049	91,618,000	72,262	102,144,000
1947-48	68,670	89,237,000	83,939	99,817,000
1948-49	87,454	115,856,000	103,964	126,531,000
1949-50	93,538	108,613,000	111,632	119,742,000
1950-51	99,890	140,962,000	120,613	155,857,000

ALL FRUITS AND VEGETABLES USED

Season	Carloads Production	Florida Gross Value	Value Per Carload
1936-37	162,945	$107,929,514	$ 662
1937-38	186,094	94,696,062	509
1938-39	220,975	102,220,663	463
1939-40	184,563	93,103,847	504
1940-41	209,389	112,768,552	539
1941-42	200,308	143,278,840	715
1942-43	224,554	240,608,979	1,071
1943-44	261,197	294,633,098	1,128
1944-45	237,912	309,585,680	1,301
1945-46	286,427	364,329,700	1,272
1946-47	262,992	248,709,580	946
1947-48	297,984	214,742,000	721
1948-49	323,481	308,719,000	954
1949-50	288,357	361,706,000	1,254
1950-51	331,989	385,116,424	1,160

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON-AUGUST 1, 1950-JULY 31, 1951

Carlot Shipment	Freight Straight & Mixed	Carloads Total Freight	Carloads Express	Boxes Freight Boat, Truck and Express	Gross FOB Returns Florida Points Box	Gross FOB Returns Florida Points For Crop	Production and Marketing Costs Box	Production and Marketing Costs For Crop	Net Return to Florida Growers Box	Net Return to Florida Growers Rail, Truck, Boat
Oranges	19,726	24,852	2,899	22,200,081	$3.12	$ 69,264,253	$1.97	$43,754,160	$1.15	$25,530,093
Grapefruit	13,831	17,125	984	13,880,116	2.73	37,892,717	1.61	22,346,987	1.12	15,545,730
Tangerines	2,476	3,309	73	2,675,426	4.35	11,638,103	2.58	6,902,599	1.77	4,735,504
Mxd.Citrus	9,253	(Converted)		(Converted)	-	-	-	-	-	-
Total	45,286	45,286	3,956	38,755,623	3.06	$118,795,073	$1.88	$72,983,746	$1.18	$45,811,327

GENERAL DISPOSITION ANALYSIS OF THE FLORIDA CITRUS CROP FOR SEASON 1950-51

BOXES	StraightCars Freight	Mxd.Cars Freight	Mxd.Cars Express	Total Boxes Rail	Total Boxes Boat	Trucked Out	Rail, Boat & Truck	Processed Fresh, Bxs.	Consumed Boxes	Total Crop Boxes
Oranges	9,621,356	2,645,269	1,154,500	13,421,125		8,778,956	22,200,081	41,914,851	3,185,068	67,300,000
Grapefruit	6,928,363	1,750,336	391,600	9,081,799	11,000	4,798,317	13,880,116	17,853,677	1,466,207	33,200,000
Tangerines	1,113,432	398,240	29,000	1,540,672		1,134,754	2,675,426	1,354,572	570,002	4,800,000(1)
Total	17,663,151	4,794,345	1,575,100	24,043,596	11,000	14,712,027	38,755,623	61,123,100	5,221,277	105,500,000
CARLOADS (Converted)						(Carloads)				Tot.Carloads
Oranges	19,726	5,126	2,899	27,751	-	17,558	45,309	83,830	6,370	135,509
Grapefruit	13,831	3,294	984	18,109	22	9,577	27,728	35,707	2,932	66,367
Tangerines	2,476	833	73	3,382	-	2,269	5,651	2,709	1,140	9,500
Total	36,033	9,253	3,956	49,242	22	29,424	78,688	122,246	10,442	211,376

ESTIMATED COST OF PRODUCING AND MARKETING 38,756,323 BOXES OF ORANGES, GRAPEFRUIT AND TANGERINES BY RAIL, TRUCK, BOAT

Cost of production such as fertilizer, spray materials, irrigation, pruning, labor, fuel, etc., but not including interest or taxes on strictly grove acreage, per Standard 1-3/5 bushel boxes.

ORANGES $ .57 GRAPEFRUIT $ .43 TANGERINES $ .63 WEIGHTED AVERAGE $ .53

Cost of picking, hauling, packing, selling, and other average ordinary marketing charges.

ORANGES $1.40 GRAPEFRUIT $1.18 TANGERINES $1.90 WEIGHTED AVERAGE $1.35

Total ordinary and average cost of production and marketing of citrus.

ORANGES $1.97 GRAPEFRUIT $1.61 TANGERINES $2.58 WEIGHTED AVERAGE $1.88

1. Estimated boxes per car: Straight Freight: Oranges 483.6, Grapefruit 500.2, Tangerines 455.6, Mixed Fruit 481.7; Mixed Express 400; Truck 500; Boat approximately 500 boxes per car.
2. Mixed Car Freight Analysis: Oranges 55.4, Grapefruit 35.6, Tangerines 9.0 per cent.
3. Mixed Car Express Analysis: Oranges 73.3, Grapefruit 24.9, Tangerines 1.8 per cent.
4. Ventilated Box Cars Used: Oranges 2425, Grapefruit 759, Tangerines 16, Mixed 1550. Total 4750 cars.
5. Interstate Shipments for By-products Manufacture Included in Rail Shipments: Oranges 47,550, Grapefruit 850 boxes.
6. Exports:(Boxes)

Exports:(Boxes)	Oranges	Grapefruit	Exports:(Boxes)	Oranges	Grapefruit
Government Rail	41,457	45,955	Commercial Rail	1,042	11,443
Government Truck	7,362	2,022	Commercial Truck	-	16,484
Government Boat	-	-	Commercial Boat from Jax.	-	11,000
Government Total	48,819	47,977	Government Total	1,042	38,927

Total Primary Exports: Oranges 49,857, Grapefruit 86,904, Grand Total 136,763 boxes.

(1) Includes 200,000 boxes Economic Abandonment.

RECORDS AND ESTIMATES ON FLORIDA CITRUS CROP FOR SEASON 1950-51 (Cont'd.)

TRUCK SHIPMENTS TO OUT-OF-STATE MARKETS (500 boxes to carload) AUGUST 1 - JULY 31										
ORANGES:	Carlot equiv.	17,558	or	8,778,956 boxes.	Gross at	$3.12	$ 27,390,343	Net* at	$1.15	$ 10,095,799
GRAPEFRUIT:	Carlot equiv.	9,597	or	4,798,317 boxes.	Gross at	2.73	13,099,405	Net* at	1.12	5,374,115
TANGERINES:	Carlot equiv.	2,269	or	1,134,754 boxes.	Gross at	4.35	4,936,180	Net* at	1.77	2,008,515
ALL CITRUS:	Carlot equiv.	29,424	or	14,712,027 boxes.	Gross at	$3.09	$ 45,425,928	Net* at	$1.19	$ 17,478,429
FREIGHT, EXPRESS AND BOAT SHIPMENTS TO OUT-OF-STATE MARKETS, AUGUST 1 - JULY 31										
ORANGES:	Carlot equiv.	27,751	or	13,421,125 boxes.	Gross at	$3.12	$ 41,873,910	Net* at	$1.15	$ 15,434,294
GRAPEFRUIT:	Carlot equiv.	18,131	or	9,081,799 boxes.	Gross at	2.73	24,793,311	Net* at	1.12	10,171,615
TANGERINES:	Carlot equiv.	3,382	or	1,540,672 boxes.	Gross at	4.35	6,701,923	Net* at	1.77	2,726,981
ALL CITRUS:	Carlot equiv.	49,264	or	24,043,596 boxes.	Gross at	$3.05	$ 73,369,144	Net* at	$1.18	$ 28,332,890
FRESH CITRUS USED FOR PROCESSING IN FLORIDA (500 boxes to carload) AUGUST 1 - JULY 31										
ORANGES:	Carlot equiv.	83,830	or	41,914,851 boxes.	Gross at	$1.86	$ 77,961,623	Net* at	$ .81	$ 33,951,029
GRAPEFRUIT:	Carlot equiv.	35,707	or	17,853,677 boxes.	Gross at	.91	16,246,846	Net* at	.08	1,428,294
TANGERINES:	Carlot equiv.	2,709	or	1,354,572 boxes.	Gross at	.65	880,472	Net* at	-.63	- 853,380
ALL CITRUS:	Carlot equiv.	122,246	or	61,123,100 boxes.	Gross at	$1.57	$ 95,088,941	Net* at	$ .56	$ 34,525,943
FRESH CITRUS CONSUMED IN FLORIDA (500 boxes to carload) AUGUST 1 - JULY 31										
ORANGES:	Carlot equiv.	6,370	or	3,185,068 boxes.	Gross at	$2.92	$ 9,300,399	Net* at	$1.05	$ 3,344,321
GRAPEFRUIT:	Carlot equiv.	2,932	or	1,466,207 boxes.	Gross at	2.53	3,709,504	Net* at	1.02	1,495,531
TANGERINES:	Carlot equiv.	1,140	or	570,002 boxes.	Gross at	4.15	2,365,508	Net* at	1.67	951,903
ALL CITRUS:	Carlot equiv.	10,442	or	5,221,277 boxes.	Gross at	$2.94	$ 15,375,411	Net* at	$1.11	$ 5,791,755
TOTAL RAIL, BOAT, TRUCK SHIPMENTS, PROCESSED AND LOCALLY CONSUMED CITRUS, AUGUST 1 - JULY 31										
ORANGES:	Carlot equiv.	135,509	or	67,300,000 boxes.	Gross at	$2.33	$156,526,275	Net* at	$ .93	$ 62,825,443
GRAPEFRUIT:	Carlot equiv.	66,367	or	33,200,000 boxes.	Gross at	1.74	57,849,066	Net* at	.56	18,469,555
TANGERINES:	Carlot equiv.	9,500	or	4,600,000 boxes.	Gross at	3.24	14,884,083	Net* at	1.05	4,834,019
ALL CITRUS:	Carlot equiv.	211,376	or	105,100,000 boxes.	Gross at	$2.18	$229,259,424	Net* at	$ .82	$ 86,129,017

NOTE: *Gross refers to returns FOB cars Florida shipping points, and net refers to returns to growers or fruit owners before deducting for interest and grove taxes, but after deducting for cost of production and marketing.

1: Trucked out shipment figures were based on inspections certified for interstate movement.

2: Processing fruit represent average gross price at processor's door. Processing fruit includes that for canning and concentrating, and the net price is the gross less production, picking, hauling, and other marketing charges.

3: Figures for Consumed in Florida are rough estimates based on population, prices, etc. Any person who does not approve this home consumption estimate may make his own estimate, but this volume, which is probably underestimated, has to be counted. This locally consumed volume of citrus includes packed, unpacked, inspected and uninspected. No thorough survey of local or Florida consumption of fresh citrus has ever been made.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS BY PRODUCTION UNITS, 1950-51 SEASON

Commodity	Units	Straight Freight	Mixed Freight	LCL Express	Boat	Interstate Truck	Total Shipped Out	Processed	Florida Consumed	Total Production Used	Abandoned (Not Included)
Beans	Bu.	1,076,000	230,000	3,175	-	3,827,900	5,137,075	752,000	328,925	6,218,000	439,000
Limas	Bu.	50,000	10,000	-	-	115,940	175,940	*	20,060	196,000	-
Cabbage	Tons	70,263	3,125	-	-	73,425	146,813	*	8,787	155,600	38,200
Cabbage	50#Pkg.	(2,810,520)	(125,000)	-	-	(2,937,000)	(5,872,520)	-	(351,480)	(6,224,000)	-
Celery	Crts.	4,551,000	63,150	2,125	-	1,740,000	6,356,275	*	314,725	6,671,000	60,000
Corn	Crts.	1,150,000	82,500	1,060	-	1,442,500	2,676,060	*	250,940	2,927,000	-
Cucumbers	Bu.	576,000	44,600	1,338	-	1,826,000	2,447,938	88,000	102,062	2,638,000	200,000
Eggplant	Bu.	38,500	75,000	1,800	-	447,000	562,300	-	35,700	598,000	-
Escarole&End.	Bu.	438,826	678,424	-	-	412,750	1,530,000	-	70,000	1,600,000	468,000
Lettuce	4 Dz.Cr.	57,600	22,400	1,600	-	179,840	261,440	-	74,560	336,000	48,000
Peppers	Bu.	927,520	480,000	3,000	-	1,547,800	2,958,320	26,000	117,680	3,102,000	200,000
Potatoes	Bu.	3,493,760	48,000	-	-	2,160,000	5,701,760	2,120	300,120	6,004,000	-
Squash	Bu.	90,000	67,500	2,250	-	750,000	909,750	*	97,250	1,007,000	51,000
Tomatoes	Bu.	3,003,800	60,000	2,750	-	3,916,000	6,982,550	808,000	426,450	8,217,000	-
Miscl.Vegs.	Bu.	226,800	856,800	3,000	-	2,056,800	(a)3,143,400	30,000	960,000	4,133,400	-
Mxd.Car Vegs.		(Converted)				(Converted)				(Converted)	
TOT.VEGETABLES	Units	18,490,326	2,843,374	22,098	-	23,359,530	44,715,328	1,706,120	3,449,952	49,871,400	1,466,000
Strawberries	36PtCrt	69,165	-	-	-	271,190	340,355	100,000	79,645	520,000	-
Watermelons	Melons	10,532,000	-	-	-	6,909,000	17,441,000	*	1,159,000	18,600,000	-
Watermelons	2-M.Crt	(5,266,000)	-	-	-	(3,454,500)	(8,720,500)	-	(579,500)	(9,300,000)	-
Avocados	Bu.	-	-	40,000	-	196,650	236,650	-	38,350	275,000	-
Limes	Bu.	-	-	80,000	-	92,250	172,250	20,000	57,750	250,000	-
Miscl.Fruits	Bu.	-	-	11,275	-	86,975	98,250	23,750	132,950	254,950	-
TOT.MISCL.FRT.	Units	5,335,165	-	131,275	-	4,101,565	9,568,005	143,750	888,195	10,599,950	-
Oranges	Boxes	9,621,356	2,645,269	1,154,500	-	8,778,956	22,200,081	41,914,851	3,185,068	67,300,000	-
Grapefruit	Boxes	6,928,363	1,750,836	391,600	11,000	(E)4,798,317	13,880,116	17,853,677	1,466,207	33,200,000	-
Tangerines	Boxes	1,113,432	398,240	29,000	-	1,134,754	2,675,426	1,354,572	570,002	4,600,000	200,000
TOTAL CITRUS	Boxes	17,663,151	4,794,345	1,575,100	11,000	14,712,027	38,755,623	61,123,100	5,221,277	105,100,000	200,000
GRAND TOTAL	Units	41,488,642	7,637,719	1,728,473	11,000	42,173,122	93,038,956	62,972,970	9,559,424	165,571,350	1,666,000

NOTES: *Included in Miscellaneous, if any. (a) An estimated 124,000 bushels of butterbeans included in Miscellaneous Vegs. (Pages 8 and 9). There is considerable difficulty in working out a detailed disposition sheet for vegetables and miscellaneous fruits as comprehensive data is not as available as for citrus. It was advisable to try to use the U.S. Department of Agriculture estimate of total production and work back from there. We have the records on the truck shipments out of State, which figures are used. We have the records on straight freight and boat for most of the individual commodities. We had only the totals for mixed freight and LCL express. The Florida consumption figures are only estimates. We had to apportion the mixed freight and mixed express totals as best we could to the various commodities with the handicap of trying to make all of the separate totals check with the total official crop estimate. (E) Export from Jacksonville.

ESTIMATED DISPOSITION OF FLORIDA VEGETABLES AND FRUITS IN CARLOTS, OR EQUIVALENT, AND VALUE 1950-51 SEASON

Commodity	Straight Freight Cars	Mixed Freight Cars	LCL Express Cars	Boat	Inter-state Truck Carlots	Total Shipped Out Carlots	Florida Processed	Florida Consumed Carlots	Total Used Carlots	Abandoned (Not Included)##	Total FOB Gross Value
Beans	1,669	400	5	-	6,174	8,248	1,213	535	9,996	708	$ 17,282,000
Limas	120	20	-	-	387	527	*	34	561	-	551,000
Cabbage	5,621	250	-	-	5,874	11,745	*	703	12,448	3,056	10,425,000
Celery	10,811	150	5	-	4,143	15,109	*	750	15,859	143	16,021,000
Corn	2,300	150	2	-	2,885	5,337	*	502	5,839	-	7,313,000
Cucumbers	1,293	100	3	-	4,169	5,565	198	227	5,990	444	7,848,000
Eggplant	77	150	3	-	818	1,048	-	58	1,106	-	1,216,000
Escarole & Endive	701	1100	-	-	635	2,436	-	108	2,544	720	2,240,000
Lettuce	180	70	5	-	562	817	-	233	1,050	150	890,000
Peppers	1,496	800	5	-	2,354	4,655	40	168	4,863	286	6,797,000
Potatoes	6,592	80	-	-	4,101	10,773	4	566	11,343	-	12,188,000
Squash	200	150	5	-	1,385	1,740	*	162	1,902	85	2,401,000
Tomatoes	6,530	120	5	-	9,790	16,445	2,000	1,055	19,500	-	47,523,000
Miscl. Vegetables	378	1,428	5	-	3,428	5,239	50	1,600	6,889	-	8,267,000
Mixed Car Vegetables	(Converted)	-	(Converted)		-	(Converted)	-	-	-	-	-
TOTAL VEGETABLES	37,968	4,968	43	-	46,705	89,684	3,505	6,701	99,890	5,592	$140,962,000
Strawberries	145	-	-	-	577	722	213	169	1,104	-	4,134,000
Watermelons	9,834	-	-	-	6,909	16,743	*	1,159	17,902	-	8,649,000
Avocados	-	-	100	-	437	537	-	85	622	-	737,000
Limes	-	-	200	-	205	405	50	144	599	-	780,000
Miscl. Fruits	-	-	25	-	141	166	50	280	496	-	595,000
TOTAL MISCL. FRUITS	9,979	-	325	-	8,269	18,573	313	1,837	20,723	-	$ 14,895,000
Oranges	19,726	5,126	2,899	-	17,558	45,309	83,830	6,370	135,509	-	156,525,275
Grapefruit	13,831	3,294	984	(E) 22	9,597	27,728	35,707	2,932	66,367	-	57,849,056
Tangerines	2,476	833	73		2,269	5,651	2,709	1,140	9,500	400	14,884,083
Mixed Citrus	(Converted)	-	(Converted)	-	-	(Converted)	-	-	-	-	-
TOTAL CITRUS	36,033	9,253	3,956	22	29,424	78,688	122,246	10,442	211,376	400	$229,259,424
GRAND TOTAL	83,980	14,221	4,324	22	84,398	186,945	126,064	18,980	331,939	5,992	$385,116,424

NOTES: (Pages 8 and 9). An additional problem was the disposition of the volume of radishes, cauliflower, carrots, spinach, broccoli, endive, etc., included in the miscellaneous figures for vegetables. Miscellaneous fruits included mangoes, grapes, guavas, persimmons, pears, blueberries, etc. #Ordinarily units of different kinds are not added but if the 50# sack is used for cabbage, instead of tons, and the number of watermelons are divided by two to get a crate, we find that all of the units are bushels or the near equivalent of bushels, with the exception of citrus which are in 1-3/5 bushel boxes. ##Abandoned because of market conditions and not included in the gross FOB Florida value. The estimated gross includes the production, marketing costs, and packing costs if packed, and profit, if any. (E) Export from Jacksonville.

Are these tabulations on these two pages any good to you? They are very troublesome for us.

FREIGHT CARLOT SHIPMENTS FROM FLORIDA BY COMMODITIES AND MONTHS, FOR 1950-51 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	9	4	518	2004	2831	2171	2214	2774	2335	2333	1747	517	19,457
Grapefruit	15	476	934	1304	1042	1463	1669	1955	2035	1806	866	153	13,718
Tangerines				193	1110	705	374	76	18				2,476
Mixed Citrus		7	203	889	1553	1227	1240	1338	1129	882	498	140	9,106
TOTAL CITRUS	24	487	1655	4390	6536	5566	5497	6143	5517	5021	3111	810	44,757
Strawberries						8	45	92					145
Watermelons									7	2106	7469	252	9,834
TOTAL MISCL.FRUITS						8	45	92	7	2106	7469	252	9,979
Beans(incl.Limas)				108	140	150	286	375	503	220	7		1,789
Cabbage					6	19	287	2230	2518	561			5,621
Cauliflower						44	22	36	12				114
Celery				56	251	1422	1658	2315	2228	2260	621		10,811
Corn, Green			1	2	4	4	13	210	657	972	437		2,300
Cucumbers			41	123	27	5	4	1	511	549	32		1,293
Eggplant									10	39	17	11	77
Escarole				10	47	96	140	137	149	121	1		701
Greens(ex. Spinach)					7	20	56	38	35	16			172
Lettuce & Romaine					6	52	74	46	2				180
Peppers					3	3	15	235	464	413	363		1,496
Potatoes					2	241	470	933	1934	2954	58		6,592
Tomatoes			6	242	483	392	343	893	1294	2558	319		6,530
Other Vegetables	3					4	30	46	6	1		2	92*
Mixed Car Vegetables			7	48	177	481	750	1266	1232	839	167	1	4,968
TOTAL VEGETABLES	3		55	589	1153	2933	4148	8761	11555	11503	2022	14	42,736
NON-CITRUS & VEGS.	3		55	589	1153	2941	4193	8853	11562	13609	9491	266	52,715
ALL FRUITS & VEGS.	27	487	1710	4979	7689	8507	9690	14996	17079	18630	12602	1076	97,472

PICK-UP-EXPRESS SHIPMENTS FROM FLORIDA STATIONS FOR 1950-51 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Mixed Citrus				84	1972	682	487	479	190		9		3,903
Mixed Vegetables									34		9		43
TOTAL FRUITS & VEGS.				84	1972	682	487	479	224		18		3,946

NOTE: * Other Vegetables by Freight include: Broccoli 19, Carrots 5, English Peas 4, Spinach 48, Sweet Potatoes 5, Turnips 11. Total 92 carloads.

RAIL - FREIGHT & EXPRESS CARLOT SHIPMENTS, FOR 1950-51 SEASON

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	9	4	518	2004	2831	2171	2214	2774	2335	2333	1747	517	19,457
Grapefruit	15	476	934	1304	1042	1463	1669	1955	2035	1806	860	153	13,718
Tangerines				193	1110	705	374	76	18				2,476
Mixed Citrus		7	203	973	3525	1909	1727	1817	1319	882	507	140	13,009
TOTAL CITRUS	24	487	1655	4474	8508	6248	5984	6622	5707	5021	3120	810	48,660
Strawberries						8	45	92					145
Watermelons									7	2106	7469	252	9,834
TOTAL MISCL. FRUITS						8	45	92	7	2106	7469	252	9,979
Beans(incl.Limas)				108	140	150	286	375	503	220	7		1,789
Broccoli						2	11	6					19
Cabbage					6	19	287	2230	2518	561			5,621
Carrots									5				5
Cauliflower						44	22	36	12				114
Celery				56	251	1422	1658	2315	2228	2260	621		10,811
Corn, Green			1	2	4	4	13	210	657	972	437		2,300
Cucumbers			41	123	27	5	4	1	511	549	32		1,293
Eggplant									10	39	17	11	77
Escarole				10	47	96	140	137	149	121	1		701
Greens(ex. Spinach)					7	20	56	38	35	16			172
Lettuce & Romaine					6	52	74	46	2				180
Peas, English							2		1	1			4
Peppers					3	3	15	235	464	413	363		1,496
Potatoes					2	241	470	933	1934	2954	58		6,592
Spinach						2	14	32					48
Sweet Potatoes	3											2	5
Tomatoes			6	242	485	592	543	895	1294	2558	319		6,530
Turnips							3	8					11
Mixed Car Vegetables			7	48	177	431	750	1236	1260	839	176	1	5,011
TOTAL VEGETABLES	3		55	589	1153	2933	4148	8761	11589	11503	2031	14	42,779
NON-CITRUS & VEGS.	3		55	589	1153	2941	4193	8853	11596	13609	9500	266	52,758
ALL FRUITS & VEGS.	27	487	1710	5063	9661	9189	10177	15475	17303	18630	12620	1076	101,418

BOAT SHIPMENTS (Carlot Equivalent FROM FLORIDA PORTS (Does not include initial rail haul exports).

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Grapefruit										22(Export)			22

FLORIDA INTERSTATE TRUCK SHIPMENT PASSINGS FOR 1950-51 SEASON

Actual Check at Nine Road Guard Stations August 1-July 31.

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	6	23	1506	2676	2980	2031	2165	2070	1550	1315	764	185	17,271
Grapefruit	41	656	1316	1125	793	969	1169	1347	982	702	341	64	9,505
Tangerines		lcl	lcl	207	973	684	329	37	10	3	lcl		2,243
TOTAL CITRUS	47	679	2822	4008	4746	3684	3663	3454	2542	2020	1105	249	29,019
Avocados	30	54	81	80	83	43	13	1	lcl	lcl	2	50	437
Limes	12	6	2	3	12	7	4	5	4	3	69	78	205
Strawberries					3	103	192	242	36	1			577
Watermelons	lcl								2	847	4986	1074	6,909
Other Non-Citrus Frts					11	10	10	2	lcl	13	87	8	141
TOTAL MISCL. FRUITS	42	60	83	83	109	163	219	250	42	864	5144	1210	8,269
Beans, Snap	lcl		7	384	477	783	1055	1356	1507	593	12		6,174
Limas & Butter Beans				lcl	6	8	12	47	56	173	85	lcl	387
Cabbage				lcl	23	216	807	2191	2158	464	15		5,874
Cauliflower					4	132	82	95	42	2			357
Celery				20	138	646	808	1023	722	593	192	1	4,143
Corn, Green			4	26	20	37	42	253	830	1201	472	lcl	2,885
Cucumbers			227	606	281	172	153	122	1204	1317	87	lcl	4,169
Eggplant	lcl		6	40	64	106	39	57	144	172	148	42	818
Escarole				11	73	130	96	117	80	26	2		535
Lettuce & Romaine				1	35	171	200	105	44	6			562
Okra	lcl	lcl	13	7	2	1	1	1	3	44	60	18	150
Field Peas	lcl		5	16	2	2	1	3	19	386	206	2	642
Peppers	1		lcl	11	40	145	240	549	507	558	297	6	2,354
Potatoes				lcl	15	153	213	540	1129	2016	28	7	4,101
Radishes	(August to January, incomplete)					21	171	172	59	2			425
Squash		lcl	12	64	60	128	206	349	406	148	12	lcl	1,385
Tomatoes			37	611	420	618	632	1711	1895	3331	534	1	9,790
Bunched Vegetables			lcl	3	21	75	165	144	44	2			454
Other Vegetables	4	lcl	lcl	54	195	376	426	278	122	40	3	2	1,500
TOTAL VEGETABLES	5	lcl	311	1854	1876	3920	5349	9113	10971	11074	2153	79	46,705
VEGS. & MISCL. FRUITS	47	60	394	1937	1985	4083	5568	9363	11013	11938	7297	1289	54,974
ALL FRUITS & VEGS.	94	739	3216	5945	6731	7767	9231	12817	13555	13958	8402	1538	83,993

CARLOT SHIPMENTS (FREIGHT, EXPRESS, BOAT & TRUCK) FRUITS AND VEGETABLES BY MONTHS FOR SEASON 1950-51

August 1-July 31, (Inclusive)

COMMODITY	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	March	April	May	June	July	TOTAL
Oranges	15	27	2024	4680	5811	4202	4379	4844	3885	3648	2511	702	36,728
Grapefruit	56	1132	2250	2429	1835	2432	2838	3302	3039	2508	1207	217	23,245
Tangerines		1cl	1cl	400	2083	1389	703	115	28	3	1cl		4,719
Mixed Citrus		7	203	973	3525	1909	1727	1817	1319	882	507	140	13,009
TOTAL CITRUS	71	1166	4477	8482	13254	9932	9347	10076	8271	7041	4225	1059	77,701
Avocados	30	54	81	80	83	43	13	1	1cl	1cl	2	50	437
Limes	12	6	2	3	12	7	4	5	4	3	69	78	205
Strawberries					3	111	237	334	36	1			722
Watermelons	1cl								9	2953	12455	1326	16,743
Other Non-Citrus Frts					11	10	10	2	1cl	13	87	8	141
TOTAL MISCL. FRUITS	42	60	83	83	109	171	264	342	49	2970	12613	1462	18,248
Beans (incl. Limas)	1cl		7	492	623	941	1353	1778	2066	986	104	1cl	8,350
Cabbage				1cl	29	235	1094	4421	4676	1025	15		11,495
Cauliflower					4	176	104	131	54	2			471
Celery				76	589	2068	2466	3338	2950	2853	813	1	14,954
Corn, Green			5	28	24	41	55	463	1487	2173	909	1cl	5,185
Cucumbers			268	729	308	177	157	123	1715	1866	119	1cl	5,462
Eggplant	1cl		6	40	64	106	39	57	154	211	165	53	895
Escarole				21	120	226	236	254	229	147	3		1,236
Lettuce & Romaine				1	41	223	274	151	46	6			742
Peas, English							2		1	1			4
Peppers	1		1cl	11	43	148	255	784	971	971	660	6	3,850
Potatoes				1cl	17	394	683	1473	3063	4970	86	7	10,693
Tomatoes			43	853	903	1010	975	2604	3189	5889	855	1	16,320
Other Vegetables	3		30	90	92	251	628	753	571	598	278	22	3,316
Mixed Car Vegetables	4	1cl	7	102	372	857	1176	1544	1388	879	179	3	6,511
TOTAL VEGETABLES	8	1cl	366	2443	7029	6853	9497	17874	22560	22577	4184	93	89,484
VEGS. & MISCL. FRUITS	50	60	449	2526	7138	7024	9761	18216	22609	25547	16797	1555	107,732
ALL FRUITS & VEGS.	121	1226	4926	11008	16392	16956	19108	28292	30880	32588	21022	2614	185,437

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS

(These figures have been revised and rearranged and may not agree or seem to agree with some previous tabulations. The totals are substantially the same.)

	Freight Shipments									
Commodity	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49	1949-50	1950-51
Oranges	34,374	43,390	51,405	41,049	41,848	43,390	33,524	26,603	14,345	19,457
Grapefruit	12,650	12,258	13,441	6,534	12,201	12,606	11,801	13,826	7,671	13,718
Tangerines	1,865	5,017	3,856	4,370	3,813	2,974	2,884	2,923	2,205	2,476
Mixed Citrus	10,062	13,162	13,626	11,102	13,573	9,599	6,667	8,155	4,804	9,106
Total Citrus	58,951	73,827	82,328	63,055	71,435	68,569	54,876	51,507	29,025	44,757
Strawberries	-	6	22	43	25	99	56	110	182	145
Watermelons	5,565	3,363	6,116	8,366	7,470	7,963	9,247	8,864	10,054	9,834
Miscellaneous Fruits	-	-	16	15	3	9	-	-	2	-
Total Non-Citrus	5,565	3,369	6,154	8,424	7,498	8,071	9,303	8,974	10,238	9,979
Beans & Limas	3,335	5,943	6,506	4,682	4,538	3,668	3,148	3,628	2,550	1,789
Cabbage	3,568	4,534	6,378	5,157	4,763	2,459	4,934	5,457	4,016	5,621
Celery	9,119	8,557	9,349	11,037	12,489	8,747	8,966	9,345	10,011	10,811
Corn, Green	7	17	18	42	104	166	338	1,223	2,191	2,300
Cucumbers	1,181	461	405	988	1,549	1,138	1,500	1,052	787	1,203
Eggplant	29	175	246	304	251	81	182	70	47	77
Escarole	818	1,003	1,120	1,347	1,317	827	1,039	974	919	701
Lettuce & Romaine	147	197	207	152	166	116	90	102	123	180
Peas, English	130	115	153	33	62	14	16	None	2	4
Peppers	863	1,352	1,805	1,622	1,612	744	1,499	1,364	1,842	1,496
Potatoes	5,540	4,756	5,282	7,068	9,591	4,001	4,807	6,593	5,322	6,592
Tomatoes	5,035	4,367	4,592	5,305	5,269	3,249	5,782	6,783	6,003	6,530
Squash (estimated)	300	400	400	500	400	400	500	400	300	200*
Other Variety Vegetables	86	133	364	426	484	224	131	202	242	374**
Mixed Car Vegetables	2,113	3,973	5,855	6,884	7,217	4,704	4,442	4,472	4,654	4,968***
Total Vegetables	32,271	35,983	42,770	45,597	49,812	30,538	35,424	41,665	39,009	42,936
Total Vegs. & Non-Citrus	37,836	39,352	48,924	54,021	57,310	38,609	44,727	50,639	49,247	52,915
ALL FRUITS & VEGETABLES	96,787	113,179	131,252	119,076	128,745	107,178	99,603	102,146	78,272	97,672

NOTE: * Includes an estimated 200 straight cars of Squash not officially reported.

** Other Vegetables include carloads as follows: Broccoli 19, Carrots 5, Cauliflower 114, Greens (except Spinach) 172, Spinach 48, Turnips 11, Sweet Potatoes 5. Total 374 carloads.

*** Mixed Vegetables includes eggplant, peppers, escarole, squash, and all other vegetables shipped in mixed cars.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd)

Commodity	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49	1949-50	1950-51
					Express Shipments					
EXPRESS										
Mixed Citrus	1,177	2,371	3,100	3,041	3,376	3,630	3,115	3,412	3,062	3,903
Strawberries	58	55	1	-	-	-	-	-	-	-
Miscellaneous Fruits	125	175	175	90	90	100	100	90	325*	360**
Total Non-Citrus	183	230	176	90	90	100	100	90	325	360
Mixed Car Vegetables	605	1,074	1,283	1,148	1,179	848	533	433	336	43
Total Vegs. & Non-Citrus	788	1,304	1,459	1,238	1,269	948	633	523	661	403
ALL FRUITS & VEGETABLES	1,965	3,675	4,559	4,279	4,645	4,578	3,748	3,935	3,723	4,306
BOAT					Boat Shipments					
Oranges	1,153				76	2,908	-	35	3,087	-
Grapefruit	514				12	1,437	-	-	1,662	22
Tangerines	147				-	222	-	-	409	-
Mixed Citrus	3	No record of any			-	-	-	-	-	-
Total Citrus	1,817				88	4,567	-	35	5,158	22
Beans & Limas	1	boat shipments			-	-	-	-	-	-
Cabbage	-				-	-	-	-	3	-
Celery	-	during (War Period)			-	100	-	-	248	-
Corn, Green	-				-	3	-	-	-	-
Cucumbers	-	1942-43 thru			-	3	-	-	1	-
Peppers	6				-	-	-	-	7	-
Potatoes	-	1944-45 Seasons			-	164	-	-	191	-
Squash	1				-	-	-	-	-	-
Other Variety Vegetables	3				-	2	5	-	7	-
Total Vegetables	11				-	272	5	-	457	-
ALL FRUITS & VEGETABLES	1,828				88	4,839	5	35	5,615	22

Note: * 1949-50 Season - LCL Express reestimated as follows: Avocados 100, Limes 200, Miscel. Fruits 25, carloads.
** 1950-51 Season - Miscellaneous Fruits by LCL Express estimated at 360 carloads including Avocados 10, Limes 325, Mangoes 15, and Miscellaneous Fruits (non-citrus) 10 carloads.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd).

	Trucked Out Shipments									
Commodity	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49	1949-50	1950-51
Oranges	10,248	6,790	5,388	3,641	5,135	8,774	14,268	30,356	20,451	17,271
Grapefruit	2,605	1,532	889	513	851	1,395	2,858	8,708	6,931	9,505
Tangerines	837	1,000	957	819	960	1,096	1,670	2,702	2,706	2,243
Total Citrus	13,690	9,322	7,234	4,973	6,946	11,265	18,796	41,766	30,088	29,019
Strawberries	860	300	164	263	446	615	321	410	724	577
Watermelons	695	190	630	654	2,538	3,278	3,503	4,888	4,500	6,909
Avocados	143	60	142	327	42	72	81	97	230	437
Limes	90	20	18	100	63	44	31	111	164	205
Miscellaneous Fruits	17	30	32	25	77	65	38	53	200	141
Total Non-Citrus	1,805	600	986	1,369	3,166	4,074	3,974	5,562	5,818	8,269
Beans	6,026	2,300	2,405	2,123	2,832	3,219	4,172	5,642	6,702	6,174
Limas	500	100	99	134	297	229	343	503	540	387
Cabbage	3,539	1,900	2,116	1,449	2,083	3,003	3,983	3,543	5,327	5,874
Celery	1,582	360	401	405	566	1,020	1,381	2,345	3,481	4,143
Corn, Green	200	150	190	121	392	479	662	1,803	2,735	2,885
Cucumbers	866	265	250	444	741	896	1,993	2,564	4,121	4,169
Eggplant	734	300	525	380	682	756	754	1,153	955	818
Escarole	116	15	7	25	20	145	200	284	421	535
Lettuce	150	36	54	51	93	90	103	142	355	562
Peas, English	222	20	77	53	52	26	18	16	27	-
Peppers	1,656	900	865	809	1,524	1,586	1,987	2,983	2,775	2,354
Potatoes	1,116	500	426	372	759	701	1,278	2,697	3,629	4,101
Tomatoes	3,994	1,700	3,190	2,826	3,549	2,526	5,826	6,907	8,797	9,790
Squash	538	300	440	447	653	645	815	1,098	1,358	1,385
Butterbeans	50	20	41	46	142	94	145	*	*	*
Field Peas	200	110	220	288	553	658	804	728	630	642
Okra	63	25	39	76	155	111	186	252	265	150
Bunched Vegetables	70	30	114	45	59	50	110	56	38	454
Other Vegetables	422	265	247	225	340	434	619	870	1,310	2,282
Total Vegetables	22,044	9,286	11,706	10,819	15,492	16,668	23,385	33,586	43,466	46,705
Total Vegs. & Non-Citrus	23,849	9,886	12,692	12,188	18,658	20,742	2 ,359	39,148	49,284	54,974
ALL FRUITS & VEGETABLES	37,539	19,208	19,926	17,161	25,604	32,007	46,155	80,914	79,372	83,993

Note: * Butterbeans estimated at 190 carloads included with Limas.

"Miscellaneous Fruits" by Truck include: Cantaloupes 92, Mangoes 15, and Miscl. 34. Total 141 carloads.

"Other Vegetables" by Truck include: Broccoli, Beets, Carrots, Celery-cabbage, Collards, Dandelion, Dill, Endive, English Peas, Onions, Parsley, Spinach, Rutabagas, Turnips, Watercress, etc.

FLORIDA SHIPMENTS BY VARIOUS MEANS OF TRANSPORTATION FOR TEN SEASONS (Cont'd).

Commodity	1941-42	1942-43	1943-44	1944-45	1945-46	1946-47	1947-48	1948-49	1949-50	1950-51
	Total Freight, Express, Boat and Truck Shipments from Florida									
Oranges	45,775	50,180	50,795	44,690	47,059	55,072	47,792	56,994	37,883	36,728
Grapefruit	15,769	13,790	14,330	9,047	13,064	15,438	14,659	22,534	16,264	23,245
Tangerines	2,849	6,017	4,813	5,189	4,773	4,292	4,554	5,625	5,320	4,719
Mixed Citrus (Rail)	11,242	15,533	16,726	14,143	16,949	13,229	9,782	11,567	7,866	13,009
Total Citrus	75,635	85,520	92,662	73,069	81,845	88,031	76,787	96,720	67,333	77,701
Strawberries	918	361	187	306	471	714	377	520	903	722
Watermelons	6,260	3,553	6,746	9,020	10,008	11,241	12,750	13,752	14,554	16,743
*Avocados (Truck & Exp.)	205	150	237	382	77	127	141	127	330	537
*Limes (Truck & Express)	145	95	88	130	103	79	63	161	364	405
(*)Miscl.Fruits(Exp.& Truck)	25	40	42	30	90	84	46	66	225	166
Total Miscl. Fruits	7,553	4,199	7,300	9,868	10,749	12,245	13,377	14,626	16,379	18,573
Beans & Limas	9,862	8,343	9,100	6,939	7,667	7,116	7,663	9,773	9,792	8,350
(a)Butterbeans(Truck)	50	20	41	46	142	94	145	**	**	**
Cabbage	7,107	6,434	8,494	6,606	6,846	5,462	8,917	9,000	9,346	11,495
Celery	10,701	8,917	9,750	11,442	13,055	9,867	10,347	11,690	13,740	14,954
Corn, Green	207	167	208	163	406	643	1,000	3,020	4,926	5,185
Cucumbers	2,047	726	655	1,432	2,290	2,037	3,499	3,616	4,909	5,462
Eggplant	763	475	771	684	933	837	936	1,223	1,002	895
Escarole	934	1,018	1,127	1,372	1,537	972	1,239	1,258	1,340	1,236
Lettuce	297	223	261	203	259	206	193	244	478	742
Peas, English	352	135	230	136	114	40	34	16	29	4
Peppers	2,525	2,252	2,670	2,431	3,136	2,330	3,486	4,347	4,624	5,850
Potatoes	6,656	5,266	5,708	7,940	10,350	4,866	6,085	9,290	9,142	10,693
Tomatoes	9,029	6,067	7,782	8,131	8,818	5,775	7,008	13,690	14,800	16,320
Squash	830	700	840	547	1,053	1,045	1,315	1,498	1,658	1,385
(a)Field Peas (Truck)	200	110	220	298	553	658	804	728	670	642
(a)Okra (Truck)	63	25	39	76	155	111	183	252	235	150
(a)Bunched Vegetables(Truck)	70	30	114	45	59	50	110	56	36	454
(a)Other Vegetables (Truck)	422	265	247	225	340	439	619	970	1,310	2,282
(b)Oth.Vegs(Freight Boat)	99	133	364	123	404	226	186	202	249	374
(c)Mixed Vegs.(Freight & Exp.)	2,718	5,047	7,136	8,032	6,396	5,552	4,975	4,905	4,900	5,011
Total Vegetables	54,931	46,353	55,759	57,564	66,483	48,326	59,347	75,684	83,268	89,484
Total Vegs. & Miscl.Frts	62,484	50,552	63,059	67,432	77,232	60,571	72,724	90,310	99,647	108,057
ALL FRUITS VEGETABLES	138,119	136,072	155,721	140,501	159,077	148,602	149,511	187,030	166,980	185,758

(*)Includes estimates for Express Shipments of avocados, limes, mangoes, etc. ** Included with beans & limas.
(a)Truck Shipments only, with small volume included in Miscellaneous or Mixed Cars. (b)Freight and Boat only.
(c)Freight and Express only. (Estimated 100 straight cars Radishes not reported or included.)

RAIL FREIGHT SHIPMENTS BY COUNTIES
1950-51 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Oranges	Grape-fruit	Tanger-ines	Mixed Citrus	Total Citrus	Beans & Limas	Broccoli	Cabbage
Alachua	66	4	2	1	73	24		19
Bradford								
Brevard	794	465		348	1607			
Broward						595		
Citrus	8				8			
Clay								3
Collier								
Columbia								
Dade						35	16	36
De Soto	397	23	36	94	550			
Duval	604	154	61	148	967			
Escambia								
Flagler								149
Gilchrist								
Glades								165
Hamilton								8
Hardee	39	10		1	50			
Hendry								351
Hernando	48	24	95	57	224			
Highlands	1195	593	44	487	2319			
Hillsborough	802	391	62	388	1643	3		88
Indian River	336	1765	4	515	2620			
Jackson								
Jefferson								
Lafayette								
Lake	1877	673	266	938	3754	2		2
Lee	12	19		17	48			19
Leon								
Levy								
Madison								
Manatee	40	49			89			147
Marion	689	74	1	63	827	28		10
Martin							3	8
Okeechobee								
Orange	4946	1243	842	1428	8459	3		188
Osceola	45	8	3	23	79			
Palm Beach	16	16		35	67	1087		2094
Pasco	182	86	32	109	409			
Pinellas	144	1459	32	140	1775			
Polk	4724	4873	712	3054	13363			2
Putnam	102		22	37	161			102
St. Johns								1329
St. Lucie	1288	1469	7	598	3362			
Sarasota	56	113		94	263			41
Seminole	771	164	123	334	1392	3		808
Sumter						9		
Suwannee								
Union								7
Volusia	276	43	132	197	648			45
Washington								
Straight Cars	19457	13718	2476	9106	44757	1789	19	5621
Pick-Up-Express				3903	3903			
Boat		22*			22			
GRAND TOTAL	19457	13740	2476	13009	48682	1789	19	5621

* Export

RAIL FREIGHT SHIPMENTS BY COUNTIES
1950-51 SEASON
(August 1-July 31)

CARLOTS Florida Counties	Carrots	Cauli-flower	Celery	Green Corn	Cucumbers	Eggplant	Escarole	Greens
Alachua			389	1	169	16		
Bradford				32				
Brevard								
Broward				1	20	25		2
Citrus								
Clay								
Collier					121			
Columbia								
Dade				145	12			
De Soto								
Duval			3					
Escambia								
Flagler								
Gilchrist								
Glades				11				
Hamilton								
Hardee					257			
Hendry					9			
Hernando								
Highlands	5							
Hillsborough		85		11	106	4		
Indian River								
Jackson					13			
Jefferson					1			
Lafayette								
Lake			868	82			4	
Lee				26	172	1		
Leon								
Levy								
Madison								
Manatee				9	88		23	
Marion			225		8			
Martin				41	57	2		
Okeechobee								
Orange		11	600	380	12		115	57
Osceola								
Palm Beach			3040	1357		29	452	92
Pasco								
Pinellas								
Polk								
Putnam								
St. Johns		12						
St. Lucie					20			21
Sarasota			1713	32	10		2	
Seminole		6	3973	166			105	
Sumter					211			
Suwannee					7			
Union				6				
Volusia								
Washington								
Straight Cars	5	114	10811	2300	1293	77	701	172
Pick-Up-Express								
Boat								
GRAND TOTAL	5	114	10811	2300	1293	77	701	172

RAIL FREIGHT SHIPMENTS BY COUNTIES
1950-51 SEASON
(August 1-July 31)

CARLOTS

Florida Counties	Lettuce & Romaine	English Peas	Peppers	Potatoes	Spinach	Sweet Potatoes	Tomatoes	Turnips
Alachua	12		140	81		4		
Bradford			11					
Brevard								
Broward			809				270	
Citrus								
Clay								
Collier			6				903	
Columbia								
Dade				1763			1903	
De Soto								
Duval								
Escambia								
Flagler				776				
Gilchrist								
Glades	21							
Hamilton								
Hardee							59	
Hendry	43						58	
Hernando								
Highlands								
Hillsborough	7	1	291	41			497	
Indian River							101	
Jackson								
Jefferson								
Lafayette								
Lake							19	
Lee			7	458		1		
Leon								
Levy								
Madison								
Manatee	16			26			1113	
Marion	28		4	11	3		148	
Martin			4				21	9
Okeechobee							261	
Orange	7				45			1
Osceola								
Palm Beach	18	3	64	172			25	
Pasco								
Pinellas								
Polk								
Putnam				444				
St. Johns				2816				
St. Lucie			12				1142	
Sarasota								
Seminole	28		52	4				1
Sumter			68				10	
Suwannee								
Union								
Volusia			28					
Washington								
Straight Cars	180	4	1496	6592	48	5	6530	11
Pick-Up-Express								
Boat								
GRAND TOTAL	180	4	1496	6592	48	5	6530	11

RAIL FREIGHT SHIPMENTS BY COUNTIES

1950-51 SEASON

(August 1-July 31)

CARLOTS

Florida Counties	Mixed Veg's	Total Vegetables	Straw-berries	Water-melons	Total Non-Citrus	Total Veg's & Non-Citrus	GRAND TOTAL
Alachua	38	893		926	926	1819	1892
Bradford	1	44		17	17	61	61
Brevard				3	3	3	1610
Broward	1377	3099				3099	3099
Citrus				120	120	120	128
Clay		3				3	3
Collier	7	1037		126	126	1163	1163
Columbia				53	53	53	53
Dade	15	3925				3925	3925
De Soto				54	54	54	604
Duval		3				3	970
Flagler		925				925	925
Gilchrist				1032	1032	1032	1032
Glades	4	201				201	201
Hamilton		8		11	11	19	19
Hardee	10	326	4	7	11	337	387
Hendry	6	467				467	467
Hernando				215	215	215	439
Highlands	76	81		21	21	102	2421
Hillsborough	159	1293	138	634	772	2065	3708
Indian River		101		32	32	133	2753
Jackson		13		124	124	137	137
Jefferson		1		315	315	316	316
Lafayette				29	29	29	29
Lake	27	1004		1551	1551	2555	6309
Lee	14	698		25	25	723	771
Leon				29	29	29	29
Levy				481	481	481	481
Madison				161	161	161	161
Manatee	20	1442		4	4	1446	1535
Marion	92	557		1110	1110	1667	2494
Martin	81	226		24	24	250	250
Okeechobee		261		42	42	303	303
Orange	345	1764		83	83	1847	10306
Osceola							79
Palm Beach	2046	10479				10479	10546
Pasco				984	984	984	1393
Pinellas							1775
Polk		2	3	172	175	177	13540
Putnam	2	548		65	65	613	774
St. Johns	46	4203				4203	4203
St. Lucie	7	1202		25	25	1227	4589
Sarasota	116	1914		2	2	1916	2179
Seminole	421	5567				5567	6959
Sumter	58	356		835	835	1191	1191
Suwannee		7		481	481	488	488
Union		13		24	24	37	37
Volusia		73		16	16	89	737
Washington				1	1	1	1
Straight Cars	4968	42736	145	9834	9979	52715	97472
Pick-Up-Express	43	43				43	3946
Boat							22
GRAND TOTAL	5011	42779	145	9834	9979	52758	101440

TRUCK PASSINGS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS
BY WEEKS FOR 1950-51 SEASON (RAIL CARLOAD EQUIVALENT)
TRUCK ROAD GUARD STATIONS
AUGUST 1, 1950 - JULY 31, 1951

Date by Weeks	Beans	Lima Butter Beans	Cabbage	Cauliflo.	Celery	Gr. Corn	Cukes	Eggplant	Escarole	Field Peas	Lettuce	Okra	Peppers
Aug. 1-30	LCL	-	-	-	-	-	-	LCL	-	LCL	-	LCL	1
Sept.1-30	-	-	-	-	-	-	-	-	-	-	-	LCL	-
Oct. 1-14	LCL	-	-	-	-	-	30	LCL	-	1	-	3	-
Oct. 15-21	1	-	-	-	-	-	55	1	-	1	-	4	-
Oct. 22-28	1	-	-	-	-	2	85	3	-	1	-	4	-
Oct. 29-Nov.4	22	-	-	-	-	2	118	7	-	4	-	4	-
Nov. 5-11	41	-	-	-	-	2	132	5	LCL	4	LCL	2	1
Nov. 12-18	114	LCL	-	-	-	4	165	9	6	5-	-	1	2
Nov. 19-25	149	LCL	-	-	-	11	176	12	-	3	1	1	4
Nov. 26-Dec.2	89	LCL	1		23	10	102	13	13	2	1	1	6
Dec. 3-9	90	LCL	2	1	17	3	90	11	17	1	2	1	7
Dec. 10-16	126	2	5	LCL	52	10	62	16	21	LCL	11	LCL	8
Dec. 17-23	100	2	3	LCL	21	6	49	13	13	LCL	9	LCL	10
Dec. 24-30	119	1	11	2	39	1	38	19	14	LCL	12	LCL	12
Dec. 31-Jan.6	146	2	24	11	116	4	51	33	22	1	25	LCL	24
Jan. 7-13	147	1	27	16	132	7	31	22	29	LCL	31	LCL	27
Jan. 14-20	193	1	35	39	116	7	31	21	29	LCL	37	LCL	25
Jan. 21-27	210	3	78	47	168	13	44	24	32	1	51	LCL	45
Jan. 28-Feb.3	193	2	98	24	214	7	50	15	30	LCL	47	1	54
Feb. 4-10	251	2	131	21	234	9	35	12	32	LCL	68	LCL	30
Feb. 11-17	217	5	213	16	188	10	26	7	22	LCL	55	LCL	50
Feb. 18-24	316	3	254	21	180	15	42	7	19	1	35	LCL	72
Feb. 25-Mar.3	309	5	314	35	201	12	50	10	22	LCL	33	LCL	104
Mar. 4-10	347	12	400	35	220	25	40	10	31	LCL	30	LCL	107
Mar. 11-17	267	9	516	26	234	65	25	11	34	1	22	LCL	130
Mar. 18-24	313	12	581	11	235	72	14	14	28	1	27	LCL	127
Mar. 25-31	304	11	546	8	246	82	22	17	13	1	15	LCL	139
Apr. 1-7	409	14	597	9	199	158	62	21	21	3	11	LCL	135
Apr. 8-14	294	13	678	8	169	197	234	35	25	3	16	LCL	119
Apr. 15-21	299	14	482	7	181	231	396	48	14	4	12	1	123
Apr. 22-28	446	13	346	17	151	208	449	38	15	8	5	1	114
Apr. 29-May 5	305	9	257	3	130	276	306	31	11	17	4	4	122
May 6-12	217	21	154	LCL	125	287	341	31	5	43	1	5	105
May 13-19	91	55	69	LCL	164	241	309	36	9	125	2	9	138
May 20-26	27	50	28	-	137	253	307	50	4	123	-	15	127
May 27-June 2	14	52	17	-	79	241	147	41	2	121	-	17	121
June 3-9	7	47	7	-	81	247	48	25	1	117	-	16	106
June 10-16	3	18	3	-	75	127	8	33	-	37	-	13	93
June 17-23	LCL	4	1	-	16	37	1	33	-	9	-	13	44
June 24-30	-	2	-	-	1	7	1	42	-	1	-	11	13
July 1-14	-	LCL	-	-	LCL	LCL	LCL	36	-	1	-	12	5
July 15-31	-	LCL	-	-	LCL	-	LCL	6	-	2	-	6	1
Total by Weeks	6177	385	5878	357	4144	2889	4172	818	534	642	563	145	2351
Total by Mos.	6174	387	5874	357	4143	2885	4169	818	535	642	562	150	2354

(1) Passings were converted into carload equivalent on basis of: Beans 620 bu, Limas and B.B. 620 bu, Cabbage 500 pkgs, Cauliflower 400 pkgs, Celery 420 crts, Corn 500 pkgs, Cucumbers 450 bu, Eggplant 620 pkgs, Escarole 650 bu, Field Peas 620 bu, Lettuce 320 large and 700 small crts, Okra 620 bu, Peppers 700 bu, Potatoes 600 bu, Radish 1000 pkgs, Squash 600 pkgs, Tomatoes 400 bu, Bunched Vegetables 1000 doz. The Weekly Totals differ from, and are usually slightly higher than the Monthly Totals, due to fractional totals by weeks. Notes apply to opposite page and vice versa

TRUCK PASSINGS OF FLORIDA VEGETABLES AND NON-CITRUS FRUITS
BY WEEKS FOR 1950-51 SEASON (RAIL CARLOAD EQUIVALENT)
TRUCK ROAD GUARD STATIONS
AUGUST 1, 1950 - JULY 31, 1951

Date by Weeks	Potatoes	Radish	Squash	Tomatoes	Bun. Vegs.	Oth. Vegs.	Tot. Vegs.	Strber.	W-mel.	Avocados	Limes	Oth. Misc. Fru.	Grand Total
Aug. 1-30	-	-	-	-	-	4	5	-	LCL	30	12	-	47
Sept. 1-30	-	-	LCL	-	-	LCL	LCL	-	-	54	6	-	60
Oct. 1-14	-	-	1	2	-	LCL	37	-	-	34	1	-	72
Oct. 15-21	-	-	4	1	LCL	LCL	67	-	-	21	LCL	-	88
Oct. 22-28	-	-	1	20	LCL	LCL	117	-	-	17	LCL	-	134
Oct. 29-Nov. 4	-	-	11	93	-	1	262	-	-	19	1	-	282
Nov. 5-11	-	*	9	154	LCL	5	355	-	-	27	1	-	383
Nov. 12-18	-	*	21	169	3	12	511	-	-	28	1	-	540
Nov. 19-25	-	*	19	143	LCL	19	538	LCL	-	9	1	-	548
Nov. 26-Dec. 2	LCL	*	13	108	1	27	410	LCL	-	14	1	-	425
Dec. 3-9	1	*	11	103	3	33	393	LCL	-	29	2	-	424
Dec. 10-16	2	*	10	98	3	49	475	LCL	-	24	4	1	504
Dec. 17-23	3	*	14	63	4	52	362	LCL	-	14	4	9	389
Dec. 24-30	6	*	18	103	8	41	444	2	-	8	1	2	457
Dec. 31-Jan. 6	19	*	29	154	22	70	753	4	-	8	2	3	770
Jan. 7-13	39	*	25	156	17	76	783	18	-	12	2	2	817
Jan. 14-20	37	*	27	143	17	77	835	30	-	12	1	2	880
Jan. 21-27	39	9	35	129	13	122	1063	34	-	11	1	2	1111
Jan. 28-Feb. 3	39	27	38	120	15	71	1045	27	-	6	1	1	1080
Feb. 4-10	45	37	29	99	33	111	1179	18	-	5	1	4	1207
Feb. 11-17	62	39	34	145	38	109	1236	35	-	3	1	4	1279
Feb. 18-24	58	43	76	187	58	119	1506	71	-	1	1	2	1581
Feb. 25-Mar. 3	68	55	75	327	51	87	1758	86	-	1	1	1	1847
Mar. 4-10	97	48	88	386	43	64	1983	96	-	-	1	-	2080
Mar. 11-17	121	38	70	333	31	68	2001	55	-	LCL	1	1	2058
Mar. 18-24	154	37	85	371	29	61	2172	42	-	-	1	-	2215
Mar. 25-31	131	30	76	422	20	54	2137	22	-	-	1	-	2160
Apr. 1-7	125	29	95	402	22	34	2346	16	-	LCL	1	-	2363
Apr. 8-14	199	17	103	287	12	40	2449	8	-	-	1	-	2458
Apr. 15-21	318	7	111	519	7	22	2796	5	-	-	1	-	2802
Apr. 22-28	414	6	87	608	3	21	2950	7	2	LCL	1	-	2960
Apr. 29-May 5	441	3	61	660	1	17	2658	1	9	LCL	1	LCL	2669
May 6-12	544	1	48	805	1	14	2748	LCL	34	LCL	LCL	LCL	2782
May 13-19	520	-	28	768	LCL	7	2571	LCL	71	LCL	1	LCL	2643
May 20-26	467	LCL	17	771	LCL	4	2380	-	330	-	1	7	2718
May 27-June 2	136	LCL	8	556	LCL	4	1556	-	587	LCL	2	10	2155
June 3-9	6	-	4	275	-	2	989	-	1088	LCL	13	27	2117
June 10-16	2	-	3	89	-	LCL	504	-	1203	LCL	16	27	1750
June 17-23	2	-	1	14	-	1	176	-	1065	LCL	14	10	1265
June 24-30	LCL	-	LCL	4	-	-	82	-	747	2	24	17	872
July 1-14	5	-	LCL	1	-	1	61	-	249	14	35	5	364
July 15-31	3	-	LCL	1	-	1	20	-	24	36	43	3	126
Tot. by Weeks	4103	426	1385	9789	455	1500	46713	577	5409	439	204	140	53482
Tot. by Mos.	4101	425	1385	9790	454	1500	46705	577	5409	437	205	141	53474

( ) Converted into carload equivalent on basis of: Other Vegetables 600 pkgs, Strawberries 470 pkgs, Watermelons 1000 melons, Avocados 1200 pkgs, Limes 1200 pkgs. Miscellaneous Fruits: Cantaloupes 475 crts, Mangoes 1200 pkgs, Other Fruits 500 pkgs.

(3) The passings are thru Road Guard Stations and destined for out-of-State points. excepting some carloads to West Florida. Several carloads of West Florida vegetables going out of State were not included. Watermelons originating West of the Suwannee River Road Guard Station and going out of State amounting to 700 cars for June and 800 cars for July are not included in the above table.

(4) "Other Miscellaneous Fruits" included the following: Cantaloupes 91, Mangoes 15, Other Fruits 34 Carloads. Total 140 Carloads. (*) Any Radish passings were included with "Other Vegetables."

FLORIDA FOB PRICES 1909-1951

AVERAGES ON PACKED FRUIT--RAIL AND BOAT

(Florida Citrus Exchange Report)
Seasons 1909-10 to 1929-30

SEASONS	ORANGES	GRAPEFRUIT	TANGERINES	(Average) ALL CITRUS
1909-10	$1.15	$2.38	$1.81	$1.34
1910-11	1.51	1.95	2.60	1.65
1911-12	1.93	3.58	1.93	2.21
1912-13	1.97	2.01	1.92	1.96
1913-14	1.69	2.09	2.51	1.83
1914-15	1.47	1.32	1.66	1.42
1915-16	1.99	1.89	2.07	1.96
1916-17	1.94	2.07	2.82	2.01
1917-18	3.92	2.72	4.39	3.46
1918-19	3.69	3.18	4.79	3.52
1919-20	4.20	2.84	5.49	3.37
1920-21	2.57	2.46	4.96	2.65
1921-22	3.77	2.41	5.57	3.17
1922-23	2.96	2.10	4.39	2.62
1923-24	1.86	1.51	4.31	1.82
1924-25	3.51	1.94	4.43	2.74
1925-26	3.58	2.92	4.83	3.36
1926-27	2.78	2.25	3.50	2.58
1927-28	4.39	3.22	5.28	3.90
1928-29	1.99	2.07	2.91	2.09
1929-30	3.22	2.98	3.38	3.13

FLORIDA STATE MARKETING BUREAU AVERAGES

Seasons 1930-31 to 1950-51
(Comparable to above prices)
Gross f.o.b. Florida per Box

SEASONS	ORANGES	GRAPEFRUIT	TANGERINES	(Average) ALL CITRUS
1930-31	$2.15	$1.50	$1.95	$1.86
1931-32	2.30	1.50	2.05	1.95
1932-33	1.48	1.16	1.42	1.36
1933-34	1.71	1.51	1.80	1.65
1934-35	1.85	1.29	1.66	1.63
1935-36	2.30	1.87	2.00	2.14
1936-37	2.50	1.48	1.45	2.04
1937-38	1.56	1.53	1.86	1.57
1938-39	1.43	1.04	1.34	1.31
1939-40	1.62	1.42	2.00	1.60
1940-41	1.63	1.21	1.68	1.51
1941-42	2.10	1.80	2.85	2.06
1942-43	2.97	2.33	2.78	2.81
1943-44	3.10	2.47	3.70	3.01
1944-45	3.50	3.00	4.25	3.48
1945-46	3.55	2.65	4.80	3.44
1946-47*	2.62	2.18	3.75	2.59
1947-48*	2.10	1.80	2.90	2.08
1948-49*	2.80	2.35	3.70	2.74
1949-50*	3.55	3.41	3.85	3.54
1950-51*	3.12	2.73	4.35	3.06

* Rail, Boat and Truck prices, with truck f.o.b. price same as rail and boat.

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 10 YEARS

Records Estimates Season ALL ORANGES	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul, Shipped by Boat(1) Carloads	Total Rail&Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Processed in Florida Boxes	Estimated Consumed(2) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1941-42	41,598	40,443	1,155	16,853,616	4,099,200	4,197,299	2,049,885	27,200,000
1942-43	52,287	52,287	None	25,799,784	2,715,823	6,438,274	2,240,300	37,200,181
1943-44	61,160	61,160	None	30,511,378	2,155,200	11,010,841	2,522,581	46,200,000
1944-45	49,507	49,507	None	24,526,000	1,456,400	14,344,000	2,473,600	42,800,000
1945-46	52,665	52,589	76	26,007,841	2,054,000	19,219,412	2,518,747	49,800,000
1946-47	54,421	51,513	2,908	26,787,122	3,509,600	19,825,485	2,677,793	52,800,000
1947-48	39,616	39,616	-	19,659,370	5,707,300	30,376,340	2,656,990	58,400,000
1948-49	33,257	33,222	35	16,446,857	12,142,400	26,851,646	2,859,097	58,300,000
1949-50	22,304	19,213	3,091	10,710,718	10,283,515	34,657,323	2,848,444	58,500,000
1950-51	27,751	27,751	-	13,421,125	8,778,956	41,914,851	3,185,068	67,300,000

NOTES: (1) Domestic boat in coastwise trade.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

FLORIDA ORANGE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 10 YEARS

Records & Estimates Season ALL ORANGES	Cost of Production(2) Before Picked Per Box	Cost of Picking, Hauling, Packing Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return(1) Rail&Boat Shipments Net Value	Estimated Net Return All Oranges Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Oranges Harvested and Used Gross Value
1941-42	$0.44	$ .90	$2.10	$ .76	$12,808,748	$18,918,916	$35,392,593	$ 51,904,503
1942-43	.40	1.01	2.97	1.56	40,247,695	53,904,492	76,625,353	101,039,208
1943-44	.50	1.25	3.10	1.35	41,190,360	60,688,332	94,585,272	129,867,001
1944-45	.50	1.21	3.50	1.79	43,901,540	74,132,856	85,841,000	135,653,600
1945-46	.48	1.24	3.55	1.83	47,414,930	91,767,533	91,979,783	161,816,586
1946-47 *	.55 (3)	1.25	2.62	.84	25,320,348 RTB	26,385,969	76,975,370 RTB	101,927,124
1947-48 *	.50	1.32	2.10	.28	7,095,000 "	8,492,216	53,212,501 "	82,619,360
1948-49 *	.50	1.40	2.80	.90	25,730,332 "	45,510,967	80,049,920 "	127,743,648
1949-50 *	.52	1.38	3.55	1.65	34,640 484 "	88,387,669	74,529,527 "	166,271,393
1950-51 *	.57	1.40	3.12	1.15	25,530,093 "	62,825,443	69,264,253 "	153,526,275

NOTES: (*) Truck Shipments included with Rail & Boat, their FOB prices being same. (RTB) Rail, Truck, Boat.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau equivalent "On Tree" average price for rail & boat shipments. This not necessarily same as U.S.Dept.of Agri."On Tree" price.

(3) An allowance was made for unusual cost in grove protection in 1946-47 season. (February freeze.)

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 10 YEARS

Records Estimates Season GRAPE-FRUIT	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul Shipped By Boat(1) Carloads	Total Rail&Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Processed in Florida Boxes	Estimated Consumed(2) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1941-42	16,813	16,298	515	6,856,510	1,042,000	10,142,575	1,058,915	19,100,000
1942-43	16,529	16,529	None	8,009,134	612,807	17,584,025	1,094,150	27,300,116
1943-44	18,041	18,041	None	8,984,800	355,600	20,445,648	1,213,952	31,000,000
1944-45	11,742	11,742	None	5,860,000	205,200	15,136,000	1,098,800	22,300,000
1945-46	16,554	16,542	12	8,306,504	340,400	22,136,149	1,216,947	32,000,000
1946-47	17,800	16,363	1,437	8,878,857	558,000	15,864,346	1,098,797	26,400,000
1947-48	14,776	14,776	-	7,497,100	1,143,367	19,448,586	1,210,947	29,300,000
1948-49	17,738	17,738	-	8,826,811	3,483,200	16,305,820	1,584,169	30,200,000
1949-50	11,710	10,048	1,662	5,792,144	3,565,121	13,486,200	1,356,535	24,200,000
1950-51	18,109	18,109	-(1)	9,081,799	4,798,317	17,853,677	1,466,207	33,200,000

NOTES: (1) Domestic Boat Shipments in coast-wise trade. Exports of 22 cars 1950-51 not included.
(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

FLORIDA GRAPEFRUIT SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 10 YEARS

Records & Estimates Season GRAPE-FRUIT	Cost of Production(2) Before Picked Per Box	Cost of Picking Hauling Packing Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated Net Returns to Growers Rail&Boat Shipments Per Box	Estimated Net Return(1) Rail&Boat Shipments Net Value	Estimated Net Return All Grapefruit Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Grapefruit Harvested and Used Gross Value
1941-42	$ .40	$ .80	$1.80	$ .60	$ 4,113,906	$ 6,439,418	$12,341,718	$22,849,773
1942-43	.35	.88	2.33	1.10	8,810,047	18,156,816	18,661,282	40,527,501
1943-44	.40	1.07	2.47	1.00	8,984,800	28,461,544	22,192,456	56,780,588
1944-45	.40	1.07	3.00	1.53	8,965,800	30,343,516	17,580,000	49,962,240
1945-46	.34	1.10	2.65	1.21	10,039,012	24,983,418	21,986,266	56,604,216
1946-47*	.37(3)	1.08	2.18	.73	6,847,915 RTB	6,883,612	20,449,939 RTB	32,971,887
1947-48*	.35	1.09	1.80	.36	3,107,194 "	- 342,474	15,535,969 "	24,102,874
1948-49*	.35	1.18	2.35	.82	10,094,209 "	10,009,553	28,928,526 "	41,549,598(4)
1949-50*	.37	1.13	3.41	1.91	17,872,376 "	36,726,607	31,908,274 "	61,332,727
1950-51*	.43	1.18	2.73	1.12	15,545,730 "	18,469,555	37,892,717 "	57,849,066

NOTES: (*) Truck Shipments included with Rail & Boat, their FOB prices being same. (RTB) Rail, Truck, Boat.
(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting taxes and interest.
(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.
(3) An allowance was made for unusual cost in grove protection in 1946-47 season.
(4) Takes into account a loss of $1,304,466 on Grapefruit sold to processors.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 10 YEARS

Records Estimates Season TAN-GERINES	Total Carloads Rail&Boat Shipped Carloads	Portion Carloads Shipped by Rail Cars	With No. Rail Haul Shipped by Boat(1) Carloads	Total Rail and Boat Shipments Boxes	Estimated Trucked Out of Florida Boxes	Estimated Processed in Florida Boxes	Estimated Consumed(2) in Florida Boxes	Estimated Florida Production Utilized Total Boxes
1941-42	3,534	3,387	147	1,432,144	334,800	No Record	333,056	2,100,000
1942-43	7,382	7,382	None	3,407,401	400,048	of	392,700	4,200,149
1943-44	6,179	6,170	None	2,818,782	382,800	any.	398,418	3,600,000
1944-45	6,847	6,847	None	3,149,000	327,600	3,000	420,400	3,900,000
1945-46	5,728	5,728	None	2,809,372	384,000	515,600	491,028	4,200,000
1946-47	4,543	4,323	222	2,058,146	438,400	930,751	472,703	3,900,000
1947-48	3,610	3,610	-	1,699,815	667,845	598,505	433,835	3,400,000 A
1948-49	4,024	4,024	-	1,827,056	1,080,800	999,354	492,790	4,400,000
1949-50	3,321	2,912	409	1,500,955	1,376,592	1,594,928	527,525	5,000,000
1950-51	3,382	3,382	-	1,540,672	1,634,754	1,354,572	570,002	4,600,000 A

NOTES: (A) Does not include 600,000 boxes abandoned for marketing reasons. Abandonment, if any, for prior years not shown here. No abandonment of any citrus in 1948-49 season. 200,000 boxes abandoned 1950-51 not included.
(1) Domestic Boat Shipments in coast-wise trade.
(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intra-state truck shipments, etc.

FLORIDA TANGERINE SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 10 YEARS

Records & Estimates Season TAN-GERINES	Cost of Production(2) before Picked Per Box	Cost of Picking Hauling Packing Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated(1) Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return(1) Rail & Boat Shipments Net Value	Estimated Net Return All Tangerines Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Tangerines Harvested and Used Gross Value
1941-42	$0.58	$1.16	$2.85	$1.11	$1,589,680	$2,280,955	$ 4,081,610	$ 5,818,344
1942-43	.40	1.35	2.79	1.03	3,509,623	4,223,464	9,472,575	11,436,280
1943-44	.65	1.68	3.70	1.37	3,861,731	4,884,190	10,429,493	13,041,107
1944-45	.65	1.68	4.25	1.92	6,046,080	7,437,192	13,383,250	16,296,690
1945-46	.64	1.71	4.80	2.45	6,882,962	8,500,902	13,484,966	17,807,898
1946-47*	.68	1.72	3.75	1.35	3,370,337 RTB	3,522,030	9,362,048 RTB	11,565,569
1947-48*	.68	1.82	2.90	.40	947,064 "	696,420	6,866,214 "	8,203,662
1948-49*	.68	1.85	3.70	1.17	3,402,191 "	3,259,910	10,759,067 "	12,894,256(3)
1949-50*	.70	1.85	3.85	1.30	3,740,811 "	3,991,182	11,078,556 "	14,360,329(3)
1950-51*	.68	1.90	4.35	1.77	4,735,504 "	4,834,019	11,638,103 "	14,834,083(3)

NOTES: (*) Truck shipments included with Rail & Boat, their FOB prices being same. (RTB) Rail, Truck, Boat.
(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting for taxes and interest.
(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated. This estimated "On Tree" price is not necessarily the same as the U.S.Dept.of Agri. "On Tree" price.
(3) Takes into account a loss of $669,567 on tangerines to processors in 1948-49 and $366,233 in 1949-50, and 853,380 boxes in 1950-51.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 24 YEARS

Records Estimates Season	Total Carloads Rail&Boat Shipped	Portion Carloads Shipped by Rail	With No. Rail Haul Shipped by Boat(1)	Total Rail&Boat Shipments	Estimated Trucked Out of Florida	Estimated Processed in Florida	Estimated Consumed(2) in Florida	Estimated Florida Production Utilized
ALL CITRUS	Carloads	Cars	Carloads	Boxes	Boxes	Boxes	Boxes	Total Boxes
1927-28	37,876	37,680	196	13,635,360	800,000	600,000	1,000,000	16,035,360
1928-29	63,673	62,996	677	22,922,280	1,500,000	1,527,320	1,950,000	27,899,600
1929-30(3)	39,485	39,231	254	14,214,600	100,000	1,710,000	1,200,000	17,224,600
1930-31	74,645	72,949	1,696	27,229,945	2,640,000	2,954,056	2,180,970	35,004,971
1931-32	49,235	44,996	4,239	18,914,165	2,525,520	966,533	2,040,000	24,446,218
1932-33	55,501	44,456	11,045	20,176,750	3,010,180	2,800,000	2,422,700	28,409,630
1933-34	53,311	32,288	21,023	20,884,890	3,249,000	2,667,397	2,475,000	29,276,287
1934-35	51,107	27,460	23,647	20,132,561	4,346,360	5,781,933	2,575,000	32,835,854
1935-36	48,916	28,790	20,126	19,232,052	3,770,000	3,900,000	2,560,000	29,462,052
1936-37	66,879	43,570	23,309	26,221,696	4,274,000	7,305,512	2,800,000	40,601,208
1937-38	67,409	45,867	21,542	26,317,533	4,973,600	6,848,496	2,800,000	40,939,629
1938-39	87,067	58,933	28,134	33,927,076	7,126,559	9,582,037	3,300,000	56,447,995
1939-40	55,310	41,761	13,549	21,449,504	5,813,200	12,970,408	2,740,000	42,973,112
1940-41	67,072	49,329	17,743	26,358,127	7,720,400	17,812,227	4,000,000	55,890,754
1941-42	61,945	60,128	1,817	25,142,270	5,476,000	14,339,874	3,441,856	48,400,000
1942-43	76,198	76,198	None	37,216,319	3,728,678	24,022,299	3,733,150	68,700,446
1943-44	85,380	85,380	None	42,314,960	2,893,600	31,456,489	4,134,951	80,800,000
1944-45	68,096	68,096	None	33,535,000	1,989,200	29,483,000	3,992,800	69,000,000
1945-46	74,947	74,859	88	39,902,117	2,778,400	41,871,161	4,226,722	86,000,000
1946-47	76,766	72,199	4,567	37,724,125	4,506,000	36,620,582	4,249,293	83,100,000
1947-48	58,002	58,002	-	28,772,771	7,518,512	50,423,431	4,301,772	91,100,000
1948-49	55,019	54,984	35	27,100,724	16,706,400	44,156,820	4,936,056	92,900,000
1949-50	37,335	32,173	5,162	18,003,817	15,225,228	49,738,451	4,732,504	87,700,000
1950-51	49,242	49,242	-(1)	24,043,596	14,712,027	61,123,100	5,221,277	105,100,000

NOTES:

(1) Domestic Boat Shipments in Coastwise Trade. Export 22 cars 1950-51 not included.

(2) Figures for "Consumed in Florida" stock are rough estimates based on supply, price, population, intrastate truck shipments, etc.

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA TOTAL CITRUS SHIPMENTS, VALUATIONS, AND OTHER DATA FOR 24 YEARS

Records & Estimates Season ALL CITRUS	Cost of Production(2) before Picked Per box	Cost of Picking, Hauling, Packing, Selling Per Box	Estimated Gross FOB Returns Florida Points Per Box	Estimated Net Returns to Growers Rail & Boat Shipments Per Box	Estimated Net Return(1) Rail&Boat Shipments Net Value	Estimated Net Return All Citrus Harvested and Used Net Value	Estimated Gross FOB Returns Rail&Boat Shipments Gross Value	Estimated Gross Return All Citrus Harvested and Used Gross Value
1927-28	$0.63	$1.28	$3.74	$1.83	$24,964,592	$ 26,980,492	$ 50,958,663	$ 54,714,563
1928-29	.64	1.25	2.08	.19	4,361,670	5,698,063	47,405,291	52,217,851
1929-30(3)	.71	1.29	5.19	1.19	16,942,604	18,320,604	45,399,313	49,097,313
1930-31	.43	1.10	1.86	.33	8,920,948	10,037,572	50,569,525	56,293,572
1931-32	.53	.92	1.95	.50	9,442,872	10,943,166	36,948,353	42,691,957
1932-33	.45	.90	1.36	.01½	309,774	562,466	27,465,441	32,616,451
1933-34	.44	.87	1.65	.33½	7,022,613	10,009,011	34,451,906	42,401,191
1934-35	.43	.88	1.63	.32	6,387,160	8,855,935	32,724,487	42,797,752
1935-36	.44	.94	2.14	.76	14,717,619	20,211,899	41,206,791	53,189,191
1936-37	.37	.92	2.04	.75	19,583,547	24,579,298	53,611,677	68,838,758
1937-38	.38	.88	1.57	.30½	8,020,166	8,988,419	41,370,281	53,285,352
1938-39	.34	.82	1.31	.15	5,228,990	3,693,314	44,446,374	58,646,931
1939-40	.42	.90	1.60	.28	6,003,437	5,014,792	34,341,712	50,365,127
1940-41	.39	.85	1.51	.27	7,113,479	8,831,633	39,711,619	64,192,695
1941-42	.43	.89	2.06	.74	18,512,334	27,639,289	51,815,921	80,572,620
1942-43	.39	1.01	2.81	1.41	52,567,333	76,284,772	104,759,215	153,052,989
1943-44	.49	1.24	3.01	1.28	54,036,891	94,032,066	127,207,221	199,688,696
1944-45	.483	1.25	3.483	1.75	58,913,420	111,913,564	116,804,250	201,912,530
1945-46	.46	1.25	3.44	1.73	64,336,904	125,551,850	127,451,035	236,230,700
1946-47*	.50	1.24	2.59	.85	35,538,600 RTB	36,791,631	108,787,717 RTB	146,565,580
1947-48*	.48	1.29	2.08	.31	11,149,258 "	8,846,162	75,614,684 "	114,925,896
1948-49*	.47	1.37	2.74	.90	39,226,732 "	58,780,430	119,737,513 "	182,187,502
1949-50*	.49	1.35	3.54	1.70	56,253,671 "	129,105,458	117,516,357 "	241,964,455
1950-51*	.53	1.35	3.06	1.18	45,811,327 "	86,129,017	118,795,073 "	229,259,424

NOTES:

(*) Truck Shipments included with Rail & Boat, their FOB prices being the same. See RTB.

(1) Net return after deducting for cost of production which includes fertilizer, spray materials, irrigation, pruning, fuel, labor, etc., but before deducting for taxes and interest.

(2) Cost of production figures added to net returns to grower will show the Marketing Bureau "On Tree" average price for rail and boat shipments. The speculator's profit or loss is not calculated.

(3) Fruit fly year when production, harvest and shipments restricted.

FLORIDA AUCTION SALES, 1942-43 - 1950-51

Furnished through courtesy of the Statistical Department
Florida Citrus Exchange, Tampa, Florida

Season		N. Y.	PHILA.	BOST.	PITTS.	CLEVE.	CHIC.	ST.L.	CINCI.	DETR.	BALT.	TOTAL
					ORANGES							
1942-43	Cars	6771	2330	851	439	483	939	359	742	412	277	13603
	Average	$3.85	3.70	3.82	3.72	3.85	3.77	3.70	3.55	3.87	3.56	3.79
1943-44	Cars	6239	2257	678	522	488	815	476	516	658	200	12849
	Average	$3.98	3.82	4.02	3.86	3.86	3.89	3.67	3.65	3.85	3.71	3.90
1944-45	Cars	4765	1651	425	293	264	532	271	299	365	157	9022
	Average	$4.62	4.38	4.47	4.27	4.34	4.29	4.17	4.02	4.37	4.39	4.48
1945-46	Cars	4510	1478	363	237	197	345	196	372	262	308	8268
	Average	$4.72	4.44	4.70	4.48	4.43	4.39	4.24	4.17	4.43	4.45	4.58
1946-47	Cars	7824	1930	870	420	639	921	430	801	562	373	14770
	Average	$3.60	3.35	3.62	3.29	3.47	3.38	3.27	3.25	3.47	3.35	3.50
1947-48	Cars	6356	2550	867	342	534	608	249	689	479	234	13406
	Average	$3.40	3.16	3.34	3.12	3.19	3.08	2.91	3.01	3.12	2.96	3.27
1948-49	Cars	6512	2377	772	393	544	818	416	571	593	137	13133
	Average	$4.35	4.04	4.35	4.17	4.17	4.14	4.10	3.86	4.23	3.96	4.23
1949-50	Cars	5364	1727	516	244	401	635	278	421	448	31	10065
	Average	$5.10	4.85	5.10	4.65	4.78	4.71	4.44	4.46	4.85	4.23	4.95
1950-51*	Cars	5920	1972	560	363	530	699	322	542	648	132	11638
	Average	$4.49	4.40	4.47	4.23	4.28	4.18	4.02	4.08	4.26	4.10	4.39
					GRAPEFRUIT							
1942-43	Cars	3411	967	487	142	96	114	19	201	85	82	5604
	Average	$3.18	2.97	3.21	2.90	2.90	3.17	2.96	2.67	3.00	2.70	3.10
1943-44	Cars	2628	778	338	128	49	69	44	90	97	43	4264
	Average	$3.63	3.48	3.64	3.36	3.32	3.20	3.51	3.05	3.31	3.14	3.56
1944-45	Cars	2320	498	183	31	23	21	13	16	13	14	3132
	Average	$4.35	4.03	4.11	3.74	3.01	3.31	3.38	3.13	3.15	3.54	4.24
1945-46	Cars	3293	737	213	33	12	19	2	18	14	45	4386
	Average	$3.88	3.67	3.88	3.06	2.60	3.62	3.33	2.91	2.81	3.19	3.82
1946-47	Cars	4894	890	546	63	80	154	31	183	111	142	7094
	Average	$3.39	3.11	3.17	2.89	3.10	3.16	3.55	2.87	3.18	2.54	3.29
1947-48	Cars	4258	1260	456	73	85	106	34	158	92	138	6660
	Average	$3.22	2.82	2.89	2.55	2.99	2.92	2.97	2.54	3.03	2.31	3.07
1948-49	Cars	4406	1287	464	158	222	355	168	237	308	36	7641
	Average	$3.87	3.58	3.72	3.49	3.86	3.68	3.71	3.33	3.80	2.82	3.77
1949-50	Cars	3387	923	237	106	189	324	120	223	245	18	5772
	Average	$5.38	4.75	4.86	4.54	4.97	4.66	4.32	4.56	4.77	3.54	5.10
1950-51	Cars	4673	1323	356	301	379	681	292	461	579	60	9105
	Average	$4.33	3.92	4.06	3.41	3.75	3.94	3.26	3.48	3.68	3.00	4.05
					TANGERINES (1/2 box basis)							
1942-43	Cars	1485	670	143	108	188	303	101	193	151	57	3399
	Average	$1.82	1.84	1.62	1.81	1.86	1.81	1.66	1.80	1.74	1.53	1.80
1943-44	Cars	326	134	22	22	22	40	26	21	31	-	644
	Average	$2.16	2.28	2.27	2.32	2.37	2.27	2.36	2.26	2.40	-	2.23
1944-45	Cars	669	300	32	72	66	150	41	53	73	9	1465
	Average	$2.42	2.38	2.35	2.49	2.45	2.42	2.15	2.40	2.47	2.77	2.41
1945-46	Cars	1188	414	57	70	86	167	46	88	59	26	2201
	Average	$2.67	2.52	2.43	2.53	2.68	2.54	2.32	2.59	2.50	2.60	2.61
1946-47	Cars	1233	335	69	91	139	202	63	128	108	35	2403
	Average	$2.28	2.18	2.11	2.12	1.99	1.90	1.92	1.99	2.04	2.08	2.17
1947-48	Cars	943	433	69	77	147	193	63	120	140	24	2209
	Average	$2.09	2.01	1.87	1.81	1.86	1.91	1.70	1.81	1.73	1.92	1.98
1948-49	Cars	1345	516	86	79	132	230	65	108	163	13	2737
	Average	$2.75	2.48	2.51	2.36	2.39	2.24	2.24	2.09	2.36	1.96	2.55
1949-50	Cars	1279	452	51	71	140	248	53	78	171	7	2550
	Average	$2.74	2.62	2.53	2.48	2.62	2.44	2.32	2.30	2.51	2.60	2.63
1950-51	Cars	1056	382	47	92	146	232	64	90	182	17	2308
	Average	$2.66	2.59	2.23	2.33	2.53	2.50	2.32	2.31	2.50	2.02	2.56

*Temple Oranges included.

ESTIMATED COSTS FROM TREE TO AUCTIONS
1948-49, 1949-50 AND 1950-51 SEASONS
(Private Sales not included)

ORANGES	1948-49	1949-50	1950-51	1948-49	1949-50	1950-51
Carloads Sold				13,133	10,065	11,688
Auction Sales at Terminal Markets				$ 4.23	$ 4.95	$ 4.37
Terminal Selling & Expenses				.07	.07	.06
Net at Terminal				4.16	4.88	4.31
Transportation Cost				1.13	1.08	1.14
Florida F.O.B. Equivalent				$ 3.03	$ 3.80	$ 3.17
Florida Marketing Charges	.08	.08	.08	$ 1.36	$ 1.39	1.41
Advertising & Inspection	.04	.04	.05			
Packing & Processing	.89	.91	.90			
Picking, Loading & Hauling	.35	.36	.38			
On Tree Equivalent				$ 1.67	$ 2.41	$ 1.76
Estimated Production Costs				.56	.58	.5[illegible]
Net to Grower before Interest, Taxes & Depreciation				$ 1.11	1.83	1.1[illegible]

GRAPEFRUIT						
Carloads Sold				7,641	6,190	9,105
Auction Sales at Terminal Markets				$ 3.77	$ 5.04	$ 4.04
Terminal Selling & Expenses				.06	.06	.06
Net at Terminal				3.71	4.98	3.98
Transportation Cost				1.06	1.04	1.14
Florida F.O.B. Equivalent				$ 2.65	$ 3.94	$ 2.84
Florida Marketing Charges	.08	.08	.08	1.10	1.12	1.19
Advertising & Inspection	.05	.05	.06			
Packing & Processing	.72	.74	.75			
Picking, Loading & Hauling	.25	.25	.30			
On Tree Equivalent				$ 1.55	2.82	1.65
Estimated Production Costs				.38	.40	.44
Net to Grower before Interest, Taxes & Depreciation				$ 1.17	$ 2.42	$ 1.21

TANGERINES						
Carloads Sold				2,737	2,550	2,302
Auction Sales at Terminal Markets				$ 5.10	$ 5.25	$ 5.12
Terminal Selling & Expenses				.08	.07	.08
Net at Terminal				5.02	5.18	5.04
Transportation Cost				1.12	1.08	1.13
Florida F.O.B. Equivalent				$ 3.90	$ 4.10	$ 3.91
Florida Marketing Charges	.08	.08	.08	$ 1.83	$ 1.87	1.93
Advertising & Inspection	.07	.07	.08			
Packing & Processing	1.22	1.24	1.27			
Picking, Loading & Hauling	.46	.48	.50			
On Tree Equivalent				$ 2.07	$ 2.23	$ 1.98
Estimated Production Costs				.68	.70	.70
Net to Grower before Interest, Taxes & Depreciation				$ 1.39	$ 1.53	$ 1.28

Percentage of all freight, express, boat and truck shipments sold at auction:

	Oranges			Grapefruit			Tangerines		
	RRT	AUCTION	% AUCTION	RRT	AUCTION	% AUCTION	RRT	AUCTION	% AUCTION
	Carloads			Carloads			Carloads		
1940-41	52,386	18,971	.36	21,515	8,823	.41	4,321	2,717	.62
1941-42	45,775	17,133	.37	15,769	7,325	.46	2,849	2,085	.73
1942-43	50,180	13,613	.27	13,790	5,604	.40	5,917	3,308	.56
1943-44	56,793	12,349	.22	14,330	4,264	.29	4,813	644	.13
1944-45	44,690	9,022	.20	9,047	3,132	.34	5,169	1,465	.27
1945-46	47,059	8,263	.17	13,064	4,366	.33	4,773	2,201	.46
1946-47	55,072	14,770	.26	15,438	7,094	.42	4,292	2,403	.55
1947-48	47,792	13,406	.28	14,652	6,660	.45	4,554	2,209	.48
1948-49	56,294	13,133	.23	22,534	7,641	.33	6,625	2,737	.43
1949-50	42,871	10,065	.23	18,540	5,772	.30	7,074	2,550	.33
1950-51	45,677	11,688	.25	20,305	9,105	.32	6,134	2,302	.37

NOTE: The above figures on estimated costs from tree to auction for 1950-51 season were compiled by the Florida Citrus Mutual Statistical Department from various reports from reliable packing houses, growers and caretakers who represent a fair cross section of the industry. The above costs are their ideas as to costs for the industry and do not necessarily represent the ideas of everyone in the industry.

The State Marketing Bureau takes note of the reports which say that the quality of the citrus fruit going to the auction markets is higher than the State average.

CITRUS PRICE ANALYSIS 1934-35 TO 1950-51

	FLORIDA GROSS FOB MARKET OR EQUIVALENT PER BOX						EQUIV.	NET* TO GROWER		COST	PICKING
	BOX YIELD	RAIL AND BOAT	TRUCKED OUT	FLORIDA CONSUMED	FLORIDA PROCESSED	GROSS ALL	ON TREE ALL	NET ALL	RAIL AND BOAT	PRODUCTION	PACKING MARKETING RAIL&BOAT (Costs)
ORANGES											
1934-35	15,529,059	$1.85	$1.35	$1.25	$ .80	$1.69	$ .98	$ .53	$ .50	$ .45	$ .90
1935-36	15,864,583	2.30	1.60	1.50	1.00	2.10	1.33	.38	.90	.45	.95
1936-37	19,460,786	2.50	1.90	1.70	1.25	2.31	1.48	1.06	1.15	.42	.93
1937-38	24,302,896	1.56	1.12	1.12	.36	1.41	.63	.25	.30	.38	.88
1938-39	30,015,287	1.43	1.15	1.15	.41	1.32	.54	.20	.25	.34	.84
1939-40	25,064,702	1.62	1.52	1.32	.19	1.37	.59	.17	.29	.42	.91
1940-41	28,752,089	1.63	1.58	1.28	.80	1.46	.72	.32	.36	.40	.87
1941-42	27,200,000	2.10	2.05	1.70	1.08	1.91	1.13	.69	.76	.44	.90
1942-43	37,200,181	2.97	2.91	2.50	1.70	2.72	1.85	1.45	1.56	.40	1.01
1943-44	46,200,000	3.10	3.10	2.60	2.02	2.81	1.81	1.31	1.35	.50	1.25
1944-45	42,800,000	3.50	3.50	3.00	2.60	3.17	2.23	1.73	1.79	.50	1.21
1945-46	49,800,000	3.55	3.55	3.10	2.83	3.25	2.32	1.84	1.83	.48	1.24
1946-47	52,800,000	2.62	2.62	2.35	.82	1.93	1.03	.50	.84**	.53	1.25
1947-48	58,400,000	2.10	2.10	1.90	.80	1.41	.65	.15	.28**	.50	1.32
1948-49	58,300,000	2.80	2.80	2.50	1.51	2.19	1.29	.79	.90**	.50	1.40
1949-50	58,500,000	3.55	3.55	3.25	2.38	2.84	2.03	1.51	1.65**	.52	1.38
1950-51	67,300,000	3.12	3.12	2.92	1.86	2.33	1.39	.82	1.15**	.57	1.40
GRAPEFRUIT											
1934-35	15,243,060	$1.29	$ .80	$ .70	$ .37	$ .88	$ .38	$ .01	$ .08	$ .37	$ .84
1935-36	11,504,067	1.87	1.20	1.10	.73	1.39	.85	.46	.61	.39	.87
1936-37	18,121,786	1.48	1.10	1.00	.55	1.09	.55	.25	.35	.30	.83
1937-38	14,378,760	1.53	1.10	1.10	.48	1.05	.54	.18	.35	.36	.82
1938-39	23,050,835	1.04	.80	.80	.22	.64	.21	-.09	-	.30	.74
1939-40	15,650,865	1.42	1.30	1.12	.33	.79	.39	-.01	.20	.40	.82
1940-41	24,387,041	1.21	1.10	.86	.37	.71	.33	-.02	.12	.35	.74
1941-42	19,100,000	1.80	1.70	1.45	.71	1.20	.74	.34	.60	.40	.80
1942-43	27,300,116	2.33	2.25	1.85	1.05	1.48	1.02	.67	1.10	.35	.88
1943-44	31,000,000	2.47	2.47	2.00	1.53	1.83	1.32	.92	1.00	.40	1.07
1944-45	22,300,000	3.00	3.00	2.60	1.91	2.24	1.76	1.36	1.53	.40	1.07
1945-46	32,000,000	2.65	2.65	2.40	1.39	1.77	1.12	.78	1.21	.34	1.10
1946-47	26,400,000	2.18	2.18	1.90	.65	1.25	.63	.26	.73**	.37	1.08
1947-48	29,300,000	1.80	1.80	1.60	.54	.82	.34	-.01	.36**	.35	1.09
1948-49	30,200,000	2.35	2.35	2.10	.57	1.38	.68	.33	.82**	.35	1.16
1949-50	24,200,000	3.41	3.41	3.10	1.87	2.53	1.89	1.52	1.91**	.37	1.13
1950-51	33,200,000	2.73	2.73	2.55	.91	1.74	.99	.56	1.12**	.43	1.18

*Net to grower (or fruit owner) indicates the amount per box after deducting production and all other costs except interest, taxes and depreciation. The State Marketing Bureau "On Tree" average price may be obtained by adding Production Costs to "Net to Grower" return for All Fruit. **Includes Truck Shipments.

CITRUS PRICE ANALYSIS 1934-35 TO 1950-51

	FLORIDA GROSS FOR MARKET OR EQUIVALENT PER BOX						EQUIV.	NET* TO GROWER		COST	PICKING PACKING
	BOX YIELD	RAIL AND BOAT	TRUCKED OUT	FLORIDA CONSUMED	FLORIDA PROCESSED	GROSS ALL	ON TREE ALL	NET ALL	RAIL AND BOAT	PRODUCTION	MARKETING RAIL&BOAT (Costs)
TANGERINES											
1934-35	2,003,755	$1.66	$1.15	$1.10	$ -	$1.51	$ .76	$ .21	$ .16	$ .55	$ .95
1935-36	2,093,397	2.00	1.50	1.40	-	1.86	.97	.42	.35	.55	1.10
1936-37	3,018,634	1.45	1.15	1.05	-	1.37	.32	-.18	-.20	.50	1.15
1937-38	2,257,973	1.86	1.28	1.28	-	1.72	.66	.14	.18	.52	1.16
1938-39	3,381,873	1.34	1.05	1.05	-	1.27	.38	-.07	-.06	.45	.95
1939-40	2,257,545	2.00	1.90	1.70	-	1.95	.92	.42	.44	.50	1.06
1940-41	2,751,624	1.68	1.65	1.31	-	1.60	.58	.08	.10	.50	1.08
1941-42	2,100,000	2.85	2.80	2.40	-	2.77	1.67	1.09	1.11	.58	1.16
1942-43	4,200,149	2.78	2.70	2.25	-	2.72	1.38	.98	1.03	.40	1.35
1943-44	3,600,000	3.70	3.70	3.00	-	3.62	2.01	1.36	1.37	.65	1.68
1944-45	3,900,000	4.25	4.25	3.60	-	4.18	2.56	1.91	1.92	.65	1.68
1945-46	4,200,000	4.80	4.80	4.00	1.00	4.24	2.74	2.10	2.45	.64	1.71
1946-47	3,900,000	3.75	3.75	3.30	.80	2.99	1.58	.90	1.35**	.68	1.72
1947-48	3,400,000	2.90	2.90	2.60	.35	2.41	.88	.20	.40**	.68	1.82
1948-49	4,400,000	3.70	3.70	3.40	.46	2.93	1.42	.74	1.17**	.68	1.85
1949-50	5,000,000	3.85	3.85	3.50	.90	2.87	1.50	;80	1.30**	.70	1.85
1950-51	4,800,000	4.35	4.35	4.15	.65	3.24	1.73	1.05	1.77**	.68	1.90
TOTAL CITRUS (And Average of All Citrus)											
1934-35	32,835,854	$1.63	$1.19	$1.05	$ .38	$1.33	$ .70	$ .27	$ .32	$ .43	$ .88
1935-36	29,462,052	2.14	1.48	1.37	.74	1.81	1.13	.69	.76	.44	.94
1936-37	40,601,208	2.04	1.58	1.43	.61	1.70	.98	.61	.75	.37	.92
1937-38	40,939,629	1.57	1.12	1.13	.46	1.30	.60	.22	.305	.38	.88
1938-39	56,447,995	1.31	1.07	1.04	.24	1.04	.41	.07	.15	.34	.82
1939-40	42,973,112	1.60	1.51	1.29	.28	1.17	.54	.12	.28	.42	.90
1940-41	55,890,754	1.51	1.49	1.18	.47	1.15	.55	.16	.27	.39	.85
1941-42	48,400,000	2.06	2.05	1.69	.83	1.66	1.00	.57	.74	.43	.89
1942-43	68,700,000	2.81	2.78	2.28	1.22	2.23	1.50	1.11	1.41	.39	1.01
1943-44	80,800,000	3.01	3.10	2.37	1.70	2.47	1.65	1.16	1.28	.49	1.24
1944-45	69,000,000	3.48	3.57	2.95	2.25	2.93	2.10	1.62	1.75	.48	1.25
1945-46	86,000,000	3.44	3.61	3.00	2.05	2.75	1.92	1.46	1.73	.46	1.25
1946-47	83,100,000	2.59	2.67	2.21	.75	1.76	.94	.44	.85**	.50	1.24
1947-48	91,100,000	2.08	2.13	1.89	.62	1.26	.58	.10	.31**	.48	1.29
1948-49	92,900,000	2.74	2.77	2.46	1.14	1.96	1.10	.63	.90**	.47	1.37
1949-50	87,700,000	3.54	3.54	3.24	2.19	2.76	1.96	1.47	1.70**	.49	1.35
1950-51	105,300,000	3.06	3.06	2.94	1.57	2.18	1.35	.82	1.18**	.53	1.35

*Net to grower (or fruit owner) indicates the amount per box after deducting production and all other costs except interest, taxes and depreciation. The State Marketing Bureau "On Tree" average price may be obtained by adding Production Costs to "Net to Grower" return for All Fruit. **Includes Truck Shipments.

INSPECTIONS OF FLORIDA CITRUS FOR SHIPMENT
BY RAIL AND TRUCK BY COUNTIES
SEASON AUGUST 1, 1950 - JULY 31, 1951

County	Grapefruit	Oranges	Tangerines	Total 1950-51	Total 1949-50	Total 1948-49
	(Boxes 1-3/5 Bushels)					
Alachua	2,989	35,123	1,138	39,250	69,756	59,503
Brevard	388,488	684,321	6,129	1,078,938	1,310,459	1,079,605
Citrus	4,414	36,748	1,154	42,316	39,213	39,150
Dade	10,723	35,324	-	46,047	68,909	113,520
DeSoto	40,658	500,432	45,754	586,844	425,672	675,856
Duval	92,724	387,946	59,773	540,443	582,548	657,025
Hardee	4,662	26,207	4,064	34,933	17,564	70,765
Hernando	35,010	80,948	57,856	173,814	240,254	316,485
Highlands	634,950	1,059,341	53,649	1,747,940	1,332,270	1,922,936
Hillsborough	391,791	841,438	93,683	1,326,912	1,020,914	1,626,964
Indian River	1,129,737	347,829	9,226	1,486,792	991,829	1,479,923
Lake	896,569	2,406,690	326,995	3,630,254	3,786,397	3,861,089
Lee	17,328	17,718	-	35,046	93,103	58,506
Manatee	25,987	10,594	-	36,581	48,820	165,017
Marion	114,624	669,767	14,370	798,761	1,165,539	1,541,805
Orange	1,454,905	4,921,648	727,708	7,104,261	7,265,904	8,153,109
Osceola	38.511	160,662	37,463	236,636	200,809	368,104
Palm Beach	37,761	68,426	6,253	112,440	227	125,121
Pasco	79,560	177,731	24,606	281,897	319,933	395,492
Pinellas	1,180,688	202,901	30,206	1,413,795	1,407,245	1,617,236
Polk	5,719,921	5,968,768	797,421	12,486,110	8,585,350	14,763,663
Putnam	4,886	112,348	29,215	146,449	218,990	237,025
St. Johns	6	19,998	-	20,004	26,756	16,357
St. Lucie	956,664	920,172	29,665	1,906,501	469,134	1,719,438
Sarasota	93,567	33,665	-	127,232	105,754	1,289
Seminole	307,247	1,301,887	169,407	1,778,541	1,697,161	1,788,017
Volusia	73,447	428,627	166,456	668,530	1,037,524	839,469
Others	1,323	17,235	423	18,981	18,090	2,442
TOTAL ABOVE	13,739,140	21,474,494	2,692,614	37,906,248	32,546,124	43,707,235
TOTAL CROP	33,200,000	67,300,000	4,800,000	105,300,000	87,700,000	92,900,000

NOTE: Some commodities are produced in one county and inspected in another county. These inspections do not include fruit for processing and some other classes of fruit

CITRUS TRUCKED THROUGH ROAD GUARD STATIONS-AUGUST 1-JULY 31, 1950-51

Tabulated from Records of Citrus & Vegetable Inspection Division, Winter Haven, Fla.

GROUP 1	HIGHWAY	ORANGES	GRAPEFRUIT	TANGERINES	TOTAL CITRUS
Wilcox	U.S. 19	2,509,518	1,464,399	251,263	4,225,180
Luraville	Fla. 51	633	168	38	839
Branford	Fla. 20	56,758	35,073	5,639	97,470
Ellaville	U.S. 90	186,850	91,556	23,483	301,889
Suwannee Springs	U.S. 129	8,410	4,693	2,012	15,115
White Springs	U.S. 41	1,195,246	645,261	151,483	1,991,990
Lake City	Fla. 47	24,139	11,992	4,612	40,743
GROUP 2					
Hilliard	U.S. 1	1,814,642	1,049,726	236,730	3,101,098
Yulee	U.S. 17	2,839,097	1,449,635	446,210	4,734,942
TOTAL ALL STATIONS		8,635,293	4,752,503	1,121,470	14,509,266

Group 1 Stations at bridges over Suwannee River; Group 2 at bridges over St. Marys Ri.

TOTAL ALL STATIONS

DATE	ORANGES	GRAPEFRUIT	TANGERINES	TOTAL CITRUS
August - - - - - - - - - - - - - - -	3,049	20,274	-	23,323
September- - - - - - - - - - - - - -	11,520	328,060	96	339,676
October- - - - - - - - - - - - - - -	753,120	657,815	51	1,410,986
November - - - - - - - - - - - - - -	1,338,035	562,387	103,519	2,003,941
December - - - - - - - - - - - - - -	1,490,109	396,593	486,290	2,372,992
January - - - - - - - - - - - - - -	1,015,579	484,523	341,812	1,841,914
February - - - - - - - - - - - - - -	1,082,306	584,273	164,569	1,831,148
March - - - - - - - - - - - - - - -	1,034,711	673,669	18,678	1,727,058
April - - - - - - - - - - - - - - -	775,099	491,152	4,975	1,271,226
May - - - - - - - - - - - - - - -	657,604	351,087	1,392	1,010,083
June - - - - - - - - - - - - - - -	381,796	170,533	88	552,417
July - - - - - - - - - - - - - - -	92,365	32,137	-	124,502
TOTAL AUGUST 1-JULY 31	8,635,293	4,752,503	1,121,470	14,509,266
CARLOADS (500 Boxes)	17,271	9,505	2,243	29,019

NOTE: The above Road Guard Stations also report on vegetables and miscellaneous fruits.

PRODUCTION AND VALUE OF AVOCADOS AND LIMES 1930-1951

	AVOCADOS					LIMES (Persian Type)			Avocados & PersianLimes Combined Gross FOB Value
	Crop Volume Tons	Bu. 50 Lbs.	Value Ton	Value Bu.	Gross FOB Value	Crop Volume 1-3/5 bu. Boxes	Value Box	Gross FOB Value	
1930	620	24,800	$192	$4.80	$119,040	$ 8,000	$4.00	$ 32,000	$ 151,040
1931	520	32,300	145	3.63	118,900	9,000	3.50	31,500	150,400
1932	1400	56,000	88	2.20	123,200	10,000	3.00	30,000	153,200
1933	2200	88,000	98	2.45	215,600	12,000	2.50	30,000	245,600
1934	2000	80,000	75	1.88	150,000	15,000	3.00	45,000	195,000
1935	1000(a)	40,000	95	2.38	95,000	12,000	3.75	45,000	140,000
1936	600(b)	24,000	120	3.00	72,000	45,000(f)	3.25	146,250	218,250
1937	2100	84,000	95	2.38	199,500	70,000	3.25	227,500	427,000
1938	2200	88,000	64	1.60	140,800	95,000	2.60	247,000	387,800
1939	2500	100,000	68	1.70	170,000	95,000	2.80	266,000	436,000
1940	880(c)	35,200	98	2.45	86,240	80,000	2.85	228,000	314,240
1941	1250	50,000	100	2.50	125,000	150,000	2.10	315,000	440,000
1942	2100	84,000	136	3.40	285,600	175,000	2.36	413,000	698,600
1943	4600(d)	184,000	120	3.00	552,000	190,000	4.79(g)	910,100	1,462,100
1944	5800	232,000	140	3.50	812,000	250,000	4.86(g)	1,215,000	2,027,000
1945	3200	128,000	144	3.60	460,800	200,000	3.58	716,000	1,176,800
1946	1600(e)	64,000	336	8.40	537,600	170,000	3.95	671,500	1,209,100
1947	2300	92,000	200	5.00	460,000	170,000	3.34	567,800	1,027,800
1948	3100	124,000	180	4.50	558,000	200,000	3.14	628,000	1,186,000
1949	3900	156,000	150	3.75	585,000	260,000	3.50	910,000	1,460,000
1950	5500	275,000	134	3.35	737,000	350,000	3.12	780,000	1,517,000
1951		(NO ESTIMATE)				300,000	(NO ESTIMATE)		

NOTES: (a) Lower yield account freeze December 9, 1934.
(b) Lower yield account hurricane in November 1935.
(c) Lower yield account freeze of January 26-30. Extremely severe.
(d) Higher yield account good crop and care with full harvesting, affected by higher prices.
(e) Lower yield account hurricane November 15-16, 1945.
(f) Heavy increase in yield account new acreage in Polk County coming into production.
(g) High prices due to shortage and high prices of California lemons.

FLORIDA PERSIAN LIMES CERTIFIED FOR SHIPMENT - BY COUNTIES, BY MONTHS
AUGUST 1, 1950-JULY 31, 1951
(In Terms of 1-3/5 Bushel Boxes)

County	Dade	Highlands	Hills-borough	Pinellas	Polk	Volusia	State Total
August, 1950	26,805	5,889			1,941		34,635
September, 1950	17,012	844			990		18,846
October, 1950	9,405	697					10,102
November, 1950	11,655	799			16		12,470
December, 1950	6,004	353					6,357
January, 1951	10,020	828					10,848
February, 1951	3,293	1,085			10		4,388
March, 1951	5,338	746					6,084
April, 1951	4,803	459					5,262
May, 1951	2,511	156					2,667
June, 1951	33,394	2,023	619	541	212		36,789
July, 1951	41,993	8,915	4,151		3,954	69	59,082
Season Total	172,233	22,794	4,770	541	7,123	69	207,530
% of State Total	82.993%	10.983%	2.298%	.261%	3.432%	.033%	100%
State Total 1949-50							252,924
State Total 1948-49							202,265

RECAPITULATION OF RAIL DISTRIBUTION, FLORIDA CITRUS FRUITS BY STATES - 1950-51 AND 1949-50 SEASONS

CARLOADS (Approximately 500 Boxes per Car for Both Seasons)

STATES	ORANGES		GRAPEFRUIT		TANGERINES		MIXED CITRUS		GRAND TOTAL	
	50-51	49-50	50-51	49-50	50-51	49-50	50-51	49-50	50-51	49-50
	Rail	Rail-Bt.	Rail	Rail-Bt.	Rail	Rail-Bt.	Rail	Rail-Bt.	Rail	Rail-Bt
Alabama	167	145	16	6	1	-	77	84	261	235
Arkansas	2	3	-	-	-	-	7	1	9	4
California	-	9	6	25	2	6	1	3	9	43
Colorado	40	57	99	60	13	8	9	2	161	127
Connecticut	292	326	120	91	28	24	24	13	464	454
Delaware	5	6	1	1	-	1	-	1	6	9
Dist.of Columbia	331	113	196	53	6	5	30	10	563	181
Florida	-	-	-	-	-	-	-	-	-	-
Georgia *	351	279*	88	67*	4	4*	154	107*	597	457*
Idaho	1	3	5	5	-	-	6	6	12	14
Illinois	1240	994	1,074	493	212	205	312	152	2,838	1,844
Indiana	122	48	51	17	1	1	75	15	249	81
Iowa	13	11	35	27	-	1	12	9	60	48
Kansas	3	3	11	15	1	1	11	2	26	21
Kentucky	239	165	55	43	6	6	84	14	384	228
Louisiana	151	96	38	9	-	2	25	26	214	133
Maine	84	52	20	10	-	1	33	31	137	94
Maryland	749	524	445	221	94	68	183	154	1,471	967
Massachusetts	1,567	1,740	848	561	208	191	628	339	3,251	2,831
Michigan	921	753	840	515	220	218	453	150	2,434	1,636
Minnesota	66	10	170	75	34	28	35	8	305	121
Mississippi	58	46	2	-	-	-	9	11	69	57
Missouri	400	442	341	208	68	59	196	82	1,005	791
Montana	7	4	18	25	-	2	5	4	30	35
Nebraska	30	27	36	31	-	1	2	1	68	60
New Hampshire	-	-	-	-	-	-	3	3	3	3
New Jersey	400	323	151	75	4	1	15	9	570	408
New Mexico	1	1	-	1	-	-	-	-	1	2
New York	5,755	6,088	4,195	3,717	535	1,025	2,647	1,234	13,132	12,064
North Carolina	398	373	78	122	24	19	193	153	693	667
North Dakota	-	1	1	2	-	-	2	6	3	9
Ohio	1,519	1,086	1,041	569	227	223	462	229	3,249	2,107
Oklahoma	12	24	12	18	-	-	5	-	29	42
Oregon	24	42	51	81	10	8	36	15	121	146
Pennsylvania	2,764	1,994	1,593	939	393	398	989	695	5,739	4,026
Rhode Island	227	199	58	75	31	25	106	58	422	357
South Carolina	275	178	9	7	2	-	94	76	380	261
South Dakota	2	-	3	4	-	-	-	-	5	4
Tennessee	798	677	188	91	16	18	360	254	1,362	1,040
Texas	33	9	20	5	-	-	3	-	56	14
Utah	5	16	37	25	-	-	-	-	42	41
Vermont	1	-	1	-	-	-	14	3	16	3
Virginia	329	234	175	154	24	1	94	38	622	427
Washington	25	72	132	151	29	26	3	1	189	250
West Virginia	92	88	10	6	6	4	65	30	173	128
Wisconsin	200	158	191	90	14	8	140	43	545	299
Wyoming	-	-	1	2	1	-	2	-	4	2
CANADA	671	389	1,399	745	92	56	185	102	2,347	1,292
TOT.CARLOADS	20,370	17,808	13,861	9,437	2,306	2,644	7,789	4,174	44,326	34,063

* Does not include Savannah, Georgia, a transfer point.

NOTE: Boat shipments for 1949-50 were: Oranges 3,091, Grapefruit 1,662, Tangerines 409, Total 5,162 carloads; for 1950-51, no boat. No distributions made by States. Truck and Rail Distribution represents abstracts of tables in the Florida Citrus Summary, by Federal-State Market News Service, Lakeland, Florida.

INTERSTATE TRUCK DISTRIBUTION, FLORIDA CITRUS FRUITS
BY STATES - 1950-51 AND 1949-50 SEASONS-OCTOBER TO MAY

CARLOAD EQUIV. (500 Boxes per Car for Both Seasons)

STATES	ORANGES		GRAPEFRUIT		TANGERINES		GRAND TOTAL	
	50-51 Cars	49-50 Cars	50-51 Cars	49-50 Cars	50-51 Cars	49-50 Cars	50-51 Cars	49-50 Cars
Alabama	973	940	239	190	58	69	1,270	1,199
Arkansas	192	189	92	41	5	7	289	237
California	2	13	3	3	12	5	17	21
Colorado	32	17	71	31	12	14	115	62
Connecticut	74	88	46	42	15	22	135	152
Delaware	17	38	5	8	3	3	25	49
Dist.of Columbia	271	401	186	233	45	47	502	681
Georgia	1,665	1,581	517	390	124	157	2,306	2,128
Illinois	917	1,214	732	582	232	274	1,881	2,070
Indiana	676	747	331	211	78	107	1,085	1,065
Iowa	102	107	132	67	13	9	247	183
Kansas	52	61	75	37	6	9	133	107
Kentucky	280	382	135	109	25	37	440	528
Louisiana	416	337	89	127	8	7	513	471
Maine	27	41	7	14	1	-	35	55
Maryland	463	505	225	168	78	88	766	761
Massachusetts	199	200	179	205	74	115	452	520
Michigan	324	512	240	171	47	65	611	748
Minnesota	123	262	177	96	21	30	321	388
Mississippi	396	336	48	26	11	14	455	376
Missouri	289	363	295	167	50	55	634	585
Nebraska	49	66	95	63	10	9	154	138
New Hampshire	1	-	-	-	-	-	1	-
New Jersey	191	360	124	119	24	26	339	505
New Mexico	3	2	6	2	-	-	9	4
New York	1,830	2,510	1,070	702	370	375	3,270	3,587
North Carolina	1,061	1,034	371	231	130	151	1,562	1,466
North Dakota	4	7	16	8	1	1	21	16
Ohio	563	947	424	356	74	119	1,061	1,422
Oklahoma	86	66	81	44	10	7	177	117
Pennsylvania	1,528	2,170	664	624	271	360	2,463	3,154
Rhode Island	33	77	29	14	8	14	70	105
South Carolina	879	880	288	222	103	123	1,270	1,225
South Dakota	6	8	16	9	-	-	22	17
Tennessee	587	679	201	163	43	64	831	906
Texas	674	597	282	168	96	90	1,052	855
Vermont	22	22	9	7	1	1	32	30
Virginia	667	822	360	350	73	118	1,100	1,290
West Virginia	246	255	107	73	25	23	378	351
Wisconsin	137	234	146	68	25	40	308	342
States Not Specified*	25	22	22	24	4	7	51	53
CANADA	177	188	152	100	21	28	350	316
TOTAL CARLOADS	16,259	19,280	8,287	6,315	2,207	2,690	26,753	28,285
N.W. Florida	165	146	49	31	18	21	232	198
GRAND TOT. CARS	16,424	19,426	8,336	6,346	2,225	2,711	26,985	28,483

*Includes: Oranges--Arizona 1, Idaho 1, Montana 2, Oregon 5, Utah 6, Washington 3, Others 7.
Grapefruit--Idaho 3, Montana 5, Oregon 4, Utah 3, Washington 2, Wyoming 2, Others 3.
Tangerines--Arizona 1, Idaho 1, Oregon 1, Others 1.

Destinations, fairly complete, were available for following periods: 1949-50--October 16 - May 31, inclusive; 1950-51--October 1-May 31, inclusive.

ESTIMATED PRICES PAID BY CANNERS AND PROCESSORS 1941-1950

(Florida Citrus Delivered to Canner's Door)

	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	July	Average
ORANGES	$	$	$	$	$	$	$	$	$	$	$	$	
1941-42					.74	.93	.91	1.10	1.20	1.25	1.35	1.40	1.076
1942-43					1.50	1.25	1.48	1.76	2.00	2.40	2.45	2.50	1.70
1943-44			2.03	2.03	2.03	1.86	1.63	1.87	2.27	2.25	2.20	2.37	2.02
1944-45	2.37		1.98	1.98	1.93	2.18	2.49	2.74	3.11	3.25	3.06	3.06	2.60
1945-46		2.49	2.49	2.41	2.52	2.37	2.31	2.62	3.00	3.66	3.68	3.50	2.83
1946-47		1.33	1.33	1.00	.55	.55	.54	.69	1.17	1.16	1.08	.79	.82
1947-48	.79		.87	.87	.80	.80	1.09	.91	.70	.65	.51	.49	.80
1948-49	.49	.46	.46	.53	.73	.96	1.20	1.70	2.20	3.10	3.40	3.00	1.51
1949-50	LCL		1.70	1.20	1.53	2.36	3.10	3.30	2.77	2.60	2.55	2.55	2.38
1950-51			2.10	1.40	1.38	1.61	2.30	2.05	2.20	2.30	1.90	.75	1.86
GRAPEFRUIT													
1941-42					.69	.67	.64	.76	.82	.80	.77	.77	.706
1942-43					.92	.96	1.08	1.20	1.32	1.47	1.50	1.50	1.05
1943-44			1.37	1.37	1.45	1.44	1.40	1.50	1.74	1.76	1.66	1.67	1.53
1944-45	1.67		1.83	1.83	1.83	1.85	2.01	2.17	2.19	2.20	1.92		1.91
1945-46		1.30	1.30	1.53	1.51	1.29	1.23	1.22	1.29	1.67	1.76	1.77	1.39
1946-47	1.77	1.18	1.19	1.18	.77	.60	.52	.53	.53	.44	.39	.40	.65
1947-48	.40		.51	.51	.44	.40	.36	.31	.28	.28	.25	.24	.34
1948-49	.24	.39	.39	.42	.42	.48	.60	.75	.83	.92	1.06	1.10	.57
1949-50	1.10	1.29	1.29	1.72	1.90	2.05	1.98	1.95	1.93	1.42	1.43	1.43	1.87
1950-51		.65	.80	.80	.80	.94	1.24	1.08	.91	.81	.55	.40	.91
TANGERINES													
1945-46						1.00	1.00	1.00	1.00	1.00			1.00
1946-47				1.50	1.00	.60	.60	.65	.65				.80
1947-48				.50	.40	.35	.35	.35					.35
1948-49			.46	.46	.46	.46	.46	.46	.46				.46
1949-50				.50	.80	.80	.80	1.05					.90
1950-51				1.00	.50	.50	.70	.70					.65

FLORIDA CITRUS VOLUME CANNED OR PROCESSED

(Carloads of 500 Boxes)

ORANGES	Aug.	Sept	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	July	Total
1944-45			167	1786	2582	4302	5705	6809	5211	1799	81		28,442
1945-46		LCL	984	3942	3997	4494	4146	5825	6128	6255	2494	103	38,368
1946-47			1049	2550	2766	5266	6461	9101	4498	4837	2734	362	39,624
1947-48	27		605	3630	7797	11092	11280	6622	6097	6999	5110	1441	60,700
1948-49	80	3	1269	4463	6930	9126	9409	8616	6007	5497	2246	59	53,705
1949-50			236	5056	13333	14044	8844	5676	7938	10007	4135	47	69,316
1950-51	1	2	827	5928	11708	12956	10060	7350	8672	13716	10740	1756	83,716
G.FRUIT													
1944-45			726	4637	8427	8607	4248	2131	1034	372	22		30,204
1945-46		105	989	2416	4000	7355	5950	7266	7516	6031	2319	302	44,249
1946-47	LCL	174	1586	3470	3319	5246	3682	5511	5043	2590	965	120	31,706
1947-48	21		596	2139	4749	5659	5769	6107	6602	4142	2023	929	38,736
1948-49	180	224	1607	4384	4946	6378	5818	5341	2328	904	534	143	32,787
1949-50	4	22	160	1151	2809	5875	5870	4826	2075	2099	2010	75	26,976
1950-51	3	190	847	3599	4343	5679	5959	5260	4033	3024	1905	785	35,627
TANG.													
1945-46						211	325	356	133	6			1,031
1946-47				188	676	742	220	26	LCL				1,852
1947-48				58	439	492	208	LCL					1,197
1948-49			37	582	654	621	83	14	7			...	1,998
1949-50				48	511	1086	1210	334	1				3,190
1950-51				22	279	668	1018	705	17				2,709
TOTAL CITRUS													
1944-45			893	6423	11009	12909	9953	8940	6245	2171	103		58,646
1945-46		105	1973	6358	7997	12060	10421	13447	13777	12292	4813	405	83,648
1946-47	LCL	174	2635	6208	6761	11254	10363	14638	9541	7427	3699	482	73,182
1947-48	48		1201	5827	12985	17243	17257	12729	12699	11141	7133	2370	100,633
1948-49	260	227	2713	9429	12530	16125	15310	13971	8342	6401	2780	202	88,490
1949-50	4	22	396	6255	16653	21005	15924	10836	10014	12106	6145	122	99,482
1950-51	4	192	1674	9549	16330	19303	17037	13315	12722	16740	12645	2541	122,052

ANNUAL PACKS OF GRAPEFRUIT AND ORANGE SEGMENTS AND JUICE FOR SELECTED YEARS

(Some Years Omitted for Lack of Space) (In Thousands)

(1,000 cases for 24 No. 2 Cans)

	FLORIDA	TEXAS	CALIF.& ARIZONA	TOTAL U.S.	GOV. PUR.	COMM. EXP.	FOR DOM.MKTS
GRAPEFRUIT SEGMENTS							
1934-35	3,588	7	4	3,599	#	1,159	2,440
1939-40	4,134	57	-	4,191	#	1,397	2,794
1942-43	888	87	-	975	832	2	141
1945-46	2,407	289	-	2,696	7	7	2,689
1947-48	3,158	242	-	3,400	#	#	#
1948-49	4,238	169	-	4,427	#	#	#
1949-50	3,379	-	-	3,379	#	#	#
1950-51	4,309	#	#	#	#	#	#
GRAPEFRUIT JUICE							
1934-35	2,237	361	442	3,040	0	#	3,040
1939-40	4,682	5,955	296	10,933	0	574	10,359
1942-43	15,193	7,360	1,049	23,602	7,556	105	1,591
1945-46	15,089	9,601	1,372	26,062	397	467	25,198
1947-48	7,987	9,000	400	17,387	#	#	#
1948-49	8,843	4,944	518	14,305	#	#	#
1949-50	7,894	2,680	1,600	12,174	#	#	#
1950-51	8,848			#	#	#	#
ORANGE JUICE							
1934-35	241	0	704	945	0	0	945
1939-40	2,851	0	744	3,595	0	110	3,485
1942-43	2,429	0	394	2,823	1,544	43	1,236
1945-46	18,421	56	3,705	22,182	2	247	21,933
1947-48	25,593	165	1,500	27,258	#	#	#
1948-49	16,757	296	2,209	19,262	#	#	#
1949-50	17,419	145	1,900	19,464	#	#	#
1950-51	16,672	#	#	#	#	#	#
BLENDED JUICE							
1935-36	85	-	-	85	0	-	85
1939-40	1,403	30	-	1,433	0	-	1,433
1942-43	3,676	25	1	3,702	2,388	-	1,314
1945-46	12,267	626	568	13,461	96	-	13,365
1947-48	11,894	300	50	12,244	#	-	#
1948-49	10,252	229	348	10,829	#	-	#
1949-50	6,768	45	-	6,813	#	#	#
1950-51	10,342	#	#	#	#	#	#

FLORIDA PRODUCTION OF CERTAIN CITRUS PRODUCTS AND BY-PRODUCTS

	CONCENTRATED ORANGE JUICE					GRAPEFRUIT JUICE			
						CONCENTRATED		BLENDED	
	(1) FROZEN GALS. (000)	(2) PROCESSED GALS. (000)	CITRUS FEED TONS (000)	MO-LASSES TONS (000)	CITRUS OILS LBS. (000)	FROZ. (000)	PROC. (000)	FROZ. (000)	PROC. (000)
1940-41	-	66(1)	33	#	#	-	-	-	-
1941-42	-	94(1)	30	#	#	-	-	-	-
1942-43	-	1,882(2)	47	#	227	-	-	-	-
1943-44	-	1,283(3)	67	14	275	-	-	-	-
1944-45	-	240	69	19	290	-	-	-	-
1945-46	226	244	108	44	372	-	-	-	-
1946-47	559	1,447	96	58	#	-	-	-	-
1947-48	1,910	1,798	154	66	#	1.4	1,440	-	-
1948-49	10,233	1,698	134	41	#	116	19	112	.4
1949-50	21,647	1,529	163	42	#	1,584	28	1,303	-
1950-51	30,785	2,509	#	#	#	188	147	245	1060

# Data unavailable. Source: Florida Citrus Fruit Annual Summaries by Florida Crop and Livestock Reporting Service, Orlando, Florida.

1. Estimated on basis of .588 gals. of concentrate per 1-3/5 bu. box.
2. Includes Government Purchases - 65° Brix - 1,832,245 gals. in 1942-43 and 1,232,742 gals. in 1943-44 season.

The original source of most information for Florida was the Florida Canners Association.

FREIGHT RATES OF CITRUS PER 1-3/5 BU. BOX (From Winter Haven, Fla.) TO AUCTION MARKETS TO JUNE, 1951

Auction Markets	ORANGES			GRAPEFRUIT			TANGERINES		
	Freight Rate	Florida Cars	*Per Box	Freight Rate	Florida Cars	*Per Box	Freight Rate	Florida Cars	*Per Box
Baltimore	$ .8091	132	$ .9642	$ .8051	60	$ .9601	$ .8188	17	$ .9484
New York	.9998	5,920	1.1605	.9968	4,673	1.1574	.9980	1,056	1.1586
Philadelphia	.8463	1,972	1.0025	.8466	1,323	1.0028	.8298	382	.9855
Boston	1.1681	560	1.3448	1.1371	356	1.3128	1.1430	47	1.3189
Cincinnati	.8463	542	1.0378	.8466	461	1.0381	.8298	90	1.0208
Cleveland	1.0509	530	1.2691	1.0541	379	1.2724	1.0368	146	1.2549
Detroit	1.0509	648	1.2691	1.0541	579	1.2724	1.0368	182	1.2549
Pittsburgh	.8928	363	1.1062	.8881	301	1.1014	.8928	92	1.1062
St.Louis	.9021	322	1.1158	.8964	292	1.1099	.8838	64	1.0970
Chicago	.9021	699	1.1158	.8964	681	1.1099	.8838	232	1.0970
Total Cars		11,688			9,105			2,308	
Avg.All Auctions			$1.1397			$1.1388			$1.1299

* Includes 3% war revenue tax and chg. for Std. Refrigeration.

Source: Freight rates supplied by Fla. Citrus Exchange and compiled by Florida Citrus Mutual.

Truck rates apply to one stop delivery. 5¢ box additional for bagged oranges. Truck rates same for other varieties. Truck includes refrigeration.

- -

MARKETING BUREAU NOTES:(1) Average rates shown in our report in 1950 were: Oranges $1.08, Grapefruit $1.04, Tangerines $1.08. (2) Truck and boat receipts note included. (3) Average truck rates to these various cities run higher than freight rates,probably averaging 10 percent higher.

GROWTH IN OUTPUT OF FROZEN CONCENTRATED CITRUS JUICES

(From The Fruit Situation, U.S.D.A., June, 1950) (See Page 39)

Started on a small scale in 1945-46, production of frozen concentrated orange juice has since increased rapidly to become a major outlet for oranges. The early success achieved with oranges has led to the more recent manufacture of frozen concentrated grapefruit juice, blended orange and grapefruit juice, and even lemonade. Among non-citrus juices, frozen concentrated grape juice is also being manufactured commercially. Experiments are being carried on with other fruit juices.

Commercial manufacture of frozen concentrated orange juice began in Florida in Florida in 1945-46, when about 226,000 gallons of 4 to 1 concentrate were produced (see accompanying table). Production in this State more than doubled in 1946-47. The orange concentrate made in these two seasons was distributed largely thru the hotel, restaurant, and soda fountain trades, where response was so favorable as to point to its widespread use by household consumers.

FROZEN CONCENTRATED CITRUS JUICES: PRODUCTION IN FLORIDA AND CALIFORNIA-ARIZONA, 1945-46 TO 1949-50

Season	Florida (Gals.)	Calif.-Ariz.(Gals.)	Total Gals.
	Orange Juice		
1945-46	225,684	0	225,684
1946-47	559,309	0	559,309
1947-48	1,935,868	437,376	2,373,244
1948-49	10,232,831	1,963,035	12,195,866
1949-50	21,647,000	-	-
1950-51	30,785,000	#	-
	Grapefruit Juice		
1947-48	402	0	402
1948-49	116,123	0	116,123
1949-50	1,584,000	0	1,584,000
1950-51	188,000	#	-
	Orange-Grapefruit Blend		
1948-49	111,836	0	111,836
1949-50	1,303,000	#	-
1950-51	245,000	#	-

Information not available when the Marketing Bureau Annual Report was released.

FEDERAL-STATE INSPECTION SERVICE
July 1, 1950 - June 30, 1951

FLORIDA Commodities	Type of Container	Rail Cars Inspected	No. of Units or Containers	Average Containers (or Units per Car) 1950-51	49-50	48-49	47-48	46-47
Oranges	Std. Box Equiv.	18,368	8,952,038	488	485	497	[illegible]	503
Grapefruit	" " "	13,071	6,547,717	501	498	[illegible]	[illegible]	515
Tangerines	" " "	2,459	1,105,791	450	442	[illegible]	437	442
Mixed Citrus	" " "	8,856	4,265,449	482	457	497	494	[illegible]
Total Citrus		42,754	20,877,995	488	485	492	[illegible]	[illegible]
Beans	Bu hprs.	47	29,848	635	590	624	636	641
Cabbage	50 lb. sks	1,639	818,064	499	496	502	501	503
"	W.B.Crts.	3,162	1,491,449	472	469	460	[illegible]	-
Celery	Std.Fla.Crts.	9,824	4,135,662	421	409	427	[illegible]	425
Corn	Std. Crts.	1,722	977,771	568	585	[illegible]	510	442
Corn	50# sks.	3	1,740	580	706	546	-	-
Cucumbers	Bu hprs.	220	137,207	447	547	379	373	459
Escarole	Bu hprs.	94	58,886	626	635	640	640	612
Lettuce (Romaine)	Crates, small	7	5,382	769	-	-	-	-
Peppers	Bu hprs.	220	137,207	641	656	597	526	672
Potatoes	Coml. 50# sks.	2,561	1,640,700	624	653	679	641	651
"	Coml. Bu.	-	-	-	589	653	-	563
"	Coml. 100# sks.	3,047	920,552	302	300	301	297	307
"	Coml. 50# crts.	2	1,085	543	628	622	-	-
"	Gov. 100# sks.	-	-	-	362	326	360	355
Tomatoes	30# lugs	1,960	1,312,589	670	666	673	631	693
"	Bushels	1,438	549,935	382	391	416	-	-
Chicory-Endive	Bushels	31	19,869	641	636	-	-	-
Total Vegetables		25,978	12,237,946					
Strawberries	36 Pt.Crates	53	25,298	477	450	-	-	-
Watermelons	Melons	8,991	4,739,396*	1054	846	973	985	938
Limes	1-3/5bu Box	-	-	-	392	-	399	-
Total Miscl. Fruits		9,044	4,764,694					
Total Rail All Fruits and Vegetables		77,776	37,880,635					

* Divide Watermelons by 2 to get units comparable to packages.

INSPECTION FOR TRUCK SHIPMENTS IN CARLOT EQUIVALENTS

	Commercial		Cannery		Total Truck Inspection	
	Boxes	Cars	Boxes	Cars	Boxes	Cars
Oranges	5,074,565	10,405	31,581,348	74,720	36,655,913	85,405
Grapefruit	3,085,872	6,197	17,461,592	35,063	20,547,464	41,260
Tangerines	810,225	1,837	1,082,272	2,454	1,892,497	4,291
Mixed Citrus	7,243,863	14,905	-	-	7,243,863	14,905
Total Citrus	16,214,525	33,424	50,125,212	112,437	66,339,737	145,861

	Container	Units	Cars
Beans (Snap)	Bu.	43,617	71
Beans (Limas)	Bu.	1,162	2
Broccoli	Bu.	23,669	46
Cauliflower	Bu.	11,690	24
Celery	Crt.	1,810,250	4,437
Cabbage	Crt.	529,310	1,129
"	50#bags	472,862	955
Chicory	Bu.	55,425	87
Corn	50#bags	3,071	6
"	Crt.	1,306,518	2,233
Cucumbers	Bu.	107,908	197
" (Market)	Bu.	1,942	4
Eggplant	Bu.	17,941	30
Escarole	Bu.	91,222	143
Lettuce	Crt.	17,687	55
Peppers	Bu.	120,704	184
Potatoes	50 bags	955,639	1,455
"	100#bags	500,787	1,66[illegible]
Radishes	Bu.	2,308	5
Romaine Lettuce	Bu.	6,357	11

	Container	Units	Cars
Squash	Bu.	22,249	49
Tomatoes	Lugs	53,162	80
"	Bu.	443,167	1,103
" (Market)	Bu.	1,029,179	2,632
Turnip Greens	Bu.	19,254	34
Onions	Bu.	5,302	11
Total Vegetables		7,655,6[illegible]2	16,65[illegible]
Cantaloupes	Bu.	100	LCL
Strawberries	36-Pt.Crt.	225,328	501
Watermelons	Melon	310,060*	311
Total Miscl-Frts		380,456	812
Total Fruits & Vegs.		8,034,140	17,[illegible]
Peanuts-Shelled	Ton	14,020	561
" Shelled	Lbs.	3,938,116	72
" Farmers' Stock	Ton	2,957,774	2,465
Lupines	Ton	129	5
		Cars	3,110
GRAND TOTAL			166,438

NOTE: Except for citrus, cabbage, celery, corn, potatoes, tomatoes, and watermelons, the inspection sample may have been too small to show the average carloadings.

The foregoing table was arranged from figures supplied by Mr. H. S. Flynt, Ass't Director, Vegetable Branch, Citrus & Inspection Division, Florida Department of Agriculture, 305 P.O. Bldg., Orlando, Florida.

CITRUS - ACREAGE AND PRODUCTION IN STANDARD BOXES (1) (In Thousands)

Crop Season	FLORIDA Acreage	FLORIDA Production	CALIFORNIA Acreage	CALIFORNIA Production	TEXAS Acreage	TEXAS Production	ARIZONA Acreage	ARIZONA Production	OTHER STATES Acreage	OTHER STATES Production	TOTAL UNITED STATES Acreage	TOTAL UNITED STATES Production
ORANGES												ORANGES
1924-25	106.2	10,400	173.0	18,506	1.0	17	.9	60	3.5	77	284.6	29,060
1929-30	133.0	8,950(A)	190.1	21,195	5.1	261	1.1	137	5.1	436	334.4	30,979
1934-35	187.3	15,600	206.7	45,047	20.9	650	4.1	170	6.6	521	425.6	61,988
1939-40	216.2	25,600	229.2	44,425	24.2	2,360	7.3	595	8.3	362	485.2	73,342
1944-45	256.3	42,800	237.8	60,500	28.4	4,400	7.1	1,150	4.5	360	534.1	109,210
1948-49	289.9	58,300	239.2	36,910	40.5	3,400(B)	8.3(B)	710(B)	4.5	300	582.4	99,620
1949-50(2)	300.9	58,500	215.6	42,330	28.0	1,760	8.3	985	4.5	360	557.3	103,935
GRAPEFRUIT												GRAPEFRUIT
1924-25	45.7	8,900	3.8	387	2.4	301	.5	105	-	-	52.4	9,693
1929-30	58.0	8,300(A)	10.1	1,000	11.1	1,550	2.1	365	-	-	81.3	11,215
1934-35	78.3	15,200	13.7	2,167	57.9	2,740	7.2	1,240	-	-	157.1	21,347
1939-40	87.5	15,900	16.4	1,992	73.1	14,400	13.8	2,900	-	-	190.8	35,192
1944-45	90.0	22,300	14.6	3,830	77.0	22,300	13.0	3,750	-	-	194.6	52.180
1948-49	95.0	30,200	13.2	2,140	82.0	11,300(B)	10.3	1,880(B)	-	-	200.5	45,520
1949-50(2)	98.5	24,200	10.4	2,490	56.0	6,400	9.6	3,400	-	-	174.5	36,490

	FLORIDA TANGERINES Acreage	FLORIDA TANGERINES Production	FLORIDA LIMES Acreage	FLORIDA LIMES Production	TOTAL FLORIDA TANGERINES, LIMES Acreage	TOTAL FLORIDA TANGERINES, LIMES Production	CALIFORNIA LEMONS Acreage	CALIFORNIA LEMONS Production	TOTAL TANGERINES LIMES, LEMONS Acreage	TOTAL TANGERINES LIMES, LEMONS Production
1924-25	6.2	900	2.5	36	8.7	936	41.3	5,301	50.0	6,237
1929-30	15.4	350(A)	1.8	8	17.2	858	40.5	6,109	57.7	6,967
1934-35	24.1	2,000	2.1	15	26.2	2,015	40.4	10,747	66.6	12,762
1939-40	25.1	2,400	3.7	95	28.8	2,495	52.0	11,983	80.8	14,478
1944-45	23.4	4,000	5.1	250	28.5	4,250	62.7	12,550	91.2	16,800
1948-49	24.0	4,400	4.6	200	28.6	4,600	64.7	9,930	93.3	14,530
1949-50(2)	24.2	5,000	4.8	260	29.0	5,260	58.2	10,500	87.2	15,760

ALL CITRUS	FLORIDA Acreage	FLORIDA Production	CALIFORNIA Acreage	CALIFORNIA Production	TEXAS Acreage	TEXAS Production	ARIZONA Acreage	ARIZONA Production	OTHER STATES Acreage	OTHER STATES Production	TOTAL UNITED STATES Acreage	TOTAL UNITED STATES Production
1924-25	160.1	20,236	218.1	24,194	3.4	318	1.4	165	3.5	77	387.0	44,990
1929-30	208.2	18,108(A)	240.7	28,304	16.2	1,811	3.2	502	5.1	436	473.4	49,161
1934-35	291.8	32,815	260.8	57,961	78.8	3,390	11.3	1,410	6.6	521	649.3	96,097
1939-40	332.5	43,995	297.6	58,400	97.3	16,760	21.1	3,495	8.3	362	756.8	123,012
1944-45	374.8	69,350	315.1	76,880	105.4	26,700	20.1	4,900	4.5	360	819.9	178,190
1948-49	413.5	93,100	317.1	48,980(B)	122.5	14,700(B)	18.6	2,590(B)	4.5	300	876.2	159,670
1949-50(2)	428.4	87,960	284.2	55,320	84.0	8,160	17.9	4,385	4.5	360	819.0	156,185

(1) Thousand of bearing acres, and thousand of boxes. Florida and Texas 1-3/5 bu., Calif. & Arizona slightly smaller.
(2) Last figure available. 1950-51 unavailable for all of the States.
(A) Fruit Fly Season. (B) Freezes.

NOTE: The grove value per acre is only the statistical value of the average grove based on the average income. The real estate value is based on location, varieties, irrigation water, yields and future possibilities.

CITRUS ACREAGE, YIELD, BOXES PER TREE, AND GROVE VALUES

FLORIDA ORANGES SEASON	Bearing Acres	Production in 1-3/5 Bu.Box	Box Yield per Acre (66 Trees)	Box Yield per Tree	Gross Return Box	Net* Return Box	Abandoned Boxes	Net per Acre* before Taxes & Depreciation	Value per Acre Based on Income per Acre at 10%	at 13%
1943-44	251,340	46,200,000	184	2.8	$2.81	$1.21	-	$241	$2410	$1850
1944-45	256,340	42,800,000	167	2.5	3.17	1.73	-	289	2890	2223
1945-46	264,900	49,600,000	188	2.8	3.25	1.84	-	346	3460	2661
1946-47	270,000	53,700,000	199	3.0	1.93	.50	900,000	99	990	761
1947-48	280,500	58,400,000	208	3.2	1.41	.15	-	31	310	239
1948-49	289,900	58,300,000	201	3.1	2.19	.79	-	159	1590	1223
1949-50	300,900	58,500,000	194	2.9	2.84	1.51	-	293	2930	2254
1950-51	309,500	67,300,000	211	3.2	2.55	.93	-	196	1960	1508
GRAPEFRUIT									at 10%	at 16%
1943-44	95,190	31,000,000	326	4.9	1.83	.92	-	300	3000	1875
1944-45	90,000	22,300,000	248	3.8	2.24	1.36	-	337	3370	2106
1945-46	90,500	32,000,000	354	5.4	1.77	.78	-	276	2760	1725
1946-47	91,000	29,000,000	319	4.8	1.25	.26	2,600,000	75	750	470
1947-48	93,000	33,000,000	355	5.4	.82	- .01	3,700,000	- 3½	-	-
1948-49	95,000	30,200,000	318	4.8	1.38	.33	-	105	1050	656
1949-50	98,500	24,200,000	246	3.7	2.53	1.52	-	378	3780	2362
1950-51	100,000	33,200,000	322	4.9	1.74	.56	-	180	1800	1125
TANGERINES									at 10%	at 15%
1943-44	23,419	3,600,000	154	2.3	3.62	1.36	-	209	2090	1393
1944-45	23,419	4,000,000	171	2.6	4.18	1.91	150,000	315	3150	2100
1945-46	23,549	4,200,000	178	2.7	4.24	2.10	-	374	3740	2493
1946-47	23,705	4,700,000	198	3.0	2.99	.90	800,000	149	1490	993
1947-48	23,800	4,000,000	168	2.5	2.41	.20	600,000	29	290	193
1948-49	24,000	4,400,000	183	2.8	2.93	.74	-	135	1350	900
1949-50	24,100	5,000,000	207	3.1	2.87	.80	-	166	1660	1167
1950-51	24,200	4,800,000	199	3.0	3.24	1.05	200,000	200	2000	1333
TOTAL CITRUS										
1943-44	369,949	80,800,000	218	3.3	2.47	1.16	-	253	2530	-
1944-45	369,759	69,100,000	187	2.8	2.93	1.62	150,000	303	3030	-
1945-46	378,949	86,000,000	227	3.4	2.75	1.46	-	331	3310	-
1946-47	384,705	87,400,000	227	3.4	1.76	.44	3,400,000	96	960	-
1947-48	397,300	95,400,000	240	3.6	1.36	.10	4,300,000	23	230	180
1948-49	408,900	92,900,000	227	3.4	1.96	.63	-	143	1430	-
1949-50	423,500	87,700,000	207	3.1	2.76	1.47	-	304	3040	2330
1950-51	433,700	105,300,000	243	3.7	2.18	.82	200,000	198	1980	1405

We estimate that the 10% income as shown above on oranges will actually yield 7% and the 13% will actually yield around 10%. It is doubtful if a prudent investor would buy a grove risk with a near term expectation of less than 10% net above all costs. High prices paid by processors account for 1949-50 citrus prosperity.

* Net after production costs deducted.

FLORIDA CARS TO AUCTION FOR SEASON 1939-40 TO 1950-51 INCLUSIVE
(Including Freight, Boat and Truck
Weighted Average Prices and Per Cent Indian River Fruit

SEASONS	INTERIOR CARS	INTERIOR AVG.	INDIAN RIVER CARS	INDIAN RIVER AVG.	COMBINED CARS	COMBINED AVG.	% IND. RIVER
1939-40							
Oranges	14,151	$2.27	2,694	$2.82	16,845	$2.36	16.0
Grapefruit	4,631	1.90	2,962	2.50	7,593	2.13	39.0
Tang's, ½ Bx(not segregated)	0	0	0	0	2,143	1.37	-
1940-41							
Oranges	15,931	$2.28	3,040	$2.69	18,971	$2.35	16.0
Grapefruit	5,314	1.76	3,509	2.12	8,823	1.91	39.8
Tang's, ½ Bx(not segregated)	0	0	0	0	2,717	1.19	-
1941-42							
Oranges	13,603	$2.80	3,530	$2.94	17,133	$2.83	20.6
Grapefruit	4,037	2.41	3,288	2.65	7,325	2.52	44.9
Tang's, ½ Bx(not segregated)	0	0	0	0	2,085	1.79	-
1942-43							
Oranges	11,030	$3.71	2,576	$4.12	13,606	$3.79	18.9
Grapefruit	2,985	2.77	2,619	3.48	5,604	3.11	46.7
Tang's, ½ Bx(not segregated)	0	0	0	0	3,399	1.80	-
1943-44							
Oranges	9,880	$3.77	2,969	$4.31	12,849	$3.89	23.1
Grapefruit	1,583	3.18	2,681	3.79	4,264	3.56	62.9
Tang's, ½ Bx(not segregated)	0	0	0	0	644	2.23	-
1944-45							
Oranges	6,550	$4.30	2,472	$4.97	9,022	$4.48	27.4
Grapefruit	1,079	3.72	2,053	4.51	3,132	4.24	65.5
Tang's, ½ Bx(not segregated)	0	0	0	0	1,465	2.41	-
1945-46							
Oranges	6,038	$4.41	2,230	$5.05	8,268	$4.58	27.0
Grapefruit	1,469	3.21	2,917	4.12	4,386	3.82	66.1
Tang's, ½ Bx(not segregated)	0	0	0	0	2,201	2.61	-
1946-47							
Oranges	11,826	$3.37	2,982	$4.03	14,808	$3.50	20.2
Grapefruit	3,215	2.90	3,884	3.61	7,099	3.29	54.8
Tang's, ½ Bx(not segregated)	0	0	0	0	2,403	2.17	-
1947-48							
Oranges	9,424	$3.08	3,982	$4.68	13,406	$3.27	29.7
Grapefruit	3.430	2.53	3,230	3.64	6,660	3.07	48.5
Tang's, ½ Bx(not segregated)	0	0	0	0	2,209	1.98	-
1948-49							
Oranges	9,830	$4.15	3,303	$4.46	13,133	$4.23	25.2
Grapefruit	3,894	3.42	3,747	4.13	7,641	3.77	49.0
Tang's, ½ Bx(not segregated)	0	0	0	0	2,737	2.55	-
1949-50							
Oranges	6,747	$4.68	2,594	$5.29	9,341	$4.85	27.8
Temple Oranges(not segregated)	0	0	0	0	724	3.13	-
All Oranges	6,747	4.68	2,594	5.29	10,065	4.73	-
Grapefruit	3,821	4.45	2,369	5.99	6,190	5.04	38.3
Tang's, ½ Bx	2,520	5.22	30	5.01	2,550	2.61	1.2
1950-51							
Oranges	7,299	$4.16	3,360	$4.58	10,659	$4.29	31.5
Temple Oranges(not segregated)	0	0	0	0	1,029	5.40	-
All Oranges	7,299	4.16	3,360	4.58	11,688	4.39	-
Grapefruit	4,759	3.43	4,346	4.72	9,105	4.05	47.7
Tang's, ½ Bx.	2,247	2.56	61	2.50	2,308	2.56	2.6

F.O.B. PRICES - FLORIDA INTERIOR CITRUS - 1950-51 SEASON

Based on quotations reported daily to the Market Information Department - Florida Citrus Mutual and represent general averages weighted as to sizes, U.S. # 1s

	INTERIOR			
	ORANGES	GRAPEFRUIT (No Pinks		TANGERINES
Week Ending	Boxes	SEED Boxes	SEEDLESS Boxes	4/5 Bu. Boxes
1950				
Sept. 9	-	-	-	-
16	-	$3.30	$4.35	-
23	-	2.75	4.00	-
30	-	2.20	3.40	-
Oct. 7	$4.75	2.20	2.35	-
14	4.25	2.15	2.75	-
21	3.50	2.15	2.75	-
28	3.00	2.15	2.75	-
Nov. 4	2.65	2.15	2.60	-
11	2.65	2.10	2.50	$3.50
18	2.75	2.15	2.60	3.40
25	2.75	2.10	2.60	3.25
Dec. 2	2.75	2.10	2.60	3.15
9	2.85	2.10	2.60	3.10
16	2.95	2.10	2.60	3.00
23	3.00	2.15	2.60	2.70
30	Holiday	2.20	2.60	2.50
1951				
Jan. 6	2.95	2.20	2.60	1.90
13	2.80	2.20	2.60	1.60
20	2.70	2.20	2.60	1.70
27	2.75	2.20	2.60	1.70
Feb. 3	3.00	2.25	2.70	1.90
10	3.45	2.30	3.00	2.00
17	3.50	2.40	2.95	1.90
24	3.65	2.40	2.90	1.85
Mar. 3	3.50	2.40	2.85	1.65
10	3.40	2.40	2.60	1.90
17	3.45	2.40	2.65	2.00
24	3.60	2.40	2.75	2.00
31	3.45	2.30	2.90	2.00
Apr. 7	3.30	2.25	2.90	2.00
14	3.30	2.25	2.90	2.00
21	3.25	2.25	2.85	2.00
28	3.25	2.25	2.70	-
May 5	3.35	2.20	2.55	-
12	3.35	2.20	2.50	-
19	3.35	2.20	2.50	-
26	3.40	2.15	2.50	-

Indian River fruit not included in the above prices.

Made available to the Federal-State Market News Service, Lakeland, Fla., through the courtesy of the Florida Citrus Mutual, Lakeland, Florida.

ACREAGE, YIELD, PRODUCTION AND VALUE
FLORIDA VEGETABLES AND MISCELLANEOUS FRUITS
1950-51 SEASON

FLORIDA	Acreage Planted	Acreage For Harvest	Yield Units	Production Total Units	Abandoned A Units	Production of Value Units	Season Avg. FOB Price PerUnit	Total Value Marketed Dollars
SNAP BEANS			Bu.					
Fall (Fresh)	25,400	13,000	65	845,000		845,000	$4.10	$ 3,464,000
(Process)	500	500	65	32,000		32,000	3.50	112,000
(Total)	25,900	13,500	65	877,000		877,000	4.08	3,576,000
Winter (Fresh)	38,000	34,000	90	3,060,000	239,000	2,821,000	3.00	8,463,000
(Process)	3,000	3,000	90	270,000		270,000	2.25	608,000
(Total)	39,000	37,000	90	3,330,000		3,091,000	2.93	9,071,000
Spring (Fresh)	20,000	20,000	100	2,000,000	200,000	1,800,000	2.20	3,960,000
(Process)	4,500	4,500	100	450,000		450,000	1.50	675,000
(Total)	24,500	24,500	100	2,450,000		2,250,000	2.06	4,635,000
TOTAL FRESH	81,400	67,000	88	5,905,000	439,000	5,466,000	2.91	15,387,000
TOTAL PROCESS	8,000	8,000	94	752,000		752,000	1.86	1,395,000
TOTAL ALL	89,400	75,000	89	6,657,000	439,000	6,218,000	2.78	17,282,000
LIMA BEANS			Bu.					
Winter	1,100	900	70	63,000		63,000	3.25	205,000
Spring	2,000	1,900	70	133,000		133,000	2.60	346,000
TOTAL	3,100	2,800	70	196,000		196,000	2.81	551,000
CABBAGE	19,000	19,000	Tons 10.2	193,800	38,200	155,600	67.00	10,425,000
CAULIFLOWER	1,200	1,000	Crt. 280	280,000		280,000	2.10	588,000
CELERY			Crt.					
Winter	6,400	6,300	630	3,969,000	60,000	3,909,000	2.65	10,359,000
Spring	4,350	4,350	635	2,762,000		2,762,000	2.05	5,662,000
TOTAL	10,750	10,650	632	6,731,000	60,000	6,671,000	2.40	16,021,000
CORN, GREEN			Crt. 5 doz.					
Fall	1,700	800	65	52,000		52,000	2.40	125,000
Spring	25,500	25,000	115	2,875,000		2,875,000	2.50	7,188,000
TOTAL	27,200	25,800	113	2,927,000		2,927,000	2.50	7,313,000
CUCUMBERS			Bu.					
Fall	4,400	3,600	175	630,000		630,000	3.00	1,890,000
Winter	3,200	500	100	50,000		50,000	8.50	425,000
Spring (Fresh)	9,500	9,200	225	2,070,000	200,000	1,870,000	2.90	5,423,000
ALL FRESH	17,100	13,300	206	2,750,000	200,000	2,550,000	3.03	7,738,000
Spring Pickles	700	700	125	88,000		88,000	1.25	110,000
TOTAL	17,800	14,000	203	2,838,000	200,000	2,638,000	2.97	7,845,000
EGGPLANT			Bu.					
Fall	650	650	120	78,000		78,000	2.65	207,000
Winter	600	500	275	138,000		138,000	3.30	455,000
Spring	900	900	425	382,000		382,000	1.45	554,000
TOTAL	2,150	2,050	292	598,000		598,000	2.03	1,216,000
ESCAROLE & ENDIVE			Bu.					
Winter	4,700	4,400	470	2,068,000	468,000	1,600,000	1.40	2,240,000
LETTUCE (Boston & Iceberg)			4-6 doz. Crt.					
Winter	2,700	2,400	160	384,000	48,000	336,000	2.65	890,000
PEAS, ENGLISH	400	400	Bu. 65	26,000		26,000	2.75	72,000
PEPPERS			Bu.					
Fall	500	400	115	46,000		46,000	5.55	255,000
Winter	2,500	2,500	400	1,000,000		1,000,000	3.15	3,150,000
Spring	9,800	9,600	235	2,256,000	200,000	2,056,000	1.65	3,392,000
TOTAL	12,800	12,500	264	3,302,000	200,000	3,102,000	2.19	6,797,000
POTATOES			Bu.					
Winter	8,600	8,500	250	2,125,000		2,125,000	2.45	5,206,000
Spring	14,600	14,600	266	3,879,000		3,879,000	1.80	6,982,000
TOTAL	23,200	23,100	260	6,004,000		6,004,000	2.03	12,188,000

A - Abandoned because of poor market prices at certain times during the season.

ACREAGE, YIELD, PRODUCTION AND VALUE
FLORIDA VEGETABLES AND MISCELLANEOUS FRUITS
1950-51 SEASON

FLORIDA	Acreage Planted	Acreage For Harvest	Yield Units	Production Total Units	Abandoned A Units	Production of Value Units	Season Avg FOB Price PerUnit	Total Value Marketed Dollars
SQUASH			Bu.					
Fall	2,400	1,900	55	104,000		104,000	$4.15	$ 432,000
Winter	5,400	4,500	100	450,000	51,000	399,000	2.85	1,137,000
Spring	4,800	4,800	105	504,000		504,000	1.65	832,000
TOTAL	12,600	11,200	94	1,058,000	51,000	1,007,000	2.38	2,401,000
TOMATOES			Bu.					
Fall(Fresh)	11,200	9,400	85	799,000		799,000	7.45	5,953,000
(Process)	1,000	1,000	85	85,000		85,000	1.10	94,000
(Total)	12,200	10,400	85	884,000		884,000	6.84	6,047,000
Winter(Fresh)	13,500	13,000	165	2,145,000		2,145,000	7.95	17,053,000
(Process)	1,500	1,500	165	248,000		248,000	1.05	260,000
(Total)	15,000	14,500	165	2,393,000		2,393,000	7.23	17,313,000
Spring(Fresh)	23,500	23,500	190	4,465,000		4,465,000	5.30	23,664,000
(Process)	2,500	2,500	190	475,000		475,000	1.05	499,000
(Total)	26,000	26,000	190	4,940,000		4,940,000	4.89	24,163,000
TOTAL FRESH	48,200	45,900	161	7,409,000		7,409,000	6.30	46,670,000
TOTAL PROCESS	5,000	5,000	162	808,000		808,000	1.05	853,000
TOTAL ALL	53,200	50,900	161	8,217,000		8,217,000	5.78	47,523,000
TOTAL VEGS.	280,200	255,200	(Packed Value per Acre Harvested $526.00)					$133,355,000
CANTALOUPES	1,500	1,400	60Crt.	84,000		84,000	4.10	344,000
STRAWBERRIES			Crt.(24 qt)					
Winter	6,500	6,500	60	390,000		390,000	10.60	4,134,000
			Melons				Per Melon	
WATERMELONS	64,000	62,000	300	18,600,000		18,600,000	.46½	8,649,000
TOTAL MISCL.FRUITS	72,000	69,900	(Packed Value per Acre Harvested $188.00)					$ 13,127,000
GRAND TOTAL	352,200	325,100	(Packed Value per Acre Harvested $420.00)					$146,482,000

A- Abandoned because of poor market price at certain times during the season.

ACREAGE, YIELD, PRODUCTION AND VALUE OF ALL FRUITS AND VEGETABLES -- 1950-51 SEASON

	Acres Planted	Abandoned	Acres Harves.	Yield per Acre	Unit	Production Units(000) Total	Abandoned	Used	Price per Unit	Total Value
Beans	89,400	14,400	75,000	89	Bu.	6,657	439	6,218	$2.78	$ 17,262,000
Limas	3,100	300	2,800	70	Bu.	196	-	196	2.81	551,000
Cabbage	19,000	-	19,000	10.2	Ton	156	38	194	67.00	10,42[illegible],000
Cauliflower	1,200	200	1,000	280	Crt.	280	-	280	2.10	588,000
Celery	10,750	100	10,650	632	Crt.	6,671	60	6,731	2.40	16,021,000
Corn,Grn	27,200	1,400	25,800	113	Crt.	2,927	-	2,927	2.50	7,313,000
Cucumbers	17,800	3,800	14,000		Bu.	2,838	200	2,638	2.97	7,848,000
Eggplant	2,150	100	2,050	292	Bu.	598	-	598	2.03	1,216,000
Escarole&Endive	4,700	300	4,400	470	Bu.	1,600	468	2,068	1.40	2,240,000
Lettuce	2,700	300	2,400	160	Crt.	336	48	384	2.65	890,000
Peas,Eng.	400	-	400	65	Bu.	26	-	26	2.73	72,000
Peppers	12,800	300	12,500	264	Bu.	3,102	200	3,302	2.19	6,797,000
Potatoes,Coml.	23,200	100	23,100	260	Bu.	6,004	-	6,004	2.03	12,1[illegible],000
Squash	12,600	1,400	11,200	94	Bu.	1,007	51	1,058	2.38	2,401,000
Tomatoes	53,200	2,300	50,900	161	Bu	8,217	-	8,217	5.78	47,523,000
TOTAL VEGS.	280,200	25,000	255,200	(Packed Value per Acre Harvested $526)						133,355,000
Cantaloupes	1,500	100	1,400	60	Crt.	84	-	84	4.10	344,000
Strawberries	6,500	-	6,500	60	24qt crt	390	-	390	10.60	4,134,000
Watermelons	64,000	2,000	62,000	300	Melon	18,600	-	18,600	.46½	8,649,000
TOT.MISCL.FR.	72,000	2,100	69,900	(Packed Value per Acre Harvested $188)						13,127,000
TOT.VEGS.AND MISCL.FRTS.	352,200	27,100	325,100	(Packed Value per Acre Harvested $420)						$146,482,000
Oranges	-	-	309,500	211*	Box	67,300	-	67,300	$2.33	$156,5[illegible],275
Grapefruit	-	-	100,000	332	"	33,200	-	33,200	1.74	57,[illegible],066
Tangerines	-	-	24,200	199	"	4,800	200	4,600	3.24	14,894,083
TOTAL CITRUS	-	-	433,700	243	"	105,300	200	105,100	2.18	229,259,424
			Citrus(Packed Value per Acre Harvested $529)							
GRAND TOTAL	-	-	758,800	(Packed Value per Acre Harvested $495)						$375,741,424

* On basis of 66 trees to acre, box yields would be: Oranges 211, Grapefruit 332, Tangerines 199. All 243 boxes.

Note: The above does not include an estimated 10,000-15,000 acres of miscellaneous vegetables such as radishes, collards, turnips, okra, etc., and does not include acreage figures for avocados, limes, mangoes and other miscellaneous fruits. The official acreage, volume and value figures supplied by the U.S. Bureau of Agricultural Economics, Orlando, Florida.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS

BEANS, SNAP

Season	Harvested Acreage	Yield Bu.	Harvested Production	Abandoned Volume(A)	Volume Used	Price per Bu. Fresh	Price per Bu. Canned	FOB Packed Total Value
1932-33	50,800	98	5,002,000	144,000	4,858,000	$ .90	$	$ 4,356,000
1933-34	61,300	101	6,216,000	430,000	5,786,000	1.00		5,773,000
1934-35	65,500	76	4,948,000	-	4,948,000	1.21		5,967,000
1935-36	59,200	71	4,183,000	-	4,183,000	1.49		6,250,000
1936-37	58,800	80	4,688,000	-	4,688,000	1.50		7,037,000
1937-38	60,700	89	5,381,000	-	5,381,000	1.17		6,272,000
1938-39	64,000	111	7,135,000	288,000	6,847,000	1.03		7,041,000
1939-40	52,000	98	5,090,000	--	5,090,000	1.47		7,430,000
1940-41	62,500	92	5,780,000	-	5,780,000	1.55		8,933,000
1941-42	68,000	105	5,783,000	-	5,783,000	1.84	.91	11,913,000
1942-43	80,000	131	7,795,000	-	7,795,000	2.62	1.27	17,989,000
1943-44	96,500	86	8,273,000	269,000	8,004,000	2.56	1.29	18,713,000
1944-45	80,500	92	7,440,000	496,000	6,244,000	2.92	1.67	18,405,000
1945-46	80,200	106	8,469,000	1,240,000	7,229,000	2.73	1.67	18,359,000
1946-47	81,700	80	6,549,700	561,000	5,988,700	2.90	1.67	16,389,000
1947-48	71,700	82	5,898,000	225,000	5,673,000	2.57	1.54	14,484,000
1948-49	79,000	106	8,389,000	1,154,000	7,235,000	(F)2.43	(C)1.63(Av)2.01	16,884,000
1949-50	73,300	101	7,368,000	286,000	7,082,000	(F)2.49	(C)1.41(Av)2.45	17,354,000
1950-51	75,000	89	6,657,000	439,000	6,218,000	2.91	(C)1.86(Av)2.78	17,282,000

For Canning: 1941-42 bu. 1,367,000; 1942-43 bu. 2,677,000; 1943-44 bu. 1,268,000; 1944-45 bu. 1,486,000; 1945-46 bu 1,106,000; 1946-47 bu 800,700; 1947-48 bu. 583,000; 1948-49 bu. 843,000; 1949-50 bu. 878,000; 1950-51 bu. 752,000.

LIMAS

Season	Harvested Acreage	Yield Bu.	Harvested Production	Abandoned Volume(A)	Volume Used	Price Bu.	FOB Packed Total Value
1935-36	1,800	70	126,000	-	126,000	$1.60	$ 202,000
1936-37	2,400	65	156,000	-	156,000	2.50	390,000
1937-38	4,500	75	338,000	-	338,000	1.50	507,000
1938-39	4,800	100	480,000	-	480,000	1.50	720,000
1939-40	4,000	70	280,000	-	280,000	1.50	420,000
1940-41	7,000	40	280,000	-	280,000	2.20	616,000
1941-42	5,000	65	325,000	-	325,000	2.10	682,000
1942-43	5,400	59	321,000	-	321,000	3.31	1,041,000
1943-44	4,500	77	345,000	-	345,000	4.16	1,436,000
1944-45	4,800	88	420,000	14,000	406,000	4.38	1,779,000
1945-46	6,300	88	555,000	87,000	468,000	3.28	1,533,000
1946-47	5,200	65	338,000	-	338,000	3.51	1,187,000
1947-48	4,250	91	387,000	32,000	419,000	3.00	1,065,000
1948-49	3,050	105	319,000	-	319,000	2.97	946,000
1949-50	3,400	76	258,000	-	258,000	2.74	707,000
1950-51	2,800	70	196,000	-	196,000	2.81	551,000

CABBAGE

Season	Harvested Acreage	Yield Tons	Harvested Production	Abandoned Volume(A)	Volume Used	Price Ton	FOB Packed Total Value
1932-33	6,200	7.0	43,400	6,500	36,900	$16.00	$ 590,000
1933-34	10,700	6.0	64,200	21,400	42,800	16.00	685,000
1934-35	5,600	5.2	29,120	-	29,120	56.00	1,630,000
1935-36	9,000	4.0	36,000	-	36,000	17.00	612,000
1936-37	8,500	6.0	51,000	20,000	31,000	16.00	496,000
1937-38	9,400	6.5	61,000	-	61,000	16.00	978,000
1938-39	10,000	5.5	55,000	-	55,000	18.00	990,000
1939-40	16,000	7.0	112,000	-	112,000	18.40	2,061,000
1940-41	10,000	6.0	60,000	-	60,000	38.90	2,334,000
1941-42	18,000	6.0	108,000	-	108,000	17.80	1,602,000
1942-43	10,000	8.5	85,000	-	85,000	76.00	6,460,000
1943-44	23,500	7.1	166,800	47,100	119,700	36.00	4,309,000
1944-45	17,500	7.5	131,000	24,000	107,000	37.00	3,959,000
1945-46	13,200	8.8	116,200	2,500	113,700	49.00	5,571,000
1946-47	14,000	7.1	99,400	18,200	81,200	37.80	3,069,000
1947-48	16,100	9.0	144,900	21,100	123,800	52.50	6,500,000
1948-49	16,000	9.6	154,000	30,000	124,000	44.60	5,530,000
1949-50	17,000	10.8	183,600	56,900	126,700	30.50	3,864,000
1950-51	19,000	10.2	193,800	38,200	155,600	67.00	10,425,000

(A) Not harvested, due to economic abandonment. Values cover harvested portion of crop.

NOTE: All 1950-51 acreage figures are preliminary as of September 15, 1951 and are subject to revision. Revisions are usually of minor consequence.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd.)

CELERY

Season	Harvested Acreage	Yield N.Y.	Crts. Fla.	Harvested Production	(A) Abandoned	Volume Used	Price NY 2/3 Crates	FOB Packed Total Value	Price Fla. Crts.
1934-35	6,000	280	(467)	1,680,000	-	1,680,000	$2.00	$ [illegible]	1.5
1935-36	6,500	265	(442)	1,723,000	-	1,723,000	2.60	[illegible]	1.5
1936-37	7,500	280	(467)	2,097,000	-	2,097,000	2.16	1,522,000	1.3
1937-38	8,000	286	(477)	2,290,000	255,000	2,0[illegible],000	1.62	3,289,000	.
1938-39	7,300	299	(498)	2,184,000	-	2,184,000	2.46	5,375,000	1.4
1939-40	7,500	304	(507)	2,279,000	-	2,279,000	2.57	5,698,000	1.5
1940-41	9,100	278	(463)	2,531,000	-	2,531,000	3.19	[illegible]	1.9
1941-42	9,350	269	(465)	2,608,000	-	2,608,000	2.71	[illegible]	[illegible]
1942-43	8,750	-	447	4,175,500 (Fla.Crts.)		4,175,500	-	17,1[illegible],000	4.1
1943-44	9,900	-	502	4,969,000	400,000	4,569,000	-	14,530,000	3.
1944-45	11,050	-	493	5,448,000	102,000	5,346,000	-	18,5[illegible],000	3.4
1945-46	13,450	-	479	6,439,000	151,000	6,288,000	-	14,266,000	2.2
1946-47	11,700	-	390	4,564,000	-	4,564,000	-	17,535,000	3.8
1947-48	11,600	-	487	5,651,000	892,000	4,759,000	-	9,778,000	2.0
1948-49	9,500	-	581	5,518,000	181,000	5,337,000	-	16,021,000	3.0
1949-50	9,500	-	649	6,170,000	-	6,170,000	-	12,295,000	1.7
1950-51	10,650	-	632	6,731,000	60,000	6,671,000	-	16,021,000	2.1

(A) Not harvested, due to economic abandonment. Values cover harvested portion crops. Florida crates are approximately 60 per cent as large as NY 2/3 crates.

CUCUMBERS

Season	Harvested Acreage	Yield Bu.	Harvested Production	(A) Abandoned	Volume Used	Price per Bushel	FOB Packed Tot. Value
1934-35	5,100	93	473,000	-	473,000	$1.62	$ 765,000
1935-36	5,700	82	468,000	-	468,000	1.98	928,000
1936-37	5,600	65	364,000	-	364,000	3.02	1,101,000
1937-38	7,000	121	850,000	-	850,000	1.24	1,053,000
1938-39	7,600	115	876,000	-	876,000	1.58	1,391,000
1939-40	8,200	145	1,186,000	-	1,186,000	1.63	1,938,000
1940-41	8,800	121	1,064,000	-	1,064,000	1.75	1,853,000
1941-42	9,700	94	912,000	-	912,000	2.24	2,042,000
1942-43	6,500	80	520,000	-	520,000	4.98	2,592,000
1943-44	6,300	73	459,000	-	459,000	4.55	2,979,000
1944-45	7,700	110	844,000	-	844,000	4.31	3,637,000
1945-46	11,150	136	1,520,000	76,000	1,444,000	3.72	5,377,000
1946-47	13,775	87	1,204,000	-	1,204,000	4.14	4,984,000
1947-48	15,900	123	1,957,000	50,000	1,907,000	3.25	6,203,000
1948-49	15,500	124	1,800,000	46,000	1,754,000	(F)3.24(P)2.00(Av)3.17	5,558,000
1949-50	14,200	154	2,190,000	-	2,190,000	(F)3.38(P)1.25(Av)3.32	7,263,000
1950-51	14,000	203	2,838,000	200,000	2,638,000	(F)3.03(P)1.25(Av)2.97	7,818,000

F Indicates Fresh: P Indicates Pickles.

CARROTS

Season	Harvested Acreage	Yield Crts.	Harvested Production	(A) Abandoned	Volume Used	Price per Crate	FOB Packed Tot. Value
1947-48	450	200	90,000	-	90,000	$3.00	$ 270,000
1948-49	500	200	100,000	60,000	40,000	1.30	52,000
1949-50	None Reported	-	-	-	-	-	-
1950-51	None Reported	-	-	-	-	-	-

CAULIFLOWER

Season	Harvested Acreage	Yield Crts.	Harvested Production	(A) Abandoned	Volume Used	Price per Crate	FOB Packed Tot. Value
1947-48	400	200	80,000	-	80,000	$2.20	$ 176,000
1948-49	600	260	156,000	-	156,000	2.25	351,000
1949-50	850	300	255,000	-	255,000	1.85	472,000
1950-51	1,000	280	280,000	-	280,000	2.10	588,000

CORN, GREEN

Season	Harvested Acreage	Yield Crts.	Harvested Production	(A) Abandoned	Volume Used	Price per Crate	FOB Packed Tot. Value
1947-48	6,000	80	480,000	-	480,000	$2.75	$1,3[illegible]
1948-49	12,000	140	1,680,000	-	1,680,000	2.70	4,5[illegible]
1949-50	29,000	120	3,480,000	530,000	2,950,000	2.15	6,342,000
1950-51	25,900	113	2,927,000	-	2,927,000	2.50	7,313,000

ESCAROLE & ENDIVE

Season	Harvested Acreage	Yield 1½Bu.Hpr.	Harvested Production	(A) Abandoned	Volume Used	Price 1½Bu.Hpr.	FOB Packed Tot. Value
1938-39	1,000	440	440,000	-	440,000	$ .60	$ 264,000
1939-40	1,350	400	540,000	-	540,000	.56	302,000
1940-41	1,000	373	373,000	-	373,000	.98	366,000
1941-42	1,200	400	480,000	-	480,000	.68	326,000
1942-43	1,450	350	507,500	-	507,500	2.25	1,142,000
1943-44	2,350	425	999,000	438,000	561,000	1.15	645,000
1944-45	2,800	310	868,000	224,000	644,000	2.10	1,352,000
1945-46	2,500	374	935,000	-	935,000	1.20	875,000
1946-47	2,800	325 Bu.Hp.	910,000	-	910,000	1.30 Bu.Hp.	1,183,000
1947-48	3,200	430 " "	1,376,000	266,000	1,110,000	1.05 " "	1,165,000
1948-49	2,800	400 " "	1,120,000	-	1,120,000	1.50 " "	1,680,000
1949-50	3,300	450 " "	1,485,000	145,000	1,340,000	.95 " "	1,273,000
1950-51	4,400	470 " "	2,068,000	468,000	1,600,000	1.40 " "	2,240,000

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd).

EGGPLANT

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price per Bushel	FOB PACKED TOTAL VALUE
1933-34	2,050	187	384,000	-	384,000	$ .75	$ 289,000
1934-35	1,500	180	270,000	-	270,000	.79	212,000
1935-36	1,100	286	315,000	-	315,000	.65	268,000
1936-37	1,460	283	410,000	-	410,000	.79	323,000
1937-38	1,800	261	470,000	-	470,000	.76	366,000
1938-39	2,100	326	686,000	-	686,000	.75	514,000
1939-40	1,400	207	290,000	-	290,000	1.44	417,000
1940-41	1,800	180	324,000	-	324,000	1.17	378,000
1941-42	2,350	237	556,500	-	556,500	1.16	643,000
1942-43	1,950	278	541,500	-	541,500	2.39	1,294,000
1943-44	3,500	259	908,000	40,000	868,000	1.65	1,501,000
1944-45	3,250	271	880,000	-	880,000	2.06	1,814,000
1945-46	3,900	345	1,344,000	240,000	1,104,000	1.63	1,805,000
1946-47	3,300	220	725,000	-	725,000	2.42	1,758,000
1947-48	3,225	277	894,000	197,000	697,000	1.65	1,151,000
1948-49	3,300	271	894,000	-	894,000	1.63	1,456,000
1949-50	2,450	296	726,000	-	726,000	1.62	1,178,000
1950-51	2,050	292	598,000	-	598,000	2.03	1,216,000

LETTUCE (Boston and Romaine)

Season	Harvested Acreage	Yield 4-6 doz. Crts	Harvested Production	Abandoned (A)	Volume Used	Price Crates	FOB PACKED TOTAL VALUE
1940-41	500	150	75,000	-	75,000	$2.00	$ 150,000
1941-42	500	100	50,000	-	50,000	2.60	130,000
1942-43	800	175	140,000	-	140,000	3.05	427,000
1943-44	1,100	150	165,000	59,000	106,000	2.15	228,000
1944-45	400	200	80,000	-	80,000	2.70	216,000
1945-46	550	258	142,000	17,000	125,000	3.00	375,000
1946-47	700	100	70,000	-	70,000	2.95	206,000
1947-48	550	125	69,000	23,000	46,000	2.05	94,000

LETTUCE (Iceberg) 4-6 doz. crates

1940-41	2,000	75	150,000	-	150,000	$1.83	$ 274,000
1941-42	3,000	55	165,000	-	165,000	2.16	356,000
1942-43	1,700	135	230,000	-	230,000	3.97	913,000
1943-44	1,350	143	193,000	78,000	115,000	2.90	334,000
1944-45	1,000	143	143,000	24,000	119,000	3.51	418,000
1945-46	1,300	165	214,000	20,000	194,000	3.72	910,250
1946-47	1,125	107	119,000	-	119,000	2.97	353,000
1947-48	1,100	118	130,000	10,000	120,000	2.88	346,000

LETTUCE (All)

1948-49	1,500	125	188,000	-	188,000	$3.10	$ 583,000
1949-50	2,200	160	352,000	64,000	288,000	2.80	806,000
1950-51	2,400	160	384,000	48,000	336,000	2.65	890,000

SQUASH

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price Bushels	FOB PACKED TOTAL VALUE
1947-48	7,900	82	651,000	-	651,000	$2.83	$ 1,839,250
1948-49	9,000	91	817,000	-	817,000	2.76	2,225,000
1949-50	10,100	85	860,000	-	860,000	2.40	2,060,000
1950-51	11,200	94	1,058,000	51,000	1,007,000	2.38	2,401,000

PEAS, ENGLISH

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price Bushels	FOB PACKED TOTAL VALUE
1934-35	5,000	80	400,000	-	400,000	$1.30	$ 520,000
1935-36	8,200	62	508,000	-	508,000	1.00	508,000
1936-37	6,200	50	310,000	-	310,000	1.35	418,000
1937-38	6,200	90	558,000	-	558,000	1.15	642,000
1938-39	5,000	70	350,000	-	350,000	1.85	648,000
1939-40	5,000	90	450,000	75,000	375,000	1.30	488,000
1940-41	3,000	70	210,000	-	210,000	1.95	410,000
1941-42	3,500	70	245,000	-	245,000	1.55	380,000
1942-43	1,500	65	98,000	-	98,000	2.60	254,000
1943-44	2,500	60	150,000	-	150,000	3.00	450,000
1944-45	2,600	75	195,000	90,000	105,000	2.70	284,000
1945-46	1,600	74	118,000	5,000	113,000	3.00	339,000
1946-47	1,600	40	64,000	-	64,000	2.95	189,000
1947-48	600	60	36,000	-	36,000	2.55	92,000
1948-49	400	40	16,000	-	16,000	2.62	42,000
1949-50	400	60	24,000	-	24,000	2.80	67,000
1950-51	400	65	26,000	-	26,000	2.75	72,000

(A) Not harvested due to economic abandonment.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd)

PEPPERS, GREEN

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price per Bushel	FOB PACKED TOTAL VALUE
1932-33	8,300	266	2,210,000	-	2,210,000	$ .58	$ 1,284,000
1933-34	6,000	241	1,446,000	-	1,446,000	1.16	1,676,000
1934-35	7,700	149	1,150,000	-	1,150,000	1.11	1,277,000
1935-36	6,500	226	1,467,000	-	1,467,000	.87	1,273,000
1936-37	7,200	221	1,590,000	-	1,590,000	1.20	1,905,000
1937-38	7,400	295	2,180,000	-	2,180,000	.77	1,668,000
1938-39	7,300	303	2,212,000	-	2,212,000	1.25	2,771,000
1939-40	6,200	224	1,390,000	-	1,390,000	1.53	2,121,000
1940-41	7,200	225	1,621,500	-	1,621,500	1.56	2,537,000
1941-42	6,500	276	1,792,000	-	1,792,000	1.75	3,133,000
1942-43	7,100	284	2,018,000	-	2,018,000	2.93	5,917,000
1943-44	8,950	265	2,371,000	86,000	2,285,000	2.16	4,964,000
1944-45	9,350	287	2,687,000	-	2,687,000	2.46	6,623,000
1945-46	11,080	275	3,050,000	380,000	2,670,000	2.45	6,545,000
1946-47	10,550	208	2,193,000	-	2,193,000	4.14	9,086,000
1947-48	11,450	250	2,860,000	143,000	2,717,000	2.17	5,886,000
1948-49	11,100	268	2,972,000	-	2,972,000	2 55	7,567,000
1949-50	13,750	292	4,015,000	175,000	3,840,000	1.87	7,188,000
1950-51	12,500	264	3,302,000	200,000	3,102,000	2.19	6,797,000

POTATOES

Season	Harvested Acreage	Yield Bushels	Harvested Production	Abandoned (A)	Volume Used	Price per Bushel	FOB PACKED TOTAL VALUE
1932-33	17,000	132	2,244,000	-	2,244,000	$ .85	$ 1,908,000
1933-34	23,500	140	3,290,000	-	3,290,000	1.13	3,708,000
1934-35	24,800	97	2,406,000	-	2,406,000	1.04	2,503,000
1935-36	24,500	91	2,235,000	-	2,235,000	1.43	3,187,000
1936-37	31,300	123	3,842,000	-	3,842,000	1.32	5,037,000
1937-38	31,400	133	4,177,000	-	4,177,000	.70	2,939,000
1938-39	26,700	121	3,235,000	-	3,235,000	1.13	3,644,000
1939-40	25,600	157	4,020,000	-	4,020,000	.93	3,725,000
1940-41	26,800	117	3,126,000	-	3,126,000	.90	2,799,000
1941-42	25,000	154	3,848,000	-	3,848,000	1.54	5,924,000
1942-43	26,200	134	3,523,000	-	3,523,000	1.96	5,914,000
1943-44	28,600	112	3,212,000	-	3,212,000	2.00	6,431,000
1944-45	31,100	162	5,035,000	-	5,035,000	2.39	12,033,000
1945-46	35,300	170	6,010,000	-	6,010,000	1.95	11,744,000
1946-47	24,100	114	2,738,000	-	2,738,000	2.00	5,475,000
1947-48	20,800	174	3,614,000	-	3,614,000	2.79	10,073,000
1948-49	20,300	264	5,362,000	-	5,362,000	2.30	12,316,000
1949-50	23,200	231	5,370,000	-	5,370,000	1.79	9,609,000
1950-51	23,100	260	6,004,000	-	6,004,000	2.03	12,188,000

TOMATOES

Season	Harvested Acreage	Yield Bu.	Harvested Prod. Fresh	Harvested Prod. Canning	Abandoned (A)	Volume Used	Price Bu. Fresh	Price Bu. Canned	FOB PACKED TOT.VALUE
1932-33	24,900	94	2,343,000	-	-	2,343,000	$1.87	$ -	$ 4,377,000
1933-34	30,500	113	2,886,000	557,000	-	3,443,000	2.86	.39	8,476,000
1934-35	32,500	102	2,714,000	589,000	-	3,303,000	2.46	.28	6,835,000
1935-36	32,600	100	2,954,000	321,000	-	3,275,000	2.75	.31	8,224,000
1936-37	35,700	86	2,746,000	314,000	-	3,060,000	2.76	.32	7,688,000
1937-38	45,300	120	4,953,000	500,000	-	5,453,000	1.73	.28	8,711,000
1938-39	40,700	129	4,948,000	312,000	-	5,260,000	2.47	.28	12,323,000
1939-40	34,000	88	3,225,000	232,000	-	3,457,000	2.53	.28	8,216,000
1940-41	26,500	110	2,765,000	165,000	-	2,930,000	3.10	.28	8,613,000
1941-42	43,000	101	3,412,000	951,000	-	4,363,000	3.92	.46	13,821,000
1942-43	25,500	102	2,226,000	*	-	2,226,000	5.30	*	11,795,000
1943-44	34,900	109	3,405,000	395,000	-	3,800,000	5.72	.59	19,712,000
1944-45	32,500	137	4,456,000	289,000	342,000	4,403,000	5.27	.72	20,376,000
1945-46	30,400	154	4,670,000	265,000	221,000	4,714,000	5.25	.74	22,405,000
1946-47	29,800	107	3,198,000	306,000	-	3,504,000	6.50	1.00	19,098,000
1947-48	30,200	130	3,588,000	346,000	-	3,934,000	5.83	.75	22,936,000
1948-49	38,200	183	6,300,000	675,000	-	6,975,000	F5.12	C.64Av4.68	32666,000
1949-50	42,500	163	6,448,000	469,000	-	6,917,000	F4.96	C.50Av4.66	32247,000
1950-51	50,900	161	7,409,000	808,000	-	8,217,000	F6.30	C1.05A5.78	47,523,000

A - Not harvested, due to economic abandonment (poor markets).
All 1950-51 acreage figures are preliminary as of September 15, 1951, and are subject to revision.

* Separate volume and price not available for 1942-43 season.

ACREAGE, YIELD AND VALUE OF SELECTED COMMODITIES IN FLORIDA BY SEASONS (Cont'd).

CANTALOUPES

Season	Harvested Production	Yield Crates	Harvested Production	Abandoned (A)	Volume Used	Price per Crate	FOB PACKED TOT.VALUE
1932-33	400	60	24,000	-	24,000	$1.00	$ 24,000
1933-34	300	60	18,000	-	18,000	1.30	23,000
1934-35	200	60	12,000	-	12,000	1.50	18,000
1935-36	200	60	12,000	-	12,000	1.25	15,000
1936-37	300	55	16,000	-	16,000	1.75	28,000
1937-38	700	75	52,000	-	52,000	1.25	65,000
1938-39	500	80	40,000	-	40,000	1.10	44,000
1939-40	500	70	35,000	-	35,000	1.10	38,000
1940-41	500	60	30,000	-	30,000	1.25	38,000
1941-42	500	70	35,000	-	35,000	1.50	52,000
1942-43	400	65	26,000	-	26,000	3.25	85,000
1943-44	550	60	33,000	-	33,000	3.75	124,000
1944-45	500	50	25,000	5,000	20,000	6.00	120,000
1945-46	800	45	36,000	18,000	18,000	3.00	54,000
1946-47	800	50	40,000	-	40,000	2.55	102,000
1947-48	1,200	65	78,000	-	78,000	4.35	339,000
1948-49	1,200	40	48,000	-	48,000	4.00	192,000
1949-50	1,400	60	84,000	-	84,000	2.25	189,000
1950-51	1,400	60	84,000	-	84,000	4.10	344,000

(A) Crates not harvester due to economic abandonment.

STRAWBERRIES

Season	Harvested Production	24-Qt. Crates	Harvested Production	Abandoned (A)	Volume Used	(48 Pts.) 24 Qts.*	FOB Packed Total Value	36 Pt. Crate
1932-33	10,600	73	774,000	-	774,000	$3.00	$2,322,000	$2.25
1933-34	8,400	75	630,000	-	630,000	4.20	2,646,000	3.15
1934-35	8,000	65	520,000	-	520,000	4.30	2,236,000	3.23
1935-36	8,900	54	481,000	-	481,000	4.10	1,972,000	3.08
1936-37	8,800	65	572,000	-	572,000	4.80	2,746,000	3.60
1937-38	7,500	70	525,000	-	525,000	4.00	2,100,000	3.00
1938-39	9,000	85	765,000	-	765,000	4.15	3,175,000	3.11
1939-40	7,200	70	504,000	-	504,000	4.65	2,344,000	3.49
1940-41	5,500	70	384,000	-	384,000	5.70	2,194,000	4.28
1941-42	5,000	70	350,000	-	350,000	6.50	2,275,000	4.88
1942-43	2,600	60	156,000	-	156,000	9.60	1,498,000	7.20
1943-44	1,400	70	98,000	-	98,000	11.30	1,107,000	8.47
1944-45	2,050	70	144,000	-	144,000	10.70	1,541,000	8.03
1945-46	2,800	80	224,000	-	224,000	10.55	2,363,000	7.92
1946-47	4,750	65	309,000	-	309,000	12.10	3,739,000	9.08
1947-48	4,200	45	189,000	-	189,000	10.60	2,003,000	7.95
1948-49	4,000	55	220,000	-	220,000	10.91	2,401,000	8.18
1949-50	5,400	80	432,000	-	432,000	8.69	3,737,000	6.49
1950-51	6,500	60	390,000	-	390,000	10.60	4,134,000	7.95

* Now shipped almost exclusively in 36-pt. crates. The 24-qt.crate was formerly used, and it is continued here for statistical purposes. Florida crate is 75% as large.

WATERMELONS

Season	Harvested Production	Yield Melons	Harvested Production	Abandoned (A)	Volume Used	Price per 1000 melons	FOB PACKED TOT.VALUE
1932-33	22,500	200	4,950,000	-	4,950,000	$200	$ 990,000
1933-34	23,400	180	4,212,000	-	4,212,000	185	779,000
1934-35	20,000	330	6,600,000	-	6,600,000	110	726,000
1935-36	16,000	280	4,480,000	-	4,480,000	200	896,000
1936-37	19,500	300	5,850,000	390,000	5,460,000	240	1,310,400
1937-38	22,500	310	6,975,000	675,000	6,300,000	150	945,000
1938-39	22,600	240	5,424,000	-	5,424,000	180	976,000
1939-40	23,500	290	6,815,000	-	6,815,000	175	1,193,000
1940-41	25,500	270	6,885,000	-	6,885,000	210	1,445,850
1941-42	22,000	325	7,150,000	-	7,150,000	225	1,602,000
1942-43	12,500	325	4,063,000	-	4,063,000	650	2,641,000
1943-44	25,500	305	7,778,000	-	7,778,000	655	5,095,000
1944-45	39,000	260	10,140,000	-	10,140,000	485	4,918,000
1945-46	47,000	225	10,575,000	-	10,575,000	525	5,552,000
1946-47	47,000	290	13,623,000	-	13,623,000	447	5,419,000
1947-48	45,000	305	13,725,000	-	13,725,000	500	6,862,000
1948-49	59,000	240	14,160,000	-	14,160,000	450	6,372,000
1949-50	63,000	300	18,900,000	4,900,000	14,000,000	395	5,530,000
1950-51	62,000	300	18,600,000	-	18,600,000	465	8,649,000

A - Not harvested due to economic abandonment. Not included in total value figures. The average carload is figured at 1000 melons but new varieties of round type melons have made a range mostly 800-1200 melons per car. Average in 1951 was 1054 melons per car.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES FOR 1950-51 SEASON

Source: U.S. Agricultural Statisticians, Orlando, Florida.

	Fall	Win.	Spr.	Total
ALACHUA				
Beans	50	-	1500	1559
Limas	-	-	875	875
Cabbage	-	100	-	100
Celery *	-	60	400	460
Corn, Green	-	-	250	250
Cucumbers	-	-	1400	1400
Eggplant	25	-	75	100
Lettuce & Romaine	-	50	-	50
Peppers	-	-	1000	1000
Potatoes	-	-	400	400
Squash	75	-	400	475
Total Vegs.	150	210	6300	6660
Cantaloupes	-	-	-	350
Watermelons	-	-	-	6100
Grand Total	150	210	6300	13110
BRADFORD				
Beans	-	-	200	200
Limas	-	-	125	125
Cabbage	-	25	-	25
Corn, Green	-	-	1200	1200
Cucumbers	-	-	100	100
Peppers	-	-	300	300
Potatoes	-	-	100	100
Squash	-	-	150	150
Total Vegs.	-	25	2175	2200
Cantaloupes	-	-	-	25
Strawberries	-	400	-	400
Watermelons	-	-	-	175
Grand Total	-	425	2175	2800
BREVARD				
Corn, Green	-	-	200	200
Squash	25	-	-	25
Tomatoes	1000	-	1100	2100
Total Vegs.	1025	-	1300	2325
BROWARD				
Beans	3500	13500	800	17300
Limas	-	150	100	250
Corn, Green	-	-	300	300
Cucumbers	50	25	100	175
Eggplant	25	75	175	275
Peas, Green	-	25	-	25
Peppers	25	800	1000	1825
Squash	200	1300	400	1900
Tomatoes	50	200	300	550
Total Vegs.	3850	16075	3175	23100
CALHOUN				
Cucumbers	-	-	250	250
Watermelons	-	-	-	500
Grand Total	-	-	250	750
CHARLOTTE				
Cucumbers	100	-	150	250
Peppers	25	-	-	25
Tomatoes	50	-	-	50
Total Vegs.	175	-	150	325
Watermelons	-	-	-	150
Grand Total	175	-	150	475
CITRUS				
Watermelons	-	-	-	900
CLAY				
Cabbage	-	300	-	300
Potatoes	-	-	50	50
Grand Total	-	300	50	350

* Alachua & Marion combined: Winter 60, Spring 400. Total 460.

	Fall	Win.	Spr.	Total
COLLIER				
Cucumbers	250	125	700	1075
Peppers	-	50	-	50
Squash	50	75	50	175
Tomatoes	1000	800	1300	3100
Total Vegs.	1300	1050	2050	4400
Cantaloupes	-	-	-	25
Watermelons	-	-	-	650
Grand Total	1300	1050	2050	5075
COLUMBIA				
Cabbage	-	50	-	50
Corn, Green	-	-	100	100
Cucumbers	-	-	100	100
Total Vegs.	-	50	200	250
Watermelons	-	-	-	500
Grand Total	-	50	200	750
DADE				
Beans	-	3900	1800	5700
Cabbage	-	300	-	300
Cauliflower	-	75	-	75
Corn, Green	-	-	1200	1200
Cucumbers	-	-	400	400
Lettuce & Romaine	-	50	-	50
Peppers	-	50	50	100
Potatoes	-	5800	-	5800
Squash	75	1500	300	1875
Tomatoes	-	12000	5600	17600
Total Vegs.	75	23675	9350	33100
Strawberries	-	50	-	50
Watermelons	-	-	-	50
Grand Total	75	23725	9350	33200
DE SOTO				
Cucumbers	150	-	50	200
Tomatoes	-	-	200	200
Total Vegs.	150	-	250	400
Watermelons	-	-	-	275
Grand Total	150	-	250	675
DIXIE				
Watermelons	-	-	-	100
DUVAL				
Cabbage	-	100	-	100
ESCAMBIA				
Beans	-	-	100	100
Cabbage	-	100	-	100
Potatoes	-	-	600	600
Total Vegs.	-	100	700	800
FLAGLER				
Cabbage	-	1700	-	1700
Potatoes	-	-	2450	2450
Total Vegs.	-	1700	2450	4150
GADSDEN				
Beans	300	-	200	500
GILCHRIST				
Cucumbers	-	-	150	150
Squash	-	-	50	50
Total Vegs.	-	-	200	200
Watermelons	-	-	-	6200
Grand Total	-	-	200	6400

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES FOR 1950-51 SEASON

	Fall	Win.	Spr.	Total
GLADES				
Cabbage	-	900	-	900
Corn, Green	-	-	300	300
Lettuce & Romaine	-	550	-	550
Tomatoes	450	-	700	1150
Total Vegs.	450	1450	1000	2900
HAMILTON				
Cabbage	-	50	-	50
Cucumbers	-	-	150	150
Peppers	-	-	50	50
Total Vegs.	-	50	200	250
Cantaloupes	-	-	-	100
Watermelons	-	-	-	200
Grand Total	-	50	200	550
HARDEE				
Beans	-	-	50	50
Corn, Green	-	-	300	300
Cucumbers	800	-	500	1300
Eggplant	225	-	25	250
Peppers	150	-	100	250
Squash	125	-	100	225
Tomatoes	250	-	1000	1250
Total Vegs.	1550	-	2075	3625
Strawberries	-	425	-	425
Watermelons	-	-	-	400
Grand Total	1550	425	2075	4450
HENDRY				
Cucumbers	250	100	300	650
Squash	50	75	50	175
Tomatoes	500	600	750	1850
Total Vegs.	800	775	1100	2675
Watermelons	-	-	-	400
Grand Total	800	775	1100	3075
HERNANDO				
Eggplant	65	-	-	65
Watermelons	-	-	-	600
Grand Total	65	-	-	665
HIGHLANDS				
Beans	200	-	-	200
Cucumbers	50	-	50	100
Total Vegs.	250	-	50	300
Watermelons	-	-	-	150
Grand Total	250	-	50	450
HILLSBOROUGH				
Beans	300	-	800	1100
Limas	-	-	50	50
Cabbage	-	375	-	375
Cauliflower	-	400	-	400
Corn, Green	75	-	1700	1775
Cucumbers	300	-	1025	1325
Eggplant	25	25	225	275
Escarole	-	-	-	50
Lettuce & Romaine	-	250	-	250
Peas, Green	-	50	-	50
Peppers	-	-	3250	3250
Potatoes	-	125	425	550
Squash	300	--	1225	1525
Tomatoes	1100	200	1650	2950
Total Vegs.	2100	1425	10350	13925
Cantaloupes	-	-	-	25
Strawberries	-	4900	-	4900
Watermelons	-	-	-	1400
Grand Total	2100	6325	10350	20250

	Fall	Win.	Spr.	Total
HOLMES				
Cucumbers	-	-	50	50
Watermelons	-	-	-	700
Grand Total	-	-	50	750
INDIAN RIVER				
Squash	50	100	100	250
Tomattoes	1200	-	1200	2400
Total Vegs.	1250	100	1300	2650
Watermelons	-	-	-	450
Grand Total	1250	100	1300	3100
JACKSON				
Cucumbers	-	-	300	300
Watermelons	-	-	-	2000
JEFFERSON				
Cucumbers	-	-	150	150
Watermelons	-	-	-	1950
Grand Total	-	-	150	2100
LAFAYETTE				
Watermelons	-	-	-	1200
LAKE				
Beans	100	-	400	500
Cabbage	-	100	-	100
Celery (see note)	-	700	1115	1815
Corn, Green	-	-	*	*
Cucumbers	50	-	150	200
Peppers	-	-	200	200
Squash	-	-	25	25
Tomatoes	-	-	300	300
Total Vegs.	150	800	2190	3140
Cantaloupes	-	-	-	50
Watermelons	-	-	-	6800
Grand Total	150	800	2190	9990

Note: Lake & Orange Celery combined.
* Corn- Included with Orange County.

	Fall	Win.	Spr.	Total
LEE				
Corn, Green	-	-	500	500
Cucumbers	600	75	500	1175
Eggplant	75	225	-	300
Peppers	100	175	-	275
Potatoes	-	1400	-	1400
Squash	75	150	50	275
Tomatoes	100	100	150	350
Total Vegs.	950	2125	1200	4275
Watermelons	-	-	-	225
Grand Total	950	2125	1200	4500
LEON				
Watermelons	-	-	-	200
LEVY				
Beans	-	-	100	100
Peppers	-	-	50	50
Squash	25	-	50	75
Total Vegs	25	-	200	225
Cantaloupes	-	-	-	50
Watermelons	-	-	-	2100
Grand Total	25	-	200	2375
MADISON				
Cantaloupes	-	-	-	25
Watermelons	-	-	-	1800
Grand Total	-	-	-	1825

Figures subject to revision as of September 15, 1951.

FLORIDA VEGETABLE STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES FOR 1950-51 SEASON

	Fall	Win.	Spr.	Total
MANATEE				
Beans	250	-	300	550
Cabbage	-	300	-	300
Cauliflower	-	100	-	100
Corn, Green	75	-	350	425
Cucumbers	75	-	900	275
Eggplant	100	50	25	175
Escarole	-	-	-	50
Lettuce & Romaine	-	100	-	100
Peas, Green	-	25	-	25
Peppers	50	100	50	200
Squash	200	-	75	275
Tomatoes	1150	300	2550	4000
Total Vegs.	1900	975	4250	7175
Watermelons	-	-	-	100
Grand Total	1900	975	4250	7275
MARION				
Beans	150	-	1100	1250
Limas	-	-	100	100
Cabbage	-	275	-	275
Corn, Green	-	-	200	200
Cucumbers	50	-	250	300
Eggplant	50	-	25	75
Lettuce & Romaine	-	50	-	50
Peppers	-	-	150	150
Potatoes	-	-	50	50
Squash	250	-	900	1150
Tomatoes	-	-	1700	1700
Total Vegs.	500	325	4475	5300
Cantaloupes	-	-	-	325
Watermelons	-	-	-	6950
Grand Total	500	325	4475	12575
MARTIN				
Beans	50	100	350	500
Limas	-	50	-	50
Cabbage	-	100	-	100
Corn, Green	-	-	700	700
Cucumbers	150	100	300	550
Eggplant	-	25	-	25
Peppers	-	150	100	250
Squash	50	250	50	350
Tomatoes	850	300	600	1750
Total Vegs.	1100	1075	2100	4275
OKEECHOBEE				
Tomatoes	300	-	800	1100
Watermelons	-	-	-	50
Grand Total	300	-	800	1150
ORANGE				
Beans	100	-	50	150
Cabbage	-	350	-	350
Corn, Green	-	-	3400	3400
Cucumbers	150	-	250	400
Escarole	-	-	-	600
Lettuce & Romaine	-	200	-	200
Peppers	-	-	50	50
Total Vegs.	250	550	3750	5150
Watermelons	-	-	-	200
Grand Total	250	550	3750	5350
PASCO				
Cantaloupes	-	-	-	50
Watermelons	-	-	-	1800
Grand Total	-	-	-	1850

	Fall	Win.	Spr.	Total
PALM BEACH				
Beans	8000	19500	15200	42700
Limas	-	700	600	1300
Cabbage	-	6550	-	6550
Cauliflower	-	50	-	50
Celery	-	2500	1575	4075
Corn, Green	600	-	12000	12600
Cucumbers	100	75	150	325
Eggplant	-	75	275	350
Escarole	-	-	-	3100
Lettuce & Romaine	-	750	-	750
Peas, Green	-	250	-	250
Peppers	25	1100	1500	2625
Potatoes	-	1100	450	1550
Squash	225	1000	300	1525
Tomatoes	-	-	500	500
Total Vegs.	8950	33650	32550	78250
POLK				
Beans	-	-	250	250
Cabbage	-	100	-	100
Corn, Green	-	-	200	200
Cucumbers	-	-	50	50
Eggplant	-	-	25	25
Peppers	-	-	550	550
Potatoes	-	-	25	25
Squash	-	-	200	200
Tomatoes	-	-	100	100
Total Vegs.	-	100	1400	1500
Strawberries	-	550	-	550
Watermelons	-	-	-	1550
Grand Total	-	650	1400	3600
PUTNAM				
Cabbage	-	1500	-	1500
Corn, Green	-	-	50	50
Potatoes	-	-	2800	2800
Total Vegs.	-	1500	2850	4350
Watermelons	-	-	-	550
Grand Total	-	1500	2850	4900
ST. JOHNS				
Cabbage	-	2800	-	2800
Cauliflower	-	225	-	225
Corn, Green	-	-	50	50
Potatoes	-	-	7100	7100
Total Vegs.	-	3025	7150	10175
ST. LUCIE				
Cauliflower	-	50	-	50
Cucumbers	300	-	600	900
Peppers	-	25	150	175
Squash	25	-	50	75
Tomatoes	2300	-	2700	[illegible]
Total Vegs.	2625	75	3700	[illegible]
Watermelons	-	-	-	[illegible]
Grand Total	2625	75	3700	7000
SARASOTA				
Cabbage	-	175	-	175
Celery	-	815	160	975
Corn, Green	-	-	650	650
Cucumbers	-	-	75	75
Escarole	-	-	-	50
Lettuce & Romaine	-	75	-	75
Potatoes	-	-	25	25
Tomatoes	50	-	-	50
Total Vegs.	50	1065	910	2075
Watermelons	-	-	-	150
Grand Total	50	1065	910	2225

Figures subject to revision as of September 15, 1951.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES FOR 1950-51 SEASON

	Fall	Win.	Spr.	Total
SEMINOLE				
Beans	350	-	500	850
Cabbage	-	2300	-	2300
Cauliflower	-	75	-	75
Celery	-	2225	1100	3325
Corn, Green	-	-	600	600
Escarole	-	-	-	500
Lettuce & Romaine	-	125	-	125
Peas, Green	-	25	-	25
Peppers	-	-	150	150
Squash	-	-	100	100
Total Vegs.	350	4750	2450	8050
SUMTER				
Beans	50	-	600	650
Cabbage	-	50	-	50
Cucumbers	100	-	500	600
Eggplant	25	-	-	25
Lettuce & Romaine	-	50	-	50
Peppers	-	-	650	650
Squash	-	-	50	50
Tomatoes	-	-	2500	2500
Total Vegs.	175	100	4300	4575
Cantaloupes	-	-	-	125
Strawberries	-	100	-	100
Watermelons	-	-	-	3800
Grand Total	175	200	4300	8600
SUWANNEE				
Cabbage	-	50	-	50
Cucumbers	-	-	50	50
Total Vegs.	-	50	50	100
Cantaloupes	-	-	-	50
Watermelons	-	-	-	5400
Grand Total	-	50	50	5550
TAYLOR				
Watermelons	-	-	-	300
UNION				
Beans	100	-	100	200
Cabbage	-	50	-	50
Corn, Green	-	-	500	500
Cucumbers	50	-	50	100
Peppers	-	-	50	50
Potatoes	-	-	100	100
Squash	50	-	50	100
Total Vegs.	200	50	850	1100
Watermelons	-	-	-	225
Grand Total	200	50	850	1325

	Fall	Win.	Spr.	Total
VOLUSIA				
Cabbage	-	200	-	200
Lettuce & Romaine	-	100	-	100
Peppers	-	-	150	150
Squash	-	-	25	25
Total Vegs.	-	300	175	475
Watermelons	-	-	-	300
Grand Total	-	300	175	775
WALTON				
Cucumbers	-	-	100	100
WASHINGTON				
Cantaloupes	-	-	-	100
Watermelons	-	-	-	700
Grand Total	-	-	-	800
MISCELLANEOUS				
Beans	-	-	100	100
Limas	-	-	50	50
Cabbage	-	100	-	100
Cauliflower	-	25	-	25
Corn, Green	50	-	250	300
Cucumbers	25	-	50	75
Eggplant	35	25	50	110
Escarole	-	-	-	50
Lettuce & Romaine	-	50	-	50
Peas, Green	-	25	-	25
Peppers	25	50	50	125
Potatoes	-	75	25	100
Squash	50	50	50	150
Tomatoes	50	-	100	150
Total Vegs.	235	400	725	1410
Cantaloupes	-	-	-	100
Strawberries	-	75	-	75
Watermelons	-	-	-	150
Grand Total	235	475	725	1735

Figures subject to revision as of September 15, 1951.

FLORIDA VEGETABLE, STRAWBERRY AND WATERMELON ACREAGE BY COUNTIES AND SEASONS

TOTAL ALL COUNTIES

	1947-48				1948-49			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	21200	34300	19000	74500	26500	31500	20000	78000
Limas	-	1500	2350	3850	-	950	2100	3050
Cabbage	-	16700	-	16700	-	-	-	16000
Carrots	-	400	-	400	-	-	-	500
Cauliflower	-	400	-	400	-	-	-	600
Celery	-	6300	5300	11600	-	5000	4400	9400
Corn, Green	-	-	-	6000	-	-	-	14700
Cucumbers	4200	1550	8900	14650	4000	1300	7550	12850
Eggplant	500	330	2500	3330	700	800	1800	3300
Escarole	-	3100	-	3100	-	-	-	3000
Lettuce & Romaine	-	-	-	1750	-	-	-	1500
Peas, Green	-	600	-	600	-	-	-	400
Peppers	450	2450	8300	11200	850	3200	6700	10750
Potatoes	-	7300	13400	20700	-	8700	11900	20600
Squash	1700	2900	3300	7900	2500	3200	3300	9000
Tomatoes	2850	9600	15900	28350	7600	13000	18200	38300
Total Vegetables	30900	87430	78950	205030	42150	67650	75950	222450
Cantaloupes	-	-	1200	1200	-	-	-	1200
Strawberries	-	4200	-	4200	-	-	-	4000
Watermelons	-	-	45000	45000	-	-	-	59000
Grand Total	30900	91630	125150	255430	42150	67650	75950	286650

	1949-50				1950-51			
	Fall	Win.	Spr.	Total	Fall	Win.	Spr.	Total
Beans	17500	35600	24500	77600	13500	37000	24500	75000
Limas	-	950	2050	3000	-	900	1900	2800
Cabbage	-	17700	-	17700	-	19000	-	19000
Cauliflower	-	800	-	800	-	1000	-	1000
Celery	-	6000	3650	9650	-	6300	4350	10650
Corn, Green	-	-	28500	28500	800	-	25000	25800
Cucumbers	3700	2600	8000	14300	3600	500	9900	14000
Eggplant	500	900	1150	2550	650	500	900	2050
Escarole	-	-	-	3600	-	-	-	4100
Lettuce & Romaine	-	2400	-	2400	-	2400	-	2400
Peas, Green	-	300	-	300	-	400	-	400
Peppers	800	4400	9100	14300	400	2500	9600	12500
Potatoes	-	9800	13800	23600	-	8500	14600	23100
Squash	2300	4100	4400	10800	1900	4500	4800	11200
Tomatoes	8000	15700	18500	42200	10400	14500	26000	50900
Total Vegetables	32800	101250	113650	251300	31250	98000	121550	255200
Cantaloupes	-	-	-	1400	-	-	-	1400
Strawberries	-	5400	-	5400	-	6500	-	6500
Watermelons	-	-	-	68000	-	-	-	[illegible]
Grand Total	32800	106650	113650	326100	31250	104500	121550	325100

Figures subject to revision as of September 15, 1951.

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 26 SEASONS

(Available For Harvest)

Season	Beans Acreage	Limas Acreage	Cabbage Acreage	Carrots Acreage	Celery Acreage	Cauliflower Acreage	Cucumbers Acreage	Season
1925-26	16,000	(1)	3,660		3,520		7,590	1925-26
1926-27	19,490	(1)	3,010	Not	4,240		7,440	1926-27
1927-28	29,730	(1)	2,900	Reported	3,380		9,450	1927-28
1928-29	27,000	(1)	6,500	"	6,620		11,340	1928-29
1929-30	35,800	(1)	3,700	"	6,650		12,100	1929-30
1930-31	40,000	(1)	6,500	"	6,150		9,650	1930-31
1931-32	41,500	(1)	5,500	"	6,850		7,300	1931-32
1932-33	50,800	(1)	6,200	"	6,650		5,600	1932-33
1933-34	61,300	1,500	10,700	"	6,000		5,000	1933-34
1934-35	65,500	1,500	5,600	"	6,000		5,100	1934-35
1935-36	59,200	1,800	9,000	"	6,500		5,700	1935-36
1936-37	58,800	2,400	8,500	"	7,500		5,600	1936-37
1937-38	60,700	4,500	9,400	"	8,000		7,000	1937-38
1938-39	64,000	4,800	10,000	"	7,300		7,600	1938-39
1939-40	52,000	4,000	16,000	"	7,500		8,200	1939-40
1940-41	62,500	7,000	10,000	"	8,700		8,800	1940-41
1941-42	68,000	5,000	18,000	"	9,350		9,700	1941-42
1942-43	80,000	5,400	10,000	"	8,750		6,500	1942-43
1943-44	96,500	4,500	23,500	"	9,900		6,300	1943-44
1944-45	80,500	4,800	17,500	"	11,050		7,700	1944-45
1945-46	80,200	6,300	13,200	"	13,450		11,950	1945-46
1946-47	81,700	5,200	14,000	"	11,700		13,775	1946-47
1947-48	71,700	4,250	16,100	450	11,600	400	15,900	1947-48
1948-49	79,000	3,050	16,000	500	9,500	600	14,100	1948-49
1949-50	73,300	3,400	17,000	None reported	9,500	850	14,200	1949-50
1950-51	75,000	2,800	19,000	"	10,650	1,000	14,000	1950-51

NOTE: (1) Limas were included with snap beans prior to the 1933-34 season. The lima figures are for the Fordhook or large variety and do not include acreage of baby limas or butterbeans.

Season	Corn Acreage	Eggplant Acreage	*Endive & Escarole (2) Acreage	Boston Lettuce (3) Acreage	Iceberg Lettuce (4) Acreage	All Lettuce Acreage	English Peas Acreage	Season
1925-26		1,020	(2)	1,500	-	1,500	760	1925-26
1926-27		630	(2)	1,500	-	1,500	700	1926-27
1927-28		1,550	340	1,500	-	1,500	1,230	1927-28
1928-29		1,320	500	1,500	-	1,500	1,350	1928-29
1929-30		1,680	460	1,100	-	1,100	700	1929-30
1930-31		1,800	850	1,600	-	1,600	2,000	1930-31
1931-32		1,950	700	1,000	-	1,000	3,800	1931-32
1932-33		2,450	700	950	-	950	3,600	1932-33
1933-34		2,050	700	1,100	-	1,100	4,800	1933-34
1934-35		1,500	650	900	(4)	900	5,000	1934-35
1935-36		1,100	700	550	(4)	550	8,200	1935-36
1936-37		1,480	900	800	(4)	800	6,200	1936-37
1937-38		1,800	1,000	900	(4)	900	6,200	1937-38
1938-39		2,100	1,000	750	250	1,000	5,000	1938-39
1939-40		1,400	1,350	900	1,100	2,000	5,000	1939-40
1940-41		1,900	1,000	500	2,000	2,500	3,000	1940-41
1941-42		2,350	1,200	500	3,000	3,500	3,500	1941-42
1942-43		1,950	1,450	800	1,700	2,500	1,500	1942-43
1943-44		3,500	2,350	1,100	1,350	2,450	2,500	1943-44
1944-45		2,850	2,800	400	1,000	1,400	2,600	1944-45
1945-46		3,900	2,500	550	1,300	1,850	1,600	1945-46
1946-47		3,300	2,800	700	1,125	1,825	1,600	1946-47
1947-48	6,000	3,225	3,200	550	1,100	1,650	600	1947-48
1948-49	12,000	3,300	2,800	-	-	1,500(5)	400	1948-49
1949-50	29,000	2,450	3,300	-	-	2,200(5)	400	1949-50
1950-51	25,800	2,050	4,400	-	-	2,400(5)	400	1950-51

NOTES: (2) Escarole acreage included with lettuce prior to 1927-28 season.
(3) Big Boston figures include Romaine acreage.
(4) Iceberg Lettuce included in Big Boston acreage figures until the 1938-39 season.
(5) Iceberg, Boston and Romaine Lettuce combined.

* Endive included with Escarole beginning with the 1950-51 season.

ACREAGE OF PRINCIPAL FLORIDA TRUCK CROPS 26 SEASONS (Cont'd.)

(Available for Harvest)

Season	Peppers Acreage	Potatoes Acreage	Squash Acreage	Tomatoes Acreage	Total Vegetables Acreage	Season
1925-26	3,370	23,070		20,700	81,190	1925-26
1926-27	2,700	28,000		29,800	97,510	1926-27
1927-28	6,410	30,000		29,280	115,770	1927-28
1928-29	5,650	22,000		38,700	122,450	1928-29
1929-30	6,550	31,000		31,260	131,000	1929-30
1930-31	8,200	27,000		26,800	130,550	1930-31
1931-32	8,050	21,500		23,700	121,850	1931-32
1932-33	8,300	17,000		24,900	127,150	1932-33
1933-34	6,000	23,500		30,500	153,150	1933-34
1934-35	7,700	24,800		32,500	156,750	1934-35
1935-36	6,500	24,500		32,600	156,350	1935-36
1936-37	7,200	31,300		35,700	166,380	1936-37
1937-38	7,400	31,400		45,300	183,600	1937-38
1938-39	7,300	26,700		40,700	177,500	1938-39
1939-40	6,200	25,600		34,000	163,250	1939-40
1940-41	7,200	26,800		26,500	165,900	1940-41
1941-42	6,500	25,000		43,000	195,100	1941-42
1942-43	7,100	26,200		25,500	176,850	1942-43
1943-44	8,950	28,600		34,900	223,950	1943-44
1944-45	9,350	31,100		32,500	204,150	1944-45
1945-46	11,080	35,300		30,400	211,730	1945-46
1946-47	10,550	24,100		29,800	200,350	1946-47
1947-48	11,450	20,800	7,900	30,200	205,425	1947-48
1948-49	11,100	20,300	9,000	38,200	221,350	1948-49
1949-50	13,750	23,200	10,100	42,500	245,150	1949-50
1950-51	12,500	23,100	11,200	50,900	255,200	1950-51

Season	Cantaloupes (1) Acreage	Strawberries Acreage	Watermelons Acreage	Grand Total Officially Reported Acreage (2)	Season
1925-26	600	2,980	24,150	108,920	1925-26
1926-27	600	3,680	29,420	131,210	1926-27
1927-28	600	4,500	37,840	158,710	1927-28
1928-29	600	6,300	35,900	165,280	1928-29
1929-30	600	8,800	34,700	175,100	1929-30
1930-31	250	9,100	31,000	170,900	1930-31
1931-32	200	7,800	28,500	158,350	1931-32
1932-33	400	10,600	22,500	160,650	1932-33
1933-34	300	8,400	23,400	185,250	1933-34
1934-35	200	8,000	20,000	184,950	1934-35
1935-36	200	8,900	16,000	181,450	1935-36
1936-37	300	8,800	19,500	194,980	1936-37
1937-38	700	7,500	22,500	214,300	1937-38
1938-39	500	9,000	22,600	209,600	1938-39
1939-40	500	7,200	23,500	194,450	1939-40
1940-41	500	5,500	25,500	196,100	1940-41
1941-42	500	5,000	21,500	221,200	1941-42
1942-43	400	2,600	12,500	192,350	1942-43
1943-44	550	1,400	25,500	251,400	1943-44
1944-45	500	2,050	39,000	245,700	1944-45
1945-46	800	2,800	51,000	266,330	1945-46
1946-47	800	4,750	47,000	252,900	1946-47
1947-48	1,200	4,200	45,000	255,825	1947-48
1948-49	1,200	4,000	59,000	285,550	1948-49
1949-50	1,400	5,400	63,000	314,950	1949-50
1950-51	1,400	6,500	62,000	325,100	1950-51

NOTES: (1) Acreage of cantaloupes for 1926, 1927 and 1928 seasons is estimated the same as for 1929 and 1930 seasons.

(2) These acreage figures do not include acres abandoned in various stages of growth for reasons other than economic marketing, that is, poor markets. Does not include any commodities not reaching harvest stage. Some additional acreage was abandoned for marketing reasons.

All acreage figures are preliminary as of September 15, 1951 and are subject to revision. Years prior to 1950-51 may have been revised slightly by the U.S. Bureau of Agricultural Economics.

FLORIDA FOB PACKED VALUE OF SELECTED VEGETABLES AND NON-CITRUS FRUITS FOR 16 SEASONS

Season	Beans	Limas	Cabbage	Carrots	Cauliflower
1935-36	$ 6,250,000	$ 202,000	$ 612,000	$	$
1936-37	7,031,000	390,000	496,000		
1937-38	6,272,000	507,000	978,000		
1938-39	7,041,000	720,000	990,000		
1939-40	7,480,000	420,000	2,061,000	Not	Not
1940-41	8,615,000	616,000	2,334,000		
1941-42	11,412,000	704,000	1,602,000	previously	previously
1942-43	17,989,000	1,041,000	6,460,000		
1943-44	19,116,000	1,436,000	4,284,000	reported	reported
1944-45	18,405,000	1,779,000	3,959,000		
1945-46	18,359,000	1,533,000	5,571,000		
1946-47	16,389,000	1,187,000	3,069,000		
1947-48	14,484,000	1,065,000	6,500,000	270,000	176,000
1948-49	16,884,000	946,000	5,530,000	52,000	351,000
1949-50	17,354,000	707,000	3,864,000	-	472,000
1950-51	17,282,000	551,000	10,425,000	-	588,000

Season	Celery	Corn	Cucumbers	Eggplant	Escarole	All Lettuce
1935-36	$ 4,488,000	$	$ 928,000	$ 268,000	$ 207,000	$ 185,000
1936-37	4,532,000		1,101,000	323,000	306,000	170,000
1937-38	3,289,000		1,053,000	356,000	204,000	149,000
1938-39	5,375,000		1,391,000	514,000	264,000	270,000
1939-40	5,868,000	Not	1,938,000	417,000	304,000	612,000
1940-41	8,066,000		1,858,000	378,000	364,000	423,750
1941-42	7,154,000	previously	2,124,000	628,000	324,000	481,000
1942-43	17,158,000		2,592,000	1,294,000	1,142,000	1,340,000
1943-44	16,236,000	reported	2,079,000	1,501,000	645,000	562,000
1944-45	18,553,000		3,637,000	1,814,000	1,352,000	634,000
1945-46	14,260,000		5,377,000	1,805,000	875,000	1,285,220
1946-47	17,535,000		4,984,000	1,758,000	1,183,000	559,000
1947-48	9,778,000	1,320,000	6,203,000	1,151,000	1,165,000	440,000
1948-49	16,021,000	4,536,000	5,558,000	1,456,000	1,680,000	583,000
1949-50	12,295,000	6,342,000	7,263,000	1,178,000	1,273,000	806,000
1950-51	16,021,000	7,313,000	7,848,000	1,216,000	2,240,000	890,000

Season	English Peas	Peppers	Potatoes	Squash	Tomatoes	Total Value Vegetables
1935-36	$ 508,000	$1,273,000	$3,187,000	$	$8,224,000	$ 25,332,000
1936-37	418,000	1,905,000	5,078,000		7,688,000	29,438,000
1937-38	642,000	1,668,000	2,939,000		8,711,000	26,768,000
1938-39	648,000	2,771,000	3,644,000		12,323,000	35,951,000
1939-40	520,000	2,121,000	3,725,000	Not	8,216,000	33,682,000
1940-41	409,500	2,537,000	2,799,000		8,618,000	37,018,250
1941-42	434,000	2,838,000	6,018,000	previously	13,468,000	47,187,000
1942-43	254,000	5,917,000	5,914,000		11,795,000	72,896,000
1943-44	450,000	5,460,000	7,431,000	reported	20,734,000	79,934,000
1944-45	284,000	6,623,000	12,033,000		20,376,000	89,449,000
1945-46	339,000	6,545,000	11,744,000		22,405,000	90,098,000
1946-47	189,000	9,086,000	5,475,000		19,098,000	80,512,000
1947-48	92,000	5,886,000	10,073,000	1,839,000	22,936,000	83,378,000
1948-49	42,000	7,569,000	12,316,000	2,255,000	32,666,000	108,445,000
1949-50	67,000	7,188,000	9,609,000	2,060,000	32,247,000	102,725,000
1950-51	72,000	6,797,000	12,188,000	2,401,000	47,523,000	133,355,000

Season	Cantaloupes	Strawberries	Watermelons	Total Miscl. Fruits	Grand Total Misc. Fruits & Vegetables
1935-36	$ 15,000	$ 1,972,000	$ 896,000	$ 2,883,000	$ 29,215,000
1936-37	28,000	2,746,000	1,310,000	4,084,000	33,522,000
1937-38	65,000	2,100,000	945,000	3,110,000	29,878,000
1938-39	44,000	3,175,000	976,000	4,195,000	40,146,000
1939-40	38,000	2,344,000	1,193,000	3,575,000	37,257,000
1940-41	37,500	2,194,000	1,445,850	3,677,350	40,695,600
1941-42	52,000	2,275,000	1,572,000	3,899,000	51,086,000
1942-43	84,500	1,498,000	2,641,000	4,223,500	77,119,500
1943-44	91,000	1,107,000	4,593,000	5,791,000	85,816,000
1944-45	120,000	1,541,000	4,918,000	6,579,000	96,028,000
1945-46	54,000	2,363,000	5,552,000	7,969,000	98,067,220
1946-47	102,000	3,737,000	5,419,000	9,258,000	89,770,000
1947-48	339,000	2,003,000	6,862,000	9,204,000	92,582,000
1948-49	192,000	2,401,000	6,372,000	8,965,000	117,410,000
1949-50	189,000	3,737,000	5,530,000	9,456,000	112,181,000
1950-51	344,000	4,134,000	8,649,000	13,127,000	146,482,000

Source: U.S. Agricultural Statistician, B.A.E., Orlando, Florida. Official estimates on carrots, cauliflower, corn and squash not available prior to 1947-48 season. Other vegetables and miscellaneous fruits probably accounted for 20,000 acres estimated at a gross F.O.B. Florida value of $8,000,000, but not included herein.

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida	Snap Beans				Lima Beans			
Counties	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	1,325	1,700	1,650	1,550	750	900	950	875
Baker	-	-	-	-	-	-	-	-
Bradford	100	200	250	200	50	75	175	125
Brevard	-	-	-	-	-	-	-	-
Broward	14,850	12,300	13,400	17,800	325	150	250	250
Calhoun	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-
Dade	3,000	3,000	5,500	5,700	-	-	-	-
De Soto	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-
Escambia	100	100	100	100	-	-	-	-
Flagler	-	-	-	-	-	-	-	-
Gadsden	350	400	550	500	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-
Hardee	50	50	50	50	-	-	-	-
Hendry	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-
Highlands	500	400	200	200	-	-	-	-
Hillsborough	1,075	1,350	1,100	1,100	100	100	50	50
Holmes	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-
Lake	300	325	350	500	-	-	-	-
Lee	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-
Levy	-	-	75	100	-	50	-	-
Madison	-	-	-	-	-	-	-	-
Manatee	450	450	275	550	-	-	-	-
Marion	800	1,500	1,700	1,250	250	150	125	100
Martin	600	1,100	1,000	500	50	15	-	50
Okeechobee	-	-	-	-	-	-	-	-
Orange	600	300	725	150	-	-	-	-
Osceola	-	-	-	-	-	-	-	-
Palm Beach	48,500	51,800	47,800	42,700	2,150	1,335	1,350	1,300
Pasco	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-
Polk	100	150	275	250	-	-	-	-
Putnam	-	-	-	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	-	50	175	-	-
Sarasota	-	-	-	-	-	-	-	-
Seminole	575	1,200	1,375	850	-	-	-	-
Sumter	650	1,050	600	650	-	-	-	-
Suwannee	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-
Union	275	425	325	200	50	25	-	-
Volusia	-	-	-	-	-	-	-	-
Walton	-	-	50	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-
Miscellaneous	300	200	250	100	75	75	100	50
Total	74,500	76,000	77,600	75,000	3,850	3,050	3,000	2,800

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida	Cabbage				Cauliflower			
Counties	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	200	125	150	100	-	-	-	-
Baker	-	-	-	-	-	-	-	-
Bradford	50	25	25	25	-	-	-	-
Brevard	-	-	-	-	-	-	-	-
Broward	50	50	-	-	-	-	-	-
Calhoun	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-
Clay	400	300	350	300	-	-	-	-
Collier	-	-	-	-	-	-	-	-
Columbia	50	75	125	50	-	-	-	-
Dade	250	250	300	300	-	-	-	75
De Soto	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-
Duval	100	100	100	100	-	-	-	-
Escambia	50	-	150	100	-	-	-	-
Flagler	1,500	1,750	1,800	1,700	-	-	-	-
Gadsden	50	-	50	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-
Glades	1,500	1,200	1,400	900	-	-	-	-
Hamilton	50	100	100	50	-	-	-	-
Hardee	150	-	-	-	-	-	-	-
Hendry	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-
Highlands	25	-	-	-	-	-	-	-
Hillsborough	350	300	300	375	225	200	325	400
Holmes	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-
Lake	200	175	125	100	-	-	-	-
Lee	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-
Levy	25	25	25	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-
Manatee	300	200	250	300	100	150	75	100
Marion	500	300	300	275	-	-	-	-
Martin	75	50	50	100	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-
Orange	600	600	400	350	-	-	-	-
Osceola	-	-	-	-	-	-	-	-
Palm Beach	3,600	3,250	4,350	6,550	-	-	50	50
Pasco	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-
Polk	100	75	75	100	-	-	-	-
Putnam	1,400	1,600	1,700	1,500	-	-	25	-
St. Johns	2,800	3,100	3,100	2,800	-	25	175	225
St. Lucie	200	100	50	-	-	75	25	50
Sarasota	75	-	50	175	-	-	-	-
Seminole	1,500	1,600	1,700	2,300	25	100	100	75
Sumter	100	50	50	50	-	-	-	-
Suwannee	-	-	125	50	-	-	-	-
Taylor	-	-	-	-	-	-	-	-
Union	150	100	150	50	-	-	-	-
Volusia	200	350	250	200	-	-	-	-
Walton	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-
Miscellaneous	100	150	100	100	50	50	25	25
Total	16,700	16,000	17,700	19,000	400	600	800	1,000

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida	Celery				Corn, Green			
Counties	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	100	100	490*	460*	200	300	450	250
Baker	-	-	-	-	-	100	100	-
Bradford	-	-	-	-	250	600	650	1,200
Brevard	-	-	-	-	-	50	300	200
Broward	-	-	-	-	-	50	100	300
Calhoun	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	50	-
Columbia	-	-	-	-	400	550	350	100
Dade	-	-	-	-	65	350	750	1,200
De Soto	-	-	-	-	50	-	-	-
Dixie	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	150	-
Gadsden	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-
Glades	-	-	-	-	100	500	600	300
Hamilton	-	-	-	-	-	100	100	-
Hardee	-	-	-	-	200	300	650	300
Hendry	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	-	-
Hillsborough	-	-	-	-	650	2,350	2,650	1,775
Holmes	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	300	-
Lafayette	-	-	-	-	-	-	-	-
Lake	625	880	1,360*	1,815*	-	300	(4,350)*	(3,400)*
Lee	-	-	-	-	100	200	200	500
Leon	-	-	-	-	-	-	-	-
Levy	-	-	-	-	100	-	50	-
Madison	-	-	-	-	-	-	-	-
Manatee	60	-	-	-	100	100	400	425
Marion	500	235	(490)*	(460)*	-	700	1,000	200
Martin	-	-	-	-	-	-	450	700
Okeechobee	-	-	-	-	-	-	-	-
Orange	860	825	(1,360)*	(1815)*	1,350	1,700	4,350	3,400
Osceola	-	-	-	-	-	-	-	-
Palm Beach	4,000	3,075	3,500	4,075	1,250	4,400	11,000	12,600
Pasco	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-
Polk	-	-	-	-	50	400	400	200
Putnam	-	-	-	-	-	-	200	50
St. Johns	-	-	-	-	-	-	450	50
St. Lucie	-	-	-	-	25	150	300	-
Sarasota	1,325	740	975	975	-	75	200	650
Seminole	4,065	3,320	3,325	3,325	750	900	1,350	600
Sumter	-	-	-	-	-	-	-	-
Suwannee	-	-	-	-	150	75	100	-
Taylor	-	-	-	-	-	-	-	-
Union	-	-	-	-	100	200	400	500
Volusia	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-
Miscellaneous	65	25	-	-	110	250	350	300
Total	11,600	9,400	9,650	10,650	6,000	14,700	28,500	25,800

Note: Celery-Marion included in Alachua Counties, Orange included in Lake Counties.
Corn - Orange County included in Lake.

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida	Cucumbers				Eggplant			
Counties	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	1,225	1,725	1,425	1,400	150	150	100	100
Baker	-	-	-	-	-	-	-	-
Bradford	75	125	200	100	-	-	-	-
Brevard	-	-	-	-	-	-	-	-
Broward	700	325	325	175	450	350	450	275
Calhoun	300	225	150	250	-	-	-	-
Charlotte	100	100	250	250	-	-	-	-
Citrus	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-
Collier	400	300	750	1,075	-	-	-	-
Columbia	100	75	75	100	-	-	-	-
Dade	125	125	250	400	-	25	25	-
De Soto	100	140	200	200	-	-	-	-
Dixie	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-
Escambia	-	200	50	-	-	-	-	-
Flagler	50	25	-	-	-	-	-	-
Gadsden	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	150	-	-	-	-
Glades	-	-	-	-	-	-	-	-
Hamilton	350	75	150	150	-	-	-	-
Hardee	2,100	1,325	1,600	1,300	75	175	150	250
Hendry	400	350	450	650	-	-	-	-
Hernando	-	-	-	-	15	50	-	65
Highlands	50	50	150	100	-	-	-	-
Hillsborough	1,325	1,100	1,400	1,325	845	700	350	275
Holmes	150	100	100	50	-	-	-	-
Indian River	-	25	-	-	-	-	-	-
Jackson	800	600	300	300	-	-	-	-
Jefferson	-	-	-	150	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-
Lake	300	350	200	200	25	50	-	-
Lee	550	775	525	1,175	215	350	175	300
Leon	-	-	-	-	-	-	-	-
Levy	50	-	25	-	-	-	-	-
Madison	-	125	100	-	-	-	-	-
Manatee	375	475	1,075	975	125	200	250	175
Marion	275	325	350	300	200	200	125	75
Martin	-	325	500	550	50	50	50	25
Okeechobee	-	-	-	-	-	-	-	-
Orange	375	400	375	400	-	-	-	-
Osceola	-	-	-	-	-	-	-	-
Palm Beach	1,900	675	750	325	975	625	675	350
Pasco	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-
Polk	200	100	50	50	100	100	25	25
Putnam	200	100	-	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-
St. Lucie	200	225	650	900	-	-	-	-
Sarasota	200	175	275	75	-	25	-	-
Seminole	-	60	100	-	-	75	25	-
Sumter	950	900	800	600	75	75	25	25
Suwannee	300	225	75	50	-	-	-	-
Taylor	-	-	-	-	-	-	-	-
Union	250	300	250	100	-	-	-	-
Volusia	-	-	-	-	-	-	-	-
Walton	-	-	125	100	-	-	-	-
Washington	50	25	125	-	-	-	-	-
Miscellaneous	125	300	125	75	30	100	125	110
Total	14,650	12,850	14,300	14,000	3,330	3,300	2,550	2,050

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida Counties	Escarole				Lettuce and Romaine			
	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	-	-	-	-	50	40	50	50
Baker	-	-	-	-	-	-	-	-
Bradford	-	-	-	-	-	-	-	-
Brevard	-	-	-	-	-	-	-	-
Broward	-	-	-	-	-	-	-	-
Calhoun	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-
Dade	-	-	-	-	-	-	-	50
De Soto	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-
Gadsden	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-
Glades	-	-	-	-	325	200	450	550
Hamilton	-	-	-	-	-	-	-	-
Hardee	-	-	-	-	-	-	-	-
Hendry	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	-	-
Hillsborough	50	40	75	50	225	250	235	250
Holmes	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-
Lake	-	-	-	-	25	-	-	-
Lee	-	-	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-
Manatee	225	100	75	50	200	100	90	100
Marion	-	-	-	-	100	80	100	50
Martin	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-
Orange	370	475	475	600	60	160	180	200
Osceola	-	-	-	-	-	-	-	-
Palm Beach	2,000	1,950	2,500	3,100	415	400	975	750
Pasco	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-
Polk	-	-	-	-	-	-	-	-
Putnam	-	-	-	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	-	-	-	-	-
Sarasota	-	50	50	50	-	-	-	75
Seminole	405	350	375	500	200	200	130	125
Sumter	-	-	-	-	75	50	40	50
Suwannee	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	-	-
Volusia	-	-	-	-	-	-	100	100
Walton	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-
Miscellaneous	50	35	50	50	75	20	50	50
Total	3,100	3,000	3,600	4,400	1,750	1,500	2,400	2,400

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida	Peas, English				Peppers			
Counties	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	75	20	-	-	550	800	800	1,000
Baker	-	-	-	-	-	-	-	-
Bradford	-	-	-	-	-	75	250	300
Brevard	-	-	-	-	-	-	-	-
Broward	-	-	25	25	1,675	1,500	2,675	1,825
Calhoun	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	50	50	50	25
Citrus	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	25	50
Columbia	-	-	-	-	-	-	-	-
Dade	-	-	-	-	-	175	75	100
De Soto	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-
Flagler	25	-	-	-	-	-	-	-
Gadsden	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	50	50
Hardee	-	-	-	-	175	400	300	250
Hendry	-	-	-	-	-	-	25	-
Hernando	-	-	-	-	-	-	-	-
Highlands	25	20	-	-	-	-	-	-
Hillsborough	100	60	50	50	3,640	2,765	3,350	3,250
Holmes	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-
Lake	-	-	-	-	230	145	250	200
Lee	-	-	-	-	350	375	350	275
Leon	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	50	50	50
Madison	-	-	-	-	-	-	-	-
Manatee	25	-	25	25	75	140	175	200
Marion	25	20	-	-	200	75	150	150
Martin	-	-	-	-	75	200	175	250
Okeechobee	-	-	-	-	-	-	-	-
Orange	-	-	-	-	160	225	125	50
Osceola	-	-	-	-	-	-	-	-
Palm Beach	200	200	125	250	2,000	2,050	3,150	2,625
Pasco	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-
Polk	25	-	-	-	650	500	600	550
Putnam	-	20	-	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	-	-	50	175	175
Sarasota	-	20	-	-	25	-	-	-
Seminole	50	25	25	25	250	200	250	150
Sumter	-	-	-	-	800	675	900	650
Suwannee	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-
Union	-	-	-	-	100	100	50	50
Volusia	-	-	-	-	100	100	125	150
Walton	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-
Miscellaneous	50	15	50	25	95	100	175	125
Total	600	400	300	400	11,200	10,750	14,300	12,500

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida	Potatoes				Squash			
Counties	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	1,500	400	550	400	150	425	450	475
Baker	-	-	-	-	-	-	-	-
Bradford	100	75	80	100	50	100	150	150
Brevard	-	-	-	-	-	50	25	25
Broward	-	-	-	-	1,350	1,350	1,850	1,900
Calhoun	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	25	25	-
Citrus	-	-	-	-	-	-	-	-
Clay	50	-	50	50	-	-	-	-
Collier	-	-	-	-	-	25	100	175
Columbia	-	-	-	-	-	-	50	-
Dade	5,800	6,700	6,600	5,800	600	800	1,400	1,375
De Soto	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-
Escambia	600	500	850	600	-	-	-	-
Flagler	1,950	2,100	2,200	2,450	-	-	-	-
Gadsden	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	50
Glades	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-
Hardee	-	-	-	-	100	125	250	225
Hendry	-	-	-	-	75	50	100	175
Hernando	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	-	-
Hillsborough	150	375	420	550	1,150	1,050	1,500	1,525
Holmes	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	25	25	250
Jackson	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-
Lake	-	-	-	-	50	50	50	25
Lee	950	1,130	1,725	1,400	325	200	250	275
Leon	-	-	-	-	-	-	-	-
Levy	-	-	-	-	50	50	100	75
Madison	-	-	-	-	-	-	-	-
Manatee	-	-	-	-	250	100	225	275
Marion	50	-	50	50	900	1,300	1,250	1,150
Martin	-	-	40	-	700	600	350	350
Okeechobee	-	-	-	-	-	-	-	-
Orange	75	-	-	-	50	75	-	-
Osceola	-	-	-	-	-	-	-	-
Palm Beach	1,100	1,370	1,850	1,550	1,200	1,650	1,750	1,525
Pasco	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-
Polk	-	25	30	25	250	225	300	200
Putnam	2,400	2,000	2,550	2,800	-	-	-	-
St. Johns	5,800	5,800	6,400	7,100	-	-	-	-
St. Lucie	-	-	-	-	100	125	200	75
Sarasota	-	-	50	25	-	-	-	-
Seminole	-	-	-	-	100	75	50	100
Sumter	-	-	-	-	50	100	50	50
Suwannee	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-
Union	100	25	70	100	100	225	100	100
Volusia	-	-	-	-	50	50	50	25
Walton	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-
Miscellaneous	75	100	85	100	250	150	150	150
Total	20,700	20,600	23,600	23,100	7,900	9,000	10,800	11,200

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida Counties	Tomatoes				Total Vegetables			
	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	100	-	-	-	6,375	6,685	7,065	6,660
Baker	-	-	-	-	-	100	100	-
Bradford	-	-	-	-	675	1,275	1,780	2,200
Brevard	50	400	300	2,100	50	500	625	2,325
Broward	1,400	1,500	1,600	550	20,800	17,575	20,675	23,100
Calhoun	-	-	-	-	300	225	150	250
Charlotte	50	50	25	50	200	225	350	325
Citrus	-	-	-	-	-	-	-	-
Clay	-	-	-	-	450	300	400	350
Collier	775	1,050	1,600	3,100	1,175	1,375	2,525	4,400
Columbia	-	-	-	-	550	700	600	250
Dade	8,900	12,000	14,300	17,600	18,740	23,425	29,200	33,100
De Soto	200	150	200	200	350	290	400	400
Dixie	-	-	-	-	-	-	-	-
Duval	-	-	-	-	100	100	100	100
Escambia	-	-	-	-	750	800	1,150	800
Flagler	-	-	-	-	3,525	3,875	4,150	4,150
Gadsden	-	-	-	-	400	400	600	500
Gilchrist	-	-	-	-	-	-	-	200
Glades	860	800	850	1,150	2,785	2,700	3,300	2,900
Hamilton	-	-	-	-	400	275	400	250
Hardee	1,850	1,400	900	1,250	4,700	3,775	3,900	3,625
Hendry	325	675	900	1,850	800	1,075	1,475	2,675
Hernando	-	-	-	-	15	50	-	65
Highlands	200	250	-	-	800	720	350	300
Hillsborough	2,150	3,100	3,200	2,950	12,035	13,740	15,005	13,925
Holmes	-	-	-	-	150	100	100	50
Indian River	390	2,400	3,100	2,400	390	2,450	3,125	2,650
Jackson	-	-	-	-	800	600	300	300
Jefferson	-	-	-	-	-	-	300	150
Lafayette	-	-	-	-	-	-	-	-
Lake	200	250	250	300	1,955	2,525	2,585	3,140
Lee	225	150	175	350	2,715	3,180	3,400	4,275
Leon	-	-	-	-	-	-	-	-
Levy	50	50	-	-	275	225	325	225
Madison	-	-	-	-	-	125	100	-
Manatee	1,950	3,650	3,300	4,000	4,235	5,665	6,315	7,175
Marion	900	1,000	1,300	1,700	4,700	5,885	6,450	5,300
Martin	50	450	500	1,750	1,600	2,790	3,115	4,275
Okeechobee	700	850	1,700	1,100	700	850	1,700	1,100
Orange	-	50	-	-	4,500	4,810	6,630	5,150
Osceola	-	-	-	-	-	-	-	-
Palm Beach	975	600	900	500	70,265	73,380	80,725	78,250
Pasco	-	-	-	-	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-
Polk	100	150	100	100	1,575	1,725	1,855	1,500
Putnam	-	-	-	-	4,000	3,720	4,475	4,350
St. Johns	-	-	-	-	8,600	8,925	10,125	10,175
St. Lucie	4,800	6,350	4,600	5,200	5,375	7,250	6,000	6,400
Sarasota	-	-	-	50	1,625	1,285	1,600	2,075
Seminole	50	-	-	-	7,970	8,105	8,805	8,050
Sumter	900	1,250	2,000	2,500	3,600	4,150	4,465	4,575
Suwannee	-	-	-	-	450	300	300	100
Taylor	-	-	-	-	-	-	-	-
Union	-	-	-	-	1,125	1,400	1,345	1,100
Volusia	-	-	-	-	350	500	525	475
Walton	-	-	-	-	-	-	175	100
Washington	-	-	-	-	50	25	125	-
Miscellaneous	200	225	400	150	1,650	1,795	2,035	1,410
Total	28,350	38,800	42,200	50,900	204,630	221,950	251,300	255,200

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida Counties	Cantaloupes 1947-48	Cantaloupes 1948-49	Cantaloupes 1949-50	Cantaloupes 1950-51	Strawberries 1947-48	Strawberries 1948-49	Strawberries 1949-50	Strawberries 1950-51
Alachua	450	400	500	350	-	-	-	-
Baker	-	-	-	-	-	-	-	-
Bradford	25	25	25	25	200	400	500	400
Brevard	-	-	-	-	-	-	-	-
Broward	-	-	-	-	-	-	-	-
Calhoun	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-
Collier	-	-	50	25	-	-	-	-
Columbia	25	25	-	-	-	-	-	-
Dade	-	-	-	-	-	50	50	50
De Soto	-	-	-	-	-	-	-	-
Dixie	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-
Gadsden	-	-	-	-	-	-	-	-
Gilchrist	-	25	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-
Hamilton	50	-	75	100	-	-	-	-
Hardee	-	-	-	-	325	250	350	425
Hendry	-	-	-	-	-	-	-	-
Hernando	-	-	-	-	-	-	-	-
Highlands	-	-	-	-	-	-	-	-
Hillsborough	50	25	25	25	3,100	2,750	3,900	4,900
Holmes	-	-	-	-	-	-	-	-
Indian River	-	-	-	-	-	-	-	-
Jackson	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-
Lake	50	50	100	50	-	-	-	-
Lee	-	60	-	-	-	-	-	-
Leon	-	-	-	-	-	-	-	-
Levy	75	75	75	50	-	-	-	-
Madison	50	25	-	25	-	-	-	-
Manatee	-	25	-	-	-	-	-	-
Marion	300	300	300	325	-	-	-	-
Martin	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-
Orange	-	-	-	-	-	-	-	-
Osceola	-	-	-	-	-	-	-	-
Palm Beach	-	-	-	-	-	-	-	-
Pasco	-	-	-	50	-	-	-	-
Pinellas	-	-	-	-	-	-	-	-
Polk	-	-	-	-	500	450	450	550
Putnam	-	-	-	-	-	-	-	-
St. Johns	-	-	-	-	-	-	-	-
St. Lucie	-	-	-	-	-	-	-	-
Sarasota	-	-	-	-	-	-	-	-
Seminole	-	-	-	-	-	-	-	-
Sumter	75	75	50	125	50	50	75	100
Suwannee	25	25	50	50	-	-	-	-
Taylor	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	-	-
Volusia	-	-	-	-	-	-	-	-
Walton	-	-	-	-	-	-	-	-
Washington	-	-	-	100	-	-	-	-
Miscellaneous	25	65	150	100	25	50	75	75
Total	1,200	1,200	1,400	1,400	4,200	4,000	5,400	6,500

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida	Watermelons				Total Miscellaneous Fruits			
Counties	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	4,700	6,200	7,300	6,100	5,150	6,600	7,800	6,450
Baker	-	-	-	-	-	-	-	-
Bradford	50	100	250	175	275	525	775	600
Brevard	50	150	-	-	50	150	-	-
Broward	150	50	-	-	150	50	-	-
Calhoun	150	700	500	500	150	700	500	500
Charlotte	-	-	-	150	-	-	-	150
Citrus	150	250	750	900	150	250	750	900
Clay	-	-	-	-	-	-	-	-
Collier	50	50	250	650	50	50	300	675
Columbia	300	600	750	500	325	625	750	500
Dade	-	-	-	50	-	50	50	100
De Soto	400	550	150	275	400	550	150	275
Dixie	100	200	400	100	100	200	400	100
Duval	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-
Gadsden	100	-	-	-	100	-	-	-
Gilchrist	6,200	8,500	10,600	6,200	6,200	8,525	10,600	6,200
Glades	-	-	-	-	-	-	-	-
Hamilton	350	450	450	200	400	450	525	300
Hardee	75	100	200	400	400	350	550	825
Hendry	50	50	200	400	50	50	200	400
Hernando	-	100	100	600	-	100	100	600
Highlands	50	-	-	150	50	-	-	150
Hillsborough	600	800	1,400	1,400	3,750	3,575	5,325	6,325
Holmes	400	750	900	700	400	750	900	700
Indian River	150	200	700	450	150	200	700	450
Jackson	1,000	1,350	1,900	2,000	1,000	1,350	1,900	2,000
Jefferson	2,400	2,000	1,900	1,950	2,400	2,000	1,900	1,950
Lafayette	1,000	1,000	1,400	1,200	1,000	1,000	1,400	1,200
Lake	6,200	6,500	7,200	6,800	6,250	6,550	7,300	6,850
Lee	50	100	-	225	50	160	-	225
Leon	50	100	300	200	50	100	300	200
Levy	2,200	4,200	2,700	2,100	2,275	4,275	2,775	2,150
Madison	1,500	2,300	2,300	1,800	1,550	2,325	2,300	1,825
Manatee	100	50	200	100	100	75	200	100
Marion	6,500	7,200	7,600	6,950	6,800	7,500	7,900	7,275
Martin	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	50	-	-	-	50
Orange	100	300	450	200	100	300	450	200
Osceola	-	-	-	-	-	-	-	-
Palm Beach	150	50	-	-	150	50	-	-
Pasco	1,200	1,850	2,300	4,800	1,200	1,850	2,300	4,850
Pinellas	100	-	-	-	100	-	-	-
Polk	700	800	700	1,550	1,200	1,250	1,150	2,100
Putnam	150	400	550	550	150	400	550	550
St. Johns	-	-	-	-	-	-	-	-
St. Lucie	300	350	400	600	300	350	400	600
Sarasota	-	-	200	150	-	-	200	150
Seminole	-	-	-	-	-	-	-	-
Sumter	3,500	3,900	4,100	3,800	3,625	4,025	4,225	4,025
Suwannee	2,400	5,300	6,800	5,400	2,425	5,325	6,850	5,450
Taylor	50	100	300	300	50	100	300	300
Union	200	200	200	225	200	200	200	225
Volusia	250	400	400	300	250	400	400	300
Walton	-	-	-	-	-	-	-	-
Washington	500	500	600	700	500	500	600	800
Miscellaneous	325	250	600	150	375	365	825	325
Total	45,000	59,000	68,000	62,000	50,400	64,200	74,800	69,900

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida Counties	Total Vegetables & Miscellaneous Fruits				Oranges			
	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	11,525	13,235	14,865	13,110	-	-	-	-
Baker	-	100	100	-	-	-	-	-
Bradford	950	1,800	2,555	2,800	-	-	-	-
Brevard	100	650	625	2,325	11,950	12,211	12,211	12,211
Broward	20,950	17,625	20,675	23,100	3,770	3,825	3,825	3,825
Calhoun	450	925	650	750	-	-	-	-
Charlotte	200	225	350	475	-	-	-	-
Citrus	150	250	750	900	-	-	-	-
Clay	450	300	400	350	-	-	-	-
Collier	1,225	1,425	2,825	5,075	-	-	-	-
Columbia	875	1,325	1,350	750	-	-	-	-
Dade	18,740	23,475	29,250	33,200	3,230	3,248	3,248	3,248
De Soto	750	840	550	675	6,835	6,933	6,933	6,933
Dixie	100	200	400	100	-	-	-	-
Duval	100	100	100	100	-	-	-	-
Escambia	750	800	1,150	800	-	-	-	-
Flagler	3,525	3,875	4,150	4,150	-	-	-	-
Gadsden	500	400	600	500	-	-	-	-
Gilchrist	6,200	8,525	10,600	6,400	-	-	-	-
Glades	2,785	2,700	3,300	2,200	-	-	-	-
Hamilton	800	725	925	550	-	-	-	-
Hardee	5,100	4,125	4,450	4,450	9,290	9,495	9,495	9,495
Hendry	850	1,125	1,675	3,075	-	-	-	-
Hernando	15	150	100	665	1,665	1,697	1,697	1,697
Highlands	850	720	350	450	9,460	9,849	9,849	9,849
Hillsborough	15,785	17,315	20,330	20,250	17,790	18,301	18,301	18,301
Holmes	550	850	1,000	750	-	-	-	-
Indian River	540	2,650	3,825	3,100	5,310	5,438	5,438	5,438
Jackson	1,800	1,950	2,200	2,300	-	-	-	-
Jefferson	2,400	2,000	2,200	2,100	-	-	-	-
Lafayette	1,000	1,000	1,400	1,200	-	-	-	-
Lake	8,205	9,075	9,885	9,990	27,980	29,157	29,157	29,157
Lee	2,765	3,340	3,400	4,500	3,445	3,478	3,478	3,478
Leon	50	100	300	200	-	-	-	-
Levy	2,550	4,500	3,100	2,375	-	-	-	-
Madison	1,550	2,450	2,400	1,825	-	-	-	-
Manatee	4,335	5,740	6,515	7,275	4,785	4,866	4,866	4,866
Marion	11,500	13,385	14,350	12,575	9,335	9,442	9,442	9,442
Martin	1,600	2,790	3,115	4,275	-	-	-	-
Okeechobee	700	850	1,700	1,150	-	-	-	-
Orange	4,600	5,110	7,080	5,350	38,040	39,766	39,766	39,766
Osceola	-	-	-	-	4,605	4,690	4,690	4,690
Palm Beach	70,415	73,430	80,725	78,250	-	-	-	-
Pasco	1,200	1,850	2,300	4,850	7,420	7,729	7,729	7,729
Pinellas	100	-	-	-	7,800	7,944	7,944	7,944
Polk	2,775	2,975	3,005	3,600	61,250	63,189	63,189	63,189
Putnam	4,150	4,120	5,025	4,900	4,450	4,450	4,450	4,450
St. Johns	8,600	8,925	10,125	10,175	-	-	-	-
St. Lucie	5,675	7,600	6.400	7,000	9,180	10,199	10,199	10,199
Sarasota	1,625	1,285	1,800	2,225	2,630	2,649	2,649	2,649
Seminole	7,970	8,105	8,805	8,050	7,110	7,301	7,301	7,301
Sumter	7,225	8,175	8,690	8,600	-	-	-	-
Suwannee	2,875	5,625	7,150	5,550	-	-	-	-
Taylor	50	100	300	300	-	-	-	-
Union	1,325	1,600	1,545	1,325	-	-	-	-
Volusia	600	900	925	775	12,085	13,004	13,004	13,004
Walton	-	-	175	100	-	-	-	-
Washington	550	525	725	800	-	-	-	-
Miscellaneous	2,025	2,160	2,860	1.735	10,285	11,039	11,039	11,039
Not apportioned	-	-	-	-	-	-	11,000	19,600
Total	255,030	286,150	326,100	325,100	280,500	289,900	300,900	309,500

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida Counties	Grapefruit				Tangerines			
	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	-	-	-	-	-	-	-	-
Baker	-	-	-	-	-	-	-	-
Bradford	-	-	-	-	-	-	-	-
Brevard	3,780	3,808	3,808	3,808	470	471	471	471
Broward	400	443	443	443	100	105	105	105
Calhoun	-	-	-	-	-	-	-	-
Charlotte	-	-	-	-	-	-	-	-
Citrus	-	-	-	-	-	-	-	-
Clay	-	-	-	-	-	-	-	-
Collier	-	-	-	-	-	-	-	-
Columbia	-	-	-	-	-	-	-	-
Dade	3,760	3,805	3,805	3,805	435	445	445	445
De Soto	1,360	1,383	1,383	1,383	520	521	521	521
Dixie	-	-	-	-	-	-	-	-
Duval	-	-	-	-	-	-	-	-
Escambia	-	-	-	-	-	-	-	-
Flagler	-	-	-	-	-	-	-	-
Gadsden	-	-	-	-	-	-	-	-
Gilchrist	-	-	-	-	-	-	-	-
Glades	-	-	-	-	-	-	-	-
Hamilton	-	-	-	-	-	-	-	-
Hardee	910	913	913	913	665	668	668	668
Hendry	-	-	-	-	-	-	-	-
Hernando	360	360	360	360	830	834	834	834
Highlands	4,340	4,409	4,409	4,409	830	832	832	832
Hillsborough	3,800	3,864	3,864	3,864	1,255	1,278	1,278	1,278
Holmes	-	-	-	-	-	-	-	-
Indian River	6,840	7,111	7,111	7,111	525	526	526	526
Jackson	-	-	-	-	-	-	-	-
Jefferson	-	-	-	-	-	-	-	-
Lafayette	-	-	-	-	-	-	-	-
Lake	6,980	7,147	7,147	7,147	1,990	2,004	2,004	2,004
Lee	2,900	2,911	2,911	2,911	120	122	122	122
Leon	-	-	-	-	-	-	-	-
Levy	-	-	-	-	-	-	-	-
Madison	-	-	-	-	-	-	-	-
Manatee	4,890	4,924	4,924	4,924	125	133	133	133
Marion	730	732	732	732	400	401	401	401
Martin	-	-	-	-	-	-	-	-
Okeechobee	-	-	-	-	-	-	-	-
Orange	4,010	4,112	4,112	4,112	3,115	3,128	3,128	3,128
Osceola	900	903	903	903	590	591	591	591
Palm Beach	-	-	-	-	-	-	-	-
Pasco	1,510	1,527	1,527	1,527	590	592	592	592
Pinellas	8,040	8,237	8,237	8,237	670	683	683	683
Polk	26,740	27,245	27,245	27,245	5,515	5,558	5,558	5,558
Putnam	450	451	451	451	640	641	641	641
St. Johns	-	-	-	-	-	-	-	-
St. Lucie	4,780	5,035	5,035	5,035	900	903	903	903
Sarasota	1,100	1,106	1,106	1,106	-	-	-	-
Seminole	720	723	723	723	825	826	826	826
Sumter	-	-	-	-	-	-	-	-
Suwannee	-	-	-	-	-	-	-	-
Taylor	-	-	-	-	-	-	-	-
Union	-	-	-	-	-	-	-	-
Volusia	1,360	1,369	1,369	1,369	1,940	1,951	1,951	1,951
Walton	-	-	-	-	-	-	-	-
Washington	-	-	-	-	-	-	-	-
Miscellaneous	2,340	2,482	2,482	2,482	750	787	787	787
Not apportioned	-	-	3,500	5,000	-	-	100	200
Total	93,000	95,000	98,500	100,000	23,800	24,000	24,100	24,200

FRUITS AND VEGETABLES

COUNTY ACREAGE SEASONS 1947-48, 1948-49, 1949-50 AND 1950-51

Florida Counties	Total Citrus				Grand Total			
	1947-48	1948-49	1949-50	1950-51	1947-48	1948-49	1949-50	1950-51
Alachua	-	-	-	-	11,525	13,285	14,865	13,110
Baker	-	-	-	-	-	100	100	-
Bradford	-	-	-	-	950	1,800	2,555	2,800
Brevard	16,200	16,490	16,490	16,490	16,300	17,140	17,115	18,815
Broward	4,270	4,373	4,373	4,373	25,220	21,798	25,048	27,473
Calhoun	-	-	-	-	450	925	650	750
Charlotte	-	-	-	-	200	225	350	475
Citrus	-	-	-	-	150	250	750	900
Clay	-	-	-	-	450	300	400	350
Collier	-	-	-	-	1,225	1,425	2,325	5,075
Columbia	-	-	-	-	875	1,325	1,350	750
Dade	7,425	7,498	7,498	7,498	26,215	31,048	36,748	40,698
De Soto	8,715	8,837	8,837	8,837	9,465	9,677	9,387	9,512
Dixie	-	-	-	-	100	200	400	100
Duval	-	-	-	-	100	100	100	100
Escambia	-	-	-	-	750	800	1,150	800
Flagler	-	-	-	-	3,525	3,675	4,150	4,150
Gadsden	-	-	-	-	500	400	600	500
Gilchrist	-	-	-	-	6,200	8,525	10,600	6,400
Glades	-	-	-	-	2,785	2,700	3,300	2,900
Hamilton	-	-	-	-	800	725	925	550
Hardee	10,865	11,076	11,076	11,076	15,965	15,201	15,526	15,526
Hendry	-	-	-	-	850	1,125	1,675	3,075
Hernando	2,855	2,891	2,891	2,891	2,870	3,041	2,721	3,556
Highlands	14,630	15,090	15,909	15,090	15,505	15,810	15,440	15,540
Hillsborough	22,845	23,443	23,443	23,443	38,630	40,758	43,773	43,693
Holmes	-	-	-	-	550	850	1,000	750
Indian River	12,675	13,075	13,075	13,075	13,215	15,725	16,900	16,175
Jackson	-	-	-	-	1,800	1,950	2,200	2,300
Jefferson	-	-	-	-	2,400	2,000	2,200	2,100
Lafayette	-	-	-	-	1,000	1.000	1,400	1,200
Lake	36,950	38,308	38,308	38,308	45,155	47,333	48,193	48,298
Lee	6,465	6,511	6,511	6,511	9,230	9,851	9,911	11,011
Leon	-	-	-	-	50	100	300	200
Levy	-	-	-	-	2,550	4,500	3,100	2,375
Madison	-	-	-	-	1,550	2,450	2,400	1,825
Manatee	9,800	9,923	9,923	9,923	14,135	15,663	16,438	17,126
Marion	10,465	10,575	10,575	10,575	21,965	23,960	24,225	23,150
Martin	-	-	-	-	1,600	2,720	3,115	4,275
Okeechobee	-	-	-	-	700	850	1,700	1,150
Orange	45,165	47,006	47,006	47,006	50,045	52,441	54,086	52,356
Osceola	6,095	6,184	6,184	6,184	6,095	6,134	6,184	6,184
Palm Beach	-	-	-	-	70,415	73,510	80,725	78,250
Pasco	9,520	9,848	9,848	9,848	10,720	11,698	12,148	14,698
Pinellas	16,510	16,864	16,864	16,864	16,610	16,864	16,864	16,864
Polk	93,505	95,292	95,922	95,292	96,280	98,967	98,997	[illegible]
Putnam	5,540	5,542	5,542	5,542	9,690	9,662	10,567	[illegible]
St. Johns	-	-	-	-	8,600	8,225	10,125	[illegible]
St. Lucie	14,860	16,137	16,137	16,137	20,535	23,737	22,537	[illegible]
Sarasota	3,730	3,755	3,755	3,755	5,355	5,040	5,555	[illegible]
Seminole	8,655	8,850	8,850	8,850	16,645	16,955	17,655	[illegible]
Sumter	-	-	-	-	7,225	8,175	8,690	[illegible]
Suwannee	-	-	-	-	2,875	5,625	7,150	[illegible]
Taylor	-	-	-	-	50	100	300	[illegible]
Union	-	-	-	-	1,325	1,600	1,545	[illegible]
Volusia	16,185	16,324	16,324	16,324	16,785	17,224	17,249	[illegible]
Walton	-	-	-	-	-	-	175	[illegible]
Washington	-	-	-	-	550	525	725	[illegible]
Miscellaneous	13,375	14,308	14,308	14,308	15,425	16,488	17,168	[illegible]
Not apportioned	-	-	14,600	24,800	-	-	14,600	24,800
Total	397,300	408,900	423,500	433,700	652,730	695,550	747,600	758,800

JACKSONVILLE JOBBING MARKET
SALES TO RETAILER OR EQUIVALENT SALES
MONTHLY SIMPLE AVERAGES

EGGS (Florida White Grade A - 24 oz. per Doz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1936	33.5	31.2	23.5	22.9	24.1	25.7	31.9	34.0	37.5	38.4	41.9	43.4	32.3
1937	29.8	27.5	25.1	25.5	24.2	25.8	30.1	33.0	37.2	38.1	39.6	38.0	31.2
1938	32.5	26.6	22.2	22.3	25.0	25.7	31.5	32.8	36.3	36.3	36.8	40.1	30.7
1939	30.8	24.3	21.6	21.9	22.6	23.0	29.1	29.6	28.8	32.4	33.9	30.9	27.4
1940	31.4	26.8	20.7	20.8	21.2	23.5	28.8	31.7	34.5	36.4	36.3	38.2	29.2
1941	33.3	25.4	24.1	25.2	28.4	31.2	36.8	39.2	41.4	42.0	44.5	42.2	34.5
1942	40.0	31.5	30.5	31.4	31.4	34.7	39.5	45.0	46.1	48.0*	48.0*	48.0*	39.7
1943	47.6	38.7	38.0	38.4*	43.0*	43.6*	46.9*	51.0*	54.8*	58.0*	57.0*	53.6*	47.6
1944	49.3*	39.7*	37.1*	37.0*	38.2*	41.4*	45.2*	50.3*	55.1*	58.6*	59.9*	59.0*	47.6
1945	50.0*	44.0*	37.8*	42.4*	42.6*	44.9*	49.3*	54.4*	57.8*	58.6*	59.9*	58.8*	50.0
1946	49.7*	40.7*	39.0*	39.1*	42.4*	45.0**	50.7	55.6	60.4	66.2	61.3	62.8	51.1
1947	59.4	52.4	51.1	52.4	56.0	57.4	62.3	64.9	70.1	73.0	74.0	75.5	62.5
1948	68.6	57.2	54.1	55.4	57.7	60.2	63.3	68.2	70.7	74.7	75.8	69.8	64.6
1949	64.3	52.9	53.7	55.2	58.5	60.7	64.1	67.0	69.7	67.0	60.6	52.8	60.5
1950	45.5	40.0	44.7	44.1	42.3	46.3	52.7	55.1	59.0	62.0	63.8	72.9	52.4
1951	57.4	55.8	56.4	57.5	58.7	61.7	64.2	67.8					

*Temporary ceiling prices on all poultry and eggs went into effect October 3, 1942.

FRYERS (Heavy Breed)

1936	25.5	25.6	27.0	27.2	25.7	25.5	23.1	22.6	22.3	21.2	20.5	20.0	23.7
1937	22.3	24.0	24.1	27.0	24.1	25.3	25.5	24.5	25.8	27.1	26.7	27.7	25.4
1938	25.8	24.6	27.2	27.8	24.0	21.8	20.5	21.6	22.9	22.9	23.0	23.6	23.8
1939	23.4	21.6	21.9	24.8	22.0	21.8	22.5	21.9	21.0	22.0	22.3	22.1	22.3
1940	22.0	21.8	22.8	22.6	24.3	23.2	21.4	20.5	21.5	21.9	20.8	21.5	22.0
1941	21.8	22.4	23.8	24.3	23.0	22.8	22.8	22.2	22.6	23.0	23.9	24.0	23.1
1942	24.1	23.7	24.2	25.6	26.8	27.5	27.4	27.5	29.0	30.5	30.5	31.4	27.4
1943	31.8	31.8	31.8	31.9*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	30.6*	31.0
1944	30.6*	30.6*	30.6*	31.0*	32.6*	31.8*	31.1*	30.6*	30.6*	30.6*	30.6*	30.6*	30.9
1945	30.6*	31.6*	32.0*	32.4*	32.8*	31.6*	31.4*	31.3*	31.3*	31.3*	31.3*	31.3*	31.6
1946	31.6*	32.1*	32.5*	32.9*	33.3*	33.0**	39.1	38.5	43.3	47.1	41.5	41.2	37.2
1947	36.2	32.5	34.5	35.0	37.4	38.0	38.5	39.0	41.2	37.9	34.7	36.8	36.8
1948	40.2	37.4	41.9	42.4	40.3	41.7	39.7	39.0	39.4	38.5	38.4	38.3	39.9
1949	32.9	30.9	32.9	34.6	31.3	30.7	30.2	32.5	32.4	32.7	34.1	28.5	32.0
1950	23.5	29.2	35.5	33.5	30.1	29.7	34.1	34.9	34.3	30.1	28.2	26.6	30.8
1951	31.8	34.3	37.5	34.1	31.5	34.1	34.4	34.7					

*Permanent ceiling prices went into effect Mar.6,1943 on eggs, Apr.6,1943 on poultry.

HENS (Heavy Breed)

1936	20.0	19.9	19.5	20.3	20.8	20.5	20.9	20.7	20.2	19.6	19.6	18.7	20.1
1937	18.7	19.3	18.6	18.5	19.0	19.5	16.8	16.0	17.5	18.7	20.2	20.7	18.6
1938	20.1	19.0	19.9	19.7	19.0	19.3	19.4	18.7	20.2	20.2	21.0	21.2	19.8
1939	21.4	20.7	20.4	21.1	19.3	18.8	17.8	18.2	16.9	16.9	17.9	15.3	18.7
1940	16.2	16.7	17.5	17.5	17.1	16.2	15.5	16.1	16.5	18.5	17.8	17.2	16.9
1941	17.6	18.1	19.0	19.9	19.8	20.8	20.7	20.5	21.1	21.5	23.0	23.1	20.4
1942	23.9	22.8	23.0	23.6	23.2	21.5	21.0	21.8	24.9	26.5	26.5	27.8	23.9
1943	29.3	29.3	29.3	29.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.1*	27.8
1944	27.1*	28.1*	27.1*	27.5*	29.2*	28.4*	27.6*	27.1*	27.1*	27.1*	27.1*	27.1*	27.5
1945	27.1*	28.1*	28.5*	28.9*	29.3*	28.1*	27.4*	27.1*	27.1*	27.1*	27.1*	27.1*	27.7
1946	27.6*	28.1*	28.5*	28.9*	29.3*	28.1**	29.1	29.2	35.0	40.6	35.2	35.0	31.2
1947	33.1	34.5	38.1	36.4	34.3	32.6	32.8	33.9	36.4	36.5	37.4	37.9	35.3
1948	40.5	40.2	41.7	42.8	43.0	43.0	40.3	38.0	39.9	40.0	40.0	40.9	40.9
1949	39.4	39.0	39.3	40.4	36.0	30.5	29.4	32.0	34.0	34.4	34.8	33.7	35.2
1950	27.5	29.2	28.4	28.0	26.1	25.5	25.5	29.8	30.5	29.8	31.2	34.2	28.8
1951	34.0	34.0	35.6	36.0	35.3	35.0	34.8	33.6					

**All ceiling poultry and egg prices ended June 30, 1946.

POULTRY AND EGG WHOLESALE PRICES
TAMPA MARKET (January 1, 1940-July 31, 1951)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
					WHITE EGGS (Grade A 24-Oz.)								
1940	31.5	29.2	21.5	22.1	22.3	24.2	29.5	32.5	35.9	37.5	37.1	33.6	30.2
1941	34.6	26.2	24.2	26.0	28.4	32.0	27.5	40.0	51.1	43.3	45.1	45.5	35.2
1942	41.9	33.2	31.2	33.0	32.4	35.5	41.0	46.1	47.3	49.0C	49.0	49.0	40.7
1943	48.7	40.1	39.0	43.0	43.0	43.1	47.1	51.3	55.0	58.3	57.3	55.8	48.3
1944	46.5	40.5	37.1	37.0	38.6	40.5	44.3	50.5	52.2	58.6	60.0	54.1	47.1
1945	49.3	44.0	38.2	41.8	42.0	44.8	49.3	55.0	57.9	58.7	60.1	59.0	50.0
1946	49.9	41.8	39.0	39.3	42.0	45.0C	51.1	56.0	61.2	67.0	62.8	63.8	51.5
1947	58.7	55.0	52.2	52.3	57.0	56.2	63.3	66.4	70.9	74.0	75.0	76.9	63.2
1948	69.6	58.2	55.2	56.3	58.0	60.5	64.5	66.8	71.2	75.6	76.8	79.3	65.4
1949	64.5	54.3	54.1	56.4	58.6	61.6	64.8	68.0	71.5	67.0	51.2	53.9	61.4
1950	48.3	41.5	46.0	43.4	41.3	46.3	53.1	56.0	60.7	64.2	64.8	72.0	53.1
1951	59.4	59.0	57.7	60.2	58.7	62.8	66.8						
					HENS (Heavy Preed)								
1940	17.1	17.1	17.3	18.0	17.0	16.5	14.6	14.7	16.8	16.6	17.5	17.5	16.7
1941	17.5	18.9	18.9	19.5	19.0	20.2	21.0	20.5	21.1	23.0	23.7	24.0	20.6
1942	24.5	24.0	23.1	24.4	24.3	22.5	22.3	22.0	25.9	26.0C	26.0	26.0	24.1
1943	28.5	29.5	29.4	29.4	29.4	27.4	27.4	27.4	27.4	27.4	27.4	27.4	28.2
1944	27.4	27.4	27.4	27.4	29.6	28.4	27.4	27.4	27.4	27.4	27.4	27.4	27.7
1945	27.5	27.8	28.8	29.2	29.6	28.5	27.6	27.4	27.3	27.3	27.3	27.3	27.9
1946	27.3	28.3	28.5	28.7	29.5	28.7C	24.8	25.1	32.2	35.6	32.1	32.0	29.3
1947	31.4	31.4	36.1	35.5	30.8	30.0	30.8	31.4	31.5	33.0	34.7	37.0	32.8
1948	38.5	36.0	36.0	36.0	36.0	36.0	34.7	33.0	34.3	37.0	38.1	39.0	36.2
1949	39.1	39.0	39.1	38.7	37.2	31.1	30.0	31.1	33.0	33.0	33.0	33.0	34.7
1950	29.0	23.8	31.9	29.0	26.0	23.7	24.6	29.0	30.0	28.0	30.0	33.3	28.6
1951	34.1	34.4	36.0	37.0	35.8	35.0	34.7						
					FRYERS (Heavy Breed)								
1940	21.5	19.5	19.3	21.5	21.3	22.4	18.6	17.9	19.4	19.5	19.7	19.4	20.0
1941	19.2	20.2	21.4	22.0	19.7	20.7	22.2	22.5	22.7	23.0	23.7	24.0	21.3
1942	25.8	24.0	23.5	25.3	26.7	27.0	27.6	29.0	29.9	31.0C	31.0	31.0	27.7
1943	33.0	31.5	31.6	31.9	31.1	30.9	30.9	30.9	30.9	30.9	30.9	30.9	31.3
1944	30.9	30.9	30.9	31.2	33.1	31.9	30.9	30.9	30.9	30.9	30.9	30.9	31.2
1945	31.0	31.3	32.3	32.7	33.1	32.0	31.7	31.7	31.6	31.6	31.6	31.6	31.8
1946	31.6	32.6	32.8	33.0	33.8	33.5C	35.2	38.1	40.4	47.3	43.0	44.6	37.1
1947	39.9	32.9	34.4	35.5	36.7	37.0	39.3	41.4	41.7	40.0	34.0	38.3	37.6
1948	40.5	40.5	41.6	44.4	42.3	44.0	41.2	39.0	39.6	38.8	39.1	40.0	40.2
1949	34.4	30.8	32.3	34.5	31.0	30.7	29.4	32.2	32.2	32.6	35.0	30.6	32.1
1950	24.6	29.7	36.0	34.7	30.3	29.7	34.3	35.2	34.6	31.0	26.5	27.3	31.3
1951	31.3	34.0	37.2	34.2	31.3	33.4	34.5						

C- Dates for the beginning and ending of ceilings were the same for Tampa as for Jacksonville.

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Yearly Avg.
			TALLAHASSEE MARKET-WHITE EGGS (Grade A, Large)					
1951	64.	55.0	55.0	56.0	58.5	62.3	64.5	59.3
					HENS (Heavy Breed)			
1951	32.0	35.0	36.5	34.0	33.9	35.0	34.0	34.3
					FRYERS (Heavy Breed)			
1951	31.0	34.4	36.5	34.0	31.5	33.0	32.5	33.4

POULTRY AND EGG WHOLESALE PRICES
MIAMI MARKET (January 1, 1940 - August 31, 1951)
WHITE EGGS (Grade A-24 oz.)

Year	Jan.	Feb.	Mar.	Apr.	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Yearly Avg.
1940	36.5	35.3	26.0	25.8	25.5	25.8	31.8	35.0	38.4	43.1	40.0	42.9	N
1941	38.3	31.7	28.1	29.0	31.6	34.1	38.6	41.5	43.1	45.0	47.8	48.0	N
1942	43.0	41.0	33.0	35.0	35.0	42.0	47.0	49.0	51.0	52.0C	52.0	52.0	44.4
1943	52.0	44.0	42.0	44.5	44.5	46.5	49.6	53.9	57.5	60.9	59.8	55.2	50.9
1944	51.5	47.5	44.5	44.5	44.5	45.5	50.0	54.5	57.6	58.0	60.5	59.3	51.5
1945	50.8	45.6	43.2	43.2	43.2	45.6	49.9	54.7	58.3	59.2	60.5	59.8	51.2
1946	50.7	45.5	43.2	43.2	43.2	45.8C	50.3	52.0	57.0	63.6	61.0	59.2	50.5
1947	53.1	52.0	52.2	57.6	54.5	53.7I	62.6	66.9	72.4	75.6	76.0	77.9	62.9
1948	66.6	52.0	53.9	56.7	54.0	60.0	62.4	66.7	70.0	71.8	75.4	74.8	63.6
1949	69.0	55.5	53.5	55.1	58.7	60.7	63.9	67.0	69.8	67.4	60.3	52.4	61.1
1950	44.7	39.9	44.6	44.0	41.2	46.0	52.3	54.9	59.0	63.9	69.3	74.7	52.8
1951	61.3	56.8	56.6	54.0	55.4	61.3	64.3	66.6					
HENS (Heavy Breed)													
1940	22.5	22.0	22.0	22.0	22.0	22.0	22.0	22.3	22.0	23.5	23.0	23.0	22.4
1941	23.0	23.0	23.0	23.0	23.5	24.5	26.5	25.0	25.0	25.0	25.5	26.0	24.4
1942	27.0	27.0	30.0	30.0	30.0	30.0	30.0	30.0	32.0	32.0C	28.0	28.0	29.5
1943	28.0	28.0	28.0	28.0	28.0	28.0	(- - No quotations on account of consider-						
1944	able price ceiling confusion - -)						29.7	29.7	29.7	29.7	29.7	29.7	29.7
1945	29.7	28.5	29.9	31.6	29.1	28.7	27.8	27.5	27.5	27.5	27.5	27.5	28.5
1946	27.5	27.5	27.5	27.5	31.4	32.4C	32.1	32.8	38.7	31.9	38.8	40.0	32.3
1947	41.4	40.6	41.9	41.3	40.9	38.3I	35.6	35.0	37.4	38.6	38.7	39.0	39.1
1948	40.9	43.3	44.4	45.0	42.6	39.3	38.5	39.0	38.3	37.8	37.3	36.7	40.3
1949	32.7	40.4	41.2	43.7	38.6	33.1	31.4	33.3	35.6	37.0	35.9	33.6	36.4
1950	30.3	29.8	29.9	29.9	26.5	25.0	25.4	28.8	31.0	29.9	31.8	34.3	29.3
1951	35.7	36.5	35.2	35.5	34.7	34.5	34.5	34.5					
FRYERS (Heavy Breed)													
1940	23.5	22.9	23.0	23.0	23.0	23.0	23.0	24.6	25.0	24.1	24.0	24.0	23.6
1941	25.0	25.0	27.0	26.5	25.0	25.0	26.0	25.0	25.0	25.0	26.0	27.0	25.6
1942	30.0	30.0	30.0	30.0	32.0	35.0	35.0	35.0	37.0	37.0C	32.0	32.0	33.0
1943	32.0	32.0	32.0	32.0	32.0	32.0	(- - No quotations on account of consider-						
1944	able price ceiling confusion - -)						33.2	33.2	33.2	33.2	33.2	33.2	33.2
1945	33.2	32.0	33.4	35.2	32.2	32.5	32.0	32.0	32.0	32.0	32.0	32.0	32.5
1946	32.0	32.0	32.0	32.0	35.9	37.1C	38.7	38.5	44.0	46.3	43.4	45.0	38.1
1947	39.2	35.0	39.6	40.0	41.3	43.0I	43.0	43.0	45.7	42.6	39.6	40.5	41.0
1948	45.1	46.2	46.7	49.4	45.3	44.2	42.3	42.0	41.2	40.1	39.4	38.7	43.3
1949	34.7	30.8	33.2	35.6	31.9	30.6	30.0	32.9	32.7	32.5	35.5	29.5	32.4
1950	24.0	30.6	36.1	33.6	30.3	29.5	33.9	35.5	34.5	30.3	29.1	28.2	31.3
1951	31.6	34.9	38.0	35.3	33.2	34.0	34.1	33.5					
ORLANDO MARKET-WHITE EGGS (Grade A, Large)													
1948	(Started)		58.0	61.8	62.8	64.5	67.9	73.5	75.1	77.6	78.0	72.5	69.2
1949	69.4	54.0	53.9	56.2	60.0	61.0	64.6	67.0	69.4	65.5	61.1	55.9	60.7
1950	48.3	42.0	47.1	46.5	44.3	47.9	54.3	57.1	61.5	64.2	65.6	78.4	54.7
1951	62.5	60.8	61.7	61.6	62.0	65.0	68.3	70.8					
HENS (Heavy Breed)													
1948	(Started)		36.2	37.0	35.5	34.5	33.0	33.1	34.1	35.1	37.9	40.9	35.7
1949	41.8	38.0	38.0	38.0	32.9	29.9	29.4	30.0	30.6	31.1	30.0	30.0	33.3
1950	25.8	25.0	28.1	27.1	23.0	23.0	23.0	24.2	28.4	26.5	28.0	30.0	26.0
1951	34.0	34.0	35.4	36.0	35.1	33.4	34.0	33.6					
FRYERS (Heavy Breed)													
1948	(Started)		44.6	44.6	41.1	41.0	38.3	38.6	40.1	38.9	39.1	37.8	40.4
1949	34.0	30.2	32.7	34.1	29.5	30.5	29.3	32.5	32.2	32.3	34.1	28.8	31.7
1950	23.4	27.4	34.8	32.2	29.9	30.0	33.3	34.7	33.9	29.7	27.4	26.8	30.2
1951	32.2	34.8	37.4	35.5	32.6	32.8	34.0	34.0					

For Miami"C" ceiling prices. The beginning and ending dates for ceilings were the same for Miami as for Jacksonville. N - Not calculated. I - Incomplete.

FLORIDA FLORICULTURE

By Neill Rhodes, Commissioner
Florida State Marketing Bureau

The Florida floricultural industry is growing more rapidly than is generally realized. The annual volume and value of Florida horticultural specialty crops gives this enterprise commercial, ranking importance. While the 1950 Census figures are unavailable at this writing, the 1945 Census figures showed the value of the Florida horticultural specialties sold was about 2½ times the value of the 1940 volume sold. The total season's value of the Florida horticultural-specialty production is probably not exceeded by more than four of Florida's principal vegetable crops. The Florida State Marketing Bureau has recognized the importance of, and served the Florida cut flower industry to the fullest extent possible under funds available. Beginning in 1946-47 and continuing regularly each season since, our daily reports have included the New York City flower quotations. Last season the Federal-State report from the Plant City station also included the New York flower market. Plans and tentative arrangements have been made for collecting truck passing reports for Florida gladiolus shipments in the 1951-52 season and possibly Florida f.o.b. gladiolus quotation service will be inaugurated the coming season.

Going farther back it was my pleasure November 26, 1941 to request Hon. J. Hardin Peterson to offer an amendment to the Federal Perishable Agricultural Commodities Act to include floricultural products, and Congressman Peterson introduced HR 6247. Incident to World War 2 consideration was deferred on this bill. At my request Congressman Peterson again introduced such a bill (HR 6869) June 10. 1948, which did not pass. Finally Congressman Peterson introduced an outright floricultural bill March 6, 1950, which received only committee consideration.

According to the New York State Department of Agriculture and Markets, from $10,000,000 to $15,000,000 worth of cut flowers pass through the New York City market annually. Some 50 wholesale commission merchants handle most of the floricultural products in Greater New York. One firm alone was reported to have done a million dollar business. Before the World War, cut flowers to New York went from Bermuda, Holland, South Africa and other lands, and still more from all over the United States to the New York market, particularly gladioli from Florida, gardenias from California carnations from New England, daffodils from the Gulf States, peonies from Jersey and the South and West, and orchids from the Middlewest.

In a Market News Service Study 1937-1944 by the New York Department it was pointed out that roses led in quantity as an individual crop - nearly fifty million annually, nearly half million in a single day, 458,612 for Mother's Day in 1939. In 1938 roses with total of 42,838,077 flowers led in receipts, asters with 34,910,184 ranked second, followed in turn by gladioli, carnations, sweet peas, daffodils, snapdragons and iris.

Analysis of the New York cut flower market for 1939 showed roses again the leading variety received, constituting about 30% of the total. Carnations were second as a strictly greenhouse crop. The total for outdoor grown material (including some greenhouse stock - daffodils, tulips, iris, pompons) was about 40%. In 1940 receipts of sweet peas, roses, daffodils, asters, gladioli, carnations, snapdragons, tulips, peonies, gardenias (Belmont), Easter lilies, dahlias, chrysanthemums, iris and chrysanthemum pompons (bunches) totalled 288,147,016 compared to 202,944,588 in 1939. Cut-flower production declined in war years as it became more difficult to operate under the many war-time restrictions, serious labor shortages, however gladioli showed the largest percentage of gain and top prices of $1.50 dozen December 1942 jumped to $3.50 dozen December 1943.

In 1944 shipments of most cut flowers continued to decrease, especially annual varieties. Perennials which could be produced with a minimum of labor predominated. Prior to 1939 Japanese lily bulbs and Holland tulips were considered superior to those locally grown, but by 1944 American growers had proven the fallacy of that belief.

Total shipments for 1945 were slightly below 1944, only carnations, chrysanthemums and tulips showed an increase. Roses, leading in shipments since 1941 dropped to third place. Asters and gladioli exceeded rose shipments and were the heaviest recorded in four years. Price ranges showed little variation.

The 1946 receipts on the New York City market were the highest since 1940. Gladioli reflected the greatest increase with shipments exceeding any year tabulated. October and November, with about 2½ million spikes each month, were the lightest; from 3½ to 5 million spikes per month were offered the balance of the year. Roses were second in volume, followed by asters and carnations. Receipts included flowers from practically every State along the Atlantic Coast, and others as far west as California. Orchids were received from South America, sweet peas and snapdragons from Haiti and Easter lily heads from Bermuda. Approximately 4½ million blooms were discarded either for poor quality on arrival or for lack of buyers. Analysis for 1947 under revision and unavailable now.

The 1948 receipts exceeded 1947 by over 8 million blooms, and were the largest since 1941. The sharpest increase was for gladioli - 5 million blooms over 1947. Gains were also recorded for roses, asters, carnations, sweet peas, gardenias and snapdragons. Daffodils, tulips, iris, peonies, and dahlias were shipped in lesser quantities than in 1947. Roses occupied first place in amount of blooms, with gladioli following a close second.

Approximately 1,000,000 more flowers were received on the New York market in 1949 than during 1948. Roses showed an increase of 8,000,000, iris 1,800,000,

(Cont'd. Page 78)

chrysanthemums 576,000. On the other hand there were 8 million less gladioli; 3 million fewer daffodils, 3 million fewer sweet peas; and a decline of 1 million tulips, 800,000 carnations, and 500,000 gardenias. Roses, gladioli and carnations were the three most important flowers on the New York market in 1949, followed by snapdragons and daffodils. Among corsage items, gardenias were received in the greatest quantity, with hybrid orchids next, followed by other varieties of orchids. Of the greatest seasonal importance were peonies, tulips, chrysanthemum pompons and chrysanthemums.

In 1950 some 181,528,287 flowers supplied some 4,000 to 5,000 retail florists in the metropolitan area, representing receipts of surplus flowers from all parts of the country. About 1-2/3% of the flowers reported were dumped. Gladioli, dahlias, peonies and tulips were in heavier receipt over 1949. Gladioli, although in heavier receipt, showed a smaller percentage of wastage, and a generally higher average price. Lighter offerings of gardenias and orchids met better sale than in 1949 due to increased number of weddings since the Korean War.

There has been considerable expansion in the last few years in the production of orchids in Florida. Authorities concede that Florida is now generally regarded as the hibiscus center of the world. Two recent hibiscus shows in Florida were each attended by 10,000 visitors. Blooms from hundreds of popular varieties and the newer introductions from seedlings and cross-pollination were displayed to enthusiasts from many states.

The buds of beautiful flowers of much of Florida floriculture such as the blossoms of the camellia, azalea, hibiscus and many others, growing profusely throughout the State to the admiration and pleasure of the Florida citizenry and visiting population as well, are borne upon the plants of luxuriant foliage sold ready-to-plant in many sections of the United States.

It is with pride that we devote space in the 1950-51 Annual Fruit and Vegetable Report in recognition of this up-and-growing industry which has attained such striking proportions in such relatively short time.

GLADIOLUS RECEIPTS AND PRICE RANGES NEW YORK CITY MARKET

Month	1944		1945		1946	
	Receipts (Bunches)	Price Range	Receipts (Bunches)	Price Range	Receipts (Bunches)	Price Range
Jan.	2,627,988	$ .25-3.00	2,685,804	$ .25-3.00	4,459,224	$ .15-2.50
Feb.	3,647,316	10-2.00	2,524,860	25-3.00	3,206,724	25-4.00
Mar.	2,173,800	10-3.00	3,463,908	50-3.00	3.401,652	10-3.00
Apr.	1,914,924	15-3.50	3,136,344	25-2.50	4,842,120	10-2.50
May	1,353,576	15-4.00	3,052,968	25-4.00	5,636,568	10-2.00
June	1,527,348	50-4.00	3,629,784	10-2.50	3,416,604	15-2.50
July	4,642,692	10-2.50	3,667,984	10-2.00	4,879,032	10-1.50
Aug.	3,613,908	5-1.00	4,145,496	10-1.25	4,577,292	10-1.50
Sept.	3,256,032	15-2.00	4,526,268	5-1.50	3,585,516	10-1.50
Oct.	1,440,144	50-2.50	741,708	10-3.50	2,555,904	10-1.25
Nov.	255,360	50-2.50	669,564	50-2.50	2,555,220	10-1.50
Dec.	1,150,704	33-4.00	2,670,852	50-4.00	4,506,011	15-3.00
Tot.Rec.	27,603,792		34,917,500		47,621,868	
Price Range		$ .05-4.00		$ .05-4.00		$ .10-4.00

Month	1948		1949		1950	
	Receipts (Bunches)	Price Range	Receipts (Bunches)	Price Range	Receipts (Bunches)	Price Range
Jan.	4,581,840	$ .15-2.50	3,729,612	$ .25-2.50	3,216,780	$ .15-2.50
Feb.	4,661,316	10-2.00	3,866,328	20-2.50	2,939,184	25-6.00
Mar.	5,128,332	15-2.00	2,864,628	25-2.50	4,004,124	25-2.00
Apr.	4,811,240	15-2.00	3,122.556	15-2.50	3,604,044	15-2.50
May	4,033,596	15-2,50	4,279,704	10-2.00	4,922,604	15-2.00
June	5,426,508	10-2.00	4,966,440	15-1.50	5,230,332	15-1.75
July	4,882,224	15-1.50	5,012,952	10-1.50	4,700,436	10-1.50
Aug.	3,642,792	10-1.25	3,610,140	15-1.50	4,637,508	10-1.00
Sept.	4,021,788	10-1.50	3.318,072	15-1.75	4,929,672	10-1.25
Oct.	2,414,508	15-2.00	1,133,616	10-1.50	3,452,124	20-1.50
Nov.	2,211,238	20-2.00	1,403,508	10-2.00	1,382,004	20-2.00
Dec.	3,608,208	20-2.50	3,227,940	25-2.50	1,994,316	50-6.00
Tot.Rec.	49,423,740		41,952,048		45,013,128	
Price Range		$ .10-2.50		$.10-2.50		$.10-6.00

NOTE: We have similar records for years 1939 to 1944, inclusive, which we omitted for lack of space.

ACKNOWLEDGMENT: All data pertaining to the New York City market extracted from summaries provided by courtesy of Director H. J. Mather, Metropolitan Division, Bureau of Markets, Market News Service.

LAND UTILIZATION, PRODUCTION AND VALUE

The 1945 U.S. Census shows 34.7 million acres of land in Florida. Of this amount nearly 38 percent was in farms or a little over 13 million acres. There were close to 61,000 farms in the state at the time of the 1945 census. Of this acreage in farms, less than 25 percent was in cropland, the remainder being in pastures, woodland pastures and other woodland. Land on which Florida's large assortment of 39 different crops were planted or growing in 1950 totaled slightly over 2.2 million, or about 92 thousand acres above plantings the year before. From this acreage over 6 million tons of food and feed were produced. This output exceeds the previous record crop of 5.9 million tons of food and feed produced in 1948-49 by 2 percent. The value of crops harvested in the state during the 1949-50 season was also the largest of record, showing a 22 percent increase over the preceding year. The total value of all crops harvested is estimated at about $371 million, compared with a value of $304 million in 1948-49. Citrus and field crops were primarily responsible for the higher value as the value of vegetables produced dropped 11 percent under the year before due to an unusually heavy economic abandonment and lower prices. A breakdown in valuation shows fruits and nuts accounted for $202,037,000; vegetables $110,010,000; and field crops $58,751,000.

An inventory of livestock on Florida farms January 1, 1951 showed 1,503,000 head of cattle, 631,000 hogs, 23,000 horses, 28,000 mules, 12,000 sheep, 2,702,000 chickens, and 26,000 turkeys. The total valuation of these numbers was - cattle $146,392,000, hogs $14,955,000, horses $1,836,000, mules $3,220,000, sheep $144,000, chickens $4,269,000, and turkeys $174,000, for a record total valuation of livestock and poultry on farms January 1, 1951 of $171,040,000. In the United States, Florida ranks 23rd in the number of cattle and 12th in the number of beef cattle.

FIELD CROPS

Florida farmers planted 1,325,100 acres of field crops in 1950, including peanuts, oats, and lupine pastured. This acreage was 22,000 above 1949 plantings which amounted to 1,303,400 acres. From the standpoint of value, the 1950 all tobacco crop exceeded other field crops with a value of production of $19.4 million. Type 14 tobacco or flue-cured accounted for $9.4 million. The crop was grown on 18,000 acres from which 18,270,000 pounds were produced. Type 62 or shade tobacco completes the tobacco picture in the state being grown in Madison and Gadsden Counties. From only 4,200 acres a crop of 4,998,000 pounds was produced, selling for almost $10,000,000. Florida's 1950 record corn crop was next in line from the standpoint of value of production and the 723,000 planted acres topped all other crops from an acreage standpoint as well. From this acreage, 9,968,000 bushels were produced with estimated value of $13,955,000. The total acreage planted in peanuts including acreage interplanted with corn amounted to only 262,000 acres, the smallest acreage reported for any year since 1930. Of this amount, 72,000 acres were harvested and the remainder used as feed for hogs. The harvested acreage produced 59,040,000 pounds of peanuts valued at $5,609,000. Florida sugarcane producers reported a record crop of 1.2 million tons of cane produced from 38.5 thousand acres and valued at $9.0 million. About 105 tons of raw sugar and 7.4 million gallons of black strap molasses were also produced from the 1950 acreage. Most of Florida's 123,000 acres of oats grown last year were either grazed or plowed under. Only about 16,000 acres were harvested for grain or cut and fed unthreshed in the bundle.

Hay crops in Florida were produced on about 88,000 acres last year, most of which is peanut hay or 67,000 acres of this amount came from peanuts that had been harvested for nuts. There were 53,000 tons of all hay produced valued at $928,000. Cotton, once an important crop in the state, has gradually declined until 1950 plantings amounted to only 32,000 acres, a near record low. From this relatively small acreage, 14,000 bales were produced, valued at $2,569,000. Other minor crops that help make up the field crop picture for the state are 27,000 acres of cowpeas, 8,000 acres of syrup cane and 172,000 acres of velvetbeans.

FRUITS AND NUTS

Citrus, Florida's most important fruit crop, in 1949-50 amounted to 87,960,000 boxes. Florida now leads all other states both as to acreage in bearing and production. In 1949-50 there were 428,400 acres of producing citrus groves in Florida, out of the 819,000 acres in the United States. California, Florida's nearest competitor, had 284,200 acres, while Texas in the third place spot accounted for 84,000 acres, a sharp drop from the 122,500 of a year earlier. Arizona with 17,900 acres and Louisiana with 4,500 acres are the only other states with any appreciable citrus acreage. The Florida bearing acreage is composed of 300,900 acres of oranges, 98,500 grapefruit, 24,200 tangerines, and 4,800 limes. In the 1949-50 season, Florida produced slightly over 87.9 million boxes of citrus, out of a total production of 156.2 million boxes for the United States. In other words, Florida produced more than 56 percent of the citrus produced in the United States during 1949-50 season. California produced 55.3 million boxes during this same year for the second smallest crop since 1936-37. A breakdown of the 87.9 million boxes of citrus produced in the state last year reveals 58,500,000 boxes of oranges, grapefruit 24,200,000, tangerines 5,000,000 and limes 260,000. In addition to the citrus fruits, small quantities of grapes, peaches, pears, and pineapples are produced in scattered areas over the state. Of the nut crops produced in the state, pecans and tung nuts are the only ones of any importance. The 1950 season produced 4,891,000 pounds of pecans and 6,200 tons of tung nuts. The value of the harvested production of fruit crops during the 1949-50 season amounted to $202,087,000. Citrus makes up the biggest percentage of this amount, being estimated at $199,110,000. Tung nuts accounted for $517,000, pecans $1,350,000, avocadoes $737,000, and peaches and pears valued at $294,000.

VEGETABLES

There were 364,350 acres of vegetables planted in Florida in 1949-50, about 39,000 acres were lost from floods, freezes, etc., leaving 326,100 acres for harvest. This acreage produced 1,463,400 tons of vegetables valued at $110 million. Approximately 171,000 tons of vegetables were left in the field unharvested due to economic reasons. Economic abandonment during the 1948-49 season was much less than last year amounting to only 47,000 tons. Also in 1948-49 there were 308,800 acres of vegetables planted, 286,650 acres harvested, with a production of 1,195,900 tons valued at $121.5 million. Vegetable yields were generally lower this year, but the larger acreage boosted production above the preceding year. In the UNITED STATES, Florida is one of the leading states in the production of fall, winter, and spring vegetables. The state now ranks first in the production for fresh market of snap beans, cucumbers, eggplant, escarole, and peppers. From an acreage standpoint, snap beans is the most important vegetable grown in the state. In 1950, Florida farmers planted 99,500 acres of snap beans. Of this, 77,600 acres were harvested with a production of 7,234,000 bushels which were sold for $17,116,000. Watermelons were the next most important vegetable crop produced accounting for 70,000 acres, producing over 14.9 million melons for a return of $5,870,000. From the standpoint of valuation, tomatoes exceeded all other crops with the 1949-50 crop being valued at over $31 million. The 1949-50 tomatoe crop was produced from 43,800 acres yielding 8,051,000 bushels. Celery ranked high from the standpoint of valuation during the 1949-50 season producing a crop valued at nearly $12.5 million, from 9,750 acres. Other important vegetables included 16,300 acres of green peppers producing 3,810,000 bushels valued at $6,380,000. Irish potatoes were planted on 23,900 acres from which a record 5,524,000 bushels were harvested, with a valuation of $9,215,000. A somewhat higher cabbage acreage which totaled 18,000 acres yielded 185,800 tons valued at $3,855,000. The value of cucumbers amounted to nearly $6.5 million when 16,950 acres produced 2,283,000 bushels. Strawberry plantings covered 5,400 acres, yielding 432,000 crates which brought $3,888,000. In addition to the above crops, Florida also produces quantities of cantaloups, carrots, cauliflower, eggplant, escarole, lettuce, and green peas.

LIVESTOCK AND POULTRY

The importance of livestock and poultry as a part of the Florida agricultural farm program continues to expand over many areas of the state. During 1950 there were about 191,460,000 pounds of beef produced, for a gross income of $35,317,000. Of almost equal importance was Florida pork production of $125,388,000 pounds which was valued at $21,040,000. From the standpoint of value, Florida's important dairy industry almost equalled gross income realized from both beef and pork produced. During 1950 the total gross income from all dairy products including some butter amounted to $40 million. Income from Florida poultry was also at a fairly high level, but did not reach the high level of production in 1949. Production dropped to 11,793,000 pounds for a gross income of $4,032,000. In addition, commercial broilers sold in 1950 brought poultry raisers a gross income of $8,123,000 from the sale of 9,036,000 broilers representing 26,204,000 pounds. From a laying flock of 2,431,000 hens and pullets, Florida produced 251,000,000 eggs, representing a gross income of $9,607,000. During 1950 the gross income received from livestock and poultry products amounted to $118.1 million.

NOTE: The foregoing is a copy of a report dated July 26, 1951, issued by the U.S. Bureau of Agricultural Economics, Federal Building, Orlando, Florida. This report covers most of the agriculture of Florida and should be of interest to those who get the Annual Statistical Report of the Florida State Marketing Bureau.

F. H. Scruggs

AVERAGE PRICES RECEIVED FOR FARM PRODUCTS BY FARMERS - INDEX NUMBERS

Commodity	Unit	FLORIDA Sept. 15 1950	FLORIDA Aug. 15 1951	FLORIDA Sept. 15 1951	UNITED STATES Average Aug. '09 to July 1914	UNITED STATES Sept. 15 1950	UNITED STATES Aug. 15 1951	UNITED STATES Sept. 15 1951
Corn	Bu.	$ 1.50	1.76	1.70	.642	1.44	1.65	1.65
Oats	Bu.	$ 1.50	1.25	1.35	.399	.728	.759	.775
Potatoes	Bu.	$ 1.50	1.40	1.40	.697	1.05	1.17	1.23
Sweet Potatoes	Bu.	$ 2.50	2.45	2.50	.878	1.92	2.73	2.87
Cotton	Lb.	¢ 39.3	34.8	34.0	12.4	[illegible]	3[illegible].60	33.73
Cottonseed	Ton	$ 76.00	62.00	59.00	22.55	76.[illegible]	[illegible].10	66.10
Tobacco	Lb.	¢ -----	44.0	----	10.0	5[illegible].4	47.7	52.4
Peanuts	Lb.	¢ 10.1	10.6	10.5	4.8	10.9	10.[illegible]	11.0
Cowpeas	Bu.	$ 6.00	4.30	4.30	----	3.57	3.[illegible]	3.79
Hogs	Cwt.	$ 19.00	21.00	19.10	7.27	a/21.00	2[illegible].2[illegible]	19.70
Beef Cattle	Cwt.	$ 19.90	24.80	24.50	5.42	a/24.60	29.10	29.50
Veal Calves	Cwt.	$ 24.90	28.80	27.80	6.75	a/27.30	32.60	32.80
Sheep	Cwt.	$ 11.00	13.50	13.00	4.53	a/11.80	15.00	14.70
Lambs	Cwt.	$ 19.50	28.70	28.70	5.38	a/25.70	29.80	29.80
Milk Cows	Head	$ 150	195	195	48	209	247	250
Chickens	Lb.	¢ 33.0	31.9	31.2	11.4	24.5	26.0	25.2
Turkeys	Lb.	¢ 50.0	42.0	41.0	14.4	33.5	35.3	36.3
Eggs	Doz.	¢ 52.0	60.0	62.0	21.5	40.4	49.7	55.0
Butter	Lb.	¢ 59.0	60.0	62.0	25.5	57.3	60.1	60.7
Butterfat	Lb.	¢ 57.0	60.0	60.0	26.3	60.9	68.5	68.4
Milk, Wholesale	Cwt.	$ 6.70	6.55	6.65	1.60	a/4.02	4.45	4.60
Milk, Retail b/	Qt.	¢ 21.7	22.5	22.5	6.8	18.7	19.9	20.0
Wool	Lb.	¢ 50.0	65.0	75.0	18.3	a/65.6	77.1	66.9
Hay, baled	Ton	$ 17.60	22.00	20.20	----	20.30	20.40	21.30
Oranges on tree c/	Box	$ -----	----	----	----	1.23	1.58	1.63
Tangerines " c/	Box	$ ----	----	----		(Included in Oranges)		
Grapefruit " c/	Box	$ 1.92	----	----	----	1.52	.7[illegible]	1.10
Limes, on tree c/	Box	$ .98	1.02	1.40	----	----	----	----

a/ Revised. b/ Sold by farmers directly to consumers.
c/ All citrus, including limes, are 1-3/5 bushel boxes.

INDEX NUMBERS	FLORIDA August 1909 - July 1914 equals 100.			UNITED STATES January 1910-December 1914 equals 100.		
	Sept. 15 1950	Aug. 15 1951	Sept. 15 1951	Sept. 15 1950	Aug. 15 1951	Sept. 15 1951
ALL FARM PRODUCTS	230	172	172	272	2[illegible]2	[illegible]
Grain	172	201	194	---	---	---
Food Grain	---	---	---	221	234	233
Feed Grain and Hay	---	---	---	194	215	216
Cotton and Cottonseed	255	224	219	---	---	---
Cotton	---	---	---	336	2[illegible]1	283
Dairy Products	205	207	209	246	277	283
Poultry and Eggs	212	234	238	196	231	247
Meat Animals	374	447	432	372	416	411
Citrus	218	71	71	---	---	---
Fruits	---	---	---	217	207	201
Truck Crops	210	180	180	126	161	161
Miscellaneous	323	319	320	---	---	---

NOTE: The above tabulations arranged from material furnished by the Bureau of Agricultural Economics, Orlando, Florida.

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS
(For Selected Years)

	1920			1922		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	8,668,000	$ 9,795,000	Bu.	8,888,000	$ 7,110,000
Cotton	Bale	20,000	1,782,000	Bale	28,000	2,902,000
Tobacco	Lbs.	4,200,000	2,041,000	Lbs.	3,330,000	1,551,000
Peanuts (Picked & Threshed)	Lbs.	40,000,000	2,520,000	Lbs.	26,875,000	1,344,000
Sweet Potatoes	Bu.	2,300,000	3,174,000	Bu.	1,680,000	2,184,000
Cow Peas	Bu.	Included in Other Field Crops				
Oats	Bu.	255,000	230,000	Bu.	180,000	137,000
Velvet Beans	Tons	Included in Other Field Crops				
Hay	Tons	83,000	1,768,000	Tons	64,000	1,254,000
Sugar Cane Syrup	Gals.	3,675,000	3,454,000	Gals.	2,320,000	1,067,000
Sugar-Raw	Tons	No Record		Tons	No Record	
Black Strap Molasses	Gals.	No Record		Gals.	No Record	
Pecans	Lbs.	440,000	141,000	Lbs.	880,000	309,000
Total Incomplete			$24,905,000			$17,858,000
Other Field Crops	Misc.		* 2,000,000	Misc.		* 1,400,000

	1924			1925		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,200,000	$ 7,848,000	Bu.	8,262,000	$ 7,684,000
Cotton	Bale	21,000	2,451,000	Bale	43,000	4,561,000
Tobacco	Lbs.	4,091,000	1,916,000	Lbs.	5,810,000	1,743,000
Peanuts (Picked & Threshed)	Lbs.	28,350,000	1,474,000	Lbs.	23,400,000	1,147,000
Sweet Potatoes	Bu.	1,764,000	2,699,000	Bu.	1,840,000	3,386,000
Cow Peas	Bu.	54,000	170,000	Bu.	36,000	129,000
Oats	Bu.	148,000	138,000	Bu.	125,000	85,000
Velvet Beans	Tons	59,000	844,000	Tons	53,000	753,000
Hay	Tons	58,000	1,119,000	Tons	51,000	1,061,000
Sugar Cane Syrup	Gals.	1,350,000	1,350,000	Gals.	1,650,000	1,732,000
Sugar-Raw	Tons	No Record		Tons	No Record	Very Light
Black Strap Molasses	Gals.	No Record		Gals.	No Record	Very Light
Pecans	Lbs.	1,300,000	449,000	Lbs.	1,916,000	609,000
Total Incomplete			$20,458,000			$22,890,000
Other Field Crops	Misc.		* 1,500,000	Misc.		* 1,500,000

	1928			1930		
Commodity	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,073,000	$ 7,427,000	Bu.	5,886,000	$ 5,180,000
Cotton	Bale	22,000	1,091,000	Bale	56,000	2,720,000
Tobacco	Lbs.	8,635,000	2,539,000	Lbs.	9,748,000	2,672,000
Peanuts (Picked & Threshed)	Lbs.	28,175,000	1,352,000	Lbs.	26,520,000	902,000
Sweet Potatoes	Bu.	1,700,000	2,465,000	Bu.	1,360,000	1,646,000
Cow Peas	Bu.	48,000	162,000	Bu.	86,000	233,000
Oats	Bu.	135,000	92,000	Bu.	112,000	87,000
Velvet Beans	Tons	68,000	877,000	Tons	44,000	572,000
Hay	Tons	54,000	1,048,000	Tons	48,000	830,000
Sugar Cane Syrup	Gals.	1,485,000	1,262,000	Gals.	1,530,000	994,000
Sugar-Raw	Tons	1,000	No Record	Tons	27,000	No Record
Black Strap Molasses	Gals.	134,000	No Record	Gals.	2,202,000	No Record
Pecans	Lbs.	2,000,000	545,000	Lbs.	1,150,000	302,000
Total Incomplete			$19,670,000			$16,138,000
Other Field Crops	Misc.		* 2,500,000	Misc.		* 2,000,000

* Estimated by Marketing Bureau

Source: U.S. Bureau of Agricultural Economics, Orlando, Florida.

VOLUME AND VALUE OF FLORIDA GENERAL FARM CROPS (Cont'd.)

(For Selected Years)

Commodity	1932			1935		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	6,350,000	$ 2,921,000	Bu.	7,496,000	$ 5,322,000
Cotton	Bale	18,000	556,000	Bale	31,000	1,576,000
Tobacco	Lbs.	3,310,000	836,000	Lbs.	8,680,000	2,398,000
Peanuts (Picked & Threshed)	Lbs.	24,070,000	1,361,000	Lbs.	38,430,000	1,114,000
Sweet Potatoes	Bu.	1,560,000	1,232,000	Bu.	1,610,000	1,368,000
Cow Peas	Bu.	94,000	99,000	Bu.	88,000	154,000
Oats	Bu.	75,000	28,000	Bu.	112,000	77,000
Velvet Beans	Tons	60,000	255,000	Tons	70,000	700,000
Hay	Tons	41,000	369,000	Tons	52,000	582,000
Sugar Cane Syrup	Gals.	1,760,000	634,000	Gals.	2,660,000	984,000
Sugar-Raw	Tons	37,000	**(1,295,000)	Tons	42,000	**(1,470,000)
Black Strap Molasses	Gals.	3,489,000	248,900	Gals.	3,292,000	395,040
Pecans	Lbs.	625,000	80,000	Lbs.	1,400,000	153,000
Total Incomplete			$ 9,914,900			$16,293,040
Other Field Crops	Misc.		* 1,500,000	Misc.		* 2,000,000

Commodity	1938			1940		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,760,000	$ 4,656,000	Bu.	8,418,000	$ 5,893,000
Cotton	Bale	26,000	1,158,000	Bale	21,000	1,102,000
Tobacco	Lbs.	19,720,000	5,325,000	Lbs.	16,328,000	4,552,000
Peanuts (Picked & Threshed)	Lbs.	56,250,000	1,688,000	Lbs.	68,400,000	1,915,000
Sweet Potatoes	Bu.	1,400,000	1,274,000	Bu.	900,000	810,000
Cow Peas	Bu.	48,000	75,000	Bu.	40,000	67,000
Oats	Bu.	140,000	69,000	Bu.	154,000	102,000
Velvet Beans	Tons	57,000	661,000	Tons	59,000	649,000
Hay	Tons	70,000	763,000	Tons	70,000	665,000
Sugar Cane Syrup	Gals.	1,815,000	817,000	Gals.	1,120,000	560,000
Sugar-Raw	Tons**	(920,000)	**(3,680,000)	Tons**	(970,000)	**(4,268,000)
Black Strap Molasses	Gals.	5,497,000	**(657,000)	Gals.	5,170,000	**(1,125,000)
Pecans	Lbs.	3,575,000	309,000	Lbs.	3,564,000	341,000
Total Incomplete			$21,132,000			$22,049,000
Other Field Crops	Misc.		* 2,500,000	Miscl.		* 3,000,000

Commodity	1941			1942		
	Unit	Production	Farm Value	Unit	Production	Farm Value
Corn	Bu.	7,200,000	$ 5,904,000	Bu.	7,766,000	$ 8,154,000
Cotton	Bale	18,000	1,461,000	Bale	17,000	1,534,000
Tobacco	Lbs.	13,711,000	4,052,000	Lbs.	14,778,000	6,808,000
Peanuts (Picked & Threshed)	Lbs.	57,800,000	2,312,000	Lbs.	65,550,000	3,343,000
Sweet Potatoes	Bu.	1,260,000	1,399,000	Bu.	1,122,000	1,560,000
Cow Peas	Bu.	45,000	102,000	Bu.	45,000	122,000
Oats	Bu.	160,000	107,000	Bu.	210,000	176,000
Velvet Beans	Tons	65,000	845,000	Tons	53,000	742,000
Hay	Tons	64,000	813,000	Tons	72,000	979,000
Sugar Cane Syrup	Gals.	1,750,000	962,000	Gals.	1,980,000	1,287,000
Sugar-Raw	Tons	949,000	3,768,000	Tons	947,000	3,072,000
Black Strap Molasses	Gals.	5,157,000	**(928,000)	Gals.	4,150,000	**(750,000)
Pecans	Lbs.	4,672,000	474,000	Lbs.	4,600,000	752,000
Total Incomplete			$23,127,000			$29,279,000
Other Field Crops	Misc.		* 3,300,000	Misc.		* 3,500,000

* Estimated by the State Marketing Bureau

** Figures in parenthesis ( ) are estimates from unofficial sources.

PRODUCTION VOLUME AND FARM VALUE OF FLORIDA PRINCIPAL FIELD CROPS

PRODUCTION VOLUME

Florida Commodity	Units	1942	1943	1944	1945	1946	1947	1948	1949	1950	(Prelim. Estimate) 1951
			(Thousands	Omitted)							
Corn	Bu.	7,766	8,522	7,550	7,755	6,910	8,292	6,910	8,983	9,968	10,890
Cotton	Bale	16	16	13	8	6	11	15	16	13	30
Tobacco	Lbs.	14,778	14,910	20,095	20,082	22,251	26,812	20,846	25,143	23,268	30,060
Peanuts(Picked & Threshed)	Lbs.	65,550	74,800	62,500	66,000	46,500	69,300	85,250	51,255	59,040	54,000
Sweet Potatoes	Bu.	1,122	1,365	1,165	1,024	1,088	1,275	960	980	1,050	780
Cow Peas	Bu.	45	36	32	36	40	36	32	40	28	#
Oats	Bu.	210	300	704	900	720	600	399	288	288	500
Velvet Beans	Bu.	53	62	48	56	44	44	45	58	60	#
Sugar Cane Syrup	Gals.	1,980	2,040	2,400	2,090	1,980	2,400	1,980	1,620	1,360	#
Sugar Cane for Sugar	Tons	648	699	780	1,041	1,037	921	1,010	1,126	1,233	#
Black Strap Molasses	Gals.	4,100*	4,100*	5,400*	5,700*	6,711	5,400	7,138	6,896	7,685	#
Pecans	Lbs.	4,600	4,524	5,100	4,234	4,526	2,774	5,475	3,650	5,200	5,256
Hay	Tons	72	66	64	63	57	63	69	52	53	55

FARM VALUE

Florida Commodity	Units	1942	1943	1944	1945	1946	1947	1948	1949	1950	1951 #
			(Thousands	Omitted)							
Corn	Bu.	$ 8,154	$13,124	$12,231	$13,339	$13,060	$17,662	$11,747	$11,768	$13,955	NO ESTIMATE AVAILABLE
Cotton	Bale	1,534	1,591	1,343	896	933	1,703	2,303	2,347	2,569	
Tobacco	Lbs.	6,808	8,883	10,421	10,923	15,739	18,188	18,279	17,238	19,387	
Peanuts(Picked & Threshed)	Lbs.	3,343	5,236	4,688	5,280	3,860	6,514	8,440	5,126	5,609	
Sweet Potatoes	Bu.	1,560	3,044	2,821	2,652	2,959	3,226	2,544	2,597	2,468	
Cow Peas	Bu.	122	141	153	174	220	252	191	217	157	
Oats	Bu.	176	342	887	963	994	990	674	395	418	
Velvet Beans	Bu.	742	1,240	1,152	1,568	1,408	1,408	1,440	2,030	2,100	
Hay	Tons	979	1,063	1,062	1,147	1,037	1,266	1,270	894	928	
Sugar Cane Syrup	Gals.	1,287	2,040	2,280	2,090	3,168	3,000	1,584	1,134	1,428	
Sugar-Raw	Tons	3,072	3,062	3,689	6,381	7,207	6,309	5,212	7,285	9,347	
Black Strap Molasses	Gals.	750	750	1,000	1,200	1,200	1,080*	1,472*	1,380*	1,516	
Pecans	Lbs.	752	1,060	1,143	1,010	1,507	628	605	652	1,438	
Group Totals		$29,279	$41,576	$42,870	$47,623	$53,342	$62,226	$55,761	$53,063	~~47,365~~ 61,370	
Other Field Crops (a)		$ 3,500	$ 4,500	$ 5,000	$ 5,200	$ 5,500	$ 6,000	$ 5,500	$ 5,000	$5,000	

* Estimates from unofficial sources. All other production and farm value figures supplied by the U.S. Agricultural Statisticians, B.A.E., Federal Building, Orlando, Florida.

# No estimate by U.S. Bureau of Agricultural Economics as of September 15. (a) Misc. crops not otherwise reported.

RECORD U.S. TURKEY CROP THIS YEAR

Farmers are raising a record crop of 53,774,000 turkeys this year -- 16 percent more than last year, according to a preliminary estimate of the U.S. Bureau of Agricultural Economics office in Orlando, Florida.

Last January, following the 1950 marketing season with the lowest turkey prices since 1943 and slightly higher feed prices, farmers expressed their intentions to raise only 1 percent more turkeys in 1951 than in 1950. However, steadily rising turkey prices during the hatching season, amounting to 6 percent during the first half of this year, contrary to a drop of 12percent last year and the average seasonal decrease of 9 percent, encouraged turkey growers to increase their 1951 turkey production by about 7 million birds over last year.

BELTSVILLE WHITE TURKEYS INCREASE

Beltsville White turkeys have been increasing rapidly during the last two years to meet a year-round demand for young turkeys 14-17 weeks old weighing 4-8 pounds dressed. To meet this fast growing demand Beltsville Whites are now being produced the year round so that they can be sold on the market as fresh killed young birds. Of all the Beltsville Whites raised in the United States, a large part of them are sold at 4-8 pounds dressed as young roasters, fryers and broilers, and the balance of the crop, part of the early spring hatch, are raised to 6 or 7 months old for the holiday trade.

Turkey producers were asked to report for the first time, the number of Beltsville White turkeys being raised in 1951. They also reported the number of Beltsville Whites raised in 1950. These reports show about 16 percent of all the turkeys being raised this year are Beltsville Whites, compared with 12 percent last year. Beltsville Whites as a percent of all turkeys raised in 1951 are 40.7 percent in the South Atlantic, 15.4 percent in the West North Central, 13.7 percent in the West, 10.6 percent in the North Atlantic, 9.6 percent in the East North Central, and 8.0 percent in the South Central States. The actual number of Beltsville Whites this year shows an increase of 55 percent from last year. This increase is responsible for about two-fifths of the increase in the total turkey crop this year. All regions of the country show large increases in numbers of Beltsville Whites raised compared with last year, ranging from 24 percent in the East North Central to 90 percent in the South Atlantic States.

BELTSVILLE WHITE TURKEYS AS A PERCENT OF ALL TURKEYS REPORTED BEING RAISED

Geographic Divisions	1950	1951
North Atlantic	7.9 percent	10.6 percent
East North Central	8.8	9.6
West North Central	9.3	15.4
South Atlantic	29.7	40.7
South Central	7.0	8.0
Western	10.5	13.7
United States	11.7	15.7

PERCENTAGE OF U.S. TURKEY CROP MARKETED IN DIFFERENT MONTHS

Geographic Divisions	1950 Crop				1951 Crop (intended)			
	Oct. or earlier	Nov.	Dec.	Jan. or later	Oct. or earlier	Nov.	Dec.	Jan. or later
N.Atlantic	11.6	40.6	31.1	16.7	15.3	42.0	31.0	9.7
E.N.Central	16.3	41.7	34.3	7.7	22.1	42.1	30.7	5.1
W.N.Central	33.7	41.0	21.7	3.6	38.2	37.3	20.9	3.6
S.Atlantic	28.0	37.3	28.4	6.3	34.9	33.6	23.9	7.5
S.Central	14.2	29.2	44.6	12.0	24.1	31.9	33.3	10.7
Western	22.3	40.6	26.7	10.4	31.3	33.0	26.6	9.1
United States	23.3	29.0	29.2	8.5	30.2	35.9	26.6	7.3

PERCENTAGE OF U.S. TURKEY CROP MARKETED IN DIFFERENT MONTHS

Year	Oct.or earlier	November	December	Jan.or later
1951 1/	30.2	35.9	26.6	7.3
1950	23.3	39.0	29.2	8.5
1949	23.3	38.3	28.5	9.9
1948	19.5	40.1	31.2	9.2
1947	19.8	40.5	32.1	7.6
1946	22.3	36.7	28.4	12.6
1945	19.5	36.4	30.0	14.0
1944	16.6	38.7	30.9	13.8
1943	10.1	41.1	35.2	13.6
1942	11.8	41.1	36.3	10.8
1941	8.5	39.8	38.9	12.8
1940	8.8	42.1	36.9	12.2

1/ Marketing intentions for 1951.

NOTE: Storage stocks of dressed turkeys were 30 million pounds in August 1951, as compared to 47 million pounds a year earlier. The storage holdings of 30 million pounds were the equivalent of only 4% of the whole turkey crop in 1950.

(The foregoing was a fairly complete abstract of a report dated August 21, 1951 issued by the U.S. Bureau of Agricultural Economics, Federal Building, Orlando, Fla.)

FLORIDA TOBACCO

Flue Cured (Bright Leaf) Type No. 14

Year	Acreage	Production	Estimated Farm Value
1932	2,000	1,200,000 Lbs.	$ 132,000 or 11¢ per Lb.
1933	5,000	3,700,000	444,000 " 12¢ " "
1934	4,700	3,408,000	682,000 " 20¢ " "
1935	7,000	6,020,000	1,066,000 " 17.7¢ " "
1936	8,000	7,200,000	1,584,000 " 22¢ " "
1937	16,800	14,112,000	2,978,000 " 21.1¢ " "
1938	16,300	15,892,000	3,226,000 " 20.3¢ " "
1939	29,500	20,650,000	2,540,000 " 12.3¢ " "
1940	12,700	11,748,000	2,056,000 " 17.5¢ " "
1941	11,300	8,192,000	1,745,000 " 21.3¢ " "
1942	13,000	11,180,000	3,611,000 " 32.3¢ " "
1943	13,600	11,832,000	4,827,000 " 40.8¢ " "
1944	19,000	17,100,000	6,190,000 " 36.2¢ " "
1945	19,400	17,169,000	6,662,000 " 38.8¢ " "
1946	20,400	19,176,000	9,147,000 " 47.7¢ " "
1947	22,800	23,256,000	9,070,000 " 39.0¢ " "
1948	16,400	16,564,000	7,918,000 " 47.8¢ " "
1949	18,900	20,223,000	7,644,000 " 37.8¢ " "
1950	18,000	18,270,000	9,391,000 " 51.4¢ " "
1951 Est.	20,900	24,976,000	- -

Sun Cured (Filler and Binder 1936-51) Dark Leaf
(Types 45 and 56)

Year Summer	Acreage	Type	Production	Estimated Farm Value	Per Pound
1936	400	F & B	380,000	$ 51,000	13.4¢
1937	700	F & B	784,000	106,000	13.5¢
1938	900	F & B	1,116,000	151,000	13.5¢
1939	1,000	F & B	960,000	127,000	13.2¢
1940	1,000	B	1,300,000	174,000	13.4¢
1941	600	B	450,000	65,000	14.4¢
1942	600	B	630,000	110,000	17.5¢
1943	200	B	166,000	37,000	22.0¢
1944	100	B	70,000	19,000	27.0¢
1945	100	B	93,000	31,000	33.0¢
1946	100	B	105,000	58,000	55.0¢
1947	200	B	140,000	66,000	47.0¢
1948	100	B	70,000	42,000	60.0¢
1949	100	B	85,000	(Estimates Discontinued)	
1950	Less than 100 Acres. No importance, practically discontinued. No further reports				
1951	Report discontinued.				

NOTE: F & B Filler and Binder types. B: Binder (Type 56) started in 1936 and continued to date.

Shade Grown-Air Cured (Dark Leaf) Wrapper Type 62

Year	Acreage	Production	Estimated Farm Value
1932	2,000	1,970,000 Lbs.	$ 690,000 or 35¢ per Lb.
1933	1,100	990,000	317,000 " 32¢ " "
1934	1,600	1,424,000	854,000 " 60¢ " "
1935	2,100	1,890,000	1,228,000 " 65¢ " "
1936	2,000	2,050,000	1,414,000 " 69¢ " "
1937	2,100	1,890,000	1,304,000 " 69¢ " "
1938	2,400	2,712,000	1,952,000 " 72¢ " "
1939	2,500	2,150,000	1,570,000 " 73¢ " "
1940	3,200	3,280,000	2,276,000 " 75¢ " "
1941	3,300	3,069,000	2,240,000 " 73¢ " "
1942	2,800	2,968,000	3,08[illegible],000 " $1.04 " "
1943	2,600	2,912,000	4,0[illegible],000 " 1.38 " "
1944	2,600	2,925,000	4,212,000 " 1.44 " "
1945	2,400	2,820,000	5,2[illegible],000 " 1.85 " "
1946	3,000	2,970,000	6,53[illegible],000 " 2.20 " "
1947	3,300	3,416,000	9,052,000 " 2.65 " "
1948	3,600	4,212,000	10,31[illegible],000 " 2.45 " "
1949	4,000	4,920,000	9,[illegible],000 " 1.95 " "
1950	4,200	4,998,000	9,99[illegible],000 " 2.00 " "
1951	4,100	5,084,000	(Not Available)

NOTE: Flue Cured Type No. 14 is generally known as cigarette tobacco.
Shade Grown Type 62 is generally known as cigar wrapper tobacco.
Sun Cured Type 56 is generally known as cigar filler tobacco.
* Farm value based on production estimate and auction price average.
(Auction Volume and Value on next page).

FLORIDA AUCTION SALES
(Flue Cured Tobacco - Type 14)

Revised figures of the Tobacco Branch, P.M.A., U.S. Department of Agriculture

	Producer's Sales			Resales		
Season	Pounds	Value	Average(1)	Pounds	Value	Average
1940	7,903,700	$1,300,069	$16.45	689,962	$107,670	$15.60
1941	5,726,227	1,211,684	21.16	707,736*	143,309*	20.25*
1942	7,269,574	2,381,502	32.76	748,850	227,822	30.43
1943	8,110,475	3,308,024	40.79	1,135,708	470,026	41.39
1944	12,330,566	4,496,293	36.46	1,255,424	417,923	33.29
1945	12,148,104	4,742,528	39.04	1,219,300	452,203	37.09
1946	13,192,482	6,353,484	48.16	1,595,702	706,444	44.27
1947	16,596,141	6,510,858	39.23	2,020,091	740,141	36.64
1948	12,346,106	5,896,173	47.76	1,698,258	782,141	46.06
1949	16,262,984	6,129,689	37.69	1,707,535	579,258	33.92
1950	13,773,151	7,137,519	51.82	1,704,686	837,736	49.14
1951	20,807,570	10,837,572	52.10	2,190,056	1,089,863	49.80

* Estimated. (1) Average Price per 100 Lbs.

1949-51 Sales by Individual Markets

		Producers		Resales	
		Pounds	Value	Pounds	Value
Jasper	1949)	3,122,799	$1,131,006	369,408	$114,939
	1950)	2,612,372	1,378,365	388,442	204,666
	1951)	4,857,527	2,427,309	580,474	287,965
Lake City	1949)	4,483,162	1,714,472	367,016	117,590
	1950)	4,099,281	2,077,067	268,832	106,186
	1951)	5,384,295	2,800,906	392,920	177,361
Live Oak	1949)	8,657,023	3,284,211	971,111	346,729
	1950)	7,061,498	3,682,087	1,047,412	526,885
	1951)	10,565,748	5,609,357	1,216,662	624,537
Totals	1949	16,262,984	$6,129,689	1,707,535	$579,258
	1950	13,773,151	7,137,519	1,704,686	837,736
	1951	20,807,570	10,837,572	2,190,056	1,089,863

ALL FLORIDA TOBACCO

Season	Acres	Production Pounds	Farm Value	Price per lb.
1940	16,900	16,328,000	$ 4,526,000	$ .277
1941	15,200	11,711,000	4,050,000	.346
1942	16,400	14,778,000	6.808,000	.461
1943	16,400	14,910,000	8,883,000	.596
1944	21,700	20,095,000	10,421,000	.519
1945	21,900	20,082,000	10,923,000	.544
1946	23,500	22,251,000	15,739,000	.707
1947	26,300	26,812,000	18,188,000	.678
1948	20,100	20,846,000	18,279,000	.877
1949	22,900	25,143,000	17,238,000	.686
1950	22,200	23,268,000	19,387,000	.833
1951	25,000	30,060,000	(Not Complete)	-

Cigars, Cigarettes, Chewing Tobacco, Smoking Tobacco, and Snuff Manufactured in the United States, by Calendar Years, 1945-49

	Cigars		Cigarettes	
Year	Large Thousands	Small Thousands	Large Thousands	Small Thousands
1945	5,274,675	98,167	82,416	332,16
1946	5,617,700	92,262	1,658	350,03
1947	5,487,656	79,670	537	369,682,7
1948	5,645,104	89,134	641	386,82
1949	5.600,000	82.000	800	384,979,

	Chewing Tobacco				Smoking Tobacco	Snuff	Total Chewing, Smoking, and Snuff Tobacco
Year	Plug 1,000 Lb.	Twist 1,000 Lb.	Fine-Cut 1,000 Lb.	Scrap 1,000 Lb.	1,000 Lb.	1,000 Lb.	1,000 Lb.
1945	59,704	6,723	3,970	47,748	168,523	43,834	330,502
1946	51,810	5,773	3,756	46,117	106,414	39,361	253,231
1947	47,306	5,152	3,793	42,189	104,680	39,163	242,283
1948	45,346	5,632	3,207	42,088	107,599	40,809	244,681
1949	41,903	5.586	2,756	39,674	108.124	40,908	238,951

Compiled from annual and monthly reports of the Commissioner of Internal Revenue, except cigars and cigarettes, which are estimates by the Tobacco Branch, PMA. No later information available for 1950 and 1951.

FLORIDA F.O.B. SHIPPING POINT PRICES
SEASON 1950-51

The f.o.b. prices listed below are weekly ranges and represent the bulk of sales on packing house stock of fair to generally good merchantable quality and condition.

Lake Okeechobee Section F.O.B. Bean Prices
Sales to Local Buyers in Bushel Hampers.

Week Ending	Contenders	Plentifuls	Tendergreens	Valentines	Florida Belles
Nov. 27 to Mar. 2	Too few sales to establish a market account periodical frost and cold snaps killed or damaged most plentings and volume insufficient to warrant quoting a market.				
Mar. 9	$ -	$1.90-2.25	$ 2.75	$2.50-4.00	$ -
16	-	2.10-2.75	2.65-2.85	2.00-3.85	-
23	3.35-4.00	2.50-3.30	2.30-3.50	3.25-4.25	-
30	2.50-2.80	2.25-2.95	2.30-3.20	2.00-3.45	-
Apr. 6	2.25-2.40	2.60-3.40	2.30-3.00	2.50-3.15	2.40-3.00
13	-	2.25-3.25	2.00-2.75	2.50	2.85
20	2.50	3.25-3.80	2.30-3.20	3.70-4.50	2.70-3.30
27	2.20-3.20	2.25-2.80	1.90-3.00	2.25-3.85	2.00-2.55
May 4	-	1.95-2.90	1.80-2.40	3.25-3.80	2.00-2.70
11	-	2.25-2.65	2.00-2.70	3.75	2.50-2.85

Pompano Beach Section F.O.B. Prices
Sales to Local Buyers in Bushel Hampers.

Week Ending	Plentifuls	Valentines	Tendergreens	Wax	Limas
Dec. 8	$4.00-6.50	$5.50-7.00	$ 5.00-6.00	$3.00-5.50	$ -
15	4.25-7.50	5.75-7.75	4.00-6.70	3.00-5.75	6.00-7.00
22	4.75-6.50	4.75-7.00	4.50-6.00	3.00-6.00	4.00-6.50
29	2.75-4.00	3.50-5.00	2.75-4.25	2.50-3.75	4.00-5.50
Jan. 5	3.25-6.00	4.00-6.75	3.00-6.50	2.00-5.50	4.50-5.50
12	4.25-7.25	4.50-7.25	4.00-7.60	3.00-5.35	6.00-6.50
19	3.50-5.00	3.50-5.25	3.50-4.25	3.00-4.50	6.50-8.50
26	2.75-5.25	3.00-6.00	3.50-4.50	2.50-4.25	5.00-7.50
Feb. 2	3.00-5.75	3.00-6.50	3.25-4.25	3.50-5.00	5.00-6.00
9	1.75-3.50	1.75-3.50	1.75-3.50	1.75-4.00	3.00-5.00
16	2.00-4.50	3.00-4.25	1.75-3.50	2.50-4.25	3.00-4.25
23	1.85-2.75	2.00-3.75	2.25-3.50	2.50-3.50	3.50-4.00
Mar. 2	2.00-3.25	2.75-4.00	2.25-3.25	3.00-3.75	3.50-4.00
9	1.75-2.50	2.25-3.25	2.25-2.65	2.50-3.50	2.25-4.00
16	2.50-3.75	3.25-4.25	2.35-3.25	3.00-4.25	2.25-3.00
23	2.50-3.50	3.50-4.50	2.00-3.10	3.50-5.50	2.50-3.00
30	1.75-3.25	3.00-4.25	1.75-2.65	2.50-5.00	2.00-3.25
Apr. 6	2.25-3.00	2.00-3.25	1.75-2.50	4.25-5.50	2.00-3.00

- -

F.O.B. Sanford-Oviedo Section Celery Prices

Price ranges apply to both Golden Heart and Pascal types, generally good merchantable quality, 16 inch crates, trimmed tops, individually washed, with an extra charge of mostly 10¢ per crate for precooling. Prices also apply to Zellwood and Weirsdale sections during their seasons.

Week Ending	Pascal		Golden	
	3-4 doz.	6-10 doz.	3-4 doz.	6-10 doz.
Jan. 5	$4.50-4.75	$4.25	No quotes	$ -
12	3.50	3.50	$4.00-4.50	4.50-5.00
19	2.50-2.75	3.00-3.50	2.25	3.00
26	2.50-2.75	3.00-3.50	2.50-2.75	3.25-3.75
Feb. 2	3.25	Too few sales to quote		
9	3.25-3.50	4.00-4.25	3.00	3.75-4.00
16	2.50-3.25	3.50-3.75	2.25-2.50	3.00-3.25
23	1.75-2.25	2.75-3.25	2.00	2.50-2.75
Mar. 2	1.50-1.75	2.00-2.50	1.50-1.75	2.00-2.50
9	1.50-1.85	1.75-2.25	1.50	2.00-2.50
16	1.75-2.25	2.00-2.25	2.00-2.25	2.25-2.50
23	2.00-2.25	2.25-2.50	2.25	2.50-2.75
30	1.75-2.25	2.25-2.50	2.25	2.50-2.75
Apr. 6	1.50-1.75	2.00-2.50	2.00	2.50-2.75
13	1.75-2.25	2.00-2.50	2.25	2.75-3.25
20	2.00-2.50	2.25-2.75	2.50-2.75	3.25-3.75
27	1.75-2.00	2.25-2.50	2.00	2.75-3.00
May 4	1.50-1.75	2.00-2.50	1.50-1.75	2.25-2.50
11	1.50-1.75	2.00-2.25	2.00-2.25	No sales
18	1.75-2.25	2.25-2.75	3.50	4.00
25	1.75-2.00	2.25-2.75	1.75-2.00	3.25-3.50
June 1	1.50-1.75	2.25-2.50	1.35-1.50	2.50-3.00

SHIPPING POINT PRICES OF TOMATOES

The following prices are weekly ranges as reported on the daily Federal-State Market Vegetable Report and are on tomatoes in lug boxes, green, wrapped, 85% or more U.S. #1 quality, unless otherwise stated.

Dade County Section F.O.B. Shipping Point

Week Ending	60 Lb. Crates - Unwrapped 6x6s	6x7s	7x7s	Lugs 6x6s	6x7s	7x7s
Mar. 2	$10.50-11.00	$9.50-11.00	$5.50-6.50	$ 6.00	$5.00-6.00	$3.50-3.7
9	9.50-10.00	8.50-9.00	4.00-5.00	5.50	4.50	2.75-3.0
16	9.00-10.00	8.50-9.00	3.50-4.00	5.50-5.75	4.00-5.00	2.50-2.7
23	9.50-10.00	8.00-8.50	3.25-4.00	5.25-5.50	4.25-4.50	2.25-2.5
30	7.50	6.50	3.00-3.25	4.00-4.25	3.00-3.25	2.0
Apr. 6	7.50	6.50	3.00-3.25	4.00-4.25	3.00-3.25	2.0

Auction Sales Farmer's Market --- Florida City, Florida

60 lbs. field crates, field run, culls out, green stock

Week Ending	Price Range	Average Price*	Good Quality	Fair to Ordinary Quality
Jan. 26	$ 1.00-13.00	$ 10.02	$ 9.00-13.00	$ 4.00-9.50
Feb. 2	2.20-12.50	9.34	7.50-12.50	4.50-9.50
9	1.05-12.20	7.91	6.00-12.20	3.00-9.00
16	1.05-11.40	8.07	7.50-11.40	4.00-8.00
23	1.05-12.70	7.86	7.00-12.70	4.00-8.00
Mar. 2	1.05-9.40	6.77	6.50-9.40	3.50-6.50
9	1.05-9.80	6.71	6.00-9.80	3.00-6.50
16	1.05-10.20	5.73	5.50-10.20	3.00-7.50
23	1.05-9.00	4.26	5.00-9.00	3.00-7.00
30	1.05-7.60	4.40	5.00-7.60	3.00-5.50
Apr. 6	1.05-7.20	4.18	4.00-7.20	2.00-5.00
13	1.05-8.40	4.47	4.00-8.40	2.50-5.00
20	1.05-8.40	4.67	4.50-8.40	3.00-5.00
27	1.00-6.10	3.17	4.00-6.10	2.50-4.50
May 5	1.00-4.90	2.15	2.70-4.90	2.00-4.00

* Averages based on figures supplied by Market Manager's Office. Weekly totals of daily averages were divided by 5. (5 sales days).

Fort Pierce, Florida F.O.B. Shipping Point

Week Ending	60 Lb. Crates - Unwrapped 6x6s	6x7s	7x7s	Lugs 6x6s	6x7s	7x7s
May 4	$ 7.50	$ 6.50	$ 4.50	$4.00-4.50	$3.50-4.00	$2.50-3.00
11	9.00-10.00	8.00-9.00	5.00-6.00	5.00-6.00	4.50-5.00	3.00-3.75

Auction Sales Farmer's Market --- Fort Pierce, Florida

59 lb. Minimum field crates, field run, culls out, green stock inc. fair quality.

Week Ending	Medium to Large Size	Pinks	No. 2 Grade
April 20	$5.50-8.00	$1.00-6.75	$ 1.00-2.70
27	3.50-7.00	1.00-3.75	1.00-2.80
May 4	3.50-4.50	1.00-4.00	.50-2.30
11	3.00-7.00	1.25-5.75	.80-4.80

WEEKLY F.O.B. PRICES OF CABBAGE IN THE LAKE OKEECHOBEE SECTION

Sales f.o.b. Shipping Point: Dom.Round

Week Ending	50 lb. Sacks	1-3/4 Bu. Crates
Jan. 27	$ 2.75-3.00	$ 3.00-3.25
Feb. 3	3.00-3.75	3.25-4.00
10	4.25-5.75	4.50-6.65
17	4.50-5.50	5.00-6.00
24	4.00-5.00	4.25-5.25
Mar. 3	3.50-4.00	4.00-4.25
10	2.25-3.50	2.50-3.75
17	1.50-2.00	1.75-2.25
24	1.40-1.90	1.50-2.15
31	.85-1.50	1.00-1.75
Apr. 7	.90-1.00	1.10-1.15
14	.90-1.25	1.10-1.35
21	1.00	1.10-1.15
28	.90-1.00	1.00-1.10
May 5	Too few sales to establish market.	
12	" " " "	" "

WEEKLY F.O.B. PRICES OF CORN IN THE LAKE OKEECHOBEE SECTION.

U.S. Fancy and U.S. #1 Grade only

Sales F.O.B. Shipping Point.

Ending	4-5 dozen crates - Yellow
Mar. 24	$ 3.50-4.00
31	2.75-3.50
Apr. 7	2.25-3.50
14	2.50-3.25
21	1.75-2.75
28	1.75-3.00
May 5	2.00-3.25
12	2.50-3.00

SHIPPING POINT PRICES OF PEPPERS AT POMPANO BEACH

The prices quoted below are weekly ranges of prices to growers on stock of good merchantable quality, in bushel baskets.

Week Ending	California Wonders		Other Bullnose Type	
	Med. to Large	Small to Med.	Med to Lge	Small to Med
Dec. 8	$ 5.50	$ 5.00	$3.75-5.25	$ 2.00-4.00
15	6.85-9.00	7.25	6.50-7.50	6.50
22	9.25-12.00	6.00-8.50	7.00-9.75	3.25-6.50
29	9.00-11.50	6.00-8.50	8.00-9.50	5.00-8.50
Jan. 5	11.00-15.00	7.00-10.50	9.00-11.25	5.00-7.50
12	11.00-15.00	8.00-13.00	9.00-13.00	6.00-8.00
19	10.50-14.50	8.00-11.50	9.50-11.50	5.00-9.00
26	6.50-13.00	3.50-8.00	5.00-11.00	2.00-6.00
Feb. 2	6.50-9.50	3.00-7.00	5.00-7.25	2.50-6.50
9	8.00-11.60	7.00-9.50	6.50-9.25	3.00-8.50
16	7.50-12.50	5.85-9.50	6.50-8.25	5.00-7.30
23	4.00-6.50	2.00-5.75	2.75-5.25	1.50-4.50
Mar. 2	3.00-5.50	2.50-4.75	1.85-3.25	1.50-2.75
9	1.75-3.75	1.00-2.75	1.35-2.25	.75-1.75
16	2.75-4.00	1.00-2.50	1.75-2.10	.75-1.50
23	2.25-3.75	1.00-2.25	1.50-2.00	.75-1.00
30	1.50-2.75	.60-1.50	1.00-1.75	.50- .85
Apr. 6	1.00-1.75	.50-1.50	.70-1.00	.40- .50
13	1.50-2.25	1.00-1.50	.85-1.10	.50- .90
20	1.75-2.75	1.25-1.75	.80-1.25	.50- .75
27	1.50-3.00	1.00-2.00	.85-1.35	-
May 4	1.50-2.00	1.00-1.50	.75-1.25	-
11	2.00-3.50	1.50-2.50	1.00-2.00	.90-1.15

F.O.B. BELLE GLADE CELERY PRICES (Lake Okeechobee Section)

Price ranges are on Golden Heart variety, 16 inch crates, trimmed tops, individually washed and precooled, of generally good merchantable quality and condition.

Week End.	Golden Heart	
	3-4 doz.	6-10 doz.
Jan. 5	$5.00-5.50	5.50-6.00
12	4.00	4.50
19	2.50	3.25
26	2.50	3.00-3.25
Feb. 2	3.00	3.50-3.75
9	3.00	3.75-4.00
16	2.25-2.50	2.50-3.00
23	2.00	2.50-2.75
Mar. 2	1.50	1.75-2.25
9	1.50	1.75-2.00
16	2.00	2.25-2.75
23	2.00-2.25	2.50-2.75
30	2.25	2.50-2.75
Apr. 6	2.00	2.50-2.75
13	2.00-2.25	2.75-3.00
20	2.50-3.00	3.25-3.75
27	1.50-1.75	2.00-2.25
May 4	1.50	1.75
11	2.00	2.25-2.50

SHIPPING POINT PRICES OF STRAWBERRIES

Plant City Farmers Market - Auction Prices
(Price to Farmers without crates)

Week Ending	1951 Range	1951 Average	1950 Average	1949 Average
Dec. 30	.32 -.56	.35 -.52-5/8	.27-5/8-.39-3/4	.18-3/4-.22
Jan. 6	.28 -.42	.31-5/8-.37½	.27-3/4-.32	.24 -.31-7/8
13	.25 -.49	.28-5/8-.43-3/4	.26-1/4-.29-1/4	.28-1/8-.35-5/8
20	.25 -.35	.29-1/8-.32-1/4	.21-3/4-.24-3/4	.28-3/4-.32-1/4
27	.28 -.34½	.31-1/4-.32-7/8	.19-3/8-.24-1/4	.29 -.33-1/8
Feb. 3	.20 -.35½	.26-7/8-.33-5/8	.14-3/4-.18	.29-3/4-.34-1/8
10	.25 -.38½	.29-3/4-.33-1/2	.15-7/8-.21-7/8	.27-1/2-.33-7/8
17	.20 -.38½	.24 -.35-3/8	.17-1/2-.23-1/2	.20 -.28-5/8
24	.18 -.26	.21-3/4-.23-3/8	.20-3/8-.27-7/8	.21 -.24-1/4
Mar. 3	.14½-.24-3/4	.19 -.22-3/4	.20-1/4-.28-1/4	.22-3/4-.30-1/4
10	.10 -.24½	.15-3/8-.20-5/8	.21-7/8-.27-1/2	.28-5/8-.34
17	.10 -.35	.14-1/8-.29-3/4	.19-3/8-.30	.26-1/8-.32-1/8
24	.10 -.35½	.15-1/8-.29-5/8	.22-1/4-30-1/4	.21-5/8-.27-3/8
31	.12½-.28½	.17 -.23	.15 -.22	.16-1/8-.24
Apr. 7	.15 -.28½	.16-7/8-.23-3/4	-	.16 -.25

Crates and loading charges 2¢ extra.

F.O.B. SARASOTA SECTION CELERY PRICES

Price ranges apply to Pascal type celery, 16 inch crates, trimmed tops, individually washed, with a charge of mostly 10¢ extra per crate for precooling, of generally good merchantable quality and condition.

Week Ending	3-4 dozen	6-10 dozen
Jan. 26	$ 2.50-2.75	$ 3.00-3.50
Feb. 2	Too few to quote	
9	3.25-3.50	4.00-4.50
16	3.00-3.25	3.75-4.25
23	2.00-2.50	3.25-3.50
Mar. 2	1.50-1.75	2.25-2.50
9	1.50	2.00-2.50
16	1.75-2.00	2.00-2.50
23	2.00-2.25	2.25-2.50
30	Too few to quote	
Apr. 6	1.65-2.00	2.25-2.75
13	1.75-2.00	2.50-2.75
20	2.00-2.50	2.50-2.75

SHIPPING POINT PRICES OF SOUTH FLORIDA POTATOES

The prices tabulated below are weekly ranges as taken from the daily f.o.b. reports. They are on Red Bliss Triumphs in 50 lb. sacks.

Sales F.O.B. Shipping Point -- U. S. No. 1 Quality

Week Ending		Lake Okeechobee Section Size A	Lake Okeechobee Section Size B	Ft. Myers Section Size A	Ft. Myers Section Size B	Dade County Section Size A	Dade County Section Size B
Jan.	6	$2.75-3.00	$1.60-2.00	$ -	$ -	$ -	$ -
	13	2.50-2.75	1.60-2.00	-	-	-	-
	20	-	-	2.50	2.25	-	-
	27	-	-	2.25-2.50	2.00-2.25	-	-
Feb.	3	-	-	2.00-2.25	1.75-2.15	-	-
	10	-	-	2.00-2.25	2.00	-	-
	17	-	-	1.85-2.00	1.75-2.00	2.00-2.10	1.90-2.00
	24	-	-	1.65-2.00	1.65-2.00	1.85-2.10	1.90-2.00
Mar.	3	-	-	1.65-1.85	1.65-1.55	1.75-2.00	1.75-1.95
	10	-	-	-	-	1.75-2.00	1.75-1.90
	17	-	-	-	-	1.75-2.00	1.75-1.90
	24	-	-	-	-	2.00-2.50	2.00-2.50
	31	-	-	-	-	2.45-2.75	2.50-2.65
Apr.	7	Volume insufficient to		-	-	2.50-2.75	2.50-2.75
	14	establish market for		-	-	2.50-3.00	2.50-2.85
	21	early spring potatoes.		-	-	2.75-2.85	2.75
	29	" " "		-	-	-	-
May	5	" " "		-	-	-	-

F.O.B. PRICES HASTINGS, FLORIDA SECTION POTATOES, WASHED STOCK. SEBAGOS (WHITE)

Week		100 Pound Sacks U.S.#1 Size A	100 Pound Sacks U.S.#1 Size B	50 Pound Sacks U.S.#1 Size A	50 Pound Sacks U.S.#1 Size B
Apr.	17	$ 4.50	$ 3.50	$2.25-2.40	$
	18	4.00	2.50-3.00	2.00-2.15	
	19	4.00	2.50-3.00	2.00-2.15	1.50-1.65
	20	4.00	3.00	2.00-2.15	
	23	4.00	3.00	2.00-2.15	
	24	3.50	2.00-2.25	1.75-1.90	1.25-1.40
	25	3.50	2.00-2.25	1.75-1.90	1.25-1.40
	26	3.00-3.50	2.50	1.65-1.90	
	27	3.00	1.75-2.25	1.50-1.65	
	30	2.75-3.00	2.00-2.25	1.50-1.65	
May	1	2.75	1.75	1.37½-1.50	
	2	2.75	1.75	1.37½-1.50	
	3	2.75	1.75	1.37½-1.50	
	4	2.75	1.75	1.37½-1.50	
	7	2.75	1.75	1.37½-1.50	
	8	2.75	1.50-1.75	1.37½-1.50	
	9	2.75	1.75	1.37½-1.50	
	10	2.75	1.75	1.37½-1.50	
	11	2.75	1.50-1.75	1.37½-1.50	
	14	3.00	1.75	1.50-1.65	
	15	3.00	1.75	1.50-1.65	
	16	3.00	1.75	1.50-1.65	
	17	3.00	1.75	1.50-1.65	
	18	3.00	1.75	1.50-1.65	
	21	3.25	2.00	1.62½-1.77½	
	22	3.25	2.00	1.62½-1.77½	
	23	3.25	2.00	1.62½-1.77½	
	24	3.25	2.00	1.62½-1.77½	
	25	3.25	2.00	1.62½-1.77½	
	28	3.00		1.50-1.65	
	29	3.00		1.50-1.65	

WEEKLY F.O.B. PRICES OF ESCAROLE IN THE LAKE OKEECHOBEE SECTION

All quotations are in bushel hampers and are fair to good quality.

Week Ending		
Dec.	2	Too few sales
	9	to establish
	16	a market
	23	"
	30	"
Jan.	6	$ 2.50-2.75
	13	2.00-2.75
	20	1.35-2.25
	27	1.50-2.00
Feb.	3	1.25-1.75
	10	1.40-2.00
	17	.65-1.00
	24	.80- .90
Mar.	3	.70- .85
	10	.60- .85
	17	.65-1.00
	24	.85-1.00
	31	.65- .90
Apr.	7	.65-1.10
	14	.80-1.00
	21	.85- .90
	28	.85-1.10
May	5	.90-1.00

Source: All of the fob prices on these four pages were based on the season summaries of the Federal State Market News Service. We believe the public will be interested in this type of information.

It should be understood that market news offices are not always open the entire season and that some relatively important shipping points do not have a special field market news station. Florida prices in the various sections are competitive and these fob prices give a good picture of the State-wide prices.

Similar information is not available in Annual Reports for previous years, but we will try to make this a continuing feature in future reports.

Neill Rhodes, Commissioner.

FORESTS OF FLORIDA - PAST AND PRESENT

Extracts from article by- F. W. Risher
Marketing Specialist, Florida State Marketing Bureau

It was the forests that furnished pioneers the material with which to build their homes, from hewn logs many years before the sawmill was invented. They provided fruits, berries, nuts, game and furs.

According to the Florida State Chamber of Commerce, Florida landowners in 1948 received from stumpage and wood products like turpentine and rosin the sum of $14,000,000. To change these forest products into finished products there was paid that year to workers the sum of $69,821,000 in wages and salaries, while the finished products brought a total of $200,216,000. Finished products were such items as paper from pulpwood, turpentine and rosin from the gum or sap of the pine tree, boxes from veneer and regular milled wood, barrels from cooperage wood or sometimes called stave wood or barrel staves. Even the old fat wood stump is now sold and furnishes certain wood preservatives, as well as charcoal when put through a distilling process. Much of the charcoal is used in making explosives, and in some instances to furnish heat for cooking.

Some Principal Items

More timber is harvested each year by the sawmills of Florida to use in manufacturing into lumber than for any other wood product. During 1948 the sawmills of Florida cut enough logs to manufacture 546,900,000 board feet of lumber, yet it should be remembered nearly all of the original or virgin timber had already been cut. The turpentine distillers of Florida made and marketed 15,206,900 gallons of turpentine. Next to the trees that were cut for lumber, the pulpwood mills used the most, for there were cut from the forests 1,221,200 cords of wood, and this is a lot of wood in anybody's language. A cord of wood is 128 cubic feet or a stack 4 feet wide, 4 feet high and 8 feet long. Timber owners were paid $3,358,000 for this pulpwood. It is well to stop and think for a minute on the wonders of "chemistry," for had not a chemist in Savannah, Ga., by the name of Doctor Herty, worked out a process of making pulp from pine trees we would not today have a market for pulpwood. Then remember it has been not more than 30 years since this process was discovered. Chemistry has been responsible for a great new industry in Florida that in 1948 paid $23,878,000 in wages, outranking the lumber industry which paid $17,610,000 in wages. The finished product of the Florida paper mills brought in more money than was obtained from the sale of lumber from the sawmills. To be exact, the finished products from paper mills brought $102,215,000 while Florida lumber was sold for $41,018,000. The third ranking forest product in value was that received by the operators in the turpentine branch; wages paid amounted to $11,869,000 and the Naval Stores products brought Florida operators at wholesale $23,738,000.

Florida Timber Land

The commercial forests of Florida were classified as follows in 1948 by the Forest Service of the United States.

Saw timber	7,094,000	acres
Pole timber	3,313,000	"
Seedling and sapling	2,019,000	"
Understocked	9,339,000	"
Total	21,765,000	"

Classified as to ownership -

Federal Government	1,713,000	acres
State, City and County	326,000	"
Privately owned	19,726,000	"
Total	21,765,000	"

Analyzing the first set of figures above one notes that almost half of the 21,000,000 acres of Florida forests are under-seeded or another way of saying more than 9,000,000 acres of potential forest land need seeding and protecting to get trees growing again. Florida folks and folks of the U.S.A. in general have been destroyers of natural resources in the extravagant destroying of forests. This is most unnecessary in case of forests for they can be made to produce again while a mine cannot be made to produce again once the original mineral has been dug.

In the second set of figures it is noted that more than 19,000,000 acres of Florida forest potential land is owned by private individuals or companies. This means when forests are rejuvenated it must be done by the private citizens, though governmental agencies have acquired over 2,000,000 acres of forest developing.

Forest Fire Control Facts

There are 1,334,000 acres of land in Florida under fire protection by the Federal Government and 12,673,789 acres of privately owned lands under protection with cooperation of the Forest Service of Florida. There are 7,266,082 acres of State and privately owned timber land unprotected, or almost a third of the land of Florida growing very little trees for the future welfare of the State.

People are beginning to take more interest in reforestation. The State, through forest nurseries, are providing millions of seedlings at a very low cost for replanting The paper mills are helping farmers too around their mills, by furnishing seedling trees for planting. The Extension Service of the University of Florida helps farmers do reforesting work and they have active 4-H Forestry Clubs. The Future Farmers have projects in forestry and are aided by such agencies as railroads and bankers and business men. Progress is being made and the effects are becoming visible.

QUESTIONS AND ANSWERS ON FLORIDA'S FARM FORESTRY PROGRAM

WHAT IS THE FARM FORESTRY PROGRAM? Florida's farm forestry program, begun in 1941, offers free management assistance to woodland owners. The purpose of the program is to assist and show woodland owners how to manage their timber so they may ultimately produce the most value of forest products per acre continuously. Although the program is designed principally to assist the farmer and small woodland owner, practical suggestions are available to any woodland owner interested in managing his timber for continuous crops.

This service is supervised by the Florida Forest Service in cooperation with the U.S. Forest Service and various county governments.

WILL THE FARM FORESTER HELP THE LANDOWNER DETERMINE VOLUME OF A STAND OF TIMBER? The farm forester will inspect the timber and recommend the type and time of harvest which should be made to give the best return - both now and from future cuttings. The he will help select; mark and measure the timber to be cut and compute the volume for the landowner.

IS THE ADVICE AND ASSISTANCE OF THE FARM FORESTER FREE AND WHAT IS EXPECTED OF THE LANDOWNER IN RETURN FOR IT? The service is free, however the landowner is required to assist the forester himself or furnish the assistance of one man and necessary paint used for marking.

WILL THE FARM FORESTER HELP LOCATE A BUYER FOR THE TIMBER? He will give the landowner the names of possible buyers and will also let buyers know that the timber is on sale.

DOES THE FARM FORESTER TELL THE TIMBER GROWER WHAT PRICE HE SHOULD RECEIVE FOR THE TIMBER? He can only indicate the price range for the timber. Prices depend upon the size and quality of timber, logging conditions, distance from markets, and possible market outlets in a given area. The landowner should request bids from buyers or bargainwith them individually.

HOW LONG CAN THE FARM FORESTER WORK WITH ANY ONE LANDOWNER? The forester is limited to 3 days of active work in the woods with any landowner during the year. For acreage involving work beyond these limitations, the landowner will be referred to consulting foresters.

WHEN THE LANDOWNER DESIRES EITHER TO BUY OR SELL A TRACT OF TIMBER OR LAND INCLUDING STANDING TIMBER, WILL THE FARM FORESTER MAKE AN OVER-ALL TIMBER APPRAISAL AS A BASIS FOR DETERMINING THE VALUE? No,this is a case for a general land appraiser or consulting forester.

WILL THE FARM FORESTER TELL ME WHAT AND WHERE TO PLANT? The forester will tell the landowner where planting is needed. He will also show the landowner how to plant and how to obtain seedlings. He will tell how to encourage natural reseeding where it is possible.

IS IT PRACTICAL FOR THE LANDOWNER TO GUM FARM HIS TREES? Depending upon the number of trees and the equipment needed by the landowner, the farm forester may recommend gum farming and assist in getting the project started.

DOES THE FARM FORESTER GIVE ADVICE ABOUT PROTECTING THE WOODS FROM FIRE AND OTHER DESTRUCTIVE AGENTS? Planning protection from forest fires and supplying information on the control of insects and disease are all part of the farm forester's service to the landowner.

SHOULD THE LANDOWNER CALL THE FARM FORESTER IF HIS WOODS DO NOT NEED CUTTING? By all means call the forester. He may be able to recommend practices that would mean more money to the woodland owner when his trees are right for the harvest. The farm forester is trained to examine the growing condition and health of a forest and to recognize immediately an ailment and recommend the cure.

WHOM SHOULD THE LANDOWNER SEE TO GET THE ASSISTANCE OF A FARM FORESTER? The list below gives the names and counties served by the ten farm foresters in Florida. They may be contacted personally or through the county agent.

Names and Addresses	Counties Served
Walter Rice, P.O. Box 1644, Co. Agent's Office, Pensacola, Fla.	Escambia
Hugh Mobley, P.O. Box 223, Co. Agent's Office, Mayo, Fla.	Lafayette
W. F. Cowan, P.O. Box 256, Stovall Bldg., 307 Morgan Street, Tampa, Fla.,	Hillsborough, Pinellas
Harry Allen, P.O. Box 187, Co. Agent's Office, Courthouse, Chipley, Fla.	Holmes, Washington, & West Jackson
James Snowden, Rt. 2, Box 144-G, (Perry Highway) Tallahassee, Florida	Gadsden, Jefferson, Leon, and Wakulla
Wyman Garland, P.O. Box 428, Courthouse Annex, Live Oak, Florida	Madison, Suwannee & Hamilton
George L. Reinert, Jr., P.O. Box 728, Florida Forest Service, Lake City, Fla.	Columbia, Union & Baker
Anthony S. Jensen, P.O. Box 926, Room 447, P.O. Bldg., Jacksonville, Fla.	Nassau, Duval, Clay & St. Johns
Ed Greeb, P.O. Box 521, Florida Forest Service, Ocala, Fla.	Levy, Marion, Sumter & Lake
William Boyd, P.O. Box 48, Co. Agent's Office, Courthouse, Blountstown, Fla.	Calhoun, Gulf, & East Jackson

Courtesy, Mr. C. H. Coulter, State Forester, Florida Forest Service, Tallahassee, Fla.

FLORIDA LIVESTOCK MARKET

(Substantially Southeastern Price Ranges Per Cwt)

	COWS		CALVES		STEERS		HOGS		
	Medium	Common	Good	Medium	Good	Medium	No. 1	No. 2	
	100 Lbs.		100 Lbs.		100 Lbs.		100 Lbs.		
1930									1930
3-4	5.00-6.00	4.00-5.50	7.00-8.25	5.50-7.00	7.00-8.50	6.00-7.00	8.50	7.50	
9-5	3.75-4.50	3.25-3.75	5.00-6.50	4.00-5.00	5.00-6.00	4.00-5.00	9.25-9.50	8.25-8.50	
1931									1931
3-3	3.50-4.25	2.50-3.50	5.50-6.50	4.75-5.50	5.50-6.75	4.50-5.50	6.00	5.50	
9-4	2.50-3.25	2.00-2.75	4.00-5.00	3.00-4.00	4.00-4.75	3.00-4.25	5.25	4.75	
1932									1932
3-4	2.50-3.00	1.75-2.50	3.50-4.75	3.00-4.00	3.50-4.25	3.00-3.75	3.50	3.20	
9-6	2.25-2.75	1.25-2.00	3.75-4.25	3.00-3.50	4.00-5.25	3.50-4.25	3.75	3.50	
1933									1933
3-7	2.00-2.50	1.50-2.00	3.25-3.75	3.00-3.25	3.50-4.25	3.00-3.50	2.65	2.40	
9-5	2.00-2.75	1.00-2.00	3.25-3.75	2.50-3.25	3.75-4.25	3.00-3.75	3.75-4.00	3.50-3.75	
1934									1934
3-6	2.25-2.75	1.50-2.25	4.00-4.75	3.00-4.00	4.00-4.50	3.50-4.00	3.75-4.00	3.50-3.75	
9-4	2.00-2.50	1.00-2.00	3.50-4.25	2.50-3.75	4.00-4.25	3.25-4.00	5.40-5.60	4.90-5.90	
1935									1935
3-5	3.50-4.00	1.75-3.25	5.50-6.50	3.75-5.25	6.25-7.25	5.00-6.25	7.00-7.25	6.25-6.50	
6-7	3.25-4.50	2.00-3.50	5.25-6.25	4.50-5.50	6.00-7.50	4.75-6.00	7.25-7.50	6.50-6.75	
9-6	2.75-4.25	2.00-2.75	5.50-6.50	4.50-5.50	5.50-6.25	4.00-5.25	9.25-9.75	8.75-9.25	
12-6	3.25-4.50	2.50-3.25	5.00-5.75	4.00-5.25	5.75-6.75	4.75-6.00	7.75-8.00	7.25-7.50	
1936									1936
3-6	4.00-5.00	3.25-4.00	5.75-6.50	4.50-5.75	6.00-7.00	5.00-6.00	7.50-7.75	7.00-7.25	
6-5	4.25-5.00	3.50-4.25	5.25-6.00	4.50-5.25	6.25-7.00	5.75-6.50	8.00-8.50	7.50-8.00	
9-4	3.75-4.50	3.00-3.75	5.00-6.00	4.25-5.00	5.50-6.00	4.50-5.50	9.00-9.50	8.50-9.00	
12-4	3.50-4.00	2.75-3.50	5.00-6.00	4.25-5.25	5.25-6.00	4.50-5.25	8.60-8.90	8.10-8.40	
1937									1937
3-12	4.00-4.50	3.25-4.00	5.25-5.75	4.00-5.25	6.00-7.25	5.00-6.50	8.00-8.40	7.60-7.90	
6-4	4.50-5.00	3.50-4.25	5.75-6.50	4.75-5.50	7.00-8.00	5.50-6.75	9.50-10	9.00-9.50	
9-7	4.00-5.25	3.00-4.00	5.50-6.00	4.50-5.25	6.00-7.25	5.00-6.25	8.75-9.00	8.25-8.50	
12-7	4.00-4.50	3.00-4.00	5.00-5.50	4.00-5.25	6.00-7.00	5.00-6.00	6.25-6.65	6.00-6.40	
1938									1938
3-4	4.25-5.00	3.25-4.25	5.25-6.50	4.50-5.50	6.25-7.00	5.50-6.50	6.75-7.75	6.25-7.25	
6-7	4.50-5.25	3.50-4.25	5.50-7.00	4.50-5.50	6.50-7.50	5.50-6.50	7.70	7.20	
9-6	4.00-5.00	3.00-4.00	5.00-6.00	4.50-5.25	6.25-7.00	5.50-6.50	7.00	6.50	
12-3	4.00-4.50	3.00-4.00	5.50-6.75	4.50-5.50	6.50-7.50	5.50-6.50	6.00	5.50	
1939									1939
3-4	4.75-5.50	3.75-4.75	6.50-7.50	5.00-6.50	7.00-8.00	6.00-7.00	6.85	6.30	
6-3	5.00-5.75	4.00-5.00	6.00-7.50	5.00-6.00	6.50-8.00	5.50-6.50	6.00	5.50	
9-2	4.50-5.25	4.00-4.75	5.75-7.25	4.75-5.75	6.50-7.50	5.50-6.50	5.90	5.40	
12-2	4.50-5.25	3.75-4.50	6.00-7.25	5.00-6.00	7.00-7.75	6.00-7.00	4.90	4.65	
1940									1940
3-2	5.00-5.75	4.00-5.00	6.25-7.25	5.25-6.25	7.00-8.00	6.00-7.00	5.00	4.75	
6-1	4.75-5.25	3.75-4.75	6.50-7.50	5.50-6.50	7.00-8.25	6.00-7.00	5.25	5.00	
9-7	4.25-5.00	3.75-4.50	6.00-7.00	5.00-6.00	6.75-7.75	5.50-6.75	6.75	6.50	
12-7	4.25-5.00	4.00-4.50	6.00-7.00	5.00-6.00	7.00-8.25	6.00-7.00	5.65	5.40	
1941									1941
3-1	5.25-6.00	4.50-5.25	6.25-7.50	5.25-6.50	7.50-8.75	6.50-7.50	6.50	6.00	
6-7	5.25-6.25	4.25-5.25	6.75-7.75	5.50-6.50	7.75-8.50	6.75-7.75	8.90	8.40	
9-6	5.50-6.75	4.50-5.50	7.50-8.75	6.50-7.50	8.00-9.00	7.00-8.00	10.25	9.75	
12-5	5.50-6.50	4.25-5.50	7.00-8.00	6.00-7.00	7.50-8.50	6.50-7.50	8.25	7.75	
1942									1942
3-6	7.50-8.25	5.75-7.25	8.20-10	6.75-8.00	9-10.50	8.00-9.00	11.25	10.75	
6-6	7.00-8.50	6.00-7.00	9.00-11	7.00-9.00	10-11.50	8.75-10	12-13	11½-12½	
9-4	7.50-8.50	6.25-7.50	10-11	8.00-10	9.75-11¼	8.00-10	12.75-13¼	12¼-12.75	
12-4	7.50-8.50	6.00-7.25	10-11.25	8.00-10	9.25-11	8.00-9.25	11.50-12	11-11.50	
1943									1943
3-5	9.00-11	7.50-8.75	11-13.00	9-11.00	11-13.50	9-11.00	13.75-14¼	13¼-13.75	
6-4	9-10.50	7.00-8.75	11-13.25	9.50-11	11-13.50	9½-11.25	13¼-13.75	12.75-13¼	
Sept	9-10.50	8.00-9.00	12-13.50	12-13.00	13.00	12-13.00	13.50-14¼	12.75-13½	
Dec	8.50-10	7.25-8.50	12-12.50	11-11.50	12-15.30	9.50-12	11.25-12½	10½-11.75	
1944									1944
Mrch	9.75-11	9-10.00	12-14.00	11-12.00	13.25-15	11½-13½	12-13.25	11¼-12½	
June	9.25-10½	8.00-9.00	13-14.00	11-12.00	13.50-15	10-13.50	12-13.00	11¼-12¼	
Sept	8.25-10	6.75-8.30	12-14.00	9.50-11½	12½-14½	9.50-12¼	13-14.25	12-14.00	
Dec	8.60-10	7.25-8.50	12.50-14	9.75-12	12.50-14½	9.75-13	12-13.25	11¼-13½	
1945									1945
1-4	9.25-11½	8-10.00	12.75-15½	10½-14	13½-15½	11-14.00	12-14.35	11½-14.35	
5-8	9.50-11½	9-10.00	13-15.00	9.50-13½	14-16.00	11.25-14½	14¼-14.35	14¼-14.35	
9-12	9.50-11½	8-9.50	12-15.00	9½-13.50	13-15½	11-13½	13.75-14.35	13.75-14.35	

FLORIDA LIVESTOCK MARKET

(Substantially Southeastern Price Ranges Per Cwt)

	COWS		CALVES		STEERS		HOGS
	Medium 100 Lbs.	Common 100 Lbs.	Good 100 Lbs.	Medium 100 Lbs.	Good 100 Lbs.	Medium 100 Lbs.	180-240 lbs.
1946							
1-4	10.00-14.00	8.50-11.50	13.50-16.50	11.00-16.00	14.50-17	12-16.00	14.00-14.35
5-8	11.50-15.00	9.10-14.50	14.00-18.00	11.00-16.50	14.50-19	12-17.00	14.35-22.00
9-12	10.20-15.60	8.40-14.40	13.00-18.00	11.00-17.00	14.00-19	11-18.00	14.00-26.00
1947							1947
1-4	12.50-16.50	10.00-14.00	15.50-23.75	13.00-19.50	15.75-24.85	13-21½	17.50-26.25
5-8	14.00-17.00	10.00-14.00	18.00-23.00	14.00-19.00	18.50-23½	15-20.00	19.00-25.50
9-12	14.00-20.00	11.00-16.00	17.00-25.00	14.00-20.00	18-26.00	14-22.00	22.00-2[illegible].75
1948							1948
1-4	18.00-24.00	15.00-20.50	23.50-30.00	18.50-25.50	23½-28½	18-25.50	17.00-25.50
5-8	19.50-25.00	18.00-21.50	25.00-34.00	21.50-28.00	25½-33.00	21½-29	19.00-27.25
9-12	18.00-23.00	16.00-20.50	23.00-29.00	19.00-26.00	23½-29.00	19½-26½	20.25-27.50
1949							1949
Jan	18.50-22.00	17.00-20.50	24.00-29.00	20.00-25.50	24-28.50	20-25.00	18.50-19.50
Feb	18.00-20.50	16.50-19.50	23.50-28.50	20.00-26.00	21-26.00	19½-24½	17.75-19.00
Mar	18.50-21.00	17.00-20.00	24.00-28.50	22.00-26.50	22-26.00	20-24.50	18.25-19.75
Apr	19.00-21.50	17.50-20.50	24.50-28.00	22.00-25.50	23-27.00	21½-25	17.00-18.00
May	19.00-21.00	17.50-20.00	23.50-27.00	21.00-25.00	23-27.00	21½-24	17.00-20.50
June	19.00-21.00	17.00-20.00	23.50-27.50	21.50-25.50	23-27.00	21½-24½	20.00-21.00
July	18.00-19.50	16.00-18.50	22.00-25.00	19.50-24.00	23-25.00	20-23.50	21.00-22.00
Aug	16.00-18.00	14.00-16.50	20.50-23.50	18.50-22.00	22-24.50	18½-22	18.75-21.75
Sept	16.50-18.50	14.00-17.50	20.00-24.00	18.00-23.00	22½-25.00	18½-22½	18.00-20.00
Oct	16.00-18.00	14.00-17.00	19.00-23.00	17.50-21.50	22-24.50	18-22.50	15.00-17.50
Nov	16.00-17.50	14.00-16.50	19.50-23.50	18.00-21.50	22-24.50	18-22.50	14.50-17.00
Dec	17.00-19.00	15.50-18.00	22.00-26.00	19.00-25.00	22½-25.00	19½-23	15.00-15.75
1950							1950
Jan	18.00-20.00	16.50-19.00	24.00-28.00	20.50-27.00	23-26.00	20-24.50	15.00-15.25
Feb	18.50-21.00	16.50-20.00	25.00-30.00	21.00-28.00	23.50-27.00	20½-25	15.50-16.50
Mar	19.00-22.00	17.50-21.00	25.00-33.00	22.00-30.00	24½-27½	22-26.00	14.50-16.00
Apr	19.50-22.00	18.00-21.00	25.00-30.00	22.50-28.00	24½-27.00	22½-25½	14.75-16.00
May	21.00-23.00	18.50-22.00	25.50-34.00	23.00-33.00	25-28.00	23-26.50	16.25-19.50
June	21.00-24.00	19.50-22.50	26.50-34.00	23.50-33.00	26½-29.00	23½-27½	18.75-20.25
July	20.50-24.50	21.00-23.50	27.00-31.00	23.50-28.50	27-29.50	23½-28	20.50-23.75
Aug	21.00-24.50	20.00-23.00	27.00-31.00	23.00-28.00	27-29.50	23-28.00	21.25-23.25
Sept	21.50-25.00	20.50-23.50	27.00-33.00	23.50-31.00	26½-29½	23-27.50	18.00-21.00
Oct	21.50-24.50	19.50-23.00	25.00-30.00	22.00-28.00	25.00-28	22-27.00	18.00-20.00
Nov	21.00-24.00	20.00-23.00	26.00-32.00	23.50-30.00	26.00-28	23-27.00	17.00-18.50
Dec	20.50-24.00	20.00-23.50	26.50-33.50	23.50-31.00	26.00-29	23-28.50	17.50-19.00
1951	Commercial	Utility	Good	Commercial	Good	Commercial	HOGS From Weekly "Quotable Top" Prices
Jan	20.50-26.50	20.00-25.50	27.00-36.00	24.50-33.00	2[illegible]-32.00	25-31.00	19.25-2[illegible].00
Feb	24.00-29.50	22.50-27.00	29.00-38.00	26.50-36.00	27.75-34½	26-32.50	20.25-22.00
Mar	25.50-29.50	24.00-28.50	30.00-38.00	28.00-36.00	30-34.50	28-32.00	20.00-20.35
Apr	25.50-31.00	24.00-29.00	32.00-39.00	30.00-37.00	32-34.50	28-33.50	20.25-20.50
May	26.00-29.50	23.00-29.00	30.00-39.00	27.00-35.00	30-35.00	27-34.50	20.75
June	26.00-30.00	22.00-29.00	30.00-40.00	28.00-37.00	29.50-34	27-33.00	21.25-22.25
July	25.00-30.00	22.00-27.50	30.00-38.00	27.00-36.00	29.50-34	27½-33½	22.50-23.25
Aug	25.50-29.25	22.00-27.00	30.00-36.00	27.00-33.00	29.50-34	26½-31	21.00-22.75
Sept	26.00-29.50	22.50-27.50	30.00-36.00	26.00-32.50	29.75-34	26½-31½	19.75-20.50

LEADING LIVESTOCK COUNTIES IN FLORIDA (Dept.of Commerce US Census '45)

County Cattle & Calves	County Hogs & Pigs	County Goats & Kids	County Sheep & Lamb	County Horses & Colts	County Mules & Colts
Polk	Jackson	Jackson	Santa Rosa	Polk	Jackson
Highlands	Suwannee	Marion	Washington	Marion	Gadsden
Osceola	Levy	Alachua	Polk	Hillsborough	Madison
Hardee	Alachua	Levy	Walton	Alachua	Holmes
Hillsborough	Madison	Washington	Osceola	Jackson	Suwannee
Marion	Santa Rosa	Santa Rosa	Duval	Sumter	Alachua
DeSoto	Holmes	Escambia	Alachua	Hardee	Jefferson
Okeechobee	Marion	Taylor	Nassau	Santa Rosa	Washington
Alachua	Gadsden	Suwannee	Calhoun	Levy	Columbia
Levy	Columbia	Union	Escambia	Palm Beach	Santa Rosa

It is difficult to make a statement as to the exact losses incurred to livestock in the USA as it involved (1) bruises, injuries, cripples and deaths on the farm, to market, in yards, and at packing plants. It is estimated that bruises and injuries take a toll of about $14,000,000 annually (USA), and possibly $450,000 in Florida annually. (2) External and internal parasite damage is very difficult to arrive at; but would probably be near $125,000,000(USA)and possibly $500,000 in Florida. (3) The loss in calf and pig crop from malnutrition, improper feeding, care and management at birth and during the feed period possibly amounts to in Florida some $4,000,000 annually on hogs and possibly $5,000,000 on cattle due to low crop of pigs and calves born and raised. The calf crop has been from 57 to 64% annually when it should have been 85% or more. The number of pigs raised is about 60% of the total born. These losses could and should be corrected.

These losses happen (1) on the farm, (2)in transit,(3)at public markets and(4) at slaughtering plants. They are caused by inferior breeding stock as to bone, conformation, quality and ability to finish. Often it is caused by lack of suitable minerals, protein supplements combined with sufficient good feed and grazing crops to keep the animals thrifty and growing.

Animals should be given the proper amount of feeds to properly develop them. Grazing crops make up a large portion of the low cost feeds and these crops are very important as they help to reduce losses from parasites by (1) cutting the mortality rate,(2)reducing the parasitic infection,(3)improving general thriftiness of the animal; at the same time these grazing crops help to prevent (1) waste in time, (2) waste in feed, (3) waste of animal life and (4) waste of income.

Some of the biggest losses are caused by (1)defective shipping equipment such as broken boards, protruding nails, holes in the floor in cars and trucks and non-installed bull-boards in cars, etc;(2) poor bedding (and there is only one good bedding- 4 inches of sand);(3)clubs, prod-poles, sharp corners, unnecessary obstructions in the feed lots and yards;(4)slippery footing, rush loading, overcrowding; (5) loss of temper, sharp horns on cattle, sharp tusks on hogs; (6) internal injuries caused by swallowed-wire, feeding clips,etc; (7) preventable diseases such as T.B., Bang's, blackleg, anthrax, cholera, etc; (8) poor feed conditions due to lack of balanced diet(lack of mineral and protein supplements,etc)-resulting in emaciation, reduced calf, pig or lamb crop, and often resulting in death prior to, during and after shipments;(9)shipping-colds or shipping-fever caused by insanitary conditions often produced by"4-overs"- Over-fatigue, over-exposure, over-crowding and over-filling; (10) insanitary conditions resulting in the production of a number of species of worms in cattle,hogs, sheep, poultry, etc.,and the loss of thousands of dollars in livers, kidneys and casings; (11) the lack of good shipping equipment including corrals, chutes, squeezes, loading and unloading pens; (12)the lack of shade and water; (13) irregular driving speed or jerky driving; and taking curves too fast; (14) mixing species in loads, such as horses, cattle, hogs, and sheep, and/or mixing classes, such as cows, steers, heifers, calves and bulls, or mixing a class within a load where there is a great difference in age,condition or weight; (15) not stopping for rest and water often enough to preclude "downers", and if "downers" occur get them up on their feet as soon as possible to prevent trampling; and (16) or other means which may lessen the comfort and/or add to the losses from bruises, injuries, cripples and deaths.

Many of these losses can be prevented by (1) feeding mineral for strength of bone to help carry the animal to market, (2) sufficient protein to properly balance the feed and to give strength, (3) by providing sufficient feeds to properly grow out the animal, (4) by proper care and management practices and (5) by exercising proper care, good judgment and practices at shipping time. Other practices include adequate feeding trough and feed rack space when feeding, comfortable shelters, dehorning of calves destined for feed lots, ample and convenient sorting pens or corrals and chutes and loading facilities on the farm and at shipping point. It is important to see that the equipment used in transportation is in good condition, free of nails, broken boards, wire, or other sharp objects; avoid striking and kicking of animals.

If one decides to kick an animal, let him first remove his shoe. Do not feed just prior to shipment, and water sparingly. Handle animals quietly - not in haste or excitement; segregate classes within a species or do not ship bulls and cows and calves in the same car unless amply partitioned. Likewise do not ship cattle and hogs and/or calves mixed in trucks or cars except partitioned. Use 3 to 4 inches of sand as bedding, never use sawdust or straw as it may cause slipping. Do not over-crowd, overheat, overtax or overload. Use canvas slappers but never use clubs or canes. Slow down on sharp curves and do not start or stop suddenly.

Losses from disease and foreign objects take a tremendous toll. Greater sanitary conditions will help eliminate waste at market time. All breeding animals should be tested for Bang's, and Tuberculosis, and calves treated for Blackleg and pigs for Cholera. Often shipped cattle will rapidly overcome shipping colds if they are given one pound of baking soda to 12 gallons of water for cattle to drink when unloaded or after they have had time to eat some hay after unloading. Insanitary conditions lead to increased tuberculosis among hogs, cattle and sheep, and increase worms in cattle, hogs and sheep. Pericarditis (puncture of heart or heart membrane by foreign objects) causing death, occurs by wires, nails, stones, clips, and other foreign objects often found in feeds. Be careful in this respect.

Internal and external parasites take a tremendous toll. Each producer should have Agricultural Year Book, 1942, "Keeping Livestock Healthy". Write U.S. Senator.

Shipping fever is generally caused by (1) over-fatigue; (2) over-exposure, (3) over-crowding, (4) over-filling. The use of baking soda as outlined above in the first water after being unloaded will do much to preclude shipping fever and/or overcome it. The amount of soda may be reduced gradually until after a period of 4 or 5 days they are on water without it. The length of time the soda would be given would depend on how serious the cold. All cattle destined for feed lots should have it when unloaded. If the cold is not serious, do not give them soda water over 1 to 2 days. If the cold is serious, animals should be isolated from others and treated until over the cold, and/or see your Veterinarian.

Grubs in cattle are caused by heel flies, warbles, and/or cattle grubs. They are causing from $1 to $3 a head loss annually wherever the grubs are found.

Improper branding of hides or branding on the upper portion of the animal's body where the higher prices of the hide are found, decreases the value of cattle hides and calf skins from 1¢ to 3¢ per lb., depending upon the location and extent of the brand.

In loading cattle one should keep in mind that the length of the car, average weight per head, the condition of the animal, etc. has much to do with the number of head loaded per car. If cattle or calves are in good condition, normally it will take about 56 head of 300 lbs. weight each or 45 head of 400 lbs. each or 40 head of 500 lbs. each, 36 head of 600 lbs. each, 31 head of 700 lbs. each, 28 head of 800 lbs. each, 25 head of 900 lbs. each or 22 head of 1,000 lbs. each to fill and/or properly load a 36 ft. car. Normally a 40 ft. car would carry about 2500 lbs. live weight more than the 36 ft. car. Thin and/or emaciated cattle must be loaded according to condition. It is difficult to state how many such cattle can be loaded in a car. One must therefore take into account condition of animals when determining the number to load in a car, or, the length of the car, condition of the animal, average weight per head, and other factors will help to determine how many animals to load in car. One should not overload, but should load snugly -not tight. Hogs: 80 hogs 200 lbs. or 90 hogs 160 lbs or 16,000 lbs. fat hogs will fill 36 ft. car.

Every producer should know grades of livestock and should sell by grade and weight. Some benefits of classifying and grading are- Animals can be sold according to their value, will be accepted by buyers when not present, can be accurately reported as Market News, be a guide for production, breeding and feeding operations, makes for comparisons of markets by grade and price, and provides the basis for statistical study of supplies, demand, prices, and movement.

L.H.Lewis, Marketing Specialist, Livestock and Field Crops, Fla. State Marketing Bureau
Gifford N.Rhodes, Livestock Market News Specialist, Florida State Marketing Bureau.

The shipments and sales of cattle are generally heavier from July thru January than from February thru June, As to calves, the shipments are generally heavier per months August thru January as compared with February thru June, and hog shipments are heavier during the months of December, January, February and March, with 75% October-March. We suggest adjusting feed conditions to more evenly distribute the marketings or finishing livestock for market, so as to feed markets.

1950 SLAUGHTER - FLORIDA - CATTLE, CALVES AND HOGS (USDA, BAE- Preliminary Estimates)

1950	CATTLE			CALVES			CATTLE & CALVES		HOGS			
		Live Weight			Live Weight					Live Weight		
Month:	Number	Total (000)	Ave.	Number	Total (000)	Ave.	Number	Pct. by Months	Number	Total (000)	Ave.	Pct. by Months
Jan	16,000	11,705	727	5,400	1,618	299	21,400	8.31	53,000	9,506	178	12.73
Feb	14,200	10,632	747	4,900	1,565	319	19,100	7.42	44,000	7,619	172	10.57
Mar.	14,700	10,724	728	3,700	1,032	276	18,400	7.15	35,000	5,931	168	8.41
Apr	15,000	11,144	742	3,400	925	272	18,400	7.15	34,000	6,103	180	8.17
May	15,000	11,179	726	4,500	1,143	256	19,500	7.58	19,000	3,505	187	4,56
June	17,000	12,393	745	6,200	1,414	228	23,200	9.01	14,600	2,701	185	3.51
July	17,000	12,379	729	7,400	1,859	251	24,400	9.48	14,600	2,760	188	3.51
Aug.	16,000	11,216	699	8,500	2,230	262	24,500	9.52	15,000	2,780	184	3.60
Sept	17,000	12,220	711	8,200	2,251	275	25,200	9.79	28,000	5,307	188	6.73
Oct	15,000	10,884	727	6,700	1,830	280	21,700	8.43	40,000	7,115	177	9.61
Nov.	15,000	11,395	758	7,100	2,008	283	22,100	8.59	57,000	10,262	179	13.70
Dec	13,800	10,610	767	5,700	1,562	276	19,500	7.57	62,000	10,666	172	14.90
TOTAL:	185,700	136,481	735	71,700	19,487	272	257,400	100%	416,200	74,255	178	100%

ESTIMATED RECEIPTS - CATTLE & CALVES, and HOGS - FLORIDA LIVESTOCK AUCTIONS, 1950,
Average Prices, Average Weights, and Percent Marketed by Months

Month:	Cattle & Calves Number Sold	Percent by Months	Average Weight	Ave.Cwt. Price	Hogs Number Sold	Percent by Months	Average Weight	Ave.Cwt. Price
Jan	18,818	6.7	412	$17.14	53,021	11.9	151	$14.53
Feb	16,341	5.9	408	18.26	33,417	7.5	162	15.39
Mar	18,208	6.5	380	17.93	27,842	6.2	168	14.86
Apr	20,647	7.4	393	18.27	18,620	4.2	126	14.36
May	27,039	9.7	413	18.20	19,473	4.4	128	15.10
June	28,046	10.0	387	19.22	20,081	4.5	108	16.60
July	27,101	9.7	421	20.35	28,830	6.4	117	19.50
Aug	33,498	12.0	425	20.85	41,002	9.2	140	20.11
Sept	26,584	9.5	443	21.44	45,696	10.2	151	18.80
Oct	25,282	9.0	455	20.16	54,269	12.1	152	17.77
Nov	23,048	8.3	466	20.71	57,091	12.8	142	16.99
Dec	14,860	5.3	516	21.04	47,224	10.6	117	16.30
Total	279,472	100%	426	$19.67	446,566	100%	141	$16.89

ESTIMATED LIVESTOCK OUTSHIPMENTS - RAIL & TRUCK- FLORIDA - 1950

Month	NUMBER OF HEAD							
	CATTLE AND CALVES				HOGS			
	Truck	Rail	Total	Pct.by Months	Truck	Rail	Total	Pct.by Months
Jan.	5,688	570	6,258	5.1	17,090	1,670	18,760	16.7
Feb.	4,886	1,120	6,006	4.9	7,154	200	7,354	6.5
March	6,915	1,880	8,795	7.2	3,704	-	3,704	3.3
April	8,245	3,450	11,695	9.6	2,812	-	2,812	2.5
May	9,294	3,590	12,884	10.6	5,041	-	5,041	4.5
June	9,812	3,360	13,172	10.8	2,326	-	2,326	2.1
July	9,920	2,410	12,330	10.1	3,679	-	3,679	3.3
Aug.	9,663	5,635	15,298	12.6	7,255	-	7,255	6.4
Sept.	8,672	4,8000	13,472	11.1	10,445	900	11,345	10.1
Oct.	6,503	4,000	10,503	8.7	16,719	800	17,519	15.5
Nov.	6,028	1,100	7,128	5.9	18,402	700	19,102	17.0
Dec.	3,798	280	4,078	3.4	12,871	710	13,581	12.1
Total	89,524	32,195	121,719	100%	107,498	4,980	112,478	100%
Pct.	73.5	26.5	100%		95.6	4.4	100%	

Similar TOTAL FIGURES for 1949 were :

	Cattle and Calves				HOGS		
	Truck	Rail	Total		Truck	Rail	Total
CATTLE & CALVES	74,330	21,429	95,759	HOGS	129,345	12,155	141,500
Pct.	77.6	22.4	100%	Pct.	91.4	8.6	100%

Sources: TRUCK: For counties east and south of Suwannee River, from daily reports sent in by Truck Passing Stations operated by Florida State Department of Agriculture, State Livestock Sanitary Board cooperating. For counties west of Suwannee River,, from data tallied on markets by USDA,, PMA, Livestock Market News office, Thomasville, Ga. RAIL: Combined numbers of carlots supplied by J.C. Townsend, Jr., Agricultural Statistician, USDA, BAE, Orlando, Fla.

FLORIDA CITRUS BY-PRODUCT FEEDS

July 1 - June 30, years indicated

Season Year	Citrus Pulp Tons	Citrus Meal Tons	Citrus Pellets Tons	Citrus Molasses Tons
1950-51	163,333.78	19,307,94	155.65	68,674.27
1949-50	150,611.92	12,575.74	203.55	41,380.73
1948-49	129,570.45	-	-	39,263,97
1947-48	154,181.32	-	-	65,687.38
1946-47	96,224.30	-	-	18,034.30
1945-46	108,470.41	-	-	44,163.63
1944-45	88,724.52	-	-	19,260.55
1943-44	67,130.50	-	-	14,495.21
1942-43	47,367.10	-	-	-
1941-42	27,696.73	-	-	-
1940-41	32,720.64	-	-	-

As to feed crops for cattle in Florida: The average corn production is about 8,000,000 bushels, oat production 200,000 bushels, black strap molasses about 60,000 tons. Citrus molasses nearly 69,000 tons, citrus pulp 163,000 tons, and other by-products of citrus about 20,000 tons. Our great need is for increased yields of corn and oats to finish our hogs as well as creep-feed and short-feed cattle.

Our pastures need to be improved in numbers of acres as well as quality of acres so as to meet the minimum requirements of 3 acres per cow, or we need a minimum of 6,500,000 acres of improved pasture composed of grasses and legumes.

FLORIDA'S POSITION AS A CATTLE STATE

(Total Cattle, Dairy and Beef Cattle)

LIVESTOCK ON FARMS, JANUARY 1, 1951

STATE	Total Cattle		Number Milk Cattle					Beef Cattle	
	No. (000)	Rank	Cows&Hfrs 2-yrs&over (000)	Hfrs 1-2 yr. (000)	Hfrs Cfs (000)	Total No. Milk Cattle (000)	Rank	Number (000)	Rank
Maine	214	43	120	35	39	194	38	20	41
New Hampshire	117	46	70	17	22	109	42	8	45-46
Vermont	429	40	281	63	67	411	28	18	42
Mass.	177	44	122	22	25	169	40	8	45-46
Rhode Island	27	48	21	2	3	26	48	1	48
Conn.	171	45	116	21	25	162	41	9	44
New York	2,248	12	1,483	310	340	2,133	3	115	39
New Jersey	228	42	164	27	27	218	36	10	43
Penna.	1,808	18	1,010	255	290	1,555	9	253	35
Ohio	2,235	13	1,060	264	302	1,626	6	609	27
Indiana	1,848	15	721	147	177	1,045	13	803	21
Illinois	3,317	8	972	265	365	1,602	8	1,715	8
Michigan	1,971	14	1,026	276	302	1,604	7	367	33
Wisconsin	3,918	4	2,456	539	608	3,603	1	315	34
Minnesota	3,342	6	1,471	381	429	2,281	2	1,061	14
Iowa	5,208	2	1,158	271	336	1,765	5	3,443	2
Missouri	3,356	7	994	200	261	1,455	10	1,901	5
No.Dakota	1,496	24	409	92	150	651	23	845	18
So.Dakota	2,454	11	368	96	175	639	24	1,815	6
Nebraska	4,170	3	467	118	176	761	19	3,409	3
Kansas	3,917	5	634	137	185	956	14	2,961	4
Delaware	63	47	38	9	10	57	46	6	47
Maryland	471	39	255	57	65	377	30	94	40
Virginia	1,197	28	507	91	136	734	20	463	30
W.Virginia	570	37	232	43	47	322	32	248	36
No.Carolina	788	35	399	83	101	583	25	205	37
So.Carolina	396	41	174	42	50	266	35	130	38
Georgia	1,330	26	414	115	149	678	22	652	24
FLORIDA	1,503	23	152	55	96	303	34	1,200	12
Kentucky	1,721	20	640	109	144	893	16	828	19
Tennessee	1,550	22	640	125	150	915	15	635	25
Alabama	1,476	25	447	142	189	778	18	698	23
Miss.	1,791	19	554	118	174	846	17	945	17
Arkansas	1,282	27	435	111	155	701	21	581	28
Louisiana	1,569	21	338	80	136	554	26	1,015	15
Oklahoma	2,814	10	648	158	248	1,054	12	1,760	7
Texas	9,260	1	1,309	274	411	1,994	4	7,266	1
Montana	1,815	17	123	27	54	204	37	1,611	9
Idaho	986	32	220	62	92	374	31	612	26
Wyoming	1,041	31	54	14	15	83	44	958	16
Colorado	1,818	16	198	50	61	309	33	1,509	10
N.Mexico	1,189	29	57	12	17	86	43	1,103	13
Arizona	883	34	50	13	13	76	45	807	20
Utah	560	38	112	27	39	178	39	382	32
Nevada	580	36	21	7	15	43	47	537	29
Washington	885	33	319	70	112	501	27	384	31
Oregon	1,118	30	235	59	86	380	29	738	22
California	2,872	9	885	201	325	1,411	11	1,461	11
United States	84,179		24,579	5,692	7,394	37,665		46,514	

Data taken from Crop Reporting Board statistics, BAE, USDA. Released Feb.15,1951.

FLORIDA'S POSITION AS A HOG, SHEEP, HORSE AND MULE STATE

LIVESTOCK ON FARMS, JANUARY 1, 1951

STATE	Hogs & Pigs		Sheep & Lambs		Horses & Colts		Mules & Colts	
	Number (000)	Rank	Number (000)	Rank	Number (000)	Rank	Number (000)	Rank
Maine	33	42	20	38	22	41		
New Hampshire	11	47	7	44	9	45		
Vermont	19	46	11	41	27	39		
Mass.	92	36	9	43	11	43		
Rhode Island	9	48	2	47-48	1	48		
Conn.	23	43	6	45	7	46-47		
New York	193	31	182	30	126	15	2	29-30-31-32
New Jersey	69	38-39-40	10	42	10	44	1	
Penna.	704	23	221	29	97	22	9	17-18-19
Ohio	3,430	6	1,128	9	112	18	5	22-23-24-25
Indiana	4,934	3	472	19	94	24	9	17-18-19
Illinois	6,976	2	625	18	157	10	15	15
Michigan	1,001	18	423	21	80	25	1	
Wisconsin	1,941	8	285	27	202	6	1	
Minnesota	3,813	5	737	15	227	3	1	
Iowa	13,231	1	1,021	10	205	5	5	22-23-24-25
Missouri	4,916	4	1,214	8	312	2	60	12
No. Dakota	421	27	375	23	140	12	1	
So. Dakota	1,543	12	893	12	140	11	1	
Nebraska	2,999	7	815	13	210	4	6	21
Kansas	1,504	13	694	16	177	8	11	16
Delaware	40	41	2	47-48	7	46-47	2	29-30-31-32
Maryland	270	29	49	35	36	36	7	20
Virginia	797	22	299	26	121	16	64	11
W. Virginia	246	30	311	25	79	26	5	22-23-24-25
No. Carolina	1,131	16	39	36	78	27	236	2
So. Carolina	617	26	3	46	20	42	142	6
Georgia	1,836	9	14	39	33	38	211	3
FLORIDA	631	25	12	40	25	40	28	13
Kentucky	1,668	11	749	14	165	9	126	7
Tennessee	1,385	14	270	28	113	17	197	4
Alabama	1,286	15	23	37	50	34	179	5
Miss.	946	19	106	33	95	23	254	1
Arkansas	1,013	17	60	34	128	14	122	8
Louisiana	643	24	148	31	107	19	111	10
Oklahoma	843	20	145	32	192	7	25	14
Texas	1,786	10	7,119	1	324	1	120	9
Montana	171	32	1,870	3	134	13	1	
Idaho	169	33	1,020	11	74	29-30	3	28
Wyoming	69	38-39-40	1,934	2	76	28	1	
Colorado	316	28	1,645	5	103	21	4	26-27
New Mexico	69	38-39-40	1,384	7	74	29-30	4	26-27
Arizona	24	45	385	22	62	32	5	22-23-24-25
Utah	71	37	1,438	6	52	33	1	
Nevada	26	44	465	20	34	37	1	
Washington	132	35	337	24	46	35	2	29-30-31-32
Oregon	141	34	656	17	63	31	2	29-30-31-32
California	835	21	1,867	4	105	20	9	17-18-19
United States	65,028		31,505		4,763		1,990	

Note: Those states with 1(000) rank 33-42 inclusive.

Data taken from Crop Reporting Board statistics, BAE, USDA, Released Feb.15,1951.

NUMBER OF CATTLE ON FARMS, VALUE PER HEAD, TOTAL VALUE, USA & FLORIDA, Jan.1, Years indicated.
Florida data shows breeding cows, number of bulls needed & produced, Marketings and Income, USDA, BAE data

	U S A			F L O R I D A										
							No. Cows						Out-shipments	
Year	No. Head (000)	Avg. Value Head	Total Value (000)	No. Head (000)	Avg. Value Head	Total Value (000)	Breeding (000)	No. P.B. Bulls Needed (a)	Supplied	No. Slaughtered Cattle (000)	Calves	Gross Income (000)	Total	Stocker-Feeder
1929	58,877	$ 59.09	$3,479,041	600	$23.40	$14,040	335	13,350	250	84	83	$3,610		
1930	61,003	57.30	3,495,472	590	29.10	12,571	328	12,600	275	44	72	1,860		
1931	63,030	39.31	2,477,709	620	23.30	14,446	336	12,600	320	38	45	1,148		
1932	65,801	26.39	1,737,000	680	17.90	12,172	345	11,600	362	70	23	1,236		
1933	70,280	19.74	1,387,000	737	14.00	10,318	376	13,445	412	98	39	1,700		
1934	74,369	17.78	1,322,000	773	13.80	10,723	402	14,250	512	113	45	2,210		
1935	68,846	20.20	1,391,000	788	14.60	11,505	416	14,470	600	128	67	3,232		
1936	67,847	34.06	2,311,000	788	18.20	14,342	420	14,200	760	128	59	3,338		
1937	66,098	34.06	2,251,000	796	18.50	14,726	420	13,700	852	151	81	4,392		
1938	65,249	36.58	2,387,000	780	20.00	15,600	413	12,440	1,100	107	46	2,937		
1939	66,029	38.44	2,538,000	820	20.50	16,810	429	12,550	1,300	113	67	3,589		
1940	68,309	40.60	2,773,000	851	20.90	17,159	451	12,480	1,550	109	61	3,546	97,000	
1941	71,755	43.20	3,109,000	902	22.40	20,205	473	12,400	1,700	120	77	5,239	103,000	
1942	76,025	55.00	4,181,000	947	28.80	30,010	506	12,770	1,820	81	91	5,715	81,000	
1943	81,204	69.30	5,627,000	1042	37.90	41,501	567	14,460	1,850	99	92	9,080	93,000	
1944	85,334	68.40	5,837,000	1136	45.10	51,234	615	15,780	1,900	172	112	13,572	145,000	
1945	85,573	66.90	5,725,000	1159	42.50	49,258	628	14,750	2,100	124	32	16,450	173,000	726
1946	82,434	76.20	6,281,000	1205	46.80	56,394	660	16,330	2,400	126	28	19,553		5,316
1947	81,207	97.40	7,910,000	1265	54.00	68,310	686	16,540	2,650	224	180	22,781		19,016
1948	78,126	116.00	9,063,000	1265	58,70	74,256	718	16,845	2,825	241	154	31,055		24,744
1949	78,495	135.00	10,587,000	1265	74.20	93,863	668	17,940	3,000	159	133	22,295		
1950	80,277	123.00	9,873,710	1392	71.60	99,667	637	17,000	3,400	186	72	55,317		
1951	84,179	160.00	13,441,384	1503	97.40	146,392	716							

(a) Bulls at rate of 1 to 25 breeding cows.

As to weather conditions, Florida has ample rainfall and moderate temperature to produce grazing over a long season, ten months or more per year. Two lbs.of 41% cottonseed cake or its equivalent per head per day for about 100 days fed during the winter, together with proper mineral supplement and normal roughage should result in a good calf crop,-85% or more annually. The average calf crop for past 10 yrs has been 60.8%. Improved winter feeding practices will help.

Florida has 35,111,040 acres of land of which 22,000,000 to 25,000,000 are adapted to the production of pastures and other feeds for livestock. Up to 8,000,000 acres could be used profitable to grow crops for livestock, leaving some 14,000,000 to 16,000,000 acres for improved pastures.

AVERAGE RAINFALL in inches and TEMPERATURE in Degrees F. 35 years, by Months (Data from Weather Bureau)

Months	Jan.	Feb.	March	April	May	June	July	Aug.	Sept.	Oct.	Nov.	Dec.	Ave. Annual
Rainfall	2.79	2.96	3.23	2.83	4.21	6.76	7.17	7.22	6.67	4.37	2.23	2.83	53.27
Temperature	59.6	61.1	65.1	70.0	75.6	79.8	81.3	81.4	79.5	73.3	65.1	60.2	71.00

CATTLE & CALVES, INVENTORY NUMBERS, CALF CROP & DISPOSITION, PRODUCTION AND INCOME - FLORIDA. USDA.BAE DATA.**

Year	On hand Jan.1. All Cattle	On hand Jan.1. All Cows 2 yrs.up	Calves born Calf Crop	Calves born Number	Marketings 2/ Cattle	Marketings 2/ Calves	Farm Slaughter Cattle	Farm Slaughter Calves	Deaths Cattle	Deaths Calves	Production Sold-Lbs. Live Wgt.	Price per 100 lbs. Cattle	Price per 100 lbs. Calves	Gross Income
	(000)			(000)										(000)
1924	740	402	45%	181	82	59	12	10	28	18	45,735	$ 3.65	$ 5.80	$ 2,157
1925	712	391	47	184	89	59	10	10	28	17	49,060	3.90	6.10	2,383
1926	684	382	52	200	110	75	8	10	21	20	60,875	4.50	6.50	3,221
1927	640	358	53	189	102	68	6	10	16	15	56,270	6.00	7.20	3,264
1928	612	343	54	185	88	66	7	3	16	17	49,390	6.50	8.00	3,627
1929	600	335	56	188	77	80	7	3	15	16	45,775	6.60	9.60	3,610
1930	590	328	54	176	34	68	10	4	16	16	42,055	5.20	8.50	1,860
1931	620	336	52	176	30	39	8	6	18	18	42,925	4.00	7.30	1,148
1932	680	345	54	185	63	15	7	8	18	18	54,395	3.20	5.10	1,236
1933	737	376	54	202	86	31	10	8	15	15	67,760	3.10	4.70	1,700
1934*	773	402	53	212	97	36	16	9	20	20	62,295	3.50	5.10	2,210
1935	788	416	57	237	119	62	9	5	20	25	65,290	4.60	6.10	3,232
1936	788	420	54	227	119	53	9	6	17	19	67,585	4.70	6.20	3,338
1937	796	420	58	244	142	74	9	7	16	15	75,960	5.20	6.40	4,392
1938	780	413	53	219	98	41	9	5	15	16	68,635	4.90	6.00	2,937
1939	820	429	58	249	103	60	15	7	23	20	70,825	5.20	6.40	3,589
1940	851	451	55	248	98	54	11	7	27	14	73,140	5.40	6.50	3,545
1941	902	473	58	272	104	68	10	9	33	17	79,520	6.70	7.70	5,289
1942	947	506	60	306	65	83	16	8	35	22	87,830	9.50	9.90	8,715
1943	1,012	567	57	322	82	85	17	7	38	23	102,045	10.60	12.00	9,080
1944	1,136	615	57	346	154	107	18	5	35	22	137,590	9.40	10.60	13,572
1945	1,159	628	65	409	65	120	124	32	33	29	149,895	10.00	11.20	16,450
1946	1,205	660	64	422	75	129	126	28	33	25	155,845	11.20	13.00	19,558
1947	1,265	686	64	438	207	176	17	4	31	27	168,280	12.20	14.00	22,770
1948	1,265	718	59	424	226	150	15	4	26	22	175,880	16.10	14.40	31,055
1949	1,265	668	64	428	143	128	16	5	19	22	124,965	15.60	18.20	22,295
1950	1,392	736	60	442	202	119	15	4	18	21	170,410	18.70	22.40	35,317
1951	1,503	796												

Some of the greatest needs to build up a profitable cattle industry: (1) Save higher percent of the best heifers of the calf crop. (2) Protect the herd against contagious diseases. (3) Use the best bulls obtainable. Spend, if necessary, the value of 5 cows in purchasing one bull, the bull to be better than the best cow. (4) See that the cattle receive ample proteins & minerals. The minimum protein equivalent for 750 lb. cow during the winter is 2½ lbs. of 41% cottonseed cake. Unless the minimum requirements of protein and minerals are met the calf crop will continue low. A good calf crop is 85% or more, based on breedable cows. (5) The cheapest feed is good pasture composed of grasses and legumes.

2/ excludes interfarm sales. *Includes government purchases. **Data from several sources, combined by Fla. S.M. Bureau.

NUMBER OF HOGS ON FARMS, VALUE PER HEAD, TOTAL VALUE, USA AND FLORIDA. Jan. 1, Years Indicated
Florida Data also Shows Number Slaughtered, Gross Income, and Average Weight Head Sold. BAE, USDA.*

	U S A			F L O R I D A					
Year	No.Head	Avg.Value Head	Total Value	No.Head	Avg.Value Head	Total Value	Number Slaughtered	Ave** Weight	Gross Income
1929	59,042,000	$13.05	$ 770,498,000	531,000	$ 8.10	$ 4,301,000	451,000	142.1	$ 5,303,000
1930	55,705,000	13.76	766,501,000	519,000	7.50	3,893,000	458,000	140.2	5,257,000
1931	54,835,000	11.36	622,926,000	514,000	6.10	3,135,000	460,000	144.9	3,879,000
1932	59,301,000	6.13	363,000,000	534,000	3.60	1,923,000	484,000	142.8	2,483,000
1933	62,127,000	4.21	262,000,000	545,000	2.70	1,472,000	504,000	137.3	2,475,000
1934	58,621,000	4.09	240,000,000	515,000	3.15	1,622,000	463,000	139.2	2,748,000
1935	39,066,000	6.31	247,000,000	447,000	3.35	1,498,000	426,000	145.7	4,197,000
1936	42,975,000	12.71	546,000,000	447,000	5.60	2,503,000	472,000	154.8	5,364,000
1937	43,083,000	11.89	512,000,000	499,000	6.80	3,393,000	550,000	151.0	6,446,000
1938	44,525,000	11.26	501,000,000	519,000	5.90	3,062,000	610,000	161.5	6,320,000
1939	50,012,000	11.18	559,000,000	582,000	5.80	3,376,000	655,000	156.3	5,871,000
1940	61,165,000	7.78	476,000,000	600,000	4.30	2,580,000	575,000	159.0	4,598,000
1941	54,353,000	8.34	453,000,000	630,000	4.45	2,804,000	635,000	154.7	7,428,000
1942	60,607,000	15.60	945,000,000	630,000	6.80	4,284,000	646,000	168.6	10,808,000
1943	73,881,000	22.50	1,662,000,000	700,000	10.90	7,630,000	762,000	164.2	15,657,000
1944	83,741,000	17.50	1,467,000,000	770,000	10.30	7,931,000	772,000	153.8	13,876,000
1945	59,331,000	20.60	1,224,000,000	716,000	10.80	7,733,000	781,000	148.6	16,896,000
1946	61,301,000	23.90	1,468,000,000	630,000	12.70	8,001,000	727,000	164.3	19,312,000
1947	56,921,000	36.00	2,049,000,000	630,000	16.20	10,080,000	695,000	160.8	24,017,000
1948	55,028,000	42.80	2,356,000,000	640,000	23.40	14,976,000	747,000	163.0	24,687,000
1949	57,139,000	38.20	2,184,000,000	666,000	21.70	14,452,000	789,000	140.0	21,355,000
1950	60,424,000	27.10	1,638,964,000	619,000	19.50	12,070,000	745,000	168.3	21,040,000
1951	65,028,000	33.20	2,161,835,000	631,000	23.70	14,955,000	-	-	-

* Source information BAE, USDA. Crop Reporting & Income . Combined by Florida State Marketing Bureau.

** Average weight obtained by dividing total production lbs. by total head marketed or slaughtered.

Production vs. Consumption of Meats in Florida. Assuming that Florida eats the average or normal amount of meat per capita USA, and using a 10 yr period, 1932-1941 which is more nearly normal, namely Pork 68.83 lbs. Beef 54.53 lbs. Veal 7.75 lbs. Mutton & Lamb 6.73 lbs. Lard 12.67 lbs. we would be producing about 60% of the Pork we are consuming in the State. Likewise we are producing about 60% of the Beef. The 1950 Census shows Florida with a population of 2,771,305. We are supplying practically no mutton and lamb. Feed is one of our greatest needs- Provide a year-round supply for cattle & hogs.

To meet these needs will require (1) selected sows as to desirable conformation and quality - intermediate type with 12 to 14 evenly spaced udders, (2) good purebred boars, better than the best sow in the herd. (3) Breeding stock quiet and docile - adapted to local conditions. (4) Gilts replacing sows to be better than sows replaced. (5) Go after, get and save the pig crop . (6) Feed the necessary proteins and minerals to develop muscle and bone. (7) Segregate classes as to size, age and weight, keeping fattening hogs separate from the breeding herd, (8) Breed no gilts under 6 months of age. (9) Feed profits into hogs. (10) Treat the herd to control cholera - prevent parasites and diseases. (11) Sell thru best markets.

HOGS INVENTORY, NUMBERS, PIG CROPS AND DISPOSITION, PRODUCTION AND INCOME, Years Indicated. USDA, BAE Data *

F L O R I D A

Year	Number Jan.1	No. Sows Farrowing	No. Boars Needed **	No. Pigs Saved	No. Head Slaughtered	No. Deaths on Farms	Production in Pounds	Price per 100 lbs.	Gross Income	Out-Shipments Total	Out-Shipments Stocker-Feeder
1924	640,000	92,000	1,700	441,000	504,000	79,000	57,735,000	$ 7.10	$5,450,000		
1925	498,000	91,000	1,534	460,000	424,000	76,000	57,670,000	9.10	6,075,000		
1926	453,000	99,000	1,800	534,000	428,000	79,000	64,055,000	9.90	6,658,000	USDA BAE	Livestock Sanitary Board
1927	485,000	110,000	2,067	576,000	439,000	79,000	67,485,000	8.70	5,766,000		
1928	543,000	109,000	1,967	566,000	493,000	85,000	67,500,000	7.10	5,234,000		
1929	531,000	101,000	1,867	514,000	451,000	75,000	64,090,000	7.70	5,303,000		
1930	519,000	103,000	1,934	527,000	458,000	74,000	64,245,000	7.50	5,257,000		
1931	514,000	108,000	1,934	555,000	460,000	75,000	66,645,000	5.50	3,879,000		
1932	534,000	111,000	1,967	571,000	484,000	76,000	69,095,000	3.35	2,483,000		
1933	545,000	111,000	2,133	546,000	504,000	72,000	69,180,000	3.20	2,475,000		
1934	515,000	100,000	1,867	457,000	453,000	72,000	60,695,000	3.85	2,748,000		
1935	447,000	106,000	2,200	526,000	426,000	100,000	62,070,000	6.50	4,197,000		
1936	447,000	126,000	2,434	614,000	472,000	90,000	73,035,000	7.30	5,364,000		
1937	499,000	140,000	2,634	720,000	550,000	150,000	83,030,000	7.50	6,446,000		
1938	519,000	153,000	2,767	815,000	610,000	142,000	98,495,000	6.50	6,320,000		
1939	582,000	158,000	2,934	853,000	655,000	180,000	102,350,000	5.60	5,871,000		
1940	600,000	148,000	2,734	760,000	575,000	155,000	91,425,000	5.10	4,598,000	258,000	
1941	630,000	152,000	2,734	785,000	635,000	150,000	98,245,000	7.30	7,428,000	232,000	
1942	639,000	163,000	3,000	881,000	646,000	145,000	108,945,000	10.40	10,308,000	237,000	
1943	700,000	215,000	3,834	1,116,000	762,000	290,000	125,150,000	12.40	15,557,000	336,000	
1944	770,000	201,000	4,034	895,000	772,000	275,000	118,571,000	11.10	13,870,000	302,000	
1945	716,000	187,000	3,667	941,000	761,000	250,000	116,055,000	15.20	16,896,000	272,000	5,006
1946	630,000	190,000	3,433	941,000	727,000	215,000	119,405,000	15.80	19,312,000		4,211
1947	630,000	189,000	3,500	959,000	695,000	255,000	111,742,000	20.90	24,017,000		1,377
1948	640,000	186,000	3,400	998,000	747,000	225,000	121,751,000	20.30	24,687,000		2,446
1949	660,000	189,000	3,500	991,000	789,000	225,000	116,980,000	17.20	21,355,000		
1950	619,000	178,000	4,000	977,000	745,000	220,000	125,388,000	16.40	21,040,000		
1951	631,000										

*USDA, BAE. Data combined by Florida State Marketing Bureau. **Number of boars obtained by using one boar to 30 sows or gilts. Sows farrowing twice a year.

With minimum of 8,000,000 acres of good land adaptable to the production of corn, oats, rye, sorghum grains, peanuts, root crops, & grazing crops for hog&cattle, & by the use of hybrid corn which has increased yields 50% to 100%, the gross income from hogs should be materially increased. Hogs are great consumers of by-products of fields and dairies and can use many waste materials about the farm, therefore hogs should be materially increased. The income from hogs for 10-yr period is about equal that of cattle.

CATTLE: NUMBER ON FLORIDA FARMS BY CLASSES JANUARY 1 (USDA, BAE)

Year	Total	Kept For Milk			Total	OTHER					Total
		Cows 2 yrs	Heifers 1-2 yrs.	Heifer Calves	Cows & Calves for Milk	Cows 2 yrs	Heifers 1-2 yrs.	Other Calves	Steers 1 yr	Bulls 1 yr	Beef Cattle & Calves
	Thousands										
1920	880	73	19	22	114	405	82	144	118	17	766
1921	840	75	21	20	116	385	80	132	110	17	724
1922	810	78	19	22	119	360	78	131	105	17	691
1923	770	82	21	20	123	340	76	114	100	17	647
1924	740	82	19	16	117	320	74	114	98	17	623
1925	712	86	18	20	124	305	71	94	102	16	588
1926	684	89	19	22	130	293	69	81	96	15	554
1927	640	91	21	25	137	267	64	70	88	14	503
1928	612	92	24	28	144	251	65	60	79	13	468
1929	600	94	27	30	151	241	64	61	71	12	449
1930	590	95	29	31	155	233	68	58	64	12	435
1931	620	95	30	36	161	241	68	54	83	13	459
1932	680	98	34	38	170	247	72	77	99	15	510
1933	737	101	36	40	177	275	76	103	89	17	560
1934	773	106	37	37	180	296	78	110	90	19	593
1935	738	110	35	36	181	306	82	111	87	21	607
1936	788	111	35	38	184	309	83	107	84	21	604
1937	796	112	36	39	187	308	84	110	86	21	609
1938	780	110	34	44	188	303	80	104	84	21	592
1939	820	113	39	45	197	316	91	112	84	20	623
1940	851	113	40	43	196	338	93	119	85	20	655
1941	902	120	42	46	208	353	105	127	88	21	694
1942	947	121	43	48	212	385	110	130	89	21	735
1943	1,042	123	41	50	214	444	124	143	94	23	828
1944	1,136	128	45	55	228	487	135	152	110	24	908
1945	1,159	133	43	56	232	495	135	158	114	25	927
1946	1,205	140	43	60	243	520	130	168	118	26	962
1947	1,265	148	40	65	253	538	146	175	125	28	1,012
1948	1,265	148	42	65	255	570	134	166	112	28	1,010
1949	1,265	148	35	75	258	520	136	173	149	29	1,007
1950	1,392	152	45	85	293	584	143	188	163	32	1,099
1951	1,503	152	55	96	303	644	135	202	185	34	1,200

Any cattle program should include good breeding stock - males and females, improved pastures, the equivalent of $2\frac{1}{2}$ lbs. of cottonseed cake 41% protein per 750 lb. adult animal, segregation of classes, and marketing thru best markets.

FLORIDA SLAUGHTERING PLANTS

Federally Inspected Packing Plants

Southern Packing Co.	Tallahassee
Swift & Company	Ocala

State Inspected Plants

City Abattoir	W.Palm Beach
Copeland Sausage Co.	Alachua
Cullison Sausage Co.	Ocala
Roberts Packing Co.	Jacksonville
Florida Packing Co.	Quincy
Harold A.Gertner Co.	Gainesville
Farmers Meat Pkg.Co.	Marianna
Hermann Sausage Co.	Tampa
Lykes Bros.Meat Plant	Tampa
Jones,Chambliss Co.	Jacksonville
Gold Merit Packing Co.	Jacksonville
Paul Russell	Tallahassee
Southland Provision Co.	Palatka
Suwannee Cold Storage	Live Oak
National Meat Packers	Tampa

Other Abattoirs-City or not inspected

Central Packing Co	Center Hill
Fla. State Hospital	Chattahoochee
Daniels & Co(Meat Packers)	Gainesville
Miami Meat Pkg. Co.	Hialeah
George Wakefield	Homestead
S. E. Harrison	Myakka City
Molineaux Pkg. Co.	Malabar
Turner & Gee	Orlando
Thomas Pkg. Co.	Okeechobee
Fla.Sausage Co.	Pensacola
M. L. McDonald	Daytona Beach
E.G.Bass	Ft.Lauderdale
Odom's Sausage Co.	Lake City
Dirr Sausage Co.	Miami
Wades Pkg. Co.	Miami
H. S. Camp & Sons	Ocala
McKinnon & Mills	Ocala
D.Z.Ard Pkg. Co.	Pensacola
Edwards Meat Pkg.Co.	Sarasota
Perry Cameron Pkg. Co.	Sanford
Clifford B.Eiland	Sebring
H. A. Lawson	Starke
S. A.Snyder	St.Augustine
J.H.Turner	Arcadia
J.E. & Wade Andrews	Bonifay
Crum Packing Co	Plant City
C. P. Russ Meat Co.	Panama City
E.M.Hawkins	East Palatka
Geo. Thigpen	East Palatka
T. J. Faulkner, Sr.	Perry
Clyde Brogdon	Wewahitchka
Smith,Richardson & Conroy	W.Palm Beach
Escambia Sausage Co.	Pensacola
Carson A. Platt	Fellsmere
S. E.Register Meat Co.	Cottondale
Tobias Sausage Co.	Chipley

and many others

LIVESTOCK AUCTION MARKETS

Gainesville L/S Mkt.,Gainesville	Mon
Tindel & Williams L/S Mkt.Graceville	Mon.
Monticello L/S Mkt., Monticello	Mon
Hillsboro L/S Commission Co.Tampa	Mon
Glades L/S Mkt'g Assn.,Belle Glade	Mon
Beebe Auction Mkt. West Palm Beach	Mon
Jacksonville LS Auct.Mkt.Jacksonville	Tues
Hamilton Co.LS Mkt. Jasper	Tues
State Farmers' LS Market, Jay	Tues
Farmers' Produce Mkt.,Gainesville	Tues
Cattlemen's LS Auct.Mkt.Lakeland	Tues
Madison LS Market, Madison	Tues
West Florida LS Market, Marianna	Tues
Sumter Co.Farmers' Mkt. Webster	Tues
Okeechobee LS Mkt. Okeechobee	Tues
P. Cauley, Florala, Ala.	Tues
Sebring LS Market. Sebring	Wed
State Farmers' LS Mkt. Arcadia	Wed
Kissimmee LS Market, Kissimmee	Wed
Davie Auction Service, Davie.	Wed
Odom's Livestock Palace,Live Oak	Wed
Gadsden Co. LS Auct.Mkt. Quincy	Wed
Chipley Livestock Market, Chipley	Wed
Orange Co.LS Auct. Mkt. Orlando	Thurs
State Farmers' LS Mkt.DeFuniak Spgs.	Thurs
Columbia Livestock Mkt. Lake City	Thurs
E E Mills LS Auct.Mkt. Ocala	Thurs
Hardee Co. LS Auct.Mkt., Wauchula	Thurs
Central Fla. LS Co-op Assn. Bithlo	Fri
State Farmers' LS Mkt.East Palatka	Fri
Goff Livestock Commission Co.Lakeland	Sat

CASH DAILY MARKETS

Frank L.Dennis,Inc. Jacksonville.
% Jones-Chambliss Co.
Quincy LS Mkt.Quincy. "Stoney" Edwards,Mgr.
Ted May, Jay.
M. G. Neel, Greenwood
C. L. Moses & Brother, Branford (Hogs)
All meat packing plants & practically all abattoirs furnish cash daily markets.

COOPERATIVE SALES

Tri-County Farmers Co-Op.Inc.Trenton.	Tues
Holmes Co. LS Market, Bonifay	Wed

NON-COOPERATIVE SALES

E.E. Mills, Williston (hogs)	Tues
Calhoun Co. Swine Ship. Assn.Altha(hog)	Wed

Luther Pumphrey, Manager

Number of Registered Beef Herds in Florida-Year*1948(Breeders Record Association)

Aberdeen-Angus	72 herds
Brahman	269 "
Hereford & Polled Hereford	175 "
Shorthorn	22 "
Devon	8 "
Red Polled	3 "
Total Registered Beef Herds	549 herds

* more in year 1951.

There are State Associations for all Pure Bred breeds of Cattle named above.

10-YEAR COMPARISON FLORIDA LIVESTOCK, 1940 vs 1950 (USDA,BAE,Orlando,Fla)

State	CATTLE and CALVES			HOGS and PIGS		
	On Hand Jan.1,1940 Thousands	On Hand Jan.1,1950 Thousands	Change Per Cent	On Hand Jan.1,1940 Thousands	On Hand Jan.1,1950 Thousands	Change Per Cent
Maine	235	216	92	53	34	64
New Hampshire	125	118	94	18	13	72
Vermont	442	433	98	32	21	66
Massachusetts	199	179	90	102	94	92
Rhode Island	28	27	96	8	9	112
Connecticut	178	171	96	29	30	103
New York	2,100	2,226	106	298	212	71
New Jersey	201	226	112	110	72	65
Pennsylvania	1,484	1,790	121	829	704	85
Ohio	2,029	2,149	106	3,420	3,176	93
Indiana	1,684	1,760	105	4,189	4,611	110
Illinois	2,884	3,159	110	5,750	6,285	109
Michigan	1,725	1,914	111	1,039	927	89
Wisconsin	3,473	3,804	110	1,820	1,733	95
Minnesota	3,407	3,276	96	3,823	3,498	91
Iowa	4,735	4,960	105	10,400	11,920	115
Missouri	2,710	3,107	115	3,920	4,429	113
North Dakota	1,313	1,527	116	464	413	89
South Dakota	1,632	2,454	150	1,226	1,442	118
Nebraska	2,940	3,920	133	2,385	2,499	105
Kansas	2,770	3,627	131	1,519	1,253	82
Delaware	53	61	115	41	37	90
Maryland	328	449	137	251	270	108
Virginia	896	1,108	124	740	752	102
West Virginia	569	548	96	250	256	102
North Carolina	595	710	119	1,205	1,120	93
South Carolina	328	360	110	712	663	93
Georgia	953	1,220	128	1,700	1,700	100
FLORIDA	851	1,392	164	600	619	103
Kentucky	1,243	1,608	129	1,500	1,668	111
Tennessee	1,211	1,462	121	1,450	1,371	95
Alabama	1,024	1,330	130	1,267	1,225	97
Mississippi	1,273	1,674	132	1,213	965	80
Arkansas	1,138	1,209	106	1,374	974	71
Louisiana	1,204	1,439	120	999	731	73
Oklahoma	2,370	2,630	111	1,225	835	68
Texas	6,817	8,574	126	2.293	1,701	74
Montana	1,148	1,712	149	160	192	120
Idaho	748	939	126	440	209	48
Wyoming	811	1,001	123	87	80	92
Colorado	1,400	1,800	129	385	351	91
New Mexico	1,263	1,166	92	110	73	66
Arizona	864	849	98	48	24	50
Utah	432	549	127	125	83	66
Nevada	376	552	147	25	28	112
Washington	793	851	107	295	155	53
Oregon	937	1,107	118	301	166	55
California	2,278	2,709	119	885	879	99
United States	68,197	80,052	117	61,115	60,502	99

NOTE: The data on hogs and pigs was supplied by J. C. Townsend, Jr., U.S. Agricultural Statistician, Orlando, Florida.

SUMMARY OF MOTOR TRUCK SHIPMENTS OF FLORIDA FRESH VEGETABLES AND MELONS THROUGH FLORIDA ROAD GUARD STATIONS DURING SEASON 1950-51

(Expressed in Carlot Equivalents)

FLORIDA TRUCK SHIPMENTS BY STATIONS AND MONTHS

Station	Aug.	Sept.	Oct.	Nov.	Dec.	Jan.	Feb.	Mar.	Apr.	May	June	July	Total
Wilcox	3	12	44	295	342	872	1211	2322	2595	2678	1549	36	11959
Branford	-	-	-	2	4	8	28	46	49	87	118	8	350
Ellaville	2	5	13	79	54	162	427	471	572	485	166	19	2455
Suwannee	-	-	-	1	3	3	3	6	7	19	268	100	410
White Spgs.	-	-	29	228	201	458	750	1258	1581	1687	1153	17	7362
Hilliard	8	7	74	328	319	633	806	1431	1836	2420	1563	60	9485
Yulee	30	34	241	1009	1050	1927	2564	3769	4325	4465	1618	194	21226
Lake City	1	-	-	8	5	14	10	16	38	49	100	10	251
Luraville	-	-	-	-	-	-	-	1	-	-	18	15	34
TOTAL	44	58	401	1950	1978	4077	5799	9320	11003	11890	6553	459	53532

FLORIDA TRUCK SHIPMENTS BY COMMODITIES AND STATIONS

Commodity	Wilcox	Branford	Ellaville	Suwannee Springs	White Spgs.	Hilliard	Yulee	Lake City	Luraville	Total
Beans	1189	32	199	8	891	845	2977	19	-	6160
Cabbage	999	32	564	3	1006	894	2361	13	-	5872
Cantaloups	6	12	4	-	15	22	19	4	-	82
Cauliflower	63	-	8	-	46	98	137	6	-	358
Celery	1331	30	159	1	439	602	1576	12	-	4150
Corn, green	644	14	82	1	411	641	1076	10	-	2879
Cucumbers	808	31	113	11	285	795	2126	9	-	4178
Eggplant	215	5	23	--	44	112	419	-	-	818
Escarole,etc.	49	1	4	--	17	94	359	-	-	524
Lettuce	82	-	9	-	57	145	281	1	-	575
Peppers	591	17	80	9	156	283	1219	3	-	2358
Potatoes	457	15	257	1	621	846	1864	15	-	4076
Tomatoes	2454	29	647	7	1594	1958	3270	29	1	9989
Strawberries	97	10	7	-	76	103	291	-	-	584
Watermelons	1547	91	118	365	937	1171	1005	105	33	5372
Field Peas	311	4	19	1	89	112	97	6	-	639
Bun. Vegs.	163	3	20	2	120	92	47	3	-	450
Avocados	57	-	38	-	10	44	262	1	-	412
Lima Beans	76	-	4	-	40	77	178	2	-	377
Limes	17	-	4	-	-	9	174	-	-	204
Okra	39	-	3	-	20	31	50	-	-	143
Other Vegs.	189	15	39	1	261	290	696	10	-	1501
Other Fruits	1	-	-	-	3	5	26	-	--	35
Radishes	113	2	7	-	74	48	164	-	--	403
Squash	461	7	47	-	150	168	552	3	-	1388
TOTAL	11959	350	2455	410	7362	9485	21226	251	34	53532

(See Page 34 for Citrus Truck Passings.)

NOTE: The above was a machine tabulation by the U.S. Department of Agriculture of daily passing records supplied the Florida State Marketing Bureau by the Florida Road Guard Stations. The project was undertaken and successfully completed under an agreement between the Fruit and Vegetable Branch, U.S. Department of Agriculture, and the Florida State Department of Agriculture. The daily truck reports and season summaries will be combined during the 1951-52 season.

SPECIAL NOTE: The Road Guard Stations are strategically located at bridges located on the St. Mary's River and the Suwannee River. Substantially all of the fruits and vegetables in Florida are produced south and east of these river crossings, and these passings show more than 96% of Florida interstate truck shipments. The State Marketing Bureau estimated that 1500 carloads of Florida watermelons west of the Suwannee River moved to other States by truck; 700 were estimated for June and 800 for July.

TRUCK DESTINATIONS TO SOUTHERN GROUP OF MARKETS IN RAIL CARLOT EQUIVALENT

VEGETABLES, STRAWBERRIES, AND MISCELLANEOUS FRUITS

AUGUST 1-JULY 31

Destinations	Beans	Limas	Cabbage	Cauliflower	Celery	Corn	Cukes	Eggplant	Escarole	Field Peas
GROUP 1										
SOUTH CAROLINA	377	58	395	22	163	269	75	13	2	76
Columbia	268	54	268	13	97	161	62	10	2	67
Other Points	109	4	127	9	66	108	13	3	*	9
NORTH CAROLINA	389	17	588	13	203	250	79	9	*	43
Raleigh	83	11	205	3	51	55	21	2	-	24
Other Points	306	6	383	10	152	195	58	7	*	19
VIRGINIA	152	8	294	10	220	76	179	7	1	3
Richmond	14	2	98	3	58	14	17	3	*	*
Other Points	138	6	196	7	162	62	162	4	1	3
WEST VIRGINIA	24	2	92	*	34	14	17	*	*	*
GEORGIA	818	74	875	27	236	459	157	26	3	199
Atlanta	459	32	641	22	167	373	57	20	2	71
Other Points	359	42	234	5	69	86	100	6	1	128
ALABAMA	233	25	351	12	162	112	32	18	*	112
Birmingham	150	12	225	9	71	78	18	11	*	45
Other Points	83	13	126	3	91	34	14	7	*	67
MISSISSIPPI	28	7	97	1	40	15	13	2	-	33
TENNESSEE	278	3	304	11	129	80	36	14	*	21
Nashville	75	1	85	3	45	30	10	2	-	7
Other Points	203	2	219	8	84	50	26	12	*	14
KENTUCKY	76	2	111	7	38	30	24	5	*	1
GROUP TOTAL 1	2375	196	3107	103	1225	1305	612	94	6	488
WEST OF SUWANNEE RIVER	32	3	42	3	5	8	7	2	1	17
GROUP 2										
WASHINGTON, D.C	110	4	167	9	147	139	96	18	12	1
MARYLAND	353	29	241	15	69	118	201	28	11	1
Baltimore	351	29	205	15	54	116	173	28	11	1
Other Points	2	*	36	*	15	2	28	*	*	*
DELAWARE	6	-	12	-	*	-	15	*	*	-
PENNSYLVANIA	537	63	405	44	240	230	419	97	88	6
Philadelphia	438	60	208	39	165	190	259	76	66	4
Pittsburgh	95	3	75	4	34	30	127	20	18	2
Other Points	4	*	122	1	41	10	33	1	4	-
NEW JERSEY	54	1	96	3	195	29	12	2	23	-
Newark	19	1	34	2	52	10	5	2	7	-
Other Points	35	-	62	1	143	19	7	*	16	-
NEW YORK	1251	33	404	82	392	315	1236	299	243	17
New York City	1197	33	322	76	296	300	1086	288	223	17
Other Points	54	*	82	6	96	15	150	11	20	*
CONNECTICUT	3	*	11	*	9	2	1	*	3	-
MASSACHUSETTS	202	2	62	10	47	55	208	17	35	1
Boston	195	2	51	10	36	49	198	16	30	1
Other Points	7	-	11	*	11	6	10	1	5	*
RHODE ISLAND	19	-	7	-	2	4	16	5	4	-
OTH.NEW ENGLAND	2	*	12	-	*	1	2	*	*	-
GROUP TOTAL 2	2537	132	1417	163	1101	893	2206	466	419	26
CANADA	15	-	24	1	70	23	36	1	1	-

NOTE: * Less than carlots.

TRUCK DESTINATIONS TO SOUTHERN GROUP OF MARKETS IN RAIL CARLOT EQUIVALENTS VEGETABLES, STRAWBERRIES, AND MISCELLANEOUS FRUITS
AUGUST 1-JULY 31

Destinations	Beans	Limas	Cabbage	Cauliflower	Celery	Corn	Cukes	Eggplant	Escarole	Field Peas
GROUP 3										
OHIO	62	1	108	12	43	17	174	11	12	*
Cincinnati	20	1	36	2	11	2	31	4	3	-
Cleveland	33	-	7	8	9	8	120	6	3	*
Others	9	-	65	2	23	7	23	1	6	-
INDIANA	50	*	177	9	153	48	15	3	1	-
MICHIGAN	22	*	111	5	173	18	34	2	3	2
Detroit	12	*	14	*	13	9	11	1	1	2
Others	10	*	97	5	160	9	23	1	2	-
WISCONSIN	10	-	17	1	36	8	21	1	*	-
MISSOURI	125	1	131	4	123	74	90	23	11	4
St.Louis	91	1	55	2	27	38	50	13	9	3
Others	34	*	76	2	96	36	40	10	2	1
IOWA	-	-	18	*	24	3	1	*	*	-
MINNESOTA	9	*	20	*	113	9	33	1	1	*
ILLINOIS	269	4	156	12	228	116	520	37	60	5
Chicago	259	4	124	10	189	108	489	36	59	5
Others	10	*	32	2	39	8	31	1	1	*
GROUP 3 TOTAL	547	6	738	43	893	293	888	78	88	11
GROUP 4										
LOUISIANA	110	6	104	5	145	40	41	58	*	39
New Orleans	87	3	46	1	100	25	35	54	*	23
Others	23	3	58	4	45	15	6	4	-	16
ARKANSAS	53	*	84	2	62	32	11	3	*	9
OKLAHOMA	25	-	35	*	64	20	12	4	1	*
TEXAS	276	2	225	7	417	119	114	45	1	22
Dallas	79	*	46	*	116	46	22	10	*	6
Houston	79	1	65	2	104	24	37	16	1	9
Others	118	1	114	5	197	49	55	19	*	7
ARIZONA	4	-	2	-	2	2	4	*	-	-
GROUP 4 TOTAL	468	8	450	14	690	213	182	110	2	70
GROUP 5										
KANSAS	6	-	12	*	39	5	9	1	-	*
NEBRASKA	3	-	16	*	22	8	14	*	*	-
N. DAKOTA	-	-	*	-	-	-	1	-	-	-
S. DAKOTA	-	-	2	-	1	-	*	-	-	-
COLORADO	8	*	2	*	31	9	12	2	-	*
OREGON	-	-	-	-	-	-	-	-	-	-
IDAHO	-	-	-	-	*	-	*	-	*	-
WASHINGTON	-	-	-	-	-	-	-	-	-	-
NEVADA	-	-	-	-	-	-	-	-	-	-
CALIFORNIA	76	*	10	-	2	87	87	10	1	*
Los Angeles	43	*	1	-	1	56	62	8	1	-
Others	33	*	9	-	1	31	25	2	-	*
OTHER STATES	2	-	*	-	1	2	4	1	-	-
New Mexico	2	-	*	-	1	2	4	1	-	-
GROUP 5 TOTAL	95	*	42	*	96	111	134	14	1	*
UNKNOWN	88	31	54	30	71	37	104	53	8	27
TOTAL ALL STATES	6157	376	5874	357	4151	2863	4169	818	526	639

NOTE: *Less Than Carlots.

TRUCK DESTINATIONS TO SOUTHERN GROUP OF MARKETS IN RAIL CARLOT EQUIVALENT
VEGETABLES, STRAWBERRIES, AND MISCELLANEOUS FRUITS
AUGUST 1-JULY 31

Destinations	Let-tuce	Pep-pers	Pota-toes	Ra-dishes	Squash	Toma-toes	Bun. Vegs.	Okra	Other Vegs.	Total Vegs.
GROUP 1										
SOUTH CAROLINA	95	66	261	1	96	707	29	24	26	2755
Columbia	59	53	181	1	70	593	21	21	16	2017
Other Points	36	13	80	*	26	114	8	3	10	738
NORTH CAROLINA	33	53	352	3	70	676	11	6	65	2860
Raleigh	4	15	108	*	21	112	2	1	26	744
Other Points	29	38	244	3	49	564	9	5	39	2116
VIRGINIA	13	51	222	1	31	487	3	1	10	1769
Richmond	2	15	77	*	7	102	-	1	4	417
Other Points	11	36	145	1	24	385	3	*	6	1352
WEST VIRGINIA	2	4	76	1	1	103	*	-	1	371
GEORGIA	93	82	523	5	156	1012	217	26	153	5141
Atlanta	33	62	392	4	122	710	113	18	129	3427
Other Points	60	20	131	1	34	302	104	8	24	1714
ALABAMA	14	47	207	5	81	600	79	9	39	2138
Birmingham	4	25	137	5	54	358	45	7	33	1287
Other Points	10	22	70	*	27	242	34	2	6	851
MISSISSIPPI	1	11	13	*	12	103	7	1	1	385
TENNESSEE	8	45	224	7	45	887	15	1	40	2148
Nashville	3	15	37	6	5	199	2	-	21	546
Other Points	5	30	187	1	40	688	13	1	19	1602
KENTUCKY	2	20	94	16	8	157	1	*	11	603
GROUP TOTAL 1	261	379	1972	39	500	4732	362	68	346	18170
FLORIDA, WEST OF SUWANNEE RIVER	12	5	12	1	9	93	10	1	1	264
GROUP 2										
WASHINGTON, D.C.	24	58	93	18	50	106	4	1	77	1134
MARYLAND	7	86	278	24	36	278	*	1	39	1815
Baltimore	7	85	264	23	36	261	*	1	38	1698
Other Points	*	1	14	1	*	17	*	-	1	117
DELAWARE	-	3	7	-	1	1	*	-	4	49
PENNSYLVANIA	33	346	554	47	43	477	4	5	177	3815
Philadelphia	27	215	196	23	37	235	3	4	135	2380
Pittsburgh	5	110	76	14	5	135	1	1	32	787
Other Points	1	21	282	10	1	107	*	-	10	648
NEW JERSEY	5	32	81	1	11	175	-	-	35	755
Newark	*	13	17	*	4	8	-	-	7	181
Other Points	5	19	64	1	7	167	-	-	28	574
NEW YORK	129	594	311	52	242	1172	4	36	386	7198
New York City	127	536	221	45	227	1049	4	36	366	6449
Other Points	2	58	90	7	15	123	*	*	20	749
CONNECTICUT	1	3	3	*	7	65	*	-	4	112
MASSACHUSETTS	6	80	34	2	50	192	*	-	30	1033
Boston	6	75	5	1	46	104	*	-	24	849
Other Points	*	5	29	1	4	88	*	-	6	184
RHODE ISLAND	-	19	2	*	11	-	-	-	2	91
OTH. NEW ENGLAND	*	2	1	*	1	4	-	*	2	27
GROUP TOTAL 2	205	1223	1364	144	452	2470	12	43	756	16029
CANADA	*	9	10	4	1	5	-	-	2	201

NOTE: * Less than carlots. Truck Distribution for Citrus see page 37.

TRUCK DESTINATIONS TO SOUTHERN GROUP OF MARKETS IN RAIL CARLOT EQUIVALENTS
VEGETABLES, STRAWBERRIES, AND MISCELLANEOUS FRUITS
AUGUST 1-JULY 31

Destinations	Lettuce	Peppers	Potatoes	Radish	Squash	Tomatoes	Bun. Vegs.	Okra	Oth. Vegs.	Total Veg.
GROUP 3										
OHIO	7	42	207	54	5	241	3	1	100	[illegible]
Cincinnati	1	7	28	12	2	89	1	-	21	271
Cleveland	4	21	28	10	3	28	*	1	20	309
Others	2	14	151	32	*	124	2	*	59	[illegible]
INDIANA	4	16	62	15	2	341	2	-	15	[illegible]
MICHIGAN	3	15	35	11	2	34	1	1	26	468
Detroit	2	9	22	5	1	19	1	1	16	139
Others	1	6	13	6	1	15	*	-	10	329
WISCONSIN	1	12	3	2	1	19	-	-	2	144
MISSOURI	7	87	30	40	15	113	6	1	47	332
St. Louis	6	56	11	29	6	64	5	1	38	205
Others	1	31	19	11	9	49	1	-	9	127
IOWA	-	1	3	2	*	7	*	-	*	59
MINNESOTA	-	16	3	6	2	22	*	-	3	228
ILLINOIS	19	141	94	76	29	284	23	5	160	2238
Chicago	18	135	52	73	28	245	23	5	158	2020
Others	1	6	42	3	1	39	*	*	2	218
GROUP 3 TOTAL	41	330	437	206	56	1061	35	8	353	6112
GROUP 4										
LOUISIANA	3	84	37	*	47	344	4	2	3	1072
New Orleans	2	72	23	*	35	267	1	1	2	777
Others	1	12	14	*	12	77	3	1	1	295
ARKANSAS	*	17	18	1	16	60	4	-	5	377
OKLAHOMA	-	15	19	1	16	75	-	-	1	[illegible]
TEXAS	3	156	139	1	190	812	2	*	2	2533
Dallas	1	32	39	*	48	125	*	*	*	570
Houston	-	43	29	*	37	195	1	-	*	643
Others	2	81	71	1	105	492	1	*	2	1320
ARIZONA	-	2	1	-	2	-	-	-	-	19
GROUP 4 TOTAL	6	274	214	3	271	1291	10	2	11	4289
GROUP 5										
KANSAS	-	5	6	*	2	21	-	-	*	106
NEBRASKA	-	9	7	*	*	16	-	-	*	95
N. DAKOTA	-	-	-	-	-	1	-	-	-	2
S. DAKOTA	-	-	-	*	-	-	-	-	1	[illegible]
COLORADO	-	12	4	-	9	2	*	*	*	98
OREGON	-	-	-	-	-	-	-	-	-	-
IDAHO	*	-	*	-	-	-	-	-	*	*
WASHINGTON	-	-	-	-	-	-	-	-	-	-
NEVADA	-	-	-	-	-	-	-	-	-	*
CALIFORNIA	*	33	1	-	11	*	*	*	*	318
Los Angeles	*	28	1	-	6	-	-	-	*	207
Others	*	5	*	-	5	*	*	*	*	111
OTHER STATES	-	8	3	2	*	3	-	-	-	26
New Mexico	-	8	2	2	-	3	-	-	-	25
Utah	-	-	1	*	*	-	-	-	-	1
Wyoming	-	-	*	-	*	-	-	-	-	*
GROUP 5 TOTAL	*	67	21	2	22	43	*	*	1	649
UNKNOWN	45	64	45	7	86	95	23	25	31	924
TOTAL ALL STATES	570	2351	4074	406	1397	9790	452	147	1501	46638

NOTE: *Less Than Carlots. Truck Distribution for Citrus see page 37.

TRUCK DESTINATIONS TO SOUTHERN GROUP OF MARKETS IN RAIL CARLOT EQUIVALENT
VEGETABLES, STRAWBERRIES, AND MISCELLANEOUS FRUITS
AUGUST 1-JULY 31

Destinations	Straw-berries	Water-melons	Avo-cados	Limes	Canta-loupes	Mangoes	Other Fruits	Total Miscl. Frts	Total Frts and Vegs.
GROUP 1									
SOUTH CAROLINA	13	716	*	*	23	-	1	753	3508
Columbia	9	581	*	*	19	-	1	610	2627
Other Points	4	135	-	-	4	-	-	143	881
NORTH CAROLINA	40	293	*	*	10	-	*	343	3203
Raleigh	7	69	*	-	3	-	*	79	823
Other Points	33	224	-	*	7	-	*	264	2380
VIRGINIA	3	217	-	1	4	-	1	226	1995
Richmond	1	59	-	-	*	-	-	60	477
Other Points	2	158	-	1	4	-	1	166	1518
WEST VIRGINIA	1	133	1	*	2	-	-	137	508
GEORGIA	28	758	15	1	15	-	1	818	5959
Atlanta	10	423	15	*	10	-	*	458	3885
Other Points	18	335	*	1	5	-	1	360	2074
ALABAMA	9	305	1	2	8	-	*	325	2463
Birmingham	6	89	*	1	*	-	*	96	1383
Other Points	3	216	1	1	8	-	*	229	1080
MISSISSIPPI	1	244	*	2	1	-	-	248	633
TENNESSEE	5	259	1	*	1	-	1	267	2415
Nashville	4	34	-	-	-	-	-	38	584
Other Points	1	225	1	*	1	-	1	229	1831
KENTUCKY	2	165	*	-	*	-	-	167	770
GROUP TOTAL 1	102	3090	18	6	64	-	4	3284	21454
FLORIDA, WEST OF SUWANNEE RIVER	1	114	*	*	2	-	*	117	381
GROUP 2									
WASHINGTON, D.C.	16	185	8	5	-	-	2	216	1350
MARYLAND	23	318	2	3	1	-	13	360	2175
Baltimore	21	304	2	3	1	-	12	343	2041
Other Points	2	14	-	-	-	-	1	17	134
DELAWARE	1	1	-	-	-	-	-	2	51
PENNSYLVANIA	49	185	10	14	*	-	5	263	4078
Philadelphia	38	41	8	12	*	-	3	102	2482
Pittsburgh	11	9	2	2	-	-	2	26	813
Other Points	-	135	-	*	-	-	-	135	783
NEW JERSEY	4	30	36	16	*	*	*	86	841
Newark	-	9	1	-	-	-	*	10	191
Other Points	4	21	35	16	*	*	-	76	650
NEW YORK	200	139	172	88	*	4	5	608	7806
New York City	197	76	171	85	*	4	5	538	6987
Other Points	3	63	1	3	-	-	*	70	819
CONNECTICUT	-	24	-	-	-	-	-	24	136
MASSACHUSETTS	29	6	16	22	*	1	-	74	1107
Boston	28	6	16	22	*	1	-	73	922
Other Points	1	-	-	-	-	-	-	1	185
RHODE ISLAND	-	*	-	-	-	-	-	*	91
OTH. NEW ENGLAND	-	3	1	1	-	-	-	5	32
GROUP TOTAL 2	322	891	245	149	1	5	25	1638	17667
CANADA	1	21	-	-	-	-	-	22	223

NOTE: * Less than carlots.   Truck Distribution for Citrus see page 37.

TRUCK DESTINATIONS TO SOUTHERN GROUP OF MARKETS IN RAIL CARLOT EQUIVALENT: VEGETABLES, STRAWBERRIES, AND MISCELLANEOUS FRUITS

AUGUST 1-JULY 31

Destinations	Strawberries	Watermelons	Avocados	Limes	Cantaloupes	Mangoes	Other Fruits	Total Miscl. Frts	Total Frts and Vegs.
GROUP 3									
OHIO	42	157	3	6	*	*	2	210	1310
Cincinnati	27	10	2	3	-	*	-	42	313
Cleveland	11	7	1	2	*	-	-	21	330
Others	4	140	*	1	-	-	2	147	667
INDIANA	2	194	1	*	8	-	1	206	1114
MICHIGAN	7	75	13	7	-	-	1	103	601
Detroit	7	9	13	7	-	-	-	36	172
Others	-	66	-	-	-	-	1	67	[illegible]
WISCONSIN	-	21	1	*	-	-	-	22	136
MISSOURI	16	190	13	4	-	-	*	223	1155
St. Louis	10	105	9	3	-	-	*	127	632
Others	6	85	4	1	-	-	-	96	523
IOWA	-	24	-	-	-	-	-	24	83
MINNESOTA	3	24	4	3	*	-	-	34	272
ILLINOIS	42	92	44	20	*	-	1	199	2437
Chicago	39	33	44	20	*	-	1	137	2157
Others	3	59	-	-	-	-	-	62	280
GROUP 3 TOTAL	112	777	79	40	8	-	5	1021	7133
GROUP 4									
LOUISIANA	1	194	33	2	*	-	1	231	1303
New Orleans	1	65	33	*	-	-	*	99	676
Others	-	129	*	2	*	-	1	132	627
ARKANSAS	1	107	1	1	-	-	-	110	487
OKLAHOMA	3	17	*	-	-	*	-	20	303
TEXAS	20	133	30	2	-	*	-	185	2718
Dallas	9	32	6	1	-	*	-	48	613
Houston	8	22	8	*	-	-	-	38	681
Others	3	79	16	1	-	-	-	99	1119
ARIZONA	-	-	-	-	-	-	-	-	19
GROUP 4 TOTAL	25	451	64	5	*	*	1	545	4835
GROUP 5									
KANSAS	*	6	1	*	-	-	-	7	113
NEBRASKA	1	1	*	*	-	-	-	2	97
N. DAKOTA	-	2	-	-	-	-	-	2	[illegible]
S. DAKOTA	-	3	-	-	-	-	-	3	7
COLORADO	1	4	*	-	-	-	-	5	103
OREGON	-	-	*	-	-	-	1	1	1
IDAHO	-	1	-	-	-	-	-	1	1
WASHINGTON	-	-	1	2	-	-	-	3	3
NEVADA	-	-	-	-	-	-	-	-	*
CALIFORNIA	-	-	2	4	-	-	-	6	324
Los Angeles	-	-	1	3	-	-	-	4	211
Others	-	-	1	1	-	-	-	2	113
OTHER STATES	-	8	-	-	-	-	-	8	34
New Mexico	-	6	-	-	-	-	-	6	31
Utah	-	1	*	*	-	-	-	1	2
Montana	-	1	-	-	-	-	-	1	1
GROUP 5 TOTAL	2	25	4	6	*	*	1	38	687
UNKNOWN	16	7	4	4	10	8	1	50	974
TOTAL ALL STATES	581	5376	414	210	85	13	37	6716	53354

NOTE: * Less Than Carlots. Truck Distribution for Citrus see page 37.

POULTRY FACTS
EGG AND POULTRY PRODUCTION

By F. W. Risher, Marketing Specialist, Dairy and Poultry Products.

Only a few years ago most people looked upon Florida as a white egg market, and most commercial poultrymen kept white Leghorn hens. Then just prior to the World War Number Two, poultrymen began to develop flocks of heavy breed layers mostly of the New Hampshire breed. As a result consumers began to find brown eggs on the market that were of just as good quality as the white eggs from commercial poultry farms. Today there are many more commercial brown eggs on the market than white eggs. Browns account for approximately 65 per cent of egg production in the State. Nassau and nearby counties produce most of the State's white eggs.

POULTRY COOPERATIVES TO GRADE, PACK AND MARKET EGGS

There are four egg cooperatives operating very successfully at the present time; one of them operating in Marion County; one in Bristol, Florida, covering Liberty and Calhoun Counties; one in Orlando, covering the central part of the State; and one located in Hernando County. These associations have all the modern equipment found in commercial egg plants. The one at Bristol has a cooler with an egg holding capacity of 700 cases.

BROILER PRODUCTION INCREASING

Broiler production began in a small way around cities like Jacksonville, Tampa and Miami, where there was a ready market years ago. Recently areas of heavy production away from the cities began to develop in West Florida in Walton County, and in North Florida around Palatka. Today more fryers are produced by commercial plants than by general farmers.

LEADING PRODUCING COUNTIES WITH LARGEST CITY OR PRODUCING POINT 1950

EGGS

County Rank	Leading City or Shipping Point
1. Hillsborough	Tampa
2. Pasco	Dade City
3. Nassau	Callahan
4. Duval	Jacksonville
5. Polk	Lakeland
6. Jackson	Marianna
7. Marion	Ocala
8. Orange	Orlando

COMMERCIAL BROILERS

County Rank	Leading City or Shipping Point
1. Putnam	Palatka
2. Walton	DeFuniak Springs
3. Duval	Jacksonville
4. Hillsborough	Tampa
5. Dade	Miami
6. Osceola	Kissimmee
7. Polk	Lakeland
8. Holmes	Bonifay

TURKEYS

1. Gilchrist	Trenton
2. Levy	Chiefland
3. Suwannee	Live Oak
4. Gadsden	Havana
5. Marion	Ocala
6. Alachua	Gainesville
7. Sumter	Bushnell
8. Lake	Leesburg

DUCKS

1. Duval	Jacksonville
2. Dade	Miami
3. Hillsborough	Tampa
4. Pasco	Dade City
5. Orange	Orlando
6. Volusia	Deland
7. Marion	Ocala
8. Alachua	Gainesville

GEESE

1. Jackson	Marianna
2. Duval	Jacksonville
3. Madison	Madison
4. Pasco	Dade City

GUINEAS

1. Polk	Lakeland
2. Jackson	Marianna
3. Hillsborough	Tampa
4. Gadsden	Quincy
5. Gilchrist	Trenton
6. Marion	Ocala
7. Levy	Williston
8. Alachua	Gainesville

LOCATION OF LARGEST COMMERCIAL POULTRY FLOCKS

WHITES

1. Nassau	Callahan
2. Columbia	Lake City
3. Manatee	Bradenton
4. Alachua	Gainesville

REDS

1. Hillsborough	Tampa
2. Pasco	Dade City
3. Hernando	Brooksville
4. Duval	Jacksonville

TURKEYS

1. Gadsden	Havana
2. Marion	Ocala
3. Sumter	Bushnell
4. Duval	Jacksonville



This outline map of Florida has been requested by numerous firms and individuals in Florida and in other states. The map is a reproduction of a larger map reduced in size to meet the requirements of this Annual Report. The county designation is therefore in very small print. The cities and towns were superimposed on this map and are in much larger print.

Most of the larger cities of the state are shown. The locations of our field market news stations are shown as well as most of the leading livestock markets. There are a few cities to represent general agricultural sections.

Tallahassee is the capitol of the state, and the Florida State Department of Agriculture is located there. The Florida State Marketing Bureau is in Jacksonville. The Agricultural Extension Service and College of Agriculture are located at Gainesville. The U. S Bureau of Agricultural Economics (Florida agricultural statistics) is in Orlando. Winter Haven, Fla., in Polk County, is the headquarters of the Florida Citrus and Vegetable Inspection Service, with a branch office in Orlando. The office of the State Agricultural Marketing Board (State Markets) is located in Winter Haven.

The Federal-State Shipping Point Market News offices are located as follows: (1) Lakeland for *citrus;* (2) Plant City for *strawberries and vegetables;* (3) Hastings for *potatoes and cabbage;* (4) Sanford for *celery, cabbage, corn and vegetables;* (5) Leesburg and Gainesville for *watermelons;* (6) Belle Glade for *beans, celery, corn and vegetables;* (7) Pompano for *beans, peppers and vegetables.* Florida City, Fort Pierce, Fort Myers, Palmetto and Ruskin, Zellwood and Weirsdale *vegetables* are reported in field Market News reports.

Our leased wire will be extended to several additional State Markets for the 1951-52 season.

3344

Date Due

Due	Returned	Due	Returned

UNIVERSITY OF FLORIDA
3 1262 05140 7749

AGRI-
CULTURAL
LIBRARY